Receiving Tube Manual

Including Picture Tubes and Industrial Receiving Tubes

RC/I Receiving Tube Manual

Including Picture Tubes and Industrial Receiving Tubes

THIS MANUAL, like its many predecessors, has been prepared to assist those who work or experiment with home-entertainment or industrial receiving types of electron tubes and circuits or with television picture tubes. It will be found valuable by engineers, service technicians, educators, experimenters, electricians, radio amateurs, hobbyists, students, and others interested in electron tubes and their applications.

Easy-to-read chapters explain the basic principles of operation, significant electrical characteristics, circuit applications, and testing of various types of electron tubes. Technical data are given on current RCA home-entertainment and industrial receiving-type tubes and on picture tubes. Circuit diagrams are given illustrating the use of RCA tubes in many practical applications. Also included are expanded and updated replacement guides for obsolete or hard-to-find industrial and home-entertainment receiving tubes.

RCA | Distributor and Special Products Division Cherry Hill Offices | Camden, N.J. 08101

Copyright 1975 by RCA Corporation
(All rights reserved under Pan-American Copyright Convention)
Printed in U.S.A. 8/75

Contents

DIECTRONIC ELECTRONEC AND ELECTRON TUBEC	PAGI
ELECTRONS, ELECTRODES, AND ELECTRON TUBES	•
ELECTRON TUBE CHARACTERISTICS	. 13
ELECTRON TUBE APPLICATIONS	. 15
ELECTRON TUBE INSTALLATION	. 81
SAFETY PRECAUTIONS—RECEIVING TUBES, PICTURE TUBES	. 93
INTERPRETATION OF TUBE DATA	. 95
ELECTRON TUBE TESTING	. 100
APPLICATION GUIDE FOR RECEIVING TUBES	. 104
TECHNICAL DATA FOR RECEIVING TUBES— ENTERTAINMENT AND INDUSTRIAL TYPES	. 111
CHARACTERISTICS CHART FOR ENTERTAINMENT ANI INDUSTRIAL RECEIVING TUBES	D . 522
TERMINAL DIAGRAMS FOR RECEIVING TUBES	. 594
OUTLINES	. 633
STRUCTURE OF A MINIATURE TUBE	. 640
RESISTANCE-COUPLED AMPLIFIERS	. 64
REPLACEMENT GUIDE— ENTERTAINMENT RECEIVING TYPES	. 650
REPLACEMENT GUIDE— INDUSTRIAL RECEIVING TYPES	. 65
PICTURE TUBE CHARACTERISTICS CHART	. 66
TERMINAL DIAGRAMS FOR PICTURE TUBES	. 67
CIRCUITS	. 67
INDEX	. 75

Information furnished by RCA is believed to be accurate and reliable. However, no responsibility is assumed by RCA for its use; nor for any infringements of patents or other rights of third parties which may result from its use. No license is granted by implication or otherwise under any patent or patent rights of RCA

Electrons, Electrodes and Electron Tubes

THE electron tube is a marvelous device. It makes possible the performing of operations, amazing in conception, with a precision and a certainty that are astounding. It is an exceedingly sensitive and accurate instrument—the product of coordinated efforts of engineers and craftsmen. Its construction requires materials from every corner of the earth. Its use is world-wide.

The importance of the electron tube lies in its ability to control almost instantly the flight of the millions of electrons supplied by the cathode. It accomplishes this control with a minimum of energy. Because it is almost instantaneous in its action, the electron tube can operate efficiently and accurately at extremely high electrical frequencies.

Electrons

All matter exists in the solid. liquid, or gaseous state. These three forms consist entirely of minute divisions known as molecules, which, in turn, are composed of atoms. Atoms have a nucleus which is a positive charge of electricity, around which revolve tiny charges of negative electricity known as electrons. Scientists have estimated that electrons weigh only 1/30billion, billion. billionths $(\frac{1}{30} \times 10^{-35})$ of an ounce, and that they may travel at speeds of thousands of miles per second.

Electron movement may be accelerated by the addition of energy. Heat is one form of energy which can be conveniently used to speed up the electron.

For example, if the temperature of a metal is gradually raised, the electrons in the metal gain velocity. When the metal becomes hot enough, some electrons may acquire sufficient speed to break away from the surface of the metal. This action, which is accelerated when the metal is heated in a vacuum, is utilized in most electron tubes to produce the necessary electron supply.

An electron tube consists of a cathode, which supplies electrons, and one or more additional electrodes, which control and collect these electrons, mounted in an evacuated envelope. The envelope may be made of glass, metal, ceramic, or a combination of these materials.

Cathodes

A cathode is an essential part of an electron tube because it supplies the electrons necessary for tube operation. When energy in some form is applied to the cathode, electrons are released. Heat is the form of energy generally used. The method of heating the cathode may be used to distinguish between the different forms of cathodes. For example, a directly heated cathode, or filament-cathode, is a wire heated by the passage of an electric current. An indirectly heated cathode, or heatercathode, consists of a filament, or heater, enclosed in a metal sleeve. The sleeve carries the electron-emitting material on its outside surface and is heated by radiation and conduction from the heater.

A filament, or directly heated cathode, such as that shown in Fig. 1 may

be further classified by identifying the filament or electron-emitting material. The materials in regular use are tungsten, thoriated tungsten, and metals which have been coated with alkalineearth oxides. Tungsten filaments are made from the pure metal. Because they must operate at high temperatures (a dazzling white) to emit sufficient electrons, a relatively large amount of filament power is required.

Thoriated-tungsten filaments are made from tungsten impregnated with thorium oxide. Due to the presence of thorium, these filaments liberate electrons at a more moderate temperature of about 1700°C (a bright yellow) and are, therefore, much more economical of filament power than are pure tungsten filaments.

Alkaline earths are usually applied as a coating on a nickel-alloy wire or ribbon. This coating, which is dried in a relatively thick layer on the filament. requires only a relatively low temperature of about 700-750°C (a dull red) to produce a copious supply of electrons. Coated filaments operate very efficiently and require relatively little filament power. However, each of these cathode materials has special advantages which determine the choice for a particular application.

Directly heated filament-cathodes require comparatively little heating power. They are used in tube types designed for battery operation because it is, of course, desirable to impose as small a drain as possible on the batteries. They are also used in rectifiers such as the 1G3GTA/1B3GT and the 5Y3GT.

An indirectly heated cathode, or heater-cathode, consists of a thin metal sleeve coated with electron-emitting material such as alkaline-earth oxides. The emissive surface of the cathode is maintained at the required temperature (approximately 1050°K) by resistanceheating of a tungsten or tungsten-alloy wire which is placed inside the cathode sleeve and electrically insulated from it, as shown in Fig. 2. The heater is used only for the purpose of heating the cathode sleeve and sleeve coating to an electron-emitting temperature.

Useful emission does not take place from the heater wire.

A new dark heater insulating coating developed by RCA has better heat transfer than earlier aluminum-oxide coatings, and makes it possible to operate heaters at lower temperatures for given power inputs. Because the tensile strength of the heater wire increases at the lower operating temperatures, tubes using dark heaters have increased reliability, stability, and life.




Fig. 2-Indirectly Fig. I—Filament or directly heated heated cathode cathode. heater-cathode.

The heater-cathode construction is well adapted for use in electron tubes intended for operation from ac power lines and from storage batteries. The use of separate parts for emitter and heater functions, the electrical insulation of the heater from the emitter, and the shielding effect of the sleeve may all be utilized in the design of the tube to minimize the introduction of hum from the ac heater supply and to minimize electrical interference which might enter the tube circuit through the heater-supply line. From the viewpoint of circuit design, the heater-cathode construction offers advantages in connection flexibility because of the electrical separation of the heater from the cathode.

Another advantage of the heatercathode construction is that it makes practical the design of a rectifier tube having close spacing between its cathode and plate, and of an amplifier tube having close spacing between its cathode and grid. In a close-spaced rectifier tube, the voltage drop in the tube is low, and, therefore, the regulation is improved. In an amplifier tube, the close spacing increases the gain obtainable from the tube. Because of the

advantages of the heater-cathode construction, almost all present-day receiving tubes designed for ac operation have heater-cathodes.

Generic Tube Types

Electrons are of no value in an electron tube unless they can be put to work. Therefore, a tube is designed with the parts necessary to utilize electrons as well as those required to produce them. These parts consist of a cathode and one or more supplementary electrodes. The electrodes are enclosed in an evacuated envelope having the necessary connections brought out through air-tight seals. The air is removed from the envelope to allow free movement of the electrons and to prevent injury to the emitting surface of the cathode.

When the cathode is heated, electrons leave the cathode surface and form an invisible cloud in the space around it. Any positive electric potential within the evacuated envelope offers a strong attraction to the electrons (unlike electric charges attract; like charges repel). Such a positive electric potential can be supplied by an anode (positive electrode) located within the tube in proximity to the cathode.

Diedes

The simplest form of electron tube contains two electrodes, a cathode and an anode (plate), and is often called a diode, the family name for a two-electrode tube. In a diode, the positive potential is supplied by a suitable electrical source connected between the plate terminal and a cathode terminal, as shown in Fig. 3. Under the influence of the positive plate potential, electrons




Fig. 3-Basic diode circuit.

flow from the cathode to the plate and return through the external plate-battery circuit to the cathode, thus completing the circuit. This flow of electrons is known as the plate current.

If a negative potential is applied to the plate, the free electrons in the space surrounding the cathode will be forced back to the cathode and no plate current will flow. If an alternating voltage is applied to the plate, the plate is alternately made positive and negative Because plate current flows only during the time when the plate is positive, current flows through the tube in only one direction and is said to be rectified. Fig. 4 shows the rectified output current produced by an alternating input voltage.




Fig. 4—Current characteristics of rectifier circuit.

Diode rectifiers are used in ac receivers to convert the ac supply voltage to dc voltage for the electrodes of the other tubes in the receiver. Rectifier tubes having only one plate and one cathode, such as the 35W4, are called half-wave rectifiers, because current can flow only during one-half of the alternating-current cycle. When two plates and one or more cathodes are used in the same tube, current may be obtained on both halves of the ac cycle. The 6X4, 5Y3GT, and 5U4GB are examples of this type and are called full-wave rectifiers.

Not all of the electrons emitted by the cathode reach the plate. Some return to the cathode, while others remain in the space between the cathode and plate for a brief period to produce an effect known as space charge. This charge has a repelling action on other electrons which leave the cathode surface and impedes their passage to the plate. The extent of this action and the amount of space charge depend on the cathode temperature, the distance between the cathode and the plate, and the plate potential. The higher the plate potential, the less is the tendency for electrons to remain in the space-charge region and repel other electrons. This effect may be noted by applying increasingly higher plate voltages to a tube operating at a fixed heater or filament voltage. Under these conditions, the maximum number of available electrons is fixed, but increasingly higher plate voltages will succeed in attracting a greater proportion of the free electrons.

Beyond a certain plate voltage, however, additional plate voltage has little effect in increasing the plate current because all of the electrons emitted by the cathode are already being drawn to the plate. This maximum current, illustrated in Fig. 5, is called saturation current. Because it is an indication of the total number of electrons emitted, it is also known as emission current or simply emission.




Fig. 5—Current characteristic of diode tube.

Although tubes are sometimes tested by measurement of their emission current, it is generally not advisable to measure the full value of emission because this value would be sufficiently large to cause change in the tube characteristics or even to damage the tube. Consequently, while the test value of emission current is somewhat larger than the maximum current which will be required from the cathode in the

use of the tube, it is ordinarily less than the full emission current. The emission test, therefore, is used to indicate whether the cathode can supply a sufficient number of electrons for satisfactory operation of the tube.

If space charge were not present to repel electrons coming from the cathode, the same plate current could be produced at a lower plate voltage. One way to make the effect of space charge small is to make the distance between plate and cathode small. This method is used in rectifier types having heatercathodes, such as the 5V4GA and the 6AX5GT. In these types, the radial distance between cathode and plate is only about two hundredths of an inch.

Another method of reducing spacecharge effect is utilized in mercuryvapor rectifier tubes. When such tubes are operated, a small amount of mercury contained in the tube is partially vaporized, filling the space inside the bulb with mercury atoms. These atoms are bombarded by electrons on their way to the plate. If the electrons are moving at a sufficiently high speed, the collisions tear off electrons from the mercury atoms. The mercury atom is then said to be "ionized," i.e., it has lost one or more electrons and, therefore, has a positive charge. Ionization is evidenced by a bluish-green glow between the cathode and plate. When ionization occurs, the space charge is neutralized by the positive mercury atoms so that increased numbers of electrons are made available. Mercury-vapor tubes are used primarily for power rectifiers.

Ionic-heated-cathode rectifiers depend on gas ionization for their operation. These tubes are of the full-wave design and contain two anodes and a coated cathode sealed in a bulb containing a reduced pressure of inert gas. The cathode becomes hot during tube operation, but the heating effect is caused by bombardment of the cathode by ions within the tube rather than by heater or filament current from an external source.

The internal structure of an ionicheated-cathode tube is designed so that when sufficient voltage is applied to the tube, ionization of the gas occurs between the anode which is instantaneously positive and the cathode. Under normal operating voltages, ionization does not take place between the anode that is negative and the cathode. so that the requirements for rectification are satisfied. The initial small flow of current through the tube is sufficient to raise the cathode temperature quickly to incandescence, whereupon the cathode emits electrons. The voltage drop in such tubes is slightly higher than that of the usual hot-cathode gas rectifiers because energy is taken from the ionization discharge to keep the cathode at operating temperature. Proper operation of these rectifiers requires a minimum flow of load current at all times to maintain the cathode at the temperature required to supply sufficient emission.

Triodes

When a third electrode, called the control grid, is placed between the cathode and plate, the tube is known as a triode, the family name for a threeelectrode tube. The grid usually consists of relatively fine wire wound on two support rods (siderods) and extending the length of the cathode. The spacing between turns of wire is large compared with the size of the wire so that the passage of electrons from cathode to plate is practically unobstructed by the grid. In some types, a frame grid is used. The frame consists of two siderods supported by four metal straps. Extremely fine lateral wire (diameter of 0.5 mil or less) is wound under tension around the frame. This type of grid permits the use of closer spacings between grid wires and between tube electrodes, and thus improves tube performance.

The purpose of the grid is to control the flow of plate current. When a tube is used as an amplifier, a negative dc voltage is usually applied to the grid. Under this conditon the grid does not draw appreciable current.

The number of electrons attracted to the plate depends on the combined effect of the grid and plate polarities, as shown in Fig. 6. When the plate is positive, as is normal, and the dc grid volt-

age is made more and more negative, the plate is less able to attract electrons to it and plate current decreases. When the grid is made less and less negative (more and more positive), the plate more readily attracts electrons to it and plate current increases. Hence, when the voltage on the grid is varied in accordance with a signal, the plate current varies with the signal. Because a small voltage applied to the grid can control a comparatively large amount of plate current, the signal is amplified by the tube. Typical three-electrode tube types are the 6C4 and 6AF4A.




Fig. 6-Basic triode circuit.

The grid, plate, and cathode of a triode form an electrostatic system, each electrode acting as one plate of a small capacitor. The capacitances are those existing between grid and plate, plate and cathode, and grid and cathode. These capacitances are known as interelectrode capacitances. Generally, the capacitance between grid and plate is of the most importance. In high-gain radio-frequency amplifier circuits, this capacitance may act to produce undesired coupling between the input circuit, the circuit between grid and cathode, and the output circuit, the circuit between plate and cathode. This coupling is undesirable in an amplifier because it may cause instability and unsatisfactory performance.

Tetrodes

The capacitance between control grid and plate can be made small by mounting an additional electrode, called the screen grid (grid No. 2), in the tube. With the addition of the grid No. 2, the tube has four electrodes and is, accordingly, called a tetrode. The screen

grid or grid No. 2 is mounted between the grid No. 1 (control grid) and the plate, as shown in Fig. 7, and acts as an electrostatic shield between them, thus reducing the grid-to-plate capacitance. The effectiveness of this shielding action is increased by a bypass




Fig. 7-Basic tetrode circuit.

capacitor connected between screen grid and cathode. By means of the screen grid and this bypass capacitor, the grid-plate capacitance of a tetrode is made very small. In practice, the grid-plate capacitance is reduced from several picofarads (pF) for a triode to 0.01 pF or less for a screen-grid tube.

The screen grid has another desirable effect in that it makes plate current practically independent of plate voltage over a certain range. The screen grid is operated at a positive voltage and, therefore, attracts electrons from the cathode. However, because of the comparatively large space between wires of the screen grid, most of the electrons drawn to the screen grid pass through it to the plate. Hence, the screen grid supplies an electrostatic force pulling electrons from the cathode to the plate. At the same time, the screen grid shields the electrons between cathode and screen grid from the plate so that the plate exerts very little electrostatic force on electrons near the cathode.

So long as the plate voltage is higher than the screen-grid voltage, plate current in a screen-grid tube depends to a great degree on the screen-grid voltage and very little on the plate voltage. The fact that plate current in a screen-grid tube is largely independent of plate voltage makes it possible to obtain much higher amplification with a tetrode than with a triode. The

low grid-plate capacitance makes it possible to obtain this high amplification without plate-to-grid feedback and resultant instability. In receiving-tube applications, the tetrode has been replaced to a considerable degree by the pentode.

Pentodes

In all electron tubes, electrons striking the plate may, if moving at sufficient speed, dislodge other electrons. In two- and three-electrode types, these dislodged electrons usually do not cause trouble because no positive electrode other than the plate itself is present to attract them. These electrons, therefore, are drawn back to the plate. Emission caused by bombardment of an electrode by electrons from the cathode is called secondary emission because the effect is secondary to the original cathode emission.

In the case of screen-grid tubes, the proximity of the positive screen grid to the plate offers a strong attraction to these secondary electrons, and particularly so if the plate voltage swings lower than the screen-grid voltage. This effect reduces the plate current and limits the useful plate-voltage swing for tetrodes.

The effects of secondary emission are minimized when a fifth electrode is placed within the tube between the screen grid and plate. This fifth electrode is known as the suppressor grid (grid No. 3) and is usually connected to the cathode, as shown in Fig. 8. Because of its negative potential with respect to the plate, the suppressor grid retards the flight of secondary electrons and diverts them back to the plate.




Fig. 8—Basic pentode circuit.

The family name for a five-electrode tube is "pentode." In power-output pentodes, the suppressor grid makes possible higher power output with lower grid-driving voltage; in radio-frequency amplifier pentodes, the suppressor grid makes possible high voltage amplification at moderate values of plate voltage. These desirable features result from the fact that the plate-voltage swing can be made very large. In fact, the plate voltage may be as low as, or lower than, the screen-grid voltage without serious loss in signal-gain capability. Representative pentodes used for power amplification are the 6CL6 and 6K6GT; representative pentodes used for voltage amplification are the 6AU6A. 6BA6, and 5879.

Beam Power Tubes

A beam power tube is a tetrode or pentode in which directed electron beams are used to increase substantially the power-handling capability of the tube. Such a tube contains a cathode. a control grid (grid No. 1), a screen grid (grid No. 2), a plate, and, optionally, a suppressor grid (grid No. 3). When a beam power tube is designed without an actual suppressor grid, the electrodes are so spaced that secondary emission from the plate is suppressed by space-charge effects between screen grid and plate. The space charge is produced by the slowing up of electrons traveling from a high-potential screen grid to a lower-potential plate. In this low-velocity region, the space charge produced is sufficient to repel secondary electrons emitted from the plate and to cause them to return to the plate.

Beam power tubes of this design employ beam-confining electrodes at cathode potential to assist in producing the desired beam effects and to prevent stray electrons from the plate from returning to the screen grid outside of the beam. A feature of a beam power tube is its low screen-grid current. The screen grid and the control grid are spiral wires wound so that each turn of the screen grid is shaded from the cathode by a grid turn. This alignment of the screen

grid and control grid causes the electrons to travel in sheets between the turns of the screen grid so that very few of them strike the screen grid. Because of the effective suppressor action provided by space charge and because of the low current drawn by the screen grid, the beam power tube has the advantages of high power output, high power sensitivity, and high efficiency.

Fig. 9 shows the structure of a beam power tube employing spacecharge suppression and illustrates how




Fig. 9—Structure of beam power tube showing beam-confining action.

the electrons are confined to beams. The beam condition illustrated is that for a plate potential less than the screen-grid potential. The high-density space-charge region is indicated by the heavily dashed lines in the beam. Note that the edges of the beam-confining electrodes coincide with the dashed portion of the beam. In this way the space-charge potential region is extended beyond the beam boundaries and stray secondary electrons are prevented from returning to the screen grid outside of the beam. The spacecharge effect may also be obtained by use of an actual suppressor grid. Examples of beam power tubes are 6AQ5A, 6L6GC, 6V6GTA, and 50C5.

Multi-Electrode and Multi-Unit Tubes

Early in the history of tube devel-

opment and application, tubes were designed for a general service; that is, a single tube type—a triode—was used as a radio-frequency amplifier, an intermediate-frequency amplifier, an audiofrequency amplifier, an oscillator, or a detector. Obviously, with this diversity of application, one tube did not meet all requirements to the best advantage.

Later and present trends of tube design are the development of "specialty" types. These types are intended either to give optimum performance in a particular application or to combine in one bulb functions which formerly required two or more tubes. The first class of tubes includes such examples of specialty types as the 6CB6A and 6BY6. Types of this class generally require more than three electrodes to obtain the desired special characteristics and may be broadly classed as multielectrode types. The 6BY6 is an especially interesting type in this class. This tube has an unusually large number of electrodes, namely seven, exclusive of the heater. Plate current in the tube is varied at two different frequencies at the same time. The tube is designed primarily for use as a combined sync separator and sync clipper in television receivers.

The second class includes multiunit tubes such as the twin-diode triodes 6CN7 and 6AV6, as well as triode-pentodes such as the 6EA8 and 6GH8A. This class also includes class A twin triodes such as the 6FQ7/6CG7 and 12AX7A, and types such as the 6CM7 containing dissimilar triode units used primarily as combined vertical oscillators and vertical deflection amplifiers in television receivers. Full-wave rectifiers are also multi-unit types.

A third class of tubes combines features of each of the other two classes. Typical of this third class are the pentagrid-converter types 6BE6 and 6SA7. These tubes are similar to the multicectrode types in that they have seven electrodes, all of which affect the electron stream; and they are similar to the multi-unit tubes in that they perform simultaneously the double function of oscillator and mixer in superheterodyne receivers.

Receiving Tube Structure

Receiving tubes generally utilize a glass or metal envelope and a base. Originally, the base was made of metal or molded phenolic material. Types having a glass envelope and a molded phenolic base include the "octal" types such as the 5U4GB and the 6SN7GTB. Types having a metal envelope and molded phenolic octal base include the 6V6 and the 6L6. Many modern types utilize integral glass bases. Present-day conventional tube designs utilizing glass envelopes and integral glass bases include the seven-pin and nine-pin miniature types, the nine-pin novar and neonoval types, and the twelve-pin duodecar types. Examples of the seven-pin miniature types are the 6AU6A and 6AV6. Examples of the nine-pin miniature types are the 12AU7A and 6EA8. Examples of the novar types are the 6CJ3 and 7868. The nine-pin base for the novar types has a relatively large pin-circle diameter and long pins to insure firm retention of the tube in its socket.

The nuvistor concept provided a new approach to electron tube design. Nuvistor tubes utilize a light-weight cantilever-supported cyclindrical electrode structure housed in a ceramicmetal envelope. These tubes combine new materials, processes, and fabrication techniques. Examples of the nuvistor are the 6CW4 and the 6DV4.

Television Picture Tubes

The picture tube, or kinescope, is a multi-electrode tube used principally in television receivers for picture display. It consists essentially of an electron gun, a glass or metal-and-glass envelope and faceplate combination, and a fluorescent screen.

The electron gun includes a cathode for the production of free electrons, one or more control electrodes for accelerating the electrons in the beam, and, optionally, a device for "trapping" unwanted ions out of the electron beam.

Focusing of the beam is accomplished either electromagnetically by

means of a focusing coil placed on the neck of the tube, or electrostatically, as shown in Fig. 10, by means of a focusing electrode (grid No. 4) within the envelope of the tube. The screen is a white-fluorescing phosphor P4 of either the silicate or the sulfide type.

Deflection of the beam is accomplished either electrostatically by means of deflecting electrodes within the envelope of the tube, or electromagnetically by means of a deflecting yoke placed on the neck of the tube. Fig. 10 shows the structure of the gun section of a picture tube and illustrates how the electron beam is formed and how the beam is deflected by means of an electromagnetic deflecting yoke. In this type of tube, ions in the beam are prevented from damaging the fluorescent screen by an aluminum film on the gun side of the screen. This film not only "traps" unwanted ions, but also improves picture contrast. In many types of non-aluminized tubes, ions are separated from the electron beam by means of a tilted-gun and ion-trapmagnet arrangement.

Color television picture tubes are similar to black-and-white picture tubes, but differ in three major ways: (1) The light-emitting screen is made up of trios

of phosphor dots deposited in an interlaced pattern. Each dot of a trio is capable of emitting light in one of the three primary colors (red, green, or blue). (2) A shadow mask mounted near the screen of the tube contains over 300,-000 apertures, one for each of the phosphor dot trios. This mask provides color separation by shadowing two of the three phosphor dots of each trio. (3) Three closely spaced electron guns. built as a unit, provide separate beams for excitation of the three different color-phosphor-dot arrays. Thus it is possible to control the brightness of each of the three colors independently of the other two. Fig. 11 shows a cutaway view of a color television picture tube.

The three electron guns are mounted with their axes tilted toward the central axis of the envelope, and are spaced 120 degrees with respect to each other. The focusing electrodes of the three guns are interconnected internally, and their potential is adjusted to cause the separate beams to focus at the phosphor-dot screen. All three beams must be made to converge at the screen while they are simultaneously being deflected. Convergence is accomplished by the action of static and




Fig. 10-Structure of television-picture-tube electron gun.

dynamic magnetic fields set up by the radial-converging magnet assembly mounted on the neck of the tube. These fields are coupled into the radial-converging pole pieces within the tube. Another pair of pole pieces in the tube is activated by the lateral-converging magnet also mounted on the neck of the tube. These pole pieces permit lateral shift in position of the blue beam in opposition to the lateral shift of the green and red beams.

A purifying magnet is used with color picture tubes to provide a magnetic field, adjustable in magnitude and direction, to effect register over the entire area of the screen. A magnetic shield is used to minimize the effects

of the earth's magnetic field.

Deflection of the three beams is accomplished simultaneously by a deflecting yoke using four electromagnetic coils similar to the deflecting yoke used for black-and-white picture tubes.

A totally new concept in color television display systems utilizing an advanced design of electron gun, deflection yoke, and picture tube has

been developed by RCA. Instead of dots, this tube utilizes a screen consisting of continuous vertical phosphor lines of alternating green, red, and blue emitting phosphors. The mask apertures are vertical slits with small cross ties to provide strength. This line-screen arrangement has the advantage of reducing beam-to-phosphor misregister, enhancing color purity, and improving white uniformity

The electron gun of this tube uses horizontal in-line structure rather than the 120° spacing of the phosphor-dot tube and is designed for use with a precision static toroid linefocus-type deflecting yoke. With this structure, the three beams and the deflecting field are in precise alignment. As a result, this precision in-line tube assembly is inherently self-converging and does not require dynamic convergence correction or its associated circuitry Consequently, the deflecting yoke and neck components can be preadjusted and permanently attached to the picture tube by the tube manufacturer.

BLUE BEAM
GREEN BEAM
RED BEAM
RED BEAM
ALUMINIZED
TRICOPIOR
PHICOSPHOR
PHICOSPHOR
PHICOSPHOR
ON INNER
SURFACE OF
FACEPLATE

SHADOW MASK

CONDUCTIVE
COATING

FACEPLATE

RESIN

PANEL SECTION

Fig. 11-Cutaway view of color television picture tube.

Electron Tube Characteristics

THE term "characteristics" is used to identify the distinguishing electrical features and values of an electron tube. These values may be shown in curve form or they may be tabulated. When the characteristics values are given in curve form, the curves may be used for the determination of tube performance and the calculation of additional tube factors.

Tube characteristics are obtained from electrical measurements of a tube in various circuits under certain definite conditions of voltages. Characteristics may be further described by denoting the conditions of measurements. For example, Static Characteristics are the values obtained with different dc potentials applied to the tube electrodes. while Dynamic Characteristics are the values obtained with an ac voltage on a control grid under various conditions of dc potentials on the electrodes. The dynamic characteristics, therefore, are indicative of the performance capabilities of a tube under actual working conditions.

Static characteristics may be shown plate characteristics curves and transfer (mutual) characteristics curves. These curves present the same information, but in two different forms to increase its usefulness. The plate characteristic curve is obtained by varying plate voltage and measuring plate current for different grid-bias voltages. while the transfer-characteristic curve is obtained by varying grid-bias voltage and measuring plate current for different plate voltages. A plate-characteristic family of curves is shown in Fig. 12. Fig. 13 gives the transfer-characteristic family of curves for the same tube.

Dynamic characteristics include amplification factor, plate resistance, control-grid—plate transconductance, and certain detector characteristics, and may be shown in curve form for variations in tube operating conditions.




Fig. 12—**Fa**mily of plate-characteristics curves.

The amplification factor, or μ , is the ratio of the change in plate voltage to a change in control-electrode voltage in the opposite direction, under the condition that the plate current remains




Fig. 13—Family of transfer-characteristics curves.

unchanged and that all other electrode voltages are maintained constant. For example, if, when the plate voltage is made 1 volt more positive, the control-electrode (grid-No. 1) voltage must be made 0.1 volt more negative to hold plate current unchanged, the amplification factor is 1 divided by 0.1, or 10. In other words, a small voltage variation in the grid circuit of a tube has the same effect on the plate current as a large plate-voltage change—the latter equal to the product of the grid-voltage change and amplification factor. The μ of a tube is often useful for

calculating stage gain. This use is discussed in the Electron Tube Applications section.

Plate resistance (r_p) of an electron tube is the resistance of the path between cathode and plate to the flow of alternating current. It is the quotient of a small change in plate voltage divided by the corresponding change in plate current and is expressed in ohms, the unit of resistance. Thus, if a change of 0.1 milliampere (0.0001 ampere) is produced by a plate-voltage variation of 1 volt, the plate resistance is 1 divided by 0.0001, or 10000 ohms.

Control grid-to-plate transconductance, or simply transconductance (gm), is a factor which combines in one term the amplification factor and the plate resistance, and is the quotient of the first divided by the second. This term has also been known as mutual conductance. Transconductance may be more strictly defined as the quotient of a small change in plate current (amperes) divided by the small change in the control-grid voltage producing it, under the condition that all other voltages remain unchanged. Thus, if a gridvoltage change of 0.5 volt causes a plate-current change of 1 milliampere (0.001 ampere), with all other voltages constant, the transconductance is 0.001 divided by 0.5, or 0.002 mho. A "mho" is the unit of conductance and was named by spelling ohm backwards. For convenience, a millionth of a mho, or a micromho (µmho), is used to express transconductance. Thus, in the example, 0.002 mho is 2000 micromhos.

Conversion transconductance (g_c) is a characteristic associated with the mixer (first detector) function of tubes and may be defined as the quotient of the intermediate-frequency (if) current in the primary of the if transformer divided by the applied radio-frequency (rf) voltage producing it; more precisely, it is the limiting value of this quotient as the rf voltage and if current approach zero. When the performance of a frequency converter is determined. conversion transconductance is used in the same way as control grid-to-plate

transconductance is used in single-frequency amplifier computations.

The plate efficiency of a power amplifier tube is the ratio of the ac power output (P_o) to the product of the average dc plate voltage (Eb) and dc plate current (Ib) at full signal, or

$$\frac{\text{Plate efficiency}}{\%} = \frac{P_0 \text{ watts}}{E_b \text{ volts} \times I_b \text{ amperes}} \times 100$$

The power sensitivity of a tube is the ratio of the power output to the square of the input signal voltage (E_{1n}). and is expressed in mhos as follows:

Power sensitivity (mhos) = $\frac{F \circ \text{ wasse}}{(E_{1n}, \text{ rms})^2}$

X-RADIATION CHARACTERISTICS OF TELEVISION PICTURE TUBES

X-rays are produced when the atoms of a material are bombarded by electrons (or ions). The relative intensity and spectral energy distribution of the X-radiation at the source are determined by the accelerating voltage, the electron (or ion) current, and the atomic number of the bombarded materials. Because of the selective filtering effect of the glass bulb and/or of other tube components, the relative intensity external to the tube is given by the following relationship:

Relative Intensity a iVnZ

where

i = current
 V = accelerating voltage
 Z = atomic number of the "target"

In present monochrome and color picture tubes, which use high absorption glass, "n" is the order of 20.

X-radiation also may be produced in the neck by stray electrons (or ions) that are accelerated by voltages that may be as high as the anode voltage. This radiation is independent of that produced by the beam and, in fact, may be produced when there is no beam current; it is dependent upon voltages that are related to interelectrode potential differences or charge patterns on the glass, and upon leakage currents.

Electron Tube Applications

THE diversified applications of an electron receiving tube have, within the scope of this section, been treated under seven headings: Rectification; Detection; Amplification: TV Scanning, Sync, and Deflection; Oscillation: Frequency Conversion; and Tuning Indication with Electron-Ray Tubes. Although these operations may take place at either radio or audio frequencies and may involve the use of different circuits and different supplemental parts, the general considerations of each kind of operation are basic.

General System Functions

When speech music, or video information is transmitted from a radio or television station, the station radiates a modulated radio-frequency (rf) carrier. The function of a radio or television receiver is simply to reproduce the modulating wave from the modulated carrier.

As shown in Fig. 14, a superheterodyne radio receiver picks up the transmitted modulated rf signal, amplifies it converts it to a modulated intermediate-frequency (if) signal, amplifies the modulated if signal, separates the modulating signal from the basic carrier wave (Detection), and amplifies the

resulting audio signal to a level sufficient to produce the desired volume in a speaker. In addition, the receiver usually includes some means of producing automatic gain control (agc) of the modulated signal before the audio information is separated from the carrier.

The transmitted rf signal picked up by the radio receiver may contain either amplitude modulation (AM) or frequency modulation (FM), (These modulation techniques are described later in the section on Detection.) In either case, amplification prior to the detector stage is performed by tuned amplifier circuits designed for the proper frequency and bandwidth. Frequency conversion is performed by mixer and oscillator circuits or by a single converter stage which performs both mixer and oscillator functions. Separation of the modulating signal is normally accomplished by one or more diodes in a detector or discriminator circuit. Amplification of the audio signal is then performed by one or more audio amplifier stages.

Audio-amplifier systems for phonograph or tape recordings are similar to the stages after detection in a radio receiver. The input to the amplifier is a low-power-level audio signal from the




Fig. 14-Simplified block diagram for a broadcast-band receiver.

phonograph or magnetic-tape pickup head. This signal is usually amplified through a preamplifier stage, one or more low-level (pre-driver or driver) audio stages, and an audio power amplifier. The system may also include frequency-selective circuits which act as equalization networks and/or tone controls.

The operation of a television receiver is more complex than that of a radio receiver, as shown by the simplified block diagram in Fig. 15. The tuner section of the receiver selects the proper rf signals for the desired channel frequency, amplifies them, and converts them to a lower intermediate frequency.

formation to the television picture tube and thus controls instantaneous "spot" brightness. At the same time, deflection circuits cause the electron beam of the picture tube to move the "spot" across the faceplate horizontally and vertically. Special "sync" signals derived from the video signal assure that the horizontal and vertical scanning are timed so that the picture produced on the receiver exactly duplicates the picture being viewed by the camera or pickup tube.

A communications transceiver contains transmitting circuits, as well as receiving circuits similar to those of a radio receiver. The transmitter portion




Fig. 15—Simplified block diagram for a black-and-white television receiver.

As in a radio receiver, these functions are accomplished in rf-amplifier, mixer, and local-oscillator stages. The if signal is then amplified in if-amplifier stages which provide the additional gain required to bring the signal level to an amplitude suitable for detection of the video information.

After detection, the video signal is amplified and separated into sound and picture information. The sound signal is amplified and processed to provide an audio signal which is fed to an audio amplifier system similar to those described above. The picture (video) signal is passed through a video amplifier stage which conveys beam-intensity in-

of such a system consists of two sections. In one section, the desired intelligence (voice, code, or the like) is picked up and amplified through one or more amplifier stages (which are usually common to the receiver portion) to a highlevel stage called a modulator. In the other section, an rf signal of the desired frequency is developed in an oscillator stage and amplified in one or more rf-amplifier stages. The audio-frequency (af) modulating signal is impressed on the rf carrier in the final rf-poweramplifier stage (high-level modulation). in the rf low-level stage (low-level modulation), or in both, Fig. 16 shows a simplified block diagram of the trans-




Fig. 16—Simplified block diagram for the transmitter portion of a 27-MHz communications receiver.

mitter portion of a citizens-band transceiver that operates at a frequency of 27 MHz (megacycles per second). The transmitting section of a communications system may also include frequency-multiplier circuits which raise the frequency of the developed rf signal as required.

Rectification

The rectifying action of a diode finds important applications in supplying a receiver with dc power from an ac line and in supplying high dc voltage from a high-voltage pulse. A typical arrangement for converting ac to dc includes a rectifier tube, a filter, and a voltage divider. The rectifying action of the tube is explained briefly under Diodes, in the Electrons, Electrodes, and Electron Tubes section. High-voltage pulse rectification is described later under Horizontal Output Circuits.

The function of a filter is to smooth out the ripple of the tube out-




Fig. 17—Voltage waveforms of full-wave rectifier circuit.

put, as indicated in Fig. 17, and to increase rectifier efficiency. The action of the filter is explained in the Electron Tube Installation section under Filters. The voltage divider is used to cut down the output voltage to the values required by the plates and the other electrodes of the tubes in the receiver.

A half-wave rectifier and a fullwave rectifier circuit are shown in Fig. 18. In the half-wave circuit, current




Fig. 18—Half-wave and full-wave rectifier circuits.

flows through the rectifier tube to the filter on every other half-cycle of the ac input voltage when the plate is positive with respect to the cathode. In the full-wave circuit, current flows to the filter on every half-cycle, through plate No. 1 on one half-cycle when plate No. 1 is positive with respect to the cathode, and through plate No. 2 on the next

half-cycle when plate No. 2 is positive with respect to the cathode.

Because the current flow to the filter is more uniform in the full-wave circuit than in the half-wave circuit, the output of the full-wave circuit requires less filtering. Rectifier operating information and circuits are given under each rectifier tube type and in the Circuits section, respectively.

Parallel operation of rectifier tubes furnishes an output current greater than that obtainable with the use of one tube. For example, when two full-wave rectifier tubes are connected in parallel, the plates of each tube act connected together and each tube acts as a half-wave rectifier. The permissible voltage and load conditions per tube are the same as for full-wave service but the total load-current-handling capability of the complete rectifier is approximately doubled.

When mercury-vapor rectifier tubes are connected in parallel, a stabilizing resistor of 50 to 100 ohms should be connected in series with each plate lead in order that each tube will carry an equal share of the load current. The value of the resistor to be used will depend on the amount of plate current that passes through the rectifier. Low plate current requires a high value; high plate current, a low value. When the plates of mercury-vapor rectifier tubes are connected in parallel, the corresponding filament leads should be similarly connected. Otherwise, the tube drops will be considerably unbalanced and larger stabilizing resistors will be required.

Two or more vacuum rectifier tubes can also be connected in parallel to give correspondingly higher output current and, as a result of paralleling their internal resistances, give somewhat increased voltage output. With vacuum types, stabilizing resistors may or may not be necessary depending on the tube type and the circuit.

A voltage-doubler circuit of simple form is shown in Fig. 19. The circuit derives its name from the fact that its dc voltage output can be as high as twice the peak value of ac input. Basically, a voltage doubler is a rectifier cir-

cuit arranged so that the output voltages of two half-wave rectifiers are in series.

The action of a voltage doubler can be described briefly as follows. On the positive half-cycle of the ac input, that is, when the upper side of the ac input line is positive with respect to the lower side, the upper diode passes current and feeds a positive charge into the upper capacitor. As positive charge accumulates on the upper plate of the capacitor, a positive voltage builds up across the capacitor. On the next half-cycle of the ac input, when the upper side of the line is negative with respect to the lower side, the lower diode passes current so that




Fig. 19—Full-wave voltage-doubler circuit.

a negative voltage builds up across the lower capacitor.

So long as no current is drawn at the output terminals from the capacitor. each capacitor can charge up to a voltage of magnitude E, the peak value of the ac input. It can be seen from the diagram that with a voltage of +E on one capacitor and -E on the other. the total voltage across the capacitors is 2E. Thus the voltage doubler supplies a no-load de output voltage twice as large as the peak ac input voltage. When current is drawn at the output terminals by the load, the output voltage drops below 2E by an amount that depends on the magnitude of the load current and the capacitance of the capacitors. The arrangement shown in Fig. 19 is called a full-wave voltage doubler because each rectifier passes current to the load on each halt of the ac input cycle.

A rectifier type especially designed for use as a voltage doubler is the 25Z6GT. This tube combines two separate diodes in one tube. As a voltage doubler, the tube is used in "transformerless" receivers. In these receivers, the heaters of all tubes in the set




Fig. 20—Full-wave and half-wave voltage-doubler circuits showing heater-supply connections.

are connected in series with a voltagedropping resistor across the line. The connections for the heater supply and the voltage-doubling circuit are shown in Fig. 20.

With the full-wave voltage-doubler circuit in Fig. 20, it will be noted that the dc load circuit cannot be connected to ground or to one side of the ac supply line. This circuit presents certain disadvantages when the heaters of all the tubes in the set are connected in series with a resistance across the ac line. Such a circuit arrangement may cause hum because of the high ac potential between the heaters and cathodes of the tubes.

The half-wave voltage-doubler circuit in Fig. 20 overcomes this difficulty by making one side of the ac line common with the negative side of the dc load circuit. In this circuit, one half of the tube is used to charge a capacitor which, on the following half cycle, discharges in series with the line voltage through the other half of the tube. This circuit is called a half-wave voltage doubler because rectified current flows to the load only on alternate halves of the ac input cycle. The voltage regulation of this arrangement is somewhat poorer than that of the fullwave voltage doubler.

Detection

When speech, music, or video information is transmitted from a radio or television station, the station radiates a radio-frequency (rf) wave which is of either of two general types. In one type, the wave is said to be amplitude modulated when its frequency remains constant and the amplitude is varied. In the other type, the wave is said to be frequency modulated when its amplitude remains essentially constant but its frequency is varied.

The function of the receiver is to reproduce the original modulating wave from the modulated rf wave. The receiver stage in which this function is performed is called the **demodulator** or **detector** stage.

AM Detection

The effect of amplitude modulation on the waveform of the rf wave is shown in Fig. 21. There are three different basic circuits used for the detection of amplitude-modulated waves: the diode detector, the grid-bias detector, and the grid-resistor detector. These circuits are alike in that they eliminate, either partially or completely, alternate half-cycles of the rf wave. With alternate half-cycles removed, the audio variations of the other half-cycles can be




Fig. 21—Waveforms showing effect of amplitude modulation on an rf wave.

amplified to drive headphones or a loudspeaker.

A diode-detector circuit is shown in Fig. 22. The action of this circuit when a modulated rf wave is applied is




Fig. 22-Basic diode-detector circuit.

illustrated by Fig. 23. The rf voltage applied to the circuit is shown in light line; the output voltage across capacitor C is shown in heavy line.

Between points (a) and (b) on the first positive half-cycle of the applied rf voltage, capacitor C charges up to the peak value of the rf voltage. Then as the applied rf voltage falls away from its peak value, the capacitor holds the cathode at a potential more positive than the voltage applied to the anode.



Fig. 23—Waveforms showing modulated rf input (light line) and output voltage (heavy line) of diode-detector circuit.

The capacitor thus temporarily cuts off current through the diode. While the diode current is cut off, the capacitor discharges from (b) to (c) through the diode load resistor R.

When the rf voltage on the anode rises high enough to exceed the potential at which the capacitor holds the cathode, current flows again and the capacitor charges up to the peak value of the second positive half-cycle at (d). In this way, the voltage across the capacitor follows the peak value of the applied rf voltage and reproduces the af modulation.

The curve for voltage across the capacitor, as shown in Fig. 23, is somewhat jagged. However, this jaggedness, which represents an rf component in the voltage across the capacitor, is

exaggerated in the drawing. In an actual circuit the rf component of the voltage across the capacitor is negligible. Hence, when the voltage across the capacitor is amplified, the output of the amplifier reproduces the speech or music originating at the transmitting station.

Another way to describe the action of a diode detector is to consider the circuit as a half-wave rectifier. When the rf signal on the plate swings positive, the tube conducts and the rectified current flows through the load resistance R. Because the dc output voltage of a rectifier depends on the voltage of the ac input, the dc voltage across C varies in accordance with the amplitude of the rf carrier and thus reproduces the af signal. Capacitor C should be large enough to smooth out rf or if variations, but should not be so large as to affect the audio variations. Two diodes can be connected in a circuit similar to a full-wave rectifier to provide full-wave detection. However, in practice, the advantages of this connection generally do not justify the extra circuit complication.

The diode method of detection produces less distortion than other methods because the dynamic characteristics of a diode can be made more linear than those of other detectors. The disadvantages of a diode are that it does not amplify the signal, and that it draws current from the input circuit and therefore reduces the selectivity of the input circuit. However, because the diode method of detection produces less distortion and because it permits the use of simple avc circuits without the necessity for an additional voltage supply, the diode method of detection is most widely used in broadcast receivers.

A typical diode-detector circuit using a diode—triode tube is shown in Fig. 24. R₁ is the diode load resistor. A portion of the af voltage developed across this resistor is applied to the triode grid through the volume control R₃. In a typical circuit, resistor R₁ may be tapped so that five-sixths of the total af voltage across R₁ is applied to the volume control. This tapped connection reduces the af voltage output of the detector circuit slightly, but it




Fig. 24—Typical diode-detector circuit using a twin diode—triode tube.

reduces audio distortion and improves the rf filtering.

DC bias for the triode section is provided by the cathode-bias resistor R_2 and the audio bypass capacitor C_3 . The function of capacitor C_2 is to block the dc bias of the cathode from the grid. The function of capacitor C_4 is to bypass any rf voltage on the grid to cathode. A diode—pentode may also be used in this circuit. With a pentode, the af output should be resistance-coupled rather than transformer-coupled.

Another diode-detector circuit, called a diode-biased circuit, is shown in Fig. 25. In this circuit, the triode grid




Fig. 25—Diode-biased detector circuit.

is connected directly to a tap on the diode load resistor. When an rf signal voltage is applied to the diode, the dc voltage at the tap supplies bias to the triode grid. When the rf signal is modulated, the af voltage at the tap is applied to the grid and is amplified by the triode.

The advantage of the circuit shown in Fig. 25 over the self-biased arrangement shown in Fig. 24 is that the diode-biased circuit does not employ a capacitor between the grid and the diode load resistor, and consequently does not produce as much distortion of a signal having a high percentage of modulation.

However, there are restrictions on the use of the diode-biased circuit. Be-

cause the bias voltage on the triode depends on the average amplitude of the rf voltage applied to the diode, the average amplitude of the voltage applied to the diode should be constant for all values of signal strength at the antenna. Otherwise there will be different values of bias on the triode grid for different signal strengths and the triode will produce distortion. Because there is no bias applied to the diodebiased triode when no rf voltage is applied to the diode, sufficient resistance should be included in the plate circuit of the triode to limit its zerobias plate current to a safe value.

These restrictions mean, in practice, that the receiver should have a separate-channel automatic-volume-control (avc) system. With such an avc system, the average amplitude of the signal voltage applied to the diode can be held within very close limits for all values of signal strength at the antenna.

The tube used in a diode-biased circuit should be one which operates at a fairly large value of bias voltage. The variations in bias voltage are then a small percentage of the total bias and hence produce small distortion. Tubes taking a fairly large bias voltage are types such as the 6BF6 or 6SR7 having a medium-mu triode. Tube types having a high-mu triode or a pentode should not be used in a diode-biased circuit.

A grid-bias detector circuit is shown in Fig. 26. In this circuit, the grid is biased almost to cutoff, *i.e.*, operated so that the plate current with zero signal is practically zero. The bias voltage can be obtained from a cathodebias resistor, a C-battery, or a bleeder tap. Because of the high negative bias, only the positive half-cycles of the risignal are amplified by the tube. The signal is, therefore, detected in the




Fig. 26-Grid-bias detector circuit.

plate circuit. The advantages of this method of detection are that it amplifies the signal, besides detecting it, and that it does not draw current from the input circuit and therefore does not reduce the selectivity of the input circuit.

The grid-resistor-and-capacitor method, illustrated in Fig. 27, is somewhat more sensitive than the grid-bias method and gives its best results on weak signals. In this circuit, there is no negative de bias voltage applied to the grid. Hence, on the positive half-cycles of the rf signal, current flows from grid to cathode. The grid and cathode thus act as a diode detector, with the grid resistor as the diode load resistor and the grid capacitor as the rf bypass capacitor. The voltage across the capacitor then reproduces the af modulation in the same manner as has been explained for the diode detector. This voltage appears between the grid and cathode and is therefore amplified in




Fig. 27—Detector circuit using grid-resistorand-capacitor bias.

the plate circuit. The output voltage thus reproduces the original af signal.

In this detector circuit, the use of a high-resistance grid resistor increases selectivity and sensitivity. However, improved af response and stability are obtained with lower values of grid-circuit resistance. This detector circuit amplifies the signal, but draws current from the input circuit and therefore reduces the selectivity of the input circuit.

FM Detection

The effect of frequency modulation on the waveform of the rf wave is shown in Fig. 28. In this type of transmission, the frequency of the rf wave deviates from a mean value, at an audiofrequency rate depending on the modu-




Fig. 28—Waveforms showing effect of frequency modulation on an rf wave.

lation, by an amount that is determined in the transmitter and is proportional to the amplitude of the af modulation signal.

For this type of modulation, a detector is required to discriminate between deviations above and below the mean frequency and to translate those deviations into a voltage whose amplitude varies at audio frequencies. Since the deviations occur at an audio frequency, the process is one of demodulation, and the degree of frequency deviation determines the amplitude of the demodulated (af) voltage.

A simple circuit for converting frequency variations to amplitude variations is a circuit which is tuned so that the mean radio frequency is on one slope of its resonance characteristic, as at A of Fig. 29. With modulation, the




Fig. 29—Resonance curve of a tuned circuit showing desired operating range for frequency-modulation converter.




Fig. 30-Balanced phase-shift discriminator circuit.

frequency swings between B and C, and the voltage developed across the circuit varies at the modulating rate. In order that no distortion will be introduced in this circuit, the frequency swing must be restricted to the portion of the slope which is effectively straight. Since this portion is very short, the voltage developed is low. Because of these limitations, this circuit is not commonly used but it serves to illustrate the principle.

The faults of the simple circuit are overcome in a push-pull arrangement, such as that shown in Fig. 30, called a balanced phase-shift discriminator. In this detector, the mutually coupled tuned circuits in the primary and secondary windings of the transformer T are tuned to the center frequency. A characteristic of a double-tuned transformer is that the voltages in the primary and secondary windings are 90 degrees out of phase at resonance, and that the phase shift changes as the frequency changes from resonance. Therefore, the signal applied to the diodes and the RC combinations for peak detection also changes with frequency.

Because the secondary winding of the transformer T is center-tapped, the applied primary voltage E_p is added to one-half the secondary voltage E_s through the capacitor C_c . The addition of these voltages at resonance can be represented by the diagram in Fig. 31(a); the resultant voltage E_1 is the signal applied to one peak-detector network consisting of one diode and its RC load. When the signal frequency decreases (from resonance), the phase shift of $E_s/2$ becomes greater than 90 degrees, as shown at (b) in Fig. 31, and E_1 becomes smaller. When the signal fre-

quency increases (above resonance), the phase shift of E_s/2 is less than 90 degrees as shown at (c), and E₁ becomes




Fig. 31—Diagram illustrating phase shift in double-tuned transformer (a) at resonance, (b) below resonance, and (c) above resonance.

larger. The curve of E_1 as a function of frequency in Fig. 32 is readily identified as the response curve of an FM detector.




Fig. 32—Diagram showing resultant voltage E_1 in Fig. 31 as a function of frequency.

Because the discriminator circuit shown in Fig. 30 uses a push-pull configuration, the diodes conduct on alternate half-cycles of the signal frequency and produce a plus-and-minus output with respect to zero rather than with

respect to E1. The primary advantage of this arrangement is that there is no output at resonance. When an FM signal is applied to the input, the audio output voltage varies above and below zero as the instantaneous frequency varies above and below resonance. The frequency of this audio voltage is determined by the modulation frequency of the FM signal, and the amplitude of the voltage is proportional to the frequency excursion from resonance. (The resistor R₂ in the circuit provides a dc return for the diodes, and also maintains a load impedance across the primary winding of the transformer.)

One disadvantage of the balanced phase-shift discriminator shown in Fig. 30 is that it detects audio modulation (AM) as well as frequency modulation (FM) in the if signal because the circuit is balanced only at the center frequency. At frequencies off resonance, any variation in amplitude of the if signal is reproduced to some extent in the audio output.

The ratio-detector circuit shown in Fig. 33 is a discriminator circuit which has the advantage of being relatively

placed "back-to-back" (in series, rather than in push-pull) so that both halves of the circuit operate simultaneously during one-half of the signal frequency cycle (and are cut off on the other half-cycle). As a result, the detected voltages E_1 and E_2 are in series, as shown for the instantaneous polarities that occur during the conduction half-cycle. When the audio output is taken between the equal capacitors C_1 and C_2 , therefore, the output voltage is equal to $(E_2-E_1)/2$ (for equal resistors R_1 and R_2).

The dc circuit of the ratio detector consists of a path through the secondary winding of the transformer, both diodes (which are in series), and resistors R_1 and R_2 . The value of the electrolytic capacitor C_2 is selected so that the time constant of R_1 , R_2 , and C_3 is very long compared to the detected audio signal. As a result, the sum of the detected voltages $(E_1 + E_2)$ is a constant and the AM components on the signal frequency are suppressed. This feature of the ratio detector provides improved AM rejection as compared to the phase-shift discriminator circuit shown in Fig. 30.




Fig. 33-Ratio-detector circuit.

insensitive to amplitude variations in the FM signal. In this circuit, E_p is added to $E_a/2$ through the mutual coupling M_2 (this voltage addition may be made by either mutual or capacitive coupling). Because of the phase-shift relationship of these voltages, the resultant detected signals vary with frequency variations in the same manner as described for the phase-shift discriminator circuit shown in Fig. 30. However, the diodes in the ratio detector are

Amplification

The amplifying action of an electron tube was mentioned under Triodes in the section on Electrons, Electrodes, and Electron Tubes. This action can be utilized in electronic circuits in a number of ways, depending upon the results desired. Four classes of amplifier service recognized by engineers are covered by definitions standardized by the Institute of Electrical and

Electronics Engineers. This classification depends primarily on the fraction of input cycle during which plate current is expected to flow under rated full-load conditions. The classes are class A, class AB, class B, and class C. The term "cutoff bias" used in these definitions is the value of grid bias at which plate current is very small (i.e., approaches zero).

Classes of Service

A class A amplifier is an amplifier in which the grid bias and alternating grid voltages are such that plate current in a specific tube flows at all times.

A class AB amplifier is an amplifier in which the grid bias and alternating grid voltages are such that plate current in a specific tube flows for appreciably more than half but less than the entire electrical cycle.

A class B amplifier is an amplifier in which the grid bias is approximately equal to the cutoff value, so that the plate current is approximately zero when no exciting grid voltage is applied, and so that plate current in a specific tube flows for approximately one-half of each cycle when an alternating grid voltage is applied.

A class C amplifier is an amplifier in which the grid bias is appreciably greater than the cutoff value, so that the plate current in each tube is zero when no alternating grid voltage is applied, and so that plate current flows in a specific tube for appreciably less than one-half of each cycle when an alternating grid voltage is applied.

The suffix 1 may be added to the letter or letters of the class identification to denote that grid current does not flow during any part of the input cycle. The suffix 2 may be used to denote that grid current flows during part of the cycle.

For radio-frequency (rf) amplifiers which operate into a selective tuned circuit, as in radio transmitter applications, or under requirements where distortion is not an important factor, any of the above classes of amplifiers may be used, either with a single tube or with a push-pull stage. For audio-frequency (af) amplifiers in which dis-

tortion is an important factor, only class A amplifiers permit single-tube operation. In this case, operating conditions are usually chosen so that distortion is kept below the conventional 5 per cent for triodes and the conventional 7 to 10 per cent for tetrodes or pentodes. Distortion can be reduced below these figures by means of special circuit arrangements such as that discussed under inverse feedback. With class A amplifiers, reduced distortion with improved power performance can be obtained by using a push-pull stage for audio service. With class AB and class B amplifiers, a balanced stage using two tubes is required for audio service.

Class A Voltage Amplifiers

As a class A voltage amplifier, an electron tube is used to reproduce gridvoltage variations across an impedance or a resistance in the plate circuit. These variations are essentially of the same form as the input signal voltage impressed on the grid, but their amplitude is increased. This increase is accomplished by operation of the tube at a suitable grid bias so that the applied grid input voltage produces plate-current variations proportional to the signal swings. Because the voltage variation obtained in the plate circuit is much larger than that required to swing the grid, amplification of the signal is obtained.

Fig. 34 gives a graphical illustration of this method of amplication and shows, by means of the grid-voltage vs. plate-current characteristics curve, the effect of an input signal (S) applied to




Fig. 34—Current characteristics of class A amplifier.

the grid of a tube. The output signal (O) is the resulting amplified plate-current variation.

The plate current flowing through the load resistance (R) of Fig. 35 causes a voltage drop which varies directly with the plate current. The ratio of this voltage variation produced in the load resistance to the input signal volt-




Fig. 35—Triode amplifier circuit.

age is the voltage amplification, or gain, provided by the tube. The voltage amplification due to the tube is expressed by the following convenient formulas:

$$\label{eq:Voltage amplification} \begin{split} \text{Voltage amplification} &= \frac{\mu \times R_L}{R_L + r_p} \\ \text{or} &\; \frac{g_m \times r_p \times R_L}{1000000 \times (r_p + R_L)} \end{split}$$

where μ is the amplification factor of the tube, R_L is the load resistance in ohms, r_p is the plate resistance in ohms, and g_m is the transconductance in micromhos.

From the first formula, it can be seen that the gain actually obtainable from the tube is less than the tube amplification factor, but that the gain approaches the amplification factor when the load resistance is large compared to the tube plate resistance. Fig. 36 shows graphically how the gain approaches the amplification factor of the tube as the load resistance is increased.

From the curve it can be seen that a high value of load resistance should be used to obtain high gain in a voltage amplifier.

In a resistance-coupled amplifier. the load resistance of the tube is approximately equal to the resistance of the plate resistor in parallel with the grid resistor of the following stage. Hence, to obtain a large value of load resistance, it is necessary to use a plate resistor and a grid resistor of large resistance. However, the plate resistor should not be too large because the flow of plate current through the plate resistor produces a voltage drop which reduces the plate voltage applied to the tube. If the plate resistor is too large, this drop will be too large, the plate voltage on the tube will be too small, and the voltage output of the tube will be too small. Also, the grid resistor of the following stage should not be too large, the actual maximum value being dependent on the particular tube type. This precaution is necessary because all tubes contain minute amounts of residual gas which cause a minute flow of current through the grid resistor. If the grid resistor is too large, the positive bias developed by the flow of this current through the resistor decreases the normal negative bias and produces an increase in the plate current. This increased current may overheat the tube and cause liberation of more gas which, in turn, will cause further decrease in bias. The action is cumulative and results in a runaway condition which can destroy the tube.

A higher value of grid resistance is permissible when cathode-resistor bias is used than when fixed bias is used.




Fig. 36—Gain curve for triode amplifier circuit.

When cathode-resistor bias is used, a loss in bias due to gas or grid-emission effects is almost completely offset by an increase in bias due to the voltage drop across the cathode resistor. Typical values of plate resistor and grid resistor for tube types used in resistance-coupled circuits, and the values of gain obtainable, are shown in the Resistance-Coupled Amplifier section.

The input impedance of an electron tube (that is, the impedance between grid and cathode) consists of (1) a reactive component due to the capacitance between grid and cathode, (2) a resistive component resulting from the time of transit of electrons between cathode and grid, and (3) a resistive component developed by the part of the cathode lead inductance which is common to both the input and output circuits. These components are dependent on the frequency of the incoming signal. The input impedance is very high at audio frequencies when a tube is operated with its grid biased negative. In a class A₁ or AB₁ transformer-coupled audio amplifier, therefore, the loading imposed by the grid on the input transformer is negligible. As a result, the secondary impedance of a class A₁ or class AB₁ input transformer can be made very high because the choice is not limited by the input impedance of the tube; however, transformer design considerations may limit the choice.

At the higher radio frequencies, the input impedance may become very low even when the grid is negative, due to the finite time of passage of electrons between cathode and grid and to the appreciable lead reactance. This impedance drops very rapidly as the frequency is raised, and increases inputcircuit loading. In fact, the input impedance may become low enough at very high radio frequencies to affect the gain and selectivity of a preceding stage appreciably. Tubes such as the "acorn" and "pencil" types and the high-frequency miniatures have been developed to have low input capacitances, low electron-transit time, and low lead inductance so that their input impedance is high even at the ultrahigh radio frequencies. **Input ad**mittance is the reciprocal of input impedance.

A remote-cutoff amplifier tube is a modified construction of a pentode or a tetrode type designed to reduce modulation-distortion and cross-modulation in radio-frequency stages. Crossmodulation is the effect produced in a radio or television receiver by an interfering station "riding through" on the carrier of the station to which the receiver is tuned. Modulation-distortion is a distortion of the modulated carrier and appears as audio-frequency distortion in the output. This effect is produced by a radio-frequency amplifier stage operating on an excessively curved characteristic when the grid bias has been increased to reduce volume. The offending stage for cross-modulation is usually the first radio-frequency amplifier, while for modulation-distortion the cause is usually the last intermediate-frequency stage. The characteristics of remote-cutoff types are such as to enable them to handle both large and small input signals with minimum distortion over a wide range of signal strength.

Fig. 37 illustrates the construction of the grid No. 1 (control grid) in a remote-cutoff tube. The remote-cutoff




Fig. 37—Structure of remote-cutoff grid. action is due to the structure of the grid which provides a variation in amplification factor with change in grid bias. The grid No. 1 is wound with open spacing at the middle and with close spacing at the ends. When weak signals and low grid bias are applied to the tube, the effect of the non-uniform turn spacing of the grid on cathode emission and tube characteristics is essentially the same as for uniform spacing. As the

grid bias is made more negative to handle larger input signals, the electron flow from the sections of the cathode enclosed by the ends of the grid is cut off. The plate current and other tube characteristics are then dependent on the electron flow through the open section of the grid. This action changes the gain of the tube so that large signals may be handled with minimum distortion due to cross-modulation and modulation-distortion.

Fig. 38 shows a typical plate-current vs. grid-voltage curve for a remotecutoff type compared with the curve




Fig. 38—Plate-current curves for triodes having remote-cutoff and uniformly spaced grids.

for a type having a uniformly spaced grid. It will be noted that while the curves are similar at small grid-bias voltages, the plate current of the remote-cutoff tube drops quite slowly with large values of bias voltage. This slow change makes it possible for the tube to handle large signals satisfactorily. Because remote-cutoff types can accommodate large and small signals, they are particularly suitable for use in sets having automatic volume control. Remote-cutoff tubes also are known as variable-mu types.

Class A Power Amplifiers

As a class A power amplifier, an electron tube is used in the output stage of a radio or television receiver to supply a relatively large amount of power to the loudspeaker. For this application, large power output is of more importance than high voltage amplification; therefore, gain possibilities are sacrificed in the design of power tubes to obtain power-handling capability.

Triodes, pentodes, and beam power

tubes designed for power amplifier service have certain inherent features for each structure. Power tubes of the triode type for class A service are characterized by low power sensitivity, low plate-power efficiency, and low distortion. Power tubes of the pentode type are characterized by high power sensitivity, high plate-power efficiency and, usually, somewhat higher distortion than class A triodes. Beam power tubes have higher power sensitivity and efficiency than triode or conventional pentode types.

A class A power amplifier is also used as a driver to supply power to a class AB₂ or a class B stage. It is usually advisable to use a triode, rather than a pentode, in a driver stage because of the lower plate impedance of the triode.

Power tubes connected in either parallel or push-pull may be employed as class A amplifiers to obtain increased output. The parallel connection (Fig. 39) provides twice the output of a single tube with the same value of grid-signal voltage. With this connection, the effective transconductance of the stage is doubled, and the effective plate




Fig. 39—Power amplifier with tubes connected in parallel.

resistance and the load resistance required are halved as compared with single-tube values.

The push-pull connection (Fig. 40), although it requires twice the grid-signal voltage, provides increased power and has other important advantages over single-tube operation. Distortion caused by even-order harmonics and hum caused by plate-voltage-supply fluctuations are either eliminated or decidedly reduced through cancellation.

Because distortion for push-pull operation is less than for single-tube operation, appreciably more than twice single-tube output can be obtained with triodes by decreasing the load resistance for the stage to a value approaching the load resistance for a single tube.

For either parallel or push-pull class A operation of two tubes, all electrode currents are doubled while all de electrode voltages remain the same as for single-tube operation. If a cathode resistor is used, its value should be about one-half that for a single tube.




Fig. 40—Power amplifier with tubes connected in push-pull.

If oscillations occur with either type of connection, they can often be eliminated by the use of a non-inductive resistor of approximately 100 ohms connected in series with each grid at the socket terminal.

Operation of power tubes so that the grids run positive is inadvisable except under conditions such as those discussed in this section for class AB and class B amplifiers.

Power-Output Calculations

Calculation of the power output of a triode used as a class A amplifier with either an output transformer or a choke having low dc resistance can be made without serious error from the plate family of curves by assuming a resistance load. The proper plate current, grid bias, optimum load resistance, and per-cent second-harmonic distortion can also be determined. The calculations are made graphically and are illustrated in Fig. 41 for given conditions. The procedure is as follows:

(1) Locate the zero-signal bias point P by determining the zero-signal bias Ec. from the formula:

Zero-signal bias (Ec_o) = $-(0.68 \times E_b)/\mu$

where E_b is the chosen value in volts of dc plate voltage at which the tube is to be operated, and μ is the amplification factor of the tube. This quantity is shown as negative to indicate that a negative bias is used.

- (2) Locate the value of zero-signal plate current, I₀, corresponding to point P.
- (3) Locate the point 2I_o, which is twice the value of I_o and corresponds to the value of the maximum-signal plate current I_{max}.
- (4) Locate the point X on the dc bias curve at zero volts, $E_c = 0$, corresponding to the value of I_{max} .
- (5) Draw a straight line XY through X and P.

Line XY is known as the load resistance line. Its slope corresponds to the value of the load resistance. The load resistance in ohms is equal to $(E_{max} - E_{min})$ divided by $(I_{max} - I_{min})$, where E is in volts and I is in amperes.

It should be noted that in the case of filament types of tubes, the calculations are given on the basis of a dcoperated filament. When the filament is ac-operated, the calculated value of dc




Fig. 41-Graphic calculations for class A amplifier using a power triode.

bias should be increased by approximately one-half the filament voltage

rating of the tube.

The value of zero-signal plate current Io should be used to determine the plate dissipation, an important factor influencing tube life. In a class A amplifier under zero-signal conditions, the plate dissipation is equal to the power input, i.e., the product of the dc plate voltage E_o and the zero-signal dc plate current Io. If it is found that the platedissipation rating of the tube is exceeded with the zero-signal bias Ec. calculated above, it will be necessary to increase the bias by a sufficient amount so that the actual plate dissipation does not exceed the rating before proceeding further with the remaining calculations.

For power-output calculations, it is assumed that the peak alternating grid voltage is sufficient (1) to swing the grid from the zero-signal bias value $E_{\rm c}$ to zero bias ($E_{\rm c}=0$) on the positive swing and (2) to swing the grid to a value twice the zero-signal bias value on the negative swing. During the negative swing, the plate voltage and plate current reach values of $E_{\rm max}$ and $I_{\rm min}$; during the positive swing, they reach values of $E_{\rm min}$ and $I_{\rm max}$. Because power is the product of voltage and current, the power output $P_{\rm o}$ as shown by a watt-meter is given by

$$P_o = \frac{(I_{max}-I_{min}) \times (E_{max}-E_{min})}{8}$$

where E is in volts, I is in amperes, and Po is in watts.

In the output of power-amplifier triodes, some distortion is present. This distortion is due predominantly to second harmonics in single-tube amplifiers. The percentage of second-harmonic distortion may be calculated by the following formula:

% distortion =
$$\frac{\frac{I_{max} + I_{min}}{2} - I_{o}}{\frac{I_{max} - I_{min}}{1}} \times 100$$

where I_o is the zero-signal plate current in amperes. If the distortion is excessive, the load resistance should be increased or, occasionally, decreased slightly and the calculations repeated.

Example: Determine the load resistance, power output, and distortion

of a triode having an amplification factor of 4.2, a plate-dissipation rating of 15 watts, and plate-characteristics curves as shown in Fig. 41. The tube is to be operated at 250 volts on the plate.

Procedure: For a first approximation, determine the operating point P from the zero-signal bias formula, Ec. $= -(0.68 \times 250) / 4.2 = -40.5$ volts. From the curve for this voltage, it is found that the zero-signal plate current is 0.08 ampere and, therefore, the platedissipation rating is exceeded $(0.08 \times$ 250 = 20 watts). Consequently, it is necessary to reduce the zero-signal plate current to 0.06 ampere at 250 volts. The grid bias is then -43.5 volts. Note that the curve was taken with a dc filament supply; if the filament is to be operated on an ac supply, the bias must be increased by about onehalf the filament voltage, or to -45 volts, and the circuit returns made to the mid-point of the filament circuit.

Point X can then be determined. Point X is at the intersection of the debias curve at zero volts with I_{max} , where $I_{max} = 2I_o = 2 \times 0.06 = 0.12$ ampere. Line XY is drawn through points P and X. E_{max} , E_{min} , and I_{min} are then found from the curves. When these values are substituted in the power-output formula, the following result is obtained:

$$P_o = \frac{(0.12 - 0.012) \times (365 - 105)}{8} = 3.52 \text{ watts}$$

The resistance represented by load line XY is

$$\frac{(365 - 105)}{(0.12 - 0.012)} = 2410 \text{ ohms}$$

When the values from the curves are substituted in the distortion formula, the following result is obtained:

% distortion =
$$\frac{\frac{0.12 + 0.012}{2} - 0.06}{\frac{0.12 - 0.012}{0.12 - 0.012}} \times 100 = 5.5\%$$

It is customary to select the load resistance so that the distortion does not exceed five per cent. When the method shown is used to determine the slope of the load-resistance line, the second-harmonic distortion generally does not exceed five per cent. In the example, however, the distortion is excessive and it is desirable, therefore, to use a slightly higher load resistance. A load resistance

of 2500 ohms will provide a distortion of about 4.9 per cent. The power output is reduced only slightly to 3.5 watts.

Operating conditions for **triodes in push-pull** depend on the type of operation desired. Under class A conditions, distortion, power output, and efficiency are all relatively low. The operating bias can be anywhere between that specified for single-tube operation and that equal to one-half the grid-bias voltage required to produce plate-current cutoff at a plate voltage of 1.4E_o, where E_o is the operating plate voltage. Higher bias than this value requires higher grid-signal voltage and results in class AB, operation, which is discussed later.

The method for calculating maximum power output for triodes in pushpull class A operation is as follows: Erect a vertical line at $0.6~E_{\circ}$ (see Fig. 42), intersecting the $E_{c}=0$ curve at the point I_{max} . Then, I_{max} is determined from the curve for use in the formula

$$P_0 = (I_{max} \times E_0)/5$$

If I_{max} is expressed in amperes and E_o in volts, power output is in watts.

Example: Assume that the plate voltage (E₀) is to be 300 volts, and the plate-dissipation rating of the tube is 15 watts. Then, for class A operation, the operating bias can be equal to, but not more than, one-half the grid bias for cutoff with a plate voltage of 1.4 × 300 = 420 volts. (Since cutoff bias is approximately -115 volts at a plate voltage of 420 volts, one-half of this value is -57.5 volts bias.) At this bias, the plate current is found from the plate family to be 0.054 ampere and, therefore, the plate dissipation is $0.054 \times$ 300 or 16.2 watts. Since -57.5 volts is the limit of bias for class A operation of these tubes at a plate voltage of 300 volts, the dissipation cannot be reduced by increasing the bias and it becomes necessary to reduce the plate voltage.

If the plate voltage is reduced to 250 volts, the bias will be found to be -43.5 volts. For this value, the plate current is 0.06 ampere, and the plate dissipation is 15 watts. Then, following the method for calculating power output, erect a vertical line at 0.6E_o = 150




Fig. 42—Graphic calculations for push-pull class A amplifier using a power triode.

The method for determining the proper load resistance for triodes in push-pull is as follows: Draw a load line through I_{max} on the zero-bias curve and through the E_o point on the zero-current axis. Four times the resistance represented by this load line is the plate-to-plate load (R_{pp}) for two triodes in a class A push-pull amplifier. Expressed as a formula,

$$R_{pp} = 4 \times (E_o - 0.6E_o)/I_{max}$$

where E_0 is expressed in volts, I_{max} in amperes, and R_{pp} in ohms.

volts. The intersection of the line with the curve $E_c = 0$ is I_{max} or 0.2 ampere. When this value is substituted in the power formula, the power output is $(0.2 \times 250)/5 = 10$ watts. The load resistance is determined from the load formula: Plate-to-plate load $(R_{pp}) = 4 \times (250 - 150)/0.2 = 2000$ ohms.

Power output for a pentode or a beam power tube as a class A amplifier can be calculated in much the same way as for triodes. Calculations can be made graphically from a special plate family of curves, as shown in Fig. 43.




Fig. 43—Graphic calculations for class A amplifier using a pentode or beam power tube.

From a point A at or just below the knee of the zero-bias curve, draw arbitrarily selected load lines to intersect the zero-plate-current axis. These lines should be on both sides of the operating point P, whose position is determined by the desired operating plate voltage, E_o, and one-half the maximum-signal plate current. Along any load line, say AA1, measure the distance AO₁. On the same line, lay off an equal distance, O1A1. For optimum operation, the change in bias from A to O₁ should be nearly equal to the change in bias from O₁ to A₁. If this condition can not be met with one line, as is the case for the line first chosen. then another should be chosen. When the most satisfactory line has been selected, its resistance may be determined by the following formula:

Load resistance (R_L) =
$$\frac{E_{max} - E_{min}}{I_{max} - I_{min}}$$

The value of R_L may then be substituted in the following formula for calculating power output.

$$P_{0} = \frac{[I_{max} - I_{min} + 1.41 (I_{x} - I_{y})]^{2} R_{L}}{32}$$

In both of these formulas, I is in amperes, E is in volts, R_L is in ohms, and P_0 is in watts. I_x and I_y are the current values on the load line at bias voltages of $Ec_1 = V - 0.707V = 0.293V$ and $E_{e1} = V + 0.707V = 1.707V$, respectively.

Calculations for distortion may be made by means of the following formulas. The terms used have already been defined.

% 2nd-harmonic distortion =
$$\frac{I_{\text{max}} + I_{\text{min}} - 2 I_{\text{o}}}{I_{\text{max}} - I_{\text{min}} + 1.41 (I_{\text{x}} - I_{\text{y}})} \times 100$$
% 3rd-harmonic distortion =

$$\frac{I_{\text{max}} - I_{\text{min}} - 1.41 (I_{\text{x}} - I_{\text{y}})}{I_{\text{max}} - I_{\text{min}} + 1.41 (I_{\text{x}} - I_{\text{y}})} \times 100$$
% total (2nd and 3rd) harmonic distortion =
$$\sqrt{(\% \text{ 2nd})^3 + (\% \text{ 3rd})^2}$$

Conversion Factors

Operating conditions for voltage values other than those shown in the published data can be obtained by use of the nomograph shown in Fig. 44 when all electrode voltages are changed simultaneously in the same ratio. The nomograph includes conversion factors for current (F_i) , power output (F_p) , plate resistance or load resistance (F.). and transconductance (Fgm) for voltage ratios between 0.5 and 2.0. These factors are expressed as functions of the ratio between the desired or new voltage for any electrode (Edea) and the published or original value of that voltage (E_{pub}). The relations shown are applicable to triodes and multigrid tubes in all classes of service.

To use the nomograph, simply place a straight-edge across the page so that it intersects the scales for E_{do} and E_{pub} at the desired values. The desired conversion factor may then be read directly or estimated at the point where the straight-edge intersects the F_1 , F_p , F_r , or F_{gm} scale.

For example, suppose it is desired to operate two 6L6GC's in class A₁ push-pull, fixed bias, with a plate voltage of 200 volts. The nearest published operating conditions for this class of service are for a plate voltage of 250 volts. The operating conditions for the new plate voltage can be determined as follows:

The voltage conversion factor, F_e , is equal to 200/250 or 0.8. The dashed lines on the nomograph of Fig. 44 indicate that for this voltage ratio F_1 is approximately 0.72, F_p is approximately 0.57, F_r is 1.12, and F_{gm} is approximately 0.892. These factors may be applied directly to operating values shown in the tube data, or to values calculated by the methods described previously.

Because this method for conversion

of characteristics is necessarily an approximation, the accuracy of the nomograph decreases progressively as the ratio E_{des}/E_{pub} departs from unity. In general, results are substantially correct when the value of the ratio E_{des}/E_{pub} is between 0.7 and 1.5. Beyond these limits, the accuracy decreases rapidly, and the results obtained must be considered rough approximations.

The nomograph does not take into consideration the effects of contact potential or secondary emission in tubes. Because contact-potential effects become noticeable only at very small dc grid-No. 1 (bias) voltages, they are generally negligible in power tubes. Secondary emission may occur in conventional tetrodes, however, if the plate voltage swings below the grid-No. 2 voltage. Consequently, the conversion




Fig. 44-Nomograph of tube conversion factors.

factors shown in the nomograph apply to such tubes only when the plate voltage is greater than the grid-No. 2 voltage. Because secondary emission may also occur in certain beam power tubes at very low values of plate current and plate voltage, the conversion factors shown in the nomograph do not apply when these tubes are operated under such conditions.

Class AB Power Amplifiers

A class AB power amplifier employs two tubes connected in push-pull with a higher negative grid bias than is used in a class A stage. With this higher negative bias, the plate and screengrid voltages can usually be made higher than for class A amplifiers because the increased negative bias holds plate current within the limit of the tube plate-dissipation rating. As a result of these higher voltages, more power output can be obtained from class AB operation.

Class AB amplifiers are subdivided into class AB₁ and class AB₂. In class AB₁, there is no flow of grid current. That is, the peak signal voltage applied to each grid is not greater than the negative grid-bias voltage. The grids therefore are not driven to a positive potential and do not draw current. In class AB2, the peak signal voltage is greater than the bias so that the grids are driven positive and draw current.


Because of the flow of grid current in a class AB, stage, there is a loss of power in the grid circuit. The sum of this loss and the loss in the input transformer is the total driving power required by the grid circuit. The driver stage should be capable of a power output considerably larger than this required power in order that distortion introduced in the grid circuit be kept low. The input transformer used in a class AB₂ amplifier usually has a stepdown turns ratio.

Because of the large fluctuations of plate current in a class AB, stage, it is important that the plate power supply have good regulation. Otherwise the fluctuations in plate current cause fluctuations in the voltage output of the power supply, with the result that power output is decreased and distortion is increased. To obtain satisfactory regulation, it is usually advisable to use a low-drop rectifier, such as the 5V4GA, with a choke-input filter. In all cases, the resistance of the choke and transformers should be as low as possible.

Class AB, Power Amplifiers

In class AB, push-pull amplifier service using triodes, the operating conditions may be determined graphically by means of the plate family if E., the desired operating plate voltage, is given. In this service, the dynamic load line does not pass through the operating point P as in the case of the single-tube amplifier, but through the point D in Fig. 45. Its position is not affected by the operating grid bias provided the plate-to-plate load resistance remains constant.

Under these conditions, grid bias has no appreciable effect on the power



E4=2.5 VOLTS DC

Fig. 45—Graphic calculations for class AB₁ amplifier Fig. 46—Instantaneous curve using a power triode. for class AB, amplifier.

output. Grid bias cannot be neglected, however, since it is used to find the zero-signal plate current and, from it, the zero-signal plate dissipation. Because the grid bias is higher in class AB₁ than in class A service for the same plate voltage, a higher signal voltage may be used without grid current being drawn and, therefore, higher power output is obtained.

In general, for any load line through point D, Fig. 45, the plate-toplate load resistance in ohms of a pushpull amplifier is $R_{pp} = 4E_o/I'$, where I' is the plate-current value in amperes at which the load line as projected intersects the plate-current axis, and E_o is in volts. This formula is another form of the one given under pushpull class A amplifiers, $R_{pp} = 4(E_o -$ 0.6E₀)/I_{max}, but is more general. Power output $\equiv (I_{max}/\sqrt{2})^2 \times R_{pp}/4$, where Imax is the peak plate current at zero grid volts for the load chosen. This formula simplified is $(I_{max})^2 \times R_{pp}/8$. The maximum-signal average plate current is $2I_{max}/\pi$ or 0.636 I_{max} ; the maximum-signal average power input is $0.636 I_{max} \times E_0$.

It is desirable to simplify these formulas for a first approximation. This simplification can be made if it is assumed that the peak plate current, I_{max} , occurs at the point of the zero-bias curve corresponding approximately to 0.6 E_o , the condition for maximum power output. The simplified formulas are:

$$\begin{array}{c} P_o \; (\text{for two tubes}) = (I_{\text{max}} \times E_o)/5 \\ R_{pp} = 1.6 E_o/I_{\text{max}} \end{array}$$

where E_o is in volts, I_{max} is in amperes, R_{pp} is in ohms, and P_o is in watts.

It may be found during subsequent calculations that the distortion or the plate dissipation is excessive for this approximation; in that case, a different load resistance must be selected, using the first approximation as a guide, and the process repeated to obtain satisfactory operating conditions.

Example: Fig. 45 illustrates the application of this method to a pair of power triodes operated at E_o = 300 volts. Each tube has a plate-dissipation rating of 15 watts. The method is to

erect a vertical line at $0.6E_0$, or at 180 volts, which intersects the $E_c = 0$ curve at the point $I_{max} = 0.26$ ampere. Using the simplified formulas, the following values are obtained:

$$R_{pp} = (1.6 \times 300)/0.26 = 1845 \text{ ohms}$$

 $P_0 = (0.26 \times 300)/5 = 15.6 \text{ watts}$

At this point, it is well to determine the plate dissipation and to compare it with the maximum rated value. From the average-plate-current formula (0.636 I_{max}) mentioned previously, the maximum-signal average plate current is 0.166 ampere. The product of this current and the operating plate voltage is 49.8 watts, the average input to the two tubes. From this value, subtract the power output of 15.6 watts to obtain the total dissipation for both tubes, which is 34.2 watts. Half of this value. 17 watts, is in excess of the 15-watt rating of the tube and it is necessary. therefore, to assume another and higher load resistance so that the plate-dissipation rating will not be exceeded.

It will be found that at an operating plate voltage of 300 volts the tubes require a plate-to-plate load resistance of 3000 ohms. From the formula for R_{pp} , the value of I' is found to be 0.4 ampere. The load line for the 3000-ohm load resistance is then represented by a straight line from the point I' = 0.4 ampere on the plate-current ordinate to the point $E_o = 300$ volts on the plate-voltage abscissa. At the intersection of the load line with the zerobias curve, the peak plate current, I_{max} , can be read at 0.2 ampere. Then

$$P_0 = (I_{max}/\sqrt{2})^2 \times R_{pp}/4$$

= $(0.2/1.41)^2 \times 3000/4$
= 15 watts

Proceeding as in the first approximation, it is found that the maximum-signal average plate current, $0.636I_{\text{max}}$, is 0.127 ampere, and the maximum-signal average power input is 38.1 watts. This input minus the power output is 38.1 - 15 = 23.1 watts. This value is the dissipation for two tubes; the value per tube is 11.6 watts, a value well within the rating of this tube type.

The operating bias and the zerosignal plate current may then be found by use of a curve which is derived from

the plate family and the load line. Fig. 46 is a curve of instantaneous values of plate current and dc grid-bias voltages taken from Fig. 45. Values of grid bias are read from each of the grid-bias curves of Fig. 45 along the load line and are transferred to Fig. 46 to produce the curved line from A to C. A tangent to this curve, starting at A. is drawn to intersect the grid-voltage abscissa. The point of intersection, B, is the operating grid bias for fixed-bias operation. In the example, the bias is -60 volts. Refer back to the plate family at the operating conditions of plate volts = 300 and grid bias = -60volts; the zero-signal plate current per tube is seen to be 0.04 ampere.

This procedure locates the operating point for each tube at P. The plate current must be doubled, of course, to obtain the zero-signal plate current for both tubes. Under maximum-signal conditions, the signal voltage swings from zero-signal bias voltage to zero bias for each tube on alternate half cycles. Hence, in the example, the peak of signal voltage per tube is 60 volts, or the grid-to-grid value is 120 volts.

As in the case of the push-pull class A amplifier, the second-harmonic distortion in a class AB₁ amplifier using triodes is very small and is largely canceled by virtue of the push-pull connection. Third-harmonic distortion. however, which may be larger than permissible, can be found by means of composite characteristic curves. A complete family of curves can be plotted, but for the present purpose only the one corresponding to a grid bias of one-half the peak grid-voltage swing is needed. In the example, the peak grid voltage per tube is 60 volts, and the half value is 30 volts. The composite curve, since it is nearly a straight line, can be constructed with only two points (see Fig. 45). These two points are obtained from deviations above and below the operating grid and plate voltages.

In order to find the curve for a bias of -30 volts, a deviation of 30 volts from the operating grid voltage of -60 volts is assumed. Next assume a deviation from the operating plate voltage of, say, 40 volts. Then at 300

-40 = 260 volts, erect a vertical line to intersect the (-60) - (-30) = -30volt bias curve and read the plate current at this intersection, which is 0.167 ampere; likewise, at the intersection of a vertical line at 300 + 40 = 340volts and the (-60) + (-30) = -90volt bias curve, read the plate current. In this example, the plate current is estimated to be 0.002 ampere. The difference of 0.165 ampere between these two currents determines the point E on the 300 - 40 = 260-volt vertical. Similarly, another point F on the same composite curve is found by assuming the same grid-bias deviation but a larger plate-voltage deviation, say, 100 volts.

These steps provide points at 260 volts and 0.165 ampere (E), and at 200 volts and 0.045 ampere (F). A straight line through these points is the composite curve for a bias of -30 volts, shown as a long-short dash line in Fig. 45. At the intersection of the composite curve and the load line, G, the instantaneous composite plate current at the point of one-half the peak signal swing is determined. This current value, designated Io.8 and the peak plate current, Imax, are used in the following formula to find the peak value of the third-harmonic component of plate current.

$$Iha = (2I_{0.5} - I_{max})/3$$

In the example, where $I_{0.8}$ is 0.097 ampere and I_{max} is 0.2 ampere, $I_{hx} = (2 \times 0.097 - 0.2)/3 = (0.194 - 0.2)/3 = -0.006/3 = -0.002$ ampere. (The fact that I_{hx} is negative indicates that the phase relation of the fundamental (first-harmonic) and third-harmonic components of the plate current is such as to result in a slightly peaked wave form. I_{hx} is positive in some cases, indicating a flattening of the wave form.)

The peak value of the fundamental or first-harmonic component of the plate current is found by the following formula:

$$Ih_1 = 2/3 \times (I_{max} + I_{0.5})$$

In the example, $I_{h1} = 2/3 \times (0.2 + 0.097) = 0.198$ ampere. Thus, the percentage of third-harmonic distortion is $(I_{hx}/I_{h1}) \times 100 = (0.002/0.198) \times 100 = 1$ per cent approx.

Class AB2 Power Amplifiers

A class AB₂ amplifier employs two tubes connected in push-pull as in the case of class AB₁ amplifiers. It differs in that it is biased so that plate current flows for somewhat more than half the electrical cycle but less than the full cycle, the peak signal voltage is greater than the dc bias voltage, grid current is drawn, and, consequently, power is consumed in the grid circuit. These conditions permit high power output to be obtained without excessive plate dissipation.

The sum of the power used in the grid circuit and the losses in the input transformer is the total driving power required by the grid circuit. The driver stage should be capable of a power output considerably larger than this required power in order that distortion introduced in the grid circuit be kept low. In addition, the internal impedance of the driver stage as reflected into or as effective in the grid circuit of the power stage should always be as low as possible in order that distortion may be kept low. The input transformer used in a class AB₂ stage usually has a stepdown ratio adjusted for this condition.

Load resistance, plate dissipation, power output, and distortion determinations are similar to those for class AB₁. These quantities are interdependent with peak grid-voltage swing and driving power; a satisfactory set of operating conditions involves a series of approximations. The load resistance and signal swing are limited by the permissible grid current and power and the distortion. If the load resistance is too high or the signal swing is excessive, the plate-dissipation rating will be exceeded, distortion will be high, and the driving power will be unnecessarily high.

Class B Power Amplifiers

A class B amplifier employs two tubes connected in push-pull, so biased that plate current is almost zero when no signal voltage is applied to the grids. Because of this low value of no-signal plate current, class B amplification has the same advantage as class AB₂, i.e., large power output can be obtained without excessive plate dissipation.

Class B operation differs from class AB₂ in that plate current is cut off for a larger portion of the negative grid swing, and the signal swing is usually larger than in class AB₂ operation.

Because certain triodes used as class B amplifiers are designed to operate very close to zero bias, the grid of each tube is at a positive potential during all or most of the positive halfcycle of its signal swing. In this type of triode operation, considerable grid current is drawn and there is a loss of power in the grid circuit. This condition imposes the same requirement in the driver stage as in a class AB, stage: i.e., the driver should be capable of delivering considerably more power output than the power required for the grid circuit of the class B amplifier so that distortion will be low. Similarly, the interstage transformer between the driver and the class B stage usually has a step-down turns ratio. Because of the high dissipations involved in class B operation at zero bias, it is not feasible to use tetrodes or pentodes in this type of class B operation.

Determination of load resistance, plate dissipation, power output, and distortion is similar to that for a class AB₂ stage.

Power amplifier tubes designed for class A operation can be used in class AB₂ and class B service under suitable operating conditions. There are several tube types designed especially for class B service. The characteristic common to all of these types is a high amplification factor. With a high amplification factor, plate current is small even when the grid bias is zero. These tubes, therefore, can be operated in class B service at a bias of zero volts so that no bias supply is required. A number of class B amplifier tubes consist of two triode units mounted in one tube. The two units can be connected in push-pull so that only one tube is required for a class B stage.

Cathode-Drive Circuits

The preceding text has discussed the use of tubes in the conventional grid-drive type of amplifier—that is, where the cathode is common to both the input and output circuits. Tubes may also be employed as amplifiers in circuit arrangements which utilize the grid or plate as the common terminal. Probably the most important of these amplifiers are the cathode-drive circuit, which is discussed below, and the cathode-follower circuit, which will be discussed later in connection with inverse feedback.

A typical cathode-drive circuit is shown in Fig. 47. The load is placed in




Fig. 47-Cathode-drive circuit.

the plate circuit and the output voltage is taken off between the plate and ground as in the grid-drive method of operation. The grid is grounded, and the input voltage is applied across an appropriate impedance in the cathode circuit. The cathode-drive circuit is particularly useful for vhf and uhf applications, in which it is necessary to obtain the low-noise performance usually associated with a triode, but where a conventional grid-drive circuit would be unstable because of feedback through the grid-to-plate capacitance of the tube. In the cathode-drive circuit, the grounded grid serves as a capacitive shield between plate and cathode and permits stable operation at frequencies higher than those in which conventional circuits can be used.

The input impedance of a cathodedrive circuit is approximately equal to $1/g_m$ when the load resistance is small compared to the r_p of the tube. A certain amount of power is required, therefore, to drive such a circuit. However, in the type of service in which cathodedrive circuits are normally used, the advantages of the grounded-grid connection usually outweigh this disadvantage.

Inverse Feedback

An inverse-feedback circuit, sometimes called a degenerative circuit, is one in which a portion of the output voltage of a tube is applied to the input of the same or a preceding tube in opposite phase to the signal applied to the tube. Two important advantages of feedback are (1) reduced distortion from each stage included in the feedback circuit and (2) reduction in the variations in gain due to changes in line voltage, possible differences between tubes of the same type, or variations in the values of circuit constants included in the feedback circuit.

Inverse feedback is used in audio amplifiers to reduce distortion in the output stage where the load impedance on the tube is a loudspeaker. Because the impedance of a loudspeaker is not constant for all audio frequencies, the load impedance on the output tube varies with frequency. When the output tube is a pentode or beam power tube having high plate resistance, this variation in plate load impedance can, if not corrected, produce considerable frequency distortion. Such frequency distortion can be reduced by means of inverse feedback. Inverse-feedback circuits are of the constant-voltage type and the constant-current type.

The application of the constant-voltage type of inverse feedback to a power-output stage using a single beam power tube is illustrated in Fig. 48. In this circuit, R₁, R₂, and C are connected as a voltage divider across the output of the tube. The secondary winding of the grid-input transformer is returned to a point on this voltage divider. Capacitor




Fig. 48—Power-output stage using constant voltage inverse feedback.

C blocks the dc plate voltage from the grid. However, a portion of the tube af output voltage, approximately equal to the output voltage multiplied by the fraction $R_2/(R_1 + R_2)$, is applied to the grid. This voltage reduces the source impedance of the circuit and a decrease in distortion results which is explained in the curves of Fig. 49.

nent of plate current i'pr. It is evident that the irregularity of the waveform of this component of plate current would act to cancel the original irregularity and thus reduce distortion.

After inverse feedback has been applied, the relations are as shown in the curve for i_p. The dotted curve shown by i'_{pt} is the component of plate current




Fig. 49-Voltage and current waveforms showing effect of inverse feedback.

Consider first the amplifier without the use of inverse feedback. Suppose that when a signal voltage e, is applied to the grid the af plate current i'p has an irregularity in its positive half-cycle. This irregularity represents a departure from the waveform of the input signal and is, therefore, distortion. For this plate-current waveform, the af plate voltage has a waveform shown by e'p. The plate-voltage waveform is inverted compared to the plate-current waveform because a plate-current increase produces an increase in the drop across the plate load. The voltage at the plate is the difference between the drop across the load and the supply voltage; thus, when plate current goes up, plate voltage goes down; when plate current goes down, plate voltage goes up.

Now suppose that inverse feedback is applied to the amplifier. The voltage fed back to the grid has the same waveform and phase as the plate voltage, but is smaller in magnitude. Hence, with a plate voltage of waveform shown by e'p, the feedback voltage appearing on the grid is as shown by e'gt. This voltage applied to the grid produces a compo-

due to the feedback voltage on the grid. The dotted curve shown by i'p is the component of plate current due to the signal voltage on the grid. The algebraic sum of these two components gives the resultant plate current shown by the solid curve of ip. Since i'p is the plate current that would flow without inverse feedback, it can be seen that the application of inverse feedback has reduced the irregularity in the output current. In this manner inverse feedback acts to correct any component of plate current that does not correspond to the input signal voltage, and thus reduces distortion.

From the curve for i_p, it can be seen that, besides reducing distortion, inverse feedback also reduces the amplitude of the output current. Consequently, when inverse feedback is applied to an amplifier there is a decrease in gain or power sensitivity as well as a decrease in distortion. Hence, the application of inverse feedback to an amplifier requires that more driving voltage be applied to obtain full power output, but this output is obtained with less distortion.

Inverse feedback may also be applied to resistance-coupled stages, as shown in Fig. 50. The circuit is conventional except that a feedback resistor,




Fig. 50—Resistance-coupled stages using feedback resistor.

R₃, is connected between the plates of tubes T₁ and T₂. The output signal voltage of T₁ and a portion of the output signal voltage of T2 appear across R2. Because the distortion generated in the plate circuit of T2 is applied to its grid out of phase with the input signal, the distortion in the output of T2 is comparatively low. With sufficient inverse feedback of the constant-voltage type in a power-output stage, it is not necessary to employ a network of resistance and capacitance in the output circuit to reduce response at high audio frequencies. Inverse-feedback circuits can also be applied to push-pull class A and class AB₁ amplifiers.

Constant-current inverse feedback is usually obtained by omitting the bypass capacitor across a cathode resistor. This method decreases the gain and the distortion but increases the source impedance of the circuit. Consequently, the output voltage rises at the resonant frequency of the loudspeaker and accentuates hangover effects.

Inverse feedback is not generally applied to a triode power amplifier because the variation in speaker impedance with frequency does not produce much distortion in a triode stage having low plate resistance. It is sometimes applied in a pentode stage, but is not always convenient. As has been shown, when inverse feedback is used in an amplifier, the driving voltage must be increased in order to provide full power output. When inverse feedback is used with a pentode, the total driving voltage required for full power output may be inconveniently large, although still less

than that required for a triode. Because a beam power tube gives full power output on a comparatively small driving voltage, inverse feedback is especially applicable to beam power tubes. By means of inverse feedback, the high efficiency and high power output of beam power tubes can be combined with freedom from the effects of varying speaker impedance.

Cathode-Follower Circuits

Another important application of inverse feedback is in the cathode-follower circuit, an example of which is shown in Fig. 51. In this application, the load has been transferred from the plate circuit to the cathode circuit of the tube. The input voltage is applied between the grid and ground, and the output voltage is obtained between the cathode and ground. The voltage amplification (V.A.) of this circuit is always less than unity and may be expressed by the following convenient formulas. For a triode:

V. A. = $\frac{\mu \times R_L}{r_p + [R_L \times (\mu + 1)]}$

For a pentode:

 $V. A. = \frac{g_m \times R_L}{1 + (g_m \times R_L)}$ In these formulas, μ is the amplification factor, R_L is the load resistance in ohms, r, is the plate resistance in ohms, and gm is the transconductance in mhos.

The use of the cathode follower permits the design of circuits which have high input resistance and high output voltage. The output impedance is




Fig. 51—Cathode-follower circuit.

quite low and very low distortion may be obtained. Cathode-follower circuits may be used for power amplifiers or as impedance transformers designed either

to match a transmission line or to produce a relatively high output voltage at a low impedance level.

In a power amplifier which is transformer coupled to the load, the same output power can be obtained from the tube as would be obtained in a conventional grid-drive type of amplifier. The output impedance is very low and provides excellent damping to the load, with the result that very low distortion can be obtained. The peak-to-peak signal voltage, however, approaches 11/2 times the plate supply voltage if maximum power output is required from the tube. Some problems may be encountered, therefore, in the design of an adequate driver stage for a cathodefollower output system.

When a cathode-follower circuit is used as an impedance transformer, the load is usually a simple resistance in the cathode circuit of the tube. With relatively low values of cathode resistor, the circuit may be designed to supply significant amounts of power and to match the impedance of the device to a transmission line. With somewhat higher values of cathode resistor, the circuit may be used to decrease the output impedance sufficiently to permit the transmission of audio signals along a line in which appreciable capacitance is present.

The cathode follower may also be used as an isolation device to provide extremely high input resistance and low input capacitance as might be required in the probe of an oscilloscope or vacuum-tube voltmeter. Such circuits can be designed to provide effective impedance transformation with no significant loss of voltage.

Selection of a suitable tube and its operating conditions for use in a cathode-follower circuit having a specified output impedance (Z_o) can be made, in most practical cases, by the use of the following formula to determine the approximate value of the required tube transconductance.

Required
$$g_m$$
 (μ mhos) = $\frac{1,000,000}{Z_o$ (ohms)

Once the required transconductance is obtained, a suitable tube and its operating conditions may be determined

from the technical data given in the Technical Data section. The tube selected should have a value of transconslightly lower than that obtained from the above expression to allow for the shunting effect of the cathode load resistance. The conversion nomograph given in Fig. 44 may be used for calculation of operating conditions for values of transconductance not included in the tabulated data. After the operating conditions have been determined, the approximate value of the required cathode load resistance may be calculated from the following formulas. For a triode:

Cathode
$$R_{L} = \frac{Z_{o} \times r_{p}}{r_{p} - [Z_{o} \times (1 + \mu)]}$$

For a pentode:
Cathode $R_{L} = \frac{Z_{o}}{1 - (g_{m} \times Z_{o})}$

Resistance and impedance values are in ohms; transconductance values are in mhos.

If the value of the cathode load resistance calculated to provide the required output impedance does not provide the required operating bias, the basic cathode-follower circuit can be modified in a number of ways. Two of the more common modifications are shown in Figs. 52 and 53.

In Fig. 52 the bias is increased by adding a bypassed resistance between




Fig. 52—Cathode-follower circuit modified for increased bias.

the cathode and the unbypassed load resistance and returning the grid to the low end of the load resistance. In Fig. 53 the bias is reduced by adding a bypassed resistance between the cathode and the unbypassed load resistance but, in this case, the grid is returned to the

junction of the two cathode resistors so that the bias voltage is only the dc voltage drop across the added resistance. The size of the bypass capacitor should be large enough so that it has negligible reactance at the lowest frequency to be handled. In both cases the B-supply should be increased to make up for the voltage taken for biasing.




Fig. 53—Cathode-follower circuit modified for reduced bias.

Example: Select a suitable tube and determine the operating conditions and circuit components for a cathode-follower circuit having an output impedance that will match a 500-ohm transmission line.

Procedure: First, determine the approximate transconductance required.

Required
$$g_m = \frac{1,000,000}{500} = 2000 \ \mu \text{mhos}$$

A survey of the tubes that have a transconductance in this order of magnitude shows that type 12AX7A is among the tubes to be considered. Referring to the characteristics given in the technical data section for one triode unit of highmu twin triode 12AX7, we find that for a plate voltage of 250 volts and a bias of -2 volts, the transconductance is 1600 micromhos, the plate resistance is 62500 ohms, the amplification factor is 100, and the plate current is 0.0012 ampere. When these values are used in the expression for determining the cathode load resistance, the following result is obtained:

Cathode
$$R_L = \frac{500 \times 62500}{62500 - 500 \times (100 + 1)} = 2600$$
 ohms

The voltage across this resistor for a plate current of 0.0012 ampere is $2600 \times 0.0012 = 3.12$ volts. Because

the required bias voltage is only -2 volts, the circuit arrangement given in Fig. 53 is employed. The bias is furnished by a resistance that will have a voltage drop of 2 volts when it carries a current of 0.0012 ampere. The required bias resistance, therefore, is 2/0.0012 = 1670 ohms. If 60 Hz is the lowest frequency to be passed, 20 microfarads is a suitable value for the bypass capacitor. The B-supply. course, is increased by the voltage drop across the cathode resistance which, in this example, is approximately 5 volts. The B-supply, therefore, is 250 + 5= 255 volts.

Because it is desirable to eliminate, if possible, the bias resistor and bypass capacitor, it is worthwhile to try other tubes and other operating conditions to obtain a value of cathode load resistance which will also provide the required bias. If the triode section of twin diode-high-mu triode 6AT6 is operated under the conditions given in the technical data section with a plate voltage of 100 volts and a bias of -1 volt, it will have an amplification factor of 70, a plate resistance of 54000 ohms, a transconductance of 1300 micromhos, and a plate current of 0.0008 ampere. Then,

Cathode
$$R_L = \frac{500 \times 54000}{54000 - 500 \times (70 + 1)} = 1460 \text{ ohms}$$

The bias voltage obtained across this resistance is $1460 \times 0.0008 = 1.17$ volts. Since this value is for all practical purposes close enough to the required bias, no addition bias resistance will be required and the grid may be returned directly to ground. There is no need to adjust the B-supply voltage to make up for the drop in the cathode voltage resistor. The amplification (V.A.) for the cathode-follower circuit utilizing the triode section of type 6AT6 is

$$V.A. = \frac{70 \times 1460}{54000 + 1460 \times (70 + 1)} = 0.65$$

For applications in which the cathode follower is used to isolate two circuits—for example, when it is used between a circuit being tested and the input stage of an oscilloscope or a vacuum-tube voltmeter—voltage output and not impedance matching is the primary consideration. In such applications it is desirable to use a relatively high value of cathode load resistance, such as 50,000 ohms, in order to get the maximum voltage output. In order to obtain proper bias, a circuit such as that of Fig. 53 should be used. With a high value of cathode resistance, the voltage amplification will approximate unity.

Corrective Filters

A corrective filter can be used to improve the frequency characteristic of an output stage using a beam power tube or a pentode when inverse feedback is not applicable. The filter consists of a resistor and a capacitor connected in series across the primary of the output transformer. Connected in this way, the filter is in parallel with the plate load impedance reflected from the voicecoil by the output transformer. The magnitude of this reflected impedance increases with increasing frequency in the middle and upper audio range. The impedance of the filter, however, decreases with increasing frequency. It follows that, by use of the proper values for the resistance and the capacitance in the filter, the effective load impedance on the output tubes can be made practically constant for all frequencies in the middle and upper audio range. The result is an improvement in the frequency characteristic of the output stage.

The resistance to be used in the filter for a push-pull stage is 1.3 times the recommended plate-to-plate load resistance; or, for a single-tube stage, is 1.3 times the recommended plate load resistance. The capacitance in the filter should have a value such that the voltage gain of the output stage at a frequency of 1000 Hz or higher is equal to the voltage gain at 400 Hz.

A method of determining the proper value of capacitance for the filter is to make two measurements of the output voltage across the primary of the output transformer: first, when a 400-Hz signal is applied to the input, and second, when a 1000-Hz signal of the same voltage as the 400-Hz signal is applied to the input. The correct value of capacitance is the one which gives equal output voltages for the two signal inputs. In practice, this value is usually found to be in the order of 0.05 microfarad.

Phonograph and Tape Preamplifiers

The frequency range and dynamic range* which can be recorded on a phonograph record or on magnetic tape depend on several factors, including the composition, mechanical characteristics, and speed of the record or tape, and the electrical and mechanical characteristics of the recording equipment. To achieve wide frequency and dynamic ranges, manufacturers of commercial recordings use equipment which introduces a nonuniform relationship between amplitude and frequency. This relationship is known as a "recording characteristic." To assure proper reproduction of a high-fidelity recording, therefore, some part of the reproducing system must have a frequency-response characteristic which is the inverse of the recording characteristic. Most manufacturers of high-fidelity recordings use the RIAA characteristic for discs and the NARTB characteristic for magnetic tape.

The simplest type of equalization network is shown in Fig. 54. Because the capacitor C is effectively an open circuit at low frequencies, the low frequencies must be passed through the resistor R and are attenuated. The capacitor has a lower reactance at high




Fig. 54—Simple RC frequency-compensation network.

The dynamic range of an amplifier is a measure of its signal-handling capability. The dynamic range expresses in dB the ratio of the maximum usable output signal (generally for a distortion of about 10 per cent) to the minimum usable output signal (generally for a signal-to-noise ratio of about 20 dB). A dynamic range of 40 dB is usually acceptable; a value of 70 dB is exceptional for any audio system.

frequencies, however, and bypasses high-frequency components around R so that they receive negligible attenuation. Thus the network effectively "boosts" the high frequencies. This type of equalization is called "attenuative."

Some typical preamplifier stages are shown in the Circuits section. The location of the frequency-compensating network or "equalizer" in the reproducing system will depend on the types of recordings which are to be reproduced and on the pickup devices used.

A ceramic high-fidelity phonograph pickup is usually designed to provide proper compensation for the RIAA recording characteristic when the pickup is operated into the load resistance specified by its manufacturer. Because this type of pickup also has relatively high output (0.5 to 1.5 volts), it does not require the use of either an equalizer network or a preamplifier, and can be connected directly to the input of a tone-control amplifier and/or power amplifier.

A magnetic high-fidelity phonograph pickup, on the other hand, usually has an essentially flat frequency-response characteristic and very low output (1 to 10 millivolts). Because a pickup of this type merely reproduces the recording characteristic, it must be followed by an equalizer network, as well as by a preamplifier having sufficient voltage gain to provide the input voltage required by the tone-control amplifier and/or power amplifier. Many designs include both the equalizing and amplifying circuits in a single unit.

A high-fidelity magnetic-tape pickup head, like a magnetic phonograph pickup, reproduces the recording characteristic and has an output of only a few millivolts. This type of pickup device, therefore, must also be followed by an equalizing network and preamplifier, or by a preamplifier which provides "built-in" equalization for the NARTB characteristic.

Feedback networks may also be used for frequency compensation and for reduction of distortion. Basically, a feedback network returns a portion of the output signal to the input circuit of an amplifier. The feedback signal may be returned in phase with the input signal (positive or regenerative feedback) or 180 degrees out of phase with the input signal (negative, inverse, or degenerative feedback). In either case, the feedback can be made proportional to either the output voltage or the output current, and can be applied to either the input voltage or the input current. A negative feedback signal proportional to the output current raises the output impedance of the amplifier; negative feedback proportional to the output voltage reduces the output impedance. A negative feedback signal applied to the input current decreases the input impedance; negative feedback applied to the input voltage increases the input impedance. Opposite effects are produced by positive feedback.

A simple negative or inverse feed-frequency boost is shown in Fig. 55. back network which provides high-This network provides equalization comparable to that obtained with Fig. 54, but is more suitable for low-level amplifier stages because it does not require the first amplifier stage to provide high-level low frequencies. In addition, the inverse feedback improves the distortion characteristics of the amplifier.

Some preamplifier or low-level audio amplifier circuits include variable resistors or potentiometers which function as volume or tone controls. Such circuits should be designed to minimize the flow of dc currents through these controls so that little or no noise will be developed by the movable contact during the life of the circuit. Volume controls and their associated circuits should permit variation of gain from zero to maximum, and should attenuate all frequencies equally for all positions




Fig. 55-Negative-feedback frequency-compensation network.

of the variable arm of the control. Several examples of volume controls and tone controls are shown in the **Circuits** section.

Tone Controls

A tone control is a variable filter (or one in which at least one element is adjustable) by means of which the user may vary the frequency response of an amplifier to suit his own taste. In radio receivers and home amplifiers, the tone control usually consists of a resistance-capacitance network in which the resistance is the variable element.

The simplest form of tone control is a fixed tone-compensating or "equalizing" network such as that shown in Fig. 56. This type of network is often




Fig. 56—Tone-control circuit for fixed tone compensation or "equalizing".

used to equalize the low- and high-frequency response of a crystal phonograph pickup. At low frequencies the attenuation of this network is 20.8 dB. As the frequency is increased, the 100-picofarad capacitor serves as a bypass for the 5-megohm resistor, and the combined impedance of the resistor-capacitor network is reduced. Thus, more of the crystal output appears across the 0.5-megohm resistor at high

frequencies than at low frequencies, and the frequency response at the grid is reasonably flat over a wide frequency range. Fig. 57 shows a comparison between the output of the crystal (curve A) and the output of the equalizing network (curve B). The response curve




Fig. 57—Curve showing output from crystal phonograph pickup (A) and from equalizing network (B).

can be "flattened" still more if the attenuation at low frequencies is increased by changing the 0.5-megohm resistor to 0.125 megohm.

The tone-control network shown in Fig. 58 has two stages with completely separate bass and treble controls. Fig. 59 shows simplified representations of the bass control of this circuit when the potentiometer is turned to its extreme variations (usually labeled "Boost" and "Cut"). In this network, as in the crystal-equalizing network shown in Fig. 56, the parallel RC combination is the controlling factor. For bass "boost," the capacitor C₂ bypasses resistor R₃ so that less impedance is placed across the output to grid B at high frequencies than at low frequencies. For bass "cut," the parallel combination is shifted so that C₁ bypasses R₂, causing more highfrequency than low-frequency output. Essentially, the network is a variable-




Fig. 58-Two-stage tone-control circuit incorporating separate bass and treble controls,

frequency voltage divider. With proper values for the components, it may be made to respond to changes in the R₃ potentiometer setting for only low frequencies (below 1000 Hz).




Fig. 59—Simplified representations of basscontrol circuit at extreme ends of potentiometer.

Fig. 60 shows extreme positions of the treble control. The attenuation of the two circuits is approximately the same at 1000 Hz. The treble "boost" circuit is similar to the crystal-equalizing network shown in Fig. 56. In the treble "cut" circuit, the parallel RC elements serve to attenuate the signal voltage further because the capacitor bypasses the resistance across the output.




Fig. 60—Simplified representations of treble-control circuit at extreme ends of potentiometer.

The effect of the capacitor is negligible at low frequencies; beyond 1000 Hz, the signal voltage is attenuated at a maximum rate of 6 dB per octave.

The location of a tone-control network is of considerable importance. In a typical radio receiver, it may be inserted in the plate circuit of the power tube, the coupling circuit between the first af amplifier tube and the power tube, or the grid circuit of the first tube. In an amplifier using a beam power tube or pentode power amplifier without negative feedback, it is desirable to connect a resistance.

capacitance filter across the primary of the output transformer. This filter may be fixed, with a supplementary tone control elsewhere, or it may form the tone control itself. If the amplifier incorporates negative feedback, the tone control may be inserted in the feedback network or else should be connected to a part of the amplifier which is external to the feedback loop. The overall gain of a well designed tone-control network should be approximately unity.

Automatic Volume or Gain Control

The chief purpose of automatic volume control (ave) or automatic gain control (age) in a radio or television receiver is to prevent fluctuations in loudspeaker volume or picture brightness when the audio or video signal at the antenna is fading in and out.

An automatic volume control circuit regulates the receiver rf and if gain so that this gain is less for a strong signal than for a weak signal. In this way, when the signal strength at the antenna changes, the avc circuit reduces the resultant change in the voltage output of the last if stage and consequently reduces the change in the speaker output volume.

The avc circuit reduces the rf and if gain for a strong signal usually by increasing the negative bias of the rf, if, and frequency-mixer stage when the signal increases. A simple avc circuit is shown in Fig. 61. On each positive half-cycle of the signal voltage, when the diode plate is positive with respect to the cathode, the diode passes current.




Fig. 61—Automatic-volume-control (avc) circuit.

Because of the flow of diode current through R_1 , there is a voltage drop across R_1 which makes the left end of R_1 negative with respect to ground. This

voltage drop across R_1 is applied, through the filter R_s and C, as negative bias on the grids of the preceding stages. When the signal strength at the antenna increases, therefore, the signal applied to the avc diode increases, the voltage drop across R_1 increases, the negative bias voltage applied to the rf and if stages increases, and the gain of the rf and if stages is decreased. Thus the increase in signal strength at the antenna does not produce as much increase in the output of the last if stage as it would produce without avc.

When the signal strength at the antenna decreases from a previous steady value, the ave circuit acts, of course, in the reverse direction, applying less negative bias, permitting the rf and if gain to increase, and thus reducing the decrease in the signal output of the last if stage. In this way, when the signal strength at the antenna changes, the ave circuit acts to reduce change in the output of the last if stage, and thus acts to reduce change in loudspeaker volume.

The filter, C and R2, prevents the ave voltage from varying at audio frequency. The filter is necessary because the voltage drop across R₁ varies with the modulation of the carrier being received. If avc voltage were taken directly from R₁ without filtering, the audio variations in avc voltage would vary the receiver gain so as to smooth out the modulation of the carrier. To avoid this effect, the avc voltage is taken from the capacitor C. Because of the resistance Rs in series with C, the capacitor C can charge and discharge at only a comparatively slow rate. The avc voltage therefore cannot vary at frequencies as high as the audio range but can vary at frequencies high enough to compensate for most fading. Thus the filter permits the avc circuit to smooth out variations in signal due to fading, but prevents the circuit from smoothing out audio modulation.

It will be seen that an avc circuit and a diode-detector circuit are much alike. It is therefore convenient in a receiver to combine the detector and the avc diode in a single stage. Examples of how these functions are combined in receivers are shown in Circuits section.

In the circuit shown in Fig. 61, a certain amount of avc negative bias is applied to the preceding stages on a weak signal. Because it may be desirable to maintain the receiver rf and if gain at the maximum possible value for a weak signal, avc circuits are designed in some cases to apply no avc bias until the signal strength exceeds a certain value. These avc circuits are known as delayed avc or dayc circuits.

A dave circuit is shown in Fig. 62. In this circuit, the diode section D₁ of the 6AL5 acts as detector and ave diode.




Fig. 62-Delayed avc (davc) circuit.

R₁ is the diode load resistor and R₂ and C2 are the avc filter. Because the cathode of diode D2 is returned through a fixed supply of -3 volts to the cathode of D₁, a dc current flows through R₁ and R₂ in series with D₂. The voltage drop caused by this current places the ave lead at approximately -3 volts (less the negligible drop through D₂). When the average amplitude of the rectified signal developed across R₁ does not exceed 3 volts, the avc lead remains at -3 volts. Hence, for signals not strong enough to develop 3 volts across R₁. the bias applied to the controlled tubes stays constant at a value giving high sensitivity.

However, when the average amplitude of rectified signal voltage across R_1 exceeds 3 volts, the plate of diode D_2 becomes more negative than the cathode of D_2 and current flow in diode D_2 ceases. The potential of the avc lead is then controlled by the voltage developed across R_1 . Therefore, with further increase in signal strength, the avc circuit applies an increasing average R_1 .

bias voltage to the controlled stages. In this way, the circuit regulates the receiver gain for strong signals, but permits the gain to stay constant at a maximum value for weak signals.

It can be seen in Fig. 62 that a portion of the -3 volts delay voltage is applied to the plate of the detector diode D_1 , this portion being approximately equal to $R_1/(R_1 + R_2)$ times -3 volts. Hence, with the circuit constants as shown, the detector plate is made negative with respect to its cathode by approximately one-half volt. However, this voltage does not interfere with detection because it is not large enough to prevent current flow in the tube.

Automatic gain control (agc) compensates for fluctuations in rf picture carrier amplitude. The peak carrier level rather than the average carrier level is controlled by the agc voltage because the peaks of the sync pulses are fixed when inserted on a fixed carrier level. The peak carrier level may be determined by measurement of the peaks of the sync pulses at the output of the video detector.

A conventional age circuit, such as that shown in Fig. 63, consists of a diode




Fig. 63—Automatic-gain control (agc) circuit.

detector circuit and an RC filter. The time constant of the detector circuit is made large enough to prevent the picture content from influencing the magnitude of the agc voltage. The output voltage (agc voltage) is equal to the peak value of the incoming signal.

The diode detector receives the incoming signal from the last if stage of the television receiver through the capacitor C₁. The resistor R₁ provides the load for the diode. The diode conducts only when its plate is driven positive with respect to its cathode. Electrons then flow from the cathode to the plate and thence into capacitor C₁, where the negative charge is stored. Because of the

low impedance offered by the diode during conduction, C_1 charges up to the value of the peak applied voltage.

During the negative excursion of the signal, the diode does not conduct, and C₁ discharges through resistor R₁. Because of the large time constant of R₁C₁, however, only a small percentage of the voltage across C₁ is lost during the interval between horizontal sync During succeeding cycles, the incoming signal must overcome the negative charge stored in C₁ before the diode conducts, and plate current flows only at the peak of each positive cycle. The voltage across C₁, therefore, is determined by the level of the peaks of the positive cycles, or the sync pulses.

The negative voltage developed across resistor R₁ by the sync pulses is filtered by resistor R₂ and capacitor C₂ to remove the 15,750-cycle ripple of the horizontal sync pulse. The dc output is then fed to the if and rf amplifiers as an age voltage.

This age system may be expanded to include amplification of the age signal before detection of the peak level, or amplification of the dc output, or both. A direct-coupled amplifier must be used for amplification of the dc signal. The addition of amplification makes the system more sensitive to changes in carrier level.

A "keyed" agc system such as that shown in Fig. 64 is used to eliminate flutter and to improve noise immunity in weak signal areas. This system provides more rapid action than the conventional agc circuits because the filter circuit can employ lower capacitance and resistance values.




Fig. 64—"Keyed" agc circuit.

In the keyed agc system, the negative output of the video detector is fed directly to the grid No. 1 of the first video amplifier. The positive output of the video amplifier is, in turn, fed directly to the grid No. 1 of the keyed ago amplifier. The video stage increases the gain of the agc system and, in addition, provides noise clipping. The plate voltage for the age amplifier is a positive pulse obtained from a small winding on the horizontal output transformer which is in phase with the horizontal sync pulse obtained from the video amplifier. The polarity of this pulse is such that the plate of the agc amplifier tube is positive during the retrace time. The tube is biased so that current flows only when the grid No. 1 and the plate are driven positive simultaneously. amount of current flow depends on the grid-No. 1 potential during the pulse. These pulses are smoothed out in the RC network in the plate circuit (R₁C₁). Because the dc voltage developed across R₁ is negative, it is suitable for application to the grids of the rf and if tubes as an agc voltage.

High-Fidelity Amplifiers

Several high-fidelity amplifiers are shown in the Circuits section. The performance capabilities of such amplifiers are usually given in terms of frequency response, total harmonic distortion, maximum power output, and noise level.

To provide high-fidelity reproduction of audio program material, an amplifier should have a frequency response which does not vary more than 1 dB over the entire audio spectrum. General practice is to design the amplifier so that its frequency response is flat within 1 dB from a frequency below the lowest to be reproduced to one well above the upper limit of the audible region.

Harmonic distortion and intermodulation distortion produce changes in program material which may have adverse effects on the quality of the reproduced sound. Harmonic distortion causes a change in the character of an individual tone by the introduction of harmonics which were not originally present in the program material. For high-fidelity reproduction, total harmonic distortion (expressed as a percentage of the output power) should not be greater than about 1 per cent at the desired listening level. Types such as the 6973, 7027A and 7868 are designed to provide extremely low harmonic distortion in suitably designed push-pull amplifier circuits.

Intermodulation distortion change in the waveform of an individual tone as a result of interaction with another tone present at the same time in the program material. This type of distortion not only alters the character of the modulated tone, but may also result in the generation of spurious signals at frequencies equal to the sum and difference of the interacting frequencies. Intermodulation distortion should be less than 2 per cent at the desired listening level. In general, any amplifier which has low intermodulation distortion will have very low harmonic distortion.

The maximum power output which a high-fidelity amplifier should deliver depends upon a complex relation of several factors, including the size and acoustical characteristics of the listening area, the desired listening level, and the efficiency of the loudspeaker system. Practically, however, it is possible to determine amplifier requirements in terms of room size and loudspeaker efficiency.

The acoustic power required to reproduce the loudest passages of orchestral music at concert-hall level in the average-size living room is about 0.4 watt. Because high-fidelity loudspeakers of the type generally available for home use have an efficiency of only about 5 per cent, the output stage of the amplifier should therefore be able to deliver a power output of at least 8 watts. Because many wide-range loudspeaker systems, particularly those using frequencydivider networks, have efficiencies of less than 5 per cent, output tubes used with such systems must have correspondingly larger power outputs. The 6973, 7027A, 7189, and 7868 can provide ample output for most systems when used in suitable push-pull circuits.

The noise level of a high-fidelity

amplifier determines the range of volume the amplifier is able to reproduce, *i.e.*, the difference (usually expressed in decibels) between the loudest and softest sounds in program material. Because the greatest volume range utilized in electrical program material at the present time is about 60 dB, the noise level of a high-fidelity amplifier should be at least 60 dB below the signal level at the desired listening level.

Limiters

An amplifier may also be used as a limiter. One use of a limiter is in receivers designed for the reception of frequency-modulated signals. The limiter in FM receivers has the function of eliminating amplitude variations from the input to the detector. Because in an FM system amplitude variations are primarily the result of noise disturbances, the use of a limiter prevents such disturbances from being reproduced in the audio output. The limiter usually follows the last if stage so that it can minimize the effects of disturbances coming in on the rf carrier and those produced locally.

The limiter is essentially an if voltage amplifier designed for saturated operation. Saturated operation means that an increase in signal voltage above a certain value produces very little increase in plate current. A signal voltage which is never less than sufficient to cause saturation of the limiter, even on weak signals, is supplied to the limiter input by the preceding stages. Any change in amplitude, therefore, such as might be produced by noise voltage fluctuation, is not reproduced in the limiter output. The limiting action, of course, does not interfere with the reproduction of frequency variations.

Plate-current saturation of the limiter may be obtained by the use of grid-No. 1 resistor-and-capacitor bias with plate and grid-No. 2 voltages which are low compared with customary if-amplifier operating conditions.

As a result of these design features, the limiter is able to maintain its output voltage at a constant amplitude over a wide range of input-signal voltage variations. The output of the limiter is frequency-modulated if voltage, the mean

frequency of which is that of the if amplifier. This voltage is impressed on the input of the detector.

The reception of FM signals without serious distortion requires that the response of the receiver be such that satisfactory amplification of the signal is provided over the entire range of frequency deviation from the mean frequency. Since the frequency at any instant depends on the modulation at that instant, it follows that excessive attenuation toward the edges of the band, in the rf or if stages, will cause distortion. In a high-fidelity receiver. therefore, the amplifiers must be capable of amplifying, for the maximum permissible frequency deviation of 75 kHz, a band 150 kHz wide. Suitable tubes for this purpose are the 6BA6 and 6BJ6.

Volume Compressors and Expanders

Volume compression and expansion are used in FM transmitters and receivers and in recording devices and amplifiers to make more natural the reproduction of music which has a very large volume range. For example, in the music of a symphony orchestra the sound intensity of the soft passages is very much lower than that of the loud passages. When this low volume level is raised above the background noise for transmitting or recording, the peak level of the program material may be raised to an excessively high volume level. It is often necessary, therefore, to compress the volume range of the program content within the maximum capabilities of the FM transmitter or the recording device. Exceeding a maximum peak volume level for FM modulation corresponds to exceeding the allowed bandwidth for transmission. In some recording devices, excessive peak volume levels may cause overloading and distortion.

Volume compression may be accomplished by either manual or automatic control. The types of compression used include peak limiters, volume limiters, and volume compressors. A peak limiter limits the peak power to some predetermined level. A volume limiter provides gain reduction based on an

average signal level above a predetermined level. A volume compressor provides gain reduction for only the sustained loud portions of the sound level. Only volume compressors can be correctly compensated for with volume expanders.

For faithful reproduction of the original sound, the volume expander used in the FM receiver or audio amplifier should have the reverse characteristic of the volume compressor used in the FM transmitter or recording device. In general, the basic requirements for either a volume compressor or expander are shown in the block diagram of Fig. 65. In a volume compressor, the




Fig. 65—Block diagram of volume compressor or expander circuit.

variable-gain amplifier V₁ has greater gain for a low-amplitude signal than for a high-amplitude signal; therefore, soft passages are amplified more than loud ones. In an expander, the gain is greater for high-amplitude signals than for low-amplitude signals; therefore, loud passages are amplified more than soft ones and the original amplitude ratio is restored.

In the diagram shown in Fig. 65, the signal to be amplified is applied to V_1 , and a portion of the signal is also applied to V_2 . The amplified output from V_2 is then rectified by V_3 , and applied as a negative (for compressors) or positive (for expanders) bias voltage to V_1 . As this bias voltage varies with variations in signal amplitude, the gain of V_1 also varies to produce the desired compression or expansion of the signal.

Tubes having a large dynamic range provide the best results in volume

compressor or expander applications. An example of this type is the 6BJ6. Push-pull operation is generally desired for the variable-gain amplifier to prevent high distortion and other undesirable effects which may occur in volume compressors and expanders.

Phase Inverters

A phase inverter is a circuit used to provide resistance coupling between the output of a single-tube stage and the input of a push-pull stage. The necessity for a phase inverter arises because the signal-voltage inputs to the grids of a push-pull stage must be 180 degrees out of phase and approximately equal in amplitude with respect to each other. Thus, when the signal voltage input to a push-pull stage swings the grid of one tube in a positive direction. it should swing the grid of the other tube in a negative direction by a similar amount. With transformer coupling between stages, the out-of-phase input voltage to the push-pull stage is supplied by means of the center-tapped secondary. With resistance coupling, the out-of-phase input voltage is obtained by means of the inverter action of a tube.

Fig. 66 shows a push-pull power amplifier, resistance-coupled by means of a phase-inverter circuit to a single-stage triode T₁. Phase inversion in this circuit is provided by triode T₂. The output voltage of T₁ is applied to the grid No. 1 of tetrode T₃. A portion of the output voltage of T₁ is also applied through the resistors R₃ and R₅ to the




Fig. 66—Push-pull power amplifier resistance-coupled to triode by means of phase inverter.

grid of T_2 . The output voltage of T_2 is applied to the grid No. 1 of tetrode T_4 .

When the output voltage of T_1 swings in the positive direction, the plate current of T_2 increases. This action increases the voltage drop across the plate resistor R_2 and swings the plate of T_2 in the negative direction. Thus, when the output voltage of T_1 swings positive, the output voltage of T_2 swings negative and is, therefore, 180 degrees out of phase with the output voltage of T_1 .

In order to obtain equal voltages at E_a and E_b , $(R_3 + R_5)/R_5$ should equal the voltage gain of T2. Under the condition where a twin-type tube or two tubes having the same characteristics are used as T₁ and T₂, R₄ should be equal to the sum of R3 and R6. The ratio of R₃ + R₅ to R₅ should be the same as the voltage gain ratio of T2 in order to apply the correct value of signal voltage to T₂. The value of R₅ is, therefore, equal to R, divided by the voltage gain of T2; Ra is equal to R4 minus Rs. Values of R₁, R₂, R₃ plus R₅, and R₄ may be taken from the chart in the Resistance-Coupled Amplifiers section. In the practical application of this circuit, it is convenient to use a twin-triode tube combining T₁ and T₂.

Tuned Amplifiers

In radio-frequency (rf) and intermediate-frequency (if) amplifiers, the bandwidth of frequencies to be amplified is usually only a small percentage of the center frequency. Tuned amplifiers are used in these applications to select the desired bandwidth of frequencies and to suppress unwanted frequencies. The selectivity of the amplifier is obtained by means of tuned interstage coupling networks.

The properties of tuned amplifiers depend upon the characteristics of resonant circuits. A simple parallel resonant circuit (sometimes called a "tank" because it stores energy) is shown in Fig. 67. For practical purposes the resonant frequency of such a circuit may be considered independent of the resistance R, provided R is small compared to the inductive reactance X_L.

The resonant frequency f, is then given by

$$f_r = \frac{1}{2\pi\sqrt{LC}}$$

For any given resonant frequency, the product of L and C is a constant; at low frequencies LC is large; at high frequencies it is small.

The **Q** (selectivity) of a parallel resonant circuit alone is the ratio of the current in the tank (I_r, or I_c) to the current in the line (I). This unloaded Q, or Q₀, may be expressed in various ways, for example:

$$Q_{r_{c}} = \frac{I_{c}}{I} = \frac{X_{r_{c}}}{R} = \frac{R_{\nu}}{X_{c}}$$

where $X_{\rm L}$ is the inductive reactance (= $2\tau fL$), $X_{\rm c}$ is the capacitive reactance (= $1/[2\pi fC]$), and $R_{\rm p}$ is the total impedance of the parallel resonant circuit




Fig. 67—Simple parallel resonant circuit. (tank) at resonance. The Q varies inversely with the resistance of the inductor. The lower the resistance, the higher the Q and the greater the difference between the tank impedance at frequencies off resonance compared to the tank impedance at the resonant frequency.

The Q of a tuned interstage coupling network also depends upon the impedances of the preceding and following stages. The output impedance of a tube can be considered as consisting of a resistance R₀ in parallel with a capacitance C₀, as shown in Fig. 68. Similarly, the input impedance can be considered as consisting of a resistance R₁ in parallel with a capacitance C₁. Because the tuned circuit is shunted by both the output impedance of the preceding tube and the input impedance of the following tube, the effective selectivity of the circuit is the loaded Q (or




Fig. 68-Equivalent output and input circuits of tubes connected by a coupling network.

Q_{i.}) based upon the total impedance of the coupled network, as follows:

$$Q_{t} = \begin{cases} \text{total loading on} \\ \text{coil at resonance} \end{cases}$$

XL or Xc

The capacitances C_0 and C_1 in Fig. 68 are usually considered as part of the coupling network. For example, if the required capacitance between terminals 1 and 2 of the coupling network is calculated to be 500 picofarads and the value of C_0 is 10 picofarads, a capacitor of 490 picofarads is used between terminals 1 and 2 so that the total capacitance is 500 picofarads. The same method is used to allow for the capacitance C_1 at terminals 3 and 4.

When a tuned resonant circuit in the primary winding of a transformer is coupled to the nonresonant secondary winding of the transformer, as shown in Fig. 69, the effect of the input impedance of the following stage on the Q of the tuned circuit can be determined by considering the values reflected (or referred) to the primary circuit by




Fig. 69—Equivalent circuit for transformercoupling network having tuned primary winding.

transformer action. The reflected resistance r_1 is equal to the resistance R_1 in the secondary circuit times the square of the effective turns ratio between the primary and secondary windings of the transformer T:

$$r_1 = R_1 (N_1/N_2)^2$$

where N_1/N_2 represents the electrical
turns ratio between the primary winding

and the secondary winding of T. If there is capacitance in the secondary circuit (C_s), it is reflected to the primary circuit as a capacitance C_{sp}, and is given by

$$C_{np} = C_p \div (N_1/N_2)^2$$

The loaded Q, or Q_L , is then calculated on the basis of the inductance L_p , the total shunt resistance (R_o plus r_1 plus the tuned-circuit impedance $Z_t = Q_oX_c = Q_oX_c$), and the total capacitance ($C_p + C_{sp}$) in the tuned circuit.

Fig. 70 shows a coupling network which consists of a single-tuned circuit using mutual inductive coupling. The




Fig. 70—Equivalent circuit for transformercoupling network using inductive coupling.

capacitance C_t includes the effects of both the output capacitance of the preceding tube and the input capacitance of the following tube (referred to the primary of transformer T_1). The bandwidth of a single-tuned transformer is determined by the half-power points on the resonance curve (—3 dB or 0.707 down from the maximum). Under these conditions, the band pass Δf is equal to the ratio of the center or resonant frequency f_r divided by the loaded (effective) Q of the circuit, as follows:

$$\Delta f = f_r/Q_L$$

In high-frequency tuned amplifiers, where the input impedance is typically low, mutual inductive coupling may be impracticable because of the small number of turns in the secondary winding. It is extremely difficult in practice to construct a fractional part of a turn. In such cases, capacitance coupling may




Fig. 71-Single-tuned coupling network using capacitive division.

be used, as shown in Fig. 71. This arrangement, which is also called capacitive division, is similar to tapping down on a coil at or near resonance. Impedance transformation in this network is determined by the ratio between capacitors C1 and C2. Capacitor C1 is normally much smaller than C2; thus the capacitive reactance Xc1 is normally much larger than X_{C2}. Provided the input resistance of the following tube is much greater than X_{C2}, the effective turns ratio from the top of the coil to the input of the following tube is $(C_1 +$ C₂)/C₁. The total capacitance C₁ across the inductance L is given by

$$C_t = \frac{C_t C_s}{C_1 + C_s}$$

The resonant frequency f_r is then given by

$$f_r = \frac{1}{2\pi\sqrt{L_iC_t}}$$

Double-tuned interstage coupling networks are often used in preference to single-tuned networks to provide flatter frequency response within the pass band, a sharper drop in response immediately adjacent to the ends of the pass band, or more attenuation at frequencies far removed from resonance. In synchronous double-tuned networks, both the resonant circuit in the input of the coupling network and the resonant circuit in the output are tuned to the same resonant frequency. In "stagger-tuned" networks, the two resonant circuits are tuned to slightly different resonant frequencies to provide a more rectangular band pass with sharper selectivity at the ends of the pass band. Double-tuned or stagger-tuned networks may use capacitive, inductive, or mutual inductance coupling, or any combination of the three.

Television Tuners

The vhf tuner of a television receiver selects the desired frequency channel in the range from 55 to 216 MHz, amplifies it, and converts it to a lower intermediate frequency. These functions are accomplished in rf-amplifier, mixer, and local-oscillator stages employing tube types that are designed specifically for these applications. The rf-amplifier stage uses a high-transconductance tube that has small dimensions to maintain low interelectrode capacitances, particularly between grid and plate. The mixer and oscillator stages usually employ a dual-unit triode-pentode unit and a medium-mu triode unit.

Fig. 72 shows a simplified schematic diagram of a typical vhf television tuner. The balun converts the 300ohm balanced antenna impedance to an unbalanced impedance of 75 ohms. The high-pass filter eliminates lower-frequency interference signals. The tuner is set to the desired frequency by simultaneous adjustment of the inductances indicated by the several sets of arrows in Fig. 72. The inductances are either replaced completely or incremental amounts of inductance are added as the tuner is switched from high frequencies to lower frequencies. Some tuners use a combination of the two methods.

Because noise generated in the first amplifier stage is often the controlling factor in determining the over-all sensitivity of a radio or television receiver, the "front end" is designed with special attention to both gain and noise characteristics. The input circuit of an amplifier inherently contains some thermal noise contributed by the resistive elements in the input device. When an input signal is amplified, therefore, the thermal noise generated in the input circuit is also amplified. If the ratio of signal power to noise power (signal-tonoise ratio, S/N) is the same in the output circuit as in the input circuit, the amplifier is considered to be "noise-




Fig. 72-Simplified schematic of typical vhf television tuner.

less," and is said to have a noise figure of unity, or zero dB.

In practical circuits, however, all amplifier stages generate a certain amount of noise as a result of thermal agitation of electrons in resistors and other components, minute variations in the cathode emission of tubes (shot effect), and minute grid currents in the amplifier tubes. As a result, the ratio of signal power to noise power is inevitably impaired during amplification. A measure of the degree of impairment is called the noise figure (NF) of the amplifier, and is expressed as the ratio of signal power to noise power at the input (S_1/N_1) divided by the ratio of signal power to noise power at the output (S_o/N_o), as follows:

$$NF = \frac{(S_1/N_1)}{(S_0/N_0)}$$

The noise figure in decibels (dB) is equal to ten times the logarithm of this power ratio. For example, a one-dB noise figure in an amplifier decreases the signal-to-noise ratio by a factor of 1.26, a 3-dB noise figure by a factor of 2, a 10-dB noise figure by a factor

of 10, and a 20-dB noise figure by a factor of 100.

The over-all noise figure of a receiver is affected by the total number of stages, as shown by the following relationship:

$$NF_{receiver} = NF_1 + \frac{(NF_2 + 1)}{G_1} + \frac{(NF_3 + 1)}{G_1G_2} \dots$$

where G represents power gain and the subscripts indicate the number of each stage. This relationship indicates that the contribution of the second-stage noise factor to that of the over-all receiver is reduced by the gain of the first stage. Therefore, it is important that the rf amplifier have enough gain to make the effect of the second stage negligible. The third stage will then have even less effect. The maximum available power gain G of an rf stage is given by

$$G = \frac{g_{m^2} R_{in} R_{out}}{4}$$

For maximum gain, therefore, the rfamplifier tube should have high transconductance and high input and output impedances. At frequencies in the vhf television band, the input resistance is small enough to affect the gain. As mentioned previously, the rf tube is designed to have low interelectrode capacitances, small interelectrode spacings, and low lead inductances (particularly the cathode lead).

The gain of the rf stage must be reduced as the incoming-signal amplitude changes to prevent overload distortion in the following stages. As the signal amplitude increases, an automatic-gain-control (agc) circuit biases the rf tube to decrease its gain. The rf tube usually employs a semiremotecutoff grid to reduce cross-modulation distortion.

Either a triode or a pentode can be used in the rf-amplifier stage of tuner input circuits of vhf television receivers. Such stages are required to amplify signals ranging from 55 to 216 MHz and having a bandwidth of 4.5 MHz (the tuner is usually aligned for a bandwidth of 6 MHz to assure complete coverage of the band). In early rf tuners, pentodes rather than triodes were used because the grid-plate capacitance of triodes created stability problems. However, the use of twin triodes in direct-coupled cathode-drive circuits makes it possible to obtain stable operation along with the low-noise characteristics of triodes.

Pentodes or tetrodes do not provide the useful sensitivity of triodes because of the "partition noise" introduced by the screen grid. The directcoupled cathode-drive circuit provides both the gain and the stability capabilities of the pentode, as well as the advantages of a low-noise triode input stage. Because the cathode-drive stage provides a low-impedance load to the grounded-cathode stage, the gain of the latter stage is very low and there is no necessity for neutralizing the grid-plate capacitance. An interstage impedance. usually an inductance in series with the plate of the first stage and the cathode of the second stage, is often used at higher frequencies to provide a degree of impedance matching between the units. The cathode-drive portion of the circuit is matched to the input network and provides most of the stage gain. Because the feedback path of the cathode-drive circuit is the plate-cathode capacitance, which in most cases is very small, excellent isolation is provided between the antenna and the local oscillator.

Development of single triodes having low grid-plate capacitance, such as the 6BN4A has made possible the design of neutralized triode rf circuits. Tubes such as the 6GK5 and 6CW4 are specially designed to minimize gridplate capacitance to permit easier neutralization of a grounded-cathode circuit over the wide frequency band. Bridge-neutralized rf-amplifier are widely used in television tuners: in this arrangement, a portion of the output signal is returned to the grid out of phase with the feedback signal from the grid-plate capacitance. This circuit provides excellent gain and noise performance with stable operation across the band.

The mixer stage of a vhf tuner usually employs a pentode tube, or the pentode unit of a triode-pentode tube. Although triodes such as the 6J6A were used as mixers in early receivers, they have been replaced by pentodes because the higher output impedance of a pentode provides a higher mixer gain than can be obtained with a triode.

The amplified signal from the rf stage in Fig. 72 is applied to the mixer grid along with a local-oscillator signal of much larger amplitude. The localoscillator signal varies the mixer grid voltage from cutoff into the grid-current region. This signal develops a gridresistor bias, called the injection voltage, which is a measure of the local-oscillator voltage. Because the transfer curve of the mixer tube is nonlinear, mixing action between the rf signal and the local-oscillator signal produces sum and difference frequencies. The output circuit of the mixer is tuned to the difference frequency (about 44 MHz) and rejects all other frequencies. This signal is then fed to the intermediate-frequency amplifier.

The mixer gain is a function of the amplitude of the local-oscillator signal. The gain has a broad maximum over a range of injection voltages from -2.5 to -5.0 volts for conventional-grid mixers and slightly lower for frame-grid mixers. Good impedance matching between the rf-amplifier plate and the mixer grid, consistent with bandpass requirements, is important to achieve maximum signal power transfer. A slight amount of regeneration is provided by a small screen-grid inductance. This regeneration effectively increases the mixer-grid input impedance and thus improves power gain.

The local-oscillator stage shown in Fig. 72 is a Colpitts type in which the tuned circuit is located between the grid and plate and the feedback path is through the tube interelectrode capacitances. A large signal is developed in the local oscillator and coupled loosely to the mixer grid to minimize the effects of changes in the mixer input on the frequency of oscillation. The circuit is designed to keep frequency shift within a very narrow range with supply-voltage and temperature changes. Fine tuning is provided by a variable inductance or capacitance across the tuned circuit. Tubes commonly used in local-oscillator and mixer circuits are the 6EA8, 6KZ8, and 6KE8.

Television IF Amplifiers

intermediate-frequency amplifier stages in a television receiver provide the additional gain required to bring the signal level to an amplitude suitable for final detection. A constant peak signal of about three to five volts is required at the input to the detector. The mixer output signal is passed through two or three stages of amplification to attain this level. High-transconductance pentodes having low grid-No.1-to-plate capacitances are normally used in if amplifiers. The coupling circuits are usually tuned transformers which may be single- or double-tuned. The transformers are either synchro-(same frequency) tuned stagger-tuned, depending on circuit requirements. The over-all bandwidth varies from a maximum of 3.58 MHz at the 6-dB points for color receivers to

values in the order of 2.0 to 2.5 MHz for the most inexpensive receivers. An expression for the figure of merit for a single tuned if-amplifier tube is the gain-bandwidth product $G \times B$, which is given by

$$G \times B = \frac{g_m}{2 \pi C}$$

where C is the total tuning capacitance. This relationship again demonstrates the need for high transconductance and low interelectrode capacitance.

The first stage (or first two stages in the case of a three-stage if) is gaincontrolled like the rf amplifier. However, the bias applied to the if-amplifier tube varies the input resistance and capacitance of the tube and thus detunes the circuit. It is important for proper reception to maintain the frequency response of the if stages constant, particularly in the case of the color receiver. Therefore, a small unbypassed cathode resistor is used which provides degenerative feedback to minimize the effect of bias changes. In addition, the effects on input impedance caused by the grid-plate capacitance are reduced by use of a partial bypass capacitor at the screen grid to provide neutralization of the grid-to-plate capacitance.

Tubes used in the gain-controlled stages of the if amplifier have remoteor semiremote-cutoff characteristics to reduce cross-modulation or intermodulation interference. Tube types commonly used in this application include the 6BZ6, 6GM6, 6JH6, 6JD6A, and 6KT6.

The last if-amplifier stage is a relatively-large-signal amplifier. For this reason, the tube must be biased so that it will operate over a region of linear operation for large voltage excursions. Because such a quiescent operating point provides a transconductance somewhat below the maximum value for the tube, the selection of the operating point involves a compromise between signal-handling capacity and gain. For purposes of linearity, the final if-amplifier stage is not gain-controlled, and operates with the cathode bypassed to ground. Because fixed bias

is used, a sharp-cutoff tube is used to provide higher transconductance than could be obtained with an equivalent remote- or semiremote-cutoff tube. Examples of types used in this stage are the 6EW6 and 6JC6A.

Wideband (Video) Amplifiers

In some applications, it is necessary for a circuit to amplify signals ranging from very low frequencies (several hertz) to high frequencies (tens of megahertz) with a minimum of frequency and time-delay distortion. For example, very exacting requirements are demanded for such applications as television camera chains, ac voltmeters, and vertical amplifiers for oscilloscopes. In response to these demands, circuit compensation techniques have been developed to minimize the amplitude and time-delay variation as the upper or lower frequency limits of the amplifier are approached.

The need for such compensation is evident when many identical stages of amplification are employed. If ten cascaded stages are used, a variation of 0.3 dB per stage results in a total variation of 3 dB. In an uncompensated amplifier, this total variation occurs two octaves (a frequency ratio of four) prior to the half-power point. Because two octaves are lost from both the high and low frequencies, the bandwidth of ten cascaded uncompensated amplifies stages is only one-sixteenth that of a single amplifier stage. Fig. 73 shows the amplitude response characteristics of various numbers of identical

uncompensated amplifiers.

In general, the output of an amplifier may be represented by a current generator iout and a load resistance R_L, as shown in Fig. 74(a). Because the signal current is shunted by various capacitances at high frequencies, as shown in Fig. 74(b), there is a loss in gain at these frequencies. If an inductor L is placed in series with the load resistor R_L, as shown in Fig. 74(c), a low-O circuit is formed which somewhat suppresses the capacitive loading. This method of gain compensation, called shunt peaking, can be effective for improving high-frequency response. Fig. 74 shows the frequency response for the circuits in Fig. 74(a), (b), and (c). If the inductor L in Fig. 74(c) is made self-resonant approximately one octave above the 3-dB frequency of the circuit of Fig. 74(b), the amplifier response is extended by about another 30 per cent.

If the stray capacitance C shown in Fig. 74(b) is broken into two parts C' and C" and an inductor L₁ is placed between them, a heavily damped form of series resonance may be employed for further improvement. This form of compensation, called series peaking, is shown in Fig. 75(a). If C' and C" are within a factor of two of each other, series peaking produces an appreciable improvement in frequency response as compared to shunt peaking. A more complex form of compensation embodying both self-resonant shunt peaking and series peaking is shown in Fig. 75(b).

The effects of various high-fre-




Fig. 73—Amplitude response characteristics of various numbers (N) of identical uncompensated amplifiers.




Fig. 74—Equivalent circuits and frequency response of uncompensated and shunt-peaked amplifiers.

quency compensation systems can be demonstrated by consideration of an amplifier consisting of three identical stages. If each of the three stages is down 3 dB at 1 MHz, and if a total gain variation of plus 1 dB and minus 3 dB is allowed, the bandwidth of the amplifier is 0.5 MHz without compensation. Shunt peaking raises the bandwidth to 1.3 MHz. Self-resonant shunt




Fig. 75—Circuits using (a) series peaking, and (b) both self-resonant shunt peaking and series peaking.

peaking raises it to 1.5 MHz. An infinitely complicated network of shunt-peaking techniques could raise it to 2 MHz. If the distribution of capacitance permits it, series peaking alone can provide a bandwidth of about 2 MHz, while a combination of shunt and series peaking can provide a band-

width of approximately 2.8 MHz. If the capacitance is perfectly distributed, and if an infinitely complex network of shunt and series peaking is employed, the ultimate capability is about 4 MHz.

The frequency response of a wideband amplifier is influenced greatly by variations in component values due to temperature effects, variation of tube parameters with voltage and rent (normal large-signal excursions). changes of stray capacitance due to relocated lead wires, or other variations. A change of 20 per cent in any of the critical parameters can cause a change of 0.7 dB in gain per stage over the last half-octave of the response for the most simple case of shunt peaking. As the bandwidth is extended by more complex peaking, a circuit becomes substantially more critical. (Measurement probes generally alter circuit performance because of their capacitance: this effect should be considered during frequency-response measurements.

In the design of wideband amplifiers using many stages of amplification, it is necessary to consider timedelay variations as well as amplitude variation. When feedback capacitance is a major contributor to response limitation, the more complex compensaing networks may produce severe ringing or even sustained oscillation. If feedback capacitance is treated as input capacitance produced by the Miller effect, the added input capacitance Cr caused by the feedback capacitor Cr is given by

$$C_{t'} = C_{t} (1 - VG)$$

where VG is the input-to-output voltage gain. The gain VG, however, has a phase angle that varies with frequency. The phase angle is 180 degrees at low frequencies, but may fead or lag this value at high frequencies; the magnitude of VG then also varies. In the design of very wideband amplifiers (20 MHz or more), the phase of the transconductance g_m must be considered.

The video amplifier stage in a television receiver usually employs a pentode-type tube specially designed to amplify the wide band of frequencies contained in the video signal and, at the same time, to provide high gain per stage. Pentodes are more useful than triodes in such stages because they have high transconductance (to provide high gain) together with low input and output interelectrode capacitances (to permit the broadband requirements to be satisfied). An approximate "figure of merit" for a particular tube for this application can be determined from the ratio of its transconductance, gm, to the sum of its input and output capacitances, Cin and Cout, as follows:

Figure of Merit =
$$\frac{g_m}{C_{in} + C_{out}}$$

Typical values for this figure are in the order of 500 x 10° or greater.

A typical video amplifier stage, such as that shown in Fig. 76, is connected between the second detector of the television receiver and the picture tube. The contrast control, R₁, in this circuit controls the gain of the video amplifier tube. The inductance, L₂, in series with the load resistor, R_L, mains the plate load impedance at a relatively constant value with increasing

frequency. The inductance L_1 isolates the output capacitance of the tube so that only stray capacitance is placed




Fig. 76—Typical video amplifier stage.

across the load. As a result, a higher-value load resistor is used to provide higher gain without affecting frequency response or phase relations. The decoupling circuit, C₁R₂, is used to improve the low-frequency response. Tubes used as video amplifiers include types 6CL6 and 12BY7A, or the pentode sections of types 6AW8A and 6AN8A.

The luminance amplifier in a colortelevision receiver is a conventional video amplifier having a bandwidth of approximately 3.5 MHz. In a color receiver, the portion of the output of the second detector which lies within the frequency band from approximately 2.4 to 4.5 MHz is fed to a bandpass amplifier, as shown in the block diagram in Fig. 77. The color




Fig. 77—Block diagram of video-amplifier section of color television receiver.

synchronizing signal, or "burst," contained in this signal may then be fed to a "burst-keyer" tube. At the same

time, a delayed horizontal pulse may be applied to the keyer tube. The output of the keyer tube is applied to the burst amplifier tube and the signal is then fed to the 3.58-MHz oscillator and to the "color-killer" stage.

The color killer applies a bias voltage to the bandpass amplifier in the absence of burst so that the color section. or chrominance channel, of the receiver remains inoperative during black-andwhite broadcasts. A threshold control varies the bias and controls the burst level at which the killer stage operates.

The output of the 3.58-MHz oscillator and the output of the bandpass amplifier are fed into phase and amplitude demodulator circuits. The output of each demodulator circuit is an electrical representation of a color-difference signal, i.e., an actual color signal minus the black-and-white, or luminance, signal. The two color-difference signals are combined to produce the third color-difference signal; each of the three signals then represents one of the primary colors.

The three color-difference signals are usually applied to the grids of the three electron guns of the color picture tube, in which case the black-and-white signal from the luminance amplifier may be applied simultaneously to the cathodes. The chrominance and luminance signals then combine to produce the color picture. In the absence of transmitted color information, the chrominance channel is cut off by the color killer, as described above, and only the luminance signal is applied to the picture tube, producing a black-and-white picture.

TV Scanning. Sync. and Deflection


For reproduction of a transmitted picture in a television receiver, the

face of a cathode-ray tube is scanned with an electron beam while the intensity of the beam is varied to control the emitted light at the phosphor screen. The scanning is synchronized with a scanned image at the TV transand the black-through-white picture areas of the scanned image are converted into an electrical signal that controls the intensity of the electron beam in the picture tube at the receiver.

Scanning Fundamentals

The scanning procedure used in the United States employs horizontal linear scanning in an odd-line interlaced pattern. The standard scanning pattern for television systems includes a total of 525 horizontal scanning lines in a rectangular frame having an aspect ratio of 4 to 3. The frames are repeated at a rate of 30 per second, with two fields interlaced in each frame. The first field in each frame consists of all odd-number scanning lines, and the second field in each frame consists of all even-number scanning lines. The field repetition rate is thus 60 per second, and the vertical scanning rate is 60 Hz.

The geometry of the standard oddline interlaced scanning pattern is illustrated in Fig. 78. The scanning beam starts at the upper left corner of the frame at point A, and sweeps across the frame with uniform velocity to cover all the picture elements in one horizontal line. At the end of each trace, the beam is rapidly returned to the left side of the frame, as shown by the dashed line, to begin the next horizontal line. The horizontal lines slope downward in the direction of scanning because the vertical deflecting signal simultaneously produces a verti-



cal scanning motion, which is very slow compared with the horizontal scanning speed. The slope of the horizontal line trace from left to right is greater than the slope of the retrace from right to left because the shorter time of the retrace does not allow as much time for vertical deflection of the beam. Thus, the beam is continuously and slowly deflected downward as it scans the horizontal lines, and its position is successively lower as the horizontal scanning proceeds.

At the bottom of the field, the vertical retrace begins, and the beam is brought back to the top of the frame to begin the second or even-number field. The vertical "flyback" time is very fast compared to the trace, but is slow compared to the horizontal scanning speed; therefore, some horizontal lines are produced during the

vertical flyback.

All odd-number fields begin at point A in Fig. 78 and are the same. All even-number fields begin at point C and are the same. Because the beginning of the even-field scanning at C is on the same horizontal level as A, with a separation of one-half line. and the slope of all lines is the same. the even-number lines in the even fields fall exactly between the odd-number lines in the odd field.

In addition to picture information, the composite video signal from the video detector of a television receiver contains timing pulses to assure that the picture is produced on the faceplate of the picture tube at the right instant and in the right location. These pulses, which are called sync pulses,

control the horizontal and vertical scanning generators of the receiver.

Fig. 79 shows a portion of the detected video signal. When the picture is bright, the amplitude of the signal is low. Successively deeper grays are represented by higher amplitudes until, at the "blanking level" shown in the diagram, the amplitude represents a complete absence of light. This "black level" is held constant at a value equal to 75 per cent of the maximum amplitude of the signal during transmission. The remaining 25 per cent of the signal amplitude is used for synchronization information. Portions of the signal in this region (above the black level) cannot produce light.

In the transmission of a television picture, the camera becomes inactive at the conclusion of each horizontal line and no picture information is transmitted while the scanning beam is retracing to the beginning of the next line. The scanning beam of the receiver is maintained at the black level during this retrace interval by means of the blanking pulse shown in Fig. 79. Immediately after the beginning of the blanking period, the signal amplitude rises further above the black level to provide a horizontal-synchronization pulse that initiates the action of the horizontal scanning generator. When bottom line of the picture is reached, a similar vertical-synchronization pulse initiates the action of the vertical scanning generator to move the scanning spot back to the top of the pattern.

The sync pulses in the composite video signal may be separated from the video information in the output of the second or video detector by means of




Fig. 79-Detected video signal.

the triode circuit shown in Fig. 80. In this circuit, the time constant of the network R₁C₁ is long with respect to the interval between pulses. During each pulse, the grid is driven positive and draws current, thereby charging capacitor C₁. Consequently, the grid develops a bias which is slightly greater




Fig. 80-Sync-separator circuit.

than the cutoff voltage of the tube. Because plate current flows only during the sync-pulse period, only the amplified pulse appears in the output. This sync-separator stage discriminates against the video information. Because the bias developed on the grid is proportional to the strength of the incoming signal, the circuit also has the advantage of being relatively independent of signal fluctuations.

After the synchronizing signals are separated from the composite video signal, it is necessary to filter out the horizontal and vertical sync signals so that each can be applied to its respective deflection generator. This filtering is accomplished by RC circuits designed to filter out all but the desired synchronizing signals. Although the horizontal, vertical, and equalizing pulses are all rectangular pulses of the same amplitude, they differ in frequency and pulse width, as shown in Fig. 81. The horizontal sync pulses have a repetition rate of 15,750 per second (one for

each horizontal line) and a pulse width of 5.1 microseconds. The equalizing pulses have a width approximately half the horizontal pulse width, and a repetition rate of 31.500 per second; they occur at half-line intervals, with six pulses immediately preceding and six following the vertical synchronizing pulse. The vertical pulse is repeated at a rate of 60 per second (one for each field), and has a width of approximately 190 microseconds. The serrations in the vertical pulse occur at half-line intervals, dividing the complete pulse into six individual pulses that provide horizontal synchronization during the vertical retrace. (Although the picture is blanked out during the vertical retrace time, it is necessary to keep the horizontal scanning generator synchronized.)

All the pulses described above are produced at the transmitter by the synchronizing-pulse generator; their waveshapes and spacings are held within very close tolerances to provide the required synchronization of receiver and transmitter scanning.

The horizontal sync signals are separated from the total sync in a differentiating circuit that has a short time constant compared to the width of the horizontal pulses. When the total sync signal is applied to the differentiating circuit shown in Fig. 82, the capacitor charges completely very soon after the leading edge of each pulse, and remains charged for a period of time equal to practically the entire pulse width. When the applied voltage is removed at the time corresponding to the trailing edge of each pulse, the capacitor discharges completely within a very short time. As a result, a positive peak of voltage is obtained for




Fig. 81—Waveform of TV synchronizing pulses (H = horizontal line period of 1/15,750 seconds, or 63.5 μs).




Fig. 82—Separation of the horizontal sync signals from the total sync by a differentiating circuit.

each leading edge and a negative peak for the trailing edge of every pulse. One polarity is produced by the charging current for the leading edge of the applied pulse, and the opposite polarity is obtained from the discharge current corresponding to the trailing edge of the pulse.

As mentioned above, the serrations in the vertical pulse are inserted to provide the differentiated output needed to synchronize the horizontal scanning generator during the time of vertical synchronization. During the vertical blanking period, many more voltage peaks are available than are necessary for horizontal synchronization (only one pulse is used for each horizontal line period). The check marks above the differentiated output in Fig. 82 indicate the voltage peaks used to synchronize the horizontal deflection generator for one field. Because the sync system is made sensitive only to positive pulses occurring at approximately the right horizontal timing, the negative sync pulses and alternate differentiated positive pulses produced by the equalizing pulses and the serrated vertical information have no effect on horizontal timing. It can be seen that although the total sync signal (including vertical synchronizing information) is applied to the circuit of Fig. 82, only horizontal synchronization information appears at the output.

The vertical sync signal is separated from the total sync in an integrating circuit which has a time constant that is long compared with the duration of the 5-microsecond horizontal pulses, but short compared with the 190-microsecond vertical pulse width. Fig. 83 shows the general circuit configuration




Fig. 83—Separation of vertical sync signals from the total sync for odd and even fields with no equalizing pulses. (Dashed line indicates triggering level for vertical scanning generator.)

used, together with the input and output signals for both odd and even fields. The period between horizontal pulses, when no voltage is applied to the RC circuit, is so much longer than the horizontal pulse width that the capacitor has time to discharge almost down to

zero. When the vertical pulse is applied, however, the integrated voltage across the capacitor builds up to the value required for triggering the vertical scanning generator. This integrated voltage across the capacitor reaches its maximum amplitude at the end of the vertical pulse, and then declines practically to zero, producing a pulse of the triangular wave shape shown for complete vertical synchronizing pulse. Although the total sync signal (including horizontal information) is applied to the circuit of Fig. 83, therefore, only vertical synchronization information appears at the output.

The vertical synchronizing pulses are repeated in the total sync signal at the field frequency of 60 per second. Therefore, the integrated output voltage across the capacitor of the RC circuit of Fig. 83 can be coupled to the vertical scanning generator to provide vertical synchronization. The six equalizing pulses immediately preceding and following the vertical pulse improve the accuracy of the vertical synchronization for better interlacing. The equalizing pulses that precede the vertical pulses make the average value of applied voltage more nearly the same for even and odd fields, so that the integrated voltage across the capacitor adjusts to practically equal values for the two fields before the vertical pulse begins. The equalizing pulses that follow the vertical pulse minimize any difference in the trailing edge of the vertical synchronizing signal for even and odd fields.

In fringe areas, two conditions complicate the process of sync separation. First, the incoming signal available at the antenna is weak and susceptible to fading and other variations; second, the receiver is operating at or near maximum gain, which makes it extremely susceptible to interference from pulse-type noise generated by certain types of electrical equipment, ignition systems, switches, or the like. Some type of **noise-immunity** provision is almost essential for acceptable performance. Noise may be reduced or eliminated from the sync and agc circuits by gating or by a combination of gating, inversion, and cancellation. An example, of the latter method is shown in Fig. 84. In this circuit the 6GY6, which has two independent control grids, serves the dual function of age amplifier and noise inverter. Because the sync tips of the video signal at grid No. 1 of the 6GY6 drive the tube near its cutoff region, any noise signal extending above the tip level will appear inverted across the grid-No.2 load resistor R. This inverted noise signal is re-combined with the video signal and fed to the sync separator at point "A" in Fig. 84, where noise cancellation takes place. This process leaves the sync pulses relatively free of disturbing noise and results in a stable picture.




Fig. 84-Typical noise-cancellation circuit.

To prevent reduction of receiver gain due to the effect of noise on the agc amplifier, a portion of the inverted noise signal is fed to the second control grid, grid No.3, of the 6GY6 to cut off or gate the agc amplifier when a noise pulse occurs.

Horizontal Deflection

In the horizontal-deflection stages of a television receiver, a current that varies linearly with time and has a sufficient peak-to-peak amplitude must be passed through the horizontal-deflection-yoke winding to develop magnetic field adequate to deflect the electron beam of the television picture tube. (This type of deflection is different from that used in a cathode-ray oscilloscope, where the beam is deflected electrostatically.) After beam is deflected completely across the face of the picture tube, it must be returned very quickly to its starting point. (As explained previously, the beam is extinguished during this retrace by the blanking pulse incorporated in the composite video signal, or in some cases by additional external blanking derived from the horizontaldeflection system.)

The simplest form of a deflection circuit is shown in Fig. 85. In this circuit, the yoke impedance L is assumed to be a perfect inductor. When the



Fig. 85—Simplest form of deflection circuit.

switch is closed, the yoke current starts from zero and increases linearly. At any time t, the current i is equal to Et/L, where E is the applied voltage. When the switch is opened at a later time t₁, the current instantly drops from a value of Et₁/L to zero.

Although the basic circuit of Fig. 85 crudely approaches the requirements for deflection, it presents some obvious problems and limitations. The voltage across the switch becomes extremely

high, theoretically approaching infinity. In addition, if very little of the total time is spent at zero current, the circuit would require a tremendous amount of dc power. Furthermore, the operation of the switch would be rather critical with regard to both its opening and its closing. Finally, because the deflection field would be phased in only one direction, the beam would have to be centered at the extreme left of the screen for zero yoke current.

If a capacitor is placed across the switch, as shown in Fig. 86, the yoke




Fig. 86—Addition of capacitor to permit flyback ringing, and yoke-current (upper) and switch-voltage (lower) waveforms.

current still increases linearly when the switch is closed at time t=0. However, when the switch is opened at time $t=t_1$, a tuned circuit is formed by the parallel combination of L and C. The resulting yoke currents and switch voltages are then as shown in Fig. 86. The current is at a maximum when the voltage equals zero, and the voltage is at a maximum when the current equals zero. If it is assumed that there are no losses, the ringing frequency f_{osc} is equal to $1/(2\pi\sqrt{LC})$.

If the switch is closed again at any time the capacitor voltage is not equal to zero, an infinite switch current flows as a result of the capacitive discharge. However, if the switch is closed at the precise moment t₂ that the capacitor voltage equals zero, the capacitor cur-

rent effortlessly transfers to the switch, and a new transient condition results. Fig. 87 shows the yoke-current and switch-voltage waveforms for this new condition.

If the switch is again opened at t₁, closed at t₃, and so on, the desired




Fig. 87—Yoke-current (upper) and switchvoltage (lower) waveforms when switch is closed at t₂.

sweep results, the peak switch voltage is finite, and the average supply current is zero. The deflection system is then lossless and efficient and, because the average yoke current is zero, beam decentering is avoided. The only fault of the circuit of Fig. 86 is the critical timing of the switch, particularly at time $t = t_2$. However, if the switch is shunted by a damper diode, as shown in Fig. 88, the diode acts as a closed switch as soon as the capacitor voltage reverses slightly. The switch may then be closed at any time between t_2 and t_3 .




Fig. 88-Incorporation of damper diode.

Fig. 89 shows a typical horizontaloutput-and-deflection circuit used in television receivers. In addition to supplying the deflection energy required for horizontal deflection of the picture-tube beam, this circuit provides the high dc voltage required for the ultor (anode) of the picture tube and the "boosted" B voltage for other portions of the receiver. The horizontal-output tube is usually a beam power tube such as the 6JB6A, 6JG6A, or 6LQ6/6JE6C.

In this circuit, a sawtooth voltage from the horizontal-oscillator tube is applied to the grid No. 1 of the horizontal-output tube. When this voltage rises above the cutoff point of the output tube, the tube conducts a sawtooth of plate current which is fed through the auto-transformer to the horizontal-deflecting yoke. At the end of the horizontal-scanning cycle, which lasts for 63.4 microseconds, the sawtooth voltage on the grid suddenly cuts off the output tube. This sudden change sets up an oscillation of about 50 to 70 kHz in the output circuit, which may be considered as an inductor shunted by the stray capacitance of the circuit. During the first half of this oscillation, a positive voltage appears across the transformer. In the




Fig. 89—Typical horizontal-deflection and high-voltage circuit.

second half of the cycle, the voltage swings below the plate supply voltage, and the damper diode conducts, damping out the oscillation. At the same time, the current through the deflecting yoke reverses and reaches its negative peak. As the damper-diode current decays to zero, the output tube begins to conduct again. The yoke current, therefore, is composed of current resulting from damper-diode conduction followed by output-tube conduction.

When the output tube is suddenly cut off, the high-voltage pulse produced is increased by means of an extra winding on the transformer. This high-voltage pulse charges a high-voltage capacitor through the high-voltage rec-

tifier. The output of this circuit is the dc high-voltage supply for the picture tube. The high-voltage rectifier also obtains its filament power through a separate winding on the horizontal-output transformer.

Current flowing through the damper diode charges the "boost" capacitor through the damper portion of the transformer winding. The polarity of the charge on the capacitor is such that the voltage at the low end of the winding is increased above the plate supply voltage, or B+. This higher voltage or "boost" is used for the output-tube plate supply, and may also supply the deflection oscillators and other low-current-drain circuits in the receiver.

Vertical Deflection

The vertical-deflection circuit in a television receiver is essentially a class A audio amplifier with a complex load line, severe low-frequency requirements (much lower than 60 Hz), and a need for controlled linearity. The equivalent low-frequency response for a 10-percent deviation from linearity is 1 Hz.

The required performance can be obtained in a vertical-deflection circuit in any of three ways. The amplifier may be designed to provide a flat response down to 1 Hz. This design, however, requires an extremely large output transformer and immense capacitors. Another arrangement is to design the amplifier for fairly good low-frequency response and predistort the generated signal.

The third method is to provide extra gain so that feedback techniques can be used to provide linearity. If loop feedback of 20 or 30 dB is used, tube gain variations and nonlinearities become fairly insignificant. The feedback automatically provides the necessary "predistortion" to correct low-frequency limitations. In addition, the coupling of miscellaneous signals (such as power-supply hum or horizontal-deflection signals) in the amplifying loop is suppressed.

A modified multivibrator in which the vertical-output tube is part of the oscillator circuit is used in the verticaldeflection stage of many television receivers. This stage supplies the deflecrequired for vertical energy deflection of the picture-tube beam. A simplified combined vertical-oscillatoroutput stage is shown in Fig. 90. Waveshapes at critical points of the circuit are included to illustrate the development of the desired current through the vertical-output transformer and deflecting yoke.

The current waveform through the deflecting yoke and output transformer should be a sawtooth to provide the desired deflection. The grid and plate voltage waveforms of the output tube could also be sawtooth except for the effect of the inductive components in the yoke and transformer. The effect of these inductive components must be taken into consideration, however, particularly during retrace. The fast rate of current change during retrace time (which is approximately 1/15 as long as trace




Fig. 90—Simplified combined vertical-oscillator-and-output stage.

time) causes a high-voltage pulse at the plate which could give a trapezoidal waveshape to the plate voltage and cause increased plate current, excess damping, and lengthened retrace time. However, the grid voltage is made sufficiently negative during retrace to keep the tube close to cutoff, as described below.

The frequency, and the relative deviation of the positive and negative portions of each cycle, are dependent on the values of resistors R₁ and R₃ and the RC combination R₃C₂, as explained in the section on multivibrators. The desired trapezoidal waveshape at the grid of V2 is created by capacitor C1 and resistor R2. If R2 were equal to zero, C₁ would cause the grid-voltage waveshape to take the form shown in Fig. 91(a). When R₂ is sufficiently large, C1 does not discharge completely when V₁ conducts. When V₁ is cut off, therefore, the voltage on the grid of V₂ immediately rises to the voltage across C₁. The resulting waveshape is shown in Fig. 91(b). The negative-going pulse of the grid-voltage waveshape prevents the high plate pulse from causing excess conduction, and thereby prevents overdamping.



Fig. 91—Waveforms showing effect of R₂ in Fig. 90.

This vertical-deflection stage utilizes twin-triode tubes such as the 6DR7 and 6GF7A. The 6GF7A is particularly suitable for this application because it incorporates dissimilar units to provide for the different operating requirements of the oscillator and output sections.

High-Voltage Regulation

In color television receivers, it is very important to regulate the highvoltage supply for the picture tube. Poor regulation of the high voltage can adversely affect the performance of the focusing and convergence circuits so that picture blooming results. In addition, excessive voltage or current may be applied to the high-voltage rectifier, horizontal-output tube, and horizontal-output (flyback) transformer so that the useful life of these components is substantially shortened. In modern color television receivers, regulation of the high voltage is accomplished by use of a shunt-type electronic voltage regulator connected across the output of the high-voltage power supply or by use of a pulse-type regulator connected in shunt with the flyback transformer.

Shunt Regulator Circuit—Fig. 92 shows the schematic diagram of a typical shunt regulator circuit. This circuit uses a 6BK4C/6EL4 or 6EN4 sharp-cutoff beam triode for the regulation of tube and is suitable for regulation of the output of a high-voltage, high-impedance supply. The cathode of the regulator beam triode is held at a fixed positive potential with respect to ground. Because the grid potential is kept slightly less positive by the voltage drop across resistor R₂, the tube operates in the negative grid region and no grid current is drawn.

When the output voltage, e₀, rises as a result of a decrease in load current.




Fig. 92—High-voltage regulator circuit for color television.

a small fraction of the additional voltage is applied to the grid of the tube by the voltage-divider circuit consisting of R₁ and R₂. This increased grid voltage causes the tube to draw an increased current from the unregulated supply. The increased current, in turn, causes a voltage drop across the high internal impedance of the unregulated supply, R_s, which tends to counteract the original rise of the voltage. If desired, the

grid may be connected to a variable point on the voltage divider to allow some adjustment of the output-voltage level.

The grid voltage for the regulator can also be obtained from a tap on the B-boost voltage supply. The use of this lower voltage (about 375 volts) eliminates the need for costly and trouble-some high-voltage resistors. In this arrangement, variations in high voltage also vary the tapped-down B-boost voltage at the regulator grid, and the resulting variations in conduction of the regulator increase or decrease the loading of the high-voltage supply so that the total load remains nearly constant.

The shunt regulator circuit, in effect, presents a variable load impedance to the output of the high-voltage rectifier. Because the regulator is connected directly across the output of the rectifier, the regulator tube is required to handle the full amount of the high voltage (approximately 25 kilovolts) applied to the picture tube. The tube area, therefore, must be well shielded to provide adequate X-ray protection, and a relatively large area is required for voltage insulation. In addition, the high-voltage rectifier is required to conduct full-load current continuously. The shunt regulator maintains a constant high voltage by sensing changes in the B Boost voltage, which are indicative of changes in beam current, and increasing or decreasing conduction accordingly.

Pulse Regulator Circuit—In pulse-regulator system, the regulator circuit is effectively shunted across part of the horizontal winding of the horizontal-output transformer. During operation, the pulse-regulator circuit maintains a substantially constant pulse amplitude in the primary winding of the horizontal-output transformer with changing loads on the high-voltage power supply. A constant-amplitude, stepped-up pulse is then applied to the high-voltage rectifier tube, and the high voltage developed from this pulse is maintained at a constant value. In the pulse-regulator system, regulator control is achieved by sampling the picturetube current by means of a special winding on the fly-back transformer and use of the resultant voltage drop (across a resistor) to control the grid circuit of the regulator tube.

Fig. 93 shows the schematic diagram and significant waveforms for a circuit that uses a 17KV6A beam-power pentode for the regulator tube. During trace and retrace, the cathode of the 17KV6A is held at B+. During the trace period, the screen grid of the 17KV6A is biased well below the cathode voltage and is unaffected by the beam current drawn by the picture tube. The control-grid bias is determined by the resistive voltage-divider network R₂, R₃, R₄, and R₅ and is directly dependent on the beam current of the picture tube. The damper tube conducts during the trace period and holds the plate potential of the 17KV6A at B+. With the plate-to-cathode potential at zero and the screen grid negative with respect to the cathode, the regulator tube is completely cut off during the trace period. At the start of the retrace period, however, the damper tube becomes reverse-biased, and the voltage on the plate of the regulator tube begins to rise. This increasing voltage is coupled to the screen grid through C₁ and R₁ and to the control grid through the interelectrode capacitance of the tube.

The waveforms in Fig. 93 show that at the start of retrace the plate and screen grid of the 17KV6A have both been driven positive with respect to the cathode and the control grid has become less negative with respect to the cathode. The regulator tube then begins to conduct. The pulses impressed on the screen and control grids are short in duration so that the screen grid remains positive with respect to the cathode and the control grid remains near cathode potential for only a short time. The regulator tube is driven into conduction for approximately 2 to 4 microseconds at the start of retrace and is then cut off. As the beam current increases or decreases, the voltage developed across the re-




Fig. 93—Schematic diagram and significant waveforms for a typical pulse-regulator circuit.

sistive voltage-divider network R_2 , R_3 , R_4 , and R_6 tracks these changes and is applied to the control grid of the regulator tube. In this way, the conduction of the regulator tube is increased or decreased as required to maintain a constant high-voltage output. By re-

moval of the energy from the rising edge of the flyback pulse in this fashion, the height of the pulse used to develop the high voltage is controlled. At the same time interference with the shape of the deflection pulse is held to a minimum.

Color Demodulation

In the transmission of picture signals for color-television receivers, all the color information is contained in three signals, a luminance (black-andwhite) or monochrome signal and two chrominance signals. The luminance signal, which is called the Y signal, contains brightness information only. The voltage response of the Y signal is made similar to the brightness response of the human eve by use of a composite signal that contains definite proportions of the red, green, and blue signals from the color-television camera (30 per cent red, 59 per cent green, and 11 per cent blue). This Y signal, which includes sync and blanking pulses, provides a correct monochrome picture in a conventional black-and-white television receiver.

For the generation of color-television signals, the Y signal is subtracted from the red, green, and blue signals to provide a new set of color-difference signals, which are designated as R-Y, B-Y, and G-Y. All of the original picture information is contained in the Y signal, the R-Y signal, and the B-Y signal. Therefore, the G-Y signal is not contained in the transmitted signal, but is synthesized in the receiver by proper combination of the R-Y and B-Y signals.

(Color signals transmitted under present color-television standards are not R-Y and B-Y, but a similar pair of signals designated as I and Q. In the color-television receiver, R-Y and B-Y signals are demodulated directly from the I and Q signals with negligible loss

of color quality. For purposes of simplicity, only R-Y and B-Y signals are considered in this explanation. In addition, a 90-degree phase-shift network is shown; the phase-shift angle could be, and often is, some other value.)

Because the luminance signal and the two color-difference signals must be transmitted with a standard 6-MHz channel, the two color signals are combined into one signal at the transmitter and are independently recovered the receiver by proper detection techniques. A color subcarrier of approximately 3.58 MHz is used for transmitting the color information within the 6-MHz spectrum of the television station. As shown in Fig. 94. the 3.58-MHz subcarrier and one of the color-difference signals are applied directly to a balanced AM modulator. The other color-difference signal is applied directly to a second balanced AM modulator, and the 3.58-MHz subcarrier is applied to this second modulator through a 90-degree phase-shifting network. The balanced modulators effectively cancel both the individual colordifference signals and the subcarrier signal, and the output contains only the sidebands of the combined chrominance signal.

Recovery of the color information at the receiver involves a process called synchronous detection. In this process, two separate detectors are used to recover the separate color information, just as two separate modulators were used to combine the information at the transmitter. The 3.58-MHz subcarrier, which was suppressed during transmission, must be reinserted at the receiver for recovery of the color information.




Fig. 94—Formation of combined color signal for transmission.




Fig. 95-Separation of combined color signal into two signals at the receiver.

The basis of synchronous detection is the phase relationship of this reinserted 3.58-MHz subcarrier.

For example, the original color information is represented in Fig. 94 by the color-difference signals A and B. At the receiver, the combined color signal is fed to two demodulators A and B, as shown in Fig. 95. At the same time, a 3.58-MHz subcarrier is also fed to the two demodulators, with the same phase relationship that was used in the modulators at the transmitter. This locally generated subcarrier essentially duplicates or replaces the original subcarrier, which was removed at the transmitter.

The local 3.58-MHz oscillator in the color-television receiver is made to function at the proper frequency and phase by means of a synchronizing signal sent out by the transmitter. This synchronizing signal consists of a short burst of 3.58-MHz signals transmitted during the horizontal blanking interval, immediately after the horizontal sync pulse, as shown in Fig. 96.




Fig. 96—Waveform for synchronizing signal.

Fig. 97 shows a simplified diagram of a low-level color demodulator fre-

quently used in color-television receivers. The locally generated 3.58-MHz signal is applied to the grid No. 3 of the pentode. The transmitted color signal containing the 3.58-MHz sidebands is applied to grid No. 1. The phase of the 3.58-MHz color signal constantly changes in accordance with its color content. For example, the following table shows six variations in color (hue) as a function of subcarrier phase:

Subcarrier Phase-degrees (with respect to 3.58-MHz local signal in phase with burst)	Hue
13	Yellow
77	Red
119	Magenta
193	Blue
257	Cyan
299	Green

The basic operating principle of the color demodulator shown in Fig. 97 is that plate current from the pentode is zero (or quite low) unless both grid No. 1 and grid No. 3 are simultaneously positive. For example, when the signals applied to the two grids are in phase, plate current can be expected to flow for 180 degrees of each ac cycle. Conversely, when the signals are 180 degrees out of phase. plate current is cut off. The output signal from the detector, therefore, is a function of the phase relationship between the transmitted color signal and the locally generated subcarrier.

In a typical color-television receiver, two color demodulators of the type shown in Fig. 97 are required. In one demodulator, the 3.58-MHz subcarrier signal is applied directly to the pentode grid No. 3 from the local "burst" oscillator. In the other demodulator, the 3.58-MHz signal from the




Fig. 97-Low-level color demodulator.

burst oscillator is shifted 90 degrees in phase before it is applied to the pentode grid No. 3. As shown previously in Fig. 95, the demodulator B produces R-Y signals. These B-Y and R-Y signals are then combined (matrixed) to produce the G-Y signal, as discussed earlier. The complete luminance signal is then amplified to the required level in a conventional video-amplifier circuit.

In some color-television receivers, the demodulators are designed so that the color output signals can be applied directly to the color picture tube. In the diagram shown in Fig. 98, for example, the 6JH8 sheet-beam demodula-





Fig. 98—Block diagram of demodulator circuit used to apply signals directly to color picture tube.

tors produce both positive and negative B-Y and R-Y signals. The positive signals are applied directly to the control grids (grid No. 1) of the blue and red guns of the color picture tube. At the same time, the negative color-difference signals are added (matrixed) in the correct proportions to produce the G-Y

signal, which is applied to grid No. 1 of the green gun.

Oscillation

As an oscillator, an electron tube can be employed to generate a continuously alternating voltage. In presentradio broadcast receivers, application is limited practically to superheterodyne receivers for supplying the heterodyning frequency. Several circuits (represented in Fig. 99) may be utilized, but they all depend on feeding more energy from the plate circuit to the grid circuit than is required to equal the power loss in the grid circuit. Feedback may be produced by electrostatic or electromagnetic coupling between the grid and plate circuits. When sufficient energy is fed back to more than compensate for the loss in the grid circuit, the tube will oscillate.






Fig. 99—Tuned-grid triode oscillator circuit: (a) using filament-type tube; (b) using heater-cathode-type tube.

The action consists of regular surges of power between the plate and the grid circuit at a frequency dependent on the circuit constants of inductance and capacitance. By proper choice of these values, the frequency may be adjusted over a very wide range.

Multivibrators

Relaxation oscillators, which are widely used in present-day electronic equipment, are used to produce non-sinusoidal waveshapes such as rectangular and sawtooth pulses. Probably the most common relaxation oscillator is the multivibrator, which may be considered as a two-stage resistance-coupled amplifier in which the output of each tube is coupled into the input of the other tube.

Fig. 100 is a basic multivibrator circuit of the free-running type. In this circuit, oscillations are maintained by the alternate shifting of conduction from one tube to the other. The cycle usually starts with one tube, V₁, at zero bias. and the other, V2, at cutoff or beyond. At this point, the capacitor C1 is charged sufficiently to cut off V2. C1 then begins to discharge through the resistor R4, and the voltage on the grid of V₂ rises until V₂ begins to conduct. The voltage on the plate of V₂ then decreases, causing V₁ to conduct less and less. At the same time, the plate voltage of V1 begins to rise, causing V2 to conduct still more heavily. Because of the amplification, this cumulative effect builds up extremely fast, and conduction switches from V₁ to V₂




Fig. 100—Basic multivibrator circuit of the free-running type.

within a few microseconds, depending on the circuit components.

In this circuit, therefore, conduction switches from V_1 to V_2 over the interval during which C_1 discharges from the voltage across R_4 to the cutoff voltage for V_2 . The actual transfer of conduction does not occur until cutoff is reached. Conduction switches back to V_1 through a similar process to complete the cycle. The plate waveform is essentially rectangular in shape, and

may be adjusted as to symmetry, frequency, and amplitude by proper choice of circuit constants, tubes, and voltages.

Although this type of multivibrator is free-running, it may be triggered by pulses of a given amplitude and frequency to provide a frequency-stabilized output. Multivibrator circuits may also be designed so that they are not free-running, but must be triggered externally to shift conduction from one tube to the other. Depending on the type of circuit, conduction may shift back to the first tube after a given time interval, or the second tube may continue conducting until another trigger signal is applied.

Synchroguide Circuits

The "synchroguide" is a controlled type of oscillator used in television receivers to generate and control the synchronized sawtooth voltage necessary for adequate line- or horizontal-frequency scanning. A simplified synchroguide circuit is shown in Fig. 101. This circuit provides stable, noise-free control of a blocking oscillator which generates a horizontal-frequency signal. It permits comparison of the received sync pulses and the generated sawtooth voltages so that properly locked-in horizontal scanning results.

The triode V_2 in Fig. 101 is a conventional blocking oscillator which enables a sawtooth voltage to be developed across the capacitor C_2 . A portion of this sawtooth is fed back to the grid of




Fig. 101-Simplified synchroguide circuit.

the control tube, V₁. The positive sync pulses are also applied to the grid of

V₁. The waveforms shown in Fig. 102 illustrate the sawtooth and sync pulses (A and B) and their proper "in-sync"




Fig. 102—Sawtooth and sync pulses in synchroguide circuit.

combination (C). The sync pulse occurs partly during the portion of the saw-tooth voltage in which the triode V_1 draws current. Any shift in sync pulse as it is superimposed on the sawtooth, therefore, will affect the amount of conduction of the control tube. A change in control-tube conduction ultimately affects the bias on the oscillator-tube grid by changing the voltage to which the capacitor C_1 in the cathode circuit may charge. An increase in the positive bias increases the frequency of oscillation.

For example, waveform D in Fig. 102 illustrates a condition in which the sawtooth voltage is advanced in phase with respect to the sync pulses. The widening of the pulse which occurs at the corner of the sawtooth waveform allows the control tube to conduct more current and, consequently, allows the capacitor C_1 to charge to a higher voltage. This increased reference voltage also appears in the grid circuit of V_2 and makes the grid more positive. The increased grid voltage then speeds up the frequency of oscillations until proper synchronization results.

The blocking oscillator can be made more immune to changes in frequency and noise if V_2 is brought out of cutoff very sharply. This effect is obtained by sine-wave stabilization. The tuned circuit L_2C_3 in the plate circuit of Fig. 101 superimposes a shock-excited sine wave on the plate and grid waveforms, as shown in Fig. 103.

Automatic Frequency Control

An automatic frequency control




Fig. 103—Waveforms showing effect of tuned circuit L_3C_3 in Fig. 101.

(afc) circuit provides a means of correcting automatically the intermediate frequency of a superheterodyne receiver when, for any reason, it drifts from the frequency to which the if stages are tuned. This correction is made by adjusting the frequency of the oscillator. Such a circuit will automatically compensate for slight changes in rf carrier or oscillator frequency as well as for inaccurate manual or push-button tuning.

An afc system requires two sections: a frequency detector and a variable reactance. The detector section may be essentially the same as the FM detector illustrated in Fig. 30 and discussed under **Detection**. In the afc system, however, the output is a dc control voltage, the magnitude of which is proportional to the amount of frequency shift. This dc control voltage is used to control the grid bias of an electron tube which comprises the variable reactance section (Fig. 104).




Fig. 104—Automatic-frequency-control (afc) circuit.

The plate current of the reactance tube is shunted across the oscillator tank circuit. Because the plate current and plate voltage of the reactance tube are almost 90 degrees out of phase, the control tube affects the tank circuit in the same manner as a reactance. The grid bias of the tube determines the magnitude of the effiective reactance and, consequently, a control of this grid bias can be used to control the oscillator frequency.

Automatic frequency control is also used in television receivers to keep the horizontal oscillator in step with the horizontal-scanning frequency (15,750 Hz) at the transmitter. A widely used horizontal afc circuit is shown in Fig. 105. This circuit, which is often referred balanced-phase-detector or to as a phase-discriminator circuit, is usually employed to control the frequency of a multivibrator-type horizontal-oscillator circuit. The 6AL5 detector supplies a dc control voltage to the grid of the horizontal-oscillator tube which counteracts changes in its operating frequency. The magnitude and polarity of the control voltages are determined by phase relationships in the afc circuit at a given moment.

The horizontal sync pulses obtained from the sync-separator circuit are fed through a single-triode phase-inverter or phase-splitter circuit to the two diode units of the 6AL5. Because of the action of the phase-inverter circuit, the signals applied to the two diode units are equal in amplitude but 180 degrees out of




Fig. 105—Balanced phase-detector or phase-discriminator circuit for horizontal afc.

phase. A reference sawtooth voltage obtained from the horizontal output circuit is also applied simultaneously to both units. Any change in the oscillator frequency alters the phase relationship between the reference sawtooth and the incoming horizontal sync pulses, causing one diode unit of the 6AL5 to conduct more heavily than the other, and thus producing a correction signal. The system remains balanced at all times, therefore, because momentary changes in oscillator frequency are instantaneously corrected by the action of the control voltage.

The diode units of the 6AL5 are biased so that conduction takes place only during the tips of the sync pulses. The relative position of the sync pulses on the retrace portion of the sawtooth waveform at any given instant determines which diode unit conducts more heavily, and thereby establishes the magnitude and polarity of the control voltage. The network between the diode units and the grid of the horizontal-oscillator tube is essentially a low-pass filter which prevents the horizontal-oscillator performance.

Frequency Conversion

Frequency conversion is used in superheterodyne receivers to change the frequency of the rf signal to an intermediate frequency. To perform this change in frequency, a frequency-converting device consisting of an oscillator and a frequency mixer is employed. In such a device, shown diagrammatically in Fig. 106, two voltages of different frequency, the rf signal voltage and the voltage generated by the oscillator, are applied to the input of the frequency mixer. These voltages beat, or heterodyne, within the mixer tube to produce a plate current having, in addition to




Fig. 106—Block diagram of simple frequency-converter circuit.

the frequencies of the input voltages, numerous sum and difference frequencies.

The output circuit of the mixer stage is provided with a tuned circuit which is adjusted to select only one beat frequency, i.e., the frequency equal to the difference between the signal frequency and the oscillator frequency. The selected output frequency is known as the intermediate frequency, or if. The output frequency of the mixer tube is kept constant for all values of signal frequency by tuning the oscillator to the proper frequency.

Important advantages gained in a receiver by the conversion of signal frequency to a fixed intermediate frequency are high selectivity with few tuning stages and a high, as well as stable, over-

all gain for the receiver.

Several methods of frequency conversion for superheterodyne receivers are of interest. These methods are alike in that they employ a frequency-mixer tube in which plate current is varied at a combination frequency of the signal frequency and the oscillator frequency. These variations in plate current produce across the tuned plate load a voltage of the desired intermediate frequency. The methods differ in the types of tubes employed and in the means of supply input voltages to the mixer tube.

A method widely used before the availability of tubes especially designed for frequency-conversion service, and currently used in many FM, television, and standard broadcast receivers, employs as mixer tube either a triode, a tetrode, or a pentode, in which oscillator voltage and signal voltage are applied to the same grid. In this method, coupling between the oscillator and mixer circuits is obtained by means of inductance or capacitance.

A second method employs a tube having an oscillator and frequency mixer combined in the same envelope. In one form of such a tube, coupling between the two units is obtained by means of the electron stream within the tube. Because five grids are used, the tube is called a pentagrid converter.

Grids No. 1 and No. 2 and the

cathode are connected to an external circuit to act as a triode oscillator. Grid No. 1 is the grid of the oscillator and grid No. 2 is the anode. Grid No. 2 is connected within the tube to the screen grid (grid No. 4). The combined two grids, Nos. 2 and 4, shield the signal grid (grid No. 3) and act as the composite anode of the oscillator triode. Grid No. 5 acts as the suppressor grid.

Converter tubes of this type are designed so that the space charge around the cathode is unaffected by electrons from the signal grid. Furthermore, the electrostatic field of the signal grid also has little effect on the space charge. The result is that rf voltage on the signal grid produces little effect on the cathode current. There is, therefore, little detuning of the oscillator by ave bias because changes in ave bias produce little change in oscillator transconductance or in the input capacitance of grid No. 1.

Examples of the pentagrid converters discussed in the preceding paragraph are the single-ended types 1R5 and 6BE6. A schematic diagram illustrating the use of the 6BE6 with self-excitation is given in Fig. 107. The 6BE6 may also be used with separate excitation. A complete circuit is shown in the Circuits section.




Fig. 107—Frequency-converter circuit using the 6BE6 pentagrid converter with self-excitation.

A further method of frequency conversion employs a tube called a pentagrid mixer. This type has two independent control grids and is used with a separate oscillator tube. RF signal voltage is applied to one of the control grids

and oscillator voltage is applied to the other. It follows, therefore, that the variations in plate current are due to the combination of the oscillator and signal frequencies.

The tube contains a heater-cathode, five grids, and a plate. Grids Nos. 1 and 3 are control grids. The rf signal voltage is applied to grid No. 1. This grid has a remote-cutoff characteristic and is suited for control by avc bias voltage. The oscillator voltage is applied to grid No. 3. This grid has a sharp-cutoff characteristic and produces a comparatively large effect on plate current for a small amount of oscillator voltage. Grids Nos. 2 and 4 are connected together within the tube. They accelerate the electron stream and shield grid No. 3 electrostatically from the other electrodes. Grid No. 5, connected within the tube to the cathode, functions similarly to the suppressor grid in a pentode.

In the converter or mixer stage of a television receiver, stable oscillator operation is most readily obtained when separate tubes or tube sections are used for the oscillator and mixer functions. A typical television mixer-oscillator circuit is shown in Fig. 108. In such circuits, the oscillator voltage is applied to the mixer grid by inductive coupling, capacitive coupling, or a combination of the two. Tubes containing electrically independent oscillator and mixer units in the same envelope, such as the 6EA8 and 6KE8 are designed especially for this application.




Fig. 108—Typical television mixer-oscillator circuit.

Tuning Indication With Electron-Ray Tubes

Electron-ray tubes are designed to indicate visually by means of a fluorescent target the effects of a change in controlling voltage. One application of them is as tuning indicators in radio receivers. Types such as the 6U5 and

the 6E5 contain two main parts: (1) a triode which operates as a dc amplifier and (2) an electron-ray indicator which is located in the bulb as shown in Fig. 109. The target is operated at a positive voltage and, therefore, attracts electrons from the cathode. When the electrons strike the target they produce a glow on the fluorescent coating of the target. Under these conditions, the target appears as a ring of light.

A ray-control electrode is mounted between the cathode and target. When the potential of this electrode is less positive than the target, electrons flowing to the target are repelled by the electrostatic field of the electrode, and do not reach that portion of the target behind the electrode. Because the target does not glow where it is shielded from electrons, the control electrode casts a




Fig. 109-Structure of electron-ray tube.

shadow on the glowing target. The extent of this shadow varies from approximately 100 degrees of the target when the control electrode is much more negative than the target to 0 degrees when the control electrode is at approximately the same potential as the target.

In the application of the electronray tube, the potential of the control electrode is determined by the voltage on the grid of the triode section, as can be seen in Fig. 110. The flow of the triode plate current through resistor R produces a voltage drop which determines the potential of the control electrode. When the voltage of the triode grid changes in the positive direction, plate current increases, the potential of the control electrode goes down because of the increased drop across R, and the shadow angle widens. When the potential of the triode grid changes in the negative direction, the shadow angle narrows.





Fig. 110—Indicating circuit using an electron-ray tube.

Another type of indicator tube is the 6AF6G. This tube contains only an indicator unit but employs two ray-control electrodes mounted on opposite sides of the cathode and connected to individual base pins. It employs an external de amplifier. (See Fig. 111.) two symmetrically opposite shadow angles may be obtained by connecting the two ray-control electrodes together; or, two unlike patterns may be obtained by individual connection of each ray-control electrode to its respective amplifier.

In radio receivers, ave voltage is applied to the grid of the de amplifier.



R: TYPICAL VALUE 15 0.5 MEGOHM

Fig. 111—Indicating circuit using 6AF6G electron-ray tube and external dc amplifier.

Because ave voltage is at maximum when the set is tuned to give maximum response to a station, the shadow angle is at minimum when the receiver is tuned to resonance with the desired station.

The choice between electron-ray tubes depends on the avc characteristic of the receiver. The 6E5 contains a sharp-cutoff triode which closes the shadow angle on a comparatively low value of avc voltage. The 6U5 has a remote-cutoff triode which closes the shadow on a larger value of avc voltage than the 6E5. The 6AF6G may be used in conjunction with dc amplifier tubes having either remote- or sharp-cutoff characteristics.

Electron Tube Installation

THE installation of electron tubes requires care if reliable performance is to be obtained from the associated circuits. Installation suggestions and precautions which are generally common to all types of tubes are covered in this section. Additional pertinent information is given under each tube type and in the Circuits section.

Filament and Heater Power Supply

The design of electron tubes allows for some variation in the voltage and current supplied to the filament or heater, but most satisfactory results are obtained from operation at the rated values. When the voltage is low, the temperature of the cathode is below normal, with the result that electron emission is limited. The limited emission may cause unsatisfactory operation and reduced tube life. On the other hand, high heater voltage may cause rapid evaporation of cathode material and shorten tube life.

To insure proper tube operation, it is important that the filament or heater voltage be checked at the socket terminals by means of a high-resistance voltmeter while the equipment is in operation. In the case of series operation of heaters or filaments, correct adjustment can be checked by means of an ammeter in the heater or filament circuit.

The filament or heater voltage supply may be a direct-current source (a battery or a dc power line) or an alternating-current power line, depending on the type of service and type of tube. Ordinarily, a step-down transformer is used with an ac supply to provide the proper filament or heater voltage. Receivers intended for operation on both dc and ac power lines have the heaters connected in series with a suitable resistor and supplied directly from the power line.

Mobile and marine receivers have the heaters of the tubes connected directly across the battery supply.

Parallel heater operation usually requires a step-down transformer to reduce the 120 Vac line voltage to typically 6.3 Vac. Care must be taken to prevent excessive voltage drop in the heater circuit wiring which would result in incorrect voltage at the tube terminals.

Series heater operation eliminates the need for a step-down transformer and is economical when a number of tubes rated at the same heater current have a total heater voltage drop which adds up to an available supply voltage. A voltage-dropping resistor in series with the heaters and the supply line is usually required. This resistance should be of such value that for normal line voltage the tubes will operate at their rated heater current. The resistor value is calculated by the following formula.

Required resistance (ohms) = supply volts — total rated volts of tubes rated amperes of tubes

The power dissipation of the resistor (in watts) is equal to the voltage drop of the resistor multiplied by the series string current in amperes. A resistor having a wattage rating well

in excess of this value should be chosen.

A convenient means exists for obtaining a heater supply voltage drop without the disadvantage of a power-dissipating resistor. A diode in series with the 120 Vac line provides a half wave rectified sine wave of 84 V $(\sqrt{\frac{2}{2}})$ x RMS input). The diode po-

larity should be such as to operate the heaters negative. (See heater-cathode voltage below.) In TV receivers designed for instant-on operation such a series-connected diode can be used for stand-by operation (70% of rated heater voltage) of a 120 Vac series string.

Heater-Cathode Voltage

When the series-heater connection is used in equipment, it is advisable to arrange the heaters in the circuit so that tubes most sensitive to hum disturbances are at or near ground potential of the circuit. This arrangement reduces the amount of AC heatercathode voltage of these tubes and minimizes hum interference. tubes operated with grounded cathode, such as horizontal deflection amplifiers or tube insulated for high heater cathode voltage, such as damper, are more immune to heater-cathode leakage.

Typical orders of series-string connections, by tube function, are shown below.

Heater-type tubes may produce

hum as a result of conduction between heater and cathode or between heater and control grid, or by modulation of the electron stream by the alternating magnetic field surrounding the heater. When a large resistor is used between heater and cathode (as in series-connected heater strings), or when one side of the heater is grounded, even a minute pulsating leakage current between heater and cathode can develop a small voltage across the cathode-circuit impedance and cause objectionable hum. The use of a large cathode bypass capacitor is recommended to minimize this source of hum.

Much lower hum levels can be achieved when heaters are connected in parallel systems in which the center-tap of the heater supply is grounded or, preferably, connected to a positive bias source of 15 to 80 volts dc to reduce the flow of alternating current. The heater leads of the tubes should be twisted and kept away from high-impedance circuits. The balanced ac supply provides almost complete cancellation of the alternating-current components.

The balanced arrangement described above also minimizes heater-grid hum. High grid-circuit impedances should be avoided, if possible. High heater voltages should also be avoided because heater-cathode hum rises sharply when the heater voltage is increased above the published value.

Certain tube types are designed especially to minimize hum in high-quality, high-fidelity audio equipment. Examples are the 5879, 7025, and 7199.




Fig. 112A—Order of series heater-string connection, by tube function, to minimize hum in a radio receiver.




Fig. 112B—Order of series heater-string connection, by tube function, to minimize hum in a TV receiver.

Plate Voltage Supply

The plate voltage for electron tubes is obtained from batteries, rectifiers, direct-current power lines, and small local generators. The maximum plate-voltage value for any tube type should not be exceeded if most satisfactory performance is to be obtained. Plate voltage should not be applied to a tube unless the corresponding recommended voltage is also supplied to the grid.

It is recommended that the primary circuit of the power transformer be fused to protect the rectifier tube(s), the power transformer, filter capacitor, and chokes in case a rectifier tube fails.

Grid Voltage Supply

The recommended grid voltages for different operating conditions have been carefully determined to give the most satisfactory performance. Grid voltage may be obtained from a fixed source such as a separate C-battery or a tap on the voltage divider of the high-voltage de supply, from the voltage drop across a resistor in the cathode circuit, or from the voltage drop across a resistor in the grid circuit. The first method is called "fixed bias"; the second is called "cathode bias" or "self bias"; the third is called "grid-resistor bias" and is sometimes incorrectly referred to in receiving-tube practice as "zero-bias operation."

In any case, the object is to make the grid negative with respect to the cathode by the specified voltage. When a C-battery is used, the negative terminal is connected to the grid return and the positive terminal is connected to the negative filament socket terminal, or to the cathode terminal if the tube is of the heater-cathode type. If the filament is supplied with alternating current, this connection is usually made to the center-tap of a low resistance (20 to 50 ohms) shunted across the filament terminals. This method reduces hum disturbances caused by the ac supply. If bias voltages are obtained from the voltage divider of a high-voltage dc supply, the grid return is connected to a more negative tap than the cathode.

The cathode-biasing method utilizes the voltage drop produced by the cathode current flowing through a resistor connected between the cathode and the negative terminal of the B-supply. (See Fig. 113.) The cathode current is, of course, equal to the plate current in the case of a triode, or to the sum of the plate and grid-No. 2 currents in the case of a tetrode, pentode, or beam power tube. Because the voltage drop along the resistance is increasingly negative with respect to the cathode, the required negative grid-bias voltage can be obtained by connecting the grid return to the negative end of the resistance.




Fig. 113—Typical grid-voltage supply circuits.

The value of the resistance tor cathode-biasing a single tube can be determined from the following formula:

Resistance (ohms) = desired grid-bias voltage × 1000
rated cathode current in milliamperes

Thus, the resistance required to produce 9 volts bias for a triode which operates at 3 milliamperes plate current is $9 \times 1000/3 = 3000$ ohms. If the cathode current of more than one tube passes through the resistor, or if the tube or tubes employ more than three electrodes, the total current determines the size of the resistor.

Bypassing of the cathode-bias resistor depends on circuit-design requirements. In rf circuits the cathode resistor usually is bypassed. In af circuits the use of an unbypassed resistor will reduce distortion by introducing degeneration into the circuit. However, the use of an unbypassed resistor decreases gain and power sensitivity. When bypassing is used, it is important that the bypass capacitor be sufficiently large to have negligible reactance at the lowest frequency to be amplified.

In the case of power-output tubes having high transconductance, such as beam power tubes, it may be necessary to shunt the bias resistor with a small mica capacitor (approximately 0.001 pF) in order to prevent oscillations. The usual af bypass may or may not be used, depending on whether or not degeneration is desired. In tubes having high values of transconductance, such as the 6BA6, 6CB6A, and 6AC7, input capacitance and input conductance change appreciably with plate current.

When such a tube having a separate suppressor-grid connection is used as an rf amplifier, these changes may be minimized by leaving a certain portion of the cathode-bias resistor unbypassed. In order to minimize feedback when this method is used, the external grid-No. 1-to-plate (wiring) capacitances should be kept to a minimum, the grid No. 2 should be bypassed to ac ground, and the grid No. 3 should be connected to ac ground.

The use of a cathode resistor to obtain bias voltage is not recommended for amplifiers in which there is appreciable shift of electrode currents with the application of a signal. In such amplifiers, a separate fixed supply is recommended.

The grid-resistor biasing method is also a self-bias method because it utilizes the voltage drop across the grid resistor produced by small amounts of grid current flowing in the grid-cathode circuit. This current is due to (1) an electromotive potential difference between the materials comprising the grid and cathode and (2) grid rectification when the grid is driven positive. A large value of resistance is required in order to limit this current to a very small value and to avoid undesirable loading effects on the preceding stage.

Examples of this method of bias are given in the Circuits section. In these circuits, the audio amplifier type 1U5 or 12AV6 has a 10-megohm resistor between the grid and the negative filament or cathode to furnish the required bias, which is usually less than 1 volt.

This method of biasing is used principally in the early voltage-amplifier stages (usually employing high-mu triodes) of audio amplifier circuits, where the tube dissipation will not be excessive under zero-signal conditions.

A grid resistor is also used in many oscillator circuits for obtaining the required bias. In these circuits, the grid voltage is relatively constant and its magnitude is usually in the order of 5 volts or more. Consequently, the bias voltage is obtained only through grid rectification. A relatively low value of resistor, 0.1 megohm or less, is used. Oscillator circuits employing this method of bias are given in the Circuits section.

Grid-bias variation for the rf and if amplifier stages is a convenient and frequently used method for controlling receiver volume. The variable voltage supplied to the grid may be obtained: (1) from a variable cathode resistor as shown in Figs. 114 and 115; (2) from a bleeder circuit by means of a potentiometer as shown in Fig. 116; or (3) from a bleeder circuit in which the bleeder current is varied by a tube




Fig. 114—Amplifier stage using a variable cathode-bias resistor for volume control.

used for automatic volume control. The latter circuit is shown in Fig 61.

In all cases it is important that the control be arranged so that at no time will the bias be less than the recommended minimum grid-bias voltage for the particular tubes used. This requirement can be met by providing a fixed stop on the potentiometer, by connecting a fixed resistance in series with the variable resistance, or by connecting a fixed cathode resistance in series with the variable resistance used for regulation. Where receiver gain is




Fig. 115—Amplifier stage similar to Fig. 114 but using heater-cathode-type tube.

controlled by grid-bias variation, it is advisable to have the control voltages extend over a wide range in order to minimize cross-modulation and modulation-distortion. A remote-cutoff type of tube should, therefore, be used in the controlled stages.




Fig. 116—Amplifier stage using a bleeder circuit and potentiometer for volume control.

In most tubes employing a unipotential cathode, a positive grid current begins to flow when the grid is slightly negative and increases rapidly as the grid is made more positive, as shown in Fig. 117. The value of grid voltage at which the grid-current curve intercepts the horizontal axis is determined by several different physical processes, including an electrothermal effect due to the differences in temperature and in material composition of the grid and the cathode, and by the positive grid current. For values of grid potentials which are larger than this intercept, the direction of the grid current is positive (i.e., from the cathode to the grid). At smaller values of grid potential, the direction of the grid current

is negative (i.e., from the grid to the cathode).

Positive grid current consists of electrons emitted from the cathode which are intercepted by the control grid. Negative grid current, which becomes appreciable only when the grid potential is more negative than the value of the intercept, is a result of the emission of electrons from the heated control grid to the cathode, the effect of gas molecules in the tube, and the influence of leakage currents between the grid and cathode and the grid and the plate.

The value of grid potential at the intercept of the grid-current curve on the horizontal axis (often mistakenly called contact potential) may be as high as 1½ volts. If the operating bias of the tube is less than this intercept, it is found that two effects are present. Direct current flows in the grid circuit. and the dynamic input resistance of the tube may be relatively low. It is generally desirable to supply the tube with a value of bias sufficiently high so that the operating point of the tube is not near the value of this intercept. If the value of the operating bias is near the value of the intercept, care should be taken to avoid undesirable effects in the grid circuit due to grid current or low input resistance.




Fig. 117—Curves showing flow of positive grid current in tubes employing unipotential cathodes.

Screen-Grid Voltage Supply

The positive voltage for the screen grid (grid No. 2) of screen-grid tubes may be obtained from a tap on a voltage divider, from a potentiometer, or from a series resistor connected to a high-voltage source, depending on the particular tube type and its application. The screen-grid voltage for tetrodes should be obtained from a voltage divider or a potentiometer rather than through a series resistor from a highvoltage source because of the characteristic screen-grid current variations of tetrodes. Fig. 118 shows a tetrode with its screen-grid voltage obtained from a potentiometer.

When pentodes or beam power tubes are operated under conditions where a large shift of plate and screengrid currents does not take place with the application of the signal, the screengrid voltage may be obtained through a series resistor from a high-voltage




Fig. 118—Tetrode circuit in which screengrid voltage is obtained from a potentiometer.

source. This method of supply is possible because of the high uniformity of the screen-grid current characteristic in pentodes and beam power tubes. Because the screen-grid voltage rises with increase in bias and resulting decrease in screen-grid current, the cutoff characteristic of a pentode is extended by this method of supply.

This method is sometimes used to increase the range of signals which can be handled by a pentode. When used in resistance-coupled amplifier circuits employing pentodes in combination

with the cathode-biasing method, it minimizes the need for circuit adjustments. Fig. 119 shows a pentode with its screen-grid voltage supplied through a series resistor.

When power pentodes and beam power tubes are operated under conditions such that there is a large change in plate and screen-grid currents with the application of signal, the series-resistor method of obtaining screen-grid voltage should not be used. A change in screen-grid current appears as a




Fig. 119—Pentode circuit in which screengrid voltage is supplied through à series resistor.

change in the voltage drop across the series resistor in the screen-grid circuit; the result is a change in the power output and an increase in distortion. The screen-grid voltage should be obtained from a point in the plate-voltage-supply filter system having the correct voltage, or from a separate source.

It is important to note that the plate voltage of tetrodes, pentodes, and beam power tubes should be applied before or simultaneously with the screen-grid voltage. Otherwise, with voltage on the screen grid only, the screen-grid current may rise high enough to cause excessive screen-grid dissipation.

Screen-grid voltage variation for the rf amplifier stages has sometimes been used for volume control in older-type receivers. Reduced screen-grid voltage decreases the transconductance of the tube and results in reduced gain per stage. The voltage variation is obtained by means of a potentiometer shunted across the screen-grid voltage supply. (See Fig. 118.) When the screen-grid voltage is varied, it must never

exceed the rating of the tube. This requirement can be met by providing a fixed stop on the potentiometer.

Shielding

In high-frequency stages having high gain, the output circuit of each stage must be shielded from the input circuit of that stage. Each high-frequency stage also must be shielded from the other high-frequency stages. Unless shielding is employed, undesired feedback may occur and may produce many harmful effects on receiver performance.

To prevent this feedback, it is a desirable practice to shield separately each unit of the high-frequency stages. For instance, in a superheterodyne receiver, each if and rf coil may be mounted in a separate shield can. Baffle plates may be mounted on the ganged tuning capacitor to shield each section of the capacitor from the other section. The oscillator coil may be especially well shielded by being mounted under the chassis.

The shielding precautions required in a receiver depend on the design of the receiver and the layout of the parts. In all receivers having high-gain highfrequency stages, it is necessary to shield separately each tube in high-frequency stages. When metal tubes, and in particular the single-ended types, are used, complete shielding of each tube is provided by the metal shell which is grounded through its grounding pin at the socket terminal. The grounding connection should be short and sturdy. Many modern tubes of glass construction have internal shields, usually connected to the cathode; where present, these shields are indicated in the socket diagram.

Dress of Circuit Leads

At high frequencies such as are encountered in FM and television receivers, lead dress, that is, the location and arrangement of the leads used for connections in the receiver, is very important. Because even a short lead provides a large impedance at high frequencies, it is necessary to keep all high-frequency leads as short as possible. This precaution is especially important for ground connections and for all connections to bypass capacitors and high-frequency filter capacitors. The ground connections of plate and screen-grid bypass capacitors of each tube should be kept short and made directly to cathode ground.

Particular care should be taken with the lead dress of the input and output circuits of high-frequency stages so that the possibility of stray coupling is minimized. Unshielded leads connected to shielded components should be dressed close to the chassis. As the frequency increases, the need for careful lead dress becomes increasingly important.

In high-gain audio amplifiers, these same precautions should be taken to minimize the possibility of self-oscillation.

Filters

Feedback effects also are caused in radio or television receivers by coupling between stages through common voltage-supply circuits. Filters find an important use in minimizing such effects. They should be placed in voltage-supply leads to each tube in order to return the signal current through a low-impedance path direct to the tube cathode rather than by way of the voltagesupply circuit. Fig. 120 illustrates several forms of filter circuits. Capacitor C forms the low-impedance path, while the choke or resistor assists in diverting the signal through the capacitor by offering a high impedance to the powersupply circuit.

The choice between a resistor and a choke depends chiefly upon the permissible dc voltage drop through the filter. In circuits where the current is small (a few milliamperes), resistors are practical; where the current is large or




Fig. 120—Typical filter circuits.

regulation important, chokes are more suitable.

The minimum practical size of the capacitors may be estimated in most cases by the following rule: The impedance of the capacitor at the lowest frequency amplified should not be more than one-fifth of the impedance of the filter choke or resistor at that frequency. Better results will be obtained in special cases if the ratio is not more than one-tenth.

Radio-frequency circuits, particularly at high frequencies, require highquality capacitors. Mica or ceramic capacitors are preferable. Where stage shields are employed, filters should be placed within the shield.

Another important application of filters is to smooth the output of a rectifier tube. (See Rectification.) A smoothing filter usually consists of capacitors and iron-core chokes. In any filter-design problem, the load impedance must be considered as an integral part of the filter because the load is an important factor in filter performance. Smoothing effect is obtained from the chokes because they are in series with the load and offer a high impedance to the ripple voltage. Smoothing effect is obtained from the capacitors because they are in parallel with the load and store energy on the voltage peaks; this energy is released on the voltage dips and serves to maintain the voltage at the load substantially

constant. Smoothing filters are classified as choke-input or capacitor-input according to whether a choke or capacitor is placed next to the rectifier tube. (See Fig. 121.)

plate and transformer winding and to connect high-voltage, rf bypass capacitors between the outside ends of the transformer winding and the center tap. (See Fig. 122.) The rf chokes should




Fig. 121—Typical smoothing filters for rectifier tubes.


The **Circuits** section gives a number of examples of rectifier circuits with recommended filter constants.

If an input capacitor is used, consideration must be given to the instantaneous peak value of the ac input voltage. This peak value is about 1.4 times the rms value as measured by an ac voltmeter. Filter capacitors, therefore, especially the input capacitor, should have a rating high enough to withstand the instantaneous peak value if breakdown is to be avoided. When the inputchoke method is used, the available dc output voltage will be somewhat lower than with the input-capacitor method for a given ac plate voltage. However, improved regulation together with lower peak current will be obtained.

Mercury-vapor and gas-filled rectifier tubes occasionally produce a form of local interference in radio receivers through direct radiation or through the power line. This interference is generally identified in the receiver as a tunable broadly 120-Hz buzz (100 Hz for 50-Hz supply line. etc.). It is usually caused by the formation of a steep wave front when plate current within the tube begins to flow on the positive half of each cycle of the ac supply voltage.

There are several ways of eliminating this type of interference. One is to shield the tube. Another is to insert an rf choke having an inductance of one millihenry or more between each

be placed within the shielding of the tube. The rf bypass capacitors should have a voltage rating high enough to withstand the peak voltage of each half of the secondary, which is approximately 1.4 times the rms value.



C=RF BYPASS CAPACITOR,MICA L=RF CHOKE
Fig. 122—Filter circuit used to eliminate
interference produced by mercury-vapor or
gas-filled rectifier tubes.

Transformers having electrostatic shielding between primary and secondary are not likely to transmit rf disturbances to the line. Often the interference may be eliminated simply by making the plate leads of the rectifier extremely short. In general, the particular method of interference elimination must be selected by experiment for each installation.

Output Coupling Devices

An output-coupling device is used in the plate circuit of a power output tube to keep the comparatively high dc plate current from the winding of an electromagnetic speaker and, also, to transfer power efficiently from the output stage to a loudspeaker of either the electromagnetic or dynamic type.

Output-coupling devices are of two types, (1) choke-capacitor and (2) transformer. The choke-capacitor type includes an iron-core choke having an inductance of not less than 10 henries which is placed in series with the plate and B-supply. The choke offers a very low resistance to the dc plate current component of the signal voltage but opposes the flow of the fluctuating component. A bypass capacitor of 2 to 6 microfarads supplies a path to the speaker winding for the signal voltage. The choke-coil output coupling device, however, is now only of historical interest.

The transformer type is constructed with two separate windings, a primary and a secondary wound on an iron core. This construction permits designing each winding to meet the requirements of its position in the circuit. Typical arrangements of each type of coupling device are shown in Fig. 123. Examples of transformers for push-pull stages are shown in several of the circuits given in the **Circuits** section.




Fig. 123-Typical output-coupling devices.

High-Fidelity Systems

The results achieved from any high-fidelity amplifier system depend to a large degree upon the skill and care with which the system is constructed. Improper placement of transformers other components, and wiring, and attempts to achieve excessive compact-

ness, can only result in instability, oscillation, hum, and other operating difficulties, as well as in damage to components by overheating. It is important, therefore, that construction of high-fidelity amplifier systems be undertaken only by persons who have had some experience in the layout, mechanical construction, and wiring of audio equipment.

It is impractical to give specific construction data for various amplifiers and supplementary units because the best arrangement for each unit or combination of units will depend on the requirements of the user. It is possible, however, to list some general considerations which should be observed in the construction of any high-fidelity amplifier system.

Any amplifier having two or more stages should be constructed with a straight-line layout so that maximum separation is provided between the signal input and output circuits and terminals. Power-supply connections, particularly those carrying ac, should be isolated as far as possible from signal connections, especially from the input connection. Signal-carrying conductors, even when shielded, should not be cabled together with power-supply conductors. Internal wiring for ac-operated tube heaters, switches, pilot-light sockets, and other devices, should be twisted and placed flat against the chassis. All connections to the ground side of the circuit in each unit should be made to a common bus of heavy wire. This bus should be connected to the chassis only at the point of minimum signal voltage, i.e., at the signal-input terminal of the unit.

All internal wiring that carries signal voltages should be as short as possible, and as far as possible above the chassis, to minimize losses at the higher audio frequencies due to stray shunt capacitance. All connections between units should be made with shielded cable having a capacitance of not more than 30 picofarads per foot, such as Alpha Type 1249 or 1704, Belden Type 8401 or 8410, or equivalent cable.

Because power amplifiers and power-supply units of high-fidelity systems normally dissipate large amounts of heat, they should be constructed and installed in such a manner as to assure adequate ventilation for the tubes and other components. A beam power tube or rectifier tube should be separated from any other tube or component on the same side of the chassis by at least 1½ tube diameters.

Power amplifiers and power-supply units which are to be installed horizontally (i.e., with the tubes vertical) in cabinets or on shelves should be provided with mounting feet, perforated bottom covers, and a number of small holes around each tube socket to permit relatively cool air to enter from below and provide ventilation for the under side of the chassis and tubes.

If a power amplifier, tone-control amplifier, and one or more preamplifiers are to be constructed on the same chassis, the mechanical layout should be planned so that the circuits operating at the lowest signal levels are farthest from the output stage and power supply. Amplifier units which normally operate at comparable signal levels but are not used simultaneously (such as preamplifiers for tape pickup heads and magnetic phonograph pickups) may be installed side by side on the same chassis without danger of interaction. Units which operate simultaneously, however (such as the channels of a stereophonic system), should not be installed side by side on the same chassis without careful consideration to placement of components and wiring, and the possible use of shielding to prevent interaction.

When an amplifier, preamplifier, mixer, or other unit requiring heater power is located more than five or six feet from its power-supply unit, the heater-current conductors in the power-supply cable must be large enough to assure that each tube receives its rated heater voltage. In cases where very large heater currents or very long power-supply cables are involved, it may be desirable to install a heater-

supply transformer on or near the amplifier unit. If such a transformer is installed on or near a preamplifier for a magnetic-tape pickup head, a magnetic phonograph pickup, or a dynamic microphone, the transformer should be completely shielded and positioned to prevent its field from inducing hum in the pickup device.

Considerations for Television Picture Tubes

Like other high-voltage devices, television picture tubes require that certain precautions be observed to minimize the possibility of failure caused by humidity, dust, and corona.

Humidity Considerations. humidity is high, a continuous film of moisture may form on the glass bulb immediately surrounding the anode cavity cap of all-glass picture tubes or on the glass part of the envelope of metal picture tubes. This film may permit sparking to take place over the glass surface to the external conductive coating or to the metal shell. Such sparking may introduce noise into the receiver. To prevent such a possibility, the uncoated bulb surface around the cap and the glass part of the envelope of metal picture tubes should be kept clean and dry.

Dust Considerations. The accumulation of dust on the uncoated area of the bulb around the anode cap of allglass picture tubes or on the glass part of the envelope or insulating supports for metal picture tubes will decrease the insulating qualities of these parts. The dust usually consists of fibrous materials and may contain soluble salts. The fibers absorb and retain moisture; the soluble salts provide electrical leakage paths that increase in conductivity as the humidity increases. The resulting high leakage currents may overload the high-voltage power supply.

It is recommended, therefore, that the uncoated bulb surface of all-glass picture tubes and the coated glass surface and insulating supports for metal picture tubes be kept clean and free from dust or other contamination such as finger-prints. The frosted Filterglass faceplate of the metal picture tubes may be cleaned with a soapless detergent, such as Dreft, then rinsed with clean water, and immediately dried.

Corona Considerations. A highvoltage system may be subject to corona, especially when the humidity is
high, unless suitable precautions are
taken. Corona, which is an electrical
discharge appearing on the surface of
a conductor when the voltage gradient
exceeds the breakdown value of air,
causes deterioration of organic insulating materials through formation of
ozone, and induces arc-over at points
and sharp edges. Sharp points or other
irregularities on any part of the high-

voltage system may increase the possibility of corona and should be avoided.

In the metal-shell picture tubes, the metal lip at the maximum diameter has rounded edges to prevent corona. Adequate spacing between the lip and any grounded element in the receiver. or between the small end of the metal shell and any grounded element, should be provided to preclude the possibility of corona. Such spacing should not be less than 1 inch of air. Similarly, an air space of 1 inch, or equivalent, should be provided around the body of the metal shell. As a further precaution to prevent corona, the deflecting-voke surface on the end adjacent to the shell should present a smooth electrical surface with respect to the small end of the metal shell or the anode terminal of all-glass tubes.

Safety Precautions

Shock Hazard and High Voltage Warning-Receiving Tubes

Most electron tubes present a shock hazard in use because of the voltages at which they operate. This hazard applies to all applications and is not restricted to high-voltage circuits. Thereprecautions should taken be when servicing equipment in which electron tubes are used.

Some electron tubes, such as highvoltage rectifiers and those used in the high-voltage regulators of television receivers, operate with very high electrode voltages. Extreme care should be taken during testing or adjustment of circuits in which such tubes are employed. Precautions must be exercised during the replacement or servicing of these tubes in equipment to assure that the high voltage output terminal is properly grounded when the tube is being removed from or inserted into its socket or when the top cap connector is being disconnected or connected. The tube and its associated apparatus, especially all parts which may be at high-potential with respect to ground, should be housed in a protective enclosure. The protective housing should be designed with interlocks so that personnel cannot possibly come in contact with any high-potential point in the electrical system.

It should be noted that high voltages may appear at normally lowpotential points in the circuit as a result of capacitor breakdown or incorrect circuit connections. Therefore, before any part of the circuit is touched, the power supply switch should be turned off and both terminals of any capacitor should be grounded.

X-Radiation Warning-Receiving Tubes

Electron tubes that are operated at potentials exceeding several thousand volts may emit X-radiation. The X-radiation is generated when electrons (or ions) which are accelerated to high velocities impact with high energy on various parts of the tube's structure. Tube types which specify an X-radiation characteristic in their published data are designed and controlled for this characteristic.

X-Radiation is measured in accordance with JEDEC Publication No. 67A, "Recommended Practice for urement of X-Radiation from Receiving Tubes", and controlled in accordance with JEDEC Publication No. "Recommended Practice for Quality Control of X-Radiation from High Voltage Rectifier and Shunt Regulator Receiving Tubes". These publications are available from the Electronic Industries Association, 2001 N.W., Washington, D.C. 20006.

Operation of these devices above the maximum values indicated in their Maximum Ratings may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

The high voltages associated with these devices result in production of X-radiation which may constitute a health hazard on prolonged exposure at close range unless the tube is adequately shielded. Equipment must provide for this shielding.

Precautions must be exercised during the servicing of equipment employing these devices to assure that the high voltage is adjusted to the recommended value and that any shielding components are replaced to their intended positions before the equipment is operated.

Shock Hazard Warning— Picture Tubes

The high voltage at which picture tubes are operated may be very dangerous. Design of the TV receiver should include safeguards to prevent the user from coming in contact with the high voltage. Extreme care should be taken in the servicing or adjustment of any high-voltage circuit.

Caution must be exercised during the replacement or servicing of the picture tube since a residual electrical charge may be contained on the high voltage capacitor formed by the external and internal conductive coatings of the picture tube funnel. To remove any undesirable residual high voltage charges from the picture tube. "bleed off" the charge by shorting the anode contact button, located in the funnel of the picture tube, to the external conductive coating before handling the tube. Discharging the high voltage to isolated metal parts such as cabinets and control brackets may produce a shock hazard.

Tube Handling Precaution— Picture Tubes

Picture tubes should be kept in the shipping box or similar protective container until just prior to installation. Wear heavy protective clothing, including gloves and safety goggles with side shields, in areas containing unpacked and unprotected tubes to prevent possible injury from flying glass in the event a tube breaks. Handle the picture tube with extreme care. Do not strike, scratch, or subject the tube to

more than moderate pressure. On types having an integral safety panel, particular care should be taken to prevent damage to the seal area and the edge of the integral safety panel.

Implosion Protection— Picture Tubes

Picture tubes which employ integral implosion protection must be replaced with a tube of the same type number or an RCA recommended replacement to assure continued safety.

X-Radiation Warning— Picture Tubes

High-voltage electron tubes that operate at potentials exceeding several thousand volts may emit X-radiation. Operation of a television picture tube at abnormal conditions may produce X-radiation in excess of design limits.

X-Radiation is measured in accordance with JEDEC Publication No. 64C, "Recommended Practice for Measurement of X-Radiation from Direct-View Television Picture Tubes." This publication is available from the Electronics Industries Association, 2001 Eye St., N.W., Washington, D. C. 20006.

For radiation safety when servicing a television receiver, it is essential to adjust the high voltage, using an accurate and reliable high-voltage meter, to the value specified by the set manufacturer following his recommended procedure. It is also essential that all external shields are properly replaced. In servicing a television receiver that requires a replacement picture tube, a tube with the same type number or an RCA recommended replacement tube type should be used to assure the same or improved integral X-radiation shielding.

Interpretation of Tube Data

THE tube data given in the followratings, typical operation values, characteristics, and characteristic curves.

The values for grid-bias voltages, other electrode voltages, and electrode supply voltages are given with reference to a specified datum point as follows: For types having filaments heated with dc, the negative filament terminal is taken as the datum point to which other electrode voltages are referred. For types having filaments heated with ac, the mid-point (i.e., the center tap on the filament-transformer secondary, or the mid-point on a resistor shunting the filament) is taken as the datum point. For types having unipotential cathodes indirectly heated, the cathode is taken as the datum point.

Ratings are established on electron tube types to help equipment designers utilize the performance and service capabilities of each tube type to best advantage. Ratings are given for those characteristics which careful study and experience indicate must be kept within certain limits to insure satisfactory performance.

Three rating systems are in use by the electron-tube industry. The oldest is known as the Absolute Maximum system, the next as the Design Center system, and the latest and newest as the Design Maximum system. Definitions of these systems have been formulated by the Joint Electron Device Engineering Council (JEDEC) and standardized by the National Electrical Manufacturers Association (NEMA) and the Electronic Industries Association (EIA) as follows:

Absolute Maximum ratings are limiting values which should not be exceeded with any tube of the specified type under any condition of operation. These ratings are not used too often for receiving types, but are generally used for transmitting and industrial types.

Design Center ratings are limiting values which should not be exceeded with a tube of the specified type having characteristics equal to the published values under normal operating conditions. These ratings, which include allowances for normal variations in both tube characteristics and operating conditions, were used for most receiving tubes prior to 1957.

Design Maximum ratings are limiting values which should not be exceeded with a tube of the specified type having characteristics equal to the published values under any conditions of operation. These ratings include allowances for normal variations in tube characteristics, but do not provide for variations in operating conditions. Design Maximum ratings were adopted for receiving tubes in 1957.

Electrode voltage and current ratings are in general self-explanatory, but a brief explanation of other ratings will aid in the understanding and interpretation of tube data.

Heater warm-up time is defined as the time required for the voltage across the heater to reach 80 per cent of the rated value in the circuit shown in Fig. 124. The heater is placed in series with a resistance having a value 3 times the nominal heater operating resistance $(R = 3 E_t/I_t)$, and a voltage having a value 4 times the rated heater voltage $(V = 4 E_t)$ is then applied. The warmup time is determined when $E = 0.8 E_t$.




Fig. 124—Test circuit for measuring heater warm-up time.

Plate dissipation is the power dissipated in the form of heat by the plate as a result of electron bombardment It is the difference between the power supplied to the plate of the tube and the power delivered by the tube to the load.

Peak heater-cathode voltage is the highest instantaneous value of voltage that a tube can safely stand between its heater and cathode. This rating is applied to tubes having a separate cathode terminal and used in applications where excessive voltage may be introduced between heater and cathode.

Maximum dc output current is the highest average plate current which can be handled continuously by a rectifier tube. Its value for any rectifier tube type is based on the permissible plate dissipation of that type. Under operating conditions involving a rapidly repeating duty cycle (steady load), the average plate current may be measured with a dc meter.

The nomograph shown in Fig. 125 can be used to determine tube voltage drop or plate current for any diode unit when values for a single plate-voltage, plate-current condition are available from the data. It can also be used to compare the relative perveance $(G = I_b/E_b^{3/2})$ of several diodes. **Perveance** can be considered a figure of merit for diodes; high-perveance units have

lower voltage drop at a fixed current level.

Tube voltage drop or plate current for a specific diode unit can be determined as follows: First, convenient values are selected for the plate-voltage and plate-current scales of the nomograph. The published plate-current and plate-voltage values are then located on the scales and connected with a straight edge. The intersection of the connecting line with the perveance scale is then used as a pivot point to determine the value of tube voltage drop corresponding to a desired current value, or the value of plate current corresponding to a desired tube voltage drop. Because the pivot point for a specific diode




Fig. 125—Diode perveance nomograph.

unit represents its perveance, the pivot points for several units (plotted to the same scales) can be used to compare their relative perveance.

For example, type 5U4GB has a tube voltage drop (per plate) of 44 volts at a plate current of 225 milliamperes. Convenient scales for this type are from 1 to 100 volts for plate voltage and from 10 to 1000 milliamperes for plate current. The points 44 volts and 225 milliamperes are then connected with a straight line to determine the pivot point. Using this pivot point, it is easy to determine such values as a plate current of 150 milliamperes at a tube voltage drop of 33 volts, or a voltage drop of 25 for a current of 100 milliamperes.

For readings in the order of one volt and/or one milliampere, the nomograph is not accurate because of the effects of contact potential and initial electron velocity.

Maximum peak plate current is the highest instantaneous plate current that a tube can safely carry recurrently in the direction of normal current flow. The safe value of this peak current in hot-cathode types of rectifier tubes is a function of the electron emission available and the duration of the pulsating current flow from the rectifier tube in each half-cycle.

The value of peak plate current in a given rectifier circuit is largely determined by filter constants. If a large choke is used at the filter input, the peak plate current is not much greater than the load current; but if a large capacitor is used as the filter input, the peak current may be many times the load current. In order to determine accurately the peak plate current in any rectifier circuit, measure it with a peak-indicating meter or use an oscillograph.

Maximum peak inverse plate voltage is the highest instantaneous plate voltage which the tube can withstand recurrently in the direction opposite to that in which it is designed to pass current. For mercury-vapor tubes and gasfilled tubes, it is the safe top value to prevent arc-back in the tube operating within the specified temperature range.

Referring to Fig. 126, when plate A of a full-wave rectifier tube is positive, current flows from A to C, but not from B to C, because B is negative. At the

instant plate A is positive, the filament is positive (at high voltage) with respect to plate B. The voltage between the positive filament and the negative plate B is in inverse relation to that causing current flow. The peak value of this voltage is limited by the resistance and nature of the path between plate B and filament. The maximum value of this voltage at which there is no danger of breakdown of the tube is known as maximum peak inverse voltage.




Fig. 126—Schematic diagram of full-wave rectifier tube and circuit connections.

The relations between peak inverse voltage, rms value of ac input voltage, and dc output voltage depend largely on the individual characteristics of the rectifier circuit and the power supply. The presence of line surges or any other transient, or wave-form distortion. may raise the actual peak voltage to a value higher than that calculated for sine-wave voltages. Therefore, the actual inverse voltage, and not the calculated value, should be such as not to exceed the rated maximum peak inverse voltage for the rectifier tube. A calibrated cathode-ray oscillograph or a peakindicating electronic voltmeter is useful in determining the actual peak inverse voltage.

In single-phase, full-wave circuits with sine-wave input and with no capacitor across the output, the peak inverse voltage on a rectifier tube is approximately 1.4 times the rms value of the plate voltage applied to the tube. In single-phase, half-wave circuits with sine-wave input and with capacitor input to the filter, the peak inverse voltage may be as high as 2.8 times the rms value of the applied plate voltage.

In polyphase circuits, mathematical determination of peak inverse voltage requires the use of vectors.

The Rating Chart for full-wave rectifiers presents graphically the relationships between maximum ac voltage input and maximum de output current derived from the fundamental ratings for conditions of capacitor-input and choke-input filters. This graphical presentation provides for considerable latitude in choice of operating conditions.

The Operation Characteristics for a full-wave rectifier with capacitor-input filter show by means of boundary line the limiting current and voltage relationships presented in the Rating Chart.

The Operation Characteristics for a full-wave rectifier with choke-input filter not only show by means of boundary line the limiting current and voltage relationships presented in the Rating Chart, but also give some information as to the effect on regulation of various sizes of chokes. The solid-line curves show the dc voltage outputs which would be obtained if the filter chokes had infinite inductance. The long-dash lines radiating from the zero position are boundary lines for various sizes of chokes as indicated. The intersection of one of these lines with a solid-line curve indicates the point on the curve at which the choke no longer behaves as though it had infinite inductance. To the left of the choke boundary line, the regulation curves depart from the solid-line curves as shown by the representative short-dash regulation curves.

Typical Operation Values. Values for typical operation are given for many types in the Technical Data section. These typical operating values are given to serve as guiding information for the use of each type. These values should not be confused with ratings, because a tube can be used under any suitable conditions within its maximum ratings, according to the application.

The power output value for any operating condition is an approximate

tube output—that is, plate input minus plate loss. Circuit losses must be subtracted from tube output in order to determine the useful output.

Characteristics are covered in the Electron Tube Characteristics section and such data should be interpreted in accordance with the definitions given in that section. Characteristic curves represent the characteristics of an average tube. Individual tubes, like any manufactured product, may have characteristics that range above or below the values given in the characteristic curves.

Although some curves are extended well beyond the maximum ratings of the tube, this extension has been made only for convenience in calculations. Do NOT operate a tube outside of its maximum ratings.

Interelectrode capacitances are direct capacitances measured between specified elements or groups of elements in electron tubes. Unless otherwise indicated in the data, all capacitances are measured with filament or heater cold, with no direct voltages present, and with no external shields. All electrodes other than those between which capacitance is being measured are grounded. In twin or multi-unit types, inactive units are also grounded.

The capacitance between the input electrode and all other electrodes, except the output electrode, connected together is commonly known as the input capacitance. The capacitance between the output electrode and all other electrodes, except the input electrode, connected together is known as the output capacitance.

Hum and noise characteristics of high-fidelity audio amplifier tube types such as the 7025 and the 7199 are tested in an amplifier circuit such as that shown in Fig. 127. The output of the test circuit is fed into a low-noise amplifier. The bandwidth of this amplifier depends on the characteristic being measured. If hum alone is being tested, a relatively narrow bandwidth is used to include both the line frequency and

the major harmonics generated by the tube under test. In noise or combination hum-and-noise measurements, the bandwidth is defined in the registration of the tube type.




Fig. 127—Test circuit for measuring hum and noise characteristics of high-fidelity audio-amplifier tubes.

The amplifier gain is calibrated so that the vacuum-tube voltmeter measures hum and noise in microvolts referenced to the grid of the tube under test. A pentode can also be evaluated in this manner by the addition of a screengrid supply adequately bypassed at the tube screen-grid pin connection. Powersupply ripple at the plate of the tube under test must be negligible compared to its hum and noise output. Extraordinary shielding of both the test socket and the associated operating circuit is required to minimize capacitances between heater leads and high-impedance connections.

The test-circuit components are determined by the tube type being tested and the type of hum to be controlled. Heater-cathode hum can be eliminated from the measurement by closing the switch S. The circuit can also be made more or less sensitive to heater-grid hum by increasing or decreasing the grid resistance $R_{\rm g}$. No circuit changes affect the component of magnetic hum generated by the tube.

Grid-No. 2 (Screen-grid) Input is the power applied to the grid-No. 2 electrode and consists essentially of the power dissipated in the form of heat by grid No. 2 as a result of electron bombardment. With tetrodes and pentodes, the power dissipated in the screengrid circuit is added to the power in the plate circuit to obtain the total B-supply input power.

When the screen-grid voltage is supplied through a series voltage-dropping resistor, the maximum screen-grid voltage rating may be exceeded, provided the maximum screen-grid dissipation rating is not exceeded at any signal condition, and the maximum screen-grid voltage rating is not exceeded at the maximum-signal condition. Provided these conditions are fulfilled, the screen-grid supply voltage may be as high as, but not above, the maximum plate voltage rating. The rating chart on page 300 shows the relationship between the maximum permissible input power to the screen grid and the screen-grid supply voltage.

Electron Tube Testing

THE electron-tube user-serviceman, experimenter, or non-technical radio listener-is interested in knowing the condition of his tubes, since they govern the performance of the device in which they are used. In order to determine the condition of a tube, some method of test is necessary. Because the operating capabilities and design features of a tube are indicated and described by its electrical characteristics, a tube is tested by measuring its characteristics and comparing them with values established as standard for that type. Tubes which read abnormally high with respect to the standard for the type are subject to criticism just the same as tubes which are too low.

Certain practical limitations are placed on the accuracy with which a tube test can be correlated with actual tube performance. These limitations make it impractical for the service man and dealer to employ complex and costly testing equipment having laboratory accuracy. Because the accuracy of the tube-testing device need be no greater than the accuracy of the correlation between test results and receiver performance, and since certain fundamental characteristics are virtually fixed by the manufacturing technique of leading tube manufacturers, it is possible to employ a relatively simple test in order to determine the serviceability of a tube.

In view of these factors, dealers and servicemen will find it economically expedient to obtain adequate accuracy and simplicity of operation by employing a device which indicates the status of a single characteristic. Whether the tube is satisfactory or unsatisfactory is judged from the test result of this single characteristic. Consequently, it is very desirable that the characteristic selected for the test be one which is truly representative of the tube's over-all condition.

The following information and cir-

cuits are given to describe and illustrate general theoretical and practical tubetester considerations and not to provide information on the construction of a home-made tube tester. In addition to the problem of determining what tube characteristic is most representative of performance capabilities in all types of receivers, the designer of a home-made tester faces the difficult problem of determining satisfactory limits for his particular tester. Getting information of this nature, if it is to be accurate and useful, is a big job. It requires the testing of many tubes of each type, testing of many types, and correlation of the data with performance in many kinds of equipment.

Short-Circuit Test

The fundamental circuit of a short-circuit tester is shown in Fig. 128. Although this circuit is suitable for tet-




Fig. 128—Fundamental circuit of a short circuit tester.

rodes and types having less than four electrodes, tubes of more electrodes may be tested by adding more indicator lamps to the circuit. Voltages are applied between the various electrodes with lamps in series with the electrode leads. The value of the voltages applied will depend on the type of tube being tested and its maximum ratings. Any two shorted electrodes complete a circuit and light one or more lamps. Since two electrodes may be just touching to give a high-resistance short, it is de-

sirable that the indicating lamps operate on very low current. It is also desirable to maintain the filament or heater of the tube at its operating temperature during the short-circuit test, because short-circuits in a tube may sometimes occur only when the electrodes are heated. However, a short-circuit tester having too high a sensitivity may indicate veryhigh-resistance shorts that do not adversely affect tube operation.

Selection of a Suitable Characteristic for Test

Some characteristics of a tube are far more important in determining its operating worth than are others. The cost of building a device to measure any one of the more important characteristics may be considerably higher than that of a device which measures a less representative characteristic. Consequently, three methods of test will be discussed, ranging from relatively simple and inexpensive equipment to more elaborate, more accurate, and more costly devices.

An emission test is perhaps the simplest method of indicating a tube's condition. (Refer to Diodes, in Electrons, Electrodes, and Electron Tubes section, for a discussion of electron emission.) Since emission falls off as the tube wears out, low emission is indicative of the end of tube serviceability. However, the emission test is subject to limitations because it tests the tube under static conditions and does not take into account the actual operation of the tube. On the one hand, coated filaments, or cathodes. often develop active spots from which the emission is so great that the relatively small grid area adjacent to these spots cannot control the electron stream. Under these conditions, the total emission may indicate the tube to be normal although the tube is unsatisfactory. On the other hand, coated types of filaments are capable of such large emission that the tube will often operate satisfactorily after the emission has fallen far below the original value.

Fig. 129 shows the fundamental

circuit diagram for an emission test. All of the electrodes of the tube, except the cathode, are connected to the plate. The filament, or heater, is operated at rated voltage; after the tube has reached con-




Fig. 129—Fundamental circuit of an emission tester

stant temperature, a low positive voltage is applied to the plate and the electron emission is read on the meter. Readings which are well below the average for a particular tube type indicate that the total number of available electrons has been so reduced that the tube is no longer able to function properly.

A transconductance test takes into account a fundamental operating principle of the tube. (This fact will be seen from the definition of transconductance in the Section on Electron Tube Characteristics.) It follows that transconductance tests, when properly made, permit better correlation between test results and actual performance than does a straight emission test.

There are two forms of transconductance test which can be utilized in a tube tester. In the first form (illustrated by Fig. 130 giving a fundamental circuit with a tetrode under test), appropriate




Fig. 130—Fundamental circuit of a transconductance tester using the "grid-shift" method.

operating voltages are applied to the electrodes of the tube. A plate current depending upon the electrode voltages will then be indicated by the meter. If the bias on the grid is then shifted by the application of a different grid voltage, a new plate-current reading is obtained. The difference between the two plate-current readings is indicative of the transconductance of the tube. This method of transconductance testing is commonly called the "grid-shift" method, and depends on readings under static conditions. The fact that this form of test is made under static conditions imposes limitations not encountered in the second form of test made under dynamic conditions.

The dynamic transconductance test illustrated in Fig. 131 gives a fundamental circuit with a tetrode under test. This method is superior to the static transconductance test in that ac voltage




Fig. 131—Fundamental circuit of a dynamic transconductance tester.

is applied to the grid. Thus, the tube is tested under conditions which approximate actual operating conditions. The alternating component of the plate current is read by means of an ac ammeter of the dynamometer type. The transconductance of the tube is equal to the ac plate current divided by the inputsignal voltage. If a one-volt rms signal is applied to the grid, the plate-currentmeter reading in milliamperes multiplied by one thousand is the value of transconductance in micromhos.

The power-output test probably gives the best correlation between test results and actual operating performance of a tube. In the case of voltage amplifiers, the power output is indicative of the amplification and output

voltages obtainable from the tube. In the case of power-output tubes, the performance of the tube is closely checked. Consequently, although more complicated to set up, the power-output test will give closer correlation with actual performance than any other single test.

Fig. 132 shows the fundamental circuit of a power-output test for class A operation of tubes. The diagram illustrates the method for a pentode. The ac output voltage developed across the




Fig. 132—Fundamental circuit of a poweroutput tester for class A operation of tubes.

plate-load impedance (L) is indicated by the current meter. The current meter is isolated as far as the dc plate current is concerned by the capacitor (C). The power output can be calculated from the current reading and known load resistance. In this way, it is possible to determine the operating condition of the tube quite accurately.

Fig. 133 shows the fundamental circuit of a power-output test for class




Fig. 133—Fundamental circuit of a poweroutput tester for class B operation of tubes.

B operation of tubes. With ac voltage applied to the grid of the tube, the current in the plate circuit is read on a dc milliammeter. The power output

of the tube is approximately equal to: $(I_b^2 \times R_L)/0.405$,

where $P_{\rm o}$ is the power output in watts, $I_{\rm h}$ is the dc current in amperes, and $R_{\rm L}$ is the load resistance in ohms.

Essential Tube-Tester Requirements

- The tester should provide for making a short-circuit test before measurement of the tube's characteristics.
- 2. It is important that some means of controlling the voltages applied to the electrodes of the tube be provided. If the tester is ac operated, a line-voltage control permits the supply of proper electrode voltages.
- 3. It is essential that the rated voltage applied to the filament or heater be maintained accurately.
- 4. It is suggested that the characteristics test follow one of the methods described. The method selected and the quality of the parts used in the test will depend upon the user's requirements.

Tube-Tester Limitations

A tube tester can only indicate the difference between a tube characteristic and those which are standard for that type. Because the operating conditions imposed upon a tube may vary within wide limits, it is impossible for a tube tester to evaluate tubes for all applications.

Commercially available tube checkers vary widely in purpose, performance, and significance of results. They range from relatively inexpensive portable units to costly laboratory-quality instruments. Design trade-offs are made by tube checker manufacturers to provide a product simple to operate, capable of testing a wide variety of tube types, and in some cases, low in cost. Accuracy of readings, completeness of testing, and even proper testing conditions for certain tube types are sometimes sacrified in these trade-offs. Recognition of the individual tester limitations are absolutely necessary before valid judgments on tube quality can be made from test results.

Tube checkers generally make two types of evaluations: tests for inter-

element shorts (leakage) and an electrical test of quality that is either an ac cathode-emission test or a more complex large-signal transconductance test.

The shorts or leakage tests are often more sensitive than those of the tube manufacturer and also, in some cases more stringent than circuit application requirements. Leakage sensitivity of 100 megohms between elements is available in some tube checkers. Some can be adjusted by the user to even higher sensitivities. Many tube checkers tie several elements together to test many parallel paths in a single test position. As a result, multiple paths having individual inter-element leakage resistances which are acceptable result in parallel combinations which cause the tube to read as defective.

Quality-test interpretations must be tempered by knowledge of the character of the quality test. Large-signal transconductance (gm) often does not correlate with small-signal transconductance. or the control limits for applications that require this characteristic. Cathode emission, as read on many tube checkers, is a function of both the emitting capability of the cathode and the mechanical spacing of the tube's internal parts. While high cathode emitting capability is generally desirable for all tubes, a high emission reading obtained by close mechanical spacing of parts can result in a false indication of good quality. In addition, high or low indications in a tube checker are often caused by compromise test conditions rather than the quality of the tube being tested.

The set-up instruction and charts furnished by the tester manufacturer establish the conditions and limits which the tester manufacturer considers adequate for the tube types evaluated. These conditions and limits are usually established independently of the tube manufacturer and without consideration of application requirements.

The tube tester cannot be looked upon as a final authority in determining whether or not a tube is satisfactory. An actual operating test in the application will give the best possible indication of a tube's worth.

Application Guide for RCA Receiving Tubes

In the Application Guide on the following pages, RCA receiving tubes are classified in two ways: (a) by function, and (b) by structure (diode, triode, etc.). The functional classification covers 27 principal types of application, as listed below.

Tube types are grouped by structure under each classification; they are also keyed to indicate miniature, octal, nuvistor, duodecar, and novar types.

Triodes are designated as low-. medium-, or high-mu types on the following basis: low, less than 10; medium, 10 or more, but less than 50; high, 50 or more. Where applicable, tubes are designated as sharp-, semiremote-, or remote-cutoff on the basis of the ratio. in per cent, of the negative control-grid voltage to the screen-grid voltage (or, for triodes, the plate voltage) for cutoff, as given in the characteristics or typical operation values. These terms are defined as follows: sharp, less than 10 per cent; semiremote, 10 or more. but less than 20 per cent, remote, 20 per cent or more.

For more complete data on these types, refer to the Technical Data For RCA Receiving Tubes.

APPLICATIONS

- 1. Audio-Frequency Amplifiers
- 2. Automatic Gain Control Circuits (AGC and AVC)
- 3. Blankers
- 4. Burst Amplifiers
- 5. Chroma Amplifiers
- 6. Color Killers 7. Color Matrixing Circuits
- 8. Dampers
- 9. Demodulators (Color TV)
- 10. Detectors (AM)
- 11. Discriminators (Detectors)
- 12. Horizontal-Deflection
- 13. Intermediate-Frequency Amplifiers
- 14. Limiters

- 15. Pentagrid Converters
- 16. Mixer-Oscillators-RF
- 17. Multivibrators
- 18. Oscillators
- 19. Phase Splitters 20. Radio-Frequency
 - Amplifiers
- 21. Reactance Circuits
- 22. Rectifiers (Vacuum)
- 23. Regulators (High Voltage) Sync Separators and Amplifiers
- 25. **Tuning Indicators**
- Vertical-Deflection Circuits (Oscillator and
- Amplifier)
- 27. Video Amplifiers

1. AUDIO-FREQUENCY **AMPLIFIERS**

Voltage Amplifiers

Medium-Mu Triode-Sharp-Cutoff Pentode

• 7199‡

Medium-Mu Twin Triode

o 6SN7GTB o 12SN7GTA

12AU7A/ECC82

Twin Diode-High-Mu Triode

• 6RN8

 4AV6 6AT6

• 8BN8

 6AV6 12AT6

Triple Diode-High-Mu Triode

• 5T8 6T8A 19T8

12AV6

14GT8

Ministure

Octal

† For high-fidelity equipment

High-Mu Twin Triode

• 6EU7+ 12AX7A/ o 12SL7GT o 6SL7GT ECC83† 7025†

Sharp-Cutoff Pentode

 6AU6A · 5879† 6HS6 7543†

Power Amplifiers

Beam Power Tube

• 5AQ5 • 25C5 ⊙ 6Y6GA/6Y6G • 35°C5 6AQ5A 11DS5 • 6AS5 • 50C5 12AB5 • 6CU5 o 50L6GT • 12AQ5 · 6973† 6DS5 • 12CA5 6GC5 12CU5/12C5 7027A† · 7355† o 6L6 12V6GT o 6L6GC† o 12W6GT ⊙ 7408† ⊙ 7581A† o 6V6GTA · 17CU5/17C5

o 6W6GT

Beam Power Tube-Sharp-Cutoff Pentode

\$ 6AD10 ± 6T10* **± 12BF11*** ± 6A1.11 ± 12AL11 ± 17BF11* ± 6BF11*

Power Pentode

 6BO5/EL34 • 10BO5 35EH5 10GK6 6EH5 50EH5 o 6F6 • 12FX5 60FX5 16GK6 6GK6 · 7189† ⊙ 6K6GT 19FX5 **▲ 7868†** 8BQ5 25EH5 ⊙ 7591A

2. AUTOMATIC GAIN CONTROL CIRCUITS (AGC & AVC)

Twin Diode-High-Mu Triode

• 4AV6 • 6AV6 • 12AV6 • 6AT6 12AT6

Medium-Mu Triode-Sharp-Cutoff Pentode

 SANR 6AZ8 • 6GH8A 5GH8A 6RASA 9GH8A 6AN8A

High-Mu Triode-Sharp-Cutoff Pentode

 6AW8A 6LC8 8KA8 • 6HF8 8A W8A 8LC8 6JV8 · SIVS 10HF8 6KA8

Sharp-Cutoff Twin Pentode

• 3BU8/ 4HS8 6HS8 3**G**S8 • 6RU8

Sharp-Cutoff Pentode*

6GY6/6GX6

Pentagrid Amplifier

 4CS6 3BY6 • 6CS6 3CS6 6BY6

3. BLANKERS

Medium-Mu Triode—Sharp-Cutoff Pentode

 5GH8A 6GH8A

 6MO8 9GH8A

Medium-Mu Twin Triode

 6FO7/6CG7 8FO7/8CG7 12BH7A 6GU7 8GU7 12FO7

Medium-Mu Triode—Semiremote-Cutoff Pentode

• 6LM8

High-Mu Triode—Sharp-Cutoff Pentode

6KT8

4. BURST AMPLIFIERS

Medium-Mu Triode—Sharp-Cutoff Pentode

 9GH8A 5EAR 6EA8 19EA8 SGH8A · 6GH8A

Medium-Mu Triode-Semiremote-Cutoff Pentode

 61.M8 6MU8

Twin Diode-High-Mu Triode

• 6BN8 • 8BN8

Sharp-Cutoff Pentode

 3CB6/3CF6 • 4EW6 · 6CB6A/6CF6 • 6EW6 • 3JC6A 4JC6A

 4CB6 5EW6 6JC6A

5. CHROMA AMPLIFIERS

Medium-Mu Triode-Sharp-Cutoff Pentode

• 6HL8 9GH8A 5GH8A

 6GH8A 6MO8

High-Mu Triode-Sharp-Cutoff Pentode

 6AW8A 6LF8 6KT8 8AW8A

Medium-Mu Twin Triode

• 6FO7/6CO7 • 8FO7/8CG7 • 12BH7A

• 6GU7 8GU7 12F07

6. COLOR KILLERS

Quadruple Diode

 6JU8A 8JU8A

Medium-Mu Triode—Sharp-Cutoff Pentode

 5GH8A 6MO8 9GH8A 6GH8A

High-Mu Triode-Sharp-Cutoff Pentode

6KT8

A Novar

* Dual-control grids

TO COLOR MATRIVING CIRCUITS	Pentagrid Am	nlifier	
7. COLOR MATRIXING CIRCUITS Medium-Mu Twin Triode	• 6BY6	piiike:	
• 6FQ7/6CG7 • 8GU7 • 12FQ7 • 6GU7 • 12AZ7			•
• 6GU7 • 12AZ7 • 8FQ7/8CG7 • 12BH7A	Twin Pentode		
01 Q.7000.	• 4MK8A • 6LE8	• 6MK8A • 10LE8	• 15LE8
Medium-Mu Triode—Sharp Cutoff Pentode	* OLEO	• IULEO	
• 5GH8A • 6GH8A • 9GH8A	Dan Dagastic	- Tube	
Medium-Mu Triple Triode	Beam Deflection	• 6ME8	
▲ 6MD8	· on	ONIES	
High-Mu Triple Triode	40 70777777	mond (ARA)	
± 6MN8	10. DETECTORS (AM)		
+ Ultar to		Cutoff Pentode	
Twin Pentode	• 5AM8	• 6AM8A	• 6A.S8
• 6LE8 • 10LE8 • 15LE8	Twin Diode		
Quadruple Diode	• 3AL5	• 6AL5	• 12AL5
• 6JU8A			
Chara Cutoff Bouts de	Twin Diode—High-Mu Triode • 4AV6 • 6BN8 • 12AT6		
Sharp-Cutoff Pentode • 3CB6/3CF6 • 6CB6A/6CF6	• 4AV6 • 6AT6	• 6BN8 • 6CN7	• 12AV6
• 4CB6	• 6AV6	• 8BN8	• 14GT8
8. DAMPERS		-High-Mu Trio	
Half-Wave (Diode)	• 5T8	• 6T8A	• 19T8
o.6AU4GTA o.6DM4A/ ‡ 17BE3/	Quadruple Di	ode	
o 6AX4GTB 6DA4 17BZ3	• 6JU8A	• 8JU8A	
^6BA3			
* 6BS3A 6BS3A 17RK19	11. DISCRIMINATORS		
‡ 6CE3/6CD3/ 12BR3/ 17DW4A	(DETECTORS)		
6DT3	FM		
6DQ3		2 1/2	
▲ 6CJ3/	Twin Diode		• 12AL5
6CH3	• 3AL5	• 6AL5	· IZALS
6CL3/ 12DW4A ‡ 22BW3 6CK3 • 12CL3 © 22DE4	Twin Diode-	High-Mu Triod	le
▲ 6CM3 ▲ 12CM3 • 25CT3	• 6BN8		
© 6DE4/	Triple Diode-	-High-Mu Trio	de
6CQ4	• 5T8	• 6T8A	• 19T8
Half-Wave (Diode)—Horizontal-Deflection	Beam Tube		
Amplifier	• 3BN6	• 4BN6	• 6BN6/
‡ 33GY7A	Jane	42110	6KS6
‡ 38HE7			
9. DEMODULATORS (COLOR TV)	Beam Power Tube-Sharp-Cutoff Pentode		
Medium-Mu Twin Triode	‡ 6AD10	‡ 6T10	‡ 12BF11
• 12BH7A • 12AZ7A	# 6AL11	‡ 6Z10/6J10	‡ 13Z10/13J10 ‡ 17BF11
Madium Margarata Change of America	‡ 6BF11	‡ 12AL11	\$ 1/BF11
Medium-Mu Triode—Sharp-Cutoff Pentode • 5GH8A • 6MO8 • 9GH8A			a
• 5GH8A • 6MQ8 • 9GH8A • 6GH8A	FM Quadrature-Grid		
High-Mu Twin Trlode	Sharp-Cutoff Pentode*		
• 12AZ7A	• 3DT6A • 4DT6A	• 5HZ6 • 6DT6A	 6GY6/6GX6 6HZ6
	- 4D10A	- 0D10A	- 0HZU
Sharp-Cutoff Pentode* • 5HZ6 • 6GY6/6GX6 ± 12BV11	Beam Tub-		
• 5HZ6 • 6GY6/6GX6 ‡ 12BV11 ‡ 6BV11 • 6HZ6	Beam Tube • 3BN6	• 4BN6	• 6BN6/
	- 3D140	- 40740	6KS6

o Octal A Nuvistor

^ Novar

‡ Duodecar

* Dual control grids

Miniature

APPLICAT	ION GUIDE				10
I	Horizontal AF	FC .	High-Mu Triod	e-Sharp-Cutof	
Twin Diode-	High-Mu Triode		• 6AW8A • 6EB8	• 6KV8 • 6MV8	• 10GN8 • 10HF8
	~		• 6GN8	• 8AW8A	• 10HF8
• 6BN8	• 8BN8	• 8CN7	• 6HF8	• 8GN8/	10LZ8
• 6CN7			• 6JV8	8EB8	• 11KV8
Twin Diodo	Medium-Mu Twi	n Triode	• 6KT8	• 8JV8	
1 6B10	1 8B10	ii iirouc			
† OPIA	† ODIA		Sharp-Cutoff Pe	entode	
Turin Diodo 6	Sharp Cutoff Pen	todo	• 3AU6	• 4EW6	· mac
• 6LT8	• 8LT8	• 11LT8	• 3BC5/	• 4JC6A	• 6DC6 • 6DE6
· ULIO	· OL IO	· 111.10	3CE5	• 4JD6	• 6DK6
			• 3CB6/	• 5EW6	• 6EJ7/
			3CF6	• 6AG5	EF184
12. HORIZ	ONTAL-DEF	LECTION	• 3DK6	• 6AK5/	• 6EW6
	o		• 3JC6A	EF95	• 6HS6
	Oscillators		• 3JD6	• 6AU6A	 6JC6A
Medium Ma T	riode—Sharp-Cu	toff Dontode	• 4AU6	• 6BC5/	• 6JD6
			• 4CB6	6CÉ5	• 12AU6
• 5GH8A	• 6GH8A	• 9GH8A	• 4DE6	 6CB6A/ 	• 12DK6
			• 4DK6	6CF6	
Twin Diode-	Medium-Mu Twi	n Triode			
‡ 6B10	‡ 8B10		Diode-Sharp-C	utoff Pentode	
			• 5AM8	• 6AM8A	• 6AS8
Three Unit Tri	lode		JAME	OKNION	- 07150
‡ 6U10					
			Semiremote-Cut	off Pentode	
Medium-Mu T	Twin Triode		• 3BZ6	• 4JH6	 6GM6
		14005	• 3EH7/	 4KT6 	• 6HR6
of 6SN7GTB	7 • 12AU7A/ ECC82	• 12FQ7 ⊙ 12SN7GTA	XF183	• 5GM6	• 6JH6
• 8FQ7/8CG		0 125N/G1A	• 3KT6	• 6BZ6	• 6KT6
· or Qii ocu	/ • 12BH/A		• 4BZ6 • 4EH7/	• 6EH7/	 12BZ6
			LF183	EF183	• 19HR6
Horizoni	tal-Deflection .	Amplifiers	LIFTOS		
_	•	• •			
Beam Power	Tube		Remote-Cutoff	Pentode	
o 6AU5GT	‡ 6KN6	^ 22JF6	• 6BA6/	• 12BA6	
o 6AV5GA	‡ 6LB6	▲ 22JG6A	EF93	· Labra	
o 6BQ6GTB/		▲ 22JR6	EF73		
6CU6	▲ 6ME6	4 22KM6			
 6CB5A 6CD6GA 	▲ 6MJ6/	▲ 24LQ6/ 24JE6C	44 * ** 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5		
⊚ 6DO5	6LQ6/ 6JE6C	243E0C 25AV5GA	14. LIMITE	RS	
▲ 6GJ5A		o 25BQ6GTB/	. 24776	- 4ID4	- CDEC
▲ 6GT5A	o 12AV5GA	25CU6	• 3AU6 • 3BC5/3CE5	• 4JD6 • 5EW6	• 6DE6 • 6DK6
o 6GW6/	o 12BQ6GTB/	o 25CD6GB	• 3CB6/3CF6	• 6AG5	• 6EJ7/
6DQ6B	12CU6 ^ 12JB6A	o 25DN6	• 3DK6	• 6AK5/	EF184
▲ 6JB6Ā	- 123B0A - 12JT6A	‡ 31 JS6C	• 3JC6A	EF95	• 6EW6
^ 6JF6	▲ 17GJ5A	^ 31LQ6	• 4AU6	· 6AU6A	• 6HS6
▲ 6JG6A	▲ 17GT5A	▲ 31LZ6	• 4CB6	• 6BC5/	· 6JC6A
‡ 6JM6A	⊙ 17GW6/	‡ 35LR6	• 4DE6	6CE5	• 6JD6
▲ 6JR6	17DQ6B	‡ 36KD6/	• 4DK6	 6CB6A/ 	• 12AU6
‡ 6JS6C	▲ 17JB6A	40KD6	• 4EW6	6CF6	 12DK6
▲ 6JT6A	^ 17JG6A	▲ 36MC6 * 30HW7	• 4JC6A	• 6DC6	
4 6JU6	‡ 17JM6A	‡ 38HK7 ‡ 42KN6			
▲ 6KM6	^ 17JT6A	+ 471/1/10			
			15. PENTAGRID CONVERTERS		
44 95		MOTION (CT)	• 6BA7	• 6BE6	• 12BE6
	MEDIATE-FF	REQUENCY			
AMPLI	FIERS				
			1		

· 6AU8A • Miniature

• 5AN8

• 5GH8A • 6AN8A

Medium-Mu Trlode---Sharp-Cutoff Pentode

6BA8A

• 6HL8

• 6AZ8

• 6MQ8

· 8AU8A

9GH8A

• 5CL8A

• 19JN8/

19CL8A

16. MIXER-OSCILLATORS—RF

Medium-Mu Triode-Sharp-Cutoff Tetrode

• 6CL8A

• 6CQ8

					2,2,11,(0,1)
	-	Cutoff Pentode		riode—Sharp-Cuto	ff Pentode
• 4KE8	• 5U8	• 6KZ8	• 6AW8A	• 8AW8A	• 10GN8
• 5AT8 • 5B8	• 5X8 • 6AT8A	• 6U8A/	• 6EB8	• 8GN8/	• 10HF8
• 5BR8/	• 6BR8A/	6KD8 • 6X8A	• 6GN8 • 6HF8	8EB8	• 10JA8/
5FV8	6FV8A	• 9KZ8	· OMF		10LZ8
• 5CG8	• 6EA8	• 9U8A	High-Mu Tv	vin Triode	
• 5EA8	• 6FG7	• 19EA8	⊙ 6SL7GT		
• 5FG7	• 6HB7	• 19X8	0 0317/01	• 12A X7A/	
• 5KE8	• 6KE8			ECC83	• 7025
High-Mu Twir	Triode		Medium-Mu	Triode—Sharp-Cu	toff Pentade
• 6DT8	• 12AT7/	• 12DT8	• 5EA8	• 6GH8A	• 7199†
- 02210	ECC81	12010	5GH8A	• 9GH8A	• 19EA8
	200-1		• 6EA8		
17 MINT	VIBRATOR	c	10 D . D.	A 222	
17. MULII	VIDRA I OK	•	20. KADIO	O-FREQUENC	Y
Medium-Mu T	riode—Sharp-C	utoff Pentode	AMPL	IFIERS	
• 5GH8A	• 6GH8A	• 9GH8A	i		
- 0011074	. 00110/1	7011071	Medium-Mu	Triode	
Medium-Mu T	win Triode		• 2BN4A	• 6BC4	• 6BN4A
· 5J6	• 8FQ7/8CG7	• 12BH7A	• 3BN4A		
6FQ7/6CG7		o 12SN7-	34-11		
• 6GU7	• 9AU7	GTA	Medium-Mu	Triode-Sharp-Ct	itoff Tetrode
• 6J6A	• 12AU7A/	• 12FQ7	• 6CQ8		
o 6SN7GTB	ECC82	• 19 J 6			
• 7AU7			Medium-Mu		
High-Mu Twin	Triode		• 4BC8	• 5BQ7A	• 6BQ7A/
• 12AX7A/ E	CC83		• 4BQ7A/ 4BZ7	• 6BC8/	6BZ7/
12.1.1.1, 15			• 5BK7A	6BZ8 • 6BK7R	6BS8
18. OSCILL	ATORS		J JBR/A	• ODK/B	
			High-Mu Tri	ode	
Radio	Frequency-	<i>—UHF</i>	△ 2CW4	• 3FH5	CD CL
Medium-Mu T			△ 2DS4	• 3GK5	△ 6DS4 • 6ER5
• 2AF4B/	• 3AF4A/	△ 6DV4	△ 2EG4	• 3HM5/3HA5	• 6FH5
2DZ4	3DZ4	• 6DZ4	• 2FH5	• 3HQ5	• 6GK5/
△ 2DV4	• 6AF4A/		• 2GK5/	• 4GK5	6FO5A
	6DZ4		2FQ5A	• 4HM5/	• 6HM5/6HA5
			• 2HM5/	4HA5	• 6HQ5
Radio	Frequency-	_VHF	2HA5 • 2HO5	4HQ56AB4	△ 13CW4
Medium-Mu Tv	vin T <i>r</i> iode		• 3ER5	4 6CW4	
• 5J6	• 6J6A	• 1936	52AC	4 00 114	
			High-Mu Twi	in Triode	
High-Mu Triod	e		• 6DT8	• 12DT8	
• 6AB4					
Power Triode			Power Triode		
=	~.		1		
• 6C4 (Class C	2)		• 6C4 (Class	C)	
3 58	MHz (Color	TV	Shara Cut-6	T-4 4-	
Medium-Mu Tri			Sharp-Cutoff		
··			• 2CY5	• 3CY5	• 6CY5
• 5GH8A	• 6GH8A	• 9GH8A	Character of Asset	m 4-1	
High-Mu Tríode	-Sharu-Cutoff	Pentode	Sharp-Cutoff		
• 6KT8	oma p-onton		• 3AU6	• 6AG5	• 6CB6A/
- OW 10			• 3CB6/ • 3BC5/3CE5	• 6AK5/ EF95	6CF6 • 6DC6
19. PHASE	SOT ITTEDS		3CF6	• 6AU6A	• 6DE6
17. FMASE	31 LILLENS		• 4AU6	• 6BC5/	• 12AU6
Medium-Mu Tw	in Triode		• 4CB6	6CE5	
• 6F07/6CG7	• 8FO7/8CG	7 • 12BH7A	o 4DE6	• 6BH6	
• 6GU7	• 8GU7	• 12FQ7			
o 6SN7GTB	• 9AU7	o 12SN7-	Remote-Cutoff	Pentode	
• 7AU7	• 12AU7A/	GTA	• 6BA6/	• 6BJ6	• 12BA6
	ECC82		EF93		

21. REACTANCE CIRCUITS

Medium-Mu Triode-Sharp-Cutoff Pentode

• 5AN8 • 6AZ8 • 6GH8A • 5GH8A • 6BA8A • 9GH8A

• 6AN8A

Twin Diodes—High-Mu Triode
• 6CN7 • 8CN7

High-Mu Triode—Sharp-Cutoff Pentode
• 6AW8A • 8AW8A

22. RECTIFIERS (VACUUM)

Power-Supply Types

Half-Wave (Diode)

• 35W4

¥4 ⊙ 35Z5GT

Full-Wave (Twin Diode)

High-Voltage Types

Half-Wave (Diode)

 1AY2A 	\$ 2BU2/	
○ IG3GTA/	2AH2	⊕ 3CU3A
1B3GT	• 3A2	
1K3A/	• 3A3C	9 3DA3/
1J3	‡ 3AT2B	3DH3
• 1V2	‡ 3AW2A	⊙ 3DB3/
• 1X2C		3CY3
‡ 2AS2A	± 3BW2/	⊙ 3DC3
• 2AV2	3BS2A/	⊙ 3DJ3
	3BT2	- 01700

23. REGULATORS (HIGH VOLTAGE)

Beam Triode-Shunt Type

○ 6BK4C/ ○ 6LJ6A/ ○ 6MA6
6EL4A 6LH6A
○ 6EN4

Beam Power Tube-Pulse Type

24. SYNC SEPARATORS AND AMPLIFIERS

High-Mu Twin Triode

• 12BZ7

Medium-Mu Triode—Sharp-Cutoff Tetrode
• 6CO8

Sharp-Cutoff Twin Pentode

• 3BU8/ • 4HS8 3GS8 • 6BU8 • 6HS8

Pentagrid Amplifier

• 3BY6 • 4CS6 • 6CS6 • 3CS6 • 6BY6

• 3CS6 • 6BY

High-Mu Triode—Sharp-Cutoff Pentode

• 6KT8

• 6MV8

Medium-Mu Triode—Sharp-Cutoff Pentode (Video Output)

• 6CX8 • 8CX8 • 11LQ8 • 6LO8

• orve

Medium-Mu Triode-Sharp-Cutoff Pentode

• 5AN8 • 6AZ8 • 6HL8 • 5GH8A • 6BA8A • 6MQ8 • 6AN8A • 6CU8 • 8AU8 • 6AU8A • 6GH8A • 9GH8A

Medium-Mu Twin Triode

• 6FQ7/6CG7 • 12AU7A/ • 12FQ7 • 8FQ7/8CG7 ECC82

Twin Diode-High-Mu Triode

• 6CN7 • 8CN7

High-Mu Triode—Sharp-Cutoff Pentode (Video Output)

 6AW8A 6KT8 • 8KA8 6EB8 6KV8 • 8LC8 • 6GN8 6LC8 10GN8 6GW8/ • 8AW8A 10HF8 ECL86 • 8GN8/ 10JA8/ • 6HF8 8EB8 10LZ8 • 6JV8 • 8JV8 • 11KV8 6KA8

25. TUNING INDICATORS

Indicator with Triode Unit 6E5 6U5

Twin Indicator Units

o 6AF6G

26. VERTICAL-DEFLECTION CIRCUITS

Oscillators and Amplifiers (Combined)

Medium-Mu Triode-Low-Mu Triode

• 6DE7 • 10EW7 • 13DE7 • 6EW7 • 10DE7

Medium-Mu Dual Triode

• 6CM7 • 8CM7 • 8CS7 • 6CS7

Medium-Mu Twin Triode

• 6FQ7/6CG7 • 8FQ7/8CG7 • 12FQ7

High-Mu Triode—Low-Mu Triode

• 6CY7	• 10DR7	○ 13FM7/
• 6DR7	o 10EM7	15FM7
6EM7/	^ 10GF7A	* 13FD7
6EA7	• 13DR7	4 13GF7A
^ 6FD7	○ 13EM7/	
▲ 6GF7A	15E A 7	

High-Mu Triode-Beam Power Tube

^ 6KY8A ^ 6LR8	‡ 6LU8 ^ 15KY8A	‡ 16LU8 ▲ 21LR8
		‡ 21LU8
		A 31LR8

Dual Triode

6EM7/	▲ 6GF7A	○ 13EM7/
6EA7		15EÅ7

Dual Triode—Beam Power Tube ‡ 23Z9

Micolam-Min	TLMOGLOMEL	rentoac
‡ 6JZ8 ‡ 13JZ8	‡ 17JZ8 ‡ 24JZ8	‡ 25JZ8

Amplifiers

Low-Mu Triode

• 12B4A

Medium-Mu Triode

• 6S4A

‡ 6JA5

Ream Power Tube

Death I Ower	Y GIVE	
• 5AQ5	‡ 6JB5/	• 11DS5
• 5CZ5	6HE5	• 12AQ5
• 6AQ5A	• 6JQ6#	• 12JQ6#
• 6CZ5	o 6V6	o 12V6GT
• 6DS5	6V6GTA	• 17JQ6#
· CERSE	- OF B##	_

‡ 10JA5

Power Pentode

•	6GK6	•	10GK6	•	16GK6
0	6K6GT				

27. VIDEO AMPLIFIERS

Medium-Mu Triode-Sharp-Cutoff Pentode

	- 11000 Distrib Caton	-	ciicoac
• 5AN8	• 6AZ8	•	6MQ8
• 5GH8A	• 6BA8A	•	8AU8
• 6AN8A	• 6GH8A	•	9GH8A
• 6AU8A	• 6HL8		

Medium-Mu Triode—Sharp-Cutoff Pentode (Video Output)

		(Alnen Chibar)
• 6CX8	• 8CX8	• 11LQ8
• 6LQ8		=

High-Mu Triode—Sharp Cutoff Pentode (Video Output)

• 0A W8A	• OLF8	• 10G142
• 6EB8	• 8AW8A	 10HF8
• 6GN8	• 8GN8/	• 10JA8/
• 6HF8	8EB8	10LZ8
• 6JV8	• 8JV8	 10LY8
• 6KV8		 11KV8

Sharp-Cutoff Pentode (Video Output)

• 6AG7	 10GK6 	• 12HG7
• 6CL6	• 11HM7	• 12HG7/
• 6GK6	 12BY7A/ 	12GN7A
• ଧG5	12BV7/	• 12HL7
 7KY6 	12DQ7	

Diode-Sharp-Cutoff Pentode

• 5A	M8	•	64	M8A	•	6AS

High-Mu Triode—Sharp-Cutoff Pentode • 6KT8

Sharp-Cutoff Pentode

• 3JC6A • 4JC6A • 6JC6A

Technical Data for RCA Receiving Tubes

Entertainment and

Industrial Types

This section contains technical data for RCA receiving tubes, intended for use in many diverse entertainment and industrial applications such as standard broadcast, FM, television receiver, audio amplifier, on-off control, voltage regulator, and voltage reference. Detailed data are presented on popular types. Essential information on less active types and on discontinued types in which there still may be some interest is given in chart form at the end of the section.

Tube types are listed in this section according to the numerical-alphabetical-numerical sequence of their type designations. Tube types which have superseding versions are cross-referenced to active types. In addition, an alpha-numeric listing of foreign type designations is included

at the end of this data section.

A grid-No. 2 input rating chart for certain voltage-amplifier types, as specified in the technical data, is shown on page 300. Safety Precautions are given on page 93. Characteristics for RCA television picture tubes for replacement use are given in RCA Picture Tube Characteristics Charts.

When choosing types for the design of new electronic equipment, the designer should refer to the Application Guide for RCA Receiving Tubes

which starts on page 104.

To expedite the preliminary search for interchangeable tube types, the section Terminal Diagrams, which starts on page 594, includes a comprehensive listing of domestic and foreign tube types having the same basing arrangement. The Key To Terminal Diagrams is given on page 612.

Two replacement guides are also included. A Replacement Guide— Entertainment Receiving Types and a Replacement Guide—Industrial Re-

ceiving Types are given on pages 650 and 657 respectively.

VOLTAGE REGULATOR



Miniature type cold-cathode, glow-discharge tube used in voltage regulator applications. Outlines section, 5D; requires miniature 7-contact socket.

MAXIMUM RATINGS (Absolute-Maximum Values)

Average Starting Current	75	mA mA
DC Cathode Current	{30 { 5 min	mA
Frequency Ambient-Temperature Range	55 to +90	Hz °C

MAXIMUM CIRCUIT VALUES	
Shunt Capacitor Series Resistor See Opers	0.1 μF ating Considerations
CHARACTERISTICS DANCE VALUES FOR EQUIPMENT RESIGN	

	M11M-	Av.	MET.	
DC Anode-Supply Voltage	185■			volts
Anode Breakdown Voltage		156	185*	volts
Anode Voltage Drop	140●	151	168*	volts
Regulation (5 to 30 mA)		2	6*	volts
100211111011 (0 00 00 1111-)				

- Averaged over starting period not exceeding 10 seconds. This starting period must be followed by a steady-state operating condition of at least 20 minutes, or tube performance will be impaired.
- Not less than indicated supply voltage should be provided to insure "starting" throughout
- * Maximum individual tube value during useful life.
- Minimum individual tube value during useful life.

Operating Considerations


Sufficient resistance must always be used in series with the tube to limit the current through the tube. The value for the series resistor is dependent on the maximum anode-supply voltage and the ratio of the current through the load to the operating current of the tube, and should be chosen to limit the operating current through the tube to the maximum rated value at all times after the starting period.

The maximum load current that can be regulated by the tube is determined by the minimum and maximum values of the supply voltage. After the value of series resistor for the maximum supply voltage has been calculated as indicated above, it is then in order to determine if this value will permit adequate starting voltage when the supply voltage falls to its minimum value. If adequate starting voltage is not obtained, a new load current of lower value must be used and the calculations repeated. It will be apparent from such calculations that the higher the minimum supply voltage and the smaller the difference between its minimum and maximum values, the higher will be the load current that can be regulated.


When equipment utilizing the tube is "turned on", a starting current in excess of the average operating current is permissible as indicated under Maximum Ratings. When the tube is subjected to such high starting currents, the regulated voltage may require up to 20 minutes to drop to its normal operating value. This performance is characteristic of voltage-regulator tubes of the glow-discharge type. Similarly, the regulation is affected by changes in current within the operating current range.

In order to handle more load current, two or more tubes may be operated in parallel, but such parallel operation requires that a resistance of approximately 100 ohms be used in series with each tube in order to equalize division of the current between the paralleled tubes. The disadvantage of this method, of course, is that the use of resistors impairs the regulation which can be obtained.


If the associated circuit has a capacitor in shunt with the tube, the capacitor should be limited in value to 0.1 μ F. A larger value may cause the tube to oscillate and thus give unstable regulation performance.



Typical circuit to provide regulated supply voltage of approximately 150 or 108 volts to load. Removal of tube from socket removes voltage from load.



Typical circuit using two OA2's or two OB2's to provide regulated supply voltages of approximately 300 or 216 volts and 150 or 108 volts to load. Socket connections are so made that voltage on load is removed when either tube is taken from its socket.



Typical circuit for bias-supply regulation. Removal of tube from socket opens B-supply circuit of regulated tubes.

OA2WA OA3 OA3A OA4G Refer to chart at end of section. Refer to chart at end of section. Refer to chart at end of section. Refer to chart at end of section.

OB2 INDUSTRIAL TYPE

Shunt Capacitor

VOLTAGE REGULATOR

Miniature type cold-cathode, glow-discharge tube used in voltage regulator applications. Outlines section, 5D; requires miniature 7-contact socket.

5BO

Average Starting Current •	75	mĄ
DC Cathode Current	{30 } 5 min.	mA mA
Frequency Ambient-Temperature Range	0 55 to +90	Hz °C
MAXIMUM CIRCUIT VALUES		

Series Resistor See Operating Considerations

CHARACTERISTICS RANGE VALUES FOR EQUIPMENT DESIGN

	Min.	Av.	Max.	
DC Anode-Supply Voltage	133■			volts
Anode Breakdown Voltage		115	133*	volts
Anode Voltage Drop	101●	108	114*	volts
Regulation (5 to 30 mA)		1	4*	volts

- Averaged over starting period not exceeding 10 seconds. This starting period must be followed by a steady-state operating condition of at least 20 minutes, or tube performance will be impaired.
- Not less than indicated supply voltage should be provided to insure "starting" throughout tube life.
- * Maximum individual tube value during useful life.
- Minimum individual tube value during useful life.

Operating Considerations

Refer to type OA2.

OB2WA

Refer to chart at end of section.


OC2

Refer to chart at end of section.

OC3 INDUSTRIAL

VOLTAGE REGULATOR

Glass octal type cold-cathode, glow-discharge tube used in voltage regulator applications. Outlines section, 22; requires octal socket.



4AJ

MAVIMIEM	DATIMOR	(Absolute-Maximum	Values

Average Starting Current	100	mA
DC Cathode Current	{40 5 min.	mA mA
Frequency Ambient-Temperature Range	0 55 to +-90	Hz
Timester at the second of the	-00 W T30	U

MAXIMUM CIRCUIT VALUES

Shunt	Canacitor		. 0.1	μF
Series	Resistor	 See	Operating	

CHARACTERISTICS RANGE VALUES FOR EQUIPMENT DESIGN

	Min.	Av.	Max.	
DC Anode-Supply Voltage	133■	_		volts
Anode Breakdown Voltage	_	115	133*	volts
Anode Voltage Drop	103●	108	116*	volts
Regulation (5 to 40 mA)	_	2	4*	volts


- ♦ Averaged over starting period not exceeding 10 seconds. This starting period must be followed by a steady-state operating condition of at least 20 minutes, or tube performance will be impaired.
- Not less than indicated supply voltage should be provided to insure "starting" throughout tube life.
- * Maximum individual tube value during useful life.
- Minimum individual tube value during useful life.

Operating Considerations

Refer to type OA2. For circuit diagrams refer to next page.

Refer to chart at end of section.

OC3A



VOLTAGE REGULATOR

OD3
INDUSTRIAL
TYPE

Glass octal type cold-cathode, glow-discharge tube used in voltage regulator applications. Outlines section, 22; requires octal socket.

MAXIMUM RATINGS (Absolute-Maximum Values)

Average Starting Current •	100	mA
Average Starting Current DC Cathode Current	{40	mA mA
Frequency	0	H
Ambient-Temperature Range	-55 to +90	°C
MAYIMUM AIRAUT VALUE		

MAXIMUM CIRCUIT VALUES

	Capacitor	 	. 0.1	μF
Series	Resistor .	 See	Operating	Considerations

CHARACTERISTICS RANGE VALUES FOR EQUIPMENT DESIGN


	Min.	A٧.	Max.	
DC Anode-Supply Voltage	185■		_	volts
Anode Breakdown Voltage	_	160	185*	volts
Anode Voltage Drop	142●	153	165*	volts
Regulation (5 to 40 mA)		4	5.5*	volts


- Averaged over starting period not exceeding 10 seconds. This starting period must be followed by a steady-state operating condition of at least 20 minutes, or tube performance will be impaired.
- Not less than indicated supply voltage should be provided to insure "starting" throughout tube life.
- Maximum individual tube value during useful life.
- Minimum individual tube value during useful life.

Operating Considerations


Refer to type OA2. For circuit diagrams refer to next page.

Refer to chart at end of section.





Typical circuit to provide regulated supply voltage of approximately 75, 105, or 150 volts to load. Removal of tube from socket removes voltage from load.




Typical circuit using two OC3's, or two OD3's to provide regulated supply voltages of approximately 210 or 300 volts and 105 or 150 volts to load. Socket connections are so made that voltage on load is removed when either tube is taken from its socket.

Refer to chart at end of data section.

OZ4 OZ4A

Refer to type OZ4A/OZ4.

† Open-circuit voltage (flat portion of transformer voltage wave).




FULL-WAVE GAS RECTIFIER OZ4A/OZ4

Metal type used as a power rectifier in equipment with vibrator-type power supplies. Outlines section, 2A; requires octal socket. This tube, like other power-handling tubes, should be adequately ventilated.

Ful	I-Wave	Rectifier

Full-Wave Rectifier		
MAXIMUM AND MINIMUM RATINGS (Design-Center Values)		
Peak Inverse Plate Voltage (Per Plate) Peak Starting-Supply Voltage (Per Plate) Peak Plate Current (Per Plate)	880 max 3004 min 330 max	volts volts mA
DC Output Current	{ 110 max 30≜ min	mA mA
TYPICAL OPERATION WITH VIBRATOR-TYPE POWER SUPPLY AND CAPACITOR INPUT TO FILTER		
Peak Plate Supply Voltage (Per Plate) #	440	volts
Filter-Input Capacitor	. 8	μ F
Total Effective Plate Supply Impedance (Per Plate)	600	ohms
DC Output at Input to Filter	310	volts
DC Output Current	100	mA
CHARACTERISTICS		
Tube Voltage Drop for current of 110 mA (Per Plate)	24	volts
MINIMUM CIRCUIT VALUE		
Total Effective Plate-Supply Impedance (Per Plate)	300	ohms
Absolute value. Under no circumstances should the tube be operated	below the valu	e shown.

Refer to chart at end of section.	OZ4G
Refer to chart at end of section.	1A3
Refer to chart at end of section.	1A4P
Refer to chart at end of section.	1A5GT
Refer to chart at end of section.	1A6
Refer to chart at end of section.	1A7GT
Refer to chart at end of section.	TAC5
Refer to chart at end of section.	1AD2



HALF-WAVE VACUUM RECTIFIER

1AD2A

Duodecar type used as a rectifier in high-voltage pulse circuits of color and black-and-white television receivers. Outlines section, 9A; requires duodecar 12-contact socket. Socket terminals 4 and 10 may be used as tie points for components at or near filament potential. For high-voltage and X-ray safety considerations, refer to page 93.

Filament Voltage (ac/dc) Filament Current Direct Interelectrode Capacitance (Approx.): Plate to Filament Pulsed Rectifier For operation in a 525-line, 30-frame system MAXIMUM RATINGS (Design-Maximum Values)	1,25 0,2 1.6	volts ampere pF
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current Filament Voltage: Absolute-maximum value Absolute-minimum value	26000 • 50 0.5 1.45 1.05	volts mA mA volts volts
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop for plate current of 7 mA X-RADIATION CHARACTERISTIC	225	volts
X-Radiation, Maximum: Statistical value controlled on a lot sampling basis # Pulse duration must not exceed 15% of a horizontal scanning cy The dc component must not exceed 22000 volts. Caution—Operation of this tube outside of the maximum values indi in either temporary or permanent changes in the X-radiation char Equipment design must be such that these maximum values are no	cated above	man waan14

IAD5

Refer to chart at end of section.

IAX2

Refer to chart at end of section.

1AY2

Refer to chart at end of section.

1AY2A

HALF-WAVE VACUUM RECTIFIER

Miniature type used to supply high voltage to the anode of the picture tube in television receivers. Outlines section, 33A; requires 2-contact socket. For high-voltage and X-ray safety considerations, refer to page 93.



mR/hr

Filament Voltage (ac/dc) Filament Current	1.25 0.2	volts ampere
Direct Interelectrode Capacitances: Plate to Filament	1.4	рF

Flyback Rectifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current	26000* 50 0.5	volts mA mA
Filament Voltage: Absolute-maximum value Absolute-minimum value		volts volts
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop for plate current of 7 mA	100	volts

X-RADIATION CHARACTERISTIC


* The dc component must not exceed 22000 volts.

Caution—Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

Refer to chart at end of section.
For replacement use type 1G3GTA/1B3GT.

volts

Refer to chart at end of section.	1B4P
Refer to chart at end of section.	1B5/25S
Refer to chart at end of section.	1B7GT
Refer to chart at end of section.	1BC2



MAXIMUM RATINGS (Design-Maximum Values)

Peak Inverse Plate Voltage#

HALF-WAVE VACUUM RECTIFIER

1BC2A

18000▲

Miniature type used as a high-voltage rectifier to supply power to the anode of the television picture tube. Outlines section, 7E. For high-voltage and X-ray safety considerations, refer to page 93. Heater: volts (ac/dc), 1.25; amperes, 0.2.

Flyback Rectifier

For operation in a 525-line, 30-frame system

Average Plate Current	0.5	mA mA
Filament Voltage: Absolute-maximum value Absolute-minimum value	1.45 1.05	volts volts
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop for plate current of 7 mA	80	volts
X-RADIATION CHARACTERISTIC		
X-Radiation, Maximum: Statistical value controlled on a lot sampling basis	0.5	mR/hr
#Pulse duration must not exceed 15% of a horizontal scanning cycle	(10	microseconds).
▲ The dc component must not exceed 15000 volts.		


Caution—Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

Refer to chart at end of section.	1BH2 1BH2A
Refer to chart at end of section.	1C5GT
Refer to chart at end of section.	1C6
Refer to chart at end of section.	1C7G
Refer to chart at end of section.	1C21
Refer to chart at end of section.	1D5GP 1D5GT
Refer to chart at end of section.	1D7G
Refer to chart at end of section.	1D8GT
Refer to chart at end of section.	1DG3

1DG3A

HALF-WAVE VACUUM RECTIFIER

Glass octal type used as a high-voltage rectifier to supply power to the television picture tube. Outlines section, 14J; requires octal socket. Socket terminals 1 and 7 may be used as tie points for components at or near filament potential. For high-voltage and X-ray safety considerations, refer to page 93. Filament: volts (ac/dc), 1.25; ampere, 0.2.



Flyback Rectifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current Filament Voltage:	26000● 50 0.5	volts mA mA
Absolute-maximum value Absolute-minimum value	1.45 1.05	volts volts
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop for plate current of 7 mA	0.07	
X-RADIATION CHARACTERISTIC	225	volts
X-Radiation, Maximum: Statistical value controlled on a lot sampling basis	0.5	mR/hr
# Pulse duration must not exceed 1500 of a horizontal assuming such		

Pulse duration must not exceed 15% of a horizontal scanning cycle.

• The dc component must not exceed 22000 volts.

Caution—Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

1DN5	Refer to chart at end of section.
1E5GP	Refer to chart at end of section.
1E7GT	Refer to chart at end of section.
1E8	Refer to chart at end of section.
1 F 4	Refer to chart at end of section.
1F5G	Refer to chart at end of section.
1 F 6	Refer to chart at end of section.
1 F 7G	Refer to chart at end of section.
1G3GT/ 1B3GT	Refer to chart at end of section. For replacement use type 1G3GTA/1B3GT.
1G3GTA	For replacement use type 1G3GTA/1B3GT.

1G3GTA/ 1B3GT

HALF-WAVE VACUUM RECTIFIER

Glass octal type used as a high-voltage rectifier to supply power to the anode of the television picture tube. Outlines section, 14B; requires octal socket. Socket terminals 4 and 6 may be used as tie points for components at or near filament potential. For high-voltage and X-ray safety considerations, refer to page 93. Filament: volts (ac/dc), 1.25; ampere, 0.2.



3C

Flyback Rectifier

For operation in a 525-line, 30-frame system


MAXIMUM KATINGS (Design-Maximum values)		
Peak Inverse Plate Voltage#	26000*	volts
Peak Plate Current	50	mA
Average Plate Current	0.5	mA
Filament Voltage: Absolute-maximum value Absolute-minimum value	1.45 1.05	volts volts
CHARACTERISTIC, Instantaneous Value		
Tube Voltage Drop for plate current of 7 mA	100	volts
X-RADIATION CHARACTERISTIC		
X-Radiation, Maximum: Statistical value controlled on a lot sampling basis	0.5	mR/hr
	1 (10	1-1

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

* The dc component must not exceed 21000 volts.

Caution—Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

Refer to chart at end of section.	1G4GT
Refer to chart at end of section.	1G5G
Refer to chart at end of section.	1G6GT
Refer to chart at end of section.	1H4G
Refer to chart at end of section.	1H5GT
Refer to chart at end of section.	1H6G
Refer to chart at end of section.	1J3
Refer to chart at end of section.	1J5G
Refer to chart at end of section.	1J6G 1J6GT
Refer to chart at end of section.	1K3 1K3/1J3



HALF-WAVE VACUUM RECTIFIER

1K3A/1J3

Glass octal type used as a high-voltage rectifier to supply power to the anode of the television picture tube. Outlines section, 14B; requires octal socket. Socket terminals 4 and 6 may be used as tie points for components at or near filament potential. For high-voltage and X-ray safety considerations, refer to page 93. Filament: volts (ac/dc), 1.25; ampere, 0.2.

MAXIMUM RATINGS (Design-Maximum Values)

Flyback Rectifier

For operation in a 525-line, 30-frame system

Peak Inverse Plate Voltage#	26000*	volts
Peak Plate Current	50	mA
Average Plate Current	0.5	mA
Filament Voltage:		_
Absolute-maximum value	1.45	volts
Absolute-minimum value	1.05	volts

CHARACTERISTIC, Instantaneous Value

114

Tube Voltage Drop for plate current of 7 mA	225	volts
X-RADIATION CHARACTERISTIC		4
X-Radiation, Maximum:		
Statistical value controlled on a lot sampling basis	0.5	mR/hr
# Pulse duration must not exceed 15% of a horizontal scanning cycle	(10	microseconds).

*The dc component must not exceed 22000 volts.

Caution—Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

Refer to chart at and of section

114	Refer to chart at end of section.
116	Refer to chart at end of section.
ILA4	Refer to chart at end of section.
1LA6	Refer to chart at end of section.
1LB4	Refer to chart at end of section.
1LC5	Refer to chart at end of section.
1LC6	Refer to chart at end of section.
1LD5	Refer to chart at end of section.
1FE3	Refer to chart at end of section.
1LG5	Refer to chart at end of section.
1LH4	Refer to chart at end of section.
1LN5	Refer to chart at end of section.
1N2A	Refer to chart at end of section.
1N5GT	Refer to chart at end of section.
1N6G	Refer to chart at end of section.
1P5GT	Refer to chart at end of section.
1Q5GT	Refer to chart at end of section.
1R5	Refer to chart at end of section.
1S2A/DY87	Refer to chart at end of section.
154	Refer to chart at end of section.
1\$5	Refer to chart at end of section.
174	Refer to chart at end of section.
1T5GT	Refer to chart at end of section.
1T6	Refer to chart at end of section.
1U4	Refer to chart at end of section.


Refer to chart at end of section.

1U5 IV

Refer to chart at end of section.

HALF-WAVE VACUUM RECTIFIER





Miniature type used as a doubler in high-voltage pulse rectifier circuits of black-and-white television receivers and as a focus rectifier in color television receivers. The very low power required by the filament permits the use of a rectifier transformer having small size and light weight. Outlines section, 6B; requires miniature 9-contact socket.

Filament Voltage (ac) Filament Current Direct Interelectrode Capacitance:	0.625= 0.3	volt ampere
Plate to Filament (Approx.)	0.8	pF

 Under no circumstances should the filament voltage be less than 0.525 volt or greater than 0.725 volt.

Pulsed Rectifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage#	8250•	volts
Peak Plate Current	11	mA
Average Plate Current	0.6	mA

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).


• The dc component must not exceed 7000 volts.

Refer to chart at end of section.

1X2A

Refer to chart at end of section.

1X2B 1X2B/1X2A



HALF-WAVE VACUUM RECTIFIER

1X2C

Miniature type used as a rectifier in high-voltage pulse circuits of black-and-white television receivers and as a focus rectifier in color television receivers. Outlines section, 7A; requires miniature 9-contact socket. Socket terminals 3 and 7 may be used as tie points for components at or near filament potential. For high-voltage and X-ray safety considerations, refer to page 93.

Filament Voltage (ac) Filament Current Direct Interelectrode Capacitance:	1.25 0.2	volts ampere
Plate to Filament and Internal Shield (Approx.)	1	pF

Flyback Rectifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current Filament Voltage:		volts mA mA
Absolute-maximum value Absolute-minimum value		volts volts
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop for plate current of 7 mA	80	volta

X-RADIATION CHARACTERISTIC

X-Radiation, Maximum:
Statistical value controlled on a lot sampling basis mR/hr

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

* The dc component must not exceed 18000 volts.


Caution—Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

2A3	Refer to chart at end of section.
2A5	Refer to chart at end of section.
2A6	Refer to chart at end of section.
2A7	Refer to chart at end of section.
2AF4A	Refer to chart at end of section.
2AF4B	Refer to chart at end of section.
2AF4B/2DZ4	Refer to type 6AF4A.
2AH2	Refer to chart at end of section. For replacement use type 2BU2/2AH2.
2AS2	Refer to chart at end of section.

2AS2A

HALF-WAVE VACUUM RECTIFIER

Duodecar type used as a rectifier in high-voltage pulse circuits of color television receivers. Outlines section, 9B; requires duodecar 12-contact socket. Socket terminals 4, 7, and 10 may be used as tie points for components at or near heater potential. For high-voltage and X-ray safety considerations, refer to page 93. Heater: volts (ac/dc), 2.5; amperes, 0.33.



Pulsed Rectifier

For operation in a 525-line, 30-frame system


MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current	30000• 90 1.7	volts mA mA
9	1	*****
CHARACTERISTIC, instantaneous Value Tube Voltage Drop for plate current of 7 mA	75	volts
X-RADIATION CHARACTERISTIC		

X-Radiation, Maximum: Statistical value controlled on a lot sampling basis 25

#Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). • The dc component must not exceed 24000 volts.

Caution-Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

volts



HALF-WAVE VACUUM RECTIFIER

2AV2

Miniature type used as a high-voltage, low-current pulse-operated focus rectifier in color television receivers. The filament of the tube can be operated directly across the filament winding of the horizontal-output transformer without a series voltage-dropping resistor. Outlines section, 6B; requires miniature 9-contact socket.


Filament Current	0.225	ampere
Direct Interelectrode Capacitance (Approx.): Plate to Filament	0.8	$p\mathbf{F}$
Pulsed Rectifier		
For operation in a 525-line, 30-frame system		
MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current	8250** 50 0.6	volts mA mA
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop for plate current of 1 mA	20	volts

Filament Voltage (ac)

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).
** Under no circumstances should this absolute value be exceeded; the dc component must not exceed 7000 volts.
* Under no circumstances should the filament voltage be less than 1.53 volts or greater than

2.07 volts.

Refer to chart at end of section.	2B7
Refer to chart at end of section.	2BA2
Refer to chart at end of section.	2BJ2 2BJ2A
Refer to chart at end of section.	2BN4
Refer to type 6BN4A.	2BN4A
Refer to type 2BU2/2AH2	2BU2



HALF-WAVE VACUUM RECTIFIER

2BU2/ 2AH2

Duodecar type used as a high-voltage rectifier to supply power to the anode of the picture tube in television receivers. Outlines section, 9B; requires 12-contact socket. Socket terminals 4, 10, and 11 may be used as tie points for components at or near heater potential. For high-voltage and X-ray safety considerations, refer to page 93. Heater: volts (ac/dc), 2.5; ampere, 0.33.

Flyback Rectifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current Heater Voltage:	30000• 80 1.5	volts mA mA
Absolute-maximum value Absolute-minimum value	2.9 2.1	volts volts
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop (Approx.), for plate current of 7 mA	60	volts
X-RADIATION CHARACTERISTIC		
X-Radiation, Maximum: Statistical value controlled on a lot sampling basis	0.5	mR/hr

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

• The dc component must not exceed 24000 volts.

Caution—Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

2CN3A	Refer to chart at end of section.
2CW4	Refer to type 6CW4.
2CY5	Refer to type 6CY5.

2D21
INDUSTRIAL
TYPE

GAS THYRATRON



Miniature type gas-tetrode thyratron intended for relay applications. Outlines section, 5C; requires miniature 7-contact socket.

7BN

Heater Voltage (ac/dc) Heater Current Cathode:	$^{6.3}_{0.6} \pm 10\%$	volts ampere
Heating time prior to tube conduction	10	seconds
Heater-Cathode Voltage:		
Peak value	-100 + 25	volts
Direct Interelectrode Capacitances (Approx.): Grid No. 1 to anode	0.026	_
	2.4	pF
InputOutput	1.6	pF
Ionization Time (Approx.):	1.0	pF
For conditions: dc anode volts = 100; grid-No. 1 square-pulse		
volts = 50; peak anode amp, during conduction = 0.5	0.5	
Deionization Time (Approx.):	0.0	μв
For conditions: dc anode volts = 125 ; grid-No. 1 volts = -100 ,		
grid-No. 1 resistor (ohms) = 1000 ; ac anode amp. = 0.1	35	μв
For conditions: dc anode volts = 125 ; grid-No. 1 volts = -10 ;		~~
grid-No. 1 resistor (ohms) $= 1000$, dc anode amp. $= 0.1$	75	μs
Maximum Critical Grid-No. 1 Current with an anode-supply volts		•
$(rms) = 460$, and average anode amp. $= 0.1 \dots$	0.5	μA
Anode Voltage Drop (Approx.)	8	volts
Grid-No. 1 Control Ratio (Approx.) with grid-No. 1 resistor (meg-		
ohms) = 0; grid-No. 2 volts = 0	250	
Grid-No. 2 Control Ratio (Approx.) with grid-No. 1 resistor (meg-		
ohms) = 0; grid-No. 2 resistor (megohms) = 0; grid-No. 1		
volts = 0	1000	


Relay and Grid-Controlled Rectifier Service

MAXIMUM RATINGS (Absolute-Maximum Values)

Peak Anode Voltage:		
Forward	650	volts
Inverse	1300	volts
Grid-No. 2 (Shield-Grid) Voltage:		
Peak, before anode conduction		volts
Average, during anode conduction	10	volts

Grid-No. 1 (Control-Grid) Voltage: Peak, before anode conduction Average, during anode conduction	—100 —10	volts volts
Cathode Current:		40108
Peak	0.5	ampere
Average	0.1	ampere
Fault, for duration of 0.1 sec. max.	10	
Grid-No. 2 Current:	10	amperes
Average	_L0_01	ampere
Grid-No. 1 Current:	70.01	#HIDELE
Average	1.0.01	
Ambient Temperature Range	TV.VI	ampere
remotent Temperature Mange	-10 to +90	°C

Operational Range of Critical Grid-No. 1 Voltage.



TYPICAL OPERATING CONDITIONS FOR RELAY SERVICE

RMS Anode Voltage Grid-No.2 Voltage RMS Grid-No.1 Bias Voltage□ DC Grid-No.1 Bias Voltage Peak Grid-No.1 Signal Voltage Grid-No.1-Circuit Resistance Anode-Circuit Resistance #	0 5 5 1.0	400 0 	volts volts volts volts volts megohm ohms
MAXIMUM CIRCUIT VALUE Grid-No.1-Circuit Resistance		10	megohms

Averaged over any interval of 30 seconds maximum.

Approximately 180° out of phase with the anode voltage.

Sufficient resistance, including the tube load, must be used under any conditions of operation to prevent exceeding the current ratings.

Refer to chart at end of section.	2D21W
Refer to type 6DS4.	2D\$4
Refer to type 6DV4.	2DV4
Refer to chart at end of section. For replacement use type 2AF4B/2DZ4.	2DZ4
Refer to chart at end of section.	2E5

2EG4

HIGH-MU TRIODE

Nuvistor type used as a grounded-cathode, neutralized rf amplifier in vhf tuners of television and FM receivers. Outlines section, 1; requires nuvistor socket.



INDEX=LARGE LUG -- SHORT PIN—IC 12AQ

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage	$^{1.7}_{0.6}$ $^{8}_{\pm 100}$	volts ampere seconds volts
---	---------------------------------	-------------------------------------

	TYP	E 2EG4	• •				
25 پي		Ě	ÿ—			_	
AMP 20		- 3 2 3 3	-3/	一 ツ			
ij 15		8/	/	/%	?——		
PLATE MILLIAMPERES		/	/	45	19. 13.		
5	_/		//		<i></i>	A.5—	
	4						
0	5	UK		SO 20	DO 2		nżosti

Direct Interelectrode Capacitances (Approx.):		0.92	рF
Grid to Plate Grid to Cathode, Heater, and Shell		4.3	pF
Plate to Cathode, Heater, and Shell		1.8	pF
Plate to Cathode		0.18	ρF
		1.6	pF
Heater to Cathode		1.0	p.
Class A, Amplifier	r		
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Supply Voltage	 .	300°	volts
Plate Voltage		135	volts
Grid Voltage:			
Negative-bias value		55	volts
Peak or de positive value		ő	volts
Peak or dc positive value		1.5	watts
Plate Dissipation		15	mA
Cathode Current		10	11176
		Typical	
CHARACTERISTICS AND TYPICAL OPERATION Cha	aracteristics	Typical Operation	
Ollardo Later Contract Contrac			volts
Plate Supply Voltage	aracteristics	Operation	voits volts
Plate Supply Voltage Grid Supply Voltage	110	Operation 70	volts
Plate Supply Voltage Grid Supply Voltage Cathode-Bias Resistor	110 130	Operation 70 0	volts ohms
Plate Supply Voltage Grid Supply Voltage Cathode-Bias Resistor Grid Resistor	110	70 0 	volts
Plate Supply Voltage Grid Supply Voltage Cathode-Bias Resistor Grid Resistor Amplification Factor	110 130 63	Operation 70 0 47000 68	volts ohms ohms
Plate Supply Voltage Grid Supply Voltage Cathode-Bias Resistor Grid Resistor Amplification Factor Plate Resistance (Approx.)	110 130 63 7000	70 0 47000 68 5440	volts ohms ohms ohms
Plate Supply Voltage Grid Supply Voltage Cathode-Bias Resistor Grid Resistor Amplification Factor Plate Resistance (Approx.) Transconductance	110 130 63 7000 9000	Operation 70 0 47000 68	volts ohms ohms ohms _{µmhos}
Plate Supply Voltage Grid Supply Voltage Cathode-Bias Resistor Grid Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Grid Voltage (Approx.) for plate current of 100 µA	110 130 63 7000 9000 5	70 0 47000 68 5440	volts ohms ohms ohms µmhos volts
Plate Supply Voltage Grid Supply Voltage Cathode-Bias Resistor Grid Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Grid Voltage (Approx.) for plate current of 100 \(\mu\text{A}\) Grid Voltage (Approx.) for plate current of 10 \(\mu\text{A}\)	110 130 63 7000 9000 5 6.8	70 0 47000 68 5440 12500	volts ohms ohms ohms umhos volts
Plate Supply Voltage Grid Supply Voltage Cathode-Bias Resistor Grid Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Grid Voltage (Approx.) for plate current of 100 µA Plate Current	110 130 63 7000 9000 5	70 0 47000 68 5440	volts ohms ohms ohms µmhos volts
Plate Supply Voltage Grid Supply Voltage Cathode-Bias Resistor Grid Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Grid Voltage (Approx.) for plate current of 100 \(\mu\text{A}\) Grid Voltage (Approx.) for plate current of 10 \(\mu\text{A}\)	110 130 63 7000 9000 5 6.8	70 0 47000 68 5440 12500	volts ohms ohms ohms umhos volts
Plate Supply Voltage Grid Supply Voltage Cathode-Bias Resistor Grid Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Grid Voltage (Approx.) for plate current of 100 µA Plate Current MAXIMUM CIRCUIT VALUES Grid-Circuit Resistance:	110 130 63 7000 9000 5 6.8 6.5	Operation 70 0	volts ohms ohms ohms umhos volts volts mA
Plate Supply Voltage Grid Supply Voltage Cathode-Bias Resistor Grid Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Grid Voltage (Approx.) for plate current of 100 µA Plate Current MAXIMUM CIRCUIT VALUES Grid-Circuit Resistance:	110 130 63 7000 9000 5 6.8 6.5	70 0 47000 68 5440 12500	volts ohms ohms ohms umhos volts
Plate Supply Voltage Grid Supply Voltage Cathode-Bias Resistor Grid Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Grid Voltage (Approx.) for plate current of 100 µA Grid Voltage (Approx.) for plate current of 10 µA Plate Current MAXIMUM CIRCUIT VALUES	110 130 63 7000 9000 5 6.8 6.5	Operation 70 0	volts ohms ohms ohms umhos volts volts mA

*A plate supply voltage of 300 volts may be used provided that a sufficiently large resistor is used in the plate circuit to limit the plate dissipation to 1.5 watts under any condition of

operation.

For operation at metal-shell temperatures up to 135° C.

Refer to chart at end of section.	2EN5
Refer to chart at end of section.	2ER5
Refer to type 6FH5.	2FH5
Refer to chart at end of section. For replacement use type 2GK5/2FQ5A.	2FQ5A
Refer to type 6FS5.	2F\$5
Refer to chart at end of section.	2GK5
Refer to type 6GK5.	2GK5/2FQ5A
Refer to chart at end of section. For replacement use type 2FS5.	2GU5
For replacement use type 2HM5/2HA5.	2HA5
Refer to type 6HM5/6HA5.	2HM5/2HA5
Refer to type 6HQ5.	2HQ5
Refer to chart at end of section.	3A2



HALF-WAVE VACUUM RECTIFIER

3A2A

0.5

mR/hr

Miniature type used in high-voltage rectifier circuits of small-screen black-and-white television receivers. Outlines section, 7A; requires miniature 9-contact socket. Socket terminals 1, 3, 4, 6, and 7 may be connected to terminal 9 or to a corona shield which connects to terminal 9. Terminals 3 and 7 may be used as tie points

terminal 9. Terminals 3 and 7 may be used as tie points at or near cathode potential. For high-voltage and X-ray safety considerations, refer to page 93.

Heater Voltage (ac/dc)	3.15	volts
Heater Current	0.22	ampere
Direct Interelectrode Capacitances: Plate to Cathode, Heater, and Internal Shield	1	pF
Pulsed Rectifier		
For operation in a 525-line, 30-frame system		
MAXIMUM RATINGS (Design-Maximum Ratings)		
Peak Inverse Plate Voltage#	20000	volts
Peak Plate Current	80	mĄ
Average Plate Current	1.5	mA
Absolute-maximum value	3.65	volts
Absolute-minimum value	2.65	volts
CHARACTERISTIC, instantaneous Value		
Tube Voltage Drop for plate current of 7 mA	70	volts
X-RADIATION CHARACTERISTIC		
X-Radiation, Maximum:		

• The dc component must not exceed 18000 volts.
Caution—Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

Statistical value controlled on a lot sampling basis

3A3

3A3/3B2

3A3A 3A3A/3B2 Refer to chart at end of section.

Refer to chart at end of section.


Refer to chart at end of section.

3A3B Refer to chart at end of section

3A3C

HALF-WAVE VACUUM RECTIFIER

Glass octal type used as a rectifier in high-voltage pulse circuits of color television receivers. Outlines section, 14F; requires octal socket. Socket terminals 1, 3, 4, 5, 6, and 8 may be connected to terminal 7. Socket terminals 4 and 6 may be used as tie points at or near cathode potential. For high-voltage and X-ray safety considerations, refer to page 93.



8EZ

100

volts

Heater Voltage (ac) Heater Current	3.15 0.22	volts ampere
Direct Interelectrode Capacitances: Plate to Heater, Cathode, and Internal Shield	1.5	pF

Pulsed Rectifier

MUMIXAM	RATINGS	(Design-Maximum	Values)
Dank Town	Di-4- 1	7-14	

Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current	100	volts mA mA
Heater Voltage: Absolute-maximum value Absolute-minimum value	3.65 2.65	volts volts
CHARACTERISTIC, Instantaneous Value		

Tube Voltage Drop (Approx.) for plate current of 7 mA

X-RADIATION CHARACTERISTIC

3A4


Refer to chart at end of section.

3A5

H-F TWIN TRIODE

Miniature type twin triode used as a A-F power amplifier or an R-F power amplifier or oscillator. Each triode can be used independently of the other. Outlines section, 5C; requires miniature 7-contact socket.

Filament Arrangement Series*
Filament Voltage (dc) 2.8
Filament Current 0.11



Parallel**

0.22

volts


Direct Interelectrode Capacitances: Grid to Plate Grid to Filament Plate to Filament Plate to Plate	Unit No. 1 3.2 0.9 1.0	Unit No. 2 3.2 0.9 1.0	pF pF pF pF
A-F Power Amplifier (Each	Unit)		
MAXIMUM RATINGS (Design-Center Values)			
Plate Voltage Plate Current Plate Dissipation		135 5 0.5	volts mA watt
CHARACTERISTICS			
Plate Voltage Grid Voltage Amplification Factor Plate Resistance Transconductance Plate Current		90 2.5 15 8300 1800 3.7	volts volts ohms µmhos mA
R-F Power Amplifier and Oscillator—C Key-down conditions per tube without			
MAXIMUM RATINGS (Design-Center Values)			
DC Plate Voltage DC Grid Voltage DC Plate Current (per unit) DC Grid Current (per unit) Plate Input (per unit) Plate Dissipation (per unit)		135 30 15 2.5 2.0 1.0	volts volts mA mA watts watt
TYPICAL OPERATION (At 40 MHz With Both Units In Pu	sh-Pull)		
DC Plate Voltage		135 ∫20	volts volts
Peak R-F Grid-to-Grid Voltage DC Plate Current DC Grid Current (approx.) Driving Power (approx.) Power Output (approx.) * Filament voltage applied across two sections in series be voltage is referred to pin No. 1. For series filament open		4000 570 90 30 5 0.2 2 No. 1 and N	ohms ohms volts mA mA watt watts o. 7. Grid
connected across the section between pins No. 1 and No rent in this section. The value of the shunting resistor voltage across the shunted section equal to the voltage No. 4 and No. 7. When other tubes in series-filament a ment current of the 3A5, an additional shunting resist No. 1 and No. 7.	. 4. to by-present should be across the crangement or may be	e adjusted to e section bety t contribute to required bety	make the ween pins the fila- ween pins
** Filament voltage applied across the two sections in pa No. 1 and No. 7 connected together. Grid voltage is refe together.	called between red to pin	en pin No.4 as No.1 and I	and pins No. 7 tied
 Obtained by grid resistor (4000), cathode resistor (570), 	or fixed s	upply.	
Refer to chart at end of section.		3A8G	т
Refer to chart at end of section.		3AF4	4
Refer to type 6AF4A.		3AF4A/3	DZ4
Refer to type 6AL5.		3AL5	
Refer to chart at end of section.		3AT2	

3AT2B

HALF-WAVE VACUUM RECTIFIER

Duodecar type used as a high-voltage rectifier to supply power to the anode of the television picture tube. Outlines section, 9B; requires duodecar 12-contact socket. Socket terminals 4, 7, and 10 may be used as tie points for components at or near filament potential. For high-voltage and X-ray safety considerations, refer to page 93. Heater: volts (ac/dc), 3.15; ampere, 0.22.

MAXIMUM RATINGS (Design-Maximum Values)



Flyback Rectifier

For operation in a 525-line, 30-frame system

manifest values,		
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current Heater Voltage:	38000* 88 1.7	volts mA mA
Absolute-maximum value Absolute-minimum value	3.65 2.65	volts volts
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop for plate current of 7 mA	60	volts
X-RADIATION CHARACTERISTIC		
X-Radiation, Maximum: Statistical value controlled on a lot sampling basis	25	mR/hr

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

The dc component must not exceed 30000 volts.

Caution—Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

3AU6

Refer to type 6AU6A.

3AV6

Refer to chart at end of section.


3AW2

Refer to chart at end of section.

3AW2A

HALF-WAVE VACUUM RECTIFIER

Duodecar type used as a high-voltage rectifier to supply power to the anode of the picture tube in color and black-and-white television receivers. Outlines section, 9B; requires duodecar 12-contact socket. Socket terminals 4, 7, and 10 may be used as tie points at or near heater potential. For high-voltage and X-ray safety considerations, refer to page 93. Heater: volts (ac/dc), 3.15; ampere, 0.35.



Pulsed Rectifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage#	38000•	volts
Peak Plate Current	110	mA
Average Plate Current	2.2	mA
Heater Voltage:		
Absolute-maximum value	3.65	volts
Absolute-minimum value	2.65	volts
CHARACTERISTIC, Instantaneous Value		
Tube Voltage Drop for plate current of 7 mA	60	volts

X-RADIATION CHARACTERISTIC

X-Radiation, Maximum:		•
Statistical value controlled on a lot sampling basis	25	mR/hr
# Pulse duration must not exceed 15% of a horizontal scanning cycle	(10	microseconds).
• The dc component must not exced 30000 volts.		

sult in ihe. Equ

ution—Operation of this tube outside of the maximum values in either temporary or permanent changes in the X-radiation cl uipment design must be such that these maximum values are	ndicated above may res haracteristic of the tu not exceeded.
Refer to chart at end of section.	3AW3
Refer to chart at end of section.	3B2
Refer to chart at end of section.	3B4WA
Refer to chart at end of section.	3BA6
Refer to chart at end of section.	3BC5
Refer to type 6BC5.	3BC5/3CE5
Refer to chart at end of section.	3BE6
Refer to chart at end of section.	3BL2
Refer to chart at end of section.	3BL2A
Refer to chart at end of section.	3BM2
Refer to chart at end of section.	3BN2
Refer to chart at end of section.	3BN2A
Refer to chart at end of section.	3BN4
Refer to type 6BN4A.	3BN4A
Refer to type 6BN6.	3BN6
Refer to chart at end of section. For replacement use type 3BW2/3BS2A/3BT2.	3BS2A
For replacement use type 3BW2/3BS2A/3BT2.	3BT2
Refer to chart at end of section.	3BU8
Refer to type 6BU8.	3BU8/3GS8
For replacement use type 3BW2/3BS2A/3BT2.	3BW2

3BW2/ 3BS2A/ **3BT2**

NC (4

12HY

HALF-WAVE

VACUUM RECTIFIER

Duodecar type used as a high-voltage rectifier to supply power to the anode of the picture tube in color television receivers. Outlines section, 9B; requires octal socket. Socket terminals 4 and 10 may be used as tie points for components at or near heater potential. For high-voltage and X-ray safety considerations, refer to page 93.

Heater Voltage (ac/dc) Heater Current		volts ampere
Direct Interelectrode Capacitance (Approx.): Plate to Cathode, Heater, and Internal Shield	1.6	pF

Flyback Rectifier

or operation in a 525-line, 30-frame system

FOr operation in a 323-line, 30-liame system		
MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current	38000● 110 2.2	volts mA mA
Heater Voltage: Absolute-maximum value Absolute-minimum value	3.65 2.65	volts volts
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop (Approx.), for plate current of 7 mA	70	volts
X-RADIATION CHARACTERISTIC X-Radiation, Maximum: Statistical value controlled on a lot sampling basis	25	mR/hr
#Pulse duration must not exceed 15% of a horizontal scanning cycl	е.	

The dc component must not exceed 30000 volts.

Caution-Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

3BY6

Refer to chart at end of section. For replacement use type 3CS6.

3BZ6

Refer to type 6BZ6.

3CA3

Refer to chart at end of section.

3CA3A

HALF-WAVE VACUUM RECTIFIER

Glass octal type used as a rectifier in high-voltage pulse circuts of color television receivers. Outlines section, 14E; requires octal socket. Socket terminals 1, 3, 4, 5, 6, and 8 may be connected to terminal 7 or to a corona shield which connects to terminal 7. Socket terminals 4 and 6 may be used as tie points at or near cathode potential. For high-voltage and X-ray safety considerations, refer to page 93.



8MH

Heater Voltage (ac) Heater Current	3.6 0.225	volts ampere
Direct Interelectrode Capacitance (Approx.): Plate to Heater, Cathode, and Internal Shield	1.6	pF

Pulsed Rectifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current	100	volts mA mA
Heater Voltage: Absolute-maximum value Absolute-minimum value		volts volts
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop for plate current of 11 mA	60	volts


X-RADIATION CHARACTERISTIC

X-Radiation, Maximum: Statistical value controlled on a lot sampling basis 25 # Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

The dc component must not exceed 30000 volts.

Caution—Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

For replacement use type 3CB6/3CF6.	3CB6
Refer to type 6CB6A.	3CB6/3CF6 `
Refer to chart at end of section. For replacement use type 3BC5/3CE5.	3CE5
Refer to chart at end of section. For replacement use type 3CB6/3CF6.	3CF6
Refer to chart at end of section.	3CN3A



HALF-WAVE VACUUM RECTIFIER

3CN3B

Glass octal type used as a high-voltage rectifier to supply power to the anode of the picture tube in color and black-and-white television receivers. Outlines section, 14F; requires octal socket. Socket terminals 4 and 6 may be used as tie points for components at or near heater potential. For high-voltage and X-ray safety

Consideration	s, refer to page to:		
	(ac/de)	3.15 0.48	volts ampere

Flyback Rectifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current		volts mA mA
Heater Voltage: Absolute-maximum value Absolute-minimum value	3.65 2.65	volts volts
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop for plate current of 7 mA	60	volts
X-RADIATION CHARACTERISTIC		

. The dc component must not exceed 30000 volts.

Caution—Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

Refer to type 6CS6.

3CS6



X-Radiation, Maximum:

BMK

HALF-WAVE VACUUM RECTIFIER

3CU3A

Glass octal type used as a rectifier in high-voltage circuits of color and black-and-white television receivers. Because of its fast warm-up time it is particularly suited for transistorized systems. Outlines section, 14F; requires octal socket. Socket terminals 4 and 6 may be used as tie points. For high-voltage and X-ray safety considerations, refer to page 93.

Filament Voltage: Filament Current (ac) Direct Interelectrode Capacitance:	3.15 0.28	volts ampere
Plate to Filament and Shield	1.5	pF

Pulsed Rectifier


For operation in a 525-line, 30-frame system		
MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage#	3000■	volts
Peak Plate Current	100	mA
Average Plate Current	2	mA
Filament Voltage: Absolute-maximum value	3.65	volts
Absolute-maximum value	2.65	volts
About te-maximum value	2.00	¥0108
CHARACTERISTIC, instantaneous Value		
Tube Voltage Drop for plate current of 7 mA	50	volts
X-RADIATION CHARACTERISTIC		
X-Radiation. Maximum:		
Statistical value controlled on a lot sampling basis	25	mR/hr
#Pulse duration must not exceed 15% of a horizontal scanning cycle	(10 mic	roseconds).
The dc component must not exceed 30000 volts.		
Caution—Operation of this tube outside of the maximum values indicate in either temporary or permanent changes in the X-radiation charact Equipment design must be such that these maximum values are not experience.	eristic of	

3CX3	Refer to chart at end of section. For replacement use type 3DA3/3DH3.
3CY3	For replacement use type 3DB3/3CY3.
3CY5	Refer to type 6CY5.
3CZ3	For replacement use type 3CZ3A.

3CZ3A

HALF-WAVE VACUUM RECTIFIER

Glass octal type for use in the high-voltage rectifier circuits of television receivers and in other high voltage applications. Outlines section, 34A; requires octal socket. Socket terminals 1, 3, 4, 5, 6, and 8 may be connected to socket terminal 7. Socket terminals 4 and 6 may be used as tie points for components at or near heater potential. For high-voltage and X-ray safety considerations, refer to page 93.



to page 93.		8E	Z
Heater Current	Time	3.15 0.48 4	volts ampere seconds
Direct Interelecti	rode Capacitance: ter, Cathode, and Internal Shield		pF

Pulsed Rectifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current	38000 • 110 2.2	volts mA mA
Heater Voltage: Absolute-maximum value Absolute-minimum value	3.65 2.65	volts volts
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop for plate current of 7 mA	60	volts


X-RADIATION CHARACTERISTIC X-Radiation, Maximum:

Statistical value of	controlled on	a lot sai	mpling basis		25	mH/hr
# Pulse duration must				scanning cycle	(10	microseconds).

Caution—Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the K-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded. Refer to chart at end of section.

3DA3/3DH3 **3DB3**

Refer to type 3DB3/3CY3.



HALF-WAVE **VACUUM RECTIFIER**

3DB3/3CY3

Octal type used as a high-voltage rectifier to supply power to the anode of the television picture tube. Outlines section, 14F; requires octal socket. Socket terminals 3, 4, 5, 6, and 8 should not be used as tie points although terminals 3, 5, and 8 may be connected to terminal 7. For high-voltage and X-ray safety considerations, refer to page 93.


Heater Voltage	3.15	volts
Heater Current	0.245	ampere
Direct Interelectrode Capacitance (Approx.): Plate to Heater, Cathode, and Internal Shield	1.5	pF

Flyhack Rectifier

i iyaaan naaciiia		
For operation in a 525-line, 30-frame system		
MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current Henter Voltage:	38000● 100 2	volts mA mA
Absolute maximum value Absolute minimum value	3.65 2.65	volts volts
CHARACTERISTIC, Instantaneous Value		
Tube Voltage Drop for plate current of 7 mA	100	volts
X-RADIATION CHARACTERISTIC X-Radiation, Maximum:	0.5	D /b
Statistical value controlled on a lot sampling basis	25	mR/hr
₱ Pulse duration must not exceed 15% of a horizontal scanning cycle. • The dc component must not exceed 30000 volts.	le (10 micre	oseconds).

Cautien—Operation of this tube outside of the maximum values indicated above may result

in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.



HALF-WAVE VACUUM RECTIFIER

3DC3

mΑ mA

Glass octal type used as a rectifier in high-voltage circuits of color and black-and-white television receivers. Because of its fast warm-up time it is particularly suited for transistorized systems. Outlines section, 14F; requires octal socket. Socket terminals 4, 6, and 8 may be used as tie points. For high-voltage and X-ray safety considerations, refer to page 93. This type is identical

with type 3CU3A except for the following items:

Pulsed Rectifier


For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)	
Peak Plate Current	110
Average Plate Current	2.2

3DF3

HALF-WAVE VACUUM RECTIFIER

Glass octal types used as a high-voltage rectifier to supply power to the anode of the picture tube in television receivers. Outlines section, 14G and 14H, respectively; requires octal socket. Socket terminals 1 and 7 may be used as tie points for components at or near heater potential. For high-voltage and X-ray safety considerations, refer to page 93. Heater: volts (ac/dc), 3.15; ampere, 0.48.



8MT

Flyback Rectifier

For operation in a 525-line, 30-frame system		
MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current Heater Voltage:	38000 ● 110 2.2	volts mA mA
Absolute maximum value Absolute-minimum value	3.65 2.65	vol ts volts
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop for plate current of 7 mA	60	volts
X-RADIATION CHARACTERISTIC X-Radiation, Maximum:		
3DF3	3DF3A	

Statistical value controlled on a lot sampling basis ...

Pulse duration must not exceed 15% of a horizontal scanning cycle.

The dc component must not exceed 30000 volts.


Caution-Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

FULL-WAVE VACUUM RECTIFIER

Glass octal type used in power supplies of color and black-and-white television receivers and other equipment having high dc requirements. Outlines section. 19E; requires octal socket. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. For discussion of Rating Chart, refer to Interpretation of Tube Data. Filament: volts (ac/dc), 3.3; amperes, 3.8.

MAYIMUM PATINCS (Decide Maximum Values)

At full-load current of 350 mA



mR/hr

volts

5DE


300

Full-Wave Rectifier

MAXIMUM KATINGS (Design-Maximum values)		
Peak Inverse Plate Voltage	1050	volts
Peak Plate Current (Per Plate)	1.2	
Hot-Switching Transient Plate Current (Per Plate)	6.5	amperes
AC Plate Supply Voltage (Per Plate, rms)		Rating Chart
DC Output Current (Per Plate)		Rating Chart
Bulb Temperature (At hottest point on bulb surface)	200	°C
TYPICAL OPERATION WITH CAPACITOR INPUT TO FILTER		
AC Plate-to-Plate Supply Voltage (rms)	550	volts
Filter-Input Capacitor	40	μF
Effective Plate-Supply Impedance per Plate	32	ohms
DC Output Voltage at Input to Filter (Approx.):		·
44 6 11 1 1 1 4 6 0 0 0 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		


Tube Voltage Drop for plate current of 350 mA (per plate) · Higher values of capacitance than indicated may be used, but the effective plate-supply impedance may have to be increased to prevent exceeding the maximum peak-plate-current rating.





For replacement use type 3DA3/3DH3.

3DH3



HALF-WAVE VACUUM RECTIFIER

3DJ3

Glass octal type used as a high-voltage rectifier to supply power to the anode of the picture tube in color television receivers. Outlines section, 14H; requires octal socket. Socket terminals 4 and 6 may be used as tie points for components at or near heater potential. For high-voltage and X-ray safety considerations, refer to page 93. Heater: volts (ac/dc), 3.15; ampere, 0.3.

Flyback Rectifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values) Peak Inverse Plate Voltage# Peak Plate Voltage Average Plate Current Heater Voltage: Absolute maximum value		volts mA mA volts
Absolute-minimum value	2.65	volts
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop for plate current of 7 mA	70	volts
X-RADIATION CHARACTERISTIC		
X-Radiation, maximum: Statistical value controlled on a lot sampling basis	25	mR/hr

Pulse duration must not exceed 15% of a horizontal scanning cycle.

• The dc component must not exceed 30000 volts.

Caution—Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

the design made be buch that these maximum values are	not exceeded.
Refer to type 6DK6.	3DK6
Refer to chart at end of section.	3DR3
Refer to chart at end of section.	3DS3
For replacement use type 3DT6A.	3DT6
Refer to type 6DT6A.	3DT6A
Refer to chart at end of section. For replacement use type 3AF4A/3DZ4.	3DZ4
Refer to chart at end of section. For replacement use type 3EH7/XF183.	3EA5 3EH <i>7</i>

4BQ7A

RCA RECEIVING TUBE MANUAL

3EH7/XF183 Refer to type 6EH7/EF183. Refer to chart at end of section. 3EJ7 3EJ7/XF184 Refer to type 6EJ7/EF184. **3ER5** Refer to type 6ER5. 3FH5 Refer to chart at end of section. 3FS5 Refer to type 6FS5. **3GK5** Refer to type 6GK5. Refer to chart at end of section. **3GS8** For replacement use type 3BU8/3GS8. 3GS8/3BU8 Refer to chart at end of section. Refer to chart at end of section. 3HA5 For replacement use type 3HM5/3HA5. 3HM5/3HA5 Refer to type 6HM5/6HA5. **3HQ5** Refer to type 6HQ5. 3HS8 Refer to chart at end of section. **3JC6** Refer to chart at end of section. 3JC6A Refer to type 6JC6A. 3JD6 Refer to type 6JD6. **3KT6** Refer to type 6KT6. 3LF4 Refer to chart at end of section. 3Q4 Refer to chart at end of section. **3Q5GT** Refer to chart at end of section. 354 Refer to chart at end of section. 3V4 Refer to chart at end of section. **4AU6** Refer to type 6AU6A. **4AV6** Refer to type 6AV6. 4BC5 Refer to chart at end of section. Refer to type 6BC8. **4BC8** Refer to chart at end of section. 4BL8 4BL8/XCF80 Refer to type 6BL8/ECF80. 4BN6 Refer to type 6BN6.

For replacement use type 4BQ7A/4BZ7.


Refer to type 6BQ7A/6BZ7/6BS8.	4BQ7A/4BZ7
Refer to chart at end of section.	4B\$8
Refer to chart at end of section.	4BU8
Refer to type 6BU8.	4BU8/4G\$8
Refer to type 6BZ6.	4BZ6
Refer to chart at end of section. For replacement use type 4BQ7A/4BZ7.	4BZ7
Refer to type 6CB6A.	4CB6
Refer to type 6CS6.	4CS6
Refer to chart at end of section.	4CY5
Refer to type 6DE6.	4DE6
Refer to type 6DK6.	4DK6
Refer to chart at end of section.	4DT6
Refer to type 6DT6A.	4DT6A
Refer to chart at end of section.	4EH7
Refer to type 6EH7/EF183.	4EH7/LF183
Refer to chart at end of section.	4EJ <i>7</i>
Refer to type 6EJ7/EF184.	4EJ7/LF184
Refer to chart at end of section.	4ES8
Refer to chart at end of section. For replacement use type 4KN8.	4ES8/XCC189
Refer to chart at end of section. For replacement use type 4LU6.	4EW6
Refer to type 6GK5.	4GK5
Refer to type 6GJ7/ECF801.	4GJ7/XCF801
Refer to chart at end of section.	4GM6
Refer to chart at end of section. For replacement use type 4BU8/4GS8.	4G\$8
Refer to chart at end of section.	4GS8/4BU8
Refer to chart at end of section.	4GX7
Refer to chart at end of section.	4GZ5
Refer to chart at end of section. For replacement use type 4HM5/4HA5.	4HA5
Refer to chart at end of section. For replacement use type 4HM5/4HA5.	4HA5/PC900
Refer to chart at end of section.	4HA7

4HA7/4HC7	Refer to chart at end of section.
4HC7	Refer to chart at end of section.
4HM5/4HA5	Refer to type 6HM5/6HA5.
4HM6	Refer to chart at end of section.
4HQ5	Refer to type 6HQ5.
4HS8	Refer to type 6HS8.
4HT6	Refer to chart at end of section.
4JC6	Refer to chart at end of section.
4JC6A	Refer to type 6JC6A.
4JD6	Refer to type 6JD6.
4JH6	Refer to type 6JH6.
4KE8	Refer to type 6KE8.
4KN8/4RHH8	Refer to chart at end of section.
4KT6	Refer to type 6KT6.
4LJ8	Refer to type 6LJ8.
4LU6	Refer to chart at end of section.
4MK8	Refer to type 6MK8A.
4RHH2	For replacement use type 4BQ7A/4BZ7
4RHH8	For replacement use type 4KN8/4RHH8.
5AM8	Refer to type 6AM8A.
5AN8	Refer to type 6AN8A.
5AQ5	Refer to type 6AQ5A.

5AR4/ GZ34

FULL-WAVE VACUUM RECTIFIER

Glass octal type used in power supply of television receivers and other equipment having high dc requirements. Outlines section, 13F; requires octal socket. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. Heater: volts (ac/dc), 5; amperes, 1.9.




Full-Wave Rectifier

MAYIMILM	DATINGS	(Design-Maximum	Values
MAXIMUM	RAIINGS	idesign-maximum	valuesi

Peak Inverse Plate Voltage
Peak Plate Current (Per Plate)
Hot-Switching Transient Plate Current (Per Plate)
AC Plate-Supply Voltage (Per Plate, rms, without load)
Average Output Current (Per Plate)


1700 volts
825 mA
3.7 amperes
See Rating Chart
See Rating Chart

TYPICAL OPERATION WITH CAPACITOR INPUT TO FILTI	ER		
AC Plate-to-Plate Supply Voltage (rms)	450	550	volts
Effective Plate-Supply Impedance per Plate	160	200	ohms
Average Output Current	2 2 5	160	mA
DC Output Voltage at Input to Filter	475	620	volts
TYPICAL OPERATION WITH CHOKE INPUT TO FILTER			
AC Plate-to-Plate Supply Voltage (rms)	450	550	volts
Filter Input Choke	10	10	henries
Average Output Current	250	225	mA
DC Output Voltage at Input to Filter	375	465	volts
CHARACTERISTIC, Instantaneous Value			
Tube Voltage Drop for plate current of 225 mA			
(Per Plate)	_	17	volts



Refer to chart at end of section.

5AS4



FULL-WAVE VACUUM RECTIFIER

5AS4A

Glass octal type used in power supplies of television receivers having high dc requirements. Outlines section, 19D; requires octal socket. This type may be supplied with pins 3, 5, and 7 omitted. Vertical mounting is preferred, but horizontal mounting is permissible if pins 2 and 4 are in vertical plane. It is especially important that this tube, like other power-handling tubes, be ade-


quately ventilated. Heater: volts (ac), 5; amperes, 3. For maximum ratings, typical operation, and curves, refer to type 5U4GB.

Refer to chart at end of section.	5AS8
Refer to type 6AT8A.	5AT8
Refer to chart at end of section. For replacement use type 5V3A/5AU4.	5AU4
Refer to chart at end of section.	5AV8
Refer to chart at end of section.	5AW4
Refer to chart at end of section.	5AZ4
Refer to chart at end of section.	5B8
Refer to chart at end of section.	5BC3

5BC3A

FULL-WAVE VACUUM RECTIFIER

Novar types used in power supplies of radio equipment and television receivers having high dc requirements. Outlines section, 31C; requires novar 9-contact




socket. Vertical operation is preferred, but tubes may be operated in horizontal position if pins 2 and 7 are in vertical plane. It is especially important that these tubes, like other power-handling tubes, be adequately ventilated. Filament: volts (ac), 5; amperes, 3.

Full-Wave Rectifier

MAXIMUM RATINGS (Design-Maximum Values) Peak Inverse Plate Voltage Peak Plate Current (Per Plate) Hot-Switching Transient Plate Current (Per Plate) AC Plate-Supply Voltage (Per Plate, rms) Average Output Current (Per Plate)				volts amperes amperes ating Chart ating Chart
TYPICAL OPERATION WITH CAPACITOR INPUT TO F	ILTER			
AC Plate-to-Plate Supply Voltage (rms) Filter-Input Capacitor Total Effective Plate-Supply Impedance per Plate	600 40 21	900 40 67	1100 40 97	volts µF ohms
DC Output Voltage at Input to Filter (Approx.): At load current of: 300 mA	290	460	_	volts volts
162 mA 150 mA 137.5 mA	335		630	voits voits voits
81 mA	_	-	680	volts
TYPICAL OPERATION WITH CHOKE INPUT TO FILTE	R			
AC Plate-to-Plate Supply Voltage (rms)		900 10	1100 10	volts henries
At load current of: 348 mA		340 355	440	volts volts volts
174 mA			445	voits

If hot switching is regularly required in operation, the use of choke-input circuits is recommended. Such circuits limit the hot-switching current to a value no higher than that of the peak plate current. When capacitor-input circuits are used, a maximum peak current value per plate of 5 amperes during the initial cycles of the hot-switching transient should not be exceeded.

Higher values of capacitance than indicated may be used, but the effective plate-supply impedance may have to be increased to prevent exceeding the maximum rating for peak plate current.



	_
Refer to chart at end of section.	5BE8
Refer to type 6BK7B.	5BK7A
Refer to type 6BQ7A.	5BQ7A
For replacement use type 5BR8/5FV8.	5 BR8
Refer to type 6BR8A.	5BR8/5FV8
Refer to chart at end of section.	5BT8
Refer to chart at end of section.	5BW8
Refer to type 6CG8A.	5CG8
Refer to chart at end of section.	5CL8
Refer to type 6CL8A.	5CL8A
Refer to chart at end of section.	5CM8
Refer to chart at end of section.	5CQ8
Refer to type 6CZ5.	5CZ5
Refer to chart at end of section.	5DH8
Refer to chart at end of section.	5DJ4
Refer to type 6EA8.	5EA8
Refer to chart at end of section.	5 ES8 5ES8/YCC189
Refer to chart at end of section.	5EU8
Refer to type 6EW6.	5EW6
Refer to type 6FG7.	5FG7
Refer to chart at end of section. For replacement use type 5BR8/5FV8.	5 FV8
Refer to type 6GH8A.	5GH8A
Refer to chart at end of section.	5GJ7
Refer to 6GJ7/ECF801.	5GJ7/LC F8 01
Refer to type 6GM6.	5GM6
Refer to type 6GS7.	5G\$7
Refer to chart at end of section. For replacement use type 5HZ6.	5GX6
Refer to chart at end of section.	5GX7
Refer to chart at end of section.	5HA7
Refer to type 6HB7.	5HB7

5HG8	Refer to chart at end of section.
5HG8/LCF86	Refer to type 6HG8/ECF86.
5HZ6	Refer to type 6HZ6.
5J6	Refer to type 6J6A.
5JK6	Refer to chart at end of section.
5JL6	Refer to chart at end of section.
5JW8	Refer to type 6JW8/ECF802.

5KD8

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used as combined vhf oscillator and mixer tube in television receivers. Outlines section, 6B; requires miniature 9-contact socket.



Heater Voltage (ac/dc) Heater Current Heater Warm-up Time	5.6 0.45 11	volts ampere seconds
Heater-Cathode Voltage: Peak value Average value	±200 max 100 max	volts volts

Class A. Amplifier

	-		
MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit	Pentode Unit	
Plate Voltage	830	330	volts
Grid-No.2 (Screen-Grid) Supply Voltage	<u> </u>	330	volts
Grid-No.2 Voltage		See curve pag	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	0	volts
Plate Dissipation	2.5	ä	watts
Grid-No.2 input:		•	
For grid-No.2 voltages up to 165 volts	_	0.55	watt
For grid-No.2 voltages between 165 and 330 volts	_	See curve pag	e 300
		200 00010 100	
CHARACTERISTICS			
Plate Voltage	1 2 5	125	volts
Grid-No.2 Voltage	_	110	volts
Grid-No.1 Voltage	1	—i	volt
Amplification Factor	40	_	
Plate Resistance (Approx.)	=	0.2	megohm
Transconductance	7500	5000	μmhos
Plate Current	18.5	9.5	· mA
Grid-No.2 Current		3.5	mA
Grid-No.1 Voltage (Approx.) for plate current of			
20 μΑ	9	-8	volts
- ·			
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
For fixed-bias operation		0.5	megohm
For cathode-bias operation		1	megohm

5KE8

Refer to type 6KE8.

5KZ8

Refer to type 6KZ8.

Refer to type 6LJ8.

5LJ8

Refer to type 6MB8.


5MB8

For replacement use type 5J6.

5MHH3

Refer to type 6MQ8.

5MQ8



FULL-WAVE VACUUM RECTIFIER

5R4GB

Glass octal type for industrial and military applications. Outlines section, 19D; requires octal socket.


Filament	Voltage	(ac/dc)	. 5 volts
Filament	Current		2 amperes
Operating	Position	n Vertical, base of	lown or up, or Horizontal 2 and 4 in vertical plane
		with pins	2 and 4 in vertical plane

Full-Wave Rectifier

Full-Maye Rectifier				
MAXIMUM RATINGS (Absolute-Maximum Values) For altitudes up to Peak Inverse Plate Voltage AC Plate Supply Voltage Per Plate (RMS, without load) Peak Plate Current Per Plate DC Output Current Per Plate	715	20000 3100 ee Rating 715 ee Rating		feet volts mA
Hot-Switching Transient Plate Current Per Plate Bulb Temperature (At hottest point on bulb surface)	230	230		°C
TYPICAL OPERATION (With Capacitor-Input Filter)				
• • •	4000			
For altitudes up to	40000		20000	feet
AC-Plate-to-Plate Supply Voltage (RMS, without load)	1400	1500	2000	volts
Filter-Input Capacitor	20	20	20	μ F
Total Effective Plate Supply Impedance Per Plate** DC Ouptut Voltage at Input to Filter (approx.):	225	250	375	ohms
At half-load current of \$75 mA		910	1210	volts
At man-load current of 1125 mA	750			volts
125 mA		800	1040	volts
1250 mA	605		_	volts
Voltage Regulation (approx.):			150	1.
Half-load to full-load current	145	110	170	volts
DC Ouput Current	250	150	150	mA
TYPICAL OPERATION (With Choke-Input Filter)				
For altitudes up to	40000	20000		feet
AC Plate-to-Plate Supply Voltage (RMS, without load)	1500	1900		volts
Filter-Input Choke	5	10		henries
DC Output Voltage at Input to Filter for dc output (approx.):				
87.5 mA		800		volts
125 mA	600	_		volts
175 mA		760		volts
250 mA	560			volts
Voltage Regulation (Approx.):				
Half-load to full-load current	40	40		volts
DC Output Current	250	175		mA
• Id has a witching in magniful in conception, wholes imput	airanita	8 FO FOO	mmandad	Such

If hot-switching is required in operation, choke-input circuits are recommended. Such circuits limit the hot-switching current to a value no higher than that of the peak plate current. When capacitor-input circuits are used, a maximum value of 3 amperes should not be exceeded.

** Indicated values for conditions shown will limit peak plate current to the maximum-rated value. When a filter-input capacitor larger than 20 \(\mu f \) is used, it may be necessary to increase plate-supply impedance to a higher value than that shown in the data to limit the peak plate current to the maximum-rated value.



5R4GY 5R4GYB

For replacement use type 5R4GB.

5T4

Refer to chart at end of section.

5T8 5U4G Refer to type 6T8A.

Refer to chart at end of section.

5U4GB

FULL-WAVE VACUUM RECTIFIER

Glass octal type used in power supplies of radio and color and black-and-white television receivers having high dc requirements. Outlines section, 19E; requires octal socket. This type may be supplied with pins 3, 5, and 7 omitted. Vertical mounting is preferred, but horizontal mounting is permissible if pins 2 and 4 are in vertical plane. The coated filament is designed to


MAXIMUM RATINGS (Design-Maximum Values)



operate from the ac line through a step-down transformer. The voltage at the filament terminals should be 5 volts at an average line voltage of 117 volts. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. For discussion of Rating Chart and Operation Characteristics, refer to Interpretation of Tube Data. Filament: volts (ac), 5; amperes, 3.

Full-Wave Rectifier


Peak Inverse Plate Voltage			1550	volts
Peak Plate Current (Per Plate)			# 1	ampere
AC Plate Supply Voltage (Per Plate, rms) Average Output Current (Per Plate)			See R	ting Chart
TYPICAL OPERATION WITH CAPACITOR INPUT TO	FILTER			
AC Plate-to-Plate Supply Voltage (rms)	600	900	1100	volts
Filter-Input Capacitor*	40	40	40	μ F
Total Effective Plate-Supply Impedance per Plate	21	67	97	ohms
DC Output Voltage at Input to Filter (Approx.):				
[150 mA	335			volts
At full-load current of { 137.5 mA	_	520	_	volts
(81 mA			680	volts
300 mA	290	_		volts
At half-load current of { 275 mA	_	460	_	volts
162 mA			630	volts
Voltage Regulation (Approx.):				
Half-load to full-load current	45	60	50	volts




TYPICAL OPERATION WITH CHOKE INPUT TO FILTER

ITPICAL OPERATION WITH CHOKE INPUT TO FILTER			
AC Plate-to-Plate Supply Voltage (rms)	900 10	1100 10	volts henries
At half-load current of { 174 mA 137.5 mA	355	455	volts volts
At full-load current of { 348 mA	340 —	440	volts volts
Half-load to full-load current	15	15	volts

- # If hot switching is regularly required in operation, the use of choke-input circuits is recommended. Such circuits limit the hot-switching current to a value no higher than that of the peak plate current. When capacitor-input circuits are used, a maximum peak current value per plate of 4.6 amperes during the initial cycles of the hot-switching transient should not be exceeded.
- Higher values of capacitance than indicated may be used, but the effective plate-supply impedance may have to be increased to prevent exceeding the maximum rating for peak plate current.





5U8

Refer to type 6U8A.

5U9/LCF201

Refer to chart at end of section.

5V3

Refer to chart at end of section. For replacement use type 5V3A/5AU4.


5V3A

For replacement use type 5V3A/5AU4.

5V3A/5AU4

FULL-WAVE VACUUM RECTIFIER

Glass octal type used in power supplies of color and black-and-white television receivers and other equipment having high dc requirements. Outlines section, 19E; requires octal socket. Vertical mounting is preferred, but horizontal mounting is permissible if pins 2 and 4 are in vertical plane. It is especially important that this tube, like other power-handling tubes, be ade-



quately ventilated. For discussion of Rating Chart, refer to Interpretation of Tube Data. Filament: volts (ac/dc), 5; amperes, 3.

Full-Wave Rectifier


MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage	1550	volts
Peak Plate Current (Per Plate)	1.4	amperes
Hot-Switching Transient Plate Current (Per Plate)	6.6	amperes
AC Plate-Supply Voltage (Per Plate, rms, without load)	550	volts
Average Output Current (Per Plate)	415°	mA
*With capacitor-input filter for ac plate-supply volts (rms, per plate,	without los	d) = 470.


TYPICAL OPERATION

Filter Input	Capacitor	Choke	
AC Plate-to-Plate Supply Voltage (rms)	850	1000	volts
Filter-Input Capacitor	40	_	μ F ohms
Effective Plate-Supply Impedance per Plate	50	_	
Minimum Filter-Input Choke		10	henries
Average Output Current	350	350	mA
DC Output at Input to Filter (Approx.)	440	390	volts

CHARACTERISTIC

Tube Voltage Drop for plate current of 350 mA (per plate) 42 volts • When capacitor values greater than 40 µF are used, the effective plate-supply impedance should be increased so that the maximum rating for peak plate current is not exceeded.





FULL-WAVE VACUUM RECTIFIER

5V4GA

SVAGT

Glass octal type used in full-wave power supplies having high dc requirements. Outlines section, 19B; requires octal socket. The heater is designed to operate from the ac line through a step-down transformer. The voltage at the heater terminals should be 5 volts under


operating conditions at an average line voltage of 117 volts. It is especially important that these tubes, like other power-handling tubes, be adequately ventilated. Heater: volts (ac/dc) 5; amperes, 2.

Full-Wave Rectifier

MAXIMUM RATINGS (Design-Center Values)		
Peak Inverse Plate Voltage	1400	volts
With capacitor-input filter		volta
With choke-input filter Peak Plate Current (Per Plate)	500 525	volts mA
Average Output Current	175	mA
TYPICAL OPERATION		

ITPICAL OPERATION			
Filter Input AC Plate-to-Plate Supply Voltage (rms)	Capacitor 750	Choke 1000	volts
Filter-Input Capacitor*	10	_	μ F
Total Effective Plate-Supply Impedance per Plate	100	_	o hms
Filter-Input Choke		4	henries
DC Output Voltage at Input to Filter (Approx.): At output current of 175 mA	410	410	volts

* Higher values of capacitance than indicated may be used, but the effective plate-supply impedance may have to be increased to prevent exceeding the maximum rating for peak plate current.



refer to chart at end of section.	34001
Refer to chart at end of section.	5W4 5W4GT
Refer to chart at end of section.	5X4G

Refer to chart at end of section

5X8

Refer to type 6X8A.


5Y3G 5Y3GA

For replacement use type 5Y3GT.

5Y3GT

FULL-WAVE VACUUM RECTIFIER


Glass octal type used in power supplies of radio and television equipment having moderate de requirements. Outlines section, 13E; requires octal socket. Vertical mounting is preferred, but horizontal mounting is permissible if pins 2 and 8 are in horizontal plane. It is especially important that this tube, like other powerhandling tubes, be adequately ventilated. For discussion



of Rating Chart and Operating Characteristics, refer to Interpretation of Tube Data. Filament: volts (ac), 5; amperes, 2.


Full-Wave Rectifier

MAXIMUM RATINGS (Design-Center Values)		
Peak Inverse Plate Voltage Peak Plate Current (Per Plate) Hot-Switching Transient Plate Current (Per Plate) AC Plate Supply Voltage (Per Plate, rms) DC Output Current (Per Plate)		volts mA amperes lating Chart lating Chart
TYPICAL OPERATION WITH CAPACITOR INPUT TO FILTER		
AC Plate-to-Plate Supply Voltage (rms) 766 Filter Input Capacitor* 20 Effective Plate-Supply Impedance per Plate 56 DC Output Voltage at Input to Filter (Approx.):	1000 10 140	voits µF ohms
At half-load current of	610 560	volts volts volts volts
Voltage Regulation (Approx.): Half-load to full-load current	50	volts
TYPICAL OPERATION WITH CHOKE INPUT TO FILTER		
AC Plate-to-Plate Supply Voltage (rms)	10 00 10	volts henries
At half-load current of { 75 mA 270 62.5 mA	405	volts volts volts
At full-load current of \ \begin{cases} 150 & mA & 245 \\ 125 & mA & \\ \ \ \ \ \ \ \ \ \ \ \ \ \	380	volts
Voltage Regulation (Approx.): Half-load to full-load current	15	volts



 Higher values of capacitance than indicated may be used but the effective plate supply impedance may have to be increased to prevent exceeding the maximum rating for hotswitching transient plate current.

#This value is adequate to maintain optimum regulation in the region to the right of line L=10H on curve OPERATION CHARACTERISTICS with Choke Input to Filter, provided the load currents are not less than 35 mA and 50 mA, respectively, for plate-to-plate supply voltages of 700 and 1000 volts (rms).



Refer to chart at end of section.	5Y4G
Refer to chart at end of section.	5Y4GA 5Y4GT
Refer to chart at end of section.	5 Z 3
Refer to chart at end of section. For replacement use type 5Y3GT.	5 Z 4
Refer to chart at end of section.	6A3
Refer to chart at end of section.	6A6
Refer to chart at end of section.	6A7
Refer to chart at end of section.	6A7S
Refer to chart at end of section.	6A8
Refer to chart at end of section.	6A8G 6A8GT

6AB4

HIGH-MU TRIODE

Miniature type used as cathode-drive amplifier, frequency converter, or oscillator at frequencies up to 300 MHz in television and FM receivers. Outlines section, 5C; requires miniature 7-contact socket. Heater: volts (ac/dc), 6.3; amperes, 0.15. For operation as resistance-coupled amplier, refer to Resistance-Coupled Amplifier section. For maximum ratings, characteristics, and curves refer to type 12AT7.



5CE

6AB5/6N5
6AB7
6AC5GT
6AC7


6AC7W

Refer to chart at end of section. Refer to chart at end of section.

6AC10 8AC10, 12AC10A

HIGH-MU TRIPLE TRIODE

Duodecar type used in matrixing (color-difference) circuits of color television receivers. Outlines section, 8B; requires duodecar 12-contact socket. Types 8AC10 and 12AC10A are identical with type 6AC10 except for heater ratings.



12FE

Heater Voltage (ac/dc) Heater Current	0.6	8AC10 8.4 0.45	12AC10A 12.5 0.3	volts ampere seconds
Heater Warm-up Time (Average)	11	11	11	seconds
Heater-Cathode Voltage: Peak value Average value		$\pm 200 \text{ max} $ 100 max	±200 max 100 max	volts volts

Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage Plate Dissipation	$^{330}_{2}$	volts watts
CHARACTERISTICS		
Plate Voltage	200	volts
Cathode-Bias Resistor	150	ohms
Amplification Factor	62	
Plate Resistance (Approx.)	10700	ohms
Transconductance	5800	μ mhos
Plate Current	5	mΑ
Grid Voltage (approx.) for plate current of 100 µA	—5	volts
MAXIMUM CIRCUIT VALUE		


6AD6G Refer to chart at end of section.
6AD7G Refer to chart at end of section.

6AD10

Grid-Circuit Resistance

BEAM POWER TUBE— SHARP-CUTOFF PENTODE

Duodecar type used as FM detector and audio-frequency output amplifier in color and black-and-white television receivers. Outlines section, 8B; requires duodecar 12-contact socket.



megohm

Heater Voltage (ac/dc)	6.3 1.05	volts amperes
Peak value	±200 max	volts
Average value	100 max	volts
Direct Interelectrode Capacitances: Beam Power Unit:		
Grid No.1 to Plate	0.26	рF
Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3,	11	рF
and Internal Shield	11	DF
and Internal Shield Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield	11	рF
Pentode Unit:	0.024	рF
Grid No.1 to Plate Grid No.3 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3,	3.4	pF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3,	_	
and Internal Shield	8	рF
Grid No.3 to Cathode, Heater, Grid No.1, Grid No.2, Plate. and Internal Shield	9.5	рF
Grid No.1 to Grid No.3	0.12	pF
Plate of Beam Power Unit to Plate of Pentode Unit	0.34	pF
Beam Power Unit as Class A. Amplifier	•	
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	275	volts
Grid-No.2 (Screen-Grid) Voltage	275 10	volts watts
Plate Dissipation	2	watts
TYPICAL OPERATION		
	250	volts
Plate Voltage	250	volts
Grid-No.1 (Control-Grid) Voltage	8	volts
Peak AF Grid-No.1 Voltage	8 35	volts mA
Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current	39	mA
Zero-Signal Grid-No.2 Current	2.5	m A
Maximum-Signal Grid-No.2 Current Plate Resistance (Approx.)	o. i	mA megohm
Transconductance	6500	μmhos
Load Resistance	5000	ohms
Total Harmonic Distortion Maximum-Signal Power Output	$\substack{\textbf{10}\\\textbf{4.2}}$	per cent watts
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.25	megohm
For cathode-bias operation	0.5	megohm
Pentode Unit as Class A, Amplifier		
CHARACTERISTICS		
Plate Supply Voltage	150	volts
Grid No.3 (Control Grid) Connected to negative	end of cathod	e resistor
Grid No.1 (Control Grid) Connected to negative	end of cathod	voits e resistor
Grid No.3 (Control Grid) Connected to negative Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control Grid) Connected to negative Cathode-Bias Resistor	180	ohms
Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.3 to Plate	V.11	meRonm
Transconductance, Grid No.3 to Plate	3400 600	μmhos μmhos
Plate Current	3.2	mA
Grid-No.2 Current	$\frac{3.2}{-4.5}$	m A volts
Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 20 μ A Grid-No.3 Voltage (Approx.) for plate current of 20 μ A	7	volts
Pentode Unit as FM Sound Detector		
MAXIMUM RATINGS (Design-Maximum Values)	900	14 .
Plate Voltage	300	volts
Negative-bias value	100	volts
Positive-hige value	25	volts
Grid-No.2 Supply Voltage Grid-No.2 Voltage Grid-No.1 Voltage:	300	volts
Grid-No.1 Voltage:	See curve	
Negative-bias value	50 0	volts volts
Positive-bias value Plate Dissipation	1.7	voits watts
Grid-No.3 Input Grid-No.2 Input:	0.1	watt
Grid-No.2 Input: For grid-No.2 voltages up to 150 volts	1	watt
For grid-No.2 voltages between 150 and 300 volts	See curve p	

6AF3

MAXIMUM CIRCUIT VALUES		
Grid-No.3-Circuit Resistance	0.68	megohm
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.22	megohm
For cathode-bias operation	0.47	megohm

6AE5GT Refer to chart at end of section. Refer to chart at end of section. 6AE6G Refer to chart at end of section. 6AE7GT

6AF3 12AF3, 12AF3/12RR3/12RK19

HALF-WAVE VACUUM RECTIFIER

Miniature type used as a damper tube in horizontaldeflection circuits of television receivers. Outlines section, 7C; requires miniature 9-contact socket. Socket terminals 1, 2, 3, 6, 7, and 8 should not be used as tie points. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. Types 12AF3 and 12AF3/12BR3/12RK19 are identical with type 6AF3 except for heater ratings.



9CB

12AF3

			12	AF3/12BR3/ 12RK19	
Heater	Current	(ac/dc)	6.3 1.2	12.6 0.6 11	volts amperes seconds

Damper Service

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage#	. 4500	volts
Peak Plate Current	. 750	mA.
Average Plate Current	. 185	mA.
Bulb Temperature (At hottest point)	. 210	°C
Heater-Cathode Voltage:		
Peak value	-4500	volts
Average value	—1000	volts
# Pulse duration must not exceed 150% of a horizontal scanning	cycle (10	microseconds).

6AF4 **6AF4A**

MEDIUM-MU TRIODE

Miniature types used as local oscillators in uhf television receivers covering the frequency range of 470 to 890 MHz. Outlines section, 5C and 5B, respectively;




requires miniature 7-contact socket. Types 2AF4B/2DZ4 and 3AF4A/3DZ4 are identical with type 6AF4A except for heater and heater-cathode ratings.

	2AF4B/ 2DZ4	3AF4A/ 3DZ4	6AF4A	
Heater Voltage (ac/dc)	2.35	3.15	6.3	volts
Heater Current	0.6	0.45	0.225	ampere
Heater Warm-up Time (Average)	11	11	_	seconds
Heater-Cathode Voltage:				_
Peak value		±50 max		volts
Average value	100 max	25 max	2 5 max	volts
Direct Interelectrode Capacitances:				_
Grid to Plate			1.9	р F
Grid to Cathode and Heater			2.2	р F
Plate to Cathode and Heater			1.4	р F
Heater to Cathode (External Shield connected			2.2	рF
 With external shield connected to cathode, except 	ot as noted	•		

Class A. Amplifier

CHARACTERISTICS Plate Supply Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current	80 volt. 150 ohm 13.5 2100 ohm 6500 μmho 17.5 mA	S S
UHF Oscillator		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage Grid Voltage, Negative-bias value Grid Current Plate Dissipation Average Cathode Current	150 volt 50 volt 2 mA 2.5 watt 24 mA	s
TYPICAL OPERATION AS OSILLATOR AT 1000 MHz		
Plate Supply Voltage Plate Resistor Grid Resistor Plate Current Grid Current (Approx.)	100 volt. 220 ohm 10000 ohm 17 mA 750 μΑ	s
MAXIMUM CIRCUIT VALUES		
Grid-Circuit Resistance: For fixed-bias operation For cathode-bias operation	Not recommended 0.5 megohm	





ELECTRON-RAY TUBE

6AF6G

Glass octal type used to indicate visually, by means of two shadows on the fluorescent target, the effects of changes in the controlling voltages. It is a twin-indicator type and is used as a convenient means of indicating accurate radio-receiver tuning. This type may be supplied with pin No. 1 omitted. Tube requires octal


socket. Heater: volts (ac/dc), 6.3; amperes, 0.15. Maximum ratings in indicator service: fluorescent-target volts, 250 max, 125 min; ray-control-electrode supply volts, 250 max; peak heater-cathode volts, 90 max. Typical operation: fluorescent-target volts, 250; fluorescent-target mA, 3.75; ray-contact-electrode volts (approx. for 0° shadow angle), 155; ray-control-electrode volts (approx. for 100° shadow angle), 0.

6AF9

DUAL PENTODE

11AF9

Miniature type used in television receiver applications. Unit No.1 is used as a video output pentode, and unit No.2 as a sound if amplifier, agc amplifier, or sync separator. Outlines section, 6L, except has 10-pin base; requires miniature 10-contact socket. Type 11AF9 is identical with type 6AF9 except for heater ratings.



Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage	6.3 0.85 ±200 max	11.5 0.45 ±200 max	volts ampere volts
Direct Interelectrode Capacitances:	Unit No.1	Unit No.2	
Plate to All Other Electrodes (except grid No.1)	7	11	pF pF pF pF
Grid No.1 to All Other Electrodes (except plate)	12	10	pF
Plate to Grid No.1	0.105	0.140	pF
Grid No.1 to Heater	_	0.140	pF
Plate of Unit No.1 to Plate of Unit No. 2	0.1	50 max	pF
Grid No.1 of Unit No.1 to Grid No.1 of Unit			
No. 2	0.0	l0 max	pF pF pF
Plate of Unit No.1 to Grid No.1 of Unit No.2	0.10	00 max	pF
Plate of Unit No.2 to Grid No.1 of Unit No.1	0.00	05 max	рF


Class A. Amplifier

Class A ₁ Amplime	:1		
MAXIMUM RATINGS (Design-Maximum Values)	Unit No.1	Unit No.2	
Plate Supply Voltage	550	550	volts
Plate Voltage	250	250	volts
Grid-No.2 (Screen-Grid) Supply Voltage	550	550	volts
Grid-No.2 Voltage	250	250	volts
Cathode Current	60	15	m A
Plate Dissipation	5.1	1.5	watts
Grid-No.2 Input	2.5	0.5	watts
CHARACTERISTICS			
Plate Voltage	170	150	volts
Grid-No.2 Voltage	170	150	volts
Grid-No.1 (Control-Grid) Voltage	—2.6	-2.1	volts
Mu Factor, Grid No.1 to Grid No.2	38	3 8	
Internal Resistance	0.032	0.16	megohm
Transconductance	22000	8500	μ mhos
Plate Current	30	10	mĄ
Grid-No.2 Current	7.2	3	mA
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance	1	1	megohm

6AF11

DUAL TRIODE— SHARP-CUTOFF PENTODE


Duodecar type used in television receiver applications. The high-mu triode unit is used for agc keyer service, the medium-mu triode unit for sync separator service, and the pentode unit for video amplifier service. Outlines section, 8C; requires duodecar 12-contact socket. Type 15AF11 is identical with type 6AF11 except for heater ratings.



Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	6.3 1.05	14.7 0.45 11	volts amperes seconds
Heater-Cathode Voltage: Peak value Average value	±200 max	±200 max	volts
	100 max	100 max	volts

Class A. Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit No.1	Triode Unit No	Pentode .2 Unit	
Plate Voltage	330	330	330	volts
Grid-No.2 (Screen-Grid) Supply Voltage			330	volts
Grid-No.2 Voltage	-		See curve	page 300
bias value	0	0	0	volts
Plate DissipationGrid-No.2 Input:	1.1	2	5	watts
For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330	_	-	1.25	watts
volts			See curve	page 300
CHARACTERISTICS				
Plate Supply Voltage	200	200	250	volts
Grid-No.2 Supply Voltage			150	volts
Grid-No.1 Voltage	2			volts
Cathode-Bias Resistor		220	100	ohms
Amplification Factor	68	41		011410
Plate Resistance (Approx.)	12400	9400	68000	ohms
Transconductance	5500	4400	11000	μmhos
Plate Current	7	9.2	24	mA
Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current		==	4.8	mA
of 100 μA	_	-6.5	10	volts
MAXIMUM CIRCUIT VALUES				
Grid-No.1-Circuit Resistance:				
For fixed-bias operation	0.5	0.5	0.25	megohm
For cathode-bias operation	1	1		megohm



SHARP-CUTOFF PENTODE

6AG5

Miniature type used in compact radio equipment as an rf or if amplifier up to 400 MHz. Outlines section, 5C; requires miniature 7-contact socket. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section.

Heater Voltage (ac/dc) Heater Current Direct Interelectiode Capacitances:	6.3 0.3	volts ampere
Pentode Unit:		
Grid No.1 to Plate	0.030 max	pF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3,		_
and Internal Shield Plate to Cathode, Heater, Grid No.2, Grid No.3,	6.5	рF
and Internal Shield	1.8	pF
Triode Unit:		•-
Grid No.1 to Plate and Grid No.2	2.5	рF
Grid No.1 to Cathode, Heater, Grid No.3, and Internal Shield	3.6	pF
Grid No.2 to Cathode, Heater, Grid No.3, and Internal Shield	3	рF
Plate to Cathode, Heater, Grid No.3, and Internal Shield	3	рF

Class A. Amplifier

MAXIMUM RATINGS (Design-Center Values)	Triode Connection	n* (Pent Conne		
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation	300 0 2.5		300 300 Se 0 2	e curv	volts volts page 300 volts watts
Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid No.2 voltages between 150 and 300 volts			0.5 See		watt page 300
CHARACTERISTICS					
Plate Supply Voltage Grid-No.2 Supply Voltage Cathode-Bias Resistor Amplification Factor	180 250 330 820 45 42	100 100 180	125 125 100	250 150 180	volts volts ohms
Piate Resistance (Approx.) Transconductance Plate Current	0.008 0.01	0.6 4500 4.5	0.5	0.8 5000 6.5	mego hm μmhos mA

	Triode Connection*		Pento onnec		
Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of		1.4	2.1	2	mA
10 μΑ		5	6	—8	volts
* Grid No.2 connected to plate.					

6AG7

POWER PENTODE

Metal type used in output stage of video amplifier of color and black-and-white television receivers. Outlines section, 2B; requires octal socket.



s S	∨р
8Y	
1	volts
•	ampere

Heater Voltage (ac/dc)	6.3	volts
Heater Current	0.65	ampere
Peak Heater-Cathode Voltage	±90 max	volts
Direct Interelectrode Capacitances:		
Grid No.1 to Plate	0.06 max	pF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, Shell.		-
and Internal Shield	13	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3, Shell,		•
and Internal Shield	7.5	рF
• Pins 1 and 3 connected to Pin No.5.		
· rins I and a connected to rin No.b.		

Class A. Amplifier

MAXIMUM RATINGS (Design-Center Values)		
Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage, Positive-bias value	300 300 0	volts volts volts
Plate Dissipation Grid-No.2 Input CHARACTERISTICS	1.5	watts watts

Plate Voltage	300	volts
Grid No.3 (Suppressor Grid) Connected	to cathode	at socket
Grid-No.2 (Screen-Grid) Voltage	150	volts
Grid-No.1 (Control-Grid) Voltage	—3	volts
Peak AF Grid-No.1 Voltage	3	volta
Zero-Signal Grid-No.2 Current	30	mA
Maximum-Signal Grid-No.2 Current	30.5	mA
Zero-Signal Grid-No.2 Current	7	mA
Maximum-Signal Grid-No.2 Current	9	mA
Plate Resistance	0.13	megohm
Transconductance	11000	umbos
Load Resistance	10000	ohms
Total Harmonic Distortion	7	per cent
Maximum-Signal Power Output	3	watts
MAYIMIM CIBCUIT VALUE		

MAXIMU	IM CIRC	UIT VALUES
Grid-No.	1-Circuit	Resistance:
For	fixed-bia	s operation
E	andhada I	Lina Ain-

Refer to chart at end of section.

6AG7Y

6AG9 MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Duodecar type with frame grid pentode unit used in color and black-and-white television receiver applications. The pentode unit is used as a video amplifier; the triode unit is used as an agc amplifier. Outlines section, 8C; requires duodecar 12-contact socket. Heater: volts (ac/dc), 6.3; amperes, 0.82; maximum heater-cathode volts, ± 200 peak, 100 average.




megohm

0.25

Class A. Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit	Pentode Unit	
Plate Voltage	330	330	volts
Grid-No.2 (Screen-Grid) Voltage	000	200	volts
Grld-No.1 (Control-Grid) Voltage, Positive-bias		200	40169
	0	O	volts
Value	1.1	10	watts
	1.1		watts
Grid-No.2 Input	-	1.5	Watus
CHARACTERISTICS			
Plate Voltage	150	55 250	volts
Grid-No.2 Voltage		125 150	volts
Grid-No.1 Voltage		0	volts
Cathode-Bias Resistor	350	- 56	ohms
Amplification Factor	39		·
Plate Resistance (Approx.)	8500	40000	ohms
Transconductance	4600	— 30000	μmhos
Plate Current	6.2	56 28	mA
Grid-No.2 Current	0.2	21 5.6	mA
Grid-No.1 Voltage (Approx.) for plate current of	_	21 0.0	шл
	— 7		volts
20 μΑ	— /		VOILS
Grid-No.1 Voltage (Approx.) for plate current of		- 4	volts
100 μA		—5.4	VOIUS
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
For fixed-bias operation	0.5	0.1	megohm
For cathode-bias operation	"1	0.25	megohm
tor comogenion operation	•		
Refer to chart at end of section.		6AG1	1

Refer to chart at end of section. **6AH4GT 6AH6** Refer to chart at end of section. Refer to chart at end of section. **6AH9** Refer to chart at end of section. 6AJ8/ECH81 For replacement use type 6AK5/EF95. 6AK5



SHARP-CUTOFF PENTODE

6AK5/ **EF95**

watt

0.5

18

See curve page 300

7BD

Plate Dissipation Grid-No.2 Input:

Miniature types used as rf or if amplifiers especially in high-frequency wide-band applications at frequencies up to 400 MHz. Outlines section, 5B; require miniature 7-contact socket.

Heater Voltage (ac/dc)	6.3	volts
Heater Current	0.175	amper e
Peak Heater-Cathode Voltage	±90 max	volts
Grid No.1 to Plate	0.02 max	р F
Internal Shield	4	pF
Internal Shield	2.8	pF
 With external shield connected to pin 2 or 7. 		
Class A, Amplifier		
MAXIMUM RATINGS (Design-Center Values)		
Plate Voltage	180	volts
Grid-No.2 (Screen-Grid) Voltage	See curve	page 300
Grid-No.2 Supply Voltage	180	volts
Grid-No.1 Voltage, Positive-bias value	0	volts
w		

Grid-No.2 Current 2.5 Grid-No.1 Voltage for plate current of 10 μ A8.5	2.4 8.5	mA volts
CHARACTERISTICS 120 Plate Supply Voltage 120 Grid-No.2 Supply Voltage 120 Cathode-Bias Resistor 180 Plate Resistance (Approx.) 0.3 Transconductance 5000 Plate Current 7.5	180 120 180 0.5 5100	volts volts ohms megohm μmhos mA

Miniature type for use as a power output pentode in compact equipment. Outlines section, 5C; requires miniature 7-contact socket.



Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage Direct Interelectrode Capacitances (Approx.):	6.8 0.15 100 max	volts ampere volts
Grid to Plate Input Output	0.12 8.6 4.2	pF pF pF

A-F Power Amplifier

MAXIMUM RATINGS (Design-Center Values)		
Plate Voltage Screen Voltage (Grid No. 2) Plate Dissipation Screen Dissipation	300 250 2.75 0.75	volts volts watts watt

CHARACTERISTICS	AND	TYPICAL	OPERATION

Plate Voltage	180 volt
Suppressor (Grid No. 8)	Connected to cathode at socke
Screen Voltage	180 volt
Grid Voltage (Grid No. 1)	—9 volt
Peak A-F Grid Voltage	9 volt
Zero-Signal Plate Current	15 m
Zero-Signal Screen Current	2.5 m
Plate Resistance	0.2 megohr
Fransconductance	2300 umbo
Load Resistance	μπρο
Total Harmonic Distortion	10000 ohm
Man Cin Thermonic Distortion	10 9
MaxSig. Power Output	1.1 watt

MAXIMUM CIRCUIT VALUES

6AK8/EABC80

Refer to chart at end of section.

6AK10


Refer to chart at end of section.

6AL3

Refer to chart at end of section.

6AL3/EY88 HALF-WAVE VACUUM RECTIFIER

Miniature type used as damper tube in horizontal-deflection circuits of black-and-white television receivers. Outlines section, 7D; requires miniature 9-contact socket. Socket terminals 1, 2, 3, 6, 7, and 8 should not be used as tie points. It is especially important that this tube, like other power-handling tubes, be adequately ventilated. Heater: volts (ac/dc), 6.3; amperes, 1.55.




Damper Service

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Center Values)		
Peak Inverse Plate Voltage# (Absolute maximum) Peak Plate Current Average Plate Current Plate Dissipation	7500° 550 220 5	volts mA mA watts
Peak Heater-Cathode Voltage	6600	volts

* Under no circumstances should this absolute value be exceeded.

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).



TWIN DIODE

6AL5

3AL5, 12AL5


Miniature, high-perveance type used as detector in FM and television circuits, especially as a ratio detector in ac-operated FM receivers. Each diode section can be used independently of the other, or the two sections can be combined in parallel or full-wave arrangement. Resonant frequency of each unit is approximately 700

Resonant frequency of each unit is approximately 700 MHz. Outlines section, 5B; requires miniature 7-contact socket. Types 3AL5 and 12AL5 are identical with type 6AL5 except for heater ratings.

Heater Voltage (ac/dc)	3AL5 3.15 0.6	6AL5 6.3 0.3	12AL5 12.6 0.15	volts ampere
Heater Warm-up Time (Average)	11 ±330 max	±330 max	±330 max	seconds volts
Direct Interelectrode Capacitances: Plate No.1 to Cathode No.1, Heater, and Plate No.2 to Cathode No.2, Heater, and Cathode No.1 to Plate No.1, Heater, and Cathode No.2 to Plate No.2, Heater, and Plate No.1 to Plate No.2.	Internal Sh Internal Sh Internal Sh	ield ield ield	2.5 2.5 3.4 3.4 0.068 max	pF pF pF pF
Half-Wave	Rectifier			
MAXIMUM RATINGS (Design-Center Values) Peak Inverse Plate Voltage Peak Plate Current (Per Plate) Average Output Current (Per Plate)			330 54 9	volts mA mA
TYPICAL OPERATION AC Plate Voltage per Plate (rms) Min. Total Effective Plate-Supply Impedance Average Output Current per Plate	per Plate .		117 300 9	volts ohms mA

Refer to chart at end of section.

6AL7GT



12BU

BEAM POWER TUBE— SHARP-CUTOFF PENTODE

6ALTT

© 628 Duodecar type used as FM detector and audio-frequency output amplifier in television receivers. Outlines section, 8C; requires duodecar 12-contact socket. Types 10AL11 and 12AL11 are identical with type 6AL11 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	0.9	10AL11 9.8 0.6 11	12AL11 12.6 0.45 11	volts ampere seconds
Peak value Average value				volts volts

Direct Interelectrode Capacitance:		
Beam Power Unit:		
Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3,	0.26	pF.
and Internal Shield	11	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield	12	рF
Pentode Unit:	0.034	~E
Grid No.3 to Plate	3.2	pF pF
Grid No.1 to Plate Grid No.3 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield	6.5	рF
Grid No.3 to Cathode, Heater, Grid No.1, Grid No.2, Plate, and Internal Shield	-	-
Plate, and Internal Shield	$7.5 \\ 0.24$	pF pF
Pentode Plate to Beam Power Plate	0.12	pF
Beam Power Unit as Class A, Amplifier		
•		
MAXIMUM RATINGS (Design-Maximum Values)	975	volts
Plate Voltage Grid-No.2 (Screen-Grid) Voltage	275 275	volts
Plate Diggination	10	watts
Grid-No.2 Input	2	watts
TYPICAL OPERATION	~~~	• •
Plate Voltage	250 250	volts volts
Grid-No.2 Voltage	-8	volts
Peak AF Grid-No.1 Voltage	8	volts
Zero-Signal Plate Current	35 39	mA mA
Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current	2.5	m A
Maximum-Signal Grid-No.2 Current	7	mA.
Maximum-Signal Grid-No.2 Current Plate Resistance (Approx.)	0.1	megohm
Transconductance	6500 5000	μmhos ohms
Total Harmonic Distortion	10	per cent
Load Resistance Total Harmonic Distortion Maximum-Signal Power Output	4.2	watts
MAXIMUM CIRCUIT VALUE		
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.25 0.5	megohm megohm
For cathode-bias operation	0.0	megonini
Pentode Unit as Class A, Amplifier		
CHARACTERISTICS		
Plate Supply Voltage	150	volts
Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor	. 0	volts
Grid-No.2 (Screen-Grid) Supply Voltage	100 560	volts ohms
Plate Resistance (Approx.)	0.15	megohm
Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance Grid No.3 to Plate	1000	μ mhos
Transconductance Grid No.3 to Plate	400 1.3	μmhos mA
Plate Current	2.1	mA
Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 30 μA	4.5	volts
Grid-No.3 Voltage (Approx.) for plate current of 50 μ A	4.5	volts
Pentode Unit as FM Detector		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	330	volts
Grid-No.3 Voltage	28	volts
Grid-No.2 Supply Voltage	330	volts
Grid-No.2 Voltage	See cu	rve page 300 volts
Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation	1.7	watts
Grid-No.2 Input:		
For grid-No.2 voltages up to 165 volts	1.1 See cu	watts rve page 300
For grid-No.2 voltages between 165 and 330 volts	See cu	I TO PAGE DOO

6AM4

Refer to chart at end of section.


6AM6/EF91

Refer to chart at end of section.

mA

Refer to chart at end of section.

6AM8



DIODE— SHARP-CUTOFF PENTODE


6AM8A

Miniature type used in television receiver applications. The pentode unit is used as an if amplifier, video amplifier, or agc amplifier. The high-perveance diode is used as an audio detector, video detector, or dc restorer. Outlines section, 6B; requires miniature 9-contact socket. Type 5AM8 is identical with type 6AM8A except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	5AM8 4.7 0.6 100 max	6AM8A 6.3 0.45 100 max	volts ampere volts
Peak value Average value	±200 max 100 max	±200 max 100 max	volts volts
Direct Interelectrode Capacitances: Diode Unit:			
Plate to Cathode and Heater Cathode to Plate and Heater Pentode Unit:		1.8 3	pF pF
Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3	and	0.015	pF
Internal Shield Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield		6.5 2.6	pF pF
Pentode Grid No.1 to Diode Plate		0.006	рF
Pentode Plate to Diode Cathode		0.15	pF
Pentode Plate to Diode Piate		0.1	pF
Pentode Unit as Class A, Am	plifier		
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage		330	volts
Grid-No.3 (Suppressor-Grid) Voltage, Positive value		0 330	volts
Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage		See curve	volts
Grid-No.1 (Control-Grid) Voltage, Positive-bias value		0	volts
Plate Dissipation		3.2	watts
Grid-No.2 Input: For grid-No.2 voltages up to 165 volts		0.55	watt
For grid-No.2 voltages between 165 and 330 volts		See curve	
CHARACTERISTICS			
Plate Supply Voltage		125	volts
Grid No.3		to cathode 125	at socket volts
Grid-No.2 Supply Voltage Cathode-Bias Resistor		56	ohms
Plate Resistance (Approx.)		0.3	megohm
Transconductance		7800	μ mhos
Plate Current		12.5 3.2	mA mA
Grid-No.2 Current		6	volts
Grid-No.1 Voltage (Approx.) for plate current of 2 mA		—- š	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation		0.25 1	megohm megohm
- ! ! !! !!			

Diode Unit

MAXIMUM RATING (Design-Maximum Value)
Average Plate Current



6AN4

Refer to chart at end of section.

6AN5

Refer to chart at end of section.

5AN8


6AN8

Refer to chart at end of section.

6AN8A

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in color television receiver applications. The pentode unit is used as an intermediate-frequency amplifier, a video amplifier, an agc amplifier, or a reactance tube. The triode unit is used in low-frequency oscillator, sync-separator, sync-clipper, and phase-splitter circuits. Outlines section, 6B; requires miniature 9-contact socket. Type 5AN8 is identical with 6AN8A except for heater ratings.



6AN8A


Heater Voltage (ac/dc)	4.7	6.3	volts
Heater Current	0.6	0.45	ampere
Heater Warm-up Time (Average)	11	11	seconds
Heater-Cathode Voltage:			
Peak value	±200 max	$\pm 200 \text{ max}$	volts
Average value	100 max		volts
Direct Interelectrode Capacitances:	100 max	100 max	VOILS
Triode Unit:			
Grid to Plate		1.5	pF
Grid to Cathode and Heater		2	pF
Plate to Cathode and Heater		0.26	pF
Pentode Unit:		·· - ·	1/-
Grid No.1 to Plate		0.04 max	pF
Grid No.1 to Cathode, Heater, Grid No.2, Grid I			P-
Internal Shield		7	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3, as		•	pr
Internal Shield		0.4	12
		2.4	р <u>Г</u>
Triode Grid to Pentode Plate		0.02	рF
Pentode Grid No.1 to Triode Plate		0.02	pΓ
Pentode Plate to Triode Plate		0.15	pF
		••••	P-


Class A₁ Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit	Pentode Unit	
Plate Voltage	330	330	volts
Grid-No.2 Supply Voltage		330	volts
Grid-No.2 (Screen-Grid) Voltage	See	curve page 300	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	0	volts
Plate Dissipation	2.8	2.3	watts

Grid-No.2 Input: For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330 volts	_ _ s	0.55 ee curve pag	watt
CHARACTERISTICS			
Plate Supply Voltage	150	125	volts
Grid-No.2 Supply Voltage	_	125	volts
Grid-No.1 Voltage	8	_	volts
Cathode-Bias Resistor	_	56	ohms
Amplification Factor	21		
Plate Resistance (Approx.)	4700	170000	ohms
Transconductance	4500	7800	μ mhos
Plate Current	15	12	m A
Grid-No.2 Current		3.8	mA
Grid-No.1 Voltage (Approx.) for plate current of			
20 μΑ	-17	6	volts
Grid-No.1 Voltage (Approx.) for plate current of			
1.6 mA		3	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:*			
For fixed-bias operation	0.5	0.25	megohm
For cathode-bias operation	1	1	megohm
A SA			

^{*} If either unit is operating at maximum rated conditions, grid-No.1-circuit resistance for both units should not exceed the stated values.





Refer to chart at end of section.

6AQ5



BEAM POWER TUBE

6AQ5A

5AQ5, 12AQ5


Miniature type used as output amplifier primarily in automobile receivers and in ac-operated receivers and, triode-connected, as a vertical-deflection amplifier in television receivers. Outlines section, 5D; requires miniature 7-contact socket. Within its maximum rat-


ings, the performance of this type is equivalent to that of larger types 6V6 and 6V6GTA. Types 5AQ5 and 12AQ5 are identical with type 6AQ5A except for heater ratings.


Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	0.6	6.3 0.45 11	12.6 0.225	volts ampere seconds
Heater-Cathode Voltage: Peak value				volts volts
Direct Interelectrode Capacitances (Approx.): Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Plate to Cathode, Heater, Grid No.2, and (and Grid I	Vo.3	0.4 8 8.5	pF pF pF

Class A₁ Amplifier

Cless At Amplifier		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	275	volts
Grid-No.2 (Screen-Grid) Voltage	275	volts
Plate Dissipation	12 2	watts watts
Grid-No.2 Input Bulb Temperature (At hottest point)	250	°C
CHARACTERISTICS (Triode Connection)		
Plate Voltage	250	volts
Grid-No.1 Voltage	-12.5	volts
Amplification Factor Plate Resistance (Approx.)	9.5 1970	ohms
Transconductance	4800	μmhos
Plate Current	49.5	mA
Grid-No.1 Voltage (Approx.) for plate current of 0.5 mA	87	volts
TYPICAL OPERATION Same as for type 6V6GTA within the limitations of the maximum	ratings.	
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.1	megohm
For cathode-bias operation	0.5	megohm
Vertical Deflection Amplifier (Triode Connec	ction)°	
For operation in a 525-line, 30-frame system	nà.	
MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Voltage	275	volts
Peak Positive-Pulse Plate Voltage#	1100 275	volts volts
Peak Cathode Current	115	mA.
Average Cathode Current	40	mA
Plate Dissipation	10	watts
Bulb Temperature (At hottest point)	250	•c







6AQ6 6AQ7GT

6AQ8


MAXIMUM CIRCUIT VALUE

Refer to chart at end of section.

Refer to chart at end of section.

Refer to chart at end of section.

volts



HIGH-MU TWIN TRIODE

6AQ8/

6AR5

6AR8

6.3

Miniature types used as rf amplifier and self-oscillating mixer in FM/AM radio receivers. Outlines section, 6B; requires miniature 9-contact socket.

Heater Current Peak Heater-Cathode Voltage		0.435 ±90 max	ampere volts
Direct Interelectrode Capacitances: Grid to Plate Cathode to Plate Grid to Cathode, Heater, and Internal Shield Plate to Cathode, Heater, and Internal Shield Plate to Grid of Other Unit Plate to Cathode of Other Unit Grid to Cathode of Other Unit Plate of Unit No.1 to Plate of Unit No.2 Grid of Unit No.1 to Grid of Unit No.2	Unit No.1 1.5 0.18 3 1.2 0.008 max 0.008 max	Unit No.2 1.5 0.18 3 1.2 0.008 max 0.003 max 0.003 max 0.004 max	pF pF pF pF pF pF
Class A ₁ Amplifier			
MAXIMUM RATINGS (Design-Maximum Values, Each U	nit)		
Plate Supply Voltage Plate Voltage Grid Voltage, Negative-bias value Cathode Current Plate Dissipation: For either plate For both plates with both units operating		550 300 100 15 2.5 4.5	volts volts volts mA watts watts
CHARACTERISTICS			
Plate Voltage, Negative-bias value Plate Current Transconductance Amplification Factor		250 2.3 10 5900 57	volts volts mA μmhos
	RF		
TYPICAL OPERATION (Each Unit) Plate Supply Voltage Plate Voltage Plate Resistor Grid Resistor Grid Voltage RMS Oscillator Voltage Cathodc-Bias Resistor Plate Resistance (Approx.) Transconductance Conversion Transconductance Input Resistance at frequency of 100 MHz Plate Current Equivalent Noise Resistance MAXIMUM CIRCUIT VALUES (Each Unit)	Amplifier 250 280 1800 —-2 —-2 200 9700 6000 10 500	Converter 250 12000 1 3 22000 2300 15000 5.2	volts volts ohms megohm volts volts ohms ohms µmhos ohms mA ohms
Grid-Circuit Resistance		1	megohm
Resistance between Cathode and Heater		20000	ohms


Refer to chart at end of section.

Refer to chart at end of section.

6ARII

SEMIREMOTE-CUTOFF TWIN PENTODE

Duodecar type used as if-amplifier tube in television receivers. Outlines section, 8A; requires duodecar 12-contact-socket. Types 8AR11 and 11AR11 are identical with type 6AR11 except for heater ratings.



12DM

	6AR11	8AR11	11AR11	
Heater Voltage (ac/dc)	6.3	8.4	11.2	volts
Heater Current	0.8	0.6	0.45	ampere
Heater Warm-up Time (Average)		11	11	seconds
Heater-Cathode Voltage:				seconds
Peak value	$\pm 200 \text{ max}$	±200 max	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances:		Init No.1	Unit No.2	
Grid No.1 to Plate		0.026	0.026	рF
Grid No.1 to Cathode, Heater, Grid No.2,			****	P.
No. 3, and Internal Shield		10	10	ρF
Plate to Cathode, Heater, Grid No.2, Grid	No.3.		10	p.
and Internal Shield		2.8	3	рF
Grid No.1 to Plate of Other Unit		0.002	0.002	
Plate of Unit No.1 to Plate of Unit No.2		0.002		p F
rate of Onit 140.1 to Flate of Onit 140.2			0.02	рF

Class A, Amplifier		
MAXIMUM RATINGS (Design-Maximum Values, Each Unit)		
Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value	330 0	volts volts
Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value	330 See curve 0	volts page 300 volts
Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 165 volts	3.1 0.65	watts watt
For grid-No.2 voltages between 165 and 330 volts		page 300
CHARACTERISTICS (Each Unit)		
Plate Supply Voltage Grid No.3		
Grid-No.2 Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.)	125 56	volts ohms
Transconductance Plate Current	0.2 10500 11	megohm µmhos mA
Grid-No.2 Current Grid-No.1 Voltage (Approx.) for transconductance of 50 µmhos	3.5 15	mA volts

6AS5

BEAM POWER TUBE

Miniature type used as output amplifier primarily in automobile and in ac-operated receivers. Outlines section, 5D; requires miniature 7-contact socket. For curves of average plate characteristics, refer to type 35C5.



7CV

Heater Voltage (ac/dc)	6.3	volts
Heater Current	0.8	ampere
Peak Heater-Cathode Voltage	$\pm 100~\mathrm{max}$	volts
Direct Interelectrode Capacitances (Approx.):		
Grid No.1 to Plate	0.6	рF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3	12	рF
Plate to Cathode, Heater, Grid No.2, and Grid No.3	9	рF

Class A₁ Amplifier

MAXIMUM RATINGS (Design-Center Values)		
Plate Voltage	150	volts
Grid-No.2 (Screen-Grid) Voltage	117	volts
Plate Dissipation	5.5	watts
Grid-No.2 Input	1.0	watt
Bulb Temperature (At hottest point)	250	°C
Build Temperature (At nottest point)	200	C
TYPICAL OPERATION		
Plate Voltage	150	volts
Grid-No.2 Voltage	110	volts
Grid-No.1 (Control-Grid) Voltage	-8.5	volts
Peak AF Grid-No.1 Voltage	8.5	volts
Zero-Signal Plate Current	35	mA
Maximum-Signal Plate Current	36	mA
Zero-Signal Grid-No.2 Current (Approx.)	2	m A
Maximum-Signal Grid-No.2 Current (Approx.)	6.5	m A
Transconductance	5600	μmhos
Load Resistance	4500	ohms
Total Harmonic Distortion	10	per cent
Maximum-Signal Power Output	2.2	watts
Maximum-Signal Fower Output	2.2	watts
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.1	megohm
For cathode-bias operation	0.5	megohm

Refer to chart at end of section.

6AS6

1700

125

volts

mA watts



LOW-MU TWIN POWER TRIODE

TYPE

Glass octal type used as a regulator tube in dc power

ning app	nits and in projection televolications. Outlines section, Refer to type 6080 for averages.	27B; requi:	res octal
Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage:		6.3 2.5	volts amperes
	(Approx.) auch unit:	± 300 max.	volts
Grid to plate Grid to heater and cathode Plate to heater and cathode Heater to cathode Grid of unit No. 1 to grid of ur	nit No. 2	10.5 6.8 2.3 11.0 0.70 1.65	pF pF pF pF pF
Class	A. Amplifier (Each Unit)		
CHARACTERISTICS	•		
Cathode-Bias Resistor■		135 250 2	volts ohms
		280 7000 125	ohms µmhos mA
DC .	Amplifier (Each Unit)		
		250 125 13	volts mA watts
Booster Sc	canning Service (Each Unit)		

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Center Values)

Peak Negative-Pulse Plate Voltage®
DC Plate Current
Plate Dissipation

MAXIMUM CIRCUIT VALUES

Grid-Circuit Resistance:
For cathode-bias operation
For fixed-bias operation

1.0 megohm Not recommended

As described in "Standards of Good Engineering Practice Concerning Television Broadcast Stations", Federal Communications Commission.

• The duration of the voltage pulse must not exceed 15 per cent of one horizontal scanning cycle. In a 525-line, 30-frame system, 15 per cent of one horizontal scanning cycle is 10 microseconds.

6AS7GA

Refer to chart at end of section.

6AS8 SHARP-CUTOFF PENTODE


Miniature type used in television and radio receiver applications. The pentode unit is used as an if amplifier, video amplifier, or agc amplifier. The high-perveance diode is used as an audio detector, video detector, or dc restorer. Outlines section, 6B; requires miniature 9-contact socket. For curve of average plate characteristics of pentode unit, see type 6AN8A.

Grid-No.2 Current
Grid-No.1 Voltage (Approx.) for plate current of 10 µA

For cathode-bias operation

MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance:

For fixed-bias operation



9DS

mA volts

megohm

megohm

0.25


Heater Voltage (ac/dc)	6.3	volts
Heater Current	0.45	ampere
Heater Warm-up Time (Average)	_	seconds
Heater-Cathode Voltage: Peak value	±200 max	volts
Average value	100 max	volts
Direct Interelectrode Capacitances:	100	******
Diode Unit:		
Plate to Cathoe, Heater, Pentode Grid No.3, and		_
Internal Shield	3	рF
Pentode Unit: Grid No.1 to Plate	0.03	$_{\mathbf{p}}\mathbf{F}$
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and	0.00	pı
Internal Shield	7	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and		
Internal Shield	2.4 0.005 max	$_{ m pF}^{ m pF}$
Pentode Plate to Diode Cathode	0.005 max	рF
Pentode Plate to Diode Plate	0.10 max	pF
Pentode Unit as Class A, Amplifier		
•		
MAXIMUM RATINGS (Design-Center Values)	300	volts
MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value	0	volts
MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 Supply Voltage	300	volts volts
MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 Supply Voltage Grid-No.2 (Screen-Grid) Voltage	0 300 See curve	volts volts page 300
MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 Supply Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0 300 See curve 0	volts volts
MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 Supply Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation	0 300 See curve	volts volts page 300 volts
MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts	0 300 See curve 0 2.5	volts volts page 300 volts watts
MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 Supply Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input:	0 300 See curve 0 2.5	volts volts page 300 volts watts
MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts	0 300 See curve 0 2.5	volts volts page 300 volts watts
MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate Supply Voltage	0 300 See curve 0 2.5 0.5 See curve	volts volts page 300 volts watts watt page 300 volts
MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate Supply Voltage Grid No.3 Connecter	300 See curve 0 2.5 0.5 See curve	volts volts page 300 volts watts watt page 300 volts at socket
MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate Supply Voltage Grid No.3 Connecte Grid-No.2 Supply Voltage Grid-No.2 Supply Voltage	300 See curve 0 2.5 0.5 See curve	volts page 300 volts watts watt page 300 volts at socket volts
MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 Supply Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate Supply Voltage Grid No.3 Grid-No.2 Supply Voltage Cathode-Bias Resistor	300 See curve 0 2.5 0.5 See curve 200 d to cathode 150 180	volts volts page 300 volts watts watt page 300 volts at socket
MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate Supply Voltage Grid No.3 Connecte Grid-No.2 Supply Voltage Grid-No.2 Supply Voltage	300 See curve 0 2.5 0.5 See curve	volts volts volts page 300 volts watts watt page 300 volts at socket volts ohms

Diode Unit

MAXIMUM RATINGS (Design-Center Values)		
Peak Inverse Plate Voltage	330	volts
Peak Plate Current	50	mA
Average Plate Current	5	mA

Refer to chart at end of section.

6AS11



TWIN DIODE— HIGH-MU TRIODE

6AT6 12AT6

Miniature type used as a combined detector, amplifier, and avc tube in automobile and ac-operated radio receivers. Outlines section, 5C; requires miniature 7-contact socket. For typical operation as resistance-coupled amplifier refer to Resistance-Coupled Amplifier section. Type 12AT6 is identical with type 6AT6 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage Direct Interelectrode Capacitances: Triode Grid to Triode Plate Triode Plate to Cathode and Heater Triode Plate to Cathode and Heater Plate of Diode Unit No.2 to Triode Grid		12AT6 12.6 0.15 ±90 max 2 2.2 0.8 0.04 max	volts ampere volts pF pF pF
Triode Unit as Class A, Amp	lifier		
MAXIMUM RATINGS (Design-Center Values)			
Plate Voltage Plate Dissipation Grid Voltage, Positive-bias value		300 0.5 0	volts watts volts
CHARACTERISTICS			
Plate Voltage Grid Voltage Amplification Factor Plate Resistance Transconductance Plate Current	$ \begin{array}{c} 100 \\ -1 \\ 70 \\ 64000 \\ 1300 \\ 0.8 \end{array} $	250 3 70 58000 1200	volts volts ohms μmhos mA


Diode Units

MAXIMUM RATING (Design-Center Value)

Plate Current (Each Unit) The two diode plates are placed around a cathode whose sleeve is common to the triode unit. Each diode plate has its own base pin. For diode operation curves, refer to type 6AV6.

Refer to chart at end of section.

6AT8



9DW

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6AT8A

Miniature types used as combined oscillator and mixer tubes in television receivers utilizing an intermediate frequency in the order of 40 MHz. Outlines section, 6B; requires miniature 9-contact socket. Except for interlectrode capacitances and basing arrangement, this type is identical with miniature type 6X8. The basing

arrangement is particularly suitable for connection to the coils of certain designs of turret tuners. Type 5AT8 is identical with type 6AT8A except for heater ratings.

Heater Voltage (ac/dc)	5AT8 4.7	6AT8A 6.3	volts
Heater Current	0.6	0.45	ampere
Heater Warm-up Time (Average)	11	11	seconds
Direct Interelectrode Capacitances:			seconds
Triode Unit:	Unshielded	Shielded=	
Grid to Plate	1.5	1.5	pF
Grid to Cathode and Heater	2.	2.4	pF
Plate to Cathode and Heater	0.5	1''	pF
Pentode Unit:	0.0	•	pr
Grid No.1 to Plate	0.06 max	0.03 max	рF
Grid No.1 to Cathode, Heater, Grid No.2 and	0.00 max	O.OO IIIAA	pr.
Grid No.3	4.6	4.8	pF
Plate to Cathode, Heater, Grid No.2, and	4.0	4.0	pr
Grid No.3	0.9	1.6	10
Pentode Grid No.1 to Triode Plate			pF
Periode Grid No.1 to Triode Flate	0.05 max	0.04 max	pF
Pentode Plate to Triode Plate	0.05 max	0.008 max	рF
Heater to Cathode	6	6†	pF
- 117741		•	-

With external shield connected to cathode except as noted. With external shield connected to plate.


6AU4GT

Refer to chart at end of section.

6AU4GTA

HALF-WAVE VACUUM RECTIFIER

Glass octal type used as damper tube in horizontaldeflection circuits of color and wide-angle picture-tube television receivers. Outlines section, 13G; requires octal socket. Type may be supplied with pin No. 1 omitted. Socket terminals 1, 2, 4, and 6 should not be used as tie points. This tube, like other power-handling tubes, should be adequately ventilated.



Heater Voltage (ac/dc) Heater Current	6.3 1.8	volts amperes
Direct Interelectrode Capacitances (Approx.):		
Plate to Heater and Cathode	8.5	рF
Cathode to Heater and Plate	11.5	pF
Heater to Cathode	4	$p\mathbf{F}$

Damper Service

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)			
Peak Inverse Plate Voltage#		4500	volts
Peak Plate Current		1300	mA
Average Plate Current		210	mA
Plate Dissipation		6.5	watts
Heater-Cathode-Voltage:			
	30 0	-4500	volts
Average value+	100	-900	volts

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

6AU5GT

BEAM POWER TUBE

Glass octal type used as horizontal-deflection amplifier in low-cost, high-efficiency deflection circuits of television receivers. Outlines section, 13D; requires octal socket.



Heater Voltage (ac/de)	6.3 1.25	volts amperes
Heater-Cathode Voltage: Peak value	±200 max	volts
Average value	100 max	volts
Grid No.1 to Plate	0.5 11.3	pF pF
Plate to Cathode, Heater, Grid No.2, and Grid No.3	7	pF

Class A. Amplifier

CHARACTERISTICS	Pentode Connection	Triode† Connection	
Plate Voltage	115	110	volts
Grid-No.2 (Screen-Grid) Voltage	175	100	volts
Grid-No.1 (Control-Grid) Voltage	—20	-4.5	volts
Plate Resistance	6000		ohms
Transconductance	5600		μmhos
Plate Current	60		mA
Grid No.2 Current	6.8		mA
+ Grid No 2 connected to plate			

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Center Values)

MAXIMOM NATINGS (DCS/8) CCITCL TOLOGS		
DC Plate Voltage	550	volts
Peak Positive-Pulse Plate Voltage# (Absolute Maximum)	5500°	volts
Peak Negative-Pulse Plate Voltage	1250	volts
DC Grid-No.2 (Screen-Grid) Voltage	200	volts
Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage	300	volts
Peak Cathode Current	400	mĄ
Average Cathode Current	110	mA
Grid-No.2 Input	2.5	watts
Plate Dissipation††	10	watts
Rulb Temperature (At hottest point)	210	°C

MAXIMUM CIRCUIT VALUE

Grid-No.1-Circuit Resistance 0.47 megohm
Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).


*Under no circumstances should this absolute value be exceeded.

• Obtained through a series dropping resistor of sufficient magnitude to limit the grid-No.2 input to the rated maximum value.

†† A bias resistor or other means is required to protect the tube in absence of excitation.

Refer to chart at end of section.

6AU6



SHARP-CUTOFF PENTODE

6AU6A 3AU6, 4AU6, 12AU6

Miniature type used in compact radio equipment as rf amplifier especially in high-frequency, wide-band applications; also used as limiter tube in FM equipment. Outlines section, 5C; requires miniature 7-contact socket. For a discussion of limiters, refer to Electron Tube Applications section. For typical operation as

7BK Tube Applications section. For typical operation as resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Types 3AU6, 4AU6, and 12AU6 are identical with type 6AU6A except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Aver-	3.15 0.6	4AU6 4.2 0.45	6AU6A 6.3 0.3	12AU6 12.6 0.15	volts ampere
age)	11	11	11		seconds
Heater-Cathode Voltage: Peak value	±200 max 100 max	±200 max 100 max	±200 max 100 max	±200 max 100 max	volts volts

Direct Interelectrode Capacitances: Pentode Connection:		
Grid No.1 to Plate	0.0035 max	pF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and		
Internal Shield Plate to Cathode, Heater, Grid No.2, Grid No.3, and	5.5	рF
Internal Shield	5	17
Triode Connection:	J.	рF
Grid No.1 to Plate, Grid No.2, Grid No.3, and Internal Shield	2.6	рF
Grid No.1 to Cathode and Heater	3.2	pF
Plate, Grid No.2, Grid No.3, and Internal Shield to Cathode and Heater	1.2	рF
† Grid No.2, grid No.3, and internal shield connected to plate. * Value is 8.5 pF with external shield connected to cathode.		

Class A₁ Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Triode† Connection	Pentode Connection	
Plate Voltage	275	330	volts
Grid-No.3 (Suppressor-Grid) Voltage. Positive value	-	0	volts
Grid-No.2 (Screen-Grid) Voltage	See cu	rve page 300	
Grid-No.2 Supply Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value	_	330	volts
Plate Dissipation	3.5	3.5	volts
Grid-No.2 Input:	3.0	3.0	watts
For grid-No.2 voltages up to 165 volts		0.75	watt
For grid-No.2 voltages between 165 and 330 volts	See cu	rve page 300	

CHARACTERISTICS	Triode† Connection	Pent	ode Con	nection		
Plate Supply Voltage	250	100	250	150		volts
Grid No.3	_	Conne	ected to	cathode	at	
Grid-No.2 Supply Voltage	_	100	125	150		volts
Cathode-Bias Resistor	330	150	100	68		ohms
Amplification Factor	36			_		
Plate Resistance (Approx.)		0.5	1.5	1		megohms
Transconductance	4800	3900	4500	5200		μmhos
Plate Current	12.2	5	7.6	10.6		mA
Grid-No.2 Current		2.1	3	4.3		mA
Grid-No.1 Voltage for plate current						
of 10 μA	_	4.2	-5.5	-6.5		volts
† Grid No.2, grid No.3, and internal shie	ld connected	to pla	te.			

TYPE 6AU6A
PENTODE CONNECTION
GRID No.2 VOLTS=100

EC1=0

GRID-No.1 VOLTS EC1=-1

1 C2

GRID-No.1 VOLTS EC1=-1

1 C2

1 C3

1 C3

1 C4

1 C5

1


6AU7

Refer to chart at end of section.

92CS-66HT3

6AU8

Refer to chart at end of section.



MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6AU8A

9DX

Miniature type used in television receiver applications. Pentode unit is used as video amplifier, if amplifier, and agc amplifier. Triode unit is used in sync-amplifier, sync-separator, sync-clipper, and phase-inverter circuits. Outlines section, 6E; requires 9-contact socket.

77 (77 3) (())			14
Heater Voltage (ac/dc)			
Heater Current Heater Warm-up Time (Average)		0.6	
Heater-Cathode Voltage:		11	seconds
Peak value		±200	max volts
Average value			max volts
Direct Interelectrode Capacitances:	• • • • • • • • •	100	max voics
Triode Unit:			
Grid to Plate		2.2	pF
Grid to Cathode and Heater			
Plate to Cathode and Heater			
Pentode Unit:	· · · · · · · · ·	0.01	p.
Grid No.1 to Plate		0.06	pF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.	3 and	0.00	ρ.
Internal Shield	o, and	7.5	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3, as	nd		P -
Internal Shield		. 3.4	pF
Triode Grid to Pentode Plate			
Pentode Grid No.1 to Triode Plate			
Pentode Plate to Triode Plate			max pF
			-
Class A, Amplifier	•		
MAXIMUM RATINGS (Design-Maximum Values)	Triode II	nit Pentod	e Unit
			volts
Grid-No.2 (Screen-Grid) Supply Voltage	330	330 330	volts
Grid-No.2 Voltage		See curve	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	See curve	volts
Plate Dissipation	2.8	3.3	watts
Grid-No.2 Input:	2.0	0.0	watts
For grid-No.2 voltages up to 165 volts	_	1	watt
For grid-No.2 voltages between 165 and 330 volts		See curve	
		Dec carre	page ove
CHARACTERISTICS			
Plate Supply Voltage	150	200	volts
Grid-No.2 Supply Voltage		125	volts
Cathode-Bias Resistor	150	82	ohms
Amplification Factor	43	_	_
Plate Resistance (Approx.)	8100	100000	oh m s
Transconductance	5300	8000	μmhos
Plate Current	9.5	17	m A
Grid-No.2 Current	_	3.4	mA
Grid-No.1 Voltage (Approx.) for plate current of			14
100 μΑ	-6.5	-7.5	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
The state of the s	0.5	0.05	maaahm



For fixed-bias operation

For cathode-bias operation

BEAM POWER TUBE

6AV5GA 12AV5GA, 25AV5GA

megohm

megohm

0.25

Glass octal type used as horizontal-deflection amplifier in television receivers. Outlines section, 19C; requires octal socket. Types 12AV5GA and 25AV5GA

are identical with type 6AV5GA except for heater

0.5

6CK ratings.

	6AV5GA	12AV5GA	25AV5GA	
Heater Voltage (ac/dc)	6.3	12.6	25	volts
Heater Current	1.2	0.6	0.3	amperes
Heater Warm-up Time (Average)	_	11		seconds

Heater-Cathode Voltage: Peak value				volts
Average value	100 max	100 max	100 max	volts
Grid No.1 to Plate			0.5	pF
Grid No.1 to Cathode, Heater, Grid No.2,	and Grid N	ĭo.8	14	рF
Plate to Cathode, Heater, Grid No.2, and	Grid No.3		7	рF

Class A. Amplifier

CHARACTERISTICS		ntode nection	Triode• Connection	
Plate_Voltage	60	250	150	volts
Grid-No.2 (Screen-Grid) Voltage	150	150	150	volts
Grid-No.1 (Control-Grid) Voltage	0	22. 5	-22.5	volts
Plate Resistance	-	14500	-	ohms
Transconductance		590 0	-	µmhos.
Plate Current	260	57		mA
Screen Current	26	2.1		mA
Grid-No.1 Voltage (Approx.) for plate current of				
1 mA	_	43		volts
Amplification Factor			4.3	
• Grid No.2 connected to plate.				

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Center Values)		
DC Plate Voltage	550	volts
reak rositive-ruise riate voltager (Absolute Maximum)	5500°	volts
Peak Negative-Pulse Plate Voltage	1250	volts
DC Grid-No.2 Voltage	175	volts
reak Negative-Pulse Grid-No.1 Voltage	300	volts
Peak Cathode Current	400	mA
Average Cathode Current	110	mA
Grid-No.2 Input	2.5	watts
Plate Dissipation †	11	watts
Bulb Temperature (At hottest point)	210	°C
MAXIMUM CIRCUIT VALUE		

Grid-No.1-Circuit Resistance

0.47 # Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds),

" Under no circumstances should this absolute value be exceeded. †† A bias resistor or other means is required to protect the tube in absence of excitation.


6AV5GT

Refer to chart at end of section.

6AV6 4AV6, 12AV6

TWIN DIODE-HIGH-MU TRIODE

Miniature type used as combined detector, amplifier, and avc tube in automobile and ac-operated radio receivers. The 6AV6 may be substituted directly for the 6AT6 in applications where the higher amplification of the 6AV6 is advantageous. Outlines section, 5C; re-



7BT


quires miniature 7-contact socket. Types 4AV6, and 12AV6 are identical with type 6AV6 except for heater ratings.


Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	4AV6 4.2 0.45 11	6AV6 6.3 0.3	12.6 0.15	volts ampere seconds
Heather-Cathode Voltage: Peak value Average value Direct Interelectrode Capacitances:		±200 max 100 max	±200 max 100 max	volts volts
Triode Grid to Triode Plate Triode Grid to Cathode and Heater Triode Plate to Cathode and Heater Plate of Diode Unit No.2 to Triode Grid			2 2.2 0.8= 0.04 max	pF pF pF pF

This value is 1.2 pF with external shield connected to cathode.

Triode Unit as Class A. Amplifier

MAXIMUM RATING (Design-Maximum Value)		
Plate Voltage Grid Voltage, Positive-bias value	0	volts volts
Plate Dissipation	0.55	watt





CHARACTERISTICS

Plate Voltage	100	250	volts
Grid Voltage	<u>—1</u>	2	volts
Amplification Factor	100	100	
Plate Resistance	80000	62500	ohms
Transconductance	1250	1600	umhos
Plate Current	0.50	1.2	mA

Diode Units

MAXIMUM RATING (Design-Maximum Value)

Installation and Application

The triode unit of the 6AV6 is recommended for use only in resistance-coupled circuits. Refer to the Resistance-Coupled Amplifier section for typical operating conditions. Grid bias for the triode unit of the 6AV6 may be obtained from a fixed source, such as a fixed-voltage tap on the dc power supply, or from a cathode-bias resistor. It should not be obtained by the diode-biasing method because of the probability of plate-current cutoff, even with relatively small signal voltages applied to the diode circuit.

Refer to chart at end of section.

6AV11

Refer to chart at end of section.


6AW8

CA WOO A

6AW8A

HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in television receiver applications. The pentode unit is used as an if amplifier, video amplifier, agc amplifier, or reactance tube. The triode unit is used in low-frequency oscillator, sync-separator, sync-clipper, and phase-splitter circuits. Outlines section, 6E; requires miniature 9-contact socket. Type 8AW8A is identical with type 6AW8A except for heater ratings.




A THE O

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	6.3 0.6 11	8.4 0.45 11	volts ampere seconds
Heater-Cathode Voltage: Peak value Average value	±200 max 100 max	±200 max 100 max	volts volts
Direct Interelectrode Capacitances: Triode Unit:	Unshielded	Shielded	
Grid to Plate Grid to Cathode, Pentode Cathode, Pentode	2.2	2.2	pF
Grid No.3, Internal Shield, and Heater	3.2	3.4	рF
Plate to Cathode, Pentode Cathode, Pentode Grid No.3, Internal Shield, and Heater Pentode Unit:	1.8	3	рF
Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2.	0.06 max	$0.05~\mathrm{max}$	pF
Grid No.3, and Internal Shield	10	10	рF
No.3, and Internal Shield	3.6	4.5	\mathbf{pF}
Pentode Grid No.1 to Triode Plate Pentode Plate to Triode Plate	0.008 max		$\mathbf{p}\mathbf{F}$
Tentode Frate to Triode Piate	0.15 max	0.025 max	рF

■ With external shield connected to pins 4 and 5.

Class A, Amplifier

Class A ₁ Ampinier	
Grid-No.2 (Screen-Grid) Supply Voltage 330 Grid-No.2 Voltage See curve page Grid-No.1 (Control-Grid) Voltage, positive-bias value 0 0 Plate Dissipation 1.1 Grid-No.2 Input: 1.1 For grid-No.2 voltages up to 165 volts 1.1	volts vatts vatts
CHARACTERISTICS	800
	volts
Grid-No.1 Voitage	volts volts
	hms







Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 20 µA	4000 4 —	0.2 9500 15 3.5 —8	megohm μπhos mA mA volts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.5	0.25	megohm
	1	1	megohm



HALF-WAVE VACUUM RECTIFIER

12AX3, 17AX3

Duodecar type used as damper tube in horizontal-deflection circuits of television receivers. Outlines section, 8C; requires 12-contact socket. Socket terminals 5, 6, 8, and 9 should not be used as tie points. This tube, like other power-handling tubes, should be adequately ventilated. Types 12AX3 and 17AX3 are identical with type 6AX3 except for heater ratings.

Heater Voltage (ac/dc)	1.2	12AX3 12.6 0.6	17 A X3 16.8 0.45	volts amperes
Heater Warm-up Time (Average) Direct Interelectrode Capacitances:		11	11	seconds
Plate to Cathode and Heater Cathode to Plate and Heater Heater to Cathode			5.5 7.5 2.8	pF pF pF

Damper Service

For operation in a 525-line, 30-frame system

MAXIMUM KATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage#		volts
Peak Plate Current		mA
Average Plate Current		m A
Plate Dissipation	5.3	watts
Heater-Cathode Voltage:		
Peak value	- -500 0	volts
Average value +100	900	volts

CHARACTERISTIC

Tube Voltage Drop for plate current of 250 mA volts # Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

Refer to chart at end of section.

(Decise Marrimum Values)

6AX4GT



HALF-WAVE VACUUM RECTIFIER

6AX4GTB 12AX4GTB, 17AX4GTA

Glass octal type used as damper tube in horizontaldeflection circuits of color and black-and-white television receivers. Outlines section, 13D; requires octal socket. May be supplied with pin No. 1 omitted. Socket terminals 1, 2, 4, and 6 should not be used as tie

6AX4-

12AX4- 17AX4-

points. This tube, like other power-handling tubes, should be adequately ventilated. Types 12AX4GTB and 17AX4GTA are identical with type 6AX4GTB except for heater ratings.

	GTB	GTB	GTA	
Heater Voltage (ac/dc)	6.3	12.6	16.8	volts
Heater Current	1.2	0.6	0.45	amperes
		11	11	seconds
Direct Interelectrode Capacitances (Approx.):				
Cathode to Plate and Heater			8.5	p F
Plate to Cathode and Heater			5	pF
Heater to Cathode			4	pF

Damper Service

For operation in a 525-line, 30-frame system


MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage#		volts
Peak Plate Current		mA
Average Plate Current	165	m A
Plate Dissipation	5.3	watts
Heater-Cathode Voltage:		
Peak value	—5000	volts
Average value	-900	volts
CHARACTERISTIC, Instantaneous Value		
Tube Voltage Drop for plate current of 250 mA	32	volts
# Pulse duration must not exceed 15% of a horizontal scanning	cycle (10	microseconds).

6AX5GT

FULL-WAVE VACUUM RECTIFIER


Glass octal type used in power supplies of radio equipment having moderate dc requirements. Outlines section, 13D; requires octal socket. This type may be supplied with pin No. 1 omitted. This tube, like other power-handling tubes, should be adequately ventilated. Heater: volts (ac), 6.3; amperes, 1.2.

(Donies Contor Values)



Full-Wave Rectifier

MAXIMUM RATINGS (Design-Center values)			
Peak Inverse Plate Voltage Peak Plate Current (Per Plate) Hot-Switching Transient Plate Current:		1250 375	volts mA
For duration of 0.2 second maximum AC Plate Supply Voltage (Per Plate, rms) Average Output Current (Per Plate, rms) Peak Heater-Cathode Voltage		See R	amperes ating Chart ating Chart volts
TYPICAL OPERATION WITH CAPACITOR INPUT TO FILTER	₹		
AC Plate-to-Plate Supply Voltage (rms)	700 10	900	volts μF
Effective Plate-Supply Impedance Per Plate DC Output Voltage at Input to Filter (Approx.):	50	105	ohms
At half-load current of 62.5 mA	395	540	volts volts
At full-load current of 125 mA	350	490	volts volts
Voltage Regulation (Approx.): Half-load to full-load current	45	50	volts
	40	30	voits
TYPICAL OPERATION WITH CHOKE INPUT TO FILTER AC Plate-to-Plate Supply Voltage (rms) Filter Input Choke DC Output Voltage at Input to Filter (Approx.):	700 10#	900 10##	volts henries
At half-load current of 62.5 mA	270	365	volts volts
At full-load current of $\left\{egin{array}{lll} 150 & ext{mA} & \dots & \dots & \\ 125 & ext{mA} & \dots & \dots & \dots \end{array}\right.$	250 —	350	volts v olts



Voltage Regulation (Approx.):
Half-load to full-load current * Higher values of capacitance than indicated may be used but the effective plate-supply impedance may have to be increased to prevent exceeding the maximum rating for hotswitching transient plate current.

#This value is adequate to maintain optimum regulation provided the load current is not less than 30 mA. For load currents less than 30 mA, a larger value of inductance is required for optimum regulation.

This value is adequate to maintain optimum regulation provided the load current is not less than 35 mA. For load currents less than 35 mA, a larger value of inductance is required for optimum regulation.

Refer to chart at end of section.

6AX8 6AY3

Refer to chart at end of section.



HALF-WAVE VACUUM RECTIFIER

6AY3B

12AY3A, 17AY3A

Novar type used as damper tube in horizontal-deflection circuits of black-and-white television receivers. Outlines section, 30B; requires novar 9-contact socket.

9HP Socket terminals 1, 3, 6, and 8 should not be used as tie points. It is especially important that these tubes, like other power-handling tubes, be adequately ventilated. Types 12AY3A and 17AY3A are identical with type 6AY3B except for heater ratings.

Heater Voltage (ac/de)	6.3 1.2	12A ¥3A 12.6 0.6	17A Y 3A 16.8 0.45	volts amperes
		11	11	seconds
Direct Interelectrode Capacitances (Approx.): Plate to Cathode and Heater Cathode to Plate and Heater			6.5 9	pF pF
Heater to Cathode			2.8	pF

Damper Service For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)

Peak Inverse Plate Voltage#		5000	volts
Peak Plate Current		1100	mA
Average Plate Current		175	mA
Plate Dissipation		6.5	watts
Heater-Cathode Voltage:			
Peak value	+800	5000	volts
Average value	+100	—900	volts
CHARACTERISTIC. Instantaneous Value			

volts Tube Voltage Drop for plate current of 350 mA # Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

Refer to chart at end of section.

6AY11



MEDIUM-MU TRIODE... SHARP-CUTOFF PENTODE

6**4**78

Miniature type used in color and black-and-white television receiver applications. The pentode unit is used as an if amplifier, video amplifier, agc amplifier, or reactance tube. The triode unit is used in low-frequency oscillator, sync-separator, sync-clipper, and phasesplitter circuits. Outlines section, 6B; requires miniature 9-contact socket.

Heater Voltage (ac/dc) Heater Current	6.3 0.45	volts ampere
Heater-Cathode Voltage: A Peak value Average value	±200 max 100 max	volts volts

Triede Unit Pentode Unit

Direct Interelectrode Capacitances:		
Triode Unit:		
Grid to Plate	1.7	p F p F
Grid to Cathode, Heater, Pentode Grid No.3, and Internal Shield	2	p F
Plate to Cathode, Heater, Pentode Grid No.3, and Internal Shield	1.7	рF
Pentode Unit:		
Grid No.1 to Plate	0.02 max	рF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and		
Internal Shield	6 .5	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and		
Internal Shield	2.2	pF pF
Triode Grid to Pentode Plate	0.027 max	рF
Pentode Grid No.1 to Triode Plate	0.020 max	рF
Pentode Plate to Triode Plate	0.045 max	рF

A The heater-cathode voltage of the pentode unit should not exceed the value of the operating cathode bias. Grid No.3 will be made negative with respect to cathode if this value is exceeded, and thus possibly cause a change in tube characteristics.

Class A, Amplifier

MAXIMUM RATINGS (Design-Center Values)

Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage	300	300 300	volts volts
Grid-No.2 Voltage			curve page 300
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	0	volts
Plate DissipationGrid-No.2 Input:	2.6	2	watts
For grid-No.2 voltages up to 150 volts	_	0.5	watt
For grid-No.2 voltages between 150 and 300 volts	_	See o	curve page 300
CHARACTERISTICS	Triode Unit	Pentode	
Plate Supply Voltage	200	200	volts
Grid-No.2 Voltage		150	volts
Grid-No.1 Voltage	6	-	volts
Cathode-Bias Resistor		180	ohms
Amplification Factor	19	_	
Plate Resistance (Approx.)	5750	300000	ohms
Transconductance	3800	6000	μ mhos
Plate Current	18	9.5	mA
Grid-No.2 Current		3	m A
Grid-No.1 Voltage (Approx.) for plate current of			
10 μΑ	19		volts
Grid-No.1 Voltage (Approx.) for transconductance			
of 100 μmhos	_	12.5	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:*			
For fixed-bias operation	0.5	0.25	megohm
For cathode-bias operation	1	1	megohm


* If either unit is operating at maximum rated conditions, grid-No.1-circuit resistance for both units should not exceed the stated values.

6B4G	Refer to chart at end of section.
6B5	Refer to chart at end of section.
6B6G	Refer to chart at end of section.
6B7 6B7S	Refer to chart at end of section.
6B8 6B8G	Refer to chart at end of section.

6B10


TWIN DIODE— MEDIUM-MU TWIN TRIODE

Duodecar type used in television receiver applications; diode units are used in horizontal-phase-detector circuits, and triode units are used in horizontal-oscillator circuits. Outlines section, 8A; requires duodecar 12-contact socket. Type 8B10 is identical with type 6B10 except for heater ratings.



12BF

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	6B10 6.3 0.6 11	8B10 8.5 0.45 11	volts ampere seconds
Heater-Cathode Voltage: Peak value Average value	±200 max 100 max	±200 max 100 max	volts volts
Class A, Amplifier (Each Trio	de Unit)		
MAXIMUM RATING (Design-Maximum Value) Plate Voltage Average Cathode Current Plate Dissipation		330 20 3	volts mA watts
CHARACTERISTICS Plate Voltage Grid Voltage		250 8	volts volts
Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid Voltage (Approx.) for plate current of 50 \(\mu A \)		18 7200 2500 10 20	ohms µmhos mA volts
MAXIMUM CIRCUIT VALUES Grid-Circuit Resistance: For fixed-bias operation For cathode-bias operation		0.25 1	megohm megohm
Diode Units (Each Uni	t)		
Plate Current		5	m A
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop for plate current of 20 mA		5	volts
Refer to chart at end of section.		6BA3	3
For replacement use type 6BA6/EF93.		6BA6	•



REMOTE-CUTOFF PENTODE

6BA6/EF93

12BA6

Miniature types used as rf amplifiers in standard broadcast and FM receivers, as well as in wide-band, high-frequency applications. The low value of grid-No.1-to-plate capacitance minimizes regenerative effects, while the high transconductance makes possible high signal-to-noise ratio. Outlines section, 5C; require miniature 7-contact socket. Type 12BA6 is identical with type 6BA6/EF93 except for heater ratings.

Heater Voltage (ac/dc) 63 Heater Current 0.3	12BA6 12.6 0.15	volts ampere
Heater-Cathode Voltage: Peak value ±200 max	±200 max	volts
Average value		volts
Direct Interelectrode Capacitances:		_
Grid No.1 to Plate	0.0035 max	pF
Internal Shield	5.5	$p\mathbf{F}$
Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield	~ _	10
Internal Smeld	5•	pr.

This value is 5.5 pF with external shield connected to cathode.

Class A. Amplifier

Class A ₁ Amplifier	
MAXIMUM RATINGS (Design-Maximum Values)	
Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 (Screen-Grid) Voltage Grid-No.2 Supply Voltage	. 0 volts . See curve page 300 . 330 volts
Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 165 volts	
For grid-No.2 voltages between 165 and 330 volts Grid-No.1 (Control-Grid) Voltage:	. See curve page 300
Negative-bias value Positive-bias value	
CHARACTERISTICS	
Plate Supply Voltage 100 Grid No.3 and Internal Shield Conn Grid-No.2 Supply Voltage 100 Cathode-Bias Resistor 68 Plate Resistance (Approx.) 0.25 Transconductance 4300 Plate Current 10.8 Grid-No.2 Current 4.4 Grid-No.1 Voltage (Approx.) for transconductance of 40 μmhos -20 -20	250 volts ected to cathode at socket 100 volts 68 ohms 1 megohm 4400
TYPE 6BA6 GRID-No. 2 VOLTS = 100 GRID-No. 3 VOLTS = 0 SY-011	0 0 0 0

Installation and Application

200 PLATE VOLTS

92CS-6609T

Control-grid bias variation is effective in changing the volume of the receiver. To obtain adequate volume control, an available grid-No.1-bias voltage of approximately 50 volts is required. The exact value depends upon the circuit design and operating conditions. This voltage may be obtained, depending on the receiver requirements, from a potentiometer across a fixed supply voltage, from a variable cathode-bias resistor, from the avc system, or from a combination of these methods.

The grid-No.2 (screen-grid) voltage may be obtained from a potentiometer or bleeder circuit across the B-supply source, or through a dropping resistor from the plate supply. The use of series resistors for obtaining satisfactory control of grid-No.2 voltage in the case of four-electrode tubes is usually impossible because of secondary-emission phenomena. In the 6BA6, however, because grid No.3 practically removes these effects, it is practical to obtain grid-No.2 voltage through a series-dropping resistor from the plate supply or from some high intermediate voltage, provided the source does not exceed the plate-supply voltage. With this method, the grid-No.2-to-cathode voltage will fall off very little from minimum to maximum value of the resistor controlling cathode bias. In some cases, it may actually rise. This rise of grid-No.2-to-cathode voltage above the normal maximum value is allowable because both the grid-No.2 current and the plate current are reduced simultaneously by a sufficient amount to prevent damage to the tube. It should be recognized that, in general, the series-

resistor method of obtaining grid-No.2 voltage from a higher voltage supply necessitates the use of the variable cathode-resistor method of controlling volume in order to prevent too high a voltage on grid No.2. When grid-No.2 and control-grid voltage are obtained in this manner, the remote "cutoff" advantage of the 6BA6 can be fully realized. However, it should be noted that the use of a resistor in the grid-No.2 circuit has an effect on the change in plate resistance with variation in grid-No.3 (suppressor-grid) voltage in case grid No.3 is utilized for control purposes.



Honton Voltage

PENTAGRID CONVERTER

6BA7

. .

Miniature type used as converter in AM and FM receivers. Outlines section, 6E: requires miniature 9contact socket.

neater voitage	6,3	voits
Heater Current	0.3	ampere
Peak Heater-Cathode Voltage	±90	volts
Direct Interelectrode Capacitances:		
Grid No. 3 to All Other Electrodes	9.5	рF
Plate to All Other Electrodes	8.3	ρF
Grid No. 1 to All Other Electrodes	6.7	ÞF
Grid No. 3 to Plate	0.19 max	pF
Grid No. 3 to Grid No. 1	0.15 max	pF
Grid No. 1 to Plate	0.05 max	pF
Grid No. 1 to All Other Electrodes, except Cathode	3.4	рF
Grid No. 1 to Cathode	3.3	pF
Cathode to All Other Electrodes except Grid No. 1	4	$\bar{\mathbf{p}}\mathbf{F}$
Converter Service		
MAXIMUM RATINGS (Design-Center Values)		
· · · · · · · · · · · · · · · · · · ·	300	volts
Plate Voltage		
Grid-No.5-and-Internal-Shield Voltage	. 0	volts
Grids-No2-and-No.4 (Screen-Grid) Voltage	100	volts
Grids-No.2-and-No.4 Supply Voltage	300	volts
Plate Dissipation	2	watts
Grids-No.2-and-No.4 Input	1.5	watts
Total Cathode Current	22	mA
Grid-No.3 Voltage:	_	
Negative-bias value	100	volts
Positive-bias value	Ŏ	volts
A OUTSITE DIEGO THANKS THE THE THE TENED	ŭ	,0163
CHARACTERISTICS (Separate Excitation)*		

Plate Voltage	100	250	volts
Grid No.5 and Internal Shield	Cor	nnected direc	tly to ground
Grids-No.2-and-No.4 (Screen-Grid) Voltage	100	100	
Grid-No.3 (Control-Grid) Voltage	—1	1	volt
Grid-No.1 (Oscillator-Grid) Resistor	20000	20000	ohms
Plate Resistance (Approx.)	0.5	1	megohm
Conversion Transconductance	900	950	μ mhos
Conversion Transconductance (Approx.)**	3.5	3.5	μmhos
Plate Current	3.6	3.8	mA
Grids-No.2-and-No.4 Current	10.2	10	mA
Grid-No.1 Current	0.35	0.35	mA
Total Cathode Current	14.2	14.2	mA

NOTE: The transconductance between grid No.1 and grids No.2 and No.4 connected to plate (not oscillating) is approximately 8000 μ mhos under the following conditions: signal applied to grid No.1 at zero bias; grids No.2 and No.4 and plate at 100 volts; grid No.3 grounded. Under the same conditions, the plate current is 32 milliamperes, and the amplification factor is 16.5.

^{*} The characteristics shown with separate excitation correspond very closely with those obtained in a self-excited oscillator circuit operating with zero bias.

^{**} With grid-No.3 bias of -20 volts.

A Internal Shield (pins No.6 and No.8) connected directly to ground.

6BA8A


0.5

6BA8A

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in color and black-and-white television receivers. The pentode unit is used as a video amplifier, an agc amplifier, or a reactance tube. The triode unit is used in low-frequency oscillator and phase-splitter circuits. Outlines section, 6E; requires miniature 9-contact socket. Type 8BA8A is identical with type 6BA8A except for the heater ratings.

Heater Voltage (ac/dc)



volts

8BA8A

Heater voltage (ac/dc)	0.3	8.4	VOILS
Heater Current	0.3	0.45	ampere
Heater Warm-up Time (Average)	11		seconds
Heater-Cathode Voltage:			
Peak value	±200 max	t ±200 max	volts
			volts
Average value	100 max	100 max	VOILS
Direct Interelectrode Capacitances (Approx.):			
Triode Unit:			
Grid to Plate	2.2	2.2	рF
Grid to Cathode and Heater	2.5	2.7	ρF
Plate to Cathode and Heater	0.4	1.9	ρF
	0.4	1.5	DI.
Pentode Unit:			
Grid No.1 to Plate	0.06	0.05	рF
Grid No.1 to Cathode, Heater, Grid No.2, Grid			
No.3, and Internal Shield	10	10	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3,			
	3.6	4.5	рF
			pF
Triode Grid to Pentode Plate	0.016	0.006	
Pentode Grid No.1 to Triode Plate	0.006	0.003	$\mathbf{p}\mathbf{F}$
Pentode Plate to Triode Plate	0.15	0.023	₽F
Class A ₁ Amplifie	r		
MAXIMUM RATINGS (Design-Center Values)	Truta de Truta	Pentode Uni	
MAXIMOM RATINGS (Design-Center Values)	Triode Citt	I chitode Om	
-1	300	300	volts
Plate Voltage		300	volts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage	300	300 300	volts volts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage	300	300 300	volts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage:	300	300 300 See curv	volts volts e page 300
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value	300	300 300 See curv 50	volts volts e page 300 volts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value	300	300 300 See curv 	volts volts e page 300 volts volts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value	300	300 300 See curv 50	volts volts e page 300 volts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation	300	300 300 See curv 	volts volts e page 300 volts volts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input:	300	300 300 See curv 50 0 3.25	volts volts e page 300 volts volts watts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts	300	300 300 See curv 50 0 3.25	volts volts e page 300 volts volts watts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input:	300	300 300 See curv 50 0 3.25	volts volts e page 300 volts volts watts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts	300	300 300 See curv 50 0 3.25	volts volts e page 300 volts volts watts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS	300	300 300 See curv 50 0 3.25 1 See curv	volts volts e page 300 volts volts watts watt e page 300
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate-Supply Voltage	300	300 300 See curv 60 0 3.25 1 See curv	volts volts e page 300 volts volts watts watt e page 300 volts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS	300	300 300 See curv 50 0 3.25 1 See curv	volts volts e page 300 volts volts watts e page 300 volts volts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate-Supply Voltage Grid-No.2 Supply Voltage	300	300 300 See curv 60 0 3.25 1 See curv	volts volts e page 300 volts volts watts watt e page 300 volts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate-Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Grid-No.1 Voltage	300 	300 300 See curv —60 0 3.25 1 See curv	volts volts e page 300 volts volts volts watts watt e page 300 volts volts volts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate-Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Grid-No.1 Voltage Cathode-Bias Resistor	300 	300 300 See curv —60 0 3.25 1 See curv 200 150 —180	volts volts e page 300 volts volts watts e page 300 volts volts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate-Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Cathode-Bias Resistor Amplification Factor	300 	300 300 See curv —50 0 3.25 1 See curv 200 150	volts volts e page 300 volts volts watts watt e page 300 volts volts volts ohms
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate-Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Grid-No.1 Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.)	300 	300 300 See curv -60 0 3.25 1 See curv 200 150 180 40000	volts volts e page 300 volts watts watt e page 300 volts volts volts volts ohms
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate-Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance	300 	300 300 See curv -60 0 3.25 1 See curv 200 150 180 400000	volts volts e page 300 volts watts watte e page 300 volts volts volts ohms ohms
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate-Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Grid-No.1 Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current	300 	300 300 See curv 60 0 3.25 1 See curv 200 150 180 400000 9000 13	volts volts e page 300 volts volts watts watte page 300 volts volts volts volts ohms ohms µmhos mA
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate-Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Grid-No.1 Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current	300 	300 300 See curv -60 0 3.25 1 See curv 200 150 180 400000	volts volts e page 300 volts watts watte e page 300 volts volts volts ohms ohms
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate-Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Grid-No.1 Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current	300 	300 300 See curv 60 0 3.25 1 See curv 200 150 180 400000 9000 13	volts volts e page 300 volts volts watts watte page 300 volts volts volts volts ohms ohms µmhos mA
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage: Negative-bias value Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts CHARACTERISTICS Plate-Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Grid-No.1 Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current	300 	300 300 See curv 60 0 3.25 1 See curv 200 150 180 400000 9000 13	volts volts e page 300 volts volts watts watte page 300 volts volts volts volts ohms ohms µmhos mA

6BA11


MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance:

For fixed-bias operation
For cathode-bias operation

8BA11

TRIODE-TWIN PENTODE

Duodecar type used as vertical-deflection oscillator and for combined sync-age applications in color and black-and-white television receivers. Outlines section, 8B; requires duodecar 12-contact socket. Type 8BA11 is identical with type 6BA11 except for heater ratings.



megohm

megohm

12ER

Heater Voltage (ac/dc)	6BA11 6.3 0.6	8BA11 8.4 0.45	volts amperes
Heater Current Heater Warm-up Time Heater-Cathode Voltage:	ïi	11	seconds
Peak value Average value Direct Interelectrode Capacitances: Triode Unit:	±200 max 100 max	±200 max 100 max	volts volts
Grid to Plate Grid to Cathode and Heater Plate to Cathode, Heater, and Internal Shield		2 2 1.9	pF pF pF
Pentode Unit Grid No.3 to Plate (Each Unit) Grid No.3 to all Other Electrodes (Each Grid) Grid No.1 to all Other Electrodes) Plate to all Other Electrodes (Each Plate) Grid No.3 of Pentode 1 to Grid No.3 of Pentode 2		2 3.6 6 3 0.026 max	pF pF pF pF
Triode Unit as Class A, Am	plifier		
MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage		300	volts
Average Cathode Current Plate Dissipation CHARACTERISTICS		20 1.5	mA watts
Plate Voltage Grid Voltage Amplification Factor		250 —11 18	volts volts
Transconductance		1800	μmhos
Plate Current		18	mA volts
MAXIMUM CIRCUIT VALUES			
Grid-Circuit Resistance: For fixed-bias operation For cathode-bias operation		0. 2 5	megohm megohm
Pentode Unit as Class A. An	nplifier		
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage (Each Unit) Grid-No.3 (Suppressor-Grid) Voltage (Each Unit): Peak positive value		300	volts
Peak positive value		50	volts
		50 3	volts volts
DC positive value Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage, Negative bias value		150	volts
		50 12	volts mA
Plate Dissipation (Each Unit) Grid-No.2 Input		1.1	watts
Grid-No.2 Input		0.75	watt
CHARACTERISTICS (With Both Units Operating)■			
Plate Voltage (Each Unit) Grid-No.3 Voltage (Each Unit) Grid-No.2 Voltage	100 —10	100	volts volts
Grid-No.2 Voltage (Each Offic)	67.5	67.5	volts
Grid-No.1 Voltage Plate Current (Each Unit)	0	* 2.5	volts mA
Grid-No.2 Current	ř	4.4	mA
CHARACTERISTICS (With One Unit Operating) †			
Plate Voltage	100	100	volts
C. 11 37 0 37.14	0 67.5	0 0	volts volts
Grid-No.2 Voltage Grid-No.2 Voltage Grid-No.1 Voltage Grid-No.3 Transconductance Grid-No.1 Transconductance	0	67.5	volts
Grid-No.3 Transconductance	1700	450	μmhos μmhos
		2.5	mA
Grid-No.2 Voltage (Approx.) for plate current of 100 µA	_	3.2	volts
Grid-No.1 Voltage (Approx.) for plate current of	2 2		
100 μΑ	2.3		volts
MAXIMUM CIRCUIT VALUES			_
Grid-No.3-Circuit Resistance (Each Unit) Grid-No.1-Circuit Resistance			megohm megohm
*Adjusted to provide a dc grid-No.1 current of 100 micross t With plate and grid No.3 of the other unit connected to salvoltages and plate current apply to each section.	mperes. ground.		

6BC4

MEDIUM-MU TRIODE

Miniature type used as an rf amplifier in the cathodedrive circuits of uhf television tuners covering the frequency range of 470 to 890 MHz. Outlines section, 6A; requires miniature 9-contact socket.



9DR

Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage Direct Interelectrode Capacitances (Approx.):	6.3 0.225 ±75 max	volts ampere volts
Grid to Plate Grid to Heater and Cathode Plate to Heater and Cathode Heater to Cathode	1.6 2.9 0.26 2.7	pF pF pF pF
Class A, Amplifier		
MAXIMUM RATINGS (Design-Center Values)		
Plate Voltage Cathode Current Plate Dissipation	250 25 2.5	volts mA watts
CHARACTERISTICS		
Plate Supply Voltage Cathode-Bias Resistor Amplification Factor	150 100 48	volts ohms
Plate Resistance (Approx.) Transconductance Plate Current	4800 10000 14.5	ohms µmhos mA
Grid Voltage (Approx.) for plate current of 10 μA	10	volts
MAXIMUM CIRCUIT VALUES		
Grid-Circuit Resistance:		

6BC5

For fixed-bias operation


For cathode-bias operation

Refer to chart at end of section.

6BC5/6CE5 SHARP-CUTOFF PENTODE

3BC5/3CE5

Miniature type used in compact radio equipment as an rf or if amplifier at frequencies up to 400 MHz. Outlines section, 5C; requires miniature 7-contact socket. For typical operation as resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Type 3BC5/3CE5 is identical with type 6BC5/6CE5 except for heater ratings.



Not recommended

megohm

7BD

	3BC5/3CE5	6BC5/6CE5	
Heater Voltage (ac/dc)	3.15	6.3	volts
Heater Current	0.6	0.3	ampere
Heater Warm-up Time (Average)	11		seconds
Heater-Cathode Voltage:			
Peak value	±200 max	±90 max	volts
Average value	100 max		volts
Direct Interelectrode Capacitances:	100 max		10.03
Pentode Connection:			
Grid No.1 to Plate		0.030 max	рF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.		U.UOU IIIAA	pr
			- 77
Internal Shield		6.5	pF
Plate to Cathode, Heater, Grid No.2, Grid No.3, a			_
Shield		1.8	pF
Triode Connection:*			
Grid No.1 to Plate and Grid No.2		2.5	pF
Grid No.1 to Cathode, Heater, Grid No.3, and Interna	al Shield	3.9	pF
Plate and Grid No.2 to Cathode, Heater, Grid No.3	3. and		-
Internal Shield		3	pF
		-	

^{*} Grid No.2 connected to plate.

Class A₁ Amplifier


MAXIMUM RATINGS (Design-Center Values)	Co	Triode nnecti		Pento Connec		
Plate Voltage		300		300		volts
Grid-No.2 (Screen-Grid) Supply Voltage		_		300		volts
Grid-No.2 Voltage			See	curve	page 30	00
Grid-No.1 (Control-Grid) Voltage, Positive-bias value.		0		0		volts
Plate Dissipation		2.5		2		watts
Grid-No.2 Input:						
For grid-No.2 voltages up to 150 volts		_		0.5		watt
For grid-No.2 voltages between 150 and 300 volts.			See 4	curve	page 30)0
	Tr	lode		Pento	de	
CHARACTERISTICS	Conr	rection		Conne	ction	
Plate Supply Voltage	180	250	100	12	5 250	volts
Grid-No.2 Supply Voltage			100			volts
Cathode-Bias Resistor	330	820	180	100	180	ohms
Amplification Factor	42	40	_			
Plate Resistance (Approx.)		0.009	0.6	0.5	0.8	megohm
Transconductance	6000	4400	4900	6100	D 5700	μmhos
Plate Current	8	6	4.7			mA
Grid-No.2 Current	_		1.4	2.	4 2.1	mA
Grld-No.1 Voltage (Approx.) for plate current of						
10 μΑ		_	5		5 —8	volts
• Grid No.2 connected to plate.						
= · ·						

Refer to chart at end of section.

6BC7

For replacement use type 6BC8/6BZ8.

6BC8



MEDIUM-MU TWIN TRIODE

6BC8/6BZ8

Miniature type used as a cascode amplifier in vhf television tuners and in push-pull cathode-drive rf amplifiers. Outlines section, 6B; requires miniature 9-contact socket. Type 4BC8 is identical with type 6BC8/6BZ8 except for heater ratings.

77 -4 77 34 (1.)	4BC8	6BC8/6BZ8	
Heater Voltage (ac/dc)	4.2	6.3	volts
Heater Current	0.6	0.4	ampere
Heater Warm-up Time (Average)	11		seconds
Heater-Cathode Voltage:			
Peak value	±200 *ms	x ±200*max	volts
Average value	100 ma	x 100 max	volts
Direct Interelectrode Capacitances*:	Unit No.1	Unit No.2	
Grid to Plate	1.2	1.2	рF
Grid to Cathode, Heater, and Internal Shield	2.6	===	pF
Cathode to Grid, Heater, and Internal Shield		5.5	pF
Plate to Cathode, Heater, and Internal Shield	1.3		pF
Plate to Grid, Heater, and Internal Shield		2.4	pF
Plate to Cathode		0.12	pF
Heater to Cathode	2.8	2.8	ρF
Plate of Unit No.1 to Plate of Unit No.2	0.02	max	pF
Plate of Unit No.2 to Plate and Grid of Unit No.1	0.04	max	pF
* Reting may be so high as 200 volts under sutoff condition	me —h.m 4		

* Rating may be as high as 300 volts under cutoff conditions, when tube is used as a cascode amplifier, the two units are connected in series, and heater is negative with respect to cathode. * With external shield connected to internal shield.

Class A. Amplifier (Each Unit)

MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage Cathode Current Plate Dissipation	250 • 22 2.2	volts mA watts
CHARACTERISTICS		
Plate Supply Voltage	150	volts
Cathode-Bias Resistor Plate Resistance (Approx.)	220 5300	ohms ohms
Amplification Factor Transconductance	35 6 20 0	μmhos
Plate Current Grid Voltage (Approx.) for transconductance of 50 μmhos	10 13	mA volts

MAXIMUM CIRCUIT VALUES


6BD4 6BD4A	Refer to chart at end of section.
6BD6	Refer to chart at end of section.
6BD11	Refer to chart at end of section.
6BE3	For replacement use type 6BE3/6BZ3.

6BE3/6BZ3

HALF-WAVE VACUUM RECTIFIER

12BE3, 17BE3/17BZ3

Duodecar type used as damper tube in horizontal-de-MC(3 flection circuits of color and black-and-white television receivers. Outlines section, 8D; requires duodecar 12-contact socket. Types 12BE3 and 17BE3/17BZ3 are identical with type 6BE3/6BZ3 except for heater ratings.



Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)		12BE3 12.6 0.6 11	17BE3/ 17BZ3 16.8 0.46 11	volts ampere seconds
Direct Interelectrode Capacitances (Approx.): Plate to Cathode, and Heater Cathode to Heater, and Plate Heater to Cathode	<i></i> .		10 8 3.4	pf pf pf

Damper Service

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum values)			
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current			volts mA mA
Plate Dissipation		6.5	watts
Heater-Cathode Voltage: Peak value Average value	$^{+300}_{+100}$	5000 900	volts volts
CHARACTERISTIC Instantaneous Value			

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

6BE6

PENTAGRID CONVERTER

Miniature type used as converter in AM and FM receivers. Outlines section, 5C; requires miniature 7-contact socket. For general discussion of pentagrid types, see Frequency Conversion in Electron Tube Applications section. Type 12BE6 is identical with type 6BE6 except for heater ratings.

Tube Voltage Drop for dc plate current of 350 mA



volts

7CH

			6 BE 6	12BE6	
Heater	Voltage	(ac/dc)	6.3	12.6	volts
Heater	Current		0.3	0.15	ampere

of 10 μmhos

Heater-Cathode Voltage:		±000 (
Peak value	±200 max 100 max	±200 max 100 max	volts volts
Direct Interelectrode Capacitances:	Unshielded		_
Grid No.3 to Plate	0.30 max	0.25 max	рF
Grid No.3 to Grid No.1	0.15 max	0.15 max	pF pF
Grid No.1 to Plate	0.10 max 7	0.05 max 7	pr pF
Grid No.1 to All Other Electrodes	5.5	5.5	pF
Plate to All Other Electrodes	8.0	13.0	ρF
Grid No.1 to Cathode and Grid No.5	3	3	рF
Cathode and Grid No.5 to All Other Electrodes			_
except Grid No.1	15	20	рF
• With external shield connected to cathode and grid N	lo.5.		
Converter			
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage		330	volts
Grids-No.2-and-No.4 (Screen-Grid) Voltage		110	volts
Grids-No.2-and-No.4 Supply Voltage		330	volts
Cathode Current		15.5	mA
Plate Dissipation		1.1 1.1	watts watts
Grids-No.2-and-No.4 Input		1.1	watts
Negative-bias value		55	volts
Positive-bias value		Ö	volts
Heater-Cathode Voltage:			
Peak value		200	volts
Average value		100	voits
TYPICAL OPERATION (Separate Excitation)*			
The TT	100	250	volts
Grids-No.2-and-No.4 (Screen-Grid) Voltage	100	100	volts
Grid-No.1 (Oscillator-Grid) Voltage (rms)	10	10	volts
Grid-No.1 (Oscillator-Grid) Voltage (rms)	-1.5	1.5	volts
Grid-No.1 (Oscillator-Grid) Resistor	20000	20000	ohms
Plate Resistance (Approx.)	0.4	1	megohm
Conversion Transconductance	455	475	μmhos
Plate Current	2.6	2.9 6.8	mA mA
Grids-No.2-and-No.4 Current	7.0 0.5	0.5	mA
Grid-No.1 Current Cathode Current	10.1	10.2	mA
Grid-No.3 Voltage for conversion transconductance	10.1		
of 10 when	30	30	volts

NOTE: The transconductance between grid No.1 and grids No.2 and No.4 connected to plate (not oscillating) is approximately 7250 μ mhos under the following conditions: grids No.1 and No.3 at 0 volts; grids No.2 and No.4 and plate at 100 volts. Under the same conditions, the cathode current is 25 mA, and the amplification factor is 20. Grid-No.1 voltage (Approx.) for plate current of 10 μ A is -11 volts.

-30


Installation and Application


Because of the special structural arrangement of the 6BE6, a change in signal-grid voltage produces little change in cathode current. Consequently, an rf voltage on the signal grid produces little modulation of the electron current flowing in the cathode circuit. This feature is important because it is desirable that the impedance in the cathode circuit should produce little degeneration or regeneration of the signal-frequency input and intermediate-frequency output. Another important feature is that, because signal-grid voltage has very little effect on the space charge near the cathode, changes in ave bias produce little change in oscillator transconductance and in the input capacitance of grid No.1. There is, therefore, little detuning of the oscillator by ave bias.

A typical self-excited oscillator circuit employing the 6BE6 is given in the Circuits section.

In the 6BE6 operation characteristics curves with self-excitation, E_k is the voltage across the oscillator-coil section between cathode and ground; E_g is the oscillator voltage between cathode and grid.

^{*} The characteristics shown with separate excitation correspond very closely with those obtained in a self-excited circuit operating with zero bias.





6BF5

Refer to chart at end of section.

6BF6


Refer to chart at end of section.

17RF11

6BF11 BEAM POWER TUBE-SHARP-CUTOFF PENTODE 12BF11, 17BF11, 24BF11

Duodecar type used as combined detector and amplifier tube in color and black-and-white television receivers. The dual-control, sharp-cutoff pentode unit is used as an FM detector and the beam power unit as an af output amplifier. Outlines section, 8C; requires duodecar 12contact socket. Types 12BF11, 17BF11 and 24BF11 are identical with type 6BF11 except for heater ratings.

6BF11



24BF11

Heater Voltage (ac/dc)		12.6	16.8	24.2	volts
Heater Current		0.6	0.45	0.315	amperes
Heater Warm-up Time (Average)	_	11	11	11	seconds
Heater-Cathode Voltage:					
Peak value	±200 max	$\pm 200 \text{ max}$	$\pm 200 \text{ max}$	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances	:				
Pentode Unit:				0.00	-
Grid No.1 to Plate			· · · · · · · · · · · ·	0.36	рF
Grid No.3 to Plate				3.2	рF
Grid No.1 to Cathode, Heat					-
and Internal Shield				6.5	pF
Grid No.3 to Cathode, Heater				•	73
and Internal Shield				. 8	pF
Grid No.1 to Grid No.3			· · · · · · · · · · · ·	0.11	pF
Beam Power Unit:					
Grid No.1 to Plate	Cold N			0.24	pF
Grid No.1 to Cathode, Heate					_
and Internal Shield			· · · · · · · · · · · · · · ·	13	рF
Plate to Cathode, Heater, Gr				4.0	. •
and Internal Shield				10	р F
Pentode Plate to Beam Power	Plate			0.13	pF


12BF11

CHARACTERISTICS

MAXIMUM RATINGS (Design-Maximum Values)

Beam Power Unit as Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Values)		4
Plate Voltage	165	volts
Grid-No.2 (Screen-Grid) Voltage	150	volts
Average Cathode Current	65	mA
Plate Dissipation	6.5	watts
Grid-No.2 Input	1.8	watts
TYPICAL OPERATION		
Plate Voltage	145	volts
Grid-No.2 Voltage	110	volts
Grid-No.1 (Control-Grid) Voltage	-6	volts
Peak AF Grid-No.1 Voltage	— ç	
Zono Cimes Dist. Comment	.0	volts
Zero-Signal Plate Current	36	m,A
Maximum-Signal Plate Current	40	m A
Zero-Signal Grid No.2 Current	3	m A
Maximum-Signal Grid-No.2 Current	9	m.A.
Plate Resistance (Approx.)	0.03	megohm
Transconductance	8600	μmhos



Load Resistance Total Harmonic Distortion Maximum-Signal Power Output	3000 10 2.4	ohms per cent watts
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.25 0.5	megohm megohm

Pentode Unit as Class A, Amplifier

Plate Supply Voltage	150	volts
Grid No.3 (Control-Grid) Connected to negative	end of	cathode resistor
Grid-No.2 (Screen-Grid) Supply Voltage	100	volta
Grid No.1 (Control Grid) Connected to negative	end of	cathode resistor
Cathode-Bias Resistor	560	
Plate Resistance (Approx.)	0.15	megohm
Transconductance, Grid No.1 to Plate	1000	
Transconductance, Grid No.3 to Plate	400	
Plate Current	1.3	
Grid-No.2 Current	- · · · · · · · · · · · · · · · · · · ·	
Grid-No.1 Voltage (Approx.) for plate current of 10 uA	4.5	
Grid-No.3 Voltage (Approx.) for plate current of 10 µA	4.5	

Pentode Unit as FM Sound Detector

Plate Voltage	330	volts
Grid-No.3 Voltage	28	volts
Grid No.2 Supply Voltage	330	volts
Grid-No.2 Voltage	See c	urve page 300
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	volts
Plate Dissipation	1.7	watts
Grid-No.2 Input:		
For grid No 2 voltages up to 165 volts	11	watta


For grid-No.2 voltages between 165 and 330 volts

See curve page 300

MAXIMUM CIRCUIT VALUES

Grid-No.1-Circuit Resistance:
For fixed-bias operation
For cathode-bias operation

0.25 megohm
0.5 megohm



6BG6GA

Refer to chart at end of section.


6BH3 6BH3A Refer to chart at end of section.

Refer to chart at end of section.

6BH6

SHARP-CUTOFF PENTODE

Miniature type used as rf amplifier particularly in ac/dc receivers and in mobile equipment where low heater-current drain is important. It is particularly useful in high-frequency, wide-band applications. Outlines section, 5C; requires miniature 7-contact socket.



Heater Voltage (ac/dc)	6.3	volts
Heater Current	0.15	ampere
Peak Heater-Cathode Voltage	±90 max	volts
Direct Interelectrode Capacitances:		
Grid No.1 to Plate	0.0035 max	рF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and		
Internal Shield	5.4	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and		
Internal Shield	4.4	рF
Without external shield or with external shield connected to cath	ode	

		C	lass	\mathbf{A}_1	Amplifie
MAXIMUM	RATINGS	(Design-Center	Valu	es)	


Plate Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.2 Supply Voltage Grid-No.1 (Control-Grid) Voltage:	300 volt See curve page 300 300 volt	õ
Negative-bias value Positive-bias value Plate Dissipation	0 volt	3
Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts	0.5 wat	t

CHARACTERISTICS

100	250	volts
Connected	to cathode	at socket
100	150	volts
—1	1	volt
0.7	1.4	megohms
3400	4600	μmhos
3.6	7.4	mA.
1.4	2.9	mA
5	-7.7	volts
	Connected 100 —1 0.7 3400	Connected to cathode 100 150 -1 -1 1.4 3400 4600 3.6 7.4

Refer to chart at end of section.

6BH8



MEDIUM-MU TWIN TRIODE— SHARP-CUTOFF PENTODE 6BH11

Duodecar type used in color and black-and-white television receiver applications. The triode units are used for general-purpose applications, and the pentode unit is used for horizontal-deflection service. Outlines section, 8B; requires duodecar 12-contact socket. Heater: volts (ac/dc), 6.3; amperes, 0.8; maximum heater-cathode volts, ±200 peak, 100 average.


Pentode Unit as Horizontal-Deflection Oscillator

Plate Voltage	350	volt
Grid-No.2 (Screen-Grid) Voltage	330	volt
Grid-No.1 (Control-Grid) Voltage:	000	
Positive-bias value	0	vol
Peak negative value	175	vol
Peak Cathode Current	300	m
Average Cathode Current	20	m
Plate Dissipation	2.5	wat
Frid-No.2 Input	0.55	Wat

Class A ₁ Amplifi	er		
MAXIMUM RATINGS (Design-Maximum Values)		Each Triode U	nit
Plate Voltage Grid Voltage, Positive-bias Value Plate Dissipation		330 0 2.5	volts volts watts
CHARACTERISTICS	Pentode Unit	Each Triode Unit	
Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 µA	125 125 —1 200000 7500 12 4	125 1 46 5400 8500 13.5 8	volts volt ohms µmhos mA mA volts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	2.2 2.2	2.2 2.2	megohms megohms

Refer to chart at end of section.

6BJ3



REMOTE-CUTOFF PENTODE 6BJ6

Miniature type used as rf amplifier in high-frequency and wide-band applications. Features high transconductance and low grid-to-plate capacitance. Outlines section, 5C; requires miniature 7-contact socket.

Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage	6.3 0.15 ±90 max	volts ampere volts
Direct Interelectrode Capacitances:		
Grid No.1 to Plate	0.0035 max	pF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and		•
Internal Shield	4.5	pF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and		
Internal Shield	5.5	pF

[·] Without external shield, or with external shield connected to cathode.

Class A₁ Amplifier

MAXIMUM RATINGS (Design-Center Values)			
Plate Voltage		300	volts
Grid-No.2 (Screen-Grid) Voltage		See curve	page 300
Grid-No.2 Supply Voltage		300	volts
Plate Dissipation		3	watts
Grid-No.2 Input:		=	
For grid-No.2 voltages up to 150 volts		0.6	watt
For grid-No.2 voltages between 150 and 300 volts		See curve	
Grid-No.1 (Control-Grid) Voltage:		200 00010	, - , - , - , - , - , -
Negative-bias value		50	volts
Positive-bias value		0	volts
CHARACTERISTICS			
Plate Voltage	100	250	volts
Grid No.3	Connected	to cathode	at socket
Grid-No.2 Voltage	100	100	volts
Grid-No.1 Voltage	1	—1	volt
Plate Resistance (Approx.)	0.25	1.3	megohms
Transconductance	3650	3600	μmhos
Plate Current	9	9.2	· mA
Grid-No.2 Current	3.5	3.3	mA
Grid-No.1 Voltage (Approx.) for transconductance of			

6BJ6A

Refer to chart at end of section. For replacement use type 6BJ6.

6BJ7

Refer to chart at end of section.

6BJ8


Plate Resistance

Transconductance

(Approx.)

TWIN DIODE-MEDIUM-MU TRIODE

Miniature type used in black-and-white and color television receiver applications. The diode units are used in phase-detector, phase-comparator, ratio-detector or discriminator, and horizontal afc discriminator circuits. The triode unit is used in phase-splitter, audio-frequency amplifier, vertical-deflection amplifier, and lowfrequency oscillator applications. Outlines section, 6E; requires miniature 9-contact socket.



9ER

Heater Voltage (ac/dc)	6.3	volts
Heater Current	0.6	ampere
Heater Warm-up Time (Average)	11	seconds
Heater-Cathode Voltage:		
Peak value	±200 max	volts
Average value	100 max	volts
Direct Interelectrode Capacitances:	100 man	10100
Triode Unit:	2.6	-E
Grid to Plate		pF
Grid to Cathode and Heater	2.8	ÞΕ
Plate to Cathode and Heater	0.31	þF
Diode Units:		
Plate to Cathode and Heater (Each Unit)	1.9	рF
Cathode to Plate and Heater (Each Unit)	4.6	þF
Plate of Unit No.1 to Plate of Unit No.2	0.06 max	ρF
Plate of Diode Unit No.1 to Triode Grid	0.07 max	ρF
Plate of Diode Unit No.2 to Triode Grid	0.11 max	ĎF
Plate of Either Diode Unit to All Other Electrodes	3	ρF
	4.8	ρF
Cathode of Either Diode Unit to All Other Electrodes	₩.0	Ъг
The state of the s		
Triode Unit as Class A, Amplifier		

Titude Offic as Olass At Amplifica		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage Grid Voltage, Positive-bias value Average Cathode Current Plate Dissipation	0 22	volts volts mA watts
CHARACTERISTICS Plate Voltage 90 Grid Voltage 0 Amplification Factor 22	250 —9 20	volts volts


4700

 $71\bar{50}$

ohms

μmhos

Plate Current 13.5 Plate Current for grid voltage of —12.5 volts 1 Grid Voltage (Approx.) for plate current of 10 μA 7 MAXIMUM CIRCUIT VALUE Grid-Circuit Resistance	8 1.7 18	mA mA volts megohm
Triode Unit as Vertical-Deflection Amplifier For operation in a 525-line, 30-frame system	_	
MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Voltage Peak Positive-Pulse Plate Voltage# Peak Negative-Pulse Grid Voltage Peak Cathode Current Peak Cathode Current	330 200 275 77 22	volts volts volts mA mA watts
MAXIMUM CIRCUIT VALUE		
Grid-Circuit Resistance, for cathode-bias operation	2.2 (2.5	megohms milliseconds).
Diode Units		
MAXIMUM RATINGS (Design-Maximum Values) Plate Current (Each Unit): Peak	-,	
Average	54 9	mA mA




Refer to chart at end of section.

6BK4A 6BK4A

6BK4C/ 6EL4A





Glass octal type used for the voltage regulation of high-voltage, low-current dc power supplies in color and black-and-white television receivers. Outlines section, 21B; requires octal socket. Socket terminals 3, 4, 6, and 8 should not be used for tie points. For high voltage and X-ray safety considerations, refer to page 93.

Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage Direct Interelectrode Capacitances (Approx.):1	0.2	volts ampere volts
Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater	2.6	DF DF DF

Shunt Voltage-Regulator Service

MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Voltage	27000	volts
Unregulated DC Supply Voltage	60000	volts
DC Grid Voltage	135	volts
Peak Grid Voltage	—440	m A
Average Plate Current	1.6	mA
Plate Dissipation	40	watts
TYPICAL OFERATION		
Unregulated DC Supply Voltage	36000	volts
Equivalent Resistance of Unregulated Supply	ii	megohms
Voltage Divider Values:		
R ₁ (5 watts)	220	megohms
R ₂ (2 watts)	1	megohm
R3 (0.5 watt)	0.82	megohm
DC Reference Voltage Supply	200	volts
Equivalent Resistance of Reference Voltage	1000	ohms
Effective Grid-Plate Transconductance	200	μmhos
DC Plate Current for Load Current of 0 mA	1000	μΑ
DC Plate Current for Load Current of 1 mA	45	μΑ
Regulated DC Output Voltage for Load Current of 0 mA	25000	volts
Regulated DC Output Voltage for Load Current of 1 mA	24500	volts

MAXIMUM CIRCUIT VALUE

Grid-Circuit Resistance

merohms

· For interval of 20 seconds maximum duration during equipment warm-up period.

X-RADIATION CHARACTERISTIC

X-Radiation, Maximum: Statistical value controlled on a lot sampling basis 0.5 mR/hr


CHARACTERISTICS RANGE VALUES	Note	Min	Max	
Grid Voltage (1)	1	7		volts
Grid Voltage (2)	2		40	volts
Grid-Voltage Change	3.	-	9	volts

Note 1: With dc plate voltage of 30000 volts and dc plate current of 1 mA.

Note 2: With dc plate voltage of 30000 volts and dc plate current of 0.1 mA.

Note 3: Difference between grid voltage (1) and grid voltage (2).

Caution-Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.




^{*} Series impedence should be used with the cathode to limit the cathode current under prolonged short-circuit conditions to 450 mA. ! Without external shield.

Refer to chart at end of section.

6BK5

Refer to chart at end of section.

6BK7A



MEDIUM-MU TWIN TRIODE

6BK7B

Miniature type used as a cascode amplifier in vhf color and black-and-white television tuners and in push-pull cathode-drive rf amplifiers. Outlines section, 6B; requires miniature 9-contact socket. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Type 5BK7A is identical with type 6BK7B except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	5BK7A 4.7 0.6 11	6.8 6.3 0.45 11	volts ampere seconds
Peak value	±200*max	±200*max	volts
Average value		100 max	volts
Direct Interelectrode Capacitances:	Unit No.1	Unit No.2	
Grid to Plate	1.8	1.8	рF
Grid to Cathode, Heater, and Internal Shield	3	3	pF
Plate to Cathode, Heater, and Internal Shield	1	0.9	рF
Cathode to Grid, Heater, and Internal Shield	6	6	рF
Plate to Grid, Heater, and Internal Shield	2.4	2.4	pF
Plate to Cathode	0.22	0.22	pF
Heater to Cathode	2.8	3	pF
Grid of Unit No.1 to Grid of Unit No.2		0.004 max	\mathbf{pF}
Plate of Unit No.1 to Plate of Unit No.2		0.075 max	рF

^{*} Rating may be as high as 300 volts under cutoff conditions when tube is used as a cascode amplifier, the units are connected in series, and heater is negative with respect to cathode.

Class A. Amplifier (Each Unit)


MAXIMUM RATINGS (Design-Center Value)		
Plate Voltage	300	volts volts
Grid Voltage, Negative-bias value	50 2.7	watts
CHARACTERISTICS		
Plate Supply Voltage	150	volts
Cathode-Bias Resistor	56	ohms
Amplification Factor	43	
Plate Resistance (Approx.)	4600	ohms
Transconductance	9300	μ mhos
Plate Current	18	mA
Grid Voltage (Approx.) for plate current of 10 µA	11	volts

Refer to chart at end of section.

6BL4

Refer to chart at end of section.

6BL7GT



MEDIUM-MU TWIN TRIODE 6BL7GTA

Glass octal type used as combined vertical-deflection amplifier and vertical-deflection oscillator in color and black-and-white television receivers. When so operated, it is recommended that unit No.1 (pins 4, 5, and 6) be used as the oscillator. Outlines section, 13D; requires octal socket.

Heater Voltage (ac/dc) Heater Current	6.3 1.5	volts amperes
Heater-Cathode Voltage:		
Peak value	$\pm 200 \text{ max}$	volts
Average value	100 max	volts

Uni	No. 1 6 4.2 0.9	Unit No. 2 6 4.6 0.9	pF pF pF
fier			
150	250	250	volts
0	17	—9	volts
_		15	
	_	2150	ohms
_			μ mhos
65=	4	40	mA
	fier	4.2 0.9 fier 150 250 0 —17 — —	6 6 4.2 4.6 0.9 0.9 fier 150 250 250 0 -17 -9 15 - 15 -2150 -7000 65 4 40

This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Vertical-Deflection Oscillator or Amplifier*

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Center Values)	Oscillator	Amplifier	
DC Plate Voltage	500	500	volts
Peak Positive-Pulse Plate Voltage#			_
(Absolute Maximum)	-	2000△	volts
Peak Negative-Pulse Grid Voltage	400	250	volts
Peak Cathode Current	210	210	mA
Average Cathode Current	60	60	mA
Plate Dissipation:			
For either plate	10	10	watts
For both plates with both units operating	12	12	watts
MAXIMUM CIRCUIT VALUE			
Grid-Circuit Resistance	4.7	4.7†	megohms

- · Unless otherwise specified, values are for each unit.
- # Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).
- A Under no circumstances should this absolute value be exceeded.
- † For cathode-bias operation.

6BL8

Refer to chart at end of section.


4BL8/

6BL8/ ECF80

MEDIUM-MU TRIODE-SHARP-CUTOFF PENTODE

4BL8/XCF80

Miniature type used in frequency-changer service in color and black-and-white television receivers. Outlines section, 6B; require miniature 9-contact socket. Type 4BL8/XCF80 is identical with type 6BL8/ECF80 except for heater ratings.



9DC

6BL8/

Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage	XCF80 4.6 0.6 ±100 max	6.3 0.45 ±100 max	volts ampere volts
Class A ₁ Amplifier			

MAXIMUM RATINGS (Design-Center Values)	Triode Unit	Pentode Unit	
Plate Supply Voltage	550	55 0	volts
Plate Voltage	250	250	volts
Grid-No.2 (Screen-Grid) Supply Voltage		550	volts
Grid-No.2 Voltage:			
With cathode current of 14 mA		175	volts
With cathode current less than 10 mA	_	200	volts
Cathode Current	14	14	mA
Plate Dissipation	1.5	1.7	watts
Grid-No.2 Input:			
With plate dissipation greater than 1.2 watts	_	0.5	watt
With p.late dissipation less than 1.2 watts		0.75	watt


CHARACTERISTICS Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage Amplification Factor Mu-Factor, Grid No.2 to Grid No.1 Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Input Resistance at frequency of 50 MHz Equivalent Noise Resistance	100 2 20 5000 14 	170 170 —2 —47 0.4 6200 10 2.8 0.01	volts volts volts megohm µmhos mA mA megohm ohms
	_	1500	Onths
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.5 0.5	0.5 1	megohm megohm

HIGH-MU TRIODE— POWER PENTODE

6BM8/ ECL82

volts

UCL82



Heater Voltage


Miniature type used in color and black-and-white tele-Georgision receiver applications. The pentode unit is used as an audio output tube, and the triode unit as an Georgical contact and af voltage amplifier. Outlines section, 6G; requires miniature 9-contact socket. Type 50BM8/ UCL82 is identical with type 6BM8/ECL82 except for heater ratings.

ECL82

Heater Current Peak Heater Cathode Voltage	0.78 100 max	0.1 ±200 max	ampere volts
Class A ₁ Amplifie	er		
MAXIMUM RATINGS (Design-Center Values)	Triode Unit	Pentode Unit	
Plate Supply Voltage	550	900	volts
Plate Voltage	300	600	volts
Grid-No.2 Supply Voltage		550	volts
Grid-No.2 Voltage		300	volts
Cathode Current	15	50	mA
Plate Dissipation	1	7	watts
Grid-No.2 Input	_	1.8	watts
CHARACTERISTICS			
Plate Voltage	100	200	volts
Grid-No.2 Voltage	_	200	volts
Grid-No.1 Voltage	0	—16	volts
Amplification Factor	70	9.5*	
Plate Resistance (Approx.)	_	0.02	megohm
Transconductance	2500	6400	μ mhos
Plate Current	3.5	35	mA.
Grid-No.2 Current	_	7	mA
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
For fixed-bias operation	1	1	megohni
For cathode-bias operation	2	2	megohms
• Grid No.2 to Grid No.1			

Refer to chart at end of section.

6BN4



MEDIUM-MU TRIODE

6BN4A 2BN4A, 3BN4A

Miniature type used as rf amplifier tube in grid-drive circuits of vhf color and black-and-white television tuners. Outlines section, 5C; requires miniature 7-contact socket. Types 2BN4A and 3BN4A are identical with type 6BN4A except for heater ratings.

Heat Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage Direct Interelectrode Capacitances (Approx.):* Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater *With external shield connected to cathode.			6BN4A 6.3 0.2 ±100 max 1.2 3.2 1.4	volts seconds volts pF pF pF
With external shield connected to cathode.				
Class A, Amo	lifier			
MAXIMUM RATINGS (Design-Center Values)				
Plate Voltage			275	volts
Grid Voltage, Positive-bias value			.0	volts
Cathode Current			22	mA
Plate Dissipaation			2.2	watts
CHARACTERISTICS				
Plate-Supply Voltage		•	50	volts
Cathode-Bias Resistor			20	ohms
Amplification Factor			43	VIIII
Plate Resistance (Approx.)			ÕÕ	ohms
Transconductance			00	μmhos
Plate Current			9	mA
Grid Voltage (Approx.) for plate current of 100 µ	A		-6	voits
MAXIMUM CIRCUIT VALUE				
Grid-Circuit Resistance),5 r	negohm

6BN6

Refer to chart at end of section.

6BN6/6KS6

3BN6, 4BN6

Cathode Current ...

BEAM TUBE


Miniature type used as combined limiter, discriminator, and audio-voltage amplifier in intercarrier television and FM receivers. Outlines section, 5D; requires miniature 7-contact socket. Types 3BN6 and 4BN6 are identical with type 6BN6/6KS6 except for heater ratings.



	3BN6	4BN6	6BN6/6KS6	12BN6	
77 4 37 - 14 (/ 3 -)	3.15	4.2	6.3	12.6	volts
Heater Voltage (ac/dc)			0.3	0.16	ampere
Heater Current	0.6	0.45	0.3	0.10	ampere
Heater Warm-up Time (Aver-					
age)	11	11			secon ds
Heater-Cathode Voltage:					
Peak value	±200 max	±200 ma:		$\pm 200~\mathrm{max}$	volts
Average value	100 max	100 ma:	(100 max	100 max	volts
Direct Interelectrode Capacitances					
Grid No.1 to Cathode, Heater	. C.H N.	o Cuid N	a 2 and		
				4.2	р F
Internal Shield				4.2	pr.
Grid No.3 to Cathode, Heater					- 10
Internal Shield				3.3	р F
Grid No.1 to Grid No.3				0.004 max	\mathbf{pF}
Limite	r and Dis	criminate	or Service		
MAXIMUM RATINGS (Design-Max	dimum Valu	ıes)			
Plate-Supply Voltage				330	volts
				110	volts
Grid-No.2 Voltage				60	volts
Grid-No.1 Voltage, Positive peak					
Cathode Current				13	mA


TWIN DIODE— HIGH-MU TWIN TRIODE

6BN8



Miniature type used in color and black-and-white television receiver applications. The triode unit is used in burst-amplifier, af amplifier, and low-frequency oscillator applications. The diode units are used in phase-detector, ratio-detector or discriminator, and horizontal afc discriminator circuits. Outlines section, 6E; requires miniature 9-contact socket. Type 8BN8 is identical with type 6BN8 except for heater ratings.

Heater Voltage (ac/dc)	6BN8 6.3	8BN8 8.4	volts
Heater Current	0.6	0.45	ampere
Heater Warm-up Time (Average)	11	11	seconds
Heater-Cathode Voltage:			
Peak value	±200 max	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances:			
Triode Grid to Triode Plate		2.5	рF
Triode Grid to Cathode and Heater		3.6	pF
Triode Plate to Cathode and Heater		0.25	ρF
Plate of Diode Unit No.1 to Triode Grid		0.06 max	pF
Plate of Diode Unit No.2 to Triode Grid		0.1 max	pΓ
Plate of Diode Unit No.1 to Plate of Diode Unit N		$0.07 \mathbf{max}$	pF
Diode Cathode to All Other Electrodes (Each Diode 1		5	pF
Diode Plate to Diode Cathode and Heater (Each Diode		1.9	pF
Diode Cathode to Diode Plate and Heater (Each Diode		4.8	pF
Diode Plate to All Other Electrodes (Each Diode Un	it)	3	pF
Triode Unit as Class A, Ar MAXIMUM RATINGS (Design-Maximum Values)	mplifier		
Plate Voltage		330	volts
Grid Voltage, Positive-bias value		Ŏ	volts
Plate Dissipation		1.7	watts
CHARACTERISTICS			
Plate Voltage	100	250	volts
Grid Voltage	—1	3	volts
Amplification Factor	75	70	_
Plate Resistance (Approx.)	21000	28000	ohms
Transconductance	3500	2500	μmhos
Plate Current	1.5	1.6	mA.
Grid Voltage (Approx.) for plate current of 10 μA	2.5	5.5	volts
MAXIMUM CIRCUIT VALUE			
Grid-Circuit Resistance		1	megohm
Diode Units			
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Current (Each Unit):			
Peak		54 9	mA mA



6BN11

SHARP-CUTOFF TWIN PENTODE

Duodecar type used as if-amplifier tube in television receivers. Outlines section, 8B; requires duodecar 12contact socket.



ı	Z	u	r	

Heater Voltage Heater Current Heater Warm-up Time Heater-Cathode Voltage:	6.3 0.8	volts ampere seconds
Peak value Average value	±200 max 100 max	volts volts

Class A. Amplifier (Each Unit)

MAXIMUM RATINGS (Design-Maximum Values)	
Plate Voltage	330 volts
Grid-No.2 (Screen-Grid) Supply Voltage	330 volts
Grid-No.2 Voltage	See curve page 300
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0 volts
Plate Dissipation	3.1 watts
Grid-No.2 Input	0.65 watt
CHARACTERISTICS	

Plate Voltage		125	volts
Grid No.3 (Suppressor Grid)	Connected t	o cathode	
Grid-No.2 Voltage			volts
Cathode-Bias Resistor		56	ohms
Plate Resistance (Approx.)		0.2	megohm
Transconductance	13	3000	μmhos
Plate Current			mA
Grid-No.2 Current			mA
Grid-No.1 Voltage (Approx.) for plate current of 20 μ A		3	volts
MAXIMUM CIRCUIT VALUE			

6BQ5

For replacement use type 6BQ5/EL84.

6BQ5/EL84

(Screen-Grid)

(Control-Grid)

Voltage

Grid-No.2

Cathode Current

POWER PENTODE

Miniature type used in the output stage of audio-frequency amplifiers. Outlines section, 6G; requires miniature 9-contact socket. Types 8BQ5 and 10BQ5 are identical with type 6BQ5/EL84 except for heater ratings.

Grid-No.1-Circuit Resistance, for cathode-bias operation



megohm

volts

volts

0.25

9CV

300


Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	6BQ5/EL84 6.3 0.76	8BQ5 8 0.6 11	10BQ5 10.6 0.45 11	volts ampere seconds
Peak value	±100 max 100 max	±100 max 100 max	±100 max	volts volts
Direct Interelectrode Capacitances: Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No Plate to Cathode, Heater, Grid No.2, an Grid No.1 to Heater	.2, and Grid d Grid No.3	No.3	0.5 max 10.8 6.5 0.25 max	pF pF pF pF
Class A	, Amplifier			
MAXIMUM RATINGS (Design-Center Values) Plate Voltage			300	volts

Voltage, Positive-bias value

Plate Dissipation Grid No.2 Input		12 2	watts watts
TYPICAL OPERATION			
		250	volts
Plate Voltage Grid-No.2 Voltage		250 250	volts
Grid-No.1 (Control-Grid) Voltage		-7.3	volts
Peak AF Grid No.1 Voltage		6.2	volts
Zero-Signal Plate Current		48	mA
Maximum-Signal Plate Current		50.6	mA
Zero-Signal Grid-No.2 Current		5.5	mA
Maximum-Signal Grid-No.2 Current		10	mA
Plate Resistance (Approx.)		38000	ohms
Transconductance		11300	μmhos
Load Resistance		4500	ohms
Total Harmonic Distortion		10	per cent
Maximum-Signal Power Output		5.7	watts
MAXIMUM CIRCUIT VALUES			
Grid-NoCircuit Resistance:			
For fixed-bias operation		0.3	megohm
For cathode-bias operation		1	megohm
Push-Pull Class AB, Ampli	fier		
Push-Pull Class AB, Ampli MAXIMUM RATINGS (Same as for Single-Tube Class A, A			
MAXIMUM RATINGS (Same as for Single-Tube Class A ₁ A			
MAXIMUM RATINGS (Same as for Single-Tube Class At A TYPICAL OPERATION (Values are for two tubes)	mplifier)	300	volta
MAXIMUM RATINGS (Same as for Single-Tube Class A ₁ A TYPICAL OPERATION (Values are for two tubes) Plate Supply Voltage	mplifier) 250	300 300	volts
MAXIMUM RATINGS (Same as for Single-Tube Class At A TYPICAL OPERATION (Values are for two tubes) Plate Supply Voltage Grid-No.2 Supply Voltage	mplifier) 250 250	300	volts
MAXIMUM RATINGS (Same as for Single-Tube Class A ₁ A TYPICAL OPERATION (Values are for two tubes) Plate Supply Voltage Grid-No.2 Supply Voltage Cathode-Bias Resistor	250 250 250 130	300 130	
MAXIMUM RATINGS (Same as for Single-Tube Class A ₁ A TYPICAL OPERATION (Values are for two tubes) Plate Supply Voltage Grid-No.2 Supply Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to-Grid-No.1 Voltage	mplifier) 250 250	300	volts ohms
MAXIMUM RATINGS (Same as for Single-Tube Class A ₁ A TYPICAL OPERATION (Values are for two tubes) Plate Supply Voltage Grid-No.2 Supply Voltage Cathode-Bias Resistor	250 250 250 130 22.6	300 130 28.3	volts ohms volts
MAXIMUM RATINGS (Same as for Single-Tube Class At A TYPICAL OPERATION (Values are for two tubes) Plate Supply Voltage Grid-No.2 Supply Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to-Grid-No.1 Voltage Zero-Signal Plate Current	250 250 250 130 22.6 62	300 130 28.3 72 92 8	volts ohms volts mA
MAXIMUM RATINGS (Same as for Single-Tube Class A ₁ A TYPICAL OPERATION (Values are for two tubes) Plate Supply Voltage Grid-No.2 Supply Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to-Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current	250 250 250 130 22.6 62 75 7	300 130 28.3 72 92 8 22	volts ohms volts mA mA
MAXIMUM RATINGS (Same as for Single-Tube Class A ₁ A TYPICAL OPERATION (Values are for two tubes) Plate Supply Voltage Grid-No.2 Supply Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to-Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Effective Load Resistance (Plate-to-plate)	250 250 250 130 22.6 62 75 7 15 8000	300 130 28.3 72 92 8 22 8000	volts ohms volts mA mA mA ohms
MAXIMUM RATINGS (Same as for Single-Tube Class A ₁ A TYPICAL OPERATION (Values are for two tubes) Plate Supply Voltage Grid-No.2 Supply Voltage Cathode-Blas Resistor Peak AF Grid-No.1-to-Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current Zero-Signal Grid-No.2 Current Effective Load Resistance (Plate-to-plate) Total Harmonic Distortion	250 250 130 22.6 62 75 7 15 8000	300 130 28.3 72 92 8 22 8000	volts ohms volts mA mA mA ohms
MAXIMUM RATINGS (Same as for Single-Tube Class A ₁ A TYPICAL OPERATION (Values are for two tubes) Plate Supply Voltage Grid-No.2 Supply Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to-Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Effective Load Resistance (Plate-to-plate)	250 250 250 130 22.6 62 75 7 15 8000	300 130 28.3 72 92 8 22 8000	volts ohms volts mA mA mA ohms
MAXIMUM RATINGS (Same as for Single-Tube Class A ₁ A TYPICAL OPERATION (Values are for two tubes) Plate Supply Voltage Grid-No.2 Supply Voltage Cathode-Blas Resistor Peak AF Grid-No.1-to-Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current Zero-Signal Grid-No.2 Current Effective Load Resistance (Plate-to-plate) Total Harmonic Distortion	250 250 130 22.6 62 75 7 15 8000	300 130 28.3 72 92 8 22 8000	volts ohms volts mA mA mA ohms
MAXIMUM RATINGS (Same as for Single-Tube Class A1 A TYPICAL OPERATION (Values are for two tubes) Plate Supply Voltage Grid-No.2 Supply Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to-Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Effective Load Resistance (Plate-to-plate) Total Harmonic Distortion Maximum-Signal Power Output MAXIMUM CIRCUIT VALUES	250 250 130 22.6 62 75 7 15 8000	300 130 28.3 72 92 8 22 8000	volts ohms volts mA mA mA ohms
MAXIMUM RATINGS (Same as for Single-Tube Class A ₁ A TYPICAL OPERATION (Values are for two tubes) Plate Supply Voltage Grid-No.2 Supply Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to-Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current Zero-Signal Grid-No.2 Current Effective Load Resistance (Plate-to-plate) Total Harmonic Distortion Maximum-Signal Power Output	250 250 250 130 22.6 62 75 7 15 8000 3	300 130 28.3 72 92 8 22 8000	volts ohms volts mA mA mA ohms
MAXIMUM RATINGS (Same as for Single-Tube Class A1 A TYPICAL OPERATION (Values are for two tubes) Plate Supply Voltage Grid-No.2 Supply Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to-Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Maximum-Signal Power Output Maximum-Signal Power Output MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance:	250 250 250 130 22.6 62 75 7 15 8000 3	300 130 28.3 72 92 8 22 8000 4 17	volts ohms volts mA mA mA ohms per cent watts

Refer to chart at end of section.

6BQ6GT



BEAM POWER TUBE

6BQ6GTB /6CU6

12BQ6GTB/12CU6, 25BQ6GTB/25CU6

Glass octal type used as horizontal-deflection amplifier in color and black-and-white television receivers. Outlines section, 14D; requires octal socket. This type may be supplied with pin No.1 omitted. Types 12BQ6GTB/

12CU6 and 25BQ6GTB/25CU6 are identical with type 6BQ6GTB/6CU6 except for heater ratings.

Heater Voltage (ac/dc)		12BQ6GTB/ 12CU6 12.6	25BQ6GTB/ 25CU6 25	volts
Heater Current	1.2	0.6	0.3	ampere
Heater Warm-up Time (Average)	-	11		seconds
Heater-Cathode Voltage:				
Peak value	$\pm 200 \text{ max}$	$\pm 200 \text{ max}$	±200 max	volts
Average value	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances (Approx.)	:			
Grid No.1 to Plate			0.6	n F
Grid No.1 to Cathode, Heater, Grid No.2,	and Grid No	n 3	15	pF pF
Plate to Cathode, Heater, Grid No.2, and	Grid No 3		7	ρF
Sumode, Meater, Orla 110.2, and	GIIG 110.0 .		•	pr

Class A. Amplifier

CHARACTERISTICS				
Plate Voltage	60	150	250	volts
Grid-No.2 Voltage	150	150	150	volts
Grid-No.1 Voltage	0	-22.5	-22.5	volts
Mu-Factor, Grid No.2 to Grid No.1		4.3		
Plate Resistance (Approx.)			14500	ohms
Transconductance		-	5900	μmhos
Plate Current	260•	-	57	mA
Grid-No.2 Current	26•	_	2.1	mA.
Grid-No.1 Voltage (Approx.) for plate mA = 1.	_		-43	volts

• These values can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Center Values)

DC Plate Voltage	600	volts
Peak Positive-Pulse Plate Voltage# (Absolute Maximum)	60 0 0†	volts
Peak Negative-Pulse Plate Voltage	1250	volts
DC Grid-No.2 (Screen-Grid) Voltage	200	volts
Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage	300	volts
Peak Cathode Current	400	mA
Average Cathode Current	110	mA
Plate Dissipation.	11	watts
Grid-No.2 Input	2.5	watts
Bulb Temperature (At hottest point)	220	$^{\circ}\mathrm{C}$

MAXIMUM CIRCUIT VALUE

megohm Grid-No.1-Circuit Resistance 0.47 Grid-No.1-Circuit Resistance 0.47 megonm #Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). † Under no circumstances should this absolute value be exceeded.

• A bias resistor or other means is required to protect the tube in absence of excitation.

6BQ7

Refer to chart at end of section. For replacement use type 6BQ7A/6BZ7/6BS8.

6BQ7A

For replacement use type 6BQ7A/6BZ7/6BS8.

6BQ7A/ 6BZ7/ 6BS8 4BQ7A/4BZ7,

MEDIUM-MU TWIN TRIODE

Miniature type used as a cascode amplifier in vhf color and black-and-white television tuners in push-pull cathode-drive rf amplifiers. Outlines section, 6B; requires miniature 9-contact socket. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Types 4BQ7A/4BZ7 and 5BQ7A are identical with type 6BQ7A/6BZ7/6BS8 except for heater ratings.



6BO7A/6BZ7/

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	0.6	5BQ7A 5.6 0.45 11	6BS8 6.3 0.4	volts ampere seconds
Peak value			±200*max 100 max	volts volts


Direct Interelectrode Capacitances:	Unit No.1	Unit No.2	
Grid to Plate	1.2	1.2	рF
Grid to Cathode, Heater, and Internal Shield	2.6		pF
Cathode to Grid, Heater, and Internal Shield		5	рF
Plate to Cathode, Heater, and Internal Shield	1.2		ρF
Plate to Grid, Heater, and Internal Shield		2.2	pF
Plate to Cathode	0.12	0.12	pF
Heater to Cathode	2.6	2.6	pF
Plate of Unit No.1 to Plate of Unit No.2	0.0	10 max	ρF
Plate of Unit No.2 to Plate and Grid of Unit No.1			pF


* Rating may be high as 300 volts under cutoff conditions, when tube is used as a cascode amplifier, the two units are connected in series, and heater is negative with respect to cathode.

Class A. Amplifier (Each Unit)

MAXIMUM RATINGS (Design-Center Values)		
Plate Supply Voltage Cathode Current Plate Dissipation	250* 20	volts mA watts
	2	watts
CHARACTERISTICS		
Plate Supply Voltage	150	volts
Cathode-Bias Resistor	220	ohms
Amplification Factor	38	
Plate Resistance (Approx.)	5900	ohms
Transconductance	6400	umhos
Plate Current	9	m A
Grid Voltage (Approx.):		· - -
For plate current of 100 μ A	6.5	volts
For plate current of 10 μ A	_	volts
MAXIMUM CIRCUIT VALUE		

Grid-Circuit Resistance 0.5 megohm
* Rating may be high as 300 volts under cutoff conditions, when tube is used as a cascode amplifier, the two units are connected in series, and heater is negative with respect to cathode.





HALF-WAVE VACUUM RECTIFIER

6BR3/6RK19

17BR3/17RK19

17BR3/

Miniature type used as damper tube in horizontal-deflection circuits of television receivers. Outlines section, 7D; requires miniature 9-contact socket. Type 17BR3/17RK19 is identical with type 6BR3/6RK19 except for heater ratings.

6BR3/

		6RK19	17RK19	
Heater	Voltage (ac/dc)	6.3	16.8	volts
Heater	Current	1.2	0.45	ampere
Heater	Warm-up Time	_	11	seconds

[&]quot;With external shield connected to internal shield.

Damper Service

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current Plate Dissipation	5500 1200 200 6.5	volts mA mA watts
Heater-Cathode Voltage: Peak value	5500 900 180	volts volts °C
CHARACTERISTIC, instantaneous Value Tube Voltage Drop for plate current of 250 mA # Pulse duration must not exceed 15% of a horizontal scanning cycle	19 (10 micros	volts econds).

6BR8

Refer to chart at end of section.
For replacement use type 6BR8A/6FV8A.

6BR8A


For replacement use type 6BR8A/6FV8A.

6BR8A/ 6FV8A

5BR8/5FV8

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in color and black-and-white television receiver applications. Especially useful as combined triode oscillator and pentode mixer in vhf television tuners. Outlines section, 6B; requires miniature 9-contact socket. Except for basing arrangement and grid-No.1-to-plate capacitance of pentode unit, types 5BR8/5FV8 and 6BR8A/6FV8A are identical with types 5U8 and 6U8A, respectively.



6BS3

Refer to chart at end of section. For replacement use type 6BS3A.

6BS3A

12BS3A/ 12DW4A, 17BS3A 17BS3A/17DW4A

HALF-WAVE VACUUM RECTIFIER

9HP

Novar type used as damper tube in horizontal-deflection circuits of black-and-white television receivers. Outlines section, 30B; requires novar 9-contact socket.

Socket terminals 1, 3, 6, and 8 should not be used as tie points; it is recommended that socket clips for these pins be removed to reduce the possibility of arc-over and to minimize leakage. These tubes, like other power-handling tubes, should be adequately ventilated. Types 12BS3A/12DW4A, 17BS3A, and 17BS3A/17DW4A are identical with type 6BS3A except for heater ratings.

	6BS3A	12BS3A/ 12DW4A		
Heater Voltage (ac/dc)	6.3	12.6	16.8	volts
Heater Current	1.2	0.6	0.45	amperes
Heater Warm-up Time (Average)	_	11	11	seconds
Direct Interelectrode Capacitances (Approx.): Plate to Cathode and Heater			6.5	pF
Cathode to Plate and Heater			9	pF pF pF
Heater to Cathode			2.8	pF


Damper Service

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values) Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current Plate Dissipation Heater-Cathode Voltage: Peak value Average value 4300 Average value 4100	1100 200	volts mA mA watts volts
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop for plate current of 140 mA # Pulse duration must not exceed 15% of a horizontal scanning of		volts microseconds).

Refer to chart at end of section. For replacement use type 6BQ7A/6BZ7/6BS8.

6B\$8



SHARP-CUTOFF TWIN PENTODE


6BU8 3BU8/3GS8 4BU8/4GS8


Miniature type used as combined sync separator, sync clipper, and age amplifier tube in color and black-and-white television receivers. Outlines section, 6E; requires miniature 9-contact socket. Types 3BU8/3GS8 and 4BU8/4GS8 are identical with type 6BU8 except for heater ratings.

SRIIS/SCSS ARTIS/ACSS

	3BU8/3GS8 4		ends	
Heater Voltage (ac/dc)	3.15	4.2	6.3	volts
Heater Current	0.6	0.45	0.3	ampere
Heater Warm-up Time (Average)	11	11		seconds
Heater-Cathode Voltage:				
Peak value	±200 max	±200 max	±200 max	volts
Average value		100 max	100 max	volts
Direct Interelectrode Capacitances:				
Grid No.3 to Plate (Each Unit)			1.9	ρF
Grid No.1 to All Other Electrodes			6	ρF
Grid No.3 to All Other Electrodes (Each U			3.6	ρF
Plate to All Other Electrodes (Each Unit)	· · · · · · · · · · · · · · · · · · ·		3	ÞΓ
Grid No.3 of Unit No.1 to Grid No.3 of Un			0.015 max	pF
did 110.3 of Citt 110.1 to did 110.3 of Ci	116 110.2		0.019 IIIAA	DI.
Class A,	Amplifier			
MAXIMUM RATINGS (Design-Maximum Values	s) .			
Plate Voltage (Each Unit)			300	volts
Grid-No.3 (Suppressor-Grid) Voltage (Each Uni	(t):		• • •	
Peak positive value	-, -		50	volts
DC negative value			50	volts
DC positive value			3	volts
Grid-No.2 (Screen-Grid) Voltage			150	volts
Grid-No.1 (Control-Grid) Voltage, Negative bia			50	volts
Cathode Current			12	mA
Plate Dissipation (Each Unit)			1.1	watts
Grid-No.2 Input			0.75	watt
Old Mold Suput			0.10	******
CHARACTERISTICS (With Both Units Operati	ng)			
Plate Voltage (Each Unit)		100	100	volts
Grid-No.3 Voltage (Each Unit)		10	0	volts
Grid-No.2 Voltage		67.5	67.5	volts
Grid-No.1 Voltage		•	•	volts
Plate Current (Each Unit)			2.2	mA
Grid-No.2 Current		6.5	3.3	mA
Cathode Current		6.6	7.8	m A
CHARACTERISTICS (With One Unit Operating)			
Plate Voltage	•	100	100	volts
Grid-No.3 Voltage		0	0	volts
Grid-No.2 Voltage		67.5	67.5	volts
Grid-No.1 Voltage		01.5	01.0	volts
Grid-No.3 Transconductance		U	180	
Grid-No.1 Transconductance		1500	100	μmhos
Ora-10.1 Itanocomunicance		1000	_	µmhos

Plate Current Grid-No.3 Voltage (Approx.) for plate current of	-	2.2	mA
100 μ A		4.5	volts
100 μΑ	-	-2.3	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.3-Circuit Resistance (Each Unit) Grid-No.1-Circuit Resistance * Adjusted to provide a dc grid-No.1 current of 100 microam † With plate and grid No.3 of the other unit connected to gr	peres.	0.5 0.5	megohm megohm






6BV8

Refer to chart at end of section.

6BV11

SHARP-CUTOFF TWIN PENTODE

Duodecar type used as color demodulators in color television applications. Grid Nos. 1 and 3 may be used as independent control electrodes. Outlines section, 8C; requires duodecar 12-contact socket. Type 12BV11 is identical with type 6BV11 except for heater ratings.



Wasten American	6BV11	12BV11	
Heater Arrangement	Series	Parallel	
Heater Voltage (ac/dc)	6.3	12.6	volts
Heater Current	0.9	0.45	ampere
Heater Warm-up Time		11	seconds
Direct Interelectrode Capacitances:			
Grid No.1 to Plate		0.1	рF
Grid No.3 to Plate		3.2	þF
Grid No.1 to Heater, Cathode, Grid No.2, Grid No.3, and	1	0.2	pr
Internal Shield		7	рF
Grid No.3 to All Other Electrodes		8.5	рF
Grid No.1 to Grid No.3		0.08	рF
		*****	pr
Class A, Amplifier (Each Uni	t)		
MAXIMUM RATINGS (Design-Maximum Values)	-		
DC Plate Voltage		300	volts
Grid-No.3 (Suppressor-Grid) Voltage:		000	VOICE
Positive-bias value		25	volts
Negative-bias value		100	volts
Grid-No.2 (Screen-Grid) Supply Voltage		300	volts
Grid-No.2 Voltage			e page 300
Grid-No.1 (Control-Grid) Voltage:		Dec cary	c page oou
Positive-bias value		0	volt
Negative-bias value		5 0	volts
Plate Dissipation		1.7	watts
Grid-No.3 Input		0.1	watt
Grid-No.2 Input:		***	
For grid-No.2 voltages up to 150 volts		1	watt
For grid-No.2 voltages between 150 and 300 volts		See curv	e page 300

CUA	-	CTE	DIC	TICS

Plate Supply Voltage Grid-No.3 Voltage Grid-No.2 Supply Voltage Cathode Resistor Plate Current Grid-No.2 Current Transconductance, Grid No.1 Transconductance, Grid No.3 Plate Resistance (Approx.) Grid-No.1 Voltage (Approx.) for plate current of 75 µA Grid-No.3 Voltage (Approx.) for plate current of 85 µA Amplification Factor	150 0 100 180 3.1 2.4 3200 390 0.17 3.5 5.5	volts volt volts ohms mA mA µmhos µmhos megohm volts
MAXIMUM CIRCUIT VALUES Grid-No.3-Circuit Resistance Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.68 0.22 0.47	megohm megohm megohm

For replacement use type 6CG3/6BW3/6DQ3. **6BW3**

6BW4 Refer to chart at end of section.

Refer to chart at end of section. **6BW8**



SHARP-CUTOFF **DUAL PENTODE**

6BW11

Duodecar type used in color and black-and-white television receiver applications. Unit No. 1 is used as a video amplifier; unit No. 2 is used in bandpass amplifier, burst amplifier, or sound-if or video-if applications. Outlines section, 8B; requires duodecar 12-contact socket. Heater: volts (ac/dc), 6.3; amperes, 0.8; maximum heater-cathode volts, ±200 peak, 100 average.

Class A₁ Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Unit No.1	Unit No.2	
Plate Voltage	330	330	volts
Grid-No.2 (Screen-Grid) Supply Voltage	330	330	volts
Grid-No.2 Voltage		urve page 300	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	7	O O	volts
	Ÿ.		
Plate Dissipation	4	3.1	watts
Grid-No.2 Dissipation	0.8	0.65	watt
CHARACTERISTICS			
Plate Voltage	125	125	volts
Grid No.3 (Suppressor Grid)		ted to cathod	
Grid-No.2 Voltage	125	125	volts
	56		
Cathode-Bias Resistor		56	ohms
Plate Resistance (Approx.)	0.12	0.2	megohm
Transconductance	8500	13000	μmhos
Plate Current	22	11	mA
Grid-No.2 Current	4.8	3.8	mA
Grid-No.1 Voltage (Approx.) for plate current of			
20 μΑ	-9.5	—3	volts
ω με	0.0		70163
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
For cathode-bias operation	0.25	0.25	megohm

Refer to chart at end of section.

6BX7GT


Refer to chart at end of section.

6BY5GA

6BY6


PENTAGRID AMPLIFIER

Miniature type used as a gated amplifier in color television receivers. In such service, it may be used as a combined sync separator and sync clipper. Outlines section, 5C; requires miniature 7-contact socket.



7CH

	701	7011	
Heater Voltage (ac/dc) Heater Current	6BY6 6.3 0.3	volts ampere	
Heater Warm-up Time (Average) Peak value	±200 max	seconds volts	
Average value	100 max	volts	
Direct Interelectrode Capacitances: Grid No.1 to Plate Grid No.3 to Plate Grid No.1 to Grid No.3 Grid No. 1 to All Other Electrodes	0.08 max 0.35 max 0.22 max	pF pF pF	
Grid No. 1 to All Other Electrodes Grid No.3 to All Other Electrodes Plate to All Other Electrodes	5.4 6.9 7.6	pF pF pF	
Class A ₁ Amplifier			
CHARACTERISTICS			
Plate Voltage Grids-No.2-and-No.4 Voltage Grid-No.3 Voltage	250 100 —2.5	volts volts volts	
Grid-No.1 Voltage Grid-No.3-to-Plate Transconductance Grid-No.1-to-Plate Transconductance	2.5 500 1900	volts μmhos μmhos	
Plate Current	6.5	m A	
Grids-No.2-and-No.4 Current	9	mA	
grid-No.1 volts = -4 Grid-No.1 Volts (Approx.) for plate current of 35 μA and	15	volts	
grid-No.3 volts = 0	12	volts	
Gated Amplifier			
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage	330	volts	
Grids-No.2-and-No.4 Voltage Grids-No.2-and-No.4 Supply Voltage Grid-No.3 Voltage:	See curve 330	page 300 volts	
Negative-bias value Positive-bias value	55 0	volts volts	
Positive peak value	27 110	voits volts	
Grid-No.1 Voltage, Negative bias value	2.3	watts	
Grid-No.3 Input Grids-No.2-and-No.4 Input:	0.1	watt	
For grids-No.2-and-No.4 voltages up to 165 volts For grids-No.2-and-No.4 voltages between 165 and 330 volts Cid No.1 Length	1.1 See curve 0.1	watts page 300 watt	
Grid-No.1 Input	0.1	WALL	
CHARACTERISTICS AS SYNC SEPARATOR AND SYNC CLIPPER		••	
Plate Voltage Grid-No.3 Voltage	10 0	volts volts	
Grids-No,2-and-No,4 Voltage	25	volts	
Grids-No.2-and-No.4 Voltage Grid-No.1 Voltage	0	volts	
Plate Current Grids-No.2-and-No.4 Current	1.4 3.5	mA mA	
Grid-No.3 Volts (Approx.) for plate voltage of 25 volts, grids-No.2- and-No.4 voltage of 25 volts, grid-No.1 voltage of 0 volts, and			
plate current of 50 µA Grid-No.1 Volts (Approx.) for plate voltage of 25 volts, grids-No.2- and-No.4 voltage of 25 volts, grid-No.3 voltage of 0 volts, and	2.5	volts	
plate current of 50 μ A MAXIMUM CIRCUIT VALUES	-2.3	volts	
Grid-No.1 or Grid-No.3-Circuit Resistance:			
Grid-No.1 or Grid-No.3-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.5 1	megohm megohm	





DIODE... SHARP-CUTOFF PENTODE

6BY8

Miniature type used in television receiver applications. The pentode unit is used as an rf amplifier and the high-perveance diode as a limiter or detector. Outlines section, 6E; requires miniature 9-contact socket.

Heater Voltage (ac/dc) Heater Current	6.3 0.6	volts ampere
Heater Warm-up Time (Average)	11	seconds
Heater-Cathode Voltage:		
Peak value	$\pm 200~max$	volts
Average value	100 max	volts
Direct Interelectrode Capacitances:° Pentode Unit:		
Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and	0.0035 max	рF
Internal Shield	5.5	pF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and	_	_
Internal Shield	. 5	рF
Diode Plate to All Other Electrodes	4.8	рF
 With external shield connected to cathode of pentode unit (pin 9), except 	ept as noted.	
With external shield connected to ground		

Diode Plate to All Other Electrodes With external shield connected to cathode of pentode unit With external shield connected to ground.	(pin 9), e	xcept as n		
Pentode Unit as Class A, A	mplifier			
MAXIMUM RATINGS (Design-Center Values)				
Plate Voltage		300	volts	
Grid-No.3 (Suppressor-Grid) Voltage, Positive value		Ö		
Grid-No.2 (Screen Grid) Supply Voltage		300	volts	
Grid-No.2 Voltage			curve page 300	
Grid-No.1 (Control-Grid) Voltage:				
Negative-bias value				
Positive-bias value		. 0		
Grid-No.2 Input:		3	watts	
For grid-No.2 voltages up to 150 volts		0.65	watt	
For grid-No.2 voltages between 150 and 300 volts			curve page 300	
CHARACTERISTICS				
Plate Supply Voltage	100	250	volts	
Grid No.3	No.3			
Grid-No.2 Supply Voltage	100	150	volts	
Cathode-Bias Resistor Plate Resistance (Approx.)	150 0.5	68 1	ohms	
Transconductance (Approx.)	3900	5200	megohm	
Plate Current	5	10.6	μmhos mA	
Grid-No.2 Current	2.1	4.3	mA	
Grid-No.1 Voltage (Approx.) for plate current of		1.0	11123	
10 μΑ	4.2	6.5	volts	

MAXIMUM CIRCUIT VALUES

Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.25	megohm
For cathode-bias operation	1	megohm

Diode Unit

MAXIMUM RATINGS (Design-Center Values)		
Peak Inverse Plate Voltage Peak Plate Current Average Plate Current	430 180 45	volts mA mA

6BY11

Refer to chart at end of section.

6BZ3


For replacement use type 6BE3/6BZ3.

6BZ6

6BZ6/6JH6 3BZ6, 4BZ6, 12BZ6

SEMIREMOTE-CUTOFF PENTODE


Miniature type used in gain-controlled video if stages of color and black-and-white television receivers. Outlines section, 5C; requires miniature 7-contact socket. Types 3BZ6, 4BZ6, and 12BZ6 are identical with type 6BZ6 except for heater ratings.



Heater Voltage (ac/dc) Heater Current	3BZ6 3.15 0.6	4BZ6 4.2 0.45	6BZ6/6JH6 6.3 0.3	12BZ6 12.6 0.15	volts ampere
Heater Warm-up Time (Average)	11	11		-	seconds
Peak value				$\pm 200 \text{ max}$ 100 max	volts volts
Direct Interelectrode Capacitances Grid No.1 to Plate			Unshielded 0.025 max	Shielded 0.015 max	рF
Grid No.1 to Cathode, Heate No.3, and Internal Shield Plate to Cathode, Heater, Gr			7	7	pF
and Internal Shield		10 140.3,	2	3	рF
A With external shield connected to	cathode.				

Class A₁ Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	
Plate Voltage	330 volts
Grid No.3 (Suppressor-Grid) Voltage, Positive value	0 volts
Grid-No.2 (Screen-Grid) Supply Voltage	330 volts
Grid-No.2 Voltage	See curve page 300
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0 volts
Plate Dissipation	2.3 watts
Grid-No.2 Input:	
For grid-No.2 voltages up to 165 volts	0.55 watt
For grid-No.2 voltages between 165 and 330 volts	See curve page 300



CHARACTERISTICS				
Plate Supply Voltage			125	volts
Grid No.3		Connect	ed to cathode	at socket volts
Grid-No.2 Supply Volta	ge		125 56	ohms
Plate Resistance (Appr	ox.)		0.26	megohm
Transconductance			8000	μmhos
			14	mA mA
Grid-No.2 Current	prox.) for transconductance of 50	umhos	3.6 19	volts
Grid-No.1 Voltage (Ap)	prox.) for transconductance of 70	0 μmhos	-4.5	volts
MAXIMUM CIRCUIT V	ALUES			
Grid-No.1-Circuit Resist			A 0.5	
	ationperation		0.25 1	megohm megohm
Refer to	chart at end of section.		/ D 77	,
For replacemen	nt use type 6BQ7A/6BZ7/6	BBS8.	6BZ7	
Refer to	chart at end of section.		4070	
For replace	ement use type 6BC8/6BZ8	3.	6BZ8	ſ
		_	6C4	6
#@ @P	POWER TRIOD	E	00-	•
H3 0° 0° 0° 0° 0° 0° 0° 0° 0° 0° 0° 0° 0°	Miniature type used as a local oscillator in FM a cuits and as a class C r 5C; requires miniature operation as a resistance Resistance-Coupled Ampl	nd other hi f amplifier. 7-contact so e-coupled an ifier section	gh-frequent Outlines oket. For mplifier, 1 n. For ad	ncy cir- section, typical cefer to Iditional
6BG	curve of plate characterist	ics, refer to t	type 12AU	7A.
			$\begin{matrix} 6.3 \\ 0.15 \end{matrix}$	volts ampere
	• •		±200 max	volts
Average value			100 max	volts
Direct Interelectrode Ca	ipacitances (Approx.)	Unshielded 1.6	Shielded△ 1.4	рF
Grid to Cathode and	d Heater	1.8	1.8	pF
	d Heater	1.3	2.5	pF
△ With external shield c	onnected to cathode.			
	Class A, Amplifier			
MAXIMUM RATINGS (D	Design-Center Values)			
			300 max	volts
Plate Dissipation			3.5 max	watts
CHARACTERISTICS				
		100	250	14
Grid Voltage*	*********	0 -	250 —8.5	volts volts
Amplification Factor .	**********	19.5	17	10.00
Flate Resistance (App.	rox.)	6250	7700	ohms

* Transformer- or impedance-type input coupling devices are recommended to minimize resistance in the grid circuit.

RF Power Amplifier and Oscillator—Class C Telegraphy

For fixed bias operation

For cathode-bias operation

Plate Resistance (Approx.)

Plate Current Grid Voltage (Approx.) for plate current of 10 μ A ...

MAXIMUM CIRCUIT VALUES Grid-Circuit Resistance:

MAXIMUM RATINGS (Design-Center Values)

mediate in italian (Design-Center Values)		
Plate Voltage	300	voits
did voicage	50	volts
Plate Current	25 8	mA mA
Plate Dissipation	ř	11125

7700

2200

10.5

-25

0.25

ohms

mA

volts

megohm

megohm

#mhos

6250


3100

11.8 ---10

TYPICAL OPERATION AT FREQUENCIES UP TO 50 MHz

Plate Voltage	300	volts
Grid Voltage	27	volts
Plate Current	25	mA
Grid Current (Approx.)	7	mA
Driving Power (Approx.)	0.35	watt
Power Output (Approx.).	5.5	watts

• Approximately 2.5 watts power output can be obtained when the 6C4 is used at 150 MHz as an oscillator with grid resistor of 10,000 ohms and with maximum rated input.



6C5	Refer to chart at end of section.
6C5GT	Refer to chart at end of section.
6C6	Refer to chart at end of section.
6C7	Refer to chart at end of section.
6C8G	Refer to chart at end of section

SHARP-CUTOFF **DUAL TETRODE**

Miniature type used as vhf rf-amplifier and autodyne mixer tube. Outlines section, 6B; except center pin is added to base; requires miniature 10-contact socket. Type 17C9 is identical with type 6C9 except for heater ratings.



Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage		16.8 0.15 +100 max	volts ampere volts
Direct Interelectrode Capacitances:	Unit No. 1 U		¥0103
Grid No.1 to Plate	0.055 max		рF
Grid No.1 to Cathode, Heater, Grid No.2, and Internal Shield	4.4	4.2	рF
Plate to Cathode, Heater, Grid No.2 and Internal Shield	2.2	2.2	рF
Heater to Cathode	4.2	4.8	ρF
Plate of Unit No.1 to Plate of Unit No.2	0.003		р <u>F</u>
Grid No.1 of Unit No.1 to Grid No.1 of Unit No.2	0.001		pF
Grid No.1 of Unit No.1 to Plate of Unit No.2 Grid No.1 of Unite No.2 to Plate of Unit No.1	0.001 t 0.032 t		p F p F


609

Class A, Amplifier (Each Unit)

MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	250	volts
Grid-No.2 (Screen-Grid) Supply Voltage	180	volts
Grid-No.2 Voltage		rve page 300
Cathode Current	20	mA
Plate Dissipation:	20	шл
Either plate	1.5	
Both plates (both units committee)		watts
Both plates (both units operating)	2.5	watts
Grid-No.2 Input:		
For grid-No.2 voltages up to 90 volts	0.5	watt
For grid-No.2 voltages between 90 and 180 volts	See cur	ve page 300
CHARACTERISTICS		
Plate Voltage	125	volts
Grid-No.2 Voltage	80	volts
Grid-No.1 Voltage	<u>—</u> i	volt
Plate Resistance (Approx.)	0.1	megohm
Transconductance	8000	μmhos
Plate Current	10	mA
Grid-No.2 Current	1.5	
Crid No.1 Volten (Annual Sandal		mA.
Grid-No.1 Voltage (Approx.) for plate current of 20 μ A	6	volts

Refer to chart at end of section.

6C10




FULL-WAVE VACUUM RECTIFIER

6CA4

Miniature type used in power supply of compact audio equipment having moderate dc requirements. Outlines section, 6G; requires miniature 9-contact socket. This tube, like other power-handling tubes, should be adequately ventilated. Heater: volts (ac/dc), 6.3; amperes, 1.

Full-Wave Rectifier

MAXIMUM RATINGS (Design-Center Values)		
Peak Inverse Plate Voltage	1000	volts
Peak Plate Current (Per Plate)	450	mA
AC Plate Supply Voltage (Per Plate, rms) with Capacitor Input		
to Filter	350	volts
Average Output Current	150	mA
Hot Switching Transient Plate Current (Per Plate)	#	
Peak Heater-Cathode Voltage	500	volts



12.6

TYPICAL OPERATION WITH CAPACITOR INPUT TO FILTER

AC Plate-to-Plate Supply Voltage (rms) Filter-Input Capacitor	500 50	600 50	700 50	volts μF
Total Effective Plate Supply Impedance per Plate	150	200	240	ohms
DC Output Voltage at Input to Filter (Approx.) For dc output current of 150 mA	245	293	347	volts


[#] When capacitor-input circuits are used, a maximum peak current value per plate of 1 ampere during the initial cycles of the hot-switching transient should not be exceeded.

6CA5

BEAM POWER TUBE

Miniature type used in af power output stage of radio and television receivers. Outlines section, 5D; requires miniature 7-contact socket. Type 12CA5 is identical with type 6CA5 except for heater ratings.

Heater Voltage (ac/dc)



volts

Heater Current	1.2		.6	ampere
Heater Warm-up Time (Average)		1	1	seconds
Heater-Cathode Voltage:				
Peak value	±200 max		300 max	volts
Average value	100 max	+100	200 max	volts
Class A ₁ A	mplifier			
MAXIMUM RATINGS (Design-Center Values)				
Plate Voltage			130	volts
Grid-No.2 (Screen-Grid) Voltage			130	volts
Grid-No.1 (Control-Grid) Voltage, Positive-bias			Ŏ	volts
Plate Dissipation			5	watts
Grid-No.2 Input			1.4	watts
Bulb Temperature (At hottest point)			180	°C
TYPICAL OPERATION				
Plate Voltage		110	125	volts
Grid-No.2 Voltage		110	125	volts
Grid-No.1 (Control-Grid) Voltage		4	-4.5	volts
Peak AF Grid-No.1 Voltage		4	4.5	volts
Zero-Signal Plate Current		32	37	mA
Maximum-Signal Plate Current		31	36	mA
Zero-Signal Grid-No.2 Current (Approx.)		3.5	4	mĄ
Maximum-Signal Grid-No.2 Current (Approx.)		7.5	11	mA
Plate Resistance (Approx.)		6000	15000	ohms
Transconductance		8100	9200	μmhos
Load Resistance		3500	4500	o hm s
Total Harmonic Distortion		5	6	per cent
Maximum-Signal Power Output		1.1	1.5	watts
MAXIMUM CIRCUIT VALUES				
Grid-No.1-Circuit Resistance:				
For fixed-bias operation			0.1	megohm
For cathode-bias operation			0.5	megohm

6CA7

Refer to chart at end of section.

P(3

6CA7/

POWER PENTODE

Glass octal types used in the output stage of audiofrequency amplifiers. Maximum dimensions: over-all length, 47/6 inches; seated height, 3% inches; diameter, 116 inches. Tube requires octal socket.

For cathode-bias operation

-/2oo	_	
Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage	6.3 1.5 ±200 max	volts amperes volts

Direct Interelectrode Capacitances: Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 Plate to Cathode, Heater, Grid No.2, and Grid No.3	1 15.5 7.2	pF pF pF
Class A: Amplifier		
MAXIMUM RATINGS (Design-Center Values)		
Plate Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.2 Input	800 425 8	volts volts watts
Cathode Current Plate Dissipation	150	mA
TYPICAL OPERATION	25	watts
	265	volts
Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage	250	volts
Peak AF Grid-No.1 Voltage	13.5 12.3	volts
Zero-Signal Plate Current	100	volts mA
Zero-Signal Grid-No.2 Current	15	mA
Transconductance	11000	μmhos
Plate Resistance	15000	ohms
Load Resistance	2000	ohma
Maximum-Signal Power Output	11	watts
Total Harmonic Distortion	10	per cent
MAXIMUM CIRCUIT VALUE		•
Grid-No.1-Circuit Resistance, for cathode-bias operation	0.7	megohm
Push-Pull Class AB, Amplifier		
MAXIMUM RATINGS (Same as for Class A ₁ Amplifier)		
TYPICAL OPERATION (Values are for two tubes)		
Plate Supply Voltage	450	volts
Grid-No.2 Supply Voltage	450	volts
Cathode-Bias Resistor	232	oh <i>m</i> s
Grid-No.2 Resistor	1000	ohms
Peak AF Grid-No.1 to Grid-No.1 Voltage	38.2	volts
Zero-Signal Plate Current	120	m A
Maximum-Signal Plate Current	143	mA
Zero-Signal Grid-No.2 Current	20	mA
Maximum-Signal Grid-No.2 Current	44	mA
Effective Load Resistance (Plate-to-plate)	6500	ohms
Total Harmonic Distortion	5.1	per cent
Maximum-Signal Power Output	40	watts

Refer to chart at end of section.

6CB5



BEAM POWER TUBE

6CB5A

Glass octal type used as horizontal-deflection amplifier in color and black-and-white television receivers. Outlines section, 21B; requires octal socket.

Heater Voltage (ac/dc)	6.3	volts
Heater Current	2.5	amperes
Heater-Cathode Voltage:		
Peak value	$\pm 200 \; \mathrm{max}$	volts
Average value	100 max	volts
Direct Interelectrode Capacitances (Approx.):		
Grid No.1 to Plate	0.4	pF pF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3	22	pF
Plate to Cathode, Heater, Grid No.2, and Grid No.3	10	pF

Class A. Amplifier

СНА	RAC	TER	IST	C:

		 75	175	volts
		 150	175	volts volts
Grid-No.1	Voltage	 v	30	VOIUS

Mu-Factor, Grid No.2 to Grid No.1	_	3.8	_
Plate Resistance (Approx.)	_	5000	oh m s
Transconductance	_	8800	μmhos
Plate Current	460●	90	m A
Grid-No.2 Current	42●	6	mA
Grid-No.1 Voltage (Approx.) for plate current of 1 mA		60	volts
• These values can be measured by a method involving a maximum rating of the tube will not be exceeded.	recurrent	waveform	such that the

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Val	lues)
-------------------------------------	-------

DC Plate Voltage	880	volts
Peak Positive-Pulse Plate Voltage#	6800	volts
Peak Negative-Pulse Plate Voltage	1650	volts
DC Grid-No.2 (Screen-Grid) Voltage	220	volts
DC Grid-No.1 (Control-Grid) Voltage	55	volts
Peak Negative-Pulse Grid-No.1 Voltage	220	volts
Peak Cathode Current	850	mA
Average Cathode Current	240	mA
Grid-No.2 Input	4	watts
Plate Dissipation†	26	watts
Bulb Temperature (At hottest point)	220	°C
ALL VILLEY AND		

MAXIMUM CIRCUIT VALUE

Grid-No.1-Circuit Resistance 0.47 megohm # Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). † A bias resistor or other means is required to protect the tube in absence of excitation.

6CB6

Refer to chart at end of section. For replacement use type 6CB6A/6CF6.

6CB6A

For replacement use type 6CB6A/6CF6.

6CB6A/

SHARP-CUTOFF PENTODE

3CB6/3CF6, 4CB6

Miniature types used in color and black-and-white television receivers as if amplifier at frequencies up to about 45 MHz and as rf amplifiers in vhf television tuners. Outlines section, 5C; requires miniature 7-con-



7CM

tact socket. For typical operation as resistance-coupled amplifiers, refer to Resistance-Coupled Amplifier section. Types 3CB6/3CF6, and 4CB6 are identical with type 6CB6A/6CF6 except for heater ratings.


	3CB6/3CF6	4CB6	6CB6A/6CF6	
Heater Voltage (ac/dc)	3.15	4.2	6.3	volts
Heater Current	0.6	0.45	0.3	ampere
Heater Warm-up Time (Average)	11	11	11	seconds
Heater-Cathode Voltage:				seconds
Peak value	∫ +2 0 0 max	∫ +200 max		volts
TERK ARING	—300 max	-300 max	±200 max	AOICS
Average value	{ +200 max -300 max 100 max	1 +100 max	100 max	volts
		(—200 max		
Direct Interelectrode Capacitances:		Unshielde	d Shielded ⁴	
Grid No.1 to Plate		0.025 max	0.015 max	рF
Grid No.1 to Cathode, Heater, Grid N	Io.2.		VIVIO	P -
Grid No.3, and Internal Shield		6.5	6.5	pF
Plate to Cathode, Heater, Grid No.2, C		•••	0.0	μ-
and Internal Shield		2	3	рF
* With external shield connected to cathode.		_	_	-
- with external anield connected to cathode.				

Class A. Amplifier

MAXIMUM RATINGS (Design-Maximum Values)

Plate Voltage	330	volts
Grid-No.3 (Suppressor-Grid) Voltage, Positive value	0	volts
Grid-No.2 (Screen-Grid) Voltage	See curve	e page 300

Grid-No.2 Supply Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input:	330 volts 0 volts 2.3 watts
For grid-No.2 voltages up to 165 volts	0.55 watt
For grid-No.2 voltages between 165 and 330 volts	See curve page 300
CHARACTERISTICS	
Plate Supply Voltage	125 volts
Grid No.3 Connected	to cathode at socket
Grid-No.2 Supply Voltage	125 volts
Cathode-Bias Resistor	56 ohms
Plate Resistance (Approx.)	0.28 megohm
Transconductance	8000 μ mhos
Plate Current	13 mA
Grid-No.2 Current	3.7 mA
Grid-No.1 Voltage (Approx.) for plate current of 20 μA	-6.5 volts
Grid-No.1 Voltage (Approx.) for plate current of 2.8 mA	-3 volts



For replacement use type 6CE3/6CD3/6DT3.

6CD3

Refer to chart at end of section.

Voltage


6CD6G

BEAM POWER TUBE

6CD6GA

volts

25CD6GB



Grid-No.1 (Control-Grid)

Mu-Factor, Grid No.2 to Grid No.1

Glass octal type used as horizontal-deflection amplifier in high-efficiency deflection circuits of color and black-and-white television receivers. Outlines section, 21B; requires octal socket. This type may be supplied with pins 1, 4, and 6 omitted. Vertical tube mounting is preferred, but horizontal operation is permissible if pins No.2 and 7 are in vertical plane. Type 25CD6GB is identical with type 6CD6GA except for heater ratings.

Heater Voltage (ac/dc)	CD6GA 6.3 2.5	25CD6GB 25 0.6	volts
Heater Current	2.0	11	amperes seconds
Heater-Cathode Voltage:			seconds
	±200 max	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances (Approx.):			
Grid No.1 to Plate		1.1	рF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3		2 2	рF
Plate to Cathode, Heater, Grid No.2, and Grid No.3		8.5	\mathbf{pF}
Class A, Amplifier			
CHARACTERISTICS			
Plate Voltage	60	175	volts
Grid-No.2 (Screen-Grid) Voltage	100	175	volts

Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of	230 · 21 •	7200 7700 5.5 5.5	ohms µmhos mA mÀ
1 mA		—5 5	volts

This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system


MAXIMUM RATINGS (Design-Center Values) DC Plate Voltage 700 volts Peak Positive-Pulse Plate Voltage# (Absolute Maximum) Peak Negative-Pulse Plate Voltage 7000= volts 1500 volta Grid-No.2 (Screen-Grid) Voltage 175 volts Peak Negative-Pulse Grid-No.1 Voltage 700 volts Peak Cathode Current ... 200 mA Average Cathode Current 200 m A Plate Dissipation† Grid-No.2 Input 20 watts

MAXIMUM CIRCUIT VALUE


Grid-No.-Circuit Resistance, for grid-resistor-bias operation 0.47 megohm # Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

Under no circumstances should this absolute value be exceeded.

A bias resistor or other means is required to protect the tube in absence of excitation.



Bulb Temperature (At hottest point)



225

6CE3

Refer to chart at end of section. For replacement use type 6CE3/6CD3/6DT3.

6CE2/

6CE3/ 6CD3/6DT3

HALF-WAVE VACUUM RECTIFIER

Duodecar type used as a damper diode in the horizontaldeflection circuit of color television receivers. Outlines section, 8G; requires duodecar 12-contact socket. Type 34CE3 is identical with type 6CE3/6CD3/6DT3 except for heater ratings.



12**GK**

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	2.5	34CE3 34.5 0.45 11	volts amperes seconds
Direct Interelectrode Capacitances: Plate to Cathode and Heater Cathode to Plate and Heater Heater to Cathode		13 18 5.5	pF pF pF

Damper Service

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage#	5000	volts
Peak Plate Current	1500	mA
Average Plate Current	350	mA
Plate Dissipation	11	watts
Bulb Temperature (At hottest point)	220	°C
Heater-Cathode Voltage		•
Peak value +300	—5500 —900	volts
Average value+100	-900	voits

CHARACTERISTIC, Instantaneous Value

Refer to chart at end of section.
For replacement use type 6BC5/6CE5.

Refer to chart at end of section.
For replacement use type 6CB6A/6CF6.

6CG3
For replacement use type 6CG3/6BW3/6DQ3.

6CG3/6BW3

For replacement use type 6CG3/6BW3/6DQ3.

HALF-WAVE VACUUM RECTIFIER

6CG3/ 6BW3/ 6DQ3


19CG3/19DQ3, 25CG3

25CG3

Duodecar type used as damper diode in horizontal-deflection circuits of color and black-and-white television receivers. Outlines section, 8G, requires duodecar 12-contact socket. Types 19CG3/19DQ3 and 25CG3 are identical with type 6CG3 except for heater ratings.

19CG3/

6CG3/ 6BW3/6DO3



Heater Voltage (ac/dc) 6.3 19	25	volts
Heater Current 1.8 0.6	0.45	amperes
Heater Warm-up Time — 11	11	seconds
Reater Warm-up Time	11	seconus
Damper Service		
For operation in a 525-line, 30-frame system		
MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage#	5000	volts
Peak Plate Current	2100	mA
Average Plate Current	350	mA
	6.5	watts
Plate Dissipation	0.5	watts
Heater-Cathode Voltage:		
Peak value+300	5000	volts
Average value+100	900	volts
CHARACTERISTIC, Instantaneous Value		
Tube Voltage Drop for plate current of 700 mA	25	volts

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

Refer to chart at end of section. For replacement use type 6CG3/6BW3/6DQ3.

6CG3/6CD3

For replacement use type 6FQ/6CG7.

6CG7


Refer to chart at end of section.

6CG8

6CG8A

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used as combined oscillator and mixer tube in color and black-and-white television receivers utilizing an intermediate frequency in the order of 40 MHz. When used in an AM/FM receiver, the triode unit is used as an oscillator for both sections. In the AM section, the pentode unit is used as a high-gain



9GF

pentode mixer; in the FM section, the pentode unit is used either as a pentode mixer or as a triode-connected mixer depending on signal-to-noise considerations. Outlines section, 6B; requires miniature 9-contact socket. Type 5CG8 is identical with type 6CG8A except for heater ratings. These types are electrically identical with miniature type 6X8 except for interelectrode capacitances.

	5CG8	6CG8A	
Heater Voltage (ac/dc)	4.7	6.3	volts
Heater Current	0.6	0.45	ampere
Heater Warm-up Time (Average)	11	11	seconds
Heater-Cathode Voltage:			
Peak value	±200 max	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances:	Unshielded	Shielded°	
Triode Unit:			
Grid to Plate	1.5	1.5	рF
Grid to Cathode, Heater, and Pentode Grid No.3	2	2.4	pF
Plate to Cathode, Heater, and Pentode Grid No.3	0.5	1	pΓ
Pentode Unit:			
Grid No.1 to Plate	0.04 max	0.02 max	рF
Grid No.1 to Cathode, Heater, Grid No.2, and			
Grid No.3	4.6	4.8	рF
Plate to Cathode, Heater, Grid No.2, and			
Grid No.3	0.9	1.6	рF
Pentode Grid No.1 to Triode Plate	0.05 max	0.04 max	pF
Pentode Plate to Triode Plate	0.05 max	0.008 max	pF
Heater to Cathode	6.5	6.5•	рF
"With outsided aspected to esthade except as	noted		

[&]quot;With external shield connected to cathode, except as noted.

[·] With external shield connected to plate.

6СНЗ	For replacement use type 6CJ3/6CH3.
6CH8	Refer to chart at end of section.
6CJ3	For replacement use type 6CJ3/6CH3.

6CJ3/6CH3 HALF-WAVE VACUUM RECTIFIER

Novar type used as damper tube in horizontal-deflection circuits of black-and-white television receivers. Outlines section, 30F; requires novar 9-contact socket. Socket terminals 1, 3, 6, and 8 should not be used as tie points. This tube, like other power-handling tubes, should be adequately ventilated. Heater: volts (ac/dc), 6.3; amperes, 1.8.



9HP

Damper Service

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)			
Peak Inverse Plate Voltage#		5500	volts
Peak Plate Current		2100	mA
Average Plate Current			mA
Plate Dissipation		6.5	watts
Heater-Cathode Voltage:			_
Peak value	+300	5500	volts
Average value	100	900	volts

CHARACTERISTICS.	Inctantanceus Valu	
CHARACTERISTICS.	. Instantaneous vait	æ

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

Refer to chart at end of section. For replacement use type 6CL3/6CK3.	6CK3
Refer to chart at end of section.	6CK4
For replacement use type 6CL3/6CK3.	6CL3



9HP

HALF-WAVE VACUUM RECTIFIER

6CL3/6CK3

Novar type used as a damper tube in horizontal-deflection circuits of color and black-and-white television receivers. Outlines section, 30B; requires novar 9-contact socket. Socket terminals 1, 3, 6, and 8 should not be used as tie points. This tube, like other power-handling tubes, should be adequately ventilated. Type 12CL3 is identical with type 6CL3/6CK3 except for

Heater Voltage (ac/dc)	1.2	12C L3 12.6 0.6 11	volts amperes seconds
Direct Interelectrode Capacitances: Plate to Cathode and Heater Cathode to Plate and Heater Heater to Cathode			pF pF pF

Damper Service

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values) volts Peak Inverse Plate Voltage# 5500 Peak Plate Current
Average Plate Current 1300 m A 250 mA 8 5 watts °C 220 Heater-Cathode Voltage: -5000 volts Peak value volts _900 Average value

heater ratings.

16 volts

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).



9BV

POWER PENTODE


6CL6

Miniature type used in output stage of video amplifier of color and black-and-white television receivers and as wide-band amplifier tube in industrial and laboratory equipment. Outlines section, 6E; requires miniature 9-contact socket.

Heater Voltage (ac/dc)	6.3 0.65	volts ampere
Peak Heater-Cathode Voltage	±100 max	volts
Direct Interelectrode Capacitances (Approx.):		_
Grid No.1 to Plate	0,12	рF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3,		_
and Internal Shield	11	pr.
Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield	5.5	nF
and internal Shield	0.0	pı.


Class A, Amplifier

Olass At Ampinion	
MAXIMUM RATINGS (Design-Center Values)	4
Plate Voltage	. 300 volts
Grid-No.3 (Suppressor-Grid) Voltage, Positive value	. 0 volts
Grid-No.2 (Screen-Grid) Supply Voltage	. 300 volts
Grid-No.2 Voltage	. 150 volts
Grid-No.1 (Control-Grid) Voltage:	. 100 4016
Negative-bias value	. 50 volts
Positive-bias value	
Plate Dissipation	
Grid-No.2 Input	. 1.7 watts
Bulb Temperature (At hottest point)	. 200 °C
TYPICAL OPERATION	
Plate Voltage	. 250 volts
Grid No.3 Cont	
Grid-No.2 Voltage	
Grid-No.1 Voltage	
Peak AF Grid-No.1 Voltage	
Zero-Signal Plate Current	
Maximum-Signal Plate Current	
Zero-Signal Grid-No.2 Current	
Maximum-Signal Grid-No.2 Current	
Plate Resistance (Approx.)	
Transconductance	
Load Resistance	
Total Harmonic Distortion	. 8 per cent
Maximum-Signal Power Output	2.8 watts
Grid-No.1 Voltage (Approx.) for plate current of 10 µA	14 volts
TYPICAL OPERATION IN MHZ-BANDWIDTH VIDEO AMPLIFIER	
	200
Plate Supply Voltage	
Grid No.8 Com	nected to cathode at socket
Grid-No.2 Supply Voltage	
Grid-No.1 Bias Voltage	
Grid-No.1 Signal Voltage (Peak to Peak)	
Grid-No.2 Resistor	
Grid-No.1 Resistor	0.1 megohm
Load Resistor	3900 ohms
Zero-Signal Plate Current	30 mA
Zero-Signal Grid-No.2 Current	
Voltage Output (Peak to Peak)	132 volts
	101
MAXIMUM CIRCUIT VALUES	
Grid-No.1 Circuit Resistance:	
For fixed-bias operation	
For cathode-bias operation	0.5 megohm



6CL8

Refer to chart at end of section.



MEDIUM-MU TRIODE— SHARP-CUTOFF TETRODE

6CL8A

Miniature type used as combined vhf oscillator and mixer in color and black-and-white television receivers. Outlines section, 6B; requires miniature 9-contact socket. For maximum ratings as class A₁ amplifier, see type 6U8A. Type 5CL8A is identical with type 6CL8A except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	5CL8A 4.7 0.6 11	6CL8A 6.3 0.45 11	volts ampere seconds
Heater-Cathode Voltage: Peak value Average value	±200 max 100 max	±200 max 100 max	volts volts
Direct Interelectrode Capacitances:	Unshielded	Shielded	
Triode Unit: Grid to Plate	1.8	1.8	рF
and Internal Shield	2.8	2.8	рF
Plate to Cathode, Tetrode Cathode, Heater, and Internal Shield Tetrode Unit:	1.5	2	pF
Grid No. 1 to Plate	0.02 max	0.01 max	рF
Grid No.1 to Cathode, Heater, Grid No.2, and Internal Shield Plate to Cathode. Heater. Grid No.2.	5	5	pF
and Internal Shield Tetrode Grid No.1 to Triode Plate Tetrode Plate to Triode Plate Heater to Cathode (Each Unit)	0.015 max 0.15 max 3	3 0.01 max 0.03 max 3	pF pF pF pF

Class A. Amplifier

CHARACTERISTICS	Triode Unit	Tetrode Unit	
Plate Supply Voltage	125	125	volts
Grid-No.2 (Screen-Grid) Voltage		125	volts
Grid-No.1 Voltage	1	-1	volt
Amplification Factor	40		
Plate Resistance (Approx.)	0.005	0.2	megohm
Transconductance	8000	6500	μm hos
Plate Current	14	12	mA
Grid-No.2 Current	_	.4	mA.
Grid-No.1 Voltage (Approx.) for plate current of			
20 μA	9	—9	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
For fixed-bias operation	0.5	0.25	megohm
For cathode-bias operation	í	1	megohm



HALF-WAVE VACUUM RECTIFIER

6CM3

Novar type used as damper tube in horizintal-deflection circuits of color and black-and-white television receivers. Outline section, 30B; requires novar 9-contact socket. Socket terminals 1, 3, 6, and 8 should not be used as tie points. This tube, like other power-handling tubes, should be adequately ventilated.

Heater Voltage (ac/dc)	6.3	volts
Heater Current	2.4	amperes
Direct Interelectrode Capacitances:		-
Plate to Cathode and Heater	20	nF
Cathode to Plate and Heater	18	ρF
Heater to Cat' de	4	pF

Damper Service

For operation in a 525-line, 30-frame system


MAXIMUM RATINGS (Design-Maximum Values)			
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current Plate Dissipation		5500 1700 400 12	volts mA mA watts
Heater-Cathode Voltage: Peak value Average value		—5500 —900	volts volts
CHARACTERISTIC, Instantaneous Value Tube Voltage Drop for plate current of 350 mA		10	volts
# Pulse duration must not exceed 15% of a horizontal scann	ing cycle	(10 microsed	conds).

6CM6

Refer to chart at end of section.

MEDIUM-MU DUAL TRIODE

Miniature type used as combined vertical-deflection oscillator and vertical-deflection amplifier in black-andwhite television receivers. Unit No.1 is used as a conventional blocking oscillator in vertical-deflection circuits, and unit No.2 as a vertical-deflection amplifier. Outlines section, 6E; requires miniature 9-contact socket. Types 8CM7 is identical with type 6CM7 except for heater ratings.



Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	6CM7 6.3 0.6 11	8CM7 8.4 0.45 11	volts ampere seconds
Heater-Cathode Voltage: Peak value Average value	100 ma:	x ±200 max x 100 max	volts volts
Direct Interelectrode Capacitances (Approx.): Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater	0.5	Unit No.2 3 3.5 0.4	pF pF pF

Class A. Amplifier

CHARACTERISTICS	Unit No.1	Unit No.2	
Plate Voltage	200	250	volts
Grid Voltage	—7	8	volts
Amplification Factor	21	18	
Plate Resistance (Approx.)	10500	4100	ohms
Transconductance	2000	4400	μmhos
Plate Current	5	20	mĄ
Plate Current for grid voltage of -10 volts	1	_	mA
Grid Voltage (Approx.) for plate current of 10 μA.	-14	_	volts


Vertical-Deflection Oscillator and Amplifier


For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		Unit No.2 Amplifier	
DC Plate Voltage	550	550	volts
Peak Positive-Pulse Plate Voltage#		2200	volts
Peak Negative-Pulse Grid Voltage	220	2 2 0	volts
Peak Cathode Current	77	77	mA.
Average Cathode Current		22	m A
Plate Dissipation	1.45	6	watts
MAXIMUM CIRCUIT VALUES			

Grid-Circuit Resistance:			
For fixed-bias operation	2.2	1	megohms
For cathode-bias operation	2.2	2.5	megohms
For grid-resistor-bias operation	2.2		megohms

[#] Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).





Refer to chart at end of section.

6CM8




Plate Current (Each Unit)

TWIN DIODE— HIGH-MU TRIODE

ance-coupled amplifier, refer to Resistance-Coupled Amplifier section.

6CN7

5.5

mΑ

Miniature type used as combined horizontal phase detector and reactance tube in color and black-and-white television receivers. The triode unit is used in syncseparator, sync-amplifier, or audio amplifier circuits. Outlines section, 6B; requires miniature 9-contact socket. For typical operation of triode unit as resist-


Heater Voltage (ac/dc): Series 6.3 volts Parallel 3.15 volts Heater Current: 0.6 ampere Series 0.3 ampere Parallel 0.6 ampere Parallel 0.6 ampere Parallel 0.6 ampere Heater Warm-up Time (Average) 11 seconds Heater-Cathode Voltage: ±200 max volts Peak value ±200 max volts Average value 100 max volts Direct Interelectrode Capacitances: Triode Units: 1.8 pF Grid to Plate 1.8 pF Grid to Cathode and Heater 1.5 pF Plate to Cathode and Heater 0.5 pF Diode-No.1 Plate to Cathode of Diodes No.1 and No. 2, Heater, and Internal Shield 3.6 pF Triode Units 3.6 pF Triode Grid to Either Diode Plate 0.006 pF MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage 330 volts Grid Voltage, Positive-bias value 0 volts Plate Voltage 100 250 volts Plate Voltage 100 250 volts Plate Resistance (Approx.) 54000 58000 ohms Transconductance 1300 1200 µmhos Plate Current 0.8 1 mAXIMUM RATINGS (Design-Maximum Values) Diode Units 1000	and trapida ampinor, rozor to reconstance coupled r	impiner section	•
Series 1,3 volts	Heater Voltage (ac/dc):		
Parallel 3.15 volts		6.3	volts
Heater Current: Series			
Series			10163
Parallel 0.6 ampere		0.3	ambara
Heater Warm-up Time (Average)			
Heater-Cathode Voltage: Peak value	Heater Warm-un Time (Average)		
Peak value			seconds
Average value Direct Interelectrode Capacitances: Triode Unit: Grid to Plate Grid to Cathode and Heater Diode Units: Diode-No.1 Plate to Cathode of Diodes No.1 and No. 2, Heater, and Internal Shield Diode-No.2 Plate to Cathode of Diodes No.1 and No. 2, Heater, and Internal Shield Triode Grid to Either Diode Plate Triode Unit as Class A₁ Amplifier MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Grid Voltage, Positive-bias value CHARACTERISTICS Plate Voltage Tolode Grid Voltage Plate Voltage Plate Voltage Tolode Grid Voltage Positive-bias value Diode-No.2 Plate Voltage The Diode-No.2 Positive-bias value Diode Voltage The Diode-No.2 Positive-bias value Diode Units Diode Units		+200 may	malta
Direct Interelectrode Capacitances: Triode Unit: Grid to Plate 1.8 pF Grid to Cathode and Heater 0.5 pF Plate to Cathode and Heater 0.5 pF Diode Units: Diode-No.1 Plate to Cathode of Diodes No.1 and No. 2, Heater, and Internal Shield 3.6 pF Diode-No.2 Plate to Cathode of Diodes No.1 and No. 2, Heater, and Internal Shield 3.6 pF Diode-No.2 Plate to Cathode of Diodes No.1 and No. 2, Heater, and Internal Shield 3.6 pF Triode Grid to Either Diode Plate 0.006 pF Triode Grid to Either Diode Plate 0.006 pF Triode Unit as Class A₁ Amplifier AMXIMUM RATINGS (Design-Maximum Values) Plate Voltage 30 volts Qrid Voltage, Positive-bias value 0 volts Qrid Voltage, Positive-bias value 0 volts Plate Dissipation 1.1 watt CHARACTERISTICS Plate Voltage 100 250 volts Qrid Voltage -1 -3 volts Amplification Factor 70 70 Plate Resistance (Approx.) 54000 58000 ohms Transconductance 1300 1200 µmhos Plate Current 0.8 1 mA			
Triode Unit: Grid to Plate	Direct Interelectrode Conscitances	100 max	VOILS
Grid to Plate 1.8			
Grid to Cathode and Heater 1.5 pF		1.0	12
Plate to Cathode and Heater 0.5 pF	Grid to Cathodo and Hoston		
Diode Units Diode-No.1 Plate to Cathode of Diodes No.1 and No. 2,			
Diode-No.1 Plate to Cathode of Diodes No.1 and No. 2, Heater, and Internal Shield 3.6 pF		0.5	pr
Heater, and Internal Shield 3.6 pF			
Diode-No.2 Plate to Cathode of Diodes No.1 and No. 2, Heater, and Internal Shield 3.6 pF		0.0	_
Heater, and Internal Shield 3.6 pF	neater, and internal Sheld	3.6	рF
Triode Grid to Either Diode Plate 0.006 pF Triode Unit as Class A₁ Amplifier MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage 330 volts Grid Voltage, Positive-bias value 0 volts Plate Dissipation 1.1 watt CHARACTERISTICS Plate Voltage 100 250 volts Grid Voltage 1 -1 -3 volts Amplification Factor 70 70 Plate Resistance (Approx.) 54000 58000 ohms Transconductance 1300 1200 μmhos Plate Current 0.8 1 mA Diode Units	Diode-No.2 Plate to Cathode of Diodes No.1 and No. 2,		
Triode Unit as Class A₁ Amplifier	neater, and internal Snield	3.6	
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	1 Plode Grid to Either Diode Plate	0.006	pr'
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	Trioda Unit as Class A Amplifi	or	
Plate Voltage 330 volts Grid Voltage, Positive-bias value 0 volts Plate Dissipation 1.1 watt CHARACTERISTICS Plate Voltage 100 250 volts Grid Voltage -1 -3 volts Amplification Factor 70 70 Plate Resistance (Approx.) 54000 58000 ohms Transconductance 1300 1200 μmhos Plate Current 0.8 1 mA	Thouse Only as Glass A, Amphili	E	
Grid Voltage, Positive-bias value 0 volts Plate Dissipation 1.1 watt CHARACTERISTICS Plate Voltage 100 250 volts Grid Voltage -1 -3 volts Amplification Factor 70 70 Plate Resistance (Approx.) 54000 58000 ohms Transconductance 1300 1200 μmhos Plate Current 0.8 1 mA	MAXIMUM RATINGS (Design-Maximum Values)		
Grid Voltage, Positive-bias value 0 volts Plate Dissipation 1.1 watt CHARACTERISTICS Plate Voltage 100 250 volts Grid Voltage -1 -3 volts Amplification Factor 70 70 Plate Resistance (Approx.) 54000 58000 ohms Transconductance 1300 1200 μmhos Plate Current 0.8 1 mA	Plate Voltage	330	volts
Plate Dissipation 1.1 watt CHARACTERISTICS Plate Voltage 100 250 volts Grid Voltage -1 -3 volts Amplification Factor 70 70 70 Plate Resistance (Approx.) 54000 58000 ohms Transconductance 1300 1200 μmhos Plate Current 0.8 1 mA			
CHARACTERISTICS Plate Voltage 100 250 volts Grid Voltage -1 -3 volts Amplification Factor 70 70 Plate Resistance (Approx.) 54000 58000 ohms Transconductance 1300 1200 μmhos Plate Current 0.8 1 mA			
Plate Voltage 100 250 volts Grid Voltage -1 -3 volts Amplification Factor 70 70 Plate Resistance (Approx.) 54000 58000 ohms Transconductance 1300 1200 μmhos Plate Current 0.8 1 mA		••••	
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	CHARACTERISTICS		
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	Plate Voltage	0 250	volts
Amplification Factor 70 70 70 70 70 70 70 70 70 70 70 70 70			
Plate Resistance (Approx.) 54000 58000 hms ohms Transconductance 1300 1200 μmhos Plate Current 0.8 1 mA	Amplification Factor		
Transconductance	Plate Resistance (Approx.) 5400		ohms
Plate Current 0.8 1 mA Diode Units	Transconductance 1300		
Diode Units	Plate Current 0		
	V,	-	
MAXIMUM RATINGS (Design-Maximum Values)	Diode Units		
	MAXIMUM RATINGS (Design-Maximum Values)		

6CQ4

Refer to chart at end of section. For replacement use type 6DE4/6CQ4.

MEDIUM-MU TRIODE-**6CQ8** SHARP-CUTOFF TETRODE

Miniature type used in color and black-and-white television receiver applications. The tetrode unit is used as a mixer, video if amplifier, or sound if amplifier G2TR tube. The triode unit is used in vhf oscillator, phasesplitter, sync-clipper, sync-separator, and rf amplifier circuits. Outlines section, 6B; requires miniature 9contact socket.



Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:		6.3 0.45 11	volts ampere seconds
Peak value Average value		±200 max 100 max	volts volts
Direct Interelectrode Capacitances: Triode Unit:	Unshielded	Shielded*	
Grid to Plate	1.8	1.8	рF
Grid to Cathode and Heater	2.7	2.7	pF
Plate to Cathode and Heater	0.4	1.2	рF
Tetrode Unit:	0.010	0.017	
Grid No.1 to Plate	0.019 max	0.015 max	pF
and Internal Shield	5	5	рF
Plate to Cathode, Heater, Grid No.2,			-
and Internal Shield	2.5	3.3	рF
Tetrode Plate to Triode Plate	0.07 max		рF
Heater to Cathode (Each Unit)	3	3†	pF
With external shield connected to enthade of unit under	tont		

With external shield connected to cathode of unit under test.

Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330 volts	330 Se 0 3.1	t Tetrode Unit 330 330 c curve page 30 3.2 0.7 c curve page 30	volts watts watt
Grid Input	0.55	_ '	watt
CHARACTERISTICS Plate-Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of	125 56 40 5000 8000 15	125 125 —1 —————————————————————————————	volts volts volts ohms ohms µmhos mA
100 μΑ	—7	7	volts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.5 1	0.25 1	megohm megohm

[†] With external shield connected to ground.




PENTAGRID AMPLIFIER

6CS6

3CS6, 4CS6, 12CS6

Miniature type used as a gated amplifier in color and black-and-white television receivers. In such service, it may be used as a combined sync separator and sync clipper. Outlines section, 5C; requires miniature 7-contact socket. Types 3CS6, 4CS6, and 12CS6 are identical with type 6CS6 except for heater ratings.

	, <u>r</u>	r			
Heater Voltage (ac/dc)	0.6 11	4CS6 4.2 0.45 11	6CS6 6.3 0.3 11	12CS6 12.6 0.15	volts ampere seconds
Peak value	100 max	±200 max 100 max	±200 max 100 max	±200 ma 100 ma	
Grid No.1 to Plate Grid No.3 to Plate Grid No.1 to Grid No.3 Grid No.1 to Cathode, Heater, Grid			0.9	7 max 6 max 2 max	pF pF pF
Grid No.4, and Grid No.5 Grid No.3 to Cathode. Heater. Gri	d No.1. Gr	id No.2.		5.5	pF
Grid No.4, and Grid No.5 Plate to Cathode, Heater, Grid No.5 Grid No.4, and Grid No.5	l, Grid No.:	2. Grid No.:	3.	7 !.5	pF pF
					pr
	s A. Amp	iltier			
CHARACTERISTICS					
Plate Voltage Grids-No.2-and-No.4 Voltage Grid-No.3 Voltage		:: <u>-</u>	30 3 -1	0 0 0	volts volts volt
Grid-No.1 Voltage Plate Resistance (Approx.) Grid-No.3-to-Plate Transconductance		0. 150	0 –	1	volt megohm μmhos
Grid-No.1-to-Plate Transconductance Plate Current	<i></i>	. 0.		0 1	μmhos mA
Grids-No.2-and-No4 Current Grid-No.3 Voltage (Approx.) for plate	e current	of	-	3	mA
$50~\mu A$ Grid-No.1 Voltage (Approx.) for plate $50~\mu A$	e current o	o f	2.	-	volts volts
				J	Voits
Gated A	Amplifier	Service			
MAXIMUM RATINGS (Design-Center Val	lues)				
Plate Voltage Grids-No.2-and-No.4 Supply Voltage Grids-No.2-and-No.4 Voltage Cathode Current Plate Dissipation Grids-No.2-and-No.4 Input:			30 Se	00 00 ee curve p 14 1	volts volts age 300 mA watt
For grids-No.2-and-No.4 voltages up For grids-No.2-and-No.4 voltages bet	to 150 volts ween 150 ar	nd 300 volts		1 e curve p	watt age 300
MAXIMUM CIRCUIT VALUES					
Grid-No.1-Circuit Resistance Grid-No.3-Circuit Resistance			0.4		megohm iegohms



MEDIUM-MU DUAL TRIODE

6CS7

Miniature type used as combined vertical-deflection oscillator and vertical-deflection amplifier in television receivers. Unit No.1 is used as a conventional blocking oscillator in vertical-deflection circuits, and unit

9EF ing oscillator in vertical-deflection circuits, and unit No.2 as a vertical-deflection amplifier. Outline section, 6E; requires miniature 9-contact socket. Type 8CS7 is identical with type 6CS7 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	6CS7 6.3 0.6 11	8CS7 8.4 0.45 11	volts ampere seconds
Peak value Average value	±200 max 100 max	±200 max 100 max	volts volts
Direct Interelectrode Capacitances (Approx.): Grid to Plate Grid to Cathode and Heater	Unit No.1 2.6 1.8	Unit No.2 2.6 3	pF pF
Plate to Cathode and Heater	0.5	0.5	pF

Class A. Amplifier

CHARACTERISTICS	Unit No.1 Oscillator	Unit No.2 Amplifler	
Plate Voltage	250	250	volts
Grid Voltage	-8.5	-10.5	volts
Amplification Factor	17	15.5	
Plate Resistance (Approx.)	7700	3450	o hms
Transconductance	2200	4500	μ mhos
Plate Current	10.5	19	mA
Plate Current for grid voltage of -16 volts	- .	3	$\mathbf{m}\mathbf{A}$
Grid Voltage (Approx.) for plate current of 10 μA	—24		volts
Grid Voltage (Approx.) for plate current of 50 µA		22	volts

Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system

ror operation in a 325-line, 30-11	tame system		
MAXIMUM RATINGS (Design-Center Values)	Unit No.1 Oscillator	Unit No.2 Amplifier	. 1.
DC Plate Voltage	500	500	v ol ts
Peak Positive-Pulse Plate Voltage# (Absolute Maximum) Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation	400 70 20 1.25	2200A 250 105 30 8.5	volts volts mA mA watts
MAXIMUM CIRCUIT VALUES			
Grid-Circuit Resistance	2.2	2.2	megohms

Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).

6CT3

Refer to chart at end of section.

6CU5

BEAM POWER TUBE

12CU5/12C5, 17CU5/17C5

Miniature type used in the audio output stage of television receivers. Outlines section, 5D; requires miniature 7-contact socket. Types 12CU5/12C5, and 17CU5/17C5 are identical with type 6CU5 except for heater ratings.



7CV

17CH5/

Heater Voltage (ac/dc)	6CU5 6.3 1.2	12CU5/12C5 12.6 0.6 11	17C5 16.8 0.45	volts ampere
Heater Warm-up Time (Average)	_	11	11	seconds
Heater-Cathode Voltage: Peak value Average value		ax ±200 max ax 100 max	±200 max 100 max	volts volts
Direct Interelectrode Capacitances (Approx.): Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, a Plate to Cathode, Heater, Grid No.2, and G	nd Grid	No.3	0.6 13 8.5	pF pF pF

A Under no circumstances should this absolute value be exceeded.

Class A. Amplifier

MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point)	150 130 0 7 1.4 220	volts volts volts watts watts
TYPICAL OPERATION Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage	120 110 8	volts volts volts
Peak AF Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current	8 49 50 4	volts mA mA mA
Zero-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Plate Resistance (Approx.) Transconductance	8.5 10000 7500	mA ohms μmhos
Load Resistance Total Harmonic Distortion Maximum-Signal Power Output	2500 10 2.3	ohms per cent watts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.1 0.5	megohm megohm

For replacement use type 6BQ6GTB/6CU6.

6CU6

Refer to chart at end of section.

6CU8



HIGH-MU TRIODE

6CW4 2CW4, 13CW4

Nuvistor type used as a grounded-cathode, neutralized rf amplifier in vhf tuners of color and black-and-white television and FM receivers. Outlines section, 1; requires nuvistor socket. Types 2CW4 and 13CW4 are identical with type 6CW4 except for heater ratings.


Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage		6CW4 6.3 0.135 ±100 max	_	volts ampere seconds volts
Direct Interelectrode Capacitances (Approx.) Grid to Plate Grid to Cathode, Heater, and Shell Plate to Cathode, Heater, and Shell Plate to Cathode Heater to Cathode		0 0	.92 4.3 1.8 .18 1.6	pF pF pF pF pF
Class A, Ampl	ifier			

MAXIMUM RATINGS (Design-Maximum Values)		
Plate Supply Voltage	300° 135	volts volts
Grid Voltage: Negative-bias value	55	volts
Peak positive value	0 15	volts mA
Plate Dissipation	1.5	watt

Typical

CHARACTERISTICS AND TYPICAL OPERATION	Characteristics	Operation	
Plate Supply Voltage	110	70	volts
Grid Supply Voltage	0	0	volts
Cathode-Bias Resistor	130	_	ohms
Grid Resistor	_	47000	ohms
Amplification Factor	65	68	
Plate Resistance (Approx.)	6600	5440	ohms
Transconductance	9800	12500	μ mhos
Plate Current	7	7.2	m A
Grid Voltage (Approx.) for plate current of 10 μA.	4		volts
MAXIMUM CIRCUIT VALUES Grid-Circuit Resistance:			
For fixed-bias operation		0.5	megohm
For cathode-bias operation		2.2	megohms
9 A mlatelalt# 200lt tl mm!	3.3 1 41		4 2 3

A plate supply voltage of 300 volts may be used provided a sufficiently large resistor is used in the plate circuit to limit the plate dissipation to 1.5 watts under any condition of operation.
 For operation at metal-shell temperatures up to 135° C.



6CW5

Refer to chart at end of section.

6CW5/ EL86

POWER PENTODE


8CW5/XL86 10CW5/LL86 15CW5/PL84

Miniature type used for vertical-deflection amplifier service in color and black-and-white television receivers. Outlines section, 6G; requires miniature 9-contact socket. Types 8CW5/XL86, 10CW5/LL86, and 15CW5/PL84 are identical with type 6CW5/EL86 except for heater ratings.



Heater Voltage (ac/dc) Heater Current Heater Warm-up Time Heater-Cathode Voltage: Peak value Ayerage value		8CW5/ XL86 8 0.6 — ±330 max ±220 max			
Direct Interelectrode Capacitances: Grid No.1 to Plate Grid No.1 to Heater Grid No.1 to Cathode, Heater, Grid Plate to Cathode, Heater, Grid No.2,	No.2, and G	rid No.3	0.).6 25 max 13 5.8	pF pF pF pF

Class A, or Class AB, Amplifier MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage Plate Supply Voltage Grid-No.2 Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode Current Plate Dissipation Grid-No.2 Input	275 600 220 600 110 14 2.1	volts volts volts volts mAt watts
Peak Grid-No.2 Input	7	watts
CHARACTERISTICS Plate Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage Mu Factor (Grid No.2 to Grid No.1) Plate Resistance Transconductance Plate Current Grid-No.2 Current	170 170 -12.5 8 26000 11000 70 3.5	volts volts volts ohms umhos mA mA
MAXIMUM CIRCUIT VALUE		
Grid-No.1-Circuit Resistance	1	megohm
Vertical-Deflection Amplifier		
For operation in a 525-line, 30-frame system		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage Peak Positive-Pulse Plate Voltage# Grid-No.2 Voltage Peak Negative-Pulse Grid-No.1 Voltage Peak Cathode Current Average Cathode Current Plate Dissipation Grid-No.2 Input	275 2200 275 250 240 110 12 2.1	volts volts volts volts mA mA watts



MAXIMUM CIRCUIT VALUE Grid-No.1-Circuit Resistance

9DX

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Pulse duration must not exceed 6% of a vertical scanning cycle (1.2 milliseconds).

6CX8

0000

megohms

Miniature type used in television receiver applications. Pentode unit is used as video amplifier; triode unit is used in sound if-amplifier, sweep-oscillator, sync-separator, sync-amplifier, and sync-clipper circuits. Outlines section, 6E; requires miniature 9-contact socket. Type 8CX8 is identical with type 6CX8 except for heater ratings.

	bCA8	8CA8	
Heater Voltage (ac/dc)	6.3	8	volts
Heater Current	0.75	0.6	ampere
Heater Warm-up Time (Average)		11	volts
Heater-Cathode Voltage:			
Peak value	±200 max	±200 max	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances:			
Triode Unit:			
Grid to Plate		4.4	ρF
Grid to Cathode and Heater		2.2	pF
Plate to Cathode and Heater		0.38	pF
Pentode Unit:			•
Grid No.1 to Plate	 .	0.06	рF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, a	and		-
Internal Shield		9	pF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and			•
Internal Shield		4.4	pF
Triode Grid to Pentode Plate		0.018 max	pF
Pentode Grid No.1 to Triode Plate		0.005 max	ρF
Pentode Plate to Triode Plate		0.17 max	pF
			-

Class A. Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Triode Un	it Pentod	e Unit
Plate Voltage	330	330	volts
Grid-No.2 (Screen-Grid) Voltage		330	volts
Grid-No.2 Voltage		See curve	page 300
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	0	
Plate Dissipation	2	5	watts
Grid-No.2 Input:			
For grid-No.2 voltages up to 165 volts		1.1	watts
For grid-No. voltages between 165 and 330 volts	_	See curve	page 300
CHARACTERISTICS			
Plate Supply Voltage	150	200	volts
Grid-No.2 Supply Voltage		125	volts
Cathode-Bias Resistor	150	68	ohms
Amplification Factor	40	_	
Plate Resistance (Approx.)	8700	70000	
Transconductance	4600	10000	μmhos
Plate Current	9.2	24	mA
Grid-No.2 Current	_	5.2	mA
Grid-Nc.1 (Voltage Approx.) for plate current of			
100 μΑ	5	-8.5	volts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance:			
For fixed-bias operation	0.5	0.25	megohm
For cathode-bias operation	ı.,	1	megohm


6CY5

SHARP-CUTOFF TETRODE 2CY5, 3CY5

MAXIMUM RATINGS (Design-Maximum Values)

Grid-No.1-Circuit Resistance

Miniature type used as rf amplifier in vhf tuners of television receivers. Outlines section, 5C; requires miniature 7-contact socket. Types 2CY5 and 3CY5 are identical with type 6CY5 except for heater ratings.




0.5

megohm

	2CY5	3CY5	6CY5	
Heater Voltage (ac/dc)	2.4	2.9	6.3	volts
Heater Current	0.6	0.45	0.2	ampere
Heater Warm-up Time (Average)	11	11	_	seconds
Peak Heater-Cathode Voltage	$\pm 100 \mathrm{max}$	±100 max	$\pm 100 \text{ max}$	volts
Direct Interelectrode Capacitances (Approx.) :				
Grid-No.1 to Plate			0.03	рF
Grid-No.1 to Cathode, Heater, Grid No.2 at	nd Internal	Shield	4.5	pF
Plate to Cathode, Heater, Grid No.2, and	Internal Sh	rield	3	рF
With external shield connected to cathode.				

Class A₁ Amplifier


Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Cathode Current	0 20	volts volts ve page 300 volts mA
Plate Dissipation	2	watts
For grid-No.2 voltages up to 90 volts	0.5 See cur	watt ve page 300
CHARACTERISTICS		
Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 20 \(\mu\)A	125 80 1 0.1 8000 10 1.5 6	volts volts volt megohm µmhos mA mA volts
MAXIMUM CIRCUIT VALUE		



DUAL TRIODE

6CY7

volts



Heater Voltage (ac/dc)

Miniature type used as combined vertical oscillator and vertical-deflection amplifier in television receivers. Unit No.1 is used as a blocking oscillator in vertical-deflection circuits, and unit No.2 is used as a vertical-deflection amplifier. Outlines section, 6E; requires miniature 9-contact socket.

Heater-Cathode Voltage:		0.10	ampere
Peak value		±200 max	volts
Average value		100 max	volts
Class A. Amplifier			
CHARACTERISTICS	Unit No.1	Unit No.2	
Plate Supply Voltage	250	150	volts
Grid Voltage	3		volts
Cathode-Bias Resistor	_	620	ohms
Amplification Factor	68	5	
Plate Resistance (Approx.)	52000	920	ohms
Transconductance	1300	5400	μ mhos
Plate Current	1.2	30	· mA
Plate Current for grid voltage of -30 volts	_	3.5	mA.
Grid Voltage (Approx.) for plate current of 10 μA	-5.5	-	volts
Grid Voltage (Approx.) for plate current of 200 µA	_	-40	voits

Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		Unit No.2 Amplifier	
DC Plate Voltage	350	350	volts
Peak Positive-Pulse Plate Voltage#		1800	volts
Peak Negative-Pulse Grid Voltage	400	250	volts
Peak Cathode Current	-	120	mA
Average Cathode Current		35	m A
Plate Dissipation	1	5.5	watts

MAXIMUM CIRCUIT VALUES

Grid-Circuit Resistance 2.2 2.2† megohms # Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).


[†] For cathode-bias operation.

6CZ5

6DB5


BEAM POWER TUBE

Miniature type used as a vertical-deflection amplifier in high-efficiency deflection circuits of color and black-and-white television receivers and in the audio output stage of television and radio receivers. Outlines section, 6G; requires miniature 9-contact socket. Type 5CZ5 is identical with type 6CZ5 except for heater ratings.



ratings.				-
Heater Voltage (ac/dc) Heater Current	ee)	5CZ5 4.7 0.6 11	6CZ5 6.3 0.45 11	volts ampere seconds
Peak value	es:	±200 max 100 max	±200 max 100 max	volts volts
Grid No.1 to Plate Grid No.1 to Cathode, Heate Plate to Cathode, Heater, (er, Grid No.2, and Grid I		0.4 max 9 6	pF pF pF
	Class A, Amplifier			
CHARACTERISTICS				
Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage Plate Resistance Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) f 100 µA	or plate current of	75 250 0 130• 16•	250 250 	volts volts volts ohms μmhos mA mA volts
Ve	rtical-Deflection Amp	lifier		
For oper	ation in a 525-line, 30-fi	ame system		
MAXIMUM RATINGS (Design-Maximum Ratings)	aximum Values)			
Peak Positive-Pulse Plate Volt Grid-No.2 (Screen-Grid) Voltag Peak Negative-Pulse Grid-No.1	(Control-Grid) Voltage		350 2200 315 275 155 45 10 2.2 250	volts volts volts volts mA mA watts watts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation			0.5 1	megohm megohm
# Pulse duration must not exceed This value can be measured by				
maximum ratings of the tube w	ill not be exceeded.			
6D4	Refer to chart	at end of	section.	
6D6	Refer to chart	at end of	section.	
6D7	Refer to chart	at end of	section.	
6D8G	Refer to chart	at end of	section.	
6D10	Refer to chart	at end of s	ection.	
6DA4	Refer to chart For replacement us			1 .

Refer to chart at end of section.



SHARP-CUTOFF PENTODE

6DC6


6DC8

6DC8/EBF89

6DE4

Miniature type used in the gain-controlled picture if stages of color and black-and-white television receivers and as an rf amplifier in the tuners of such receivers. Outlines section, 5C; requires 7-contact miniature socket.

Heater Voltage (ac/de) Heater Current Heater-Cathode Voltage:	6.3 0.3	volts ampere
Peak value Average value	±200 max 100 max	volts volts
Direct Interelectrode Capacitances: Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and	0.02 max	pF
Internal Shield	6.5	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield	2	рF



Class A, Amplifier


MAXIMUM RATINGS (Design-Center Values) Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value Grid-No.2 Supply Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts	0 2 0.5	volts volts volts curve page 300 volts watts watts curve page 300
CHARACTERISTICS		
Plate Supply Voltage Grid No.3 Connected Grid-No.2 Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for transconductance of 50 \(\mu\)mhos	150 180	volts ode at socket volts ohms megohm µmhos mA volts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.25 1	megohm megohm

Refer to chart at end of section.

Refer to chart at end of section.

HALF-WAVE VACUUM RECTIFIER

6DE4/6CQ4



Glass octal type used as damper tube in horizontal-deflection circuits of television receivers. Outlines section, 13G; requires octal socket. Socket terminals 1, 2, 4, and 6 should not be used as tie points. This tube, like other power-handling tubes, should be adequately ventilated. Types 17DE4 and 22DE4 are identical with type 6DE4/6CQ4 except for heater ratings.


Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Direct Interelectrode Capacitances (Approx.): Plate to Cathode and Heater Cathode to Plate and Heater		17 0.6 11	22DE4 22.4 0.45 11 8.5 11.5	volts amperes seconds pF pF
Heater to Cathode			4	рF
Damper Ser For operation in a 525-line,		stem		
MAXIMUM RATINGS (Design-Maximum Values)				
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current Plate Dissipation	·		5500 1100 180 6.5	volts mA mA watts
Heater-Cathode Voltage: Peak value Average value			5500 -900	volts volts
CHARACTERISTIC Instantaneous Value				
Tube Voltage Drop for plate current of 350 mA			34	volts

6DE6

SHARP-CUTOFF PENTODE

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

Miniature type used in the gain-controlled picture if stages of television receivers utilizing an intermediate frequency in the order of 40 MHz and as an rf amplifier in vhf television tuners. Outlines section, 5C; requires miniature 7-contact socket. Type 4DE6 is identical with type 6DE6 except for heater ratings.



6DE6


	4.2	6.3	volts
Heater Voltage (ac/dc)			
Heater Current	0.45	0.3	ampere
Heater Warm-up Time (Average)	11	_	seconds
Heater-Cathode Voltage:			
Peak value	$\pm 200~\mathrm{max}$	±200 max	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances:	Unshielded	Shielded*	
Grid No.1 to Plate	0.025 max	0.015 max	p₽
Grid No.1 to Cathode, Heater, Grid No.2,			_
Grid No.3, and Internal Shield	6.5	6.5	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3,	_	_	_
and Internal Shield	2	3	рF
■ With external shield connected to cathode.			

4DE6

Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	330	volts
Grid-No.3 (Suppressor-Grid) Voltage, Positive value	. 0	volts
Grid-No.2 (Screen-Grid) Supply Voltage	330	volts
Grid-No.2 Voltage	See curve	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	, V	volts watts
Plate Dissipation	2.3	WHILE

Grid-No.2 Input:		
For grid-No.2 voltages up to 165 volts	0.55	watt
For grid-No.2 voltages between 165 and 330 volts	See curve	page 300



CHARACTERISTICS		
	125	volts
Grid No.3 Connected	to cathode	at socket
Grid-No.2 Supply Voltage	125	volts
Cathode-Bias Resistor	56	ohms
Plate Resistance (Approx.)	0.25	megohm
Transconductance	8000	μ mhos
Transconductance for grid-No.1 volts of -5.5 and cathode resistor		
of 0 ohms	700	μmhos
Plate Current	15.5	mĄ
Grid-No.2 Current	4.2	mA
Grid-No.1 Voltage (Approx.) for plate current of 20 µA	9	volts



DUAL TRIODE

6DE7

10DE7, 13DE7

Miniature type used as combined vertical oscillator and vertical-deflection amplifier in television receivers. Unit No.1 is used as a blocking oscillator in vertical-deflection circuits, and unit No.2 is used as a vertical-deflection amplifier. Outlines section, 6E; requires mini-

ature 9-contact socket. For curve of average plate characteristics, Unit No.2, refer to type 6DR7. Types 10DE7 and 13DE7 are identical with type 6DE7 except for heater ratings.

	01/13		IVDI		1022.	
Heater Voltage (ac/dc)	6.3		9.7		13	volts
Heater Current	0.9		0.6		0.45	ampere
Heater Warm-up Time (Average)	_		11		11	seconds
Heater-Cathode Voltage:						
Peak value	+200	max	+200	max	±200 ma	x volts
Average value	100	max	100	max	100 ma	x volts
Direct Interelectrode Capacitances (Approx.):		Unit	No.1	Unit	No.2	
Grid to Plate			4	8.	.5	рF
Grid to Cathode and Heater		2	2	5	.5	pF
				4.		
Plate to Cathode and Heater		0.1	oz		1	рF

Class A. Amplifier

CHARACTERISTICS	Unit No.1	Unit No.2	
Plate Voltage	250	150	volts
Grid Voltage	—11	17.5	volts
Amplification Factor	17.5	6	
Plate Resistance (Approx.)	8750	925	ohms
Transconductance	2000	650 0	μmhos
Plate Current	5.5	35	m A
Plate Current for grid voltage of -24 volts		10	mA
Grid Voltage (Approx.) for plate current of 10 µA	20		volts volts
Grid Voltage (Approx.) for plate current of 50 µA			Voits

200

125

8.5

180

46 47

110

 $\frac{110}{-7.5}$

7.5

49

volts

volts

volts

volts

ohms mA

> mA mA


Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		Unit No.2 Amplifier	
DC Plate Voltage	330	275	volts
Peak Positive-Pulse Plate Voltage#	_	1500	volts
Peak Negative-Pulse Grid Voltage	400	250	volts
Peak Cathode Current	77	175	mA
Average Cathode Current	22	50	mA
Plate Dissipation	1.5	7	watts

MAXIMUM CIRCUIT VALUES

Grid-Circuit Resistance:
For grid-resistor bias or cathode-bias operation
Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).




6DG6GT **BEAM POWER TUBE** H(S) Glass octal type used as output tube in audio-amplifier applications Outlines section, 13D; requires octal socket. This type may be supplied with pin 1 omitted. **7S** Heater Voltage (ac/dc) Heater Current volts 6.3 1.2 amperes Heater-Cathode Voltage: ±200 max volts Peak value volts 100 max Average value Direct Interelectrode Capacitances (Approx.): Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 Plate to Cathode, Heater, Grid No.2, and Grid No.3 0.6 \mathbf{pF} рF 15 10 Class A. Audio-Frequency Power Amplifier MAXIMUM RATINGS (Design-Center Values) 200 volts Plate Voltage Grid-No.2 (Screen-Grid) Voltage 125 volts watts Plate Dissipation 10 Grid-No.2 Input 1.25 watts TYPICAL OPERATION

Plate Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 (Control-Grid) Supply Voltage Peak AF Grid-No.1 Voltage

Zero-Signal Plate Current
Maximum-Signal Plate Current
Zero-Signal Grid-No.2 Current

Maximum-Signal Grid-No.2 Current

Plate Resistance (Approx.) Transconductance Load Resistance Total Harmonic Distortion Maximum-Signal Power Output	13000	28000	ohms
	8000	8000	µmhos
	2000	4000	ohms
	10	10	per cent
	2.1	3.8	watts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation			megohm megohm



MEDIUM-MU TWIN TRIODE


6DJ8/ ECC88

Miniature type used as a cascode amplifier in vhf color and black-and-white television tuners. Outlines section, 6B: requires miniature 9-contact socket.

Heater Voltage (ac/dc) Heater Current		6.3 0.365	volts ampere
Heater-Cathode Voltage: Peak value	Unit No. 1	Unit No. 2 150	volts
Average value	50	-130	volts
Direct Interelectrode Capacitances:			_
Grid to Plate	1.4	1.4	pF
Grid to Cathode, Heater, and Internal Shield	3.3		pΓ
Cathode to Grid, Heater, and Internal Shield	_	6.0	рF
Plate to Cathode, Heater, and Internal Shield	1.8		рF
Plate to Grid, Heater, and Internal Shield		2.8	рF
Plate to Cathode		1.8	pF
Heater to Cathode		2.7	pF
Grid to Heater		0.13	рF
Plate of Unit No. 1 to Plate of Unit No. 2		0.045	pF
Grid of Unit No. 2 to Plate of Unit No. 1		0.005	pF

Class A. Amplifier (Each Unit)

MAXIMUM RATINGS (Design-Center Values)		
Plate Supply Voltage Cathode Current Plate Dissipation Negative Grid Voltage Plate Supply Voltage (cold condition)	130 25 1.8 50 550	volts mA watts volts volts
CHARACTERISTICS		
Plate Voltage Grid Voltage	90 1.3	volts volts
Amplification Factor Transconductance Plate Current Equivalent Noise Resistance	33 12250 15 300	μmhos mA ohms
MAXIMUM CIRCUIT VALUES	000	711111
Grid-Circuit Resistance Heater to Cathode Circuit Resistance	1.0 0.02	megohm megohm




SHARP-CUTOFF PENTODE

3DK6, 4DK6, 12DK6

Miniature type used as if-amplifier tube in color and black-and-white television receivers. Outlines section, 5C; requires miniature 7-contact socket. Types 3DK6, 4DK6, and 12DK6 are identical with type 6DK6 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage: Peak value	3DK6 3.15 0.6 11 \$\frac{+200 max}{-300 max}	4DK6 4.2 0.45 11 ±200 max	6DK6 6.3 0.3 — ±200 max	12.6 0.15 — ±200 ma:	volts ampere seconds
Average value Direct Interelectrode Capacitances:	100 max	100 max	100 max		
Grid No.1 to Plate			0.02	5 max	pF
Grid No.1 to Cathode, Heater, Grid Internal Shield			6	.3	pF
Internal Shield			1	.9	pF
Cla	ss A, Ampl	ifier			
MAXIMUM RATINGS (Design-Maximum	Values)				
Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, P Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Posi Plate Dissipation Grid-No.2 Input:	ositive value e tive-bias valu		35 Se	30 0 30 se curve p 0 .3	volts volts volts age 300 volts watts
For grid-No.2 voltages up to 165 v For grid-No.2 voltages between 165				i5 e curve p	watt age 300



CHARACTERISTICS Plate Supply Voltage	 Connected	125 to cathode	volts at socket
Grid-No.2 Supply Voltage Cathode-Bias Resistor		125	volts ohms
Plate Resistance (Approx.) Transconductance			megohm µmhos
Plate Current		12	mA.
Grid-No.2 Current		3.8 6.5	mA volts

6DL3

HALF-WAVE VACUUM RECTIFIER

Novar type used as a damper tube in television receivers. Outlines section, 40B; requires novar 9-contact socket. Socket terminals 1, 3, 6, 8, and 9 should not be used as tie points. Type 25DL3 is identical with type 6DL3 except for heater ratings.



9GD

Heater Voltage (ac/dc) 6.3 25DL3 Heater Current 2.3 0.45 Heater Warm-up Time (average) 11 Direct Interelectrode Capacitances: Cathode to Plate and Heater 17 Plate to Cathode and Heater 13 Heater to Cathode 4.4 Heater to Cathode 4.4	volts ampere seconds pF pF pF
Damper Service	,-
For operation in a 525-line, 30-frame system	
Peak Inverse Plate Voltage# 6500 Peak Plate Current 1800 Average Plate Current 400 Plate Dissipation 11 Bulb Temperature (At hottest point) 220 Heater-Cathode Voltage:	volts mA mA watts °C
Peak value +300 -6500 Average value +100 -900	volts volts
CHARACTERISTIC, instantaneous Value Tube Voltage Drop for plate current of 800 mA	volts

Refer to chart at end of section.

Pulse duration must not exceed 15% of a horizontal scanning cycle.

6DL4/EC88

Refer to chart at end of section.

6DL5 6DL5/EL95

Refer to chart at end of section. For replacement use type 6DM4A/6DA4.

6DM4 6DM4A

VA

HALF-WAVE VACUUM RECTIFIER

6DM4A/ 6DA4

Glass octal type used as damper tube in horizontal-deflection circuits of television receivers. Outlines section, 13G; requires octal socket. Socket terminals 1, 2, 4, and 6 should not be used as tie points. This tube, like other power-handling tubes, should be adequately ventilated. Type 17DM4A is identical with type 6DM4A/6DA4 except for heater ratings.

CD3444 /CD44 18D344



4CG

	bDM4A/bDA4	I/DM4A	
Heater Voltage (ac/dc)	6.3	16.8	volts
Heater Current	1.2	0.45	amperes
Heater Warm-up Time (Average)	_	11	seconds

Damper Service

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage# Peak Plate Current	. 1200	volts mA
Average Plate Current Plate Dissipation	20 0	mA watts
Heater-Cathode Voltage: Peak value	005000 00900	volts volts

[#] Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

6DN3

HALF-WAVE VACUUM RECTIFIER

Novar type used as a damper diode in horizontaldeflection circuits of color television receivers. Outlines section, 8G; requires novar 9-contact socket. Terminals 1, 3, 6, and 8 should not be used as tie points for external-circuit components.



Heater Voltage (ac/dc)	6.3	volts
Heater Current	2.4	amperes
Direct Interelectrode Capacitances:		-
Plate to Cathode and Heater		рF
Cathode to Plate and Heater		pF
Heater to Cathode	4	pF

Damper Service

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Peak Inverse Plate Voltage#	5500	volts
Peak Plate Current	2100	mA
Average Plate Current		mA
Plate Dissipation	9	watts
Bulb Temperature (At hottest point)	220	$^{\circ}\mathrm{C}$
Heater-Cathode Voltage:		
	5500	volts
Average value +100	900	volts

6DN6


CHARACTERISTIC, Instantaneous Value

Refer to chart at end of section.

6DN7

MEDIUM-MU DUAL TRIODE

Glass octal type used as combined vertical-deflection-oscillator and vertical-deflection-amplifier tube in television receivers. Outlines section, 13B; requires octal socket. Heater: volts (ac/dc), 6.3; amperes, 0.9; maximum heater-cathode volts, ±200 peak, 100 average.



8BD

Class A. Amplifier

CHARACTERISTICS	Unit No.1	Unit No.2	
Plate Voltage	250	250	volts
Grid Voltage	—8	9.5	volts
Amplification Factor	22.5	15.4	
Plate Resistance (Approx.)	9000	2000	ohms
Transconductance	2500	7700	μ mhos
Plate_Current	8	41	m A
Grid Voltage (Approx.) for plate current of 10 μA	18	_	volts
Grid Voltage (Approx.) for plate current of 50 μ A		23	volts

Vertical-Deflection Oscillator and Amplifier For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)	Unit No.1 Oscillator	Unit No.2 Amplifier	
DC Plate Voltage	350	550	volts
Peak Positive-Pulse Plate Voltage#	_	2500	volts
Peak Negative-Pulse Grid Voltage	400	250	mA
Peak Cathode Current	_	150	mA
Average Cathode Current	-	50	mA
Plate Dissipation	1	10	watts
MAXIMUM CIRCUIT VALUES Grid-Circuit Resistance:			
For fixed-bias operation For cathode-bias operation	2.2 2.2	2.2	megohms megohms

[#] Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).

Refer to chart at end of section. For replacement use type 6CG3/6BW3/6DQ3.

6DQ3

Refer to chart at end of section.

6DQ4



BEAM POWER TUBE

6DQ5

Glass octal type used as horizontal-deflection amplifier in color and black-and-white television receivers.


816 Outlines section, 21B; requires octal s	воскет.	
Heater Voltage (ac/dc)	6.3	volts
Heater Current	2.5	amperes
Heater-Cathode Voltage:		_
Peak value	$\pm 200 \text{ max}$	volts
Average value	100 max	volts
Direct Interelectrode Capacitances (Approx.):		
Grid No.1 to Plate	0.5	рF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3	23	pF
Plate to Cathode, Heater, Grid No.2, and Grid No.3	11	pF
Olasa A. Amulician		


Class A, Amplifier

CHARACTERISTICS	Pentode Connection		
Plate Voltage	70 17	5 125	volts
Grid No.2 (Screen-Grid) Voltage	125 12	5 —	volts
Grid No.1 (Control-Grid) Voltage	0 —2	5 —25	volts
Amplification Factor		- 3.3	
Plate Resistance (Approx.)	5500) —	ohms
Transconductance	10500) —	μ mhos
Plate Current	550* 110) —	m A.
Grid-No.2 Current	42*	5	mA.
Grid-No.1 Voltage (Approx.) for plate $mA = 1$.	→ −5 8	i —	volts
0.11.37.0			

Grid No.2 connected to plate.

^{*}This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.





Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum values)		
DC Plate Voltage	990	volts
Peak Positive-Pulse Plate Voltage#	6500	volts
Peak Negative-Pulse Plate Voltage	1100	volts
DC Grid-No.2 (Screen-Grid) Voltage	190	volts
Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage	250	volts
Peak Cathode Current	1100	mA.
Average Cathode Current	315	mA
Grid-No.2 Input	3.2	watts
Plate Dissipation.	24	watts
Bulb Temperature (At hottest point)	220	$^{\circ}\mathbf{C}$

MAXIMUM CIRCUIT VALUE

Grid-No.1-Circuit Resistance, for grid-resistor-bias operation 0.47 # Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). A bias resistor or other means is required to protect the tube in absence of excitation.

6DQ6A

Refer to chart at end of section.

6DQ6B

For replacement use type 6GW6/6DQ6B.

CNDS

6DR7

DUAL TRIODE

tvpe high-mu and Miniature containing low-mu triodes; used as combined vertical-deflection-oscillator and vertical-deflection-amplifier tube in television receivers. Outlines section, 6E; requires miniature 9-contact socket. Types 10DR7 and 13DR7 are identical with type 6DR7 except for heater ratings.





9HF

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	6.3 0.9	9.7 0.6 11	13 <i>D</i> R 7 13 0.45 11	volts ampere seconds
Heater-Cathode Voltage:				
Peak value	±200 max	±200 max	±200 ma	x volts
Average value	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances (Approx.):	Unit	No.1 Uni	t No.2	
Grid to Plate		1.5	8.5	pF
Grid to Cathode and Heater		2.2	5.5	pF
Plate to Cathode and Heater	. 0.	34	1	ρF

Class A. Amplifier

CHARACTERISTICS Plate Voltage	Unit No.1 250	Unit No.2 150	volts
Grid Voltage	3	17.5	volts
Amplification Factor	68	6	VOILS
Plate Resistance (Approx.)	40000	925	ohms
Transconductance	1600	6500	μmhos
Plate Current	1.4	35	m A
Plate Current for grid voltage of -24 volts		10	mA
Grid Voltage (Approx.) for plate current of 10 μ A	5.5	-	volts
Grid Voltage (Approx.) for plate current of 50 μA	_	44	volts





Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)

Oscillator Amplifier 330 DC Plate Voltage 275 Peak Positive-Pulse Plate Voltage#

Unit No.1 Unit No.2 1500

volts volts

Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation	400	250	volts
	70	175	mA
	20	50	mA
	1	7	watts
MAYIMIM CIRCUIT VALUES	-	•	***************************************

MAXIMUM CIRCUIT VALUES

Grid-Circuit Resistance:

For grid-resistance-bias or cathode-bias operation 2.2 2.2 megohms # Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).




HIGH-MU TRIODE

6DS4

Nuvistor type used as grounded-cathode, neutralized rf amplifier in vhf tuners of color and black-and-white television and FM receivers. Outlines section, 1; requires nuvistor socket. Type 2DS4 is identical with type 6DS4 except for heater ratings.

Heater Voltage (ac/dc) 2.1 Heater Current 0.45 Heater Warm-up Time (Average) 8 Peak Heater-Cathode Voltage ±100 max	6.3 0.135 ±100 max	volts ampere seconds volts
Direct Interelectrode Capacitances (Approx.) Grid to Plate Grid to Cathode, Heater, and Shell Plate to Cathode, Heater, and Shell Plate to Cathode Heater to Cathode	0.92 4.3 1.8 0.18 1.6	of of of of of
Class A. Amplifier		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Supply Voltage Plate Voltage Grid Voltage, Negative-bias value Grid Voltage, Peak positive value Cathode Current Plate Dissipation	300° 135 55 0 15 1.5	volts volts volts volts mA watt
CHARACTERISTICS		
Plate Supply Voltage Grid Supply Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current	110 0 130 63 7000 9000 6.5	volts volts ohms ohms µmhos mA
Grid Voltage (Approx.) for plate current of 100 μA	—5 —6.8	volts volts



TYPICAL OPERATION

Plate Voltage Grid Supply Voltage Grid Resistor Amplification Factor Plate Resistance (Approx.) Transconductance	70 0 47000 68 5440 12500	volts volts ohms ohms μmhos
Plate Current	7	mA

MAXIMUM CIRCUIT VALUES

Grid-Circuit Resistance:		
For fixed-bias operation	0.5	megohm
For cathode-bias operation	2.2	megohm

A plate supply voltage of 300 volts may be used provided a sufficiently large resistor is used in the plate circuit to limit the plate dissipation to 1.5 watts under any condition of operation.

6DS5

BEAM POWER TUBE

Miniature type used in the audio output stages of television and radio receivers. Outlines section, 5D; requires miniature 7-contact socket. Type 11DS5 is identical with type 6DS5 except for heater ratings.

Grid-No.2 Input
Bulb Temperature (At hottest point)



7BZ

250

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time Peak Heater-Cathode Voltage Direct Interelectrode Capacitances (Approx.): Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Grid N Plate to Cathode, Heater, Grid No.2, and Grid No.1	lo.3	11DS5 11.2 0.45 11 ±200 max 0.19 9.5 6.3	volts ampere seconds volts pF pF pF
Class A ₁ Amplifier	•		
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input		275 275 0 9 2.2	volts volts volts watts watts

€ 100	TYPE GRID	6DS5	VOLTS =				
B.		16	EC100				
MPENES				.2 .EC.	-4		
09.00 MILLIA	G	RID-No	702		-6	8-	
76 (Ib	5		Ic			-10	
\$				1			-14-4 -18-4
C	•	ı	00 Plate		00 .TS		00 -92 92 T

TYPICAL OPERATION AND CHARACTERISTICS	Cathode Opera			i-Bias ration	
Plate Supply Voltage	200 200	250 200	200 200	250 200	volts volts
Grid-No.1 Voltage	180	270	7.5 	—8.5 —	ohms

[•] For operation at metal-shell temperatures up to 125°C.

Peak AF Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Plate Resistance (Approx.) Transconductance Load Resistance Total Harmonic Distortion Maximum-Signal Power Output	7.5 34.5 32.5 3.5 9 28000 6000 10 2.8	9.2 27 25 3 9 28000 5800 8000 10 3.6	7.5 35 36 3 9 28000 6000 6000 9	8.5 29 32 3 10 28000 5800 8000 10 3.8	volts mA mA mA ohms µmhos ohms per cent watts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation				0.1	megohm megohm

Refer to chart at end of section. For replacement use type 6CE3/6CD3/6DT3.

6DT3



BEAM POWER TUBE

19DT5

Miniature type used as a vertical-deflection-amplifier tube in television receivers employing 110-degree picture-tube systems. Outlines section, 6E; requires miniature 9-contact socket. Type 12DT5 is identical with type 6DT5 except for heater ratings.

6DT5

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage: Peak value Average value		3	12.6 0.6 11 ±200 max 100 max	volts amperes seconds volts volts
Class A. Amplific	er			
CHARACTERISTICS				
Plate Voltage	60	80	250	volts
Grid-No. 2 Voltage	150	250	250	volts
Grid-No.1 Voltage	0	0	16.5	volts
Transconductance			6200	μmhos
Plate Current	95•	195•	44	mA
Grid-No.2 Current	8.5•	19•	1.5	mA
Grid-No.1 Voltage (Approx.) for plate current of 100 mA		 rent w	-35	volts
maximum ratings of the tube will not be exceeded.				
Vertical-Deflection An	nnlifier			

Vertical-Deflection Amplifier

MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Voltage	315	volts
Peak Positive-Pulse Plate Voltage#	2200	volts
Grid-No.2 (Screen-Grid) Voltage	285	volts
Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage	250	volts
Peak Cathode Current	190	mA
Average Cathode Current	55	mA
Plate Dissipation	9	watts
Grid-No.2 Input		watts
MAXIMUM CIRCUIT VALUES		


Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.5	megohni
For cathode-bias operation	1	megohm

[#] Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).

6DT6A

3DT6A, 4DT6A SHARP-CUTOFF PENTODE

Miniature type used as FM detector in color and blackand-white television receivers. Outlines section, 5C; requires miniature 7-contact socket. Types 3DT6A and 4DT6A are identical with type 6DT6A except for heater ratings.



Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	3DT6A 3.15 0.6 11	4DT6A 4.2 0.45 11	6DT6A 6.3 0.3 —	volts ampere seconds
Peak value Average value Direct Interelectrode Capacitances (Approx.)*	100 max		±200 max 100 max	
Grid No.1 to Plate	No.3, and		.02	pF
Internal Shield Grid No.3 to Plate Grid No.1 to Grid No.3 Grid No.3 to Cathode, Heater, Grid No.1, Grid			5.8 1.7 0.1	pF pF pF
Internal Shield		(6.1	$p\mathbf{F}$

^{*} External shield connected to cathode.

CHARACTERISTICS

Class A. Amplifier

Plate Supply Voltage	150	volts
Grid No.3 (Suppressor Grid) Connected	to cathode	at socket
Grid-No.2 (Screen-Grid) Supply Voltage	100	volts
Cathode-Bias Resistor	560	ohms
Plate Resistance (Approx.)	0.15	megohm
Transconductance, Grid No.1 to Plate	1350	μmhos
Transconductance, Grid No.3 to Plate	515	umhos
Plate Current	1.55	mA
Grid-No.2 Current	1.8	mA.
Grid-No.1 Voltage (Approx.) for plate current of 10 μ A	5.2	volts
Grid-No.3 Voltage (Approx.) for plate current of 10 μA	4.2	volts
FM Detector		
MAXIMUM RATINGS (Design-Maximum Values)		
Dista Vales	000	•••


maximom kariitao (besign maximum talaes)	
Plate Voltage	330 volts
Grid-No.3 Voltage	28 volts
Grid-No.2 Supply Voltage	330 volts
Grid-No.2 Voltage	See curve page 300
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0 volts
Plate Dissipation	1.7 watts
Grid-No.2 Input:	
For grid-No.2 voltages up to 165 volts	
For grid-No.2 voltages between 165 and 330 volts	See curve page 300
MAXIMUM CIRCUIT VALUES	
Grid-No.1-Circuit Resistance:	

For fixed-bias operation	0.25	megohm
For cathode-bias operation	0.5	megohm

6DT8

HIGH-MU TWIN TRIODE

Miniature type used in radio and television receiver applications and in push-pull rf amplifiers or as frequency converter in FM tuners. Outlines section, 6B; requires miniature 9-contact socket. Type 12DT8 is identical with type 6DT8 except for the heater ratings. Except for heater and heater-cathode ratings, interelectrode capacitances, and basing arrangement, these types are identical with miniature type 12AT7.



9AJ

Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage:	6DT8 6.3 0.3	12DT8 12.6 0.15	volts ampere
Peak value Average value	±200 max 100 max	±200 max 100 max	volts volts
Direct Interelectrode Capacitances (Approx., Each Unit 1 Noted:	Except as		
Grid to Plate		1.6*	рF
Grid to Cathode, Heater, and Internal Shield		2.7*	pF
Plate to Cathode, Heater, and Internal Shield		1.6*	рF
Heater to Cathode		3•	ρF
Cathode to Grid, Heater, and Internal Shield (Unit N		5.3†	ρF
Plate to Grid, Heater, and Internal Shield (Unit No.2))	2.8†	pF
+ With outcome shield connected to said of unit under test	•		_

- † With external shield connected to grid of unit under test.
- · With external shield connected to ground.
- * With external shield connected to cathode of unit under test.




MEDIUM-MU TRIODE

6DV4

Nuvistor type used at frequencies up to 1000 MHz in uhf oscillator stages of color and black-and-white television receivers. Outlines section, 1; requires nuvistor socket. Type 2DV4 is identical with type 6DV4 except for heater ratings.

INDEX = LARGE LUG = = SHORT PIN
12EA

12EA	
Company	6DV4 6.3 volts 0.135 ampere
Direct Interelectrode Capacitance (Approx.): Grid to Plate Grid to Cathode, Heater, and Shell Plate to Cathode, Heater, and Shell Plate to Cathode Heater to Cathode Grid to Cathode	. 4.4 pF . 1.9 pF . 0.25 pF . 1.4 pF
Class A, Amplifier	
MAXIMUM RATINGS (Design-Maximum Values)	
Plate Supply Voltage Plate Voltage Grid Voltage:	
Negative-bias value Peak positive value Plate Dissipation Cathode Current	2 volts 1 watt
CHARACTERISTICS	
Plate Supply Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.)	. 100 ohms . 35
Transconductance Plate Current Grid Voltage (Approx.) for plate current of 10 μA	. 11500 μmhos . 10.5 mA
TYPICAL OPERATION AS OSCILLATOR AT 950 MHz	
Plate Voltage Grid Voltage Grid Resistor Plate Current Grid Current	$\begin{array}{cccccccccccccccccccccccccccccccccccc$



MAXIMUM CIRCUIT VALUES

Grid-Circuit Resistance:		
For fixed-bias operation	0.1	megohm
For cathode-bias operation	0.2	megohm
 For operation at metal-shell temperatures up to 135°C. 		

6DW4 6DW4A

Refer to chart at end of section.

6DW4B

HALF-WAVE VACUUM RECTIFIER

Novar types used as damper tubes in horizontal-deflection circuits of color and black-and-white television receivers. Outlines section, 11D and 30B, respectively; require novar 9-contact socket. Socket terminals 1, 3, 6, and 8 should not be used as tie points; it is recom-



volts

mended that socket clips for these pins be removed to reduce the possibility of arc-over and to minimize leakage. These tubes, like other power-handling tubes, should be adequately ventilated.

Heater Voltage (ac/dc)	6.3	volts
Heater Current	1.2	amperes
Direct Interelectrode Capacitances (Approx.):		-111,0 41 60
Plate to Cathode and Heater	6.5	\mathbf{pF}
Cathode to Plate and Heater	9	ρF
Heater to Cathode	28	ર્વેવ
	2.0	PI

Damper Service

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)	
Peak Inverse Plate Voltage#	
Peak Plate Current Average Plate Current	1300 mA 250 mA
Plate Dissipation	8.5 watts
Peak value +300 Average value +100	

CHARACTERISTIC, Instantaneous Value

Tube Voltage Drop for plate current of 350 mA .


Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

6DW5

Refer to chart at end of section.

6DX8

Refer to chart at end of section.



HIGH-MU TRIODE....

6DX8/ ECL84

10DX8/LCL84

SHARP-CUTOFF PENTODE

Miniature type used in color and black-and-white tele-

6DX8/ECL84 10DX8/LCL84

vision-receiver applications. The triode unit is used as a sync-separator, sync-amplifier, keyed-agc, or noise-9HX suppressor tube. The pentode unit is used as a video-output tube. Outlines

section, 6E; requires miniature 9-contact socket. Type 10DX8/LCL84 is identical with type 6DX8/ECL84 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage			6.3 0.72 ±200 max	10.2 0.45 ±200 max	volts ampere volts
Class	s A, Amplit	fier			
MAXIMUM RATINGS (Design-Center Val	ues)		Triode Unit	Pentode Unit	
Plate Supply Voltage Peak Plate Voltage, with maximum plat			550	550	volts
0.1 mA			600		volts
Plate Voltage			300	300	volts
Grid-No.2 (Screen-Grid) Supply Voltage			-	550	volts
Grid-No.2 Voltage				300	volts
Cathode Current			12	40	mA
Plate Dissipation			1	4	watts
Grid-No.2 Input			_	1.7	watts
CHARACTERISTICS	Triode Unit		Pentode Un	it	
Plate Voltage	200	170		220	volts
Grid-No.2 Voltage	_	170		220	volts
Grid No.1 Voltage		-2.1	2.9	3.4	volts
Amplification Factor	65	_			
Mu-Factor, Grid-No.2 to Grid-No.1	_	36		36	
Plate Resistance (Approx.)	4000	0.1		0.15	megohni
Transconductance		1000		10000	μmhos
Plate Current	3	18		18 3	mA
Grid-No.2 Current	_	3	3	3	mA
MAXIMUM CIRCUIT VALUES					
Grid-No.1- Circuit Resistance:			Triode Unit	Pentode Unit	
For fixed-bias operation			1	1	megohm



MEDIUM-MU TRIODE

· With maximum duty factor of 0.18 and maximum pulse duration of 18 microseconds.

For cathode-bias operation

6DZ4

megohms

Miniature type used as a local-oscillator tube in uhf color and black-and-white television receivers covering the frequency range from 470 to 890 MHz. Outlines section, 5B; requires miniature 7-contact socket. For curve of average plate characteristics, refer to type 6AF4A.

Heater Voltage (ac/dc)	$\begin{array}{c} 6.3 \\ 0.225 \end{array}$	volts ampere
Heater-Cathode Voltage: Peak value Average value	±50 max 25 max	volts volts
Direct Interelectrode Capacitances (Approx.): Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater	1,8 2.2 1.3	pF pF pF
 With external shield connected to cathode. 		

Class A₁ Amplifier


CHARACTERISTICS		
Plate Supply Voltage Plate Resistor	80 2700	volts ohms
Amplification Factor Plate Resistance (Approx.)	14 2000	ohms
Transconductance	6700	μ mhos
Plate Current Grid Voltage (Approx.) for plate current of 20 μA	—15 —11	mA volts
UHF Oscillator		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate_Voltage	135	volts
Grid Voltage, Negative-bias value	50	volts
Grid Current Cathode Current	2 20	mA.
Plate Dissipation	2.3	mA watts
TYPICAL OPERATION AS OSCILLATOR AT 1000 MHz		
Plate Supply Voltage	135	volts
Plate-Circuit Resistance	2700	ohms
Grid Resistor Plate Current	10000	ohms
Grid Current (Approx.)	15.5 800	mΑ μΑ
MAXIMUM CIRCUIT VALUES	500	μ21
Grid-Circuit Resistance:		
For fixed-bias operation	Not r	ecommended
For cathode-bias operation	0.5	megohm

6DZ7

Refer to chart at end of section.

6E5 ELECTRON-RAY TUBE

Glass type used to indicate the effects of a change in a controlling voltage. It is used to indicate accurate radio-receiver tuning. Outlines section, 13H; requires 6-contact socket. Heater: volts (ac/dc), 6.3; amperes, 0.3. For additional considerations, refer to Tuning Indication with Electron-Ray Tubes in Electron Tube Applications section.




Tuning Indicator

MAXIMUM AND MINIMUM RATINGS (Design-Center Va	alues)		
Plate-Supply Voltage		250 max	volts
Target Voltage		∫250 max }125 min	volts volts
TYPICAL OPERATION		(125 mm	VOILS
Plate and Target Supply Voltage	200	250	volts
Series Triode-Plate Resistor	1	1	megohm
Target Current*†	3	4	mA
Triode-Plate Current*	0.19	0.24	mA
Triode-Grid Voltage (Approx.):			
For shadow angle of 0°	6.5	8	volts
For shadow angle of 90°	0	0	volts
* For zero triode-grid voltage. † Subject to wide variations.			

6EA5	Refer to chart at end of section. For replacement use type 6CY5.
6EA4	Refer to chart at end of section.
6E7	Refer to chart at end of section.
6E6	Refer to chart at end of section.

Refer to chart at end of section. For replacement use type 6EM7/6EA7.

6EA7



9AF

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6**EA**8

19EA8

Miniature type used as combined oscillator and mixer in color and black-and-white television receivers utilizing an intermediate frequency in the order of 40 MHz. Outlines section, 6B; requires miniature 9-contact socket. Types 5EA8 and 19EA8 are identical with type 6EA8 except for heater ratings.

6EA8

5EA8


	••	


Heater Voltage (ac/dc)	4.7	6.3	18.9	volts
Heater Current	0.6	0.45	0.15	ampere
Heater Warm-up Time (Average)	11	11	11	seconds
Heater-Cathode Voltage:				
Peak value	$\pm 200 \text{ max}$	$\pm 200 \text{ max}$	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	100 max	volts
	Uı	nshielded S	Shielded	
Direct Interelectrode Capacitances:				
Triode Unit:				
Grid to Plate		1.7	1.7	рF
Grid to Cathode, Heater, Pentode Cathode,				•
Pentode Grid No.3, and Internal Shield		3	3.2	pF
Plate to Cathode, Heater, Pentode Cathode,		_		•
Pentode Grid No.3, and Internal Shield		1.4	1.9	pF
Cathode to Heater		3	3.0	pF
Pentode Unit:		U	U	P.
Grid No.1 to Plate		0.02 max	0.01 max	рF
Grid No.1 to Cathode, Heater, Grid No.2,		0.02 IIIAA	0.01 Hida	pı
Grid No.3, and Internal Shield		5	5	pF
		υ	Ð	pr
Plate to Cathode, Heater, Grid No.2, Grid I		0.0	0.4	- 173
and Internal Shield		2.6	3.4	pF
Heater to Cathode		3	3.●	рF

With external shield connected to cathode of unit under test except as noted.

Class A. Amplifier

Oldas VI Vinhille	, l	
MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit Pentode Unit	
Plate Voltage	330 330 volts	
Grid-No.2 (Screen-Grid) Supply Voltage	→ 330 volts	
Grid-No.2 Voltage	— See curve page 300	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0 0 volts	
Plate Dissipation	2.5 3.1 watts	
Grid-No.2 Input:		
For grid-No.2 voltages up to 165 volts	0.55 watt	
For grid-No 2 voltages between 165 and 330 volts	See curve page 300	





[•] With external shield connected to ground.

Triode Unit Pentode Unit

0.5

megohm megohm

CHARACTERISTICS

150	125	volts
	125	volts
_	1	volt
56		ohms
40	_	
5000	200000	ohms
8500	6400	μ mhos
18	12	mA
	4	mA
—12	9	volts
	56 40 5000 8500 18	125 40 40 5000 200000 8500 6400 18 12 4

6EB8

HIGH-MU TRIODE— SHARP-CUTOFF PENTODE


Miniature type used in color and black-and-white television receiver applications. Pentode unit is used as video output amplifier; triode unit is used in syncseparator, sync-clipper, and phase-inverter circuits. Outlines section, 6E; requires miniature 9-contact socket.

MAXIMUM RATINGS (Design-Maximum Values)

For fixed-bias operation

For cathode-bias operation


MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance:




Heater Voltage (ac/dc)	6.3	volts
Heater Current	0.75	ampere
Heater-Cathode Voltage:		
Peak value	$\pm 200 \text{ max}$	volts
Average value	100 max	volts
Direct Interelectrode Capacitances:		
Triode Unit:		
Grid to Plate	4.4	рF
Grid to Cathode and Heater	2.4	\mathbf{pF}
Plate to Cathode and Heater	0.36	pF
Pentode Unit:		
Grid No.1 to Plate	0.1 max	рF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and		
Internal Shield	11	\mathbf{pF}
Plate to Cathode, Heater, Grid No.2, Grid No.3, and		
Internal Shield	4.2	\mathbf{pF}
Triode Grid to Pentode Plate	0.018 max	рF
Pentode Grid No.1 to Triode Plate	$0.005 \mathrm{max}$	рF
Pentode Plate to Triode Plate	0.17 max	\mathbf{pF}

Class A. Amplifier

Plate Voltage	330	330	volts
Grid-No.2 (Screen-Grid) Supply Voltage	_	330	volts
Grid-No.2 Voltage		See curve page	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	õ	volts
Plate Dissipation	1	5	watts
Grid-No.2 Input:		11	watts
For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330 volts	_	I.1 See curve page	
For grid-No.2 voltages between 165 and 350 volts	_	See curve page	300
CHARACTERISTICS			
Plate Supply Voltage	250	200	volts
Grid-No.2 Supply Voltage	_	125	volts
Grid Voltage	—2	_	volts
Cathode-Bias Resistor		68	ohms
Amplification Factor	100	_	
Plate Resistance (Approx.)	37000	75000	ohms
Transconductance	2700	12500	μmhos
Plate Current	2	25	mĄ
Grid-No.2 Current		7	mA.
Grid Voltage (Approx.) for plate current of 20 μA	5		volts
Grid-No.1 Voltage (Approx.) for plate current of			74-
100 μΑ		9	volts






Refer to chart at end of section.

6EC4A/EY500

Refer to chart at end of section. For replacement use type 6EH4A.

6EH4



BEAM TRIODE

6EH4A

Duodecar type used as a shunt regulator in the high-voltage power supply of color television receivers. Outlines section, 16G; requires duodecar 12-contact socket. For high-voltage and X-ray safety considerations, refer to page 93. This type is electrically identical with type 6EJ4A.



(ac/dc)

Heater Voltage

POWER PENTODE

SFU5

6EH5

25EH5, 50EH5


CARTE

Miniature type used in the audio output stage of radio and television receivers and in phonographs. Outlines section, 5D; requires miniature 7-contact socket. Types 25EH5 and 50EH5 are identical with type 6EH5 except for heater ratings.

25 E 13 5

Totale (ac/dc)	UEIIJ	43EH3	OVEHO	
Heater Current	6.3	25	50	volts
Heater-Cathode Voltage:	1.2	0.3	0.15	ampere
Peak value	±200 max	±200 max	±200 max	volts
Average value	100 max	100 max		
		100 max	100 max	volts
Direct Interelectrode Capacitances (Approx.):			
Grid No.1 to Plate			0.65	рF
Grid No.1 to Cathode, Heater, Grid No.2	2. and Grid No	1.3	17	pF
Plate to Cathode, Heater, Grid No.2, and	d Grid No 3		19	pF
	4 GII4 110.0		3	pr
Class A	Amplifier			
	-			
MAXIMUM RATINGS (Design-Maximum Val				
Plate Voltage			150	volts
Grid-No.2 (Screen-Grid) Voltage			130	
Plate Dissipation				volts
Crid No 9 Input			5.5	watts
Grid-No.2 Input			_ 2	watts
Bulb Temperature (At hottest point)			220	°C
TYPICAL OPERATION				
Plata Cumpler Voltage				_
Plate Supply Voltage			110	volts
Grid-No.2 Supply Voltage			115	volts
Cathode-Bias Resistor			62	ohms
Peak AF Grid-No.1 Voltage			3	volts

Zero-Signal Plate Current Maximum-Signal Plate Current		mA mA
Zero-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current	11.5	mA mA
Plate Resistance (Approx.)	11000	ohms µmhos
Transconductance Load Resistance	3000	ohms
Total Harmonic Distortion Maximum-Signal Power Output		per cent watts



MAXIMUM CIRCUIT VALUES

Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.1	megohm
For cathode-bias operation	0.5	megohm

Push-Pull Class AB, Audio-Frequency Power Amplifier

MAXIMUM RATINGS (Same as for Class A1 audio-frequency power amplifier) TYPICAL OPERATION (Values are for two tubes)

Plate Supply Voltage	140	volts
Grid-No.2 Supply Voltage	120	volts
Cathode-Bias Resistor	68	ohms
Peak AF Grid-No.1 Voltage	9.4	volts
Zero-Signal Plate Current	47	mA
Maximum-Signal Plate Current	51	mA
Zero-Signal Grid-No.2 Current	11	mA
	17.7	mA
Effective Load Resistance (Plate-to-plate)	6000	ohms
Total Harmonic Distortion	5	per cent
Maximum-Signal Power Output	28	wotte

maximum-Signal Fower Output	0.8	watts
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.1	megohm
For cathode-hiss operation	0.5	merchm


6EH7

Refer to chart at end of section. For replacement use type 6EH7/EF183.

6EH7/

SEMIREMOTE-CUTOFF **PENTODE**

Miniature types used as if-amplifier tubes in color and black-and-white television receivers. Outlines section, 6C; requires miniature 9-contact socket. Types 3EH7/XF183 and 4EH7/



9AQ LF183 are identical with type 6EH7/EF183 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage Direct Interelectrode Capacitances: Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Internal Shield Plate to Cathode, Heater, Grid No.2, Gri Internal Shield	Grid No.3.	4EH7/ LF183 4.4 0.45 ±150 max and	6EH7/ EF183 6.3 0.3 ±150 max 0.005 max	volts ampere volts pF pF
Class A, A	Amplifier			•
MAXIMUM RATINGS (Design-Center Values)	•			
, , , , , , , , , , , , , , , , , , , ,				• .
Plate Supply Voltage			550	volts
Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive	volue		250	volts
Grid-No.2 (Screen-Grid) Supply Voltage	value		0 550	volts volts
Grid-No.2 Voltage			250	volts
Cathode Current			20	mA
Plate Dissipation		, ,	2.5	watts
Grid-No.2 Input			0.65	watt
CHARACTERISTICS Plate Voltage Grid No.3 Grid-No.2 Voltage Grid-No.1 Voltage Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current		Connec	200 ted to cathode 90 2 0.5 12500 12 4.5	volts at socket volts volts megohm μmhos mA mA
TYPICAL OPERATION				
Plate Voltage 20	0 200	200	200	volts
Grid No.3	onnected to	cathode at	socket	
Grid-No.2 Supply Voltage 20	0 200	200	200	volts
Grid-No.2 Series Resistor 22000		22000	22000	ohms
Grid-No.1 Voltage ——19.		6.5	—2	volts
Transconductance 12: RMS Grid-No.1 Voltage, for	5 625	1250	12500	μ mhos
cross-modulation factor of 0.01 450	0 160	100	_	$_{ m mV}$
MAXIMUM CIRCUIT VALUE				
Grid-No.1-Circuit Resistance			1	
STATEST OF CHILD RESISTANCE			1	megohm

Refer to chart at end of section.


6EH8

Refer to chart at end of section.

6EJ4A

Refer to chart at end of section. For replacement use type 6EJ7/EF184.

6EJ7



SHARP-CUTOFF PENTODE

6EJ7/ EF184

3EJ7/XF184,

volts ampere

6E 17/

Miniature types used as if-amplifier tubes in color and black-and-white television receivers. Outlines section, 6C; requires miniature 9-contact socket. Types 3EJ7/XF184 and 4EJ7/LF184 are identical with type 6EJ7/EF184 except for heater ratings.

4E 17/

2 E I 7 /

	XF184	LF184	EF184	
Heater Voltage (ac/dc)	3.4	4.4	6.3	
Peak Heater-Cathode Voltage	0.6	0.45	0.3 +150 may	
reak neater-Cathode voltage	150 max	-100 max	-100 max	

Direct Interelectrode Capacitances: Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, a	nd	0.005 max	pF
Internal Shield Plate to Cathode, Heater, Grid No.2, Grid No.3, and		10	pF
Internal Shield		я	рF
Class A ₁ Amplifier			
MAXIMUM RATINGS (Design-Center Values)			
Plate Supply Voltage		550	volts
Plate Voltage		250	volts
Grid-No.2 (Screen-Grid) Supply Voltage		550	volts
Grid-No.2 Voltage		250	volts
Cathode Current		25	mA
Plate Dissipation		2.5	watts
Grid-No.2 Input		0.9	watt
CHARACTERISTICS			
Plate Voltage	190	200	volts
Grid No.3	Conne	cted to cathode	
Grid-No.2 Voltage	190	200	volts
	-2.35	2.5	volts
Plate Resistance (Approx.)	0.35	0.35	megohm
Transconductance	15000	15000	μ mhos
Plate Current	10	10	mA.
Grid-No.2 Current	4.1	4.1	mA
MAXIMUM CIRCUIT VALUE			
Grid-No.1-Circuit Resistance		1	megohm

6EL4 6EL4A Refer to chart at end of section. For replacement use type 6BK4C/6EL4A.

6EM5

BEAM POWER TUBE

Miniature type used as vertical-deflection amplifier in television receivers utilizing picture tubes having diagonal deflection angles of 110 degrees. Outlines section, 6G; requires miniature 9-contact socket. Type 8EM5 is identical with type 6EM5 except for heater ratings.



Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	6.3 0.8	8EM5 8.4 0.6 11	volts ampere seconds
Heater-Cathode Voltage: Peak value Average value =		±200 max 100 max	volts volts
Direct Interelectrode Capacitances: Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 Plate to Cathode, Heater, Grid No.2, and Grid No.3.		0.7 max 10 5.1	pF pF pF

Class A, Amplifier

CHARACTERISTICS			
Plate Voltage	60	250	volts
Grid-No.2 Voltage	250	250	volts
Grid-No.1 Voltage	0	—18	volts
Mu Factor, Grid No.1 to Grid No.2		8.7	
Plate Resistance	_	0.05	megohm
Transconductance		5100	μ mhos
Plate Current	180•	40	mA
Grid-No.2 Current	30∙	3	mA
Grid-No.1 Voltage (Approx.) for plate current of			_
0.2 mA	_	37	volts

 These values can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

megohms

Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system


	I or operation	020	of Italie Bybec
MAXIMUM RATINGS	(Design-Center	r Values)	


DC Plate Voltage Peak Positive-Pulse Plate Voltage# (Absolute Maximum) Grid-No.2 (Screen-Grid) Voltage Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage Peak Cathode Current Average Cathode Current Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point)	315 22004 285 250 210 60 10 1.5 250	volts volts volts volts mA mA watts watts
MAYIMUM CIDCUIT VALUE		

Grid-No.1-Circuit Resistance

Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).

Under no circumstances should this absolute value be exceeded.





2.2

Refer to chart at end of section. For replacement use type 6EM7/6EA7. 6EM7



6EM7/6EA7

DUAL TRIODE

Glass octal type used as combined vertical-deflection

amplifier and vertical-deflection oscillator in color and black-and-white television receivers. Outlines section, 13A; requires octal socket. For curve of average plate characteristics, Unit No.1, refer to type 6DR7 (Unit No.1). Types 10EM7, and 13EM7/15EA7 are identical with type 6EM7/6EA7 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	6EM7/6EA7 6.3 0.925 —	10EM7 9.7 0.6 11	13EM7/15E 13 0.45 11	volts ampere seconds
Peak value Average value			x ±200 ma x 100 ma	
Direct Interelectrode Capacitances (Approx.): Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater	4	No.1 Un 4.8 2.2 3.6	it No.2 10 7 1.8	pF pF pF

Class A. Amplifier


CHARACTERISTICS	Unit No.1	Unit No.2	4
Plate Voltage	250	150	volts
Grid Voltage	3	20	volts
Amplification Factor	64	5.4	
Plate Resistance (Approx.)	40000	750	ohms
Transconductance	1600	7200	umhos
Plate Current	1.4	50	m A
Plate Current, for plate voltage of 60 volts and			
zero grid voltage	_	95	mA
Plate Current, for grid voltage of -28 volts	_	10	mA
Grid_Voltage (Approx.):			
For plate current of 10 μA	5.5		volts
For plate current of 100 μA	-	-45	volts

Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values) DC Plate Voltage Peak Positive-Pulse Plate Voltage# Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation	Unit No.1 Oscillator 330 400 77 22 1.5	Unit No.2 Amplifier 330 1500 250 175 50	volts volts volts mA mA watts
MAXIMUM CIRCUIT VALUES Grid-Circuit Resistance: For grid-resistor-bias operation For cathode-bias operation	Unit No.1 2.2 2.2	Unit No.2	megohms

Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).



6EN4

SHARP-CUTOFF BEAM TRIODE

Glass octal type used as a shunt voltage-regulator tube in the high-voltage power supply of color television receivers. Outlines section, 21B; requires octal socket. Socket terminals 3, 4, and 8 should not be used as tie points. For high voltage and X-ray safety considerations, refer to page 93.



8NJ

Heater Current 0.2 amper	e
Peak Heater-Cathode Voltage —450° max volts	
Direct Interelectrode Capacitances (Approx.):	~
Grid to Plate	F
Plate to Cathode and Heater 2.6	Ē
Grid to Cathode and Heater 1	F

- * Series impedance should be used with the cathode to limit the cathode current under prolonged short-circuit conditions to 450 mA.
- ‡ Without external shield.

Shunt Voltage-Regulator Service

MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Voltage	30000	volts
Unregulated DC Supply Voltage	60000	volts
DC Grid Voltage	$-135 \\ -440$	volts mA
Peak Grid Voltage	-440 1.6	mA mA
Plate Dissipation	40	watts
tiate Dissipation	40	Watis
TYPICAL OPERATION		
Unregulated DC Supply Voltage	36000	volts
Equivalent Resistance of Unregulated Supply	11	megohms
Voltage Divider Values:		_
R ₁ (5 watts)	220	megohms
R ₂ (2 watts)	1	megohm
R ₃ (0.5 watt)	0.82	megohm
DC Reference Voltage Supply	200	volts ohms
Equivalent Resistance of Reference Voltage Effective Grid-Plate Transconductance	$\frac{1000}{200}$	μmhos
DC Plate Current for Load Current of 0 mA	1000	μ mnos μ A
DC Plate Current for Load Current of 1 mA	45	μA
Regulated DC Output Voltage for Load Current of 0 mA	25000	volts
Regulated DC Output Voltage for Load Current of 1 mA	24500	volts
Amplification Factor	2000	

MAXIMUM CIRCUIT VALUE

Grid-Circuit Resistance 3 megohms
■ For interval of 20 seconds maximum during equipment warm-up period.

	٩u	A D	٠.	CT	ED		'ICS	 ٨м	CE	1//	٠.		-	
ı	:н	Δн	ιа	t: I	ĿК	151	11:5	 ΔN		v	31 .	u		•

	Note	Min	Max	
Grid Voltage (1)	1	7		volts
Grid Voltage (2)	2		40	volts
Grid-Voltage Change	3		9	volts

Note 1: With dc plate voltage of 30000 volts and dc plate current of 1 mA.


Note 2: With dc plate voltage of 30000 volts and dc plate current of 0.1 mA.

Note 3: Difference between grid voltage (1) and grid voltage (2).

X-RADIATION CHARACTERISTIC

X-Radiation, Maximum:

Statistical value controlled on a lot sampling basis . . . 0.5 mR/hr Caution—Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.



6ER5

HIGH-MU TRIODE

Miniature type with frame grid used in vhf tuners of color and black-and-white television receivers. Outlines section 5C; requires miniature 7-contact socket. Type 3ER5 is identical to type 6ER5 except for heater ratings.



/FE

Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage	0.45	6.3 0.18	volts ampere volts
Direct Interelectrode Capacitances:	Unshielded	Shielded	
Grid to Plate	0.38	0.36	рF
Grid to Cathode, Heater, and Internal Shield	4.4	4.4	pF
Plate to Cathode, Heater, and Internal Shield	3	4	pF pF
Grid to Heater	0.28 max	0.28 max	þF
Plate to Cathode	0.24	0.2△	pF
Cathode to Grid	3.1	3.1△	pΓ
Heater to Cathode	2.5	2.54	pF
0.317241 4 3 -1-2-33 4 1 4 43 3			

- "With external shield connected to cathode except as noted.
- A With external shield connected to ground.

Class A. Amplifier

MAXIMUM RATINGS (Design-Center Values)		
Plate Voltage	250	volts
Grid Voltage, Negative-bias value	50	volts
Cathode Current	20	m A.
Plate Dissipation	2.2	watts
CHARACTERISTICS		
Plate Voltage	200	volta
Grid Voltage	1.2	volts
Amplification Factor	80	
Plate Resistance (Approx.)	8000	ohms
Transconductance	10500	μ mhos
Plate Current	10	· mA
Grid Voltage (Approx.) for transconductance of 500 µmhos	3.8	volts
Grid Voltage (Approx.) for transconductance of 100 μmhos	5.6	volts
MAXIMUM CIRCUIT VALUE		
Grid-Circuit Resistance	1	megohm

6ES5

Refer to chart at end of section.

6ES8

Refer to chart at end of section.

6ES8/ VARIABLE-MU TWIN TRIODE ECC189

Miniature type used as cascode-type amplifier in tuners of television receivers. Outlines section, 6B; requires miniature 9-contact socket.



Heater Voltage (ac/dc) Heater Current		6.3 0.365	volts ampere
Direct Interelectrode Capacitances:	Unshielded		dinperc
Grid to Plate (Each Unit)	1.9	1.9	рF
Plate to Cathode (Each Unit)	0.18	0.17	ρF
Heater to Cathode (Each Unit)	3	3₄	ÞF
Plate of Unit No.2 to Plate of Unit No.1		0.015 max	ρF
Plate of Unit No.2 to Grid of Unit No.1	0.003 max	0.003 max	ρF
Grid of Unit No.1 to Cathode of Unit No.2		0.002 max	ρF

[•] With external shield connected to cathode of unit under test except as noted.

A With external shield connected to ground.

Class A. Amplifier (Each Unit)

CHARACTERISTICS		
Plate Voltage 90 90	90	volts
Grid Voltage —1.2 —5 Plate Resistance (Approx.) 2500 —	9	volts ohms
Plate Resistance (Approx.) 2500 — Transconductance 12500 625	125	umhos
Plate Current 15 —		mA.
Cascode-Type Amplifier		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Supply Voltage with plate current of 0 mA	550	volts
Plate Voltage (Each unit)	130	volts
Grid Voltage, Negative-bias value (Each unit)	50	volts
Cathode Current (Each unit) Plate Dissipation (Each unit)	22 1.8	mA watts
Heater-Cathode Voltage:	1.0	Watts
Unit No.1:°		
RMS voltage between cathode and heater	50	volts
RMS voltage between cathode and heater	50	volts
DC voltage between cathode and heater.	130	volts
TYPICAL OPERATION in a cascode-type circuit■		
Supply Voltage	180	volts
Plate Current	15	mΑ
Transconductance	12500	μmhos
Noise Figure* Grid Voltage (Approx.) for transconductance of 125 µmhos	6.5 —9	dB volts
Input Voltage for cross-modulation factor of 0.01 and	3	VUILS
transconductance of 125 µmhos	500	mV
MAXIMUM CIRCUIT VALUE		
Grid-Circuit Resistance (Each unit)	1	megohm
Grounded-cathode input unit—pins 6, 7, and 8.		_
• Grounded-grid output unit—pins 1, 2, and 3,		


Grounded-grid output unit-pins 1, 2, and 3.

- Grounded-grid output unit pins 1, 2, and
- Cathode positive with respect to heater.
- With grid of output unit connected to a voltage divider.
- * Measured with tube operating in a television tuner.

Refer to chart at end of section.

6ET7

6EU7



9LS

HIGH-MU TWIN TRIODE

Miniature type used in high-gain, resistance-coupled, low-level audio-amplifier applications where low-hum and non-microphonic characteristics are important, such as microphone amplifiers and pre-amplifiers for phonographs. Outlines section, 6B; requires miniature 9-contact socket. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section.

Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage:		volts ampere
Peak value Average value	±200 max 100 max	volts volts
Direct Interelectrode Capacitances (Each Unit, Approx.): Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater	1.5 1.6 0.2	pF pF pF
Equivalent Noise and Hum Voltage (Referenced to Grid,	0.2	pr

Each Unit):


Average Value*

...

* Measured in "true rms" units under the following conditions: Heater volts (ac), 6.3; center-tap of heater transformer grounded; plate supply volts, 250; plate load resistor, 100000 ohms; cathode resistor, 2700 ohms; cathode bypass capacitor, 100 μF; grid resistor, 0 ohms; amplifier frequency range, 25 to 10000 Hz.

Class A. Amplifier (Each Unit)

MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage		330	volts
Grid Voltage: Negative-bias value		55	volts
Positive-bias value		ő	watts
Plate Dissipation	.	1.2	watts
CHARACTERISTICS			
Plate Voltage	100	250	volts
Grid Voltage	1	—2	volts
Amplification Factor	10 0	100	
Plate Resistance (Approx.)	80000	62500	ohms
Transconductance	1250	1600	μ mhos
Plate Current	0.5	1.2	mA



6EU8

Refer to chart at end of section.

7EW

6EV5

SHARP-CUTOFF TETRODE

Miniature type used as rf amplifier in vhf tuners of television receivers. Outlines section, 5C; requires miniature 7-contact socket.

Heater Voltage (ac/dc) Heater Current	6.3 0.2	volts ampere
Heater-Cathode Voltage:		-
Peak value	±100 max	volts volts
	XBIII OG	voits
Direct Interelectrode Capacitances:		
Grid No.1 to Plate	0.035 max	рF
Grid No.1 to Cathode, Heater, Grid No.2, and Internal Shield	4.5	pΓ
Plate to Cathode, Heater, Grid No.2, and Internal Shield	2.9	pF
. With external shield connected to anthodo		•

Class A. Amplifier

•• · · · · · · · · · · · · · · · · ·	
MAXIMUM RATINGS (Design-Maximum Values)	
Plate Voltage	275 volts
Grid-No.2 (Screen-Grid) Supply Voltage	180 volts
Grid-No.2 Voltage	See curve page 300
Grid-No.1 (Control-Grid) Voltage, Positive-bias value Cathode Current	0 volts
Plate Dissipation	20 mA 3.25 watts
Grid-No.2 Input;	o.zo watts
For grid-No.2 voltages up to 90 volts	0.2 watt
For grid-No.2 voltages between 90 and 180 volts	See curve page 300

CH	ΔR	ICTE	RIS	rics :


Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for transconductance of 100 \(\mu\)mhos	250 80 1 0.15 8800 11.5 0.9 4.5	volts volts volt megohm µmhos mA mA volts
MAXIMUM CIRCUIT VALUE Grid-No.1-Circuit Resistance	0.5	megohm

Refer to chart at end of section.

MAXIMUM RATINGS (Design-Maximum Values)

6EV7






SHARP-CUTOFF PENTODE

Miniature type used in the gain-controlled picture-if stages of vhf color and black-and-white television receivers operating at an interemediate frequency in the order of 40 MHz. Outlines section, 5C; requires miniature 7-contact socket. Type 5EW6 is identical with type 6EW6 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage: Peak value Average value	. 0.45 . 11 . ±200 n	6EW6 6.3 0.4 —	
			. VOILS
Direct Interelectrode Capacitances:	Unshielded		_
Grid No.1 to Plate	0.04 max	0.03 max	₽F
Grid No.1 to Cathode, Heater, Grid No.2,			_
Grid No.3, and Internal Shield	10	10	рF
Plate to Cathode, Heater, Grid No.2,			_
Grid No.3, and Internal Shield	2.4	3.4	рF
* With external shield connected to cathode.			

Class A₁ Amplifier

Plate Voltage	330	volts
Grid No.3 (Suppressor-Grid) Voltage, Positive value	0	volts
Grid-No.2 (Screen-Grid) Supply Voltage	330	volts
Grid-No.2 Voltage	See curve page	e 300
Grid-No.1 (Control-Grid) Voltage, Positive-bias value		volts
Plate Dissipation	3.1	watts
Grid-No.2 Input:		
For grid-No.2 voltages up to 165 volts		watt
For grid-No.2 voltages between 165 and 330 volts	See curve page	e 300



CHARAC	CTER	ITZII	CS
--------	------	-------	----

Plate Supply Voltage Grid No.3 Connec Grid-No.2 Supply Voltage	ted to authodo at acaleui
Cathode-Bias Resistor Plate Resistance (Approx.)	56 ohms
Plate Current	. 14000 μmhos
Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 20 \(\mu A\)	. 3.2 m.A

6EW7

10EW7, 15EW7

DUAL TRIODE

Miniature type used as combined vertical-deflection oscillator and vertical-deflector amplifier in television receivers. Outlines section, 6E, requires miniature 9-contact socket. For curve of average plate characteristics, Unit No.1, refer to type 6DE7 (Unit No.1). Types 10EW7 and 15EW7 are identical with type 6EW7 except for heater ratings.




9HF

	6EW7	10EW7	15EW7	
Heater Voltage (ac/dc)	6.3	9.7	14.8	volts
Heater Current	0.9	0.6	0.45	ampere
	<u> </u>	11	11	seconds
Heater-Cathode Voltage:				00001140
Peak value	±200 ma	x ±200 m	ax ±200	max volts
Average value	100 max	(100 m	ax 100	max volts
Direct Interelectrode Capacitances (Approx.):		No.1 U	it No.2	
Grid to Plate	. 4	.2	9	pF
Grid to Cathode and Heater	. 2	.2	7	ρĒ
Plate to Cathode and Heater	0	.4	1.2	ρF

Class A, Amplifier

CHARACTERISTICS	Unit No.1	Unit No.2	
Plate Voltage	250	150	volts
Grid Voltage	11	17.5	volts
Amplification Factor	17.5	6	
Plate Resistance (Approx.)	8750	800	ohms
Transconductance	2000	7500	μmbos
Plate Current	5.5	45	mA
Plate Current for plate voltage of 60 volts and zero			
grid voltage		95	mA
Plate Current for grid voltage of -25 volts		8	mA
Grid Voltage (Approx.) for plate current of 10 μA	20		volts
Grid Voltage (Approx.) for plate current of 100 μ A		40	volts




Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)	Unit No.1 Oscillator	Unit No.2 Amplifier	
DC Plate Voltage Peak Positive-Pulse Plate Voltage# Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation	330 400 77 22 1.5	330 1500 250 175 50	volts volts volts mA mA watts
MAXIMUM CIRCUIT VALUES Grid-Circuit Resistance: For cathode-bias operation For grid-resistor-bias operation	2.2 2.2	2.2 2.2	megohms megohms

Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).

6EX6	Refer to chart at end of section.
6EY6	Refer to chart at end of section.
6EZ5	Refer to chart at end of section.
6EZ8	Refer to chart at end of section.
6F4	Refer to chart at end of section.
6 F 5	Refer to chart at end of section.
6F5GT	Refer to chart at end of section.
6F6 6F6G 6F6GT	Refer to chart at end of section.
6F7	Refer to chart at end of section.
6F8G	Refer to chart at end of section.
6FA7	Refer to chart at end of section.



DUAL TRIODE

6FD7

Miniature type containing high-mu and low-mu triode units used as combined vertical-deflection oscillator and vertical-deflection amplifier in television receivers. Outlines section, 6E; requires miniature 9-contact socket. Type 13FD7 is identical with type 6FD7 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	6FD7 6.3 0.925	13FD7 13 0.45 11	volts ampere seconds
Peak value		±200 max 100 max	volts volts
Direct Interelectrode Capacitances (Approx.): Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater	Unit No.1 4.5 2.2 0.4	Unit No.2 10 6.5 0.2	pF pF pF

Class A, Amplifier

CHARACTERISTICS	Unit No.1	Uni	t No.2	
Plate Voltage	250	60	150	volts
Grid Voltage	—3	Ö	17.5	volts
Amplification Factor	64	_	6	
Plate Resistance (Approx.)	40000		800	ohms
Transconductance	1600		7500	μ mhos
Plate Current	1.5	95=	40	mA
Grid Voltage (Approx.):				
For plate current of 10 µA	5.5	_		volts
For plate current of 100 μA		-	—40	volts
Transconductance, For plate current of 1 mA			500	μ mhos
Plate Current, For grid voltage of -25 volts	_		6	mA

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)	Oscillator	Amplifier	
DC Plate Voltage	330	330	volts
Peak Positive-Pulse Plate Voltage#		1500	volts
Peak Negative-Pulse Grid Voltage	400	250	volts
Peak Cathode Current	70	175	mA
Average Cathode Current	20	50	mA
Plate Dissipation	1.5	10	watts
MAXIMUM CIRCUIT VALUES			
Grid-Circuit Resistance:			
For grid-resistor-bias or cathode-bias operation	2.2	2.2	megohms
#Pulse duration must not exceed 15% of a vertical s	canning cycle	(2.5 millised	onds).

6FE5

Refer to chart at end of section.

Unit No.1

Unit No.2

6FG6/EM84

Refer to chart at end of section.


5FG7

6FG7

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used as combined oscillator and mixer tube in vhf color and black-and-white television receivers. Outlines section, 6B; requires miniature 9-contact socket. Type 5FG7 is identical with type 6FG7 except for heater ratings.

. With external shield connected to ground.




6FG7

	OF G1	OT. CI.	
Heater Voltage (ac/dc)	4.7	6.3	volts
Heater Current	0.6	0.45	ampere
Heater Warm-up Time (Average)	11	11	seconds
Heater-Cathode Voltage:			
Peak value	±200 max	±200 max	volts
Average value	100 max	100 max	volts
	100	IOU MEX	10163
Direct Interelectrode Capacitances:			
Triode Unit:			
Grid to Plate	1.8	1.8	рF
Grid to Cathode, Pentode Grid No.3, and Heater	3	3	pF
Plate to Cathode, Pentode Grid No.3, and Heater	1.3	1.9	υF
Pentode Unit:			
Grid No.1 to Plate	0.02 max	0.01 max	рF
Grid No.1 to Cathode, Grid No.3, Grid No.2,	Old B III	OIVE IIIGA	PL
and Heater	5	5	рF
Plate to Cathode, Grid No.3, Grid No.2.	v	J.	pr
	0.4	0.4	. 171
and Heater	2.4	3.4	р <u>F</u>
Heater to Cathode, and Pentode Grid No.3	. 6	6●	\mathbf{pF}
 With external shield connected to cathode except as 	noted.		

Class A₁ Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Triode	Unit	Pentode U	nit .
Plate_Voltage	33	0	330	volts
Grid-No.2 (Screen-Grid) Supply Voltage		-	330	volts
Grid-No.2 Voltage		 See 	curve page	e 300
Grid-No.1 (Control-Grid) Voltage, Positive-bias value		0	0	volts
Plate Dissipation	2.	5	3	watts
Grid-No.2 Input:				
For grid-No.2 voltages up to 165 volts	–	- See	curve page	e 300
For grid-No.2 voltages between 165 and 330 vol	ts -	-	0.55	watt
CHARACTERISTICS	Triode Unit	Pen	tode Unit	
Plate Voltage	125	100	125	volts
Grid-No.2 Voltage	_	100	125	volts
Grid-No.1 Voltage	1	() —1	volts
Amplification Factor	43			
Plate Resistance (Approx.)	5700	_	180000	ohms
Transconductance	7500	7400	6000	μ mhos
Plate Current	13		- 11	· mA
Grid-No.2 Current		_	- 4	mA
Grid-No.1 Voltage (Approx.) for plate current				
of 30 "A	6.5	_	-7.5	volts



HIGH-MU TRIODE


6FH5

Miniature type used as an rf amplifier in vhf tuners of color and black-and-white television receivers. Outlines section, 5C; requires 7-contact socket. Type 2FH5 is identical to type 6FH5 except for heater ratings.

	2FH5	6FH5	
Heater Voltage (ac/dc)	2.35	6.3	volts
Heater Current		0.2	ampere
Heater Warm-up Time (Average)			seconds
Peak Heater-Cathode Voltage		nax ±100 r	nax volts
Direct Interelectrode Capacitances (Approx.): Ur	nshielded	Shielded•	
Grid to Plate	0.52	0.52	pF
Grid to Cathode, Heater, and Internal Shield	3.2	3.2	pF
Plate to Cathode, Heater, and Internal Shield	3.2	4	pF
· With external shield connected to Pin 1.			

Class A. Amplifier

MAXIMOM RATHING (Design-Maximum Values)		
Plate Voltage	150	volts
Grid Voltage, Positive-bias value	0	volts
Cathode Current	22	mA
Plate Dissipation	2.2	watts




2.0	1011 10001111	1022	
CHARACTERISTICS			_
Grid Voltage		. 135 . —1	volts volts
Plate Resistance (Approx	.)	. 5600	ohms
Transconductance	•)	. 9000	μ mhos
			4
Grid Voltage (Approx.) fo	or plate current of 100 μA	-5.5	mA volts
MAXIMUM CIRCUIT VALU			
	r cathode-bias operation	. 1	megohm
and one in the second to	cathode blab operation	•	ancgonini
		H,K_ (5)	G.
		····	€ ITR
/ELIO	MEDIUM-MU TRIODE—	₽τ ③ //	TATO GETR
6FH8	THREE-PLATE TETRODE	- (III + -	
		.@\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	77 %
	in complex-wave generator appli-	· cts///	PIATR
cations and in televis	sion receiver applications. Sharp-	. (1) —	1 000
cutoff tetrode unit ha	is pair of additional plates. Out-	PIBTR	P2TR
lines section, 6B; requi	ires 9-contact socket.	9K	P
Haster Voltage (sc/de)	· · · · · · · · · · · · · · · · · · ·	6.3	volts
Heater Current	·····	0.45	ampere
Direct Interelectrode Capa	citances:°		
Triode Unit:			_
Grid to Plate	Heater	1.4 2.6	pF pF
Plate to Cathode and	Teater Heater	ĩ	pF
Tetrode Unit:	- 0	0.06 ma	x pF
Grid No.1 to Flate No.	o.2	0.06 ma	x pr
Plate No.1B		4.5	pF
Plate No.2 to Cathode	, Heater, Grid No.2, Plate No.1A, and	1.4	
Tetrode Grid No.1 to Tr	riode Plateriode Plate	0.35 max	pF
		0.008 max	pF
* With external shield con	nected to cathode.		
	Class A, Amplifier		
CHARACTERISTICS	Triode Unit		
***************************************	Tilode Onic	100	volts
Grid Voltage	• • • • • • • • • • • • • • • • • • • •	—i	volt
Amplincation Factor	· · · · · · · · · · · · · · · · · · ·	40	
Transconductance (Approx.)	7400 5400	ohms µmhos
Plate Current		7.9	· mA
	r plate current of 100 μA	—7	volts
	Plates No.1A and No.1B Connected to C	athode at So	rket
MAXIMUM RATINGS (Desi	gn-Maximum Values)		_
Plate-No.2 Voltage		250 250	volts volts
Grid-No.1 Voltage		—2	volts
Plate-No.2 Resistance (Ap	prox.)	0.75	megohm
Transconductance, Grid No	oil to Plate No.2	4400 7.3	μmhos m.A.
Plate-No.2 Current			mA
Grid-No.2 Current		1.4	
Grid-No.2 Current	c.) for plate-No.2 current of 100 μA		volts
Grid-No.2 Current	c.) for plate-No.2 current of 100 μA	1.4	
Grid-No.2 Current Grid-No.2 Current Grid-No.1 Voltage (Approx	c.) for plate-No.2 current of 100 μA Complex-Wave Generator	1.4 7	
Grid-No.2 Current Grid-No.1 Voltage (Approx MAXIMUM RATINGS (Desi Plate Voltage	c.) for plate-No.2 current of 100 μA Complex-Wave Generator gn-Maximum Values) Triode Unit	1.4	
Grid-No.2 Current Grid-No.1 Voltage (Approx MAXIMUM RATINGS (Desi Plate Voltage	Complex-Wave Generator gn-Maximum Values) Triode Unit	1.4 7 Tetrode Unit	volts volts volts
Plate-No.2 Current Grid-No.2 Current Grid-No.1 Voltage (Approx MAXIMUM RATINGS (Desi Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage	Complex-Wave Generator gn-Maximum Values) Triode Unit 275	1.4 7 Tetrode Unit 200 200	volts volts volts volts
Plate-No.2 Current Grid-No.2 Current Grid-No.1 Voltage (Approx MAXIMUM RATINGS (Desi Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage Crid-No.2 (Sergen-Grid) S	Complex-Wave Generator gn-Maximum Values) Triode Unit 275	1.4 7 Tetrode Unit 	volts volts volts volts volts volts
Plate-No.2 Current Grid-No.2 Current Grid-No.1 Voltage (Approx MAXIMUM RATINGS (Desi Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage Crid-No.2 (Sergen-Grid) S	Complex-Wave Generator gn-Maximum Values) Triode Unit 275	1.4 7 Tetrode Unit 200 200 275	volts volts volts volts volts volts
Plate-No.2 Current Grid-No.2 Current Grid-No.1 Voltage (Approx MAXIMUM RATINGS (Desi Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage Crid-No.2 (Sergen-Grid) S	Complex-Wave Generator gn-Maximum Values) Triode Unit 275	1.4 7 Tetrode Unit 	volts volts volts volts volts volts volts
Plate-No.2 Current Grid-No.1 Voltage (Approx MAXIMUM RATINGS (Desi Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage Grid-No.2 (Screen-Grid) Si Grid-No.2 Voltage Grid-No.1 (Control-Grid) Negative-bias value Positive-bias value	C.) for plate-No.2 current of 100 μA Complex-Wave Generator gn-Maximum Values) Triode Unit	1.4 7 Tetrode Unit 200 200 275 275 ee curve page	volts volts volts volts volts volts volts volts
Plate-No.2 Current Grid-No.2 Current Grid-No.1 Voltage (Approx MAXIMUM RATINGS (Desi Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Grid-No.2 (Screen-Grid) S Grid-No.2 (Voltage Grid-No.1 (Control-Grid) Negative-bias value Positive-bias value Plate Dissipation	Complex-Wave Generator gn-Maximum Values) Triode Unit 275 — upply Voltage Voltage: -40 0 1.7	1.4 7 Tetrode Unit 200 200 275 275 275 ee curve page40 0	volts volts volts volts volts volts volts
Plate-No.2 Current Grid-No.2 Current Grid-No.2 Voltage (Approx MAXIMUM RATINGS (Desi Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Grid-No.2 (Screen-Grid) S Grid-No.2 (Screen-Grid) Grid-No.1 (Control-Grid) Negative-bias value Positive-bias value Plate Dissipation Plate-No.1A Dissipation Plate-No.1B Dissipation	C.) for plate-No.2 current of 100 µA Complex-Wave Generator gn-Maximum Values) Triode Unit	1.4 7 Tetrode Unit 200 200 275 275 275 20 curve page40 0 0.3 0.3	volts volts volts volts volts volts volts volts volts volts volts watts watt watt
Plate-No.2 Current Grid-No.1 Voltage (Approx MAXIMUM RATINGS (Desi Plate Voltage Plate-No.1A Voltage Plate-No.1B Voltage Plate-No.2 Voltage Grid-No.2 (Screen-Grid) Si Grid-No.2 Voltage Grid-No.1 (Control-Grid) Negative-bias value Positive-bias value	C.) for plate-No.2 current of 100 µA Complex-Wave Generator gn-Maximum Values) Triode Unit	1.4 7 Tetrode Unit 200 200 275 275 275 ee curve page40 0 0.3	volts watts

Grid-No.2 Input: For grid-No.2 voltages up to 137.5 volts 0.45 For grid-No.2 voltages between 137.5 and 275 volts - See curve page 3	watt
TYPICAL OPERATION WITH SEPARATE PLATE OPERATION Tetrode Unit	
Plates-No.1A, No.1B, and No.2 Voltage	volts
Grid-No.2 Voltage	volts
Grid-No.1 Voltage1	volts
Plate-No.1A Current 0.04	mA
Plate-No.1B Current 0.04	mA
Plate-No.2 Current	mA
Grid-No.2 Current 0.3	mA
Transconductance (Approx.);	
Grid No.1 to Plate No.1A	μmhos
Grid No.1 to Plate No.1B	μmhos
Grid No.1 to Plate No.2 2500	μmhos
MAXIMUM CIRCUIT VALUES Triode Unit Tetrode Unit	;
Grid-No.1-Circuit Resistance, for fixed-bias operation 0.5 0.5	megohm

Refer to chart at end of section.

6FJ7



DUAL TRIODE

6FM7

13FM7/15FM7

Duodecar type used as combined vertical-deflection oscillator and vertical-deflection amplifier in color and black-and-white television receivers. Triode unit No.1 is used as an oscillator, and triode unit No.2 is used as an amplifier. Outlines section, 8C; requires duodecar 12-contact socket. Type 13FM7/15FM7 is identical with type 6FM7 except for heater ratings.

6FM7

6.3	13	volts
1.05	0.45	amperes
	11	seconds
		Decoman
+200 mex	+200 may	volts
		volts
100 max	100 IIIax	AOICS
97		
Unit No.1	Unit No.2	
250	175	volts
		volts
		10.00
		ohms
		umhos
2200		
_ Z	40	mૃΑ
—5. 3	-	volts
	45	volts
		1.05

Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		Unit No.2 Amplifier	
DC Plate Voltage	350	500	volts
Peak Positive-Pulse Plate Voltage#	·	1500	volts
Peak Negative-Pulse Plate Voltage	400	250	volts
Peak Cathode Current		175	m A
Average Cathode Current		50	mA
Plate Dissipation†	1	10	watts
MAXIMUM CIRCUIT VALUES			
Grid-Circuit Resistance:			
For fixed-bias operation		_ 1	megohm
For cathode-bias operation	2.2	2.2	megohms

Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).

† A bias resistor or other means is required to protect the tube in absence of excitation.

6FM8

Refer to chart at end of section.

6FQ5A

Refer to chart at end of section. For replacement use type 6GK5/6FQ5A.

6FQ7


Refer to chart at end of section.

6FQ7/ 6CG7

MEDIUM-MU TWIN TRIODE

8FQ7/8CG7, 12FQ7

Miniature type used as combined vertical- and horizontal-deflection oscillator in color and black-and-white television receivers. Outlines section, 6E; requires miniature 9-contact socket. Types 8FQ7/8CG7 and 12FQ7 are identical with type 6FQ7/6CG7 except for heater ratings. For




12FQ7 are identical with type 6FQ7/6CG7 except for heater ratings. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section.

	6FQ7/6CG7	8FQ7/8CG7	12FQ7	
Heater Voltage (ac/dc)	6.3	8.4	12.6	volts
Heater Current	0.6	0.45	0.3	ampere
Heater Warm-up Time (Average)	11	_	_	seconds
Heater-Cathode Voltage:				
Peak value	$\pm 200 \text{ max}$	$\pm 200 \text{ max}$	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances (App	rox.):	Unit No.1	Unit No.2	
Grid to Plate		3.6	3.8	pF
Grid to Cathode and Heater		2.4	2.4	pF
Plate to Cathode and Heater		0.34	0.26	pF
Plate of Unit No.1 to Plate of Unit	No.2	1		\mathbf{pF}
MAXIMUM RATINGS (Design-Maximum	Values)			
Plate Voltage			330	volts
Grid Voltage, Positive-bias value			Õ	volts
Cathode Current			22	mA
Plate Dissipation:				
For either plate			4	watts
For both plates with both units opera-	ating		5.7	watts
CHARACTERISTICS				
Plate Voltage		90	250	volts
Grid Voltage		ŏŏ	—8	volts
Amplification Factor		2Ď	20	
Plate Resistance (Approx.)		6700	7700	ohms
Transconductance		3000	2600	μmhos
Plate Current		10	9	m A
Grid Voltage (Approx.) for plate current	t of 10 μ A	 7	18	volts
Plate Current for grid voltage of -12.5	volts	_	1.3	mA
MAXIMUM CIRCUIT VALUE				
Grid Circuit Resistance, for fixed-bias of	peration		1	megohm

Oscillator


MAXIMUM RATINGS (Design-Maximum Values)	Deflection	Horizontal- Deflection Oscillator	
DC Plate Voltage	330	330	volts
Peak Negative-Pulse Grid Voltage	440	660	volts
Peak Cathode Current	77	3 30	mA
Average Cathode Current	22	22	mA.
Plate Dissipation:			
For either plate	4	4	watts
For both plates with both units operating	5.7	5.7	watts
MAXIMUM CIRCUIT VALUES			
Grid-Circuit Resistance	2.2	2.2	megohms



BEAM HEXODE

6FS5

2F55, 3F55



7GA

Miniature type used as rf-amplifier tube in vhf television receivers. In this tube, grid No.1 is the control grid, grid No.2 is a focusing grid, grid No.3 is the screen grid, and grid No.4 is the suppressor grid. Grid No.2 is internally connected to the cathode and grid No.4 and aligned with grid No.3 Outlines section, 5C; requires miniature 7-contact socket. Types 2FS5 and 3FS5 are identical with type 6FS5 except for heater ratings.

2FS5 3FS5 6FS5

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	2.4 0.6 11	2.9 0.45 11	6.3 0.2	volts ampere seconds
Peak value	±200 max	±200 max	±200 max	volts volts
Direct Interelectrode Capacitances: Grid No.1 to Plate		Shielded U		рF
Grid No.1 to Cathode, Heater, Grid No.2,	Grid	4.8	4.8	
No.3, and Grid No.4 Plate to Cathode, Heater, Grid No.2, Grid and Grid No.4	No.3,	4.8	2.8	pF pF
With external shield connected to pin 7.	• • • • •	4	4.0	рr
Class A, A	mplifier			
MAXIMUM RATINGS (Design-Maximum Values)	,			
Plate Voltage			300	volts
Grid-No.3 (Screen-Grid) Voltage			150	volts
Grid-No.1 (Control-Grid) Voltage:			100	VOIG
Negative-bias value			50	volts
Positive-bias value			ő	volts
Cathode Current			20	mA
Plate Dissipation			3.25	watts
Grid-No.3 Input			0.15	watt
CHARACTERISTICS				
Flate Voltage			275	volts
Grid-No.3 Voltage			135	volts
Grid-No.1 Voltage			0.2	volt
Plate Resistance (Approx.)			0.24	megohm
Transconductance			10000	μ mhos
Plate Current			9	mA
Grid-No.3 Current			0.17	mA
Grid-No.1 Voltage (Approx.) for transconductan	ce of 100 µ	mnos	—5	volts
MAXIMUM CIRCUIT VALUE				
Grid-No.1-Circuit Resistance, for fixed-bias oper	ation		0.5	megohm
Refer to chart at end of sec	tion.		6FV6	5

6FV8 Refer to chart at end of section.

Refer to chart at end of section.

For replacement use type 6BR8A/6FV8A.

Refer to chart at end of section.

6FW8 Refer to chart at end of section.


6FY5/EC97 Refer to chart at end of section.

6FY7

DUAL TRIODE

11FY7, 15FY7

Duodecar type used as combined vertical-deflection oscillator and vertical-deflection amplifier in television receivers. Triode unit No.1 is used as an oscillator, and triode unit No.2 is used as an amplifier. Outlines section, 8D; requires duodecar 12-contact socket. Types 11FY7 and 15FY7 are identical with type 6FY7 except for heater ratings.



12EU 15FY7

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	6.3 1.05	11 0.6 11	14.7 0.45 11	volts amperes seconds
Heater-Cathode Voltage: Peak value Average value		±200 max 100 max		

6FV7

11FV7

Class A. Amplifier

CHARACTERISTICS	Unit No.1	Unit No.2	
Plate Voltage	250	150	volts
Grid Voltage	3	17.5	volts
Amplification Factor	65	6	
Plate Resistance (Approx.)	40500	920	ohms
Transconductance	1600	6500	μ mhos
Plate Current	1.4	35	m A
Grid Voltage (Approx.) for plate current of 30 μA	— 5.5		volts
Grid Voltage (Approx.) for plate current of 50 μA		36	volts
Plate Current (Approx.) for grid voltage of -25 volts		6	m A

Vertical-Deflection Oscillator and Amplifier For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)	Unit No.1 Oscillator	Unit No.2 Amplifier	
DC Plate Voltage	330	275	volts
Peak Positive-Pulse Plate Voltage#		2000	volts
Peak Negative-Pulse Plate Voltage	400	250	volts
Peak Cathode Current	70	175	mA
Average Cathode Current	20	50	m A
Plate Dissipation	1	7†	watts
MAXIMUM CIRCUIT VALUES			


† A bias resistor or other means is required to protect the tube in absence of excitation.

6G6G	Refer to chart at end of section.
6G11	Refer to chart at end of section.
6GB3A	For replacement use type 6BQ6GTB/6CU6.
6GB5	Refer to chart at end of section.

6GB5/ EL500

BEAM POWER TUBE

13GB5/XL500 18GB5/LL500 27GB5/PL500



MAXIMUM RATINGS (Design-Maximum Values)

Magnoval type used as horizontal-deflection amplifier in television receivers. Outlines section, 35B; requires neonoval 9-contact socket. Typical instantaneous characteristics (measured with recurrent waveform such that maximum ratings are not exceeded): plate volts, 75; grid-No.2 volts, 200; grid-No.1 volts, -10; plate mA, 440; grid-No.2 mA, 37. Types 13GB5/XL500, 18GB5/LL500 and 27GB5/PL500 are identical with type 6GB5/EL500 except for heater ratings.

Heater Voltage (ac/dc) Heater Current	13GB5/ XL500 13.3 0.6	18GB5/ LL500 18 0,45	27GB5/ PL500 27 0.3 a	volts mperes
Heater-Cathode Voltage: Peak value Average value		±250 max 125 max	±250 max 125 max	

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

maximom aximus (besign maximum values)		
DC Plate Voltage	275	volts
Peak Positive-Pulse Plate Voltage#	7700	volts
DC Grid-No.2 (Screen-Grid) Voltage	275	volts
Average Cathode Current	275	m A
Plate Dissipation	17	watts
Grid-No.2 Input=	5	watts
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
Without grid current	0.5	megohm
With grid current (horizontal-output service only)	2.2	megohms
# Pulse duration must not exceed 15% of a horizontal scanning cycle (10	microseco	onds).
A bias resistor or other means is required to protect the tube in	absence of	f excitation.
· Grid-No.2 input may reach 6 watts for plate-dissipation values below	11 watts.	

For replacement use type 6GW6/6DQ6B. 6GB6

For replacement use type 6GW6/6DQ6B. 6GB7



BEAM POWER TUBE

6GC5

Miniature type used in color and black-and-white television receiver applications and as output tube in audio-amplifier applications. Outlines section, 6E, requires miniature 9-contact socket.

Heater Voltage (ac/dc)	6.3	volts
Heater Current	1.2	amperes
Heater-Cathode Voltage:		
Peak value	$\pm 200~\mathrm{max}$	volts
Average value	100 max	volts
Direct Interelectrode Capacitances (Approx.):		
Grid No.1 to Plate	0.9	pF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3	18	ρF
Plate to Cathode. Heater, Grid No.2, and Grid No.3	7	pF

Class A₁ Amplifier

MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage		220	volts
Grid-No.2 (Screen-Grid) Voltage		140	volts
Plate Dissipation		12	watts
Grid-No.2 Input		1.4	watts
TYPICAL OPERATION AND CHARACTERISTICS			
Plate Voltage	110	200	volts
Grid-No.2 Voltage	110	125	volts
Grid-No.1 Voltage	7.5	120	volts
Cathode-Bias Resistor		180	ohms
Peak AF Grid-No.1 Voltage	7.5	8.5	volts
Zero-Signal Plate Current	49	46	m A
Maximum-Signal Plate Current	50	47	mA
Zero-Signal Grid-No.2 Current	4	2.2	mA
Maximum-Signal Grid-No.2 Current	10	8.5	mA
Plate Resistance (Approx.)	13000	28000	ohms
Transconductance	8000	8000	μmhos
Load Resistance	2000	4000	ohms
Total Harmonic Distortion	10	10	per cent
Maximum-Signal Power Output	2.1	3.8	watts
		0.0	
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
For fixed-bias operation		0.1	megohm
For cathode-bias operation		0.5	megohm
• • • • • • • • • • • • • • • • • • • •		***	

6GE5

BEAM POWER TUBE

12GE5, 17GE5

Duodecar type used as horizontal-deflection-amplifier tube in television receivers. Outlines section, 15A; requires duodecar 12-contact socket. Types 12GE5 and 17GE5 are identical with type 6GE5 except for heater ratings.



٠	7	
ı	4	J

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	6GE5 6.3 1.2	12 GE5 12.6 0.6 11	17GE5 16.8 0.45 11	volts amperes seconds
Heater-Cathode Voltage: Peak value Average value	±200 max 100 max		±200 max 100 max	volts volts

Class A. Amplifier

CHARACTERISTICS		ntode nection	Triode* Connection	
Plate Voltage	60	250	150	volts
Grid-No.2 (Screen-Grid) Voltage	150	150	150	volts
Grid-No.1 (Control-Grid) Voltage	0	-22.5	_	volts
Amplification Factor	_		4.4	
Plate Resistance (Approx.)	_	18000	_	ohms
Transconductance		7300	_	μmhos
Plate Current	345•	65		mA
Grid-No.2 Current	27•	1.8	_	mA
Grid-No.1 Voltage (Approx.) for plate current of 1 mA		42	_	volts

Grid No.2 tied to plate.

Horizontal-Deflection Amplifier

MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Supply Voltage	770	volts
Peak Positive-Pulse Plate Voltage#	6500	volts
Peak Negative-Pulse Plate Voltage	1500	volts
DC Grid-No.2 Voltage	220	volts
Peak Negative-Pulse Grid-No.1 Voltage	330	volts

[•] This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

DC Grid-No.1 Voltage	—55	volts
Peak Cathode Current	550	mĄ
Average Cathode Current	175	mA.
Plate Dissipation†	17.5	watts
Grid-No.2 Input	3.5	watts
Bulb Temperature (At hottest point)	200	°C
MAXIMUM CIRCUIT VALUE		
Grid-No.1 Circuit Resistance	1	megohm


#Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).
† A bias resistor or other means is required to protect the tube in absence of excitation.

Refer to chart at end of section.

6GF5

Refer to chart at end of section.

6GF7



DUAL TRIODE

6GF7A 10GF7A, 13GF7A

Novar types used as combined vertical-deflection oscillator and vertical-deflection amplifiers in color and black-and-white television receivers. Outlines section, 30A; requires novar 9-contact socket. For curves of average plate characteristics for Unit No.1 and Unit No.2, refer to types 6DR7 (Unit No.1) and 6EM7, respectively. Types 10GF7A and 13GF7A are identical with type 6GF7A except for heater ratings.

	6GF7.	A	10GF7	A	13GF7 <i>I</i>	A	
Heater Voltage (ac/dc)	6.3		9.7		13		volts
Heater Current	0.985		0.6		0.45		ampere
Heater Warm-up Time (Average)			11		11		seconds
Heater-Cathode Voltage:							
Peak value	±200	max	± 200	max	±200 r	nax	volts
Average value	100	max	100	max	100 n	nax	volts
Direct Interelectrode Capacitances (Approx.):		Unit	No.1	Unit	No.2		
Grid to Plate		4	.6		9		\mathbf{pF}
Grid to Cathode and Heater		2	.4	6.	5		pF
Plate to Cathode and Heater		0.3	26	1.	4		\mathbf{pF}

Class A. Amplifier

CHARACTERISTICS	Unit No.1	Unit No.2	
Plate Voltage	250	150	volts
Grid Voltage	—3	20	volts
Amplification Factor	64	5.4	
Plate Resistance (Approx.)	40000	750	ohms
Transconductance	1600	7200	μmhos
Grid Voltage (Approx.):			
For plate current of 10 μ A	5.5		volts
For plate current of 100 μ A		-45	volts
Plate Current	1.4	50	mA
For plate voltage of 60 volts and zero grid voltage	_	95	m A
For grid voltage of -28 volts		10	"mA

Vertical-Deflection Oscillator and Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Unit No.1 Oscillator	Unit No.2 Amplifier	
DC Plate Voltage	330	330	volts
Peak Positive-Pulse Plate Voltage			
(Absolute Maximum)#		1 500 •	volts
Peak Negative-Pulse Grid Voltage	400	250	volts
Peak Cathode Current	7 7	175	mA
Average Cathode Current	22	50	mA.
Plate Dissipation	1.5	11	watts

MAXIMUM CIRCUIT VALUES

Grid-Circuit Resistance:

For grid-resistor-bias or cathode-bias operation 2.2 2.2 megohms

· Under no circumstances should this absolute value be exceeded.

Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).

Refer to chart at end of section.

6GH8

6GH8A 5GH8A. 9GH8A

MEDIUM-MU TRIODE---SHARP-CUTOFF PENTODE

Miniature type used in multivibrator-type horizontal-G2PG deflection circuits and for agc-amplifier or sync-separator applications in color and black-and-white television receivers. Outlines section, 6B; requires miniature 9-contact socket. Types 5GH8A and 9GH8A are identical with type 6GH8A except for heater ratings.

9GH8A

TT . TT	O CA ALOIE	ACTION	Julion	
Heater Voltage (ac/dc)	4.7	6.3	9.45	volts
	0.6	0.45	0.3	ampere
Heater Warm-up Time (Average)			0.0	
neater warm-up lime (Average)	11	11		seconds
Heater-Cathode Voltage:				
Peak value	±200 max	±200 max	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances:		Unshielded		10100
		Cusmenten	Silielded	
Triode Unit:				
Grid to Plate		1.7	1.7	рF
Grid to Cathode, Heater, Pentode Grid N	10.9			
		3	0.0	- 70
Pentode Cathode, and Internal Shield		3	3.2	\mathbf{pF}
Plate to Cathode, Heater, Pentode Grid No.	.3.			
Pentode Cathode, and Internal Shield		1.4	1.9	pF
		4.7	1,0	
Heater_to Cathode		3	3	$_{\mathbf{pF}}$
Pentode Unit:				
Grid No.1 to Plate		0.02 max	0.01 max	рF
Grid No.1 to Cathode, Heater, Grid No.2.		oroz men	0101 11141	P.
		_	_	_
Grid No.3, and Internal Shield		5	5	рF
Plate to Cathode, Heater, Grid No.2, Grid	No.3.			
and Internal Shield	,	2.6	3.4	рF
Transaction of the control of the co	a1 . 1 1	2.0	0.4	
Heater to Cathode, Grid No.3, and Internal	Shield	3	3	рF

5CH8A


6CH8A


Class A. Amplifier

CHARACTERISTICS	Triode Unit	Pentode Unit	
Plate Voltage	125	125	volts
Grid-No.2 Voltage		125	volts
Grid-No.1 Voltage	1	<u>—1</u>	volts
Amplification Factor	46	-	
Plate Resistance (Approx.)	5 400	200000	ohms
Transconductance	8500	7500	μ mhos
Plate Current	13.5	12	mA
Grid-No.2 Current	_	4	m A
Grid-No.1 Voltage (Approx.) for plate current of			
10 μΑ	—8	8	volts

Horizontal-Deflection Oscillator

MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit	Pentode Unit	
Plate_Voltage	330	350	volts
Grid-No.2 (Screen-Grid) Voltage		330	volts
Grid-No.1 (Control-Grid) Voltage:			
Positive-bias value	0	0	volts
Peak negative value		175	volts
Peak Cathode Current		300	mA
Average Cathode Current		20	mA
Plate Dissipation	2.5	2.5	watts
Grid-No.2 Input	_	0.55	watt






MAXIMUM CIRCUIT VALUES

Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation

2.2 2.2 2.2 2.2

Refer to chart at end of section.

6GJ5



BEAM POWER TUBE

6GJ5A

megohms

megohms

12GJ5A, 17GJ5A

Novar type used in high-efficiency horizontal-deflection-amplifier circuits of television receivers. Outlines section, 18A; requires novar 9-contact socket. For curve of average characteristics see type 6GW6. Types 12GJ5A and 17GJ5A are identical with type 6GJ5A except for heater ratings.

T-1-3-

Heater Voltage (ac/dc)	6GJ5A 6.3 1.2	12GJ5A 12.6 0.6 11	17GJ5A 16.8 0.45 11	volts amperes seconds
Heater-Cathode Voltage:			••	becomes
Peak value		$\pm 200~\mathrm{max}$ $100~\mathrm{max}$		
Direct Interelectrode Capacitances (Approx.): Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Plate to Cathode, Heater, Grid No.2, and Gri	Grid No.3		0.26 15 6.5	pF pF pF

Class A. Amplifier

CHARACTERISTICS	Connection	Pentode (Connection	
Plate Voltage	150	60	250	volts
Grid-No.2 Voltage	150	150	150	volts
Grid-No.1 Voltage	22.5	0	-22.5	volts
Mu-Factor, Grid No.2 to Grid No.1	4.4		_	
Plate Resistance (Approx.)		_	15000	ohms
Transconductance	_	-	7100	μ mhos
Plate Current	_	390 •	70	mA
Grid-No.2 Current	-	32●	2.1	mA.
Grid-No.1 Voltage for plate current of 1 mA.	-	-	-42	volts

 \blacksquare This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Horizontal-Deflection Amplifier

KAM	MI	UM	RAT	INC	iS	(Design-Maximum	Values)
			_	-		• .	

DC Plate Supply Voltage	volts
Peak Positive-Pulse Plate Voltage#	volts
Peak Negative-Pulse Plate Voltage	 volts

DC Grid-No.2 Voltage DC Grid-No.1 Voltage Peak Negative-Pulse Grid-No.1 Voltage Peak Cathode Current Average Cathode Current Plate Dissipation•	55 330 550 175 17.5	volts volts volts mA mA watts
Grid-No.2 Input Bulb Temperature (at hottest point)	3.5 24 0	watts °C

MAXIMUM CIRCUIT VALUE

Grid-No.1-Circuit Resistance:

For grid-resistor-bias operation. megohm

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).
• A bias resistor or other means is required to protect the tube in absence of excitation.

6GJ7

Refer to chart at end of section.

6GJ7/

6GJ7/ **ECF801**

4GJ7/XCF801 5GJ7/LCF801 8GJ7/PCF801


Honton Voltage (as/de)

MEDIUM-MU TRIODE... SHARP-CUTOFF PENTODE

Miniature types used as combined oscillator and mixer tubes in color and black-and-white television receivers utilizing an intermediate frequency in the order of 40 MHZ. Outlines section, 6J; requires miniature 9contact socket. Types 4GJ7/XCF801, 5GJ7/LCF801, and 8GJ7/PCF801 are identical with type 6GJ7/ECF801 except for heater ratings.

4GJ7/

Grid-No.1 Voltage for grid-No.1 current of 0.3 µA ...



volts

megohm

8GJ7/

-1.3 max -1.3 max

Heater Voltage (ac/dc)	XCF801	LCF801	ECF801	PCF801	
Heater Current	4.1	5.6	6.3	8	volts
Peak Heater-Cathode	0.6	0.45	0.41	0.3	ampere
Voltage▲	生110 max	$\pm 110 \text{ max}$	±100 max	$\pm 110 \text{ max}$	volts
	Clas	ss A. Amplific	er		
MAXIMUM RATINGS (Desi	ign-Maximum	Values)	Triode Unit	Pentode Unit	
Plate-Supply Voltage			600	600	volts
DC Plate Voltage			140	275	volts
Grid-No.2 (Screen-Grid) Si	upply Voltage		-	600	volts
DC Grid-No.2 Voltage				275	volts
DC Grid-No.1 (Control-Gr:	id) Voltage .			50	volts
Cathode Current			22	20	mA
Plate Dissipation			1.8	2.4	watts
Grid-No.2 Input.		· · · · · · · · · · · · · · ·	_	0.55	watt
CHARACTERISTICS					
DC Plate Voltage			100	170	volts
DC Grid-No.2 Voltage			_	120	volts
DC Grid-No.1 Voltage			—3	-1.2	volts
Amplification Factor			20	55*	
Plate Resistance (Approx.)			0.35	megohm
Transconductance			9000	11000	μmhos
Plate Current			15	10	mA
Grid-No.2 Current				3	mA

5GJ7/

Grid-No.1-Circuit Resistance: For fixed-bias operation .

For cathode-bias operation 0.5 megohms ▲ The hum should be minimized in intercarrier applications by limiting the heater-cathode

oltage to 100 volts rms, and in AM receivers to 50 volts rms.

Grid No.2 to grid No.1, approximate value.

When control-grid bias is between —1.5 and —2 volts, screen-grid dissipation is limited to 0.50 watt. When this hias is greater than —2 volts, maximum screen-grid dissipation is 0.36 watt.

For replacement use type 6GK5/6FQ5A.

6GK5


6**GK**5/

HIGH-MU TRIODE

2GK5/2FQ5A




4GK5 6GK5/6FQ5A



Miniature type with frame grid used as grounded-cathode rf-amplifier tube in vhf tuners of color and blackand-white television receivers. Outlines section, 5C; requires miniature 7-contact socket. Types 2GK5/2FQ5A, 3GK5, and 4GK5 are identical with type 6GK5/6FQ5A except for heater ratings.

3GK5

Heater Warm-up Time (Average)	prox.):°	2.8 0.45 11 ±100 max	 6.3 0.18 	volts ampere seconds volts
Grid to Cathode, Heater, and Inter Plate to Cathode, Heater, and Inter Heater to Cathode "With external shield connected to cathode"	rnal Shield rnal Shield	l	 5 3.5 2.5	pF pF pF
• With external shield and internal shi		-		
	ss A. Am	plifier		
MAXIMUM RATINGS (Design-Maximum Plate Voltage			 200	volts
Grid Voltage: Negative-bias value Positive-bias value Average Cathode Current Plate Dissipation			 50 0 22 2.5	volts volts mA watts
CHARACTERISTICS Plate Voltage Grid Voltage Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Input Resistance Input Resistance Noise Figuret Grid Voltage (Approx.) for transconductance Grid Voltage (Approx.) for transconductance Grid Voltage (Approx.) for transconductance	ctance of	150 μmhos	 135 —1 78 5400 15000 11.5 275 11.2 4.7 —4.2 —2.5	volts volts ohms µmhos mA ohms pF dB volts volts



MAXIMUM CIRCUIT VALUE

• Measured at 200 MHz with heater volts = 6.3 and plate effectively grounded for rf voltages. \dagger For a neutralized triode amplifier at a frequency of 200 MHz with signal source impedance adjusted for minimum noise output.

6GK6

POWER PENTODE

6CK6

10CK6

10GK6, 16GK6

Miniature type used in the output stage of audio amplifying equipment and also in the video output stage of color and black-and-white television receivers. Outlines section, 6G; requires miniature 9-contact socket. Types 10GK6 and 16GK6 are identical with type 6GK6 except for heater ratings.



16CK6

174 37-14 (/de)	6.3	10GK6 10	16GK6	14
Heater Voltage (ac/dc)	0.76	0.45	16 0.3	volts
Heater Warm-up Time (Average)	0.70	11	11	ampere seconds
Peak Heater-Cathode Voltage		±100 max		volts
Direct Interelectrode Capacitances:	-100 max	_100 max	_100 max	Voits
Grid No.1 to Plate			0.14 max	pF
Grid No.1 to Cathode, Heater, Grid No.2,	Grid No.3,	and		-
Internal Shield	<i></i>		10	рF
Plate to Cathode, Heater, Grid No.2, Grid				
Internal Shield	 .	• • • • • • • •	7	рF
Class A, A	Amplifier			
MAXIMUM RATINGS (Design-Maximum Values	3			
Plate Supply Voltage			605	volts
Plate Voltage			330	volts
Grid-No.2 Supply Voltage			605	volts
Grid-No.2 (Screen-Grid) Voltage		· · · · · · · · · ·	330	volts
Grid-No.1 (Control-Grid) Voltage, Negative-bis	as value		100	volts
Cathode Current			65	mA
Plate Dissipation			13.2	watts
Grid-No.2 Input. Peak			4	watts
Grid-No.2 Input, Average			2	watts
CHARACTERISTICS AND TYPICAL OPERATION				
Plate Supply Voltage			250	volts
Grid-No.2 Supply Voltage			250	volts
Cathode-Bias Resistor			135	ohms
Mu-Factor, Grid No.2 to Grid No.1			19	
Plate Resistance (Approx.)			38000 11300	ohms µmhos
Peak AF Grid-No.1 Voltage			7.3	μmnos volts
Zero-Signal Plate Current			48	mA
Maximum-Signal Plate Current			50.6	mA
Zero-Signal Grid-No.2 Current			5.5	mA
Maximum-Signal Grid-No.2 Current			10	mA
Effective Load Resistance			5200	ohms
Total Harmonic Distortion			10	per cent
Maximum-Signal Power Output			5.7	watts

Push-Pull Class AB, and Class B Amplifier


MAXIMUM RATINGS (Same as for Class A1 Amplifier)

TYPICAL OPERATION (Values are for two tubes)

	Class	AB ₁	Cla	ass B	
Plate Voltage	250	300	250	300	volts
Grid-No.2 Voltage	250	300	250	300	volts
Grid-No.1 Voltage			-11.6	-14.7	volts
Cathode-Bias Resistor	130	130			ohms
Peak AF Grid-No.1-to-Grid-No.1 Voltage	22.4	28	22.4	28	volts
Zero-Signal Plate Current	62	72	20	15	m.A.
Maximum-Signal Plate Current	75	92	75	92	mA.
Zero-Signal Grid-No.2 Current	7	8	2.2	1.6	mA
Maximum-Signal Grid-No.2 Current	15	22	15	22	mA.
Effective Load Resistance (plate to plate)	8000	8000	8000	8000	ohms
Total Harmonic Distortion	3	4	3	4	per cent
Maximum-Signal Power Output	11	17	11	17	watts

MAXIMUM CIRCUIT VALUES





For replacement use type 6AU4GTA.

6GK17

Refer to chart at end of section.

6GL7

Refer to chart at end of section.

6GM5



7CM

SEMIREMOTE-CUTOFF PENTODE

6GM6

5GM6


Miniature type used in gain-controlled picture-if stages of color and black-and-white television receivers operating at intermediate frequencies in the order of 40 MHz. Outlines section, 5C; requires 7-contact socket. Type 5GM6 is identical with type 6GM6 except for heater ratings.

	5GM6	6GM6	
Heater Voltage (ac/dc)	5.6	6.3	volts
Heater Current	0.45	0.4	ampere
Heater Warm-up Time (Average)	11		seconds
Heater-Cathode Voltage:			
Peak value	±200 max	±200 max	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances:	Unshielded		
Grid No.1 to Plate	0.036 max	0.026 max	рF
Grid No.1 to Cathode, Heater, Grid No.2,	*****	****	-
Grid No.3, and Internal Shield	10	10	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3,			
and Internal Shield	2.4	3.4	рF
		011	P-
 With external shield connected to cathode. 			
01 4 4			
Class A, Amplifier			
MANUALISE DATINGS (Design Mayimum Values)			
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage		330	volts

riate voitake	000 40109
Grid-No.3 (Suppressor-Grid) Voltage, Positive value	0 volts
Grid-No.2 (Screen-Grid) Supply Voltage	330 volts
Grid-No.2 Voltage	See curve page 300
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0 volts
Plate Dissipation	3.1 watts
Grid-No.2 Input:	
For grid-No.2 voltages up to 165 volts	0.65 watt
For grid-No.2 voltages between 165 and 330 volts	See curve page 300

CHARACTERISTICS

Plate Supply Voltage Grid No.3 Co	nnected	to cathode	
Grid-No.2 Supply Voltage Cathode-Bias Resistor			volts ohms
Plate Resistance (Approx.)		0.2	megohm
Transconductance Plate Current		13000 14	μmhos mA
Grid-No.2 Current Grid-No.1 Voltage (Approx.) for transconductance of 60 µmh		3.4	mA volts




6GN8 8GN8/8EB8 10GN8

HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in color and black-and-white television receiver applications. Triode unit is used as sync-separator, sync-clipper, phase inverter, or sound-if amplifier. Pentode unit is used in output stage of video amplifier. Outlines section, 6E; requires miniature 9-contact socket. For direct interelectrode capaci-

MAYIMIM DATINGS (Decima Marriagem Values)



9DX

Wate Ja Trada - Trada - A. A. Tr. 44


tances, refer to type 6EB8; curve for average plate characteristics of triode unit is same as for type 6EB8. Types 8GN8/8EB8, and 10GN8 are identical with type 6GN8 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	6GN8 6.3 0.75	8GN8/8EB8 8 0.6 11	10GN8 10.5 0.45 11	volts ampere seconds
Peak value	±200 max 100 max	$\pm 200 \text{ max} $ 100 max	±200 max 100 max	

Class A, Amplifier

MAXIMUM KATINGS (Design-Maximum values)	Triode U	nit Per	itode Unit	
Plate Voltage	330		330	volts
Grid-No.2 (Screen-Grid) Supply Voltage	· · · · · · · · · · · · · · · · · · ·		330	volts
Grid-No.2 Voltage	-	See cu	rve page 300	
Grid-No.1 (Control-Grid) Voltage, Positive-bias va	lue 0		0	volt
Plate Dissipation	1		5	watts
Grid-No.2 Input:	_		•	
For grid-No.2 voltages up to 165 volts			1.1	watts
For grid-No.2 voltages between 165 and 330 vo		See cu	rve page 300	************
CHARACTERISTICS	Triode Unit	Pent	tode Unit	
Plate Supply Voltage	250	60	200	volts
Grid-No.2 Supply Voltage		150	150	volts
Grid-No.1 Voltage	—2	Õ		volts
Cathode-Bias Resistor		_	100	ohms
Amplification Factor	100	_	100	Onns
Dista Desistance (Assessed)			40000	
Plate Resistance (Approx.)	37000		60000	ohms

	Triode Unit	Pent	ode Unit	
Transconductance	2700	—	11500	μmhos
Plate Current	2	55•	25	mA.
Grid-No.2 Current		18•	5.5	mA
Grid Voltage (Approx.) for plate current of				
20 μΑ	—5			volts
Grid-No.1 Voltage (Approx.) for plate current				
of 100 μA			-10	volts
•				
MAXIMUM CIRCUIT VALUES				
Grid-No.1-Circuit Resistance:				
For fixed-bias operation	0.5	0.5	25	megohm
For cathode-bias operation			ĭ	megohm
				-
• This value can be measured by a method involving	a recurrent	waver	orm sucn	tnat tne
maximum ratings of the tube will not be exceeded.				



Refer to chart at end of section.

6GQ7



9GF

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6GS7

5GS7, 7GS7

Miniature type used as a frequency changer in vhf television tuners. Outlines section, 6B; requires 9-contact socket. Types 5GS7 and 7GS7 are identical with type 6GS7 except for heater ratings. Heater: volts, 7.6; ampere, 0.3; maximum heater-cathode volts, ±100 peak, 100 average.

Heater Voltage	5.4	6.3	7.6	volts
Heater Current	0.45	0.375	0.3	ampere
Heater-Cathode Voltage:				=
Peak value	$\pm 200 \text{ max}$	$\pm 200 \text{ max}$	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	100 max	volts
Class	A. Amplifi	er		
MAXIMUM RATINGS (Design-Center Valu	es)	Triode Unit	Pentode Unit	
Plate Voltage		125	250	volts
Grid-No.2 (Screen-Grid) Voltage			150	volts
Plate Dissipation		1.5	2	watts
Grid-No.2 Input			0.5	watt
Cathode Current		15	18	mA
CHARACTERISTICS				
Plate Voltage		100	170	volts
Grid-No.2 Voltage			150	volts
Grid-No.1 (Control-Grid) Voltage		3	-1.2	volts
Plate Current		14	10	mA
Grid-No.2 Current		_	3.3	mA
Transconductance		5500	12000	μmhos
Plate Resistance			0.35 min	megohm
Amplification Factor		17		

5**GS**7

MAXIMUM CIRCUIT VALUES				
Grid-No.1-Circuit Resistance Grid-No.1-Circuit Resistance:		0.5	_	megohm
For fixed-bias operation For cathode-bias operation		_	$0.25 \\ 0.5$	megohm megohm
	it as Frequency	Changer		
CHARACTERISTICS				
Plate Voltage			190	volts
Grid-No.2 Supply Voltage			190	volts
Oscillator Voltage Grid-No.2 Circuit Resistance			$\frac{2.3}{0.018}$	volts (rms) megohm
Grid-No.1 Circuit Resistance			0.018	megohm
Plate Current			8.5	mA
Grid-No.2 Current			2.7	mA
Grid-No.1 Current			30	$\mu \mathbf{A}$
Plate Resistance Conversion Transconductance	· · · · · · · · · · · · · · · · · · ·		0.6 4500	megohm μmhos
	Unit as Oscilla	itor		
CHARACTERISTICS				
Plate Supply Voltage			190	volts
Plate Circuit Resistance			8200	ohms
Grid Circuit Resistance			10000	ohms
Oscillator Voltage			4.5	volts(rms)
Plate Current Transconductance			12	mA.
Transconductance			3500	μmhos
6GT5	Refer to chart	at end of	section.	

17GT5A

BEAM POWER TUBE

Novar type used as horizontal-deflection amplifier in television receivers. Outlines section, 31A; requires novar 9-contact socket. For curve of average characteristics, refer to type 6GW6. Type 17GT5A is identical with type 6GT5A except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	6.3 1.2	17GT5A 16.8 0.45 11	volts ampere seconds
Heater-Cathode Voltage:			
Peak value	±200 max	±200 max	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances (Approx.):			
Grid No.1 to Plate		0.26	рF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid N		15	pF pF
Plate to Cathode, Heater, Grid No.2, and Grid No.3		6.5	pF

Class A. Amplifier

CHARACTERISTICS	Triode Connection		tode nection	
Plate Voltage	150	60	250	volts
Grid-No.2 (Screen-Grid) Voltage	150	150	150	volts
Grid-No.1 (Control-Grid) Voltage	22.5	0	-22.5	volts
Mu Factor, Grid No.2 to Grid No.1	4.4			
Plate Resistance (Approx.)	_		15000	ohms
Transconductance	_		7100	μ mhos
Plate Current		390*	70	m A
Grid-No.2 Current		32*	2.1	mA
Grid-No.1 Voltage (Approx.) for plate current				
of 1 mA			-42	volts

This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system


MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Supply Voltage Peak Positive-Pulse Plate Voltage#	770 6500	volts volts

Peak Negative-Pulse Plate Voltage DC Grid-No.2 Voltage DC Grid-No.1 Voltage Peak Negative-Pulse Grid-No.1 Voltage Peak Cathode Current Average Cathode Current Plate Dissipation* Grid-No.2 Input	220 55 330 550 175 17.5 3.5	volts volts volts volts mA mA watts
Bulb Temperature (At hottest point)		"Lig

MAXIMUM CIRCUIT VALUE

Refer to chart at end of section.

6GU5



MEDIUM-MU TWIN TRIODE

6GU7

8GU7

Miniature type used in the matrixing circuits of color and black-and-white television receivers and in phaseinverter, multivibrator, and general-purpose amplifier applications. Outlines section, 6E; requires miniature 9-contact socket. Type 8GU7 is identical with type 6GU7 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	6GU7 6.3 0.6 11	8GU7 8.4 0.45 11	volts ampere seconds
Peak value Average value Direct Interelectrode Capacitances (Approx.):	±200 max 100 max Unit No.1	±200 max 100 max Unit No.2	volts volts
Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater	3 3.4 0.44	3 3.6 0.34	pF pF pF
Plate of Unit No.1 to Plate of Unit No.2 Class A ₁ Amplifier			рF
MAXIMUM RATINGS (Design-Maximum Values)			

Plate voltage	33 U	voits
Grid Voltage, Positive-bias value	0	volts
Plate Dissipation	3	watts
CHARACTERISTICS		
Plate Voltage	250	volts
Grid Voltage		volts
Amplification Factor	17	
Plate Resistance (Approx.)	5500	ohms
Transconductance	3100	umhos





Plate Current Grid Voltage (Approx.) for plate current of 50 µA Plate Current for grid voltage of -14 volts	23	mA volts mA
MAXIMUM CIRCUIT VALUE Grid-Circuit Resistance, for fixed-bias operation	1	megohm

6GV5

BEAM POWER TUBE

Duodecar type used as horizontal-deflection amplifier in television receivers. Outlines section, 39A; requires duodecar 12-contact socket. Type 17GV5 is identical with type 6GV5 except for heater ratings.



Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	6.3 1.2	16.8 0.45 11	volts amperes seconds
Peuk value	$\pm 200~\mathrm{max}$ $100~\mathrm{max}$	±200 max	volts
Average value		100 max	volts

Class A. Amplifier

CHARACTERISTICS	Pentode Connection			Triode* Connection	
Plate Voltage	5000	60	250	150	volts
Grid-No.2 (Screen-Grid) Voltage	150	150	150	150	volts
Grid-No.1 (Control-Grid) Voltage		0	-22.5	-22.5	volts
Plate Resistance (Approx.)	_	_	18000		ohms
Transconductance		_	7300		μmhos
Amplification Factor				4.4	
Plate Current	_	345■	65		mA
Grid-No.2 Current		27•	1.8		mA
Grid-No.1 Voltage (Approx.) for plate current					
of 1 mA	100		-42		volts

^{*} Grid No.2 tied to plate.

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system


MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Supply Voltage	770	voits
Peak Positive-Pulse Plate Voltage#	6500	volts
Peak Negative-Pulse Plate Voltage	1500	volts
DC Grid-No.2 Voltage	220	volts
Peak Negative-Pulse Grid-No.1 Voltage	330	volts
DC Grid-No.1 Voltage	—55	volts
Peak Cathode Current	550	mA
Average Cathode Current	175	mA.
Plate Dissipation†	17.5	watts
Grid-No.2 Input	3.5	watts
Bulb Temperature (At hottest point)	220	$^{\circ}\mathrm{C}$

MAXIMUM CIRCUIT VALUE Grid-No.1-Circuit Resistance

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). † A bias resistor or other means is required to protect the tube in absence of excitation.

Refer to chart at end of section.

[•] This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.



HIGH-MU TRIODE-**POWER PENTODE**

6**GV**8/ ECL85 18GV8/PCL85

19CVe/

9LY

Miniature type used for sync-amplifier and video-output applications in television receivers. Outlines sec-

10GV8/

tion, 6G; requires miniature 9-contact socket. Types 9GV8/XCL85, 10GV8/ LCL85, and 18GV8/PCL85 are identical with type 6GV8/ECL85 except for heater ratings. 9GV8/

6GV8/

Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode	ECL85 6.3 0.9	XCL85 9.5 0.6	LCL85 11.6 0.45		PCL85 18 0.3	volts ampere
Voltage	±220 max	±200 max	±200 m	ax	±200 max	volts
	Clas	s A, Amplifie	r			
MAXIMUM RATINGS (Abso	olute-Maximu	m Values)	Triode Unit	:	Pentode Unit	
Plate Supply Voltage Peak Plate Voltage DC Plate Voltage			550 250		550 2000 250	volts volts volts
Grid-No.2 (Screen-Grid) S Grid-No.2 Voltage Peak Cathode Current*	Supply Voltag	;e	200		550 250	volts volts mA
Average Cathode Current Plate Dissipation Grid-No.2 Input			15 0.5		75 7 2	mA watts watts
CHARACTERISTICS						
Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage Amplification Factor			0.8	50 170 —1	65 170 210 170 —1 —15	volts volts volts
Mu-Factor, Grid No.1 to Plate Resistance (Approx. Transcenductance Plate Current Grid-No.2 Current	Grid No.2		. 7600 . 6500 . 5	200• 40•		ohms µmhos mA mA
MAXIMUM CIRCUIT VALU Grid-No.1-Circuit Resistand For fixed-bias operati For cathode-bias operati	e: on ation		3.3		1 2.2	megohm megohms


Maximum pulse duration 5 per cent of a cycle with a maximum of 1 millisecond.

■ Maximum pulse duration 200 microseconds .If a larger flyback is required, this value may be reduced to 100 mA with a maximum pulse duration of 400 microseconds.

This value can be measured by a method involving a recurrent waveform such that the maximum tube ratings will not be exceeded.

Refer to chart at end of section. For replacement use type 6GW6/6DQ6B.

6**GW**6



6AM

BEAM POWER TUBE

6GW6/ 6DQ6B

12GW6/12DO6B 17GW6/17DQ6B

Glass octal type used as horizontal-deflection amplifier in high-efficiency deflection circuits of television receivers. Outlines section, 20A; requires octal socket. Types 12GW6/12DQ6B and 17GW6/17DQ6B are identical with type 6GW6/6DQ6B except for heater ratings.

	6GW6/ 6DQ6B	12GW6/ 12DQ6B	17GW6/ 17DQ6B	
Heater Voltage (ac/dc)	6.3	12.6	16.8	volts
Heater Current	1.2	0.6	0.45	amperes
Heater Warm-up Time (Average)	~-	11	11	seconds
Heater-Cathode Voltage:				
Peak value		±200 max		volts
Average value	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances (Approx.):				
Grid No.1 to Plate			0.5	рF
Grid No.1 to Cathode, Heater, Grid No.2, and			17	pF
Plate to Cathode, Heater, Grid No.2, and Gri	id No.3		7	рF

Class A. Amplifier


CHARACTERISTICS	Triode Connection	Pento	de Connection	
Plate Voltage	150	60	250	volts
Grid-No.2 Voltage	150	150	150	volts
Grid-No.1 Voltage	22.5	0	22.5	volts
Mu-Factor, Grid No.2 to Grid No.1	4.4			
Plate Resistance (Approx.)			15000	ohms
Transconductance			7100	μ mhos
Plate Current		390¢	70	mA
Grid-No.2 Current	_	32°	2.1	mA
Grid-No.1 Voltage (Approx.) for plate current of				
1 mA			42	volts

^a This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values) DC Plate Supply Voltage 770 volts Peak Positive-Pulse Plate Voltage Peak Negative-Pulse Plate Voltage Voltage# 6500 volts 1500 volts DC Grid-No.2 (Screen-Grid) Voltage DC Grid-No.1 (Control-Grid) Voltage 220 volts -55 volts 330 Peak Negative-Pulse Grid-No.1 Voltage Peak Cathode Current volts




Average Cathode Current	175	mA
Plate Dissipation.	17.5	watts
Grid-No.2 Input	3.5	watts
Bulb Temperature (At hottest point)	240	°C

MAXIMUM CIRCUIT VALUES

Grid-No.1-Circuit Resistance, for grid-resistor-bias operation 1 megohm

[#] Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

• A bias resistor or other means is required to protect the tube in absence of excitation.



HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

6GW8/ ECL86


Miniature type used in preamplifier and audio output stages of audio equipment and television receivers. Outlines section, 6G; requires miniature 9-contact socket. Heater: volts (ac/dc), 6.3; amperes, 0.7; maximum heater-cathode volts, 100 peak.

Class A. Amplifier

MAXIMUM RATINGS (Design-Center Values)	Triode Unit	Pentode Unit	
Plate Supply Voltage	550	550	volts
Plate Voltage	300	300	volts
Grid-No.2 (Screen-Grid) Supply Voltage	_	550	volts
Grid-No.2 Voltage	_	300	volts
Grid-No.1 (Control-Grid) Voltage, Negative-bias value	1.3	1.3	volts
Cathode Current	4	55	mA
Plate Dissipation	0.5	9	watts
Grid-No.2 Input	_	1.5	watts
CHARACTERISTICS			
Plate Voltage	250	250	volts
Grid-No.2 Voltage	_	250	volts
Grid-No.1 Voltage	1.9	—7	volts
Amplification Factor	100	21#	
Plate Resistance (Approx.)	_	45000	ohms
Transconductance	1600	10000	μmhos
Plate Current	1.2	36	mA
Grid-No.2 Current	_	6	mA
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance, for fixed-bias operation	1	0.5	megohm
* Grid No.2 to grid No.1.	_		-

Refer to chart at end of section. For replacement use type 6GY6/6GX6.

6GX6



MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6GX7

Miniature type used as combined oscillator-mixer tube in vhf tuner circuits of color and black-and-white television receivers. Outlines section, 6B; requires miniature 9-contact socket.

Heater Voltage (ac/dc) Heater Current	6.3 0.4	volts ampere
Heater-Cathode Voltage:	0.4	umpere
Peak value	±200 max	volts
Average value	100 max	volts
Direct Interelectrode Capacitances:**		
Triode Unit:		
Grid to Plate	1.2	pF
Grid to Cathode, Heater, Pentode Cathode, Grid No.3,		
and Internal Shield	2.3	υF
Plate to Cathode, Heater, Pentode Cathode, Grid No.3,		
and Internal Shield	1.9	pF
Pentode Unit:	1.0	PI
	0.005	рF
Grid No.1 to Plate	0.000	l) L
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3,		
and Internal Shield	5.4	pF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and		
Internal Shield	3.3	рF
Grid No.1 to Grid No.2	1.6	pF
** With external shield connected to cathode.		

Triode Unit Pentode Unit

0.25

0.5

0.5

MAXIMUM RATINGS (Design-Maximum Values)		Triode U	nit Pe	ntode Un	it	4
Plate Voltage		275		275		volts
Grid-No.2 (Screen-Grid) Supply Voltage				275		volts
Grid-No.2 Voltage		•	See cu	rve page	300)
Grid-No.1 (Control-Grid) Voltage:				- 0-		
Positive-bias value		0		0		
Negative-bias value		40		40		volts
Cathode Current		20		20		mA
Plate Dissipation		1.5		2.2		watts
Grid-No.2 Input:						
For grid-No.2 voltages up to 137.5 volts		_	().45		watts
For grid-No.2 voltages between 137.5 and						
275 volts			See cu	rve page	300)
CHARACTERISTICS	Triode	Unit	Per	ıtode Un	it	
Plate Voltage	100	125	12	12	5	volts
Grid-No.2 Voltage		120	9			volts
Grid-No.1 Voltage		-1	-			volt
Grid-No.1-Circuit Resistance	0.1		0.			megohm
Amplification Factor	40		· · ·			megonini
Plate Resistance	-	4700	_			ohms
	700	8500	13000			μmhos
	12.5	13	8.		8	mA
Grid-No.2 Current	14.0		2.			mA
Grid-No.1 Voltage for plate current				. <u>.</u>	.0	ша
of 20 µA	6		2.	5 -		volts
MAXIMUM CIRCUIT VALUES						


6GY5 16GY5, 21GY5

Grid-No.1-Circuit Resistance:

BEAM POWER TUBE

Duodecar type used as horizontal-deflection amplifier in television receivers. Outlines section, 39A; requires duodecar 12-contact socket. Types 16GY5 and 21GY5 are identical with type 6GY5 except for heater ratings.

For fixed-bias operation
For cathode-bias operation



megohm

megohm

			1201	•
<u> </u>	6GY5	16GY5	21GY5	
Heater Voltage (ac/dc)	6.3	15.8	21	volts
Heater Current	1.5	0.6	0.45	amperes
Heater Warm-up Time (Average)		11	11	seconds
Heater-Cathode Voltage:		**		acconds
Peak value	±200 max	±200 max	±200 ma	x volts
Average value	100 max		100 ma	

Class A, Amplifier

CHARACTERISTICS	Pento	de Conne	ction	Triode† Connection	
Plate Voltage	5000	60	130	130	volts
Grid-No.2 (Screen-Grid) Voltage	130	130	130	130	volts
Grid-No.1 (Control-Grid) Voltage		0	20	20	volts
Amplification Factor			_	4.7	
Plate Resistance (Approx.)	_	_	11000	_	ohms
Transconductance		_	9100		μmhos
Plate Current	_	410**	50	-	mA
Grid-No.2 Current		24**	1.75	-	mA
Grid-No.1 Voltage (Approx.) for plate current of 1 μ A	66		33	_	volts

** This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

† Grid No.2 tied to plate.

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

DC.	Plate Supply	Voltage	2200000		770	volts
Peak	Positive-Pulse	Plate	Voltage#	***************************************	6500	volts

volts


volts

volts

ampere seconds

Peak Negative-Pulse Plate Voltage	1500	volts
DC Grid-No.1 Voltage	220 —55	volts volts
1 Car Nekalive-Filise Grid-No. I Voltage	330	volts
Peak Cathode Current Average Cathode Current	800 230	mA mA
Plate Dissipation†† Grid-No.2 Input	18 3.5	watts
Bulb Temperature (At hottest point)	220	watts °C

MAXIMUM CIRCUIT VALUE





7EN Heater Voltage (ac/dc)

Average value

Miniature type used in gated-agc-amplifier circuits and as a noise-inverter tube in color and black-and-white television receivers. Tube has two independent control grids. Outlines section, 5C; requires miniature 7-contact socket.

6.3

11 ±200 max

100 max

0.45

Average value	100 max	volts
Direct Interelectrode Capacitances:	0.000	17
Grid No.1 to Plate	0.026	\mathbf{pF}
Internal Shield	8	υF
Grid No.1 to Grid No.3	0.12	pF
Grid No.3 to Plate	1.6	рF
Grid No.3 to Cathode, Heater, Plate, Grid No.1, Grid No.2.		
and Internal Shield	6.5	рF
Class A, Amplifier		
CHARACTERISTICS		
Plate Supply Voltage	150	volts
Grid-No.3 Supply Voltage	. 0	volts
Grid-No.2 Supply Voltage	100	volts
Grid-No.1 Supply Voltage	0	volts ohms
Cathode-Bias Resistor Plate Resistance (Approx.)	180 0.14	onms megohm
Transconductance, Grid No.1 to Plate	3700	megonm μ mh os
Transconductance, Grid No.3 to Plate	750	μmhos
Plate Current	3.7	m A
Grid-No.2 Current	3	mA
Grid-No.3 Supply Voltage (Approx.) for plate current of 20 µA	7	volts
Grid-No.1 Supply Voltage (Approx.) for plate current of 20 μA .	-4.5	v ol t s
Gated AGC Amplifier and Noise Inverter		
For operation in a 525-line, 30-frame system		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	300	volts
Peak Positive-Pulse Plate Voltage#	600	volts
Grid-No.3 (Control-Grid) Voltage:		
Negative-bias value	100	volts
Positive-bias value	.0	volts
Grid-No.2 (Screen-Grid) Supply Voltage	300	volts
Grid-No.2 Voltage	See curve	page 300
Grid-No.1 (Control-Grid) Voltage: Negative-bjas value	50	volts
Positive-bias value	0	volts
Plate Dissipation	1.7	watts
Grid-No.2 Input:		
For grid-No.2 voltages up to 150 volts	1	watt
For grid-No.2 voltages between 150 and 300 volts	See curve	page 300

Heater Current
Heater Warm-up Time (Average)
Heater-Cathode Voltage:

Screen-Grid (Grid-No. 2) Input Rating Chart




Fig. 134—Grid-No.2 input rating curve.

For certain voltage amplifier types, as listed in the data section, the maximum permissible screen-grid (grid-No. 2) input varies with the screen-grid voltage, as shown in the chart above. (This chart cannot be assumed to apply to types other than those for which it is specified in the data section.) Full rated screen-grid input is permissible at screen-grid voltages up to 50 per cent of the maximum rated screen-grid supply voltage. From the 50-per-cent point to the full rated value of supply voltage, the screen-grid input must be decreased. The decrease in allowable screen-grid input follows a curve of the parabolic form. This rating chart is useful for applications utilizing either a fixed screen-grid voltage or a series screen-grid voltage-dropping resistor.


When a fixed voltage is used, it is necessary only to determine that the screen-grid input is within the boundary of the operating area on the chart at the selected value of screen-grid voltage to be used. When a voltage-dropping resistor is used, the minimum value of resistor that will assure tube operation within the boundary of the curve can be determined from the following relation:


$$R_{g^2} \ge \frac{E_{c2} (E_{cc2} - E_{c2})}{P_{c2}}$$

where R_{g2} is the minimum value for the voltage-dropping resistor in ohms, E_{c2} is the selected screen-grid voltage in volts, E_{c2} is the screen-grid supply voltage in volts, and P_{c2} is the screengrid input in watts corresponding to E_{c2}.


MAXIMUM CIRCUIT VALUES

Grid-No.3-Circuit Resistance	0.68	megohm
For fixed-bias operation For cathode-bias operation	$0.22 \\ 0.47$	megohm megohm
# Pulse duration must not exceed 15% of a horizontal scanning cycle	(10	microseconds).





Refer to chart at end of section.	6GY8
Refer to chart at end of section.	6GZ5
Refer to chart at end of section.	6H6
Refer to chart at end of section.	6H6GT
For replacement use type 6HM5/6HA5.	6HA5




HIGH-MU TRIODE

6HA5-S

Miniature type used as rf-amplifier tube in vhf television tuners. Outlines section, 5B; requires miniature 7-contact socket. Type 6HA5-S is electrically identical with type 6HM5/6HA5.

For replacement use type 6HB6/6HA6.

6HA6



BEAM POWER TUBE

6HB5

Duodecar type used as horizontal-deflection amplifier in television receivers. Outlines section, 15B; requires duodecar 12-contact socket.

Heater Voltage (ac/dc)	6.3	volts
Heater Current	1.5	amperes
Heater-Cathode Voltage:		
Peak value	$\pm 200~\mathrm{max}$	volts
Average value	100 max	volts

Class A. Amplifier

CHARACTERISTICS	Pento	de Conne	ction	Triode* Connection	
Plate Voltage	5000	60	130	130	volts
Grid-No.2 (Screen-Grid) Voltage	130	130	130	130	volts
Grid-No.1 (Control-Grid) Voltage	_	0	20	20	volts
Amplification Factor	_			4.7	
Plate Resistance (Approx.)		_	11000	_	ohms
Transconductance			9100	_	μ mhos
Plate Current		410=	50	_	mA
Grid-No.2 Current	_	24•	1.75	_	mA
Grid-No.1 Voltage (Approx.) for plate current of 1 mA	—66	_	-33	_	volts

Grid No.2 tied to plate.

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Supply Voltage	770	volts
Peak Positive-Pulse Plate Voltage#	6000	volts
Peak Negative-Pulse Plate Voltage	1500	volts
DC Grid-No.2 Voltage	220	volts
DC Grid-No.1 Voltage	55	volts
Peak Negative-Pulse Grid-No.1 Voltage	330	volts
Peak Cathode Current	800	mA
Average Cathode Current	230	mA
Plate Dissipation†	18	watts
Grid-No.2 Input	3.5	watts
Bulb Temperature (At hottest point)	220	*C

MAXIMUM CIRCUIT VALUE

Grid-No.1-Circuit Resistance 1 megoh:
Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

† A bias resistor or other means is required to protect the tube in absence of excitation.


6HB6 6HB6/6HA6

Refer to chart at end of section.

HB.

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used as combined oscillator and mixer tube in color and black-and-white television receivers utilizing an intermediate frequency in the order of 40 MHz. Outlines section, 6B; requires miniature 9-contact socket. Type 5HB7 is identical with type 6HB7 except for heater ratings.



9QA

6HB7


5HB7


Heater Voltage (ac/dc)	4.7	6.3	volts
Heater Current	0.6	0.45	ampere
Heater Warm-up Time (Average)	11	11	seconds
Heater-Cathode Voltage:			
Peak value	±200 max	±200 max	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances:	100 max	100 max	10100
Triode Unit:			
Grid to Plate		1.9	рF
Grid to Cathode, Heater, Pentode Grid No.3, and Intern	al Chiald	1.5	
			pF
Plate to Cathode, Heater, Pentode Grid No.3, and Intern	ar Shieid	1.9	\mathbf{pF}
Pentode Unit:			
Grid No.1 to Plate		0.010 max	рF
Grid No 1 to Cathode, Heater, Grid No.2, Grid No.3			
Internal Shield		5	\mathbf{pF}
Plate to Cathode, Heater, Grid No.2, Grid No.3, and	Internal		
Shield		3.4	рF
Heater to Cathode		3.8	pF
			-
A With external shield connected to cathode except as noted.			

[&]quot; With external shield connected to ground,

Class A. Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Triode U	nit Pentod	e Unit
Plate Voltage	330	330	volts
Grid-No.2 (Screen-Grid) Supply Voltage		330	volts
Grid-No.2 Voltage		See curve	
Grid-No.1 (Control-Grid) Voltage:		Dec carre	page ore
Positive-bias value	0	0	volts
Plate Dissipation	2.5	3.1	
Grid-No.2 Input:	2.0	3.1	wates
For grid-No.2 voltages up to 165 volts		0.55	watt
For grid-No.2 voltages between 165 and 330 volts	_	See curve	page 300
CHARACTERISTICS			
Plate Supply Voltage	150	125	volts
Grid-No.2 Supply Voltage		125	volts
Grid-No.1 Supply Voltage	G	<u>—</u> i	volts
Cathode-Bias Resistor	56		ohms
Amplification Factor	40		011110
	0.005	0.2	megohm
Plate Resistance (Approx.)	8500	6400	
	18	12	μiiiios mA
Plate Current	10	4	mA
Grid-No.2 Current	_	4	mA
Grid-No.1 Voltage (Approx.) for plate current of			
10 μΑ	12	9	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.i-Circuit Resistance:			
For fixed-bias operation	0.5	0.25	megohm
For cathode-bias operation	1	0.5	megohm
Lor comogo simo epotentom , , , , , , , , , , , , , , , , , , ,	-	•••	-1100






Refer to chart at end of section.

6HD7

Refer to chart at end of section. For replacement use type 6JB5/6HE5.

6HE5



BEAM POWER TUBE

6HF5

Duodecar type used as horizontal-deflection amplifier in color and black-and-white television receivers. Outlines section, 16B; requires duodecar 12-contact socket. Heater: volts (ac/dc), 6.3; amperes, 2.25; maximum heater-cathode volts, ±200 peak, 100 average.

Class A₁ Amplifier

CHARACTERISTICS	Pente	ode Conne	ction	Triode* Connection	
Plate Voltage	5000	70	175	125	volts
Grid-No.2 (Screen-Grid) Voltage	125	125	125	125	volts
Grid-No.1 (Control-Grid) Voltage		0	25	25	volts
Amplification Factor			_	3	
Plate Resistance (Approx.)			5600		ohms
Transconductance			11300	_	μ mhos
Plate Current		570 -	125		mA
Grid-No.2 Current		34=	4.5	-	mA
Grid-No.1 Voltage (Approx.) for plate					
current of 1 mA	140		-54	_	volts

• Grid No.2 tied to plate.

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Supply Voltage	900	volts
Peak Positive-Pulse Plate Voltage# (Absolute Maximum)	7500 ^	volts
Peak Negative-Pulse Plate Voltage	1100	volts
DC Grid-No.2 Voltage	190	volts
Peak Negative-Pulse Grid-No.1 Voltage	250	volts
Peak Cathode Current	1100	mA
Average Cathode Current	315	mA
Plate Dissipation†	28	watts
Grid-No.2 Input	5.5	watts
Bulb Temperature (At hottest point)	225	°C

MAXIMUM CIRCUIT VALUE

Grid-No.1-Circuit Resistance 1 megol # Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).


▲ Under no circumstances should this absolute value be exceeded.

† A bias resistor or other means is required to protect the tube in absence of excitation.

5HF8

HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in color and black-and-white television receiver applications. The triode unit is used in high-gain, sound-if stages and in sync-separator, sync-clipper, and phase-inverter circuits; the pentode unit is used as a video-output amplifier. Outlines section, 6E; requires miniature 9-contact socket. For



9DX

10HF8

curves of average characteristics, refer to type 6AW8A for the triode unit and to type 6EB8 for the pentode unit. Type 10HF8 is identical with type 6HF8 except for heater ratings.

6HF8

	OTTL O	IUMFO	
Heater Voltage (ac/dc)	6.3	10.5	volts
Heater Current	0.75	0.45	ampere
Heater Warm-up Time (Average)		11	seconds
Heater-Cathode Voltage:			00001140
Peak value	±200 max	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances:	100 IIIax	100 max	VOILS
Triode Unit:			
		0.5	10
Grid to Plate		3.5	рF
Grid to Cathode, Heater, Pentode Cathode, Grid No.			
and Internal Shield		2.8	рF
Plate to Cathode, Heater, Pentode Cathode, Grid No.			
and Internal Shield		2.6	рF
Pentode Unit:			
Grid No.1 to Plate		0.1 max	рF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3,			-
and Internal Shield		10	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3,			ν-
and Internal Shield		4.2	рF
Triode Grid to Pentode Plate		0.015 max	ρF
Trode did to remode riste		O.OIO MEX	рr

Class A, A	Amplifier				
MAXIMUM RATINGS (Design-Maximum Values	;)	Triode U	nit P	entode Unit	
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias		330	See e	330 330 curve page	volts volts 300
Plate Dissipation	value	ĭ		5	watts
For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330		_	See o	1.1 curve page	watts 300
CHARACTERISTICS	riode Uni	t	Pent	ode Unit	
Plate Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Cathode-Bias Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 100 µA Grid-No.1 Voltage (Approx.) for plate current of 20 µA	200 -2 70 17500 4000 - 6		45 125 0 	200 125 68 75000 12500 25 7	volts volts volts ohms ohms μmhos mA wolts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation		Triode U	nit P	entode Unit 0.25	megoḩm

Refer to chart at end of section.

6HG5

SHC8/

megohm

Refer to chart at end of section.

6HG8



For cathode-bias operation

MEDIUM-MU TRIODE-SHARP-CUTOFF PENTODE

This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

6HG8/

7HC8/

Miniature type with frame-grid pentode unit used as combined oscillator and mixer tubes in vhf color and black-and-white television receivers. Outlines section, 6B; requires miniature 9-contact socket. Types 5HG8/LCF86 and 7HG8/PCF86 are identical with type 6HG8/ECF86 except for heater ratings.

STICE!

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage	100 max	ECF86 6.3 0.34 ±100 max	PCF86 7.2 0.3 ±100 max	volts ampere seconds volts
Class A.	Amplifier			
MAXIMUM RATINGS (Design-Maximum Value	s)	Triode Unit	Pentode Unit	
Plate Voltage Grid-No.2 (Screen-Grid) Voltage Cathode Current Plate Dissipation Grid-No.2 Input		125 15 1.5	250 150 18 2 0.5	volts volts mA watts watt
CHARACTERISTICS Plate Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage Amplification Factor		100 3 17	170 150 —1.2	volts volts volts

Mu-Factor, Grid No.2 to Grid No.1 Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current	5500 14	70 0.35 12000 10 3.3	megohm μmhos mA mA
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance; For fixed-bias operation For cathode-bias operation	0.5	0.25 0.5	megohm megohm

6HJ5

Refer to chart at end of section.

6HJ8 6HK5 Refer to chart at end of section.

Refer to chart at end of section.

6HL8

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in color and black-and-white television receiver applications. The triode unit is used as a sync-separator or voltage-amplifier tube, and the pentode unit is used as a video if-amplifier, agc-amplifier, or reactance tube. Outlines section, 6B; requires miniature 9-contact socket. Heater: volts (ac/dc), 6.3; amperes, 0.6; warm-up time (average), 11 seconds; maximum heater-cathode volts, ± 200 peak, 100 average.



Class A. Amplifier

Olass At Ampline	•			
MAXIMUM RATINGS (Design-Maximum Values)	Triode U	nit Pentode	Unit	
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage	330	330 330 See curve	1	volts volts
Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input:	0 2.5	0 2.5	١	olts atts
For grid-No.2 voltages up to 165 volts	=	0.55 See curve		watt
CHARACTERISTICS				
Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage Amplification Factor Plate Resistance (Approx.)	125 — —1 40 5000	125 125 —1 —— 150000	v	olts olts volt
Transconductance Plate Current	7000 12.5	10000 12	μn	nhos mA
Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 20 μA	_	4.5 7		mA olts
MAXIMUM CIRCUIT VALUE				
Grid-No.1-Circuit Resistance	1	_	mego	hm

6HM5


For replacement use type 6HM5/6HA5.

6HM5/ 6HA5 2HM5/2HA5

2HM5/2HA5 3HM5/3HA5 4HM5/4HA5

HIGH-MU TRIODE


Miniature type used as rf-amplifier tube in vhf color and black-and-white television tuners. Outlines section, 5C; requires miniature 7-contact socket. Types 2HM5/2HA5, 3HM5/3HA5, and 4HM5/4HA5 are identical with type 6HM5/6HA5 except for heater ratings.



	2HM5/ 2HA5	3HM5/ 3HA5	4HM5/ 4HA5	6HM5/ 6HA5	
Heater Voltage (ac/dc)	2nA3 2.0	2.7	4.0	6.3	volts
Heater Current	0.6	0.45	0.3	0.18	ampere
Peak Heater-Cathode Voltage					volts
Direct Interelectrode Capacitances:					
Grid to Plate				0.36	pF
Grid to Cathode, Heater, Intern	al Shield.	and Extern	al Shield	4.3	ρF
Plate to Cathode, Heater, Interr	al Shield.	and Extern	al Shield	0.080	ρF
Cathode to Plate				2.9	ρF
Cathode to Heater, Grid, Intern	al Shield,	and Externa	al Shield	3.1	ρF
Heater to Cathode				2.3	pF
Heater to Grid		<i></i>	· · · · · · · · ·	0.070 max	рF
C	Class A. A	\mplifier			
MAXIMUM RATINGS (Design-Maxim	um Values	:)			
DC Plate Voltage				220	volts
DC Plate Supply Voltage				600	volts
Grid Voltage				50	volts
Cathode Current		<i></i>		22	mA
Plate Dissipation		<i></i>		2.6	watts
CHARACTERISTICS AND TYPICAL O	PERATION				
	F	ixed Bias	Cathod	e Bias	
DC Plate Supply Voltage	13	5 135	135	135	volts
Plate-Load Resistor			1000	5600	ohms
Internal-Shield Voltage		0 0	0	0	volts
DC Grid_Voltage		1 —2.7			volts
Cathode-Bias Resistor			_0	87	ohms
Amplification Factor			80	72	
Transconductance			20000	14500	μmhos
Plate Current DC Grid Current		o —	19 10	11.5	mΑ μΑ
Grid-No.1 Voltage for one-per-cent			10		μΑ
transconductance			5.3	-8.1	volts

Refer to chart at end of section.

6HM6



HIGH-MU TRIODE

6HQ5

2HQ5, 3HQ5, 4HQ5

Miniature type used as grounded-cathode rf-amplifier tube in vhf tuners of television receivers. Outlines section, 5C; requires miniature 7-contact socket. Types 2HQ5, 3HQ5, and 4HQ5 are identical with type 6HQ5 except for heater ratings.

	2HQ5	3HQ5	4HQ5	6HQ5	
Heater Voltage (ac/dc)	. 2.4	3	4.2	6.3	volts
Heater Current	0.6	0.45	0.3	0.2	ampere
Heater Warm-up Time (Average) .		11	11		seconds
Peak Heater-Cathode Voltage	$\pm 100 \text{ max}$	$\pm 100 \text{ max}$	$\pm 100 \text{max}$	$\pm 100 \text{ max}$	volts
Direct Interelectrode Capacitances (Approx.):*				
Grid to Plate				0.52	рF
Grid to Cathode, Heater, and Ir	iternal Shie	ld		5	ρF
Plate to Cathode, Heater, and In	nternal Shie	l d		3.5	pF
Heater to Cathode				2.5	ρF
* With external shield connected to	cathode.				-

Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	200	volts
Grid Voltage, Negative-bias Value	50	v olts
Cathode Current	22	mA
Plate Dissipation	2.5	watts

CHARACTERISTICS		
Plate Voltage	135	volts
Grid Voltage	<u>—1</u>	volt
Amplification Factor	78	
Plate Resistance	5400	ohms
Transconductance	15000	μ mhos
Plate Current	11.5	mA
Input Resistance**	275	ohms
Input Capacitance**	11.2	pF
Noise Figure#	4.7	ďΒ
Grid Voltage (Approx.) for transconductance of 150 \(mu\)mhos	4.2	volts
Grid Voltage (Approx.) for transconductance of 1500 μmhos	2.5	volts
MAXIMUM CIRCUIT VALUE		

For a neutralized triode amplifier at a frequency of 200 MHz with signal source impedance adjusted for minimum noise output.

6HR5

Refer to chart at end of section.


6HR6

Refer to chart at end of section.

6HS5

BEAM TRIODE


Duodecar type used as a pulse-type regulator in the high-voltage power supply of color television receivers. Outlines section, 15F; requires duodecar 12-contact socket. Heater: volts (ac/dc), 6.3; amperes, 1.5.



12GY

Class A ₁ Amplifier			
CHARACTERISTICS Pulse Plate Voltage* Grid No.2 (Beam Plate)	to catl	3500 node at 4.4 300 300 65000 4600 —13	volts socket volts mA µmhos ohms volts
* Duty cycle of the pulse must be less than 2.5%.			
High-Voltage Regulator Service For operation in a 525-line, 30-frame system			
MAXIMUM RATINGS (Design-Maximum Values)			
Peak Plate Voltage# Plate Dissipation Peak Plate Current Heater-Cathode Voltage:		5500 30 325	volts watts mA
Peak value Average value Bulb Temperature (At hottest point)	+200	-450 100 220	volts volts °C
MAXIMUM CIRCUIT VALUE			
Grid-Circuit Resistance		0.1 n	1egohm

#Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). *Larger values of grid-circuit resistance may be used if provisions are made to protect the tube.




SHARP-CUTOFF PENTODE

6HS6

Miniature type used as if-amplifier and limiter tube in FM receivers. Outlines section, 5C; requires miniature 7-contact socket.


Heater Voltage (ac/dc)	6.3	volts
Heater Current	0.45	ampere
Heater Warm-up Time (Average)	11	seconds
Heater-Cathode Voltage:		
Peak value	$\pm 200 \text{ max}$	volts
Average value	100 max	volts
Direct Interelectrode Capacitances:		
Grid No.1 to Plate	0.006 max	volts
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield		
	8.8	\mathbf{pF}
Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield		_
Internal Shield	5.2	рF
Class A ₁ Amplifier		
MAXIMUM RATINGS (Design-Maximum Values)		
771		
Plate Supply Voltage	300	volts
Grid-No.3 (Suppressor-Grid) Voltage, Positive Value	0	volts
Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage	300	volts
Grid-No.1 (Control-Grid) Voltage:	See curve	page 300
Negative-bias value	50	volts
Positive-bias value	80 0	volts
Plate Dissipation	3	volts
Grid-No.2 Input:	o	VOILS
For grid-No.2 voltages up to 150 volts	1	watt
For grid-No.2 voltages between 150 and 300 volts	See curve	
	Dec curve	page boo
CHARACTERISTICS		
Plate Supply Voltage	150	volts
Grid No.3 Connect	ed to cathode	at socket
Grid-No.2 Supply Voltage 75	75	volts
Grid-No.1 Supply Voltage 0	0	volts
Cathode-Bias Resistor 68	68	ohms
Amplification Factor 50	_	_
Plate Resistance (Approx.)	0.5	megohm
Transconductance —	9500	μmhos
Plate Current	8.8	mĄ
Grid-No.2 Current —	2.8	mA
Grid-No.1 Voltage (Approx.) for plate current of		
20 μA —	4	volts
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.5	megohm
For cathode-bias operation	ĭ	megohm
_	_	



6HS8 3HS8 4HS8

SHARP-CUTOFF TWIN PENTODE

Miniature type used in agc amplifier, sync, and noiselimiting circuits of color and black-and-white television receivers. One pentode unit is used as combined sync separator and sync clipper; second pentode unit is used as agc amplifier. Outlines section, 6E; requires miniature 9-contact socket. Types 3HS8 and 4HS8 are identical with type 6HS8 except for heater ratings.




9FG


	3 H 58	4HS8	6HS8	
Heater Voltage (ac/dc)	. 3.5	4.2	6.3	volts
Heater Current	0.6	0.45	0.3	ampere
Heater Warm-up Time (Average)	. 11	11	=	seconds
Heater-Cathode Voltage:				20001100
Peak value		$\pm 200 \text{ max}$	$\pm 200 \text{ max}$	volts
Average value		100 max	100 max	volts
Direct Interelectrode Capacitances:				
Grid No.3 to Plate (Each Unit)			2	рF
Grid No.1 to All Other Electrodes			5	pF
Grid No.3 (Each Unit) to All Other El	lectrodes		3.6	pF
Plate (Each Unit) to All Other Electrod	es		3	pF
Grid No.3 (Unit No.1) to Grid No.3 (Un	it No.2)	· · · · · · · · · · · · · · · ·	0.015 max	pF

Class A. Amplifier

MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage (Each Unit)	300	volts
Grid-No.3 (Suppressor-Grid) Voltage (Each Unit):		
Peak positive value	50	volts
DC negative value	50	volts
DC positive value	3	volts
Grid-No.2 (Screen-Grid) Voltage	150	volts
Grid-No.1 (Control-Grid) Voltage, Negative-bias value	50	volts
Cathode Current	12	mA
Plate Dissipation (Each Unit)	1.1	watts
Grid-No.2 Input	0.75	watt

CHARACTERISTICS Y	vitn '	Une	Unit	Operating•			
Plate Voltage					100	100	volts
Grid-No.3 Voltage					0	0	volts
Grid-No 2 Voltage					67.5	67.5	volts
Grid-No.1 Voltage					0	•	volts
Transconductance, Grid No.3 to I	Plate					450	μ mhos
Transconductance, Grid No.1 to I	'late				1100	_	μ mhos
Plate Current					_	2	mA
Grid-No.3 Voltage (Approx.) for	plate	e cu	rrent	of			
100 μΑ					_	-3.5	volts
Grid-No 1 Voltage (Approx.) for	plate	e cu	rrent	υf			
100 μΑ						-2.3	volts





With Both Units Operation	ng		
Plate Voltage (Each Unit) Grid-No.3 Voltage (Each Unit) Grid-No.2 Voltage Grid-No.1 Voltage Plate Current (Each Unit) Grid-No.2 Current Cathode Current	100 10 67.5 	100 0 67,5 2 4.4 8.5	volts volts volts volts mA mA
MAXIMUM CIRCUIT VALUES Grid-No.3-Circuit Resistance (Each Unit) Grid-No.1-Circuit Resistance • With plate and grid No.3 of other unit connected to grou • Adjusted to give grid-No.1 current of 0.1 milliampere.		0.5 0.5	megohm megohm

Refer to chart at end of section.


6HU6/EM87

Refer to chart at end of section.

6HU8/ELL80

Refer to chart at end of section.

6HV5



CHARACTERISTICS

BEAM TRIODE

6HV5A

Duodecar type used as a pulse-type regulator in the high-voltage power supply of color television receivers. Outlines section, 15F; requires duodecar 12-contact socket. Heater: volts (ac/dc), 6.3; amperes, 1.8.

Class A₁ Amplifier

Pulse Plate Voltage* Grid No.2 (Beam Plate) Grid-Voltage, Negative-bias value Peak Plate Current Amplification Factor Transconductance Plate Resistance (Approx.) Grid Voltage (Approx.) for plate current * Duty cycle of the pulse must be less the	Connected t	co cathode at 4.4 300 300 65000 4600	volts socket volts mA µmhos ohms volts
High-Voltag	ge Regulator Service		
For operation in	a 525-line, 30-frame system		
MAXIMUM RATINGS (Design-Maximum	Values)		
Peak Plate Voltage# Plate Dissipation Peak Plate Current		5500 35 325	volts watts mA

Peak Plate Voltage# Plate Dissipation Peak Plate Current	500 volts 35 watts 325 mA
Heater-Cathode Voltage: Peak value Average value Bulb Temperature (At hottest point)	150 volts 100 volts 240 °C

MAXIMUM CIRCUIT VALUE

Grid-Circuit Resistance▲ 0.1 megohm

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). ▲ Larger values of grid-circuit resistance may be used if provisions are made to protect the tube.


Refer to chart at end of section. For replacement use type 6JH5/6JD5/6HZ5.

6HZ5/6JD5

6**HZ**6

SHARP-CUTOFF PENTODE


Miniature type used as sound-detector tube in FM and color and black-and-white television receivers. Tube has two independent control grids. Outlines section, 5C; requires miniature 7-contact socket. Type 5HZ6 is identical with type 6HZ6 except for heater ratings.




7EN

	HZ6	6HZ6	
	.75	6.3	volts
Heater Current	0.6	0.45	ampere
Heater Warm-up Time (Average)	11	11	seconds
Heater-Cathode Voltage:			
		$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances (Approx.):			
Grid No.1 to Plate		0.023	pF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and	l		-
Internal Shield		8.2	ъF
Grid No.1 to Grid No.3		0.09	pF pF
Grid No.3 to Plate		1.6	$\mathbf{p}\mathbf{F}$
Grid No.3 to Cathode, Heater, Grid No.1, Grid No.2, Pl	late		-
and Internal Shield		7.2	pF
and internal billera			-

Class A. Amplifier		
CHARACTERISTICS		
Plate Supply Voltage	150	volts
Grid-No.3 Supply Voltage	0	volts
Grid-No.2 Supply Voltage	100	voits
Grid-No.1 Supply Voltage	0	volts
Cathode-Bias Resistor	180	ohms
Plate Resistance (Approx.)	0.11	megohm
Transconductance, Grid No.1 to Plate	3400	μ mhos
Transconductance, Grid No.3 to Plate	600	μ mhos
Plate Current	3.2	mA
Grid-No.2 Current	3.2	mA
Grid-No.3 Supply Voltage (Approx.) for plate current of 20 μ A	7	volts
Grid-No.1 Supply Voltage (Approx.) for plate current of 20 µA.	-4.5	volts



MAXIMUM RATINGS (Design-Maximum Values)



FM Sound Detector

MAXIMOM KATHUG (Design-maximum values)		
Plate Voltage	300	volts
Grid-No.3 (Control-Grid) Voltage:		
Negative value (dc and peak ac)	100	volts
Positive value (dc and peak ac)	25	volts
Grid-No.2 (Screen-Grid) Supply Voltage	300	volts
Grid-No.2 Voltage	See curv	e page 300
Grid-No.1 (Control-Grid) Voltage:		
Negative-bias value	50	volts
Positive-bias value	0	volts
Plate Dissipation	1.7	watts

Grid-No.3 Input	0.1	watt
For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts		watt ve page 300
MAXIMUM CIRCUIT VALUES		
Grid-No.3-Circuit Resistance	0.68	megohm
Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.22 0.47	megohm megohm
•		

Refer to chart at end of section.

6HZ8

Refer to chart at end of section.

6J4

Refer to chart at end of section.


6J5
6J5GT

Refer to chart at end of section. 6J6

MEDIUM-MU TWIN TRIODE

6J6A

5J6



7BF

Miniature type used as combined rf power amplifier and oscillator or as twin af amplifier. With push-pull arrangement of the grids and the plates in parallel, this type can also be used as a mixer at frequencies as high as 600 MHz. Outlines section, 5C; requires miniature 7-contact socket. Type 5J6 is identical with type 6J6A except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Peak Heater-Cathode Voltage Direct Interelectrode Capacitances (Each Unit, Approx.): Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater (Unit No.1) Plate to Cathode and Heater (Unit No.2)	5J6 4.7 0.6 11 ±100 max Unshielded 1.6 2.2 0.4	6J6A 6.3 0.45 11 ±100 ms Shielded 1.6 2.6 1.6	volts ampere seconds x volts pF pF pF pF
Class A. Amplifier			•-
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage Grid Voltage, Positive-bias value Plate Dissipation		300 0 1.5	volts volts watts
CHARACTERISTICS			
Plate Voltage Cathode-Bias Resistor Amplification Factor		100 50† 38	volts ohms
Plate Resistance (Approx.) Transconductance Plate Current		7100 5300 8.5	ohms µmhos mA
MAXIMUM CIRCUIT VALUES			
Grid-Circuit Resistance: For fixed-bias operation For cathode-bias operation † Value is for both units operating at the specified con		Not 0.5	recommended megohm

RF Power Amplifier and Oscillator-Class C Telegraphy


Key-down conditions per tube without modulation

MAXIMUM RATINGS (Design-Cent	ter Values, Each Unit)	
Plate Voltage	300	volts
Grid Voltage:		
	40	volts
Positive-bias value		volts
Plate Current		mA
Grid Current		mA
Plate Input		watts
Plate Dissipation	1.5	watts
TYPICAL PUSH-PULL OPERATION	(Both Units)	
Plate Voltage		volts
Grid Voltage°		volts
Plate Current		mA
Grid Current (Approx.)		mA
Driving Power (Approx.)	0.35	watt
Power Output (Approx.)	3.5	watts
 Obtained by grid resistor (625 of 	hms), cathode-bias resistor (220 ohms), or fix	ed supply.
AW6L6	Refer to chart at end of section.	

6J6WA	Refer to chart at end of section.
6J6WB	Refer to chart at end of section.
6J7 6J7G 6J7GT	Refer to chart at end of section.
6J8G	Refer to chart at end of section.
619	Refer to chart at end of section.
6110	Refer to chart at end of section. For replacement use type 6Z10/6J10.
6J11	Refer to chart at end of section.
6JA5	Refer to chart at end of section.
6JB5	For replacement use type 6JB5/6HE5.

6JB5/6HE5

television receivers. Outlines section, 15D; requires duodecar 12-contact socket.



Heater Cathode Voltage: Peak value Average value Direct Interelectrode Capacitances:		±200 max 100 max	volts volts
Grid No.1 to Plate		0.49	$\mathbf{p}\mathbf{F}$
Grid No.1 to Cathode, Heater, Grid No.2, and Grid N		9.5	\mathbf{pF}
Plate to Cathode, Heater, Grid No.2, and Grid No.3		6.5	pF
Class A, Amplifier			
CHARACTERISTICS			
Plate Voltage	60	250	volts
Grid-No.2 (Screen-Grid) Voltage	250	250	volts
Grid-No.1 (Control-Grid) Voltage	0	20	volts
Plate Resistance (Approx.)	_	50000	ohms
Transconductance	_	4100	μ mhos
Plate Current	180•	43	m A
Grid-No.2 Current	20•	3.5	m A
Grid-No.1 Voltage (Approx.) for plate current of			
100 μΑ		50	volts

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Vertical-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Voltage Peak Positive-Pulse Plate Voltage# Grid-No.2 Voltage Peak Cathode Current Average Cathode Current Plate Dissipation† Grid-No.2 Input† Bulb Temperature (At hottest point)	350 2500 300 260 75 15 2.75 200	volts volts volts mA mA watts vatts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-higs operation	1	megohm


For cathode-bias operation # Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds). † A resistor or other means is required to protect the tube in absence of excitation.

Refer to chart at end of section.

6JB6

megohms

 $2.\bar{2}$



BEAM POWER TUBE

6JB6A

12JB6A, 17JB6A

Novar types used as high-efficiency horizontal-deflection amplifiers in television receivers. Outlines section, 32A; requires novar 9-contact socket. Types 12JB6A and 17JB6A are identical with type 6JB6A except for heater ratings.

	6JB6A	12JB6A	17JB6A	
Heater Voltage (ac/dc)	6.3	12.6	16.8	volts
Heater Current	1.2	0.6	0.45	amperes
Heater Warm-up Time (Average)		11	11	seconds
Heater-Cathode Voltage:				
Peak value	$\pm 200 \text{ max}$	$\pm 200 \text{ max}$	$\pm 200 \text{ max}$	
Average value	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances (Approx.):				
Grid No.1 to Plate			0.2	р <u>F</u>
Grid No.1 to Cathode, Heater, Grid No.2, and	Grid No.3		15	рF
Plate to Cathode, Heater, Grid No.2, and Grid	No.3		6	рF

Class A. Amplifier

CHARACTERISTICS	Triode Connection		itode nection	
Plate Voltage	150	60	150	volts
Grid No.3 (Suppressor Grid)		Connected	to cathode	at socket
Grid-No.2 (Screen-Grid) Voltage	_	150	150	volts
Grid-No.1 (Control-Grid) Voltage	-22.5	0	22.5	volts
Mu-Factor, Grid No.2 to Grid No.1	4.4	_		
Plate Resistance (Approx.)	_	_	15000	ohms
Transconductance	_		7100	μ mhos
Plate Current	_	390=	70	m.A
Grid-No.2 Current		32=	2.1	mA
Grid-No.1 Voltage for plate current of 1 mA		_	—42	volts
[▲] Grid No.2 connected to plate.				

• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.


Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Supply Voltage Peak Positive-Pulse Plate Voltage#	770 6500	volts volts

Peak Negative-Pulse Plate Voltage	1500	volts
DC Grid-No.3 Voltage;	70	volts
DC Grid-No.2 Voltage	220	volts
DC Grid-No.1 Voltage	55	volts
Peak Negative-Pulse Grid-No.1 Voltage	330	volts
Peak Cathode Current	550	mA
Average Cathode Current	175	mA
Plate Dissipation.	17.5	watts
Grid-No.2 Input	3.5	watts
Bulb Temperature (At hottest point)	240	°C

Grid-No.1-Circuit Resistance, for grid-resistor-bias operation # Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). † For horizontal-deflection service, a positive voltage may be applied to grid No.3 to minimize "snivets" interference in both vhf and uhf television receivers. A typical value is 30 volts. · A bias resistor or other means is required to protect the tube in absence of excitation.



6JC6

Refer to chart at end of section.


6JC6A

MAXIMUM CIRCUIT VALUE

SHARP-CUTOFF PENTODE

3JC6A, 4JC6A Miniature type with frame grid used in if-amplifier stages of color and black-and-white television receivers utilizing intermediate frequencies in the order of 40 MHz. Outlines section, 6B; requires miniature 9-contact socket. Type 4JC6 is identical with type 6JC6 except for heater ratings. Types 3JC6A and 4JC6A are identical with type 6JC6A except for heater ratings.

Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage



33ō


330

volts

See curve page 300

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	3JC6A 3.5 0.6 11	4JC6A 4.5 0.45 11	6JC6A 6.3 0.3	volts ampere seconds
Peak value	±200 max 100 max	±200 max	±200 max	
Direct Interelectrode Capacitances:			. 100 max	VOILS
Grid No.1 to Plate	No 2 and	0.0)19 max	\mathbf{pF}
Internal Shield Plate to Cathode, Heater, Grid No.2, Grid No.			8.5	рF
Internal Shield			3	pF
Class A ₁ Ampi	ifier			
MAXIMUM RATINGS (Design-Maximum Values)				
Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive value	3: 3:	30 0	330 0	volts volts

Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	$\begin{matrix} 0\\3.1\end{matrix}$	volts
Plate Dissipation	2.5		watts
For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330 volts CHARACTERISTICS	0.6	0.7 See cu	watt rve page 300
Plate Supply Voltage Grid No.3 Grid-No.2 Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of	125 Con 125 56 0.18 15000 13 3.2	125 nected to cath 125 56 0.18 16000 14 3.4 —3	volts node at socket volts ohms megohm µmhos mA volts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.25	0.25	megohm
	1	1	megohm





MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6JC8

Miniature type used as combined vhf oscillator and mixer tube in television receivers. Outlines section, 6B; requires miniature 9-contact socket. Heater: volts (ac/dc), 6.3; amperes, 0.45; warm-up time (average), 11 seconds; maximum heater-cathode volts, ±200 peak, 100 average.

Class A₁ Amplifier

	• •		
MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit	Pentode Unit	ŧ
Plate Voltage	275	275	volts
Grid-No.2 (Screen-Grid) Supply Voltage	_	27 5	volts
Grid-No.2 Voltage	_		e page 300
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	0	volts
Plate Dissipation	1.7	2.3	watts
For grid-No.2 voltages up to 137.5 volts		0.45	watt
For grid-No.2 voltages between 137.5 and 275 volts		See curv	e page 300
CHARACTERISTICS			
Plate Voltage	125	100 12	5 volts
Grid-No.2 Voltage	_	70 12	5 volts
Grid-No.1 Voltage	1	0 —	1 volt
Amplification Factor	40		_
Plate Resistance (Approx.)	6000	— 30000	0 ohms
Transconductance	6500	5700 550	0 μm.hos
Plate Current	12		9 mA
Crid-No 2 Current		2	2 mA

Grid-No.1 Voltage (Approx.) for plate current of 20 \(\mu A\)	—7	_	6.5 volts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	_	0.1	megohm
For cathode-bias operation		0.5	megohm

6JD5

For replacement use type 6JH5/6JD5/6HZ5


3JD6

4JD6

6JD6 3JD6, 4JD6

SHARP-CUTOFF PENTODE

Miniature type with frame grid used as if-amplifier tube in color and black-and-white television receivers utilizing an intermediate frequency in the order of 40 MHz. Outlines section, 6B; requires miniature 9-contact socket. Types 3JD6 and 4JD6 are identical with type 6JD6 except for heater ratings.




9PN	1
6JD6	

0.6

See curve page 300

watt


Heater Voltage 3.5	4.5	6.3	volts
Heater Current 0.6	0.45	0.3	
Heater Warm-up Time (Average)		0.0	ampere
meater warm-up lime (Average)	11		seconds
Heater-Cathode Voltage:			
Peak value	+200 may	+200 mas	volts
Average value	100 max	100 max	
Direct Interelectrode Capacitances:		TOO MEY	c volts
Grid No.1 to Plate		19 max	рF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and		10 IIIax	PΓ
Internal Chieff			
Internal Shield		8.2	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and			
Internal Shield		3	рF
		U	br.
Class A, Amplifier			
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage			7.
Call Mr. 6 (Communication of the Call Mr. 19 19 19 19 19 19 19 19 19 19 19 19 19		30	volts
Grid-No.3 (Suppressor-Grid) Voltage, Positive value		0	volts
Grid-No.2 (Screen-Grid) Supply Voltage		30	volts
Grid-No.2 Voltage		ee curve p	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value			
District District Control-Gridy Voltage, Tositive-bias Value		0	volts
Plate Dissipation	•	7.5	motto



CHARACTERISTICS

Plate Supply Voltage	125	volts
Grid-No.3 Voltage	0	volts
Grid-No.2 Supply Voltage	125	volts

Grid-No.1 Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for transconductance of 600 µmhos	0 56 160000 14000 15 4 4.5	volts ohms ohms µmhos mA volts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.25 1	megohm megohm
Refer to chart at end of section. For replacement use type 6MJ6/6LQ6/6JE6C.	6JI	6
Refer to chart at end of section. For replacement use type 6MJ6/6LQ6/6JE6C.	6JE	6A
For replacement use type $6MJ6/6LQ6/6JE6C$.	6JE	5C
Refer to chart at end of section.	6JI	8



BEAM POWER TUBE

6JF6

17JF6, 22JF6

Novar type used as horizontal-deflection amplifier in black-and-white television receivers. Outlines section, 18E or 18F; requires novar 9-contact socket. Types 17JF6 and 22JF6 are identical with type 6JF6 except for heater ratings.

Heater Voltage (ac/dc)	6JF6 6.3 1.6	17 JF6 16.8 0.6 11	22JF6 22 0.45 11	volts amperes seconds
Heater-Cathode Voltage:				
Peak value	$\pm 200 \text{ max}$	$\pm 200 \mathrm{max}$	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances (Appro	ox.):			
Grid No.1 to Plate			1.2	рF
Grid No.1 to Cathode, Heater, Grid N	o.2. and Grid	No.3	22	ρF
Plate to Cathode, Heater, Grid No.2,	, and Grid N	o.3	9	pF pF


Class A, Amplifier Triodes


	TIIUUE-				
CHARACTERISTICS	Connection	Pent	ode Conn	ection	
Plate Voltage	125		50	130	volts
Peak Positive-Pulse Plate Voltage#		6500		_	volts
Grid No.3 (Suppressor Grid)	Conn	ected to	cathode	at socket	
Grid-No.2 (Screen-Grid) Voltage	125	125	125	125	volts
Grid-No.1 (Control-Grid) Voltage	—20		0	20	volts
Triode Amplification Factor	4.1		_	_	
Plate Resistance (Approx.)		_	_	12000	ohms
Transconductance			 -	10000	μ mhos
Plate Current	_	_	525†	80	mA
Grid-No.2 Current			32†	2.5	mA.
Grid-No.1 Voltage for plate current					
of 1 mA	-	125	_	40	volts

Horizontal-Deflection Amplifier

For operation in a 525-line, 39-frame system		
MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Supply Voltage	770	volts
Peak Positive-Pulse Plate Voltage#	6500	volts
Peak Negative-Pulse Plate Voltage	1500	volts
DC Grid-No 3 Voltage*	100	nolta.

DC Grid-No.2 Voltage Peak Negative-Pulse Grid-No.1 Voltage	220 330	volts volts
Peak Cathode Current Average Cathode Current	950 275	mA mA
Grid-No.2 Input Plate Dissipation†	3.5 17	watts watts
Bulb Temperature (At hottest point)	240	°C





MAXIMUM CIRCUIT VALUES

Grid-No.1-Circuit Resistance: For cathode-bias operation For grid-leak-bias operation For fixed-bias operation megohm 10 megohms megohm 0.47

• Grid-No.2 connected to plate at socket.
† This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.
Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).
• In this service, a positive value may be applied to grid No.3 to minimize "snivets" interference; a typical value for this voltage is 50 volts.

‡ A bias resistor or other means is required to protect the tube in absence of excitation.

6JG5

SHARP-CUTOFF PENTODE

Miniature type with frame grid used as video output amplifier in color television receivers. Outlines section, 6E; requires miniatue 9-contact socket. Heater: volts, 6.3; amperes, 0.525; maximum heater-cathode volts. ± 200 peak, 100 average.



9SF

Class A. Amplifier MAXIMUM RATINGS (Design-Maximum Values)

mountain marines (sesign maximum rataes)			
Plate Voltage		330	volts
Grid-No.3 (Suppressor-Grid) Voltage, Positive value		Õ	volts
Grid-No.2 (Screen-Grid) Supply Voltage		330	volts
Grid-No.2 Voltage			Dage 300
Grid-No.1 (Control-Grid) Voltage, Positive value		0	volts
Plate Dissipation		ÿ	
Cuid No 9 Innut			watts
Grid-No.2 Input		1.1	watts
CHARACTERISTICS			
Plate Voltage	200	60	volts
Grid-No.2 Supply Voltage	150	150	volts
Grid-No.1 Voltage		0.	volts
Cathode-Bias Resistor, Bypassed	100		ohms
Plate Resistance (Approx.)	60000	. —	
Transconductance (Grid No.1 to Plate)		_	ohms
Plate Officiality (Grid No.1 to Flate)	11500		μ mhos
Plate Current	25	55	mA
Grid No.2 Current	5.5	18	mA
Grid-No.1 Voltage (Approx.) for plate current			
of 100 μA	10		volts

				_
MAXIMU	JM (CIRCU	JIT VAL	.UES

Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.25	megohm
For cathode-bias operation	1	megohm

· Applied not exceeding two seconds, to avoid damage to tube.

Refer to chart at end of section.

6JG6



BEAM POWER TUBE

6**JG**6A 17JG6A, 22**J**G6A

Novar type used as horizontal-deflection amplifier in low-B+, black-and-white television receivers. Outlines section, 31D; requires novar 9-contact socket. For curves of average plate characteristics, refer to type 6JF6. Types 17JG6A and 22JG6A are identical with type 6JG6A except for heater ratings.

Heater Voltage (ac/dc)	6JG6A 6.3 1.6 —	17JG6A 16.8 0.6 11	22JG6A 22 0.45 11	volts amperes seconds
Heater-Cathode Voltage: Peak value Average value Direct Interelectrode Capacitances:		±200 max 100 max		
Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Plate to Cathode, Heater, Grid No.2, and Gr	Grid No. 3		0.7 22 9	pF pF pF

Class A, Amplifier

CHARACTERISTICS	Triode= Connection	Pen Conr	tode rection		
Plate Voltage	125	50	130		volts
Grid-No.3 (Suppressor Grid)		Connected	to cathode	at	socket
Grid-No.2 (Screen-Grid) Voltage		125	125		volts
Grid-No.1 (Control-Grid) Voltage	20	0	—20		volts
Amplification Factor	4.1	_	_		
Plate Resistance (Approx.)			12000		ohms
Transconductance			10000		μmhos
Plate Current		5 2 5•	80		mA
Grid-No.2 Current	-	32•	2.5		mA
Grid-No.1 Voltage (Approx.),					
for plate current of 1 mA	_	_	—40		volts

- With grid No.2 connected to plate at socket.
- This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Supply Voltage	770	volts
Peak Positive-Pulse Plate Voltage#	6500	volts
Peak Negative-Pulse Plate Voltage	1500	volts
DC Grid-No.3 Voltage*	75	volts
DC Grid-No.2 Voltage	220	volts
DC Grid-No.1 Voltage, Negative-bias value		volts
Peak Negative-Pulse Grid-No.1 Voltage		volts
Peak Cathode Current	950	$\mathbf{m}\mathbf{A}$
Average Cathode Current	275	mA
Plate Dissipation;	17	watts
Grid-No.2 Input	3.5	watts
Bulb Temperature (At hottest point)	240	°C

MAXIMUM CIRCUIT VALUE

Grid-No.1-Circuit Resistance, for grid-No.1-resistor-bias operation 2.2

2 megohms

- # Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). In a horizontal-deflection-amplifier service, a positive voltage (typical value, 30 volts) may be applied to grid No.3 to reduce "snivets" interference, which may occur in both vhf and uhf television receivers.
- † A bias resistor or other means is required to protect the tube in absence of excitation.


6JH5

CHARACTERISTICS

JH5/6HZ5/6JD5

BEAM TRIODE

Duodecar type used as a pulse-type regulator in the high-voltage power supply of color television receivers. Outlines section, 15F; requires duodecar 12-contact socket. Heater: volts (ac/dc), 6.3; amperes, 2.4.



12JE

Class A. Amplifier

Pulse Plate Voltage* Grid No.2 (Beam Plate) Connected Grid-Voltage, Negative-bias value Peak Plate Current Amplification Factor Transconductance Plate Resistance (Approx.) Grid Voltage (Approx.) for plate current of 1 mA	to cath	3500 node at 4.4 300 300 65000 4600 —16	volts socket volts mA µmhos ohms volts
* Duty cycle of the pulse must be less than 2.5%.			
High-Voltage Regulator Service For operation in a 525-line, 30-frame system MAXIMUM RATINGS (Design-Maximum Values)			
Peak Plate Voltage# Plate Dissipation Peak Plate Current Heater-Cathode Voltage:		5500 35 325	volts watts mA
Peak value Average value Bulb Temperature (At hottest point)	+200	450 100 240	volts volts °C
MAXIMUM CIRCUIT VALUE			
Grid-Circuit Resistance▲	0.1	n	negohm


Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

A Larger values of grid-circuit resistance may be used if provisions are made to protect the tube.

6JH6

SEMIREMOTE-CUTOFF PENTODE

Miniature type used in the gain-controlled picture ifamplifier stages of color and black-and-white television receivers. Outlines section, 5C; requires miniature 7contact socket. For curves of average plate characteristics, refer to type 6BZ6. Type 4JH6 is identical with type 6JH6 except for heater ratings.



7CM

aH1a


4JH6

Heater Arrangement	Series	Parallel	
Heater Voltage (ac/dc)	4.2	6.3	volts
Heater Current	0.45	0.3	ampere
Heater Warm-up Time	11	-	seconds
Heater-Cathode Voltage:			
Peak value		$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances:	Unshielded	Shielded=	
Grid No.1 to Plate	0.025 max	0.015 max	pF
Grid No.1 to Cathode, Heater, Grid No.2,			-
Grid No.3, and Internal Shield	7	7	pF
Plate to Cathode, Heater, Grid No.2, Grid No.3,			_
and Internal Shield	2	3	pF

[·] With external shield connected to cathode.

Class A. Amplifier

MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	300	volts
Grid-No.3 (Suppressor-Crid) Voltage, Positive value	őő	volts
Grid-No.2 (Screen-Grid) Supply Voltage	300	volts
Grid-No.2 Voltage		ve page 300
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	volts
Grid-No.2 Input:	•	10,103
For grid-No.2 voltages up to 150 volts	0.55	watt
For grid-No.2 voltages between 150 and 300 volts		ve page 300
Tot gird-10.2 voltages between 100 and 500 volts	See cui	ve page 500
CHARACTERISTICS		
Plate Supply Voltage	125	volts
Grid-No.3 Connecte		
Grid-No.2 Supply Voltage	125	volts
Cathode-Bias Resistor	56	ohms
Plate Resistance (Approx.)	0.26	
	8000	μmhos
Transconductance Range for grid-No.1 voltage of —4.5 volts and	8000	μιιιιοσ
cathode-bias resistor of 56 ohms	400-900	umhos
Plate Current	14	mA
Grid-No.2 Current	3.6	mA
Grid-No.1 Voltage (Approx.) for transconductance of 50 \(\mu\)mhos	—19	volts
Grid-Mo.1 Voltage (Approx.) for transconductance of 50 µmnos	-13	40109
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.25	megohm
For cathode-bias operation	1	megohm



BEAM-DEFLECTION TUBE

6JH8

Miniature type used in color-demodulator and burstgate circuits in color television receivers. This type has two plates and two deflecting electrodes; the control grid varies beam deflection. Outlines section, 6E; requires miniature 9-contact socket. Pin 5 should be connected to cathode at socket. The 6JH8 should be

so located in the equipment that it is not subjected to stray	y magneti	ic fields.
Heater Voltage (ac/dc) Heater Current Direct Interelectrode Capacitances:	6.3 0.3	volts amperes
Direct Interelectrode Capacitances: Grid No.1 to All Other Electrodes, Except Both Plates Grid No.1 to Deflecting Electrode No.2 Grid No.1 to Deflecting Electrode No.2 Plate No.1 to All Other Electrodes Plate No.2 to All Other Electrodes Plate No.1 to Plate No.2 Deflecting Electrode No.1 to All Other Electrodes Deflecting Electrode No.2 to All Other Electrodes Deflecting Electrode No.2 to All Other Electrodes Deflecting Electrode No.1 to Deflecting Electrode No.2	7.5 0.04 max 0.07 max 5 5 0.4 4.8 4.8 0.38	pF pF pF pF pF pF pF
Color TV Demodulator		
MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage (Each Plate)	330	volts
Peak Deflecting-Electrode Voltage (Each Electrode): Negative value Positive value	165 165	volts volts
Grid-No.3 (Accelerating-Grid) Voltage	330 0 33	volts volts mA
Cathode Current Plate Dissipation (Each Plate) Grid-No.3 Input	3 1	watts watt
MAXIMUM CIRCUIT VALUES Grid-No.1 Circuit Resistance:		
For fixed-bias operation For cathode-bias operation	0.1 0.25	megohm megohm

Class A. Amplifier

With both plates connected together and with both deflecting electrodes connected to cathode at socket

CHARACTERISTICS		
Plate-No.1 Supply Voltage	250	volts
Plate-No.2 Supply Voltage	250	volts
Grid-No.3 Voltage	250	volts
Cathode-Bias Resistor	220	oh ms
Transconductance	4400	μmhos
Total Plate Current	14	mA
Grid-No.3 Current	1.5	mA
Grid-No.1 Voltage (Approx.) for total plate current of 10 uA	13	volts

6JK6

Refer to chart at end of section.

6JK8

Refer to chart at end of section.

6ML6


Refer to chart at end of section.

6JM6A

17JM6A

BEAM POWER TUBE

Duodecar types used as horizontal-amplifier tubes in color and black-and-white television receivers. Outlines section, 39A; requires duodecar 12-contact socket. Type 17JM6A is identical with type 6JM6A except for heater ratings.



Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	6.3 1.2	17JM6A 16.8 0.45 11	volts amperes seconds
Peak value Average value Direct Interelectrode Capacitances:		±200 max 100 max	volts volts
Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 Plate to Cathode, Heater, Grid No. 2, and Grid No. 3		0.6 16 7	pF pF pF

Class A, Amplifier

CHARACTERISTICS	n .			Triode**	
CHARACTERISTICS	Pentode Connection			Connection	
Plate Voltage	5000	55	250	150	volts
Grid-No.3 (Suppressor-Grid)	Conne	cted to ca	thode at s	socket	
Grid-No.2 (Screen-Grid) Voltage	150	150	150	150	volts
Grid-No.1 (Control-Grid) Voltage	_	0	22.5	22.5	volts
Plate Resistance (Approx.)		_	15000		ohms
Transconductance		_	7300		μ mhos
Plate Current	-	345*	65	_	mA.
Grid-No.2 Current	-	30*	1.8	_	mA
Grid-No.1 Voltage (Approx.) for plate					
current of 1 µA	—100		-42		volts
Amplification Factor	_	_	_	4.4	
MAXIMUM CIRCUIT VALUE					
Grid-No.1-Circuit Resistance				1	megohm

* This value can be measured by a method utilizing a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Horizontal-Deflection Amplifier


For operation	n in a	525-line.	30-frame	system

MAXIMUM HATINGS (Design-Maximum values)		
DC Plate Supply Voltage	770	volts
Peak Positive-Pulse Plate Voltage#	6500	volts
Peak Negative-Pulse Plate Voltage	1500	volts
DC Grid-No 2 Voltage	70	wolte

^{**} Grid No.2 tied to plate.

DC Grid-No.2 Voltage	220	v ol ts
DC Grid-No.1 Voltage, Negative-bias value	55	v ol t s
Peak Negative-Pulse Grid-No.1 Voltage	330	volts
Average Cathode Current	175	mA
Peak Cathode Current	550	mA
Plate Dissipation##	17.5	watts
Grid-No.2 Input	3.5	watts
Bulb Temperature (At hottest point)	220	•C

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). ## A bias resistor or other means is required to protect the tube in absence of excitation.




BEAM POWER TUBE

6JN6 12JN6, 17JN6

Duodecar type used as horizontal-amplifier tube in color and black-and-white television receivers. Outlines section, 15A; requires duodecar 12-contact socket. This type is electrically identical with type 6JM6 except that it has a slightly lower grid-No.1-to-plate capacitance. Types 12JN6 and 17JN6 are identical with type 6JN6 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	6JN6 6.3 1.2	12JN6 12.6 0.6 11	17JN6 16.8 0.45 11	volts amperes seconds
Direct Interelectrode Capacitances: Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Grid Plate to Cathode, Heater, Grid No.2, and Grid No.	No.3		$\begin{array}{c} 0.34 \\ 16 \\ 7 \end{array}$	pF pF pF



MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6JN8 19JN8/19CL8A

Miniature type used as FM converter and rf amplifier in radio receivers. Outlines section, 6B; requires miniature 9-contact socket. Type 19JN8/19CL8A is identical with type 6JN8 except for heater ratings.

	6JN8	19CL8A	
Heater Voltage (ac/dc)	6.3	18.9	volts
Heater Current	0.45	0.15	ampere
Heater Warm-up Time (Average)	11		seconds
Heater-Cathode Voltage:			
Peak value	$\pm 200~\mathrm{max}$	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances:*			
Pentode Unit:			
Grid No.1 to Plate		0.01	рF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3,			
Shield		5.5	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3, a	nd Internal		
_ Shield		3.4	рF
Triode Unit:			
Grid to Plate	· · · · · · · · · · · ·	1.7	рF
Grid to Cathode, Heater, Pentode Cathode, Grid N	o.3,		
and Internal Shield		3.2	рF
Plate to Cathode, Heater, Pentode Cathode, Grid			
and Internal Shield		2 .2	рF
# 37744			

^{*} With external shield connected to cathode of unit under test.

Class A₁ Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Triode U	nit Pentode Unit	
Plate Voltage	300	300	volts
Grid-No.2 (Screen-Grid) Supply Voltage		300	volts
Grid-No.2 Voltage		See curve page 300	

Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volts	2.5 	0 2.5 0.55 See curve	volts watts page 300
CHARACTERISTICS Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 \(\mu A \)	125 —1 46 5400 8500 13.5 —	125 125 —1 200000 7500 12 4	volts volt ohms µmhos mA mA
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	2.2 2.2	2.2 2.2	megohms megohms

6JQ6

BEAM POWER TUBE with integral diode

AOT A

19106


Miniature type featuring integral diode, internally connected to grid No.3, used in feedback-stabilized vertical-deflection-amplifier applications in color and black-and-white television receivers. Outlines section, 6G; requires miniature 9-contact socket. Types 12JQ6 and 17JQ6 are identical with type 6JQ6 except for heater ratings.




0	DA.
J	RM.

	e) de	12 JQ 6	17JQ6	
Heater Voltage (ac/dc)	6.3	12.6	17	volts
Heater Current	1.2	0.6	0.45	amperes
Heater Warm-up Time (Average)	_	11	11	seconds
Heater-Cathode Voltage:				
Peak value	$\pm 200~\mathrm{max}$	$\pm 200 \text{ max}$	±200 max	volts
Average value	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances:			200 111011	*******
Grid No.1 to Plate			0.32	рF
Grid No.1 to Cathode, Heater, Grid	No.2. Grid	No. 3.	0.02	pr
and Diode Plate	21012, 0114	,	13	рF
Plate to Cathode, Heater, Grid No.2,	Crid No 3	• • • • • • • • • • • • • •	10	Pr
and Diode Plate	din 110.0,		6	рF
and Dioge Flate		• • • • • • • • • • • • •	U	PΓ
Class	A ₁ Amplific	er		
CHARACTERISTICS				
Plate Voltage		40	140	volts
Grid-No.3 (Suppressor-Grid) Voltage		0	0	volts
Grid-No.2 (Screen-Grid) Voltage		120	140	volts
Grid-No.1 (Control-Grid) Voltage		0	18	volts
Triode Amplification Factor.			6.5	
Plate Resistance (Approx.)			10500	ohms
Transconductance			4200	umhos
Plate Current		150#	35	mA
Grid-No.2 Current		20#	2.5	mA
Grid-No.1 Voltage for plate current of 1	m A		-37	volts
Instantaneous Diode-Plate-to-Cathode Volt			0,	*****
for Instantaneous Diode-Plate Current			5	volts
tor Instantantons Diode-Line Ouriens			U	VOICS
Vertical-De	flection Am	plifier		
For operation in a	525-line, 30-1	frame system		
MAXIMUM RATINGS (Design-Maximum V		pysociii		
DC Plate Voltage			425	volts
Peak Positive-Pulse Plate Voltage				
(Absolute-Maximum Value)*			2000	volts
DC Grid-No.3 and Diode-Plate Voltage .			+10	14
DO OTTO-110.0 ALIG DIOUE-Flate VOILAGE .			_150	volts

DC Grid-No.2 Voltage Peak Negative-Pulse Grid-No.1 Voltage Average Cathode Current Peak Cathode Current Average Diode-Plate (and Grid-No.3) Current Plate Dissipation	10	volts volts mA mA mA watts
Grid-No.2 Input Bulb Temperature (At hottest point)	2 240	watts °C





MAXIMUM CIRCUIT VALUES

Grid-No.1—Circuit Resistance:

For grid-No.1-resistor-bias operation

For cathode-bias operation

2.2 megohms

megohms

 Grid No.3 and diode plate connected to cathode, and grid-No.2 connected to plate at socket.

#This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).



BEAM POWER TUBE

6JR6


17JR6, 22JR6, 33JR6


Novar type used for horizontal-deflection amplifier service in low B+, black-and-white television receivers. Outlines section, 31D; requires novar 9-contact socket. Types 17JR6, 22JR6 and 33JR6 are identical with type 6JR6 except for heater ratings.


Heater Voltage (ac/dc) Heater Current	6JR6 6.3 1.6	17 JR6 16.8 0.6	22JR6 22 0.45	33JR6 33 0.3	volts
Heater Warm-up Time	***	0.0	0.10	0.0	amperes
(Average) Heater-Cathode Voltage:		11	11	11	seconds
Peak value Average value	±200 max	± 200 max 100 max	±200 max 100 max	±200 max 100 max	volts
Direct Interelectrode Capa	citances (Apr	rox.):		100 max	volts
Grid No.1 to Plate Grid No.1 to Cathode,	Heater, Grid	No.2.		0.7	pF
and Grid No.3 Plate to Cathode, Her	ter, Grid No			22	pF
and Grid No.3		.		9	рF

Class A. Amplifier

CHARACTERISTICS	Connection	Pent	tode Conne	ction	
Plate Voltage	125	_	50	130	volts
Peak Positive-Pulse Plate Voltage#		6500	- .		volts
Grid No.3 (Suppressor Grid) Grid-No.2 (Screen-Grid) Voltage	105			ode at socket	_
Grid-No.1 (Control-Grid) Voltage	125 20	125	125	125	volts
Plate Resistance (Approx.):	20		U	20	volts
Transconductance		_	_	18000 7000	ohms µmhos
				1000	μmnos







Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Ratings)

Plate Supply Voltage	770	volts
Peak Positive-Pulse Plate Voltage#	6500	volts
Peak Negative-Pulse Plate Voltage	1500	volts
Grid-No.3 Voltage	75	volts
Grid-No.2 Voltage	220	volts
Grid-No.1 Voltage, Negative-bias value	55	volts
Peak Negative-Pulse Grid-No.1 Voltage	330	volts
Peak Cathode Current	950	mA
Average Cathode Current	275	
Grid-No.2 Input		mA.
Plate Dissipation•	3.5	watts
Dulk Temperature (AA better)	17	watts
Bulb Temperature (At hottest point)	240	•c
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
Cathode bias (with min. $R_K = 100\Omega$)	1	megohm

Grid-leak bias (with signal peak clamped to zero bias)

maximum ratings of the tube will not be exceeded.

Fixed bias (where positive grid current is not drawn) megohm * Grid No. 2 connected to plate at socket. # Pulse duration must not exceed 15% of one horizontal scanning cycle (10 microseconds). This value can be measured by a method involving a recurrent waveform such that the

• In this service, a positive value may be applied to grid No.3 to minimize "snivets" interference; a typical value for this voltage is 30 volts.

· A bias resistor or other means is required to protect the tube in absence of excitation.

6JS6 6JS6A

Refer to chart at end of section.

6JS6C

BEAM POWER TUBE

Duodecar types used as horizontal-deflection amp in color and black-and-white television receivers. lines section, 16B; requires duodecar 12-contact so Types 23JS6A and 31JS6A are identical with 6JS6C except for heater ratings.

lifiers	G
Out-	
ocket.	
type	

3€ 10)Gz

megohma

10

10	EV
12	ГΊ

Wanton	Voltage (ac/dc)	6JS6C	23JS6A	31JS6A	
Heater	Current	$\frac{6.3}{2.25}$	23.6	31.5	volts
Heater	Warm-up Tme (Average)	2.25	0.6	0.45	amperes seconds

Heater-Cathode Voltage: Peak value Average value	±200 max	±200 max	±200 max	volts
	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances: Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid N Plate to Cathode, Heater, Grid No.2,	o.2. and Grid	No.3	0.7 24 10	pF pF pF

Class A. Amplifier

CHARACTERISTICS	Triodett Connection	ъ.	_4_4_4	D	
				Connection	
Plate Voltage	125	5000	60	175	volts
Grid No.3 (Suppressor Grid)		Connected	to cat	hode at socket	1010
Grid-No.2 (Screen-Grid) Voltage	125	125	125	125	volts
Grid-No.1 (Control-Grid) Voltage	25		0	25	volts
Plate Resistance (Approx.)				5500	ohms
Transconductance				11500	μ mhos
Plate Current			600†	130	mA
Grid-No.2 Current			32†	2.8	mΑ
Grid-No.1 Voltage (Approx.) for plate					
current of 1 mA		-125		54	volts
Triode Amplification Factor	3		•		

 $[\]dagger$ This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system	
MAXIMUM RATINGS (Design-Maximum Values)	
DC Plate Supply Voltage	volts
Peak Positive-Pulse Plate Voltage# 7500	volts
Peak Negative-Pulse Plate Voltage	volts
DC Grid-No.3 Voltage	volts
DC Grid-No.2 Voltage	volts
Peak Negative-Pulse Grid-No.1 Voltage	volts
Average Cathode Current	mA
Peak Cathode Current	m A
Plate Dissipation**	watts
Grid-No.2 Input 5.5	watts
Bulb Temperature (At hottest point)	°C
MAXIMUM CIRCUIT VALUE Grid-No.1-Circuit Resistance For grid bias feedback HV regulation 0.47 For dc or pulse shunt HV regulation 10	megohm megohms
# Pulse duration must not exceed 15% of one horizontal scanning cycle (10	mieroveconds)

^{**} A bias resistor or other means is required to protect the tube in absence of excitation

^{††} Grid No.2 connected to plate.

TYPE 6JS6C GRID No. 2=125 V BEAM PLATES TIED TO CATHODE 900 WILLIAMPERES 900 900 900 900 900 900 GRID-No.I VOLTS EQ

ratings.

6JT6A 12JT6A, 17JT6A

BEAM POWER TUBE

Novar types used as horizontal-deflection amplifiers in high-efficiency deflection circuits of black-and-white television receivers employing wide-angle or high-



voltage picture tubes. Outlines section, 31A; requires novar 9-contact socket. Types 12JT6A and 17JT6A are identical with type 6JT6A except for heater

	6JT6A	12 JT6A	17JT6A	
Heater Voltage (ac/dc)	6.3	12.6	16.8	volts
Heater Current		0.6	0.45	amperes
Heater Warm-up Time (Average)	—	11	11	seconds
Heater-Cathode Voltage:				
Peak value	$\pm 200 \text{ max}$	$\pm 200~\mathrm{max}$	$\pm 200~\mathrm{max}$	volts
Average value	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances: Grid No.1 to Plate			0.26	pF pF pF
Grid No.1 to Cathode, Heater, Grid No.2, a	nd Grid No	.3	15	рF
Plate to Cathode, Heater, Grid No.2, and G	rid No.3 .		6.5	pF

Class A, Amplifier


CHARACTERISTICS			Triode* onnection	
Plate Voltage	60	250	150	volts
Grid-No.3 (Suppressor Grid)		Connected	to cathode	
Grid-No.2 (Screen-Grid) Voltage	150	150	150	volts
Grid-No.1 (Control-Grid) Voltage	0	-22.5	-22.5	volts
Triode Amplification Factor	_		4.4	
Plate Resistance (Approx.)		15000		o hms
Transconductance	_	7100		μ mhos
Plate Current	390■	70		$\mathbf{m}\mathbf{A}$
Grid-No.2 Current	32■	2.1		mA.
Grid-No.1 Voltage (Approx.) for plate current of				
1 mA	_	42	_	volts

* Grid No.2 connected to plate.

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Supply Voltage	770	volts
Peak Positive-Pulse Plate Voltage#	6500	volts
Peak Negative-Pulse Plate Voltage	1500	volts
DC Grid-No.3 Voltage*	70	vol ts
DC Grid-No.2 Voltage	220	volt s
DC Grid-No.1 Voltage, Negative-bias value	55	volts
Peak Negative-Pulse Grid-No.1 Voltage	330	volts



This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

volts

ampere

Peak Cathode Current Average Cathode Current Plate Dissipation† Grid-No.2 Input Bulb Temperature (At hottest point) MAXIMUM CIRCUIT VALUE	550 175 17.5 3.5 240	mA .mA watts watts °C
Grid-No.1-Circuit Resistance, for grid-resistor-bias operation		

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

A positive voltage may be applied to grid No.3 to reduce interference from "snivets" which may occur in television receivers. A typical value for this voltage is 30 volts.

† A bias resistor or other means is required to protect the tube in absence of excitation.

HIGH-MU TRIODE— SHARP-CUTOFF PENTODE


Voltage (ac/dc)

6JT8

10JT8

10.2

0.45



Neonoval type with frame-grid pentode unit used in color and black-and-white television receivers. The triode unit is used as a voltage-amplifier or sync-separator tube, and the pentode unit is used as a video-amplified tube. Outlines section, 10A, except base is small-button miniature 9-pin; requires miniature 9-contact socket. Type 10JT8 is identical with type 6JT8 except for heater ratings.

6JT8

6.3

0.725

Heater Warm-up Time (Average)		1	.1	seconds
Heater-Cathode Voltage:	±200 n	nax ±20	00 max	volts
Peak value	100 n	nax 10	00 max	volts
Average value				
Class A. Amplifie	er			
MAXIMUM RATINGS (Design-Maximum Values)	Triode Uni	t Pento	de Unit	
Plate Voltage	330	33	0	volts
Grid-No.2 (Screen-Grid) Supply Voltage		33	0	volts
Grid-No.2 Voltage	_	See curv	e page	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0		0	volts
Plate Dissipation	1		4	watts
Grid-No.2 Input:				
For grid-No.2 voltages up to 165 volts	_	1.		watts
For grid-No.2 voltages between 165 and 330 volts	_	See curv	e page	300
CHARACTERISTICS				
Plate Supply Voltage	250	50	200	volts
Grid-No.2 Supply Voltage		100	100	volts
Grid-No.1 Voltage	2	0		volts
Cathode-Bias Resistor	-	_	82	ohms
Amplification Factor	100	_	_	
Plate Resistance (Approx.)	37000	_	50000	oḥms
Transconductance	2700		20000	μmhos
Plate Current	1.5	55•	17	mA
Grid-No.2 Current		18•	3.5	mA
Grid-No.1 Voltage (Approx.) for plate current of			_	
100 μΑ	_	_	5	volts
Grid-No.1 Voltage (Approx.) for plate current of	- 0			14
20 μA	5.3		_	volts
MAXIMUM CIRCUIT VALUES				
Grid-No.1-Circuit Resistance:				
For fixed-bias operation	0.5	0.25		megohm
For cathode-bias operation	1	1	Ĺ	megohm
• This value can be measured by a method involving a	recurrent	wavefor	m such	that the



maximum ratings of the tube will not be exceeded.

BEAM POWER TUBE

6JU6

Novar type used as horizontal-deflection amplifier in color television receivers. Outlines section, 18E or 18F; requires novar 9-contact socket. Type 22JU6 is identical with type 6JU6 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time	6.3 1.6	22 JU6 20 0.45 11	volts amperes seconds
Heater-Cathode Voltage: Peak value	+200 max	±200 max	volts
Average value		100 max	volts
Direct Interelectrode Capacitances:			
Grid No.1 to Plate		1.2	pF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.	.3 <i></i>	22	pF
Plate to Cathode, Heater, Grid No.2, and Grid No.3		9	DF

Class A, Amplifier


	TLIOREA					
CHARACTERISTICS	Connection	Pentoc	le Conn	ection		
Plate Voltage	125		50	130		volts
Peak Positive-Pulse Plate Voltage#	_	6500				volts
Grid No.3 (Suppressor Grid)		Connected	to cat	hode at	socket	
Grid-No.2 (Screen-Grid) Voltage	125	125	125	125		volts
Grid-No.1 (Control-Grid) Voltage	20	_	0	20		volts
Amplification Factor	4.7					
Plate Resistance (Approx.)			-	18000		ohms
Transconductance			_	7000		μmhos
Plate Current			470††	45		mA
Grid-No.2 Current	_		32††	1.5		mA
Grid-No.1 Voltage for plate current			-			
of 1 mA		75		32		volts


Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

rot operation in a 525-time, 55-trame system		
MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Supply Voltage	770	volts
Peak PositivePulse Plate Voltage#	6500	volts
Peak Negative-Pulse Plate Voltage	1500	volts
DC Grid-No.3 Voltage	75	volts
DC Grid-No.2 Voltage	220	volts
DC Grid-No.1 Voltage, Negative-bias value	55	volts
Peak Negative Pulse Grid-No.1 Voltage	330	volts
Peak Cathode Current	950	mA.
Average Cathode Current	275	mA
Grid-No.2 Input	3.5	watts
Plate Dissipation	17	watts
Bulb Temperature (At hottest point)	240	°C
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
For grid-resistor-bias operation	0.47	megohm
For plate-pulsed operation	10	megohms


- # Pulse duration must not exceed 15% of one horizontal scanning cycle (10 microseconds). † Grid No.2 connected to plate.
- ††This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.
- In this service, a positive value may be applied to grid No.3 to minimize "snivets" interference; a typical value for this voltage is 30 volts.
- •• A bias resistor or other means is required to protect the tube in absence of excitation.





Refer to chart at end of section.

6JU8



QUADRUPLE DIODE

A8UL6


Miniature type used in phase-detector and noise-immune color-killer circuits of color television receivers, and in bridge-matrixing circuits in FM stereo multiplex equipment. Outlines section, 6B; requires miniature 9-contact socket. Units 1 and 2 are shielded from units 3 and 4 to minimize coupling between the series-

connected pairs of diodes. Type 8JU8A is identical with type 6JU6A except for heater ratings.

Heater Voltage (ac/dc)	6JU8A 6.3	8JU8A 8.4	volts
	0.6	0.45	ampere
Heater Current	0.0		
Heater Warm-up Time	1.000	11	seconds
Peak Heater-Cathode Voltage	$\pm 300~\mathrm{max}$	$\pm 300 \text{ max}$	volts
Direct Interelectrode Capacitances (Approx.):			
Plate of Unit No.1 and Cathode of Unit No.2 to	Cathode of		_
Unit No.1		1.8	\mathbf{pF}
Plate of Unit No.1 and Cathode of Unit No.2 to Pla	te of		
Unit No.2		2.2	\mathbf{pF}
Plate of Unit No.2 to Heater and Internal Shield		0.62	рF
Plate of Unit No.3 and Cathode of Unit No.4 to	Cathode of		
Unit No.3		1.9	рF
Plate of Unit No.3 and Cathode of Unit No.4 to Plat	e of		-
Unit No.4		2.2	pF
Plate of Unit No.4 to Heater and Internal Shield		0.94	pF
Cathode of Unit No.1 to Heater and Internal Shield		1.8	pF
Cathode of Unit No.3 to Heater and Internal Shield		1.9	pF
		2.0	-
MAXIMUM RATINGS (Design-Center Values, Each Diode			
Peak Inverse Plate Voltage		300	volts
Peak Plate Current		54	mA
Average Output Current		9	mA
CHARACTERISTIC, Instantaneous Value (Each Unit)			
Plate Current for plate voltage of 10 volts		60	mA

HIGH-MU TRIODE— SHARP-CUTOFF PENTODE


6JV8



Miniature type used in television receiver applications, particularly those having low-voltage "B" supplies. The triode unit is used in sound-if, keyed-agc, sync-separator, sync-amplifier, and noise-suppression circuits. The pentode unit is especially useful as a video amplifier tube. Outlines section, 6E; requires miniature 9-contact socket. Type 8JV8 is identical with type 6JV8 except for heater ratings.

	6JV8	8JV8	
Heater Voltage (ac/dc)	6.3	8.5	volts
Heater Current	0.6	0.45	ampere
Heater Warm-up Time (Average)	11	11	seconds
Heater-Cathode Voltage:			
Peak value	±200 max	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances (Approx.):			
Triode Unit:			
Grid to Plate		2.2	pF
Grid to Cathode and Heater		3	рF
Plate to Cathode and Heater		2	pΓ
Pentode Unit:			
Grid No.1 to Plate		0.08 max	pF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, a	nd		-
Internal Shield		8	pF
			-

Plate to Cathode, Heater, Grid No.2, Gri Internal Shield Pentode Grid No.1 to Triode Plate Pentode Plate to Triode Plate		3.2 0.012 max 0.24 max	pF pF pF		
Class A	. Amplif	ier			
MAXIMUM RATINGS (Design-Maximum Value		Tri	ode Unit	Pentode Unit	
Plate Voltage			330	330	volts
Grid-No.2 (Screen-Grid) Voltage				330	volts
Grid-No.1 (Control-Grid) Voltage:					
Positive-bias value	 .		0	0	volts
Negative-bias value	<i></i>		50	50	volts
Plate Dissipation			1.1	4	watts
Grid-No.2 Input				1.7	watts
CHARACTERISTIC Tries	de Unit		Pentode	Unit	
Plate Voltage	200	60	125	200	volts
Grid-No.2 Voltage		200	125	200	volts
Grid-No.1 Voltage	2	Ō	<u>—1</u>	-2.9	volts
Amplification Factor	70	_		_	
Plate Resistance (Approx.) 0.0	0175	_	0.1	0.15	megohm
Transconductance	1000		11500	10700	µmhos
Plate Current	4	51•	22	22	mA.
Grid-No.2 Current	_	14•	4	4	mA
Grid-No.1 Voltage (Approx.) for plate					
current of 20 μA	5	_	—5.5	9	volts
MAXIMUM CIRCUIT VALUES					
Grid-No.1-Current Resistance:					
For fixed-bias operation			0.5	0.25	megohm
For cathode-bias operation			1	1	megohm
• This value can be measured by a method		a re	rurrant	waveform such	
maximum ratings of the tube will not be ex	ceeded.	. 16		wavetorm such	that tile



6JW8/ ECF802

5JW8 6LX8/LCF802 9JW8/PCF802

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used as horizontal-oscillator and frequency-control tube in color and black-and-white television receivers. Outlines section, 6B; requires miniature 9-contact socket. Types 5JW8, 6LX8/LCF802 and 9JW8/PCF802 are identical with type 6JW8/ECF802 except for heater ratings.



9AE

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time	5JW8 4.7 0,6	6JW8/ ECF802 6.3 0.43	6LX8/ LCF802 6 0.45	9JW8/ PCF802 9 0.3	volts ampere
(Average)	11	_	_		seconds
Peak value	±200 max 100 max	±200 max 100 max	±200 max 100 max	±200 max 100 max	volts volts


335

Class A. Amplifier

Oluss Al Amplille	• •		
MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit	Pentode Unit	
Plate Supply Voltage	550	550	volts
Plate Voltage	250	250	volts
Grid-No.2 (Screen-Grid) Supply Voltage		550	volts
Grid-No.2 Voltage	_	250	volts
Peak Cathode Current.	_	50	mA
Cathode Current	10	15	mA
Plate Dissipation	1.4	1.2	watts
Grid-No.2 Input		0.8	watts
Input Impedance at 60 Hz	50	300	kohms
CHARACTERISTICS			
Plate Voltage	200	100	volts
Grid-No.2 Voltage		100	volts
Grid-No.1 (Control-Grid) Voltage	-2	 1	volts
Mu Factor, Grid-No.1 to Grid-No.2		47	
Amplification Factor	70		
Input Resistance	0.2	0.4	megohm
Transconductance	3500	5500	μmhos
Plate Current	3.5	6	mA.
Grid-No.2 Current		1.7	mA
Plate Current:			
For grid-No.1 voltage of 0 volts	_	12.5	mA
For grid current of 10 µA	10		mA
Grid-No.2 Current for grid-No.1 voltage of 0 volts		3.5	mA
Grid-No.1 Voltage:			
For grid-No.1 current of +0.3 μA	1.3	-1.3	volts
For plate and grid-No.2 voltage of 200 volts			
and plate current of 10 µA	_	16	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
For fixed-bias operation	_	0.56	megohm
For cathode-bias operation	3	ĭ	megohms
2 of comode-play operation	-	-	

Refer to chart at end of section.

6JZ6



MEDIUM-MU TRIODE— POWER PENTODE

· With a maximum duty factor of 0.30 and maximum pulse duration of 30 microseconds.

6JZ8
13JZ8, 17JZ8, 24JZ8, 25JZ8

Duodecar type used in combined vertical-deflection-oscillator and vertical-deflection-amplifier applications in television receivers. Outlines section, 8C; requires duodecar 12-contact socket. Types 13JZ8, 17JZ8, 24JZ8, and 25JZ8 are identical with type 6JZ8 except for

12DZ heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time .	6JZ8 6.3 1.2	13JZ8 12.7 0.6 11	17 JZ8 16.8 0.45 11	24JZ8 24.2 0.315 11	25JZ8 25.2 0.3	volts amperes seconds
Heater-Cathode Voltage: Peak value Average value	±200 max	±200 max	±200 max	±200 max	±200 max	volts
	100 max	100 max	100 max	100 max	100 max	volts

| Class A, Amplifier | CHARACTERISTICS | Triode Unit Beam Power Unit Plate Voltage | 150 45 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120 | 120

Plate Voltage	150	45	120	volts
Grid-No.2 (Screen-Grid) Voltage		110	110	volts
Grid-No.1 (Control-Grid) Voltage	б	0	8	volts
Amplification Factor	20			
Plate Resistance (Approx.)	8500		11700	ohms
Transconductance	2350		7100	μmhos
Plate Current	5.5	122	46	mA
Grid-No.2 Current		16.5	3.5	mA
Grid-No.1 Voltage (Approx.) for plate current				
of 10 μA	10		_	volts

Triode

--25

Beam Power

volts

* This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)	Unit Oscillator	Unit Amplifier	
DC Plate Voltage	250	250	volts
Peak Positive-Pulse Plate Voltage#		2000	volts
DC Grid-No.2 Voltage	_	200	volts
Peak Negative-Pulse Grid-No.1 Voltage	400	150	volts
Peak Cathode Current	70	245	mA
Average Cathode Current	20	70	mA
Plate Dissipation	1	7	watts
Grid-No.2 Input	_	1.8	watts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
For fixed-bias operation	1	1	megohm
For cathode-bias operation	2.2	2.2	megohms
# Pulse dynatics must bet social 1500 of a section		(0.5	

- # Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).
- · A bias resistor or other means is required to protect the tube in absence of excitation.

6K5GT


Refer to chart at end of section.

6K6GT

POWER PENTODE

Glass octal type used in output stage of radio receivers and, triode-connected, as a vertical-deflection amplifier in television receivers. This type may be supplied with pin No.1 omitted. Outlines section, 13D; requires octal socket. This tube, like other power-handling tubes, should be adequately ventilated.

Maximum-Signal Power Output



4.5

watts

Heater Voltage (ac/dc)	3 volts
Heater Current 0.2	
Heater-Cathode Voltage:	
Peak value	max volts
Average value	max volts
Direct Interelectrode Capacitances (Approx.):	-
Grid No.1 to Plate	pF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 5.5	
Plate to Cathode, Heater, Grid No.2, and Grid No.3	5 pF
	•

Plate to Cathode, Heater, Grid No.2, and Gri			6	pF pF
Class A, Amp	lifier			
MAXIMUM RATING (Design-Center Values)				
Plate Voltage			315	volts
Grid-No.2 (Screen-Grid) Voltage		.	285	volts
Plate Dissipation			8.5	watts
Grid-No.2 Input			2.8	watts
TYPICAL OPERATION				
Plate Voltage	100	250	315	volts
Grid-No.2 Voltage	100	250	250	volts
Grid-No.1 (Control-Grid) Voltage	7	18	-21	volts
Peak AF Grid-No.1 Voltage	7	18	21	volts
Zero-Signal Plate Current	9	32	25.5	mA
Maximum-Signal Plate Current	9.5	33	28	m A
Zero-Signal Grid-No.2 Current	1.6	5.5	4.0	m A
Maximum-Signal Grid-No.2 Current	3	10	9	mA
Plate Resistance (Approx.)	104000	90000	110000	ohms
Transconductance	1500	2300	2100	μ mhos
Load Resistance	12000	7600	9000	ohms
Total Harmonic Distortion	11	11	15	per cent

0.35

mA watts

megohms

2.2

6K7

6K11/6Q11

TYPICAL PUSH-PULL OPERATION (Values are for two tubes) Fix B	xed Cathode ias Bias	
Plate Supply Voltage 2	85 285	volts
	85 285	volts
Grid-No.1 Voltage	5.5 —	volts
Cathode-Bias Resistor	400	ohms
Peak AF Grid-No.1-to-Grid-No.1 Voltage	51 51	volts
Zero-Signal Plate Current	55 55	mA
	72 61	mA
Zero-Signal Grid-No.2 Current	9 9	mA
	17 13	mA
Effective Load Resistance (Plate-to-plate) 1200	00 12000	ohms
Total Harmonic Distortion	6 4	per cent
Maximum-Signal Power Output 10	.5 9.8	watts
CHARACTERISTICS (Triode Connection)*		
Plate Voltage		volts
Grid-No.1 Voltage		volts
Plate Current		mΑ
Transconductance		μ mhos
Amplification Factor		
Plate Resistance (Approx.)		ohms
Grid-No.1 Voltage (Approx.) for plate current of 0.5 mA	48	volts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation		megohm megohm
* Grid-No.2 connected to plate.		
Vertical Deflection Amplifier (Triode Conne For operation in a 525-line, 30-frame syste		
MAXIMUM RATINGS		
	. 315	volts
Peak Positive-Pulse Plate Voltage# (Absolute maximum)		volts
Peak Negative-Pulse Grid-No.1 Voltage		volts
Peak Cathode Current		mA.
Average Cathode Current		mA
- ***CLBEC - OBUBUIC - OBLICHU	. 20	11122

MAXIMUM CIRCUIT VALUE

Average Cathode Current
Plate Dissipation

Grid-No.1-Circuit Resistance, for cathode-bias operation

Refer to chart at end of section.	6K7G 6K7GT
Refer to chart at end of section.	6K8 6K8G 6K8GT
Refer to chart at end of section.	6K11

^{*} Grid No.2 connected to plate.

[#] Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).


Onder no circumstances should this absolute value be exceeded.

6KA8

Positive-bias value Negative-bias value

HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in color and black-and-white television receivers. The triode unit is used in sync-separator circuits; the pentode unit has two independent control grids and is used in gated-agc-amplifier and noise-inverter circuits. Outlines section, 6E; requires miniature 9-contact socket. For curves of average plate characteristics for triode unit, refer to type 6AW8A.




QDV


volts volts


plate characteristics for triode unit, refer to type 6AW8A. Type 8KA8 is identical with type 6KA8 except for heater ratings.

	6KA8	8KA8	
Washing Williams (a. (1.)			
Heater Voltage (ac/dc)	6.3	8.4	volts
Heater Current Heater Warm-up Time (Average)	0.6	0.45	ampere
Hester Warm-up Time (Average)	11	11	seconds
Heater-Cathode Voltage:			Seconds
Peak value	±200 max	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances:	200 11142	200 max	10103
Triode Unit:			
Grid to Plate		2.2	рF
Grid to Cathode, Heater, and Internal Shield		2.8	pF
Plate to Cathode, Heater, and Internal Shield			
		2.2	рF
Pentode Unit:			
Grid No.1 to Plate		0.1 max	рF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.	2		P^
and Internal Chieff	,	0.5	-
and Internal Shield		9.5	$\mathbf{p}\mathbf{F}$
Grid No.1 to Grid No.3		0.5	pΓ
Grid No.3 to Plate		2.2	рF
Grid No.3 to All Other Electrodes, Heater, and Inte	aunal Chield	7.7	
Grid No.5 to All Other Electrodes, Heater, and The	ernar Smeld	1	рF
Class A, Amplifie	r		
	-		
MAXIMUM RATINGS (Design-Maximum Values)		Triode Unit	
			- 14
		300	volts
Grid Voltage:			
Positive-bias value		0	volts
Negative-bias value		50	volts
Plate Dissipation		1.1	watts
CHARACTERISTICS	m . 1 v		
CHARACTERISTICS	Triode Unit	Pentode Unit	
Plate Supply Voltage	200	150	volts
Grid-No.3 Supply Voltage		Ŏ	volts
Grid-No.2 Supply Voltage			
		100	volts
Grid-No.1 Supply Voltage	2	0	volts
Cathode-Bias Resistor Amplification Factor		180	ohms
Amplification Factor	70	100	OHILIS
Distribution (A			
Plate Resistance (Approx.)	17500	100000	ohms
Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate	4000	4400	μ mhos
Transconductance, Grid No.3 to Plate		600	μmhos.
Plate Current	4	4	mA
Collina de Company	*		
Grid-No.2 Current		2.8	mA
Grid-No.1 Supply Voltage (Approx.):			
For plate current of 10 µA	5		volts
For plate current of 20 μA		4	volts
Colline of 1 37 1		4	VOICE
Grid No.3 Supply Voltage (Approx.) for plate current			
of 20 μA	_	7	volts
MAXIMUM CIRCUIT VALUES		Triode Unit	
Grid-Circuit Resistance:			
For fixed-bias operation		0.25	megohm
For cathode-bias operation		1	megohm
			-
Gated AGC Amplifier and No	ice Inverter		
dated Ado Ampinier and No.	130 111101101		
MAXIMUM RATINGS (Design-Maximum Values)	D	entode Unit	
DC Plate Voltage		300	volts
Peak Positive-Pulse Plate Voltage#		600	volts
Grid-No.3 (Control-Grid) Voltage:			
Positive biog velve		^	14
Positive-bias value		0	volts
Negative-bias value		100	volts
Grid-No.2 (Screen-Grid) Supply Voltage		300	volts
Grid-No 2 Voltage		See curve	
Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage:		see curve	PERC DOG
Positive-hiss value		0	volte

Plate Dissipation	2	watts
For grid-No.2 voltages up to 150 volts		watts curve page 300
MAXIMUM CIRCUIT VALUES Grid-No.3-Circuit Resistance Grid-No.1-Circuit Resistance:	0.68	megohm
For fixed-bias operation For cathode-bias operation	0.5 1	megohm megohm
# Pulse duration must not exceed 15% of a horizontal scanning cycl	e (10	microseconds).







12**GW**

BEAM POWER TUBE

6KD6

36KD6/40KD6

30KD6, 36KD6/40KD6

Duodecar type used as horizontal-deflection amplifier in television receivers. Outlines section, 16C; requires duodecar 12-contact socket. Types 30KD6 and 36KD6/40KD6 are identical with type 6KD6 except for heater ratings.

30KD6

Heater Voltage	6.3	30	36	volts
Heater Current	2.85	0.6	0.45	amperes
Heater Warm-up Time		11	11	seconds
Heater-Cathode Voltage:				
Peak value	$\pm 200~\mathrm{max}$	$\pm 200 \text{ max}$	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances:				
Grid No.1 to Plate			0.8	рF
Grid No.1 to Cathode, Heater, Grid N	lo.2, and Grid	No.3	40	pF
Plate to Cathode, Heater, Grid No.2	, and Grid No	o . 3	16	pF
Horizontal-	Deflection A	mnlifier		
For operation in				
For operation in	a 525-line, 30-			
For operation in MAXIMUM RATINGS (Design-Maximum \DC Plate Supply Voltage	a 525-line, 30- /alues)	frame system	990	volte
For operation in MAXIMUM RATINGS (Design-Maximum \ DC Plate Supply Voltage Plate Voltage#	a 525-line, 30- /alues)	frame system	990 7000	volts volts
For operation in : MAXIMUM RATINGS (Design-Maximum \ DC Plate Supply Voltage	a 525-line, 30- /alues)	frame system	7000	volts
For operation in MAXIMUM RATINGS (Design-Maximum \ DC Plate Supply Voltage Peak Positive-Pulse Plate Voltage# Positive DC Grid-No.3 Voltage Grid-No.2 Voltage	a 525-line, 30- /alues)	frame system		
For operation in MAXIMUM RATINGS (Design-Maximum \ DC Plate Supply Voltage Peak Positive-Pulse Plate Voltage# Positive DC Grid-No.3 Voltage Grid-No.2 Voltage Peak Negative-Pulse Grid-No.1 Voltage	a 525-line, 30- /alues)	frame system	7000 20	volts volts
For operation in MAXIMUM RATINGS (Design-Maximum \ DC Plate Supply Voltage Peak Positive-Pulse Plate Voltage# Positive DC Grid-No.3 Voltage Grid-No.2 Voltage Peak Negative-Pulse Grid-No.1 Voltage Peak Cathode Current	a 525-line, 30- /alues)	frame system	7000 20 200	volts volts volts
For operation in MAXIMUM RATINGS (Design-Maximum \ DC Plate Supply Voltage Peak Positive-Pulse Plate Voltage# Positive DC Grid-No.3 Voltage Grid-No.2 Vcltage Peak Negativc-Pulse Grid-No.1 Voltage Peak Cathode Current Average Cathode Current	a 525-line, 30- /alues)	frame system	7000 20 200 250	volts volts volts volts
For operation in MAXIMUM RATINGS (Design-Maximum \ DC Plate Supply Voltage Peak Positive-Pulse Plate Voltage# Positive DC Grid-No.3 Voltage Grid-No.2 Voltage Peak Negative-Pulse Grid-No.1 Voltage Peak Cathode Current Average Cathode Current Plate Dissipation*	a 525-line, 30- /alues)	frame system	7000 20 200 250 1 40 0	volts volts volts volts mA
For operation in MAXIMUM RATINGS (Design-Maximum \ DC Plate Supply Voltage Peak Positive-Pulse Plate Voltage# Positive DC Grid-No.3 Voltage Grid-No.2 Vcltage Peak Negativc-Pulse Grid-No.1 Voltage Peak Cathode Current Average Cathode Current	a 525-line, 30- /alues)	frame system	7000 20 200 250 1400 400	volts volts volts volts mA mA

6KD6

Class A. Amplifier

CHARACTERISTICS	Triode† Connection	Pentod Connec		
Plate Voltage	150	60	150	volts
Grid No.3 (Suppressor Grid)	Con	nected to	cathode	at socket

Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage Amplification Factor	150 —22.5	110 0	110 22.5	volts volts
Plate Resistance (Approx.) Transconductance		Ξ	6000 14000	ohms µmhos
Plate Current Grid-No.2 Current		750 = 42 = =	120 1.8	m A m A
Grid-No.1 Voltage (Approx.) for plate current of 1.0 µA		_	-40	volts
MAXIMUM CIRCUIT VALUE Grid-No.1-Circuit Resistance			2.2	megohms
Grid-No.3-Circuit Resistance			0.01	megohm

- A bias resistor or other means is required to protect the tube in absence of excitation. # Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). †Grid-No.2 connected to plate at socket.
- •• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

6KD8

For replacement use type 6U8A/6KD8.

6KE8

MEDIUM-MU TRIODE—SHARP-CUTOFF PENTODE

Miniature type with frame-grid pentode unit used as combined oscillator-mixer tube in television receivers using an intermediate frequency in the order of 40 MHz. Outlines section, 6B; requires miniature 9-contact socket. Types 4KE8 and 5KE8 are identical with type 6KE8 except for heater ratings.



	4 K E 8	DKES	ONES	
Heater Voltage (ac/dc)	4.5	5.6	6.3	volts
Heater Current	0.6	0.45	0.4	ampere
Heater Warm-up Time (Average)	11	11		seconds
Heater-Cathode Voltage:				
Peak value	±200 max	$\pm 200 \text{ max}$	±200 max	volts
Average value	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances:				
Triode Unit:				
Grid to Plate			1.3	рF
Grid to Cathode, Heater, Pentode Cathode, Pe				
and Internal Shield			2.4	\mathbf{pF}
Plate to Cathode, Heater, Pentode Cathode, P	entode Grid	No.3,		_
and Internal Shield			2	рF
Pentode Unit:				_
Grid No.1 to Plate			0.015 max	рF
Grid No.1 to Cathode, Heater, Grid No.2, Gr				_
and Internal Shield			5	рF
Plate to Cathode, Heater, Grid No.2, Grid N				_
and Internal Shield			3.4	$\mathbf{p}\mathbf{F}$
Heater to Triode Cathode and Pentode Cathode			5.5	рF
† With external shield connected to cathode of un	it under tes	t, except as	noted.	


† With external shield connected to cathode of unit under test, except as noted.


With external shield connected to ground.

Class A. Amplifier

MAXIMUM RATINGS (Design-Maximum Values)		Pentode Unit	
Plate Voitage	280	280	volts
Grid-No.2 (Screen-Grid) Supply Voltage		280	volts
Grid-No.2 Voltage	Se	e curve page 300	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	0	volts
Cathode Current	20	20	mA.
Plate Dissipation	2	2	watts
Grid-No.2 Input:			
For grid-No.2 voltages up to 140 volts		0.5	watt
For grid-No.2 voltages between 140 and 280 volts	Se	e curve page 300	
CHARACTERISTICS			
Plate Supply Voltage	125	125	volts
Grid-No.2 Supply Voltage		125	volts
Grid-No.1 Supply Voltage	0	0	volts
Cathode-Bias Resistor	68	33	ohms
Amplification Factor	40		
Plate Resistance (Approx.)	5000	125000	ohms
Transconductance	8000	12000	μ mhos

Plate Current	13	10	mA
Grid-No.2 Current		2.8	mA
Grid-No.1 Voltage (Approx.):			4
For plate current of 100 μA	5		volts
For plate current of 50 μA		3	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
For fixed-bias operation	0.5	0.25	megohm
For cathode-bias operation	1	0.5	megohm





POWER PENTODE

6KG6A/ EL509

40KG6A/

40KG6A/PL509



Magnoval type used as a horizontal-deflection amplifier in color television receivers. Outlines section, 38A; requires 9-contact magnoval socket. Type 40KG6A/PL509 is identical with type 6KG6A/EL509 except for heater ratings.

6KG6A/

Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage Direct Interelectrode Capacitances: Plate to Grid-No.1 Grid-No.1 to Heater	EL509 6.3 2 250 2.5 0.2	PL509' 40 0.3	volts amperes volts pF pF
Class A ₁ Amplifier			
CHARACTERISTICS			
Plate Voltage Grid-No.3 Voltage‡ Grid-No.2 Voltage Grid-No.1 Voltage Plate Current ^a Grid-No.2 Current ^a	45 0 160 0 1000 (min.)	160 0 160 0 1400 45	volts volts volts volts mA mA
Horizontal-Deflection Am	plifier		
For operation in a 525-line, 30-fra	ame system		
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Supply Voltage Peak Positive-Pulse Plate Voltage* Grid-No.2 Voltage (zero-current) Grid-No.2 Voltage Plate Dissipation (Absolute-Maximum Value) Grid-No.2 Input Cathode Current		700 7000 700 250 34 7 500	volts volts volts volts watts watts mA

MAXIMUM CIRCUIT VALUES

Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.25 2.2	megohm megohms
! In horizontal-deflection service, 15 volts may be applied to grid-No.3	to minimiz	e eniveta

These values can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

* Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).


6KL8

Refer to chart at end of section.



BEAM POWER TUBE


Novar type used as horizontal-deflection amplifier in color and black-and-white television receivers. Outlines section, 18A; requires novar 9-contact socket. Type 22KM6 is identical with type 6KM6 except for heater ratings.




Heater Voltage (ac/dc) 6	.M6 3.3 6	22KM6 22 0.45 11	volts amperes seconds
Heater-Cathode Voltage:			5000.145
		±200 max 100 max	volts volts
Direct Interelectrode Capacitances:		200	******
Grid No.1 to Plate		1.2	рF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3		22	pF
Plate to Cathode, Heater, Grid No.2, and Grid No.3		9	pF

Class A, Amplifier

	Triode				
CHARACTERISTICS	Connection	Pentode Connection			
Plate Voltage	140		60	140	volts
Peak Positive-Pulse Plate Voltage**	-	6500	_		volts
Grid-No.3 (Suppressed-Grid) Voltage .	0	30	30	30	volts
Grid-No.2 (Screen-Grid) Voltage	140	140	140	140	volts
Grid-No.1 (Control-Grid) Voltage	-24.5		0	24.5	volts
Amplification Factor	4		_		
Plate Resistance (Approx.)	-			6000	ohms
Transconductance			_	9500	μ mhos
Plate Current	_		560††	80	mA
Grid-No.2 Current			31††	2.4	mA
Grid-No.1 Voltage for plate current					
of 1 mA		110	_	42	volts





Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

770	volts
	volts
	mA
	mA
	watts
	watts
240	$^{\circ}\mathrm{c}$
	megohm
10	megohms
	770 6500 1500 75 220 330 950 275 3.5 20 240

- # Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). † With grid No.3 and grid No.2 connected, respectively, to cathode and plate at socket. †† This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.
- In this service, a positive value may be applied to grid No.3 to minimize "snivets" interference; a typical value for this voltage is 30 volts.
- •• A bias resistor or other means is required to protect the tube in absence of excitation.



DIODE—SHARP-CUTOFF THREE-PLATE TETRODE

6KM8

volts

Miniature type used in frequency-divider and complexwave generator circuits of electronic musical instruferm ments. In such circuits the tetrode unit can provide three independent output-signal voltages; the diode unit can be used as a key in a vibrato circuit. Outlines section, 6E; requires miniature 9-contact socket.


Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage:	6.3 0.3	volts ampere
Peak value	±200 max	volts
Average value	100 max	volts
Direct Interelectrode Capacitances:	100 max	VOILS
Tetrode Unit:		
Grid No.1 to Plate No.1A	0.02 max	рF
Grid No.1 to Plate No.1B	0.02 max	pF
Grid No.1 to Plate No.2	0.06 max	pF
Grid No.1 to Cathode, Heater, Grid No.2, and Internal Shield	5.5	pF
Plate No.1A to Cathode, Heater, Grid No.2, and Internal Shield	1.2	pF
Plate No.1B to Cathode, Heater, Grid No.2, and Internal Shield	1.3	ρF
Plate No.2 to Cathode, Heater, Grid No.2, and Internal Shield	1.8	pF
Tetrode Grid No.1 to Diode Plate	0.024 max	pF
Tetrode Plate No.1A to Diode Plate	0.18	pF
Tetrode Plate No.1B to Diode Plate	0.024	pF
Tetrode Plate No.2 to Diode Plate	0.013	pF
Tetrode Unit as Class A. Amplifier Plates No. 1A, 1B, and 2 connected together		
CHARACTERISTICS		
Plate Voltage	100	volts
Grid-No.2 Voltage	100	volts
Grid-No.1 Supply Voltage	0	volts
Grid-No.1 Resistor (Bypassed)	2.2	megohms
Plate Resistance (Approx.)	30000	ohms
Transconductance	3400	μmhos
Plate Current	4.2	mA
Grid-No.2 Current	1.7	mA


Grid-No.1 Voltage (Approx.) for plate current of 20 µA

Triode Connection-Plates No.1A, 1B, a	nd 2 con	nected to	erid No	. 2
Plate Voltage			100	volts
Grid-No.1 Supply Voltage			0	voits
Grid-No.1 Resistor (Bypassed)			2.2	megohms
Transconductance			4500	μmhos
Amplification Factor			45	μιιιοε
Plate Current			5.5	m.A
Separate-plate operation; plates n	ot under	test grou	ınded	
Plate	1 A	1B	2	
Plate Voltage	100	100	100	volts
Grid-No.2 Voltage	100	100	100	volts
Grid-No.1 Supply Voltage	0	0	Ô	volts
Grid-No.1 Resistor (Bypassed)	2.2	2.2	2.2	megohms
Transconductance	2000	2000	1800	μmhos
Plate Resistance (Approx.)	0.1	0.1	0.12	megohn
Plate Current	2.3	2.3	2.1	m.A
Grid-No.2 Current	3.8	3.8	3.3	mA
Tetrode Unit as Frequency Divider a	nd Comi	olex-Wav	e Gener	ator
MAXIMUM RATINGS (Design-Maximum Values)				
Plate Voltage (Each plate)			330	volts
Grid-No.2 (Screen-Grid) Supply Voltage			330	volts
Grid-No.2 Voltage				ve page 300
Grid-No.1 (Control-Grid) Voltage:			Dec eur	ve page ove
Positive-bias value			0	volts
Negative-bias value			50	volts
Plate Dissipation (Each plate)			ĭ	watt
Grid-No.2 Input:			-	
For grid-No.2 voltages up to 165 volts			0.65	watt
For grid-No.2 voltages between 165 and 330 vol				ve page 300
MAXIMUM CIRCUIT VALUE		· · · · · •	200 041	
Grid-No.1-Circuit Resistance, for grid-No.1-resistor	-hine one	ration	2.2	megohms
dild-140.1-Offcuit Mesistance, for Rild-140.1-resistor	-nies obe	TOTION	4.4	megonina

Diode Unit

MAXIMUM RATINGS (Design-Maximum Values)		
Plate Current	1	mA.
CHARACTERISTICS, Instantaneous Value		
Tube Voltage Drop for plate current of 2 mA	10	volts






6KN6

BEAM PENTODE

Duodecar type used as horizontal-deflection amplifier in color and black-and-white television receivers. Outlines section, 39B; requires duodecar 12-contact socket. Type 42KN6 is identical with type 6KN6 except for heater ratings.



12**GU**

Heater Arrangement Heater Voltage Heater Current Heater Warm-up Time	6.3	42KN6 Series 42 0.45 11	volts ampere seconds
Heater-Cathode Voltage: Peak value Average value	±200 max	±200 max	volts
	100 max	100 max	volts

Class A. Amplifier

CHARACTERISTICS	Triode* Connection	Pento	de Conne	ection	
Plate Voltage	130	5500	60	130	volts
Grid-No.2 (Screen-Grid) Voltage	130	125	125	130	volts
Grid-No.1 (Control-Grid) Voltage	20		0	20	volts
Plate Resistance		_		4000	ohms
Transconductance		-		16000	μmhos
Plate Current		-	800*	100	mA
Grid-No.2 Current	_		50▲	4	mA
Grid-No.1 Voltage (Approx.) for plate current of 1 mA	_	_		33	volts
Grid-No.1 Voltage (Approx.) for plate current of 75 μA		100		_	volts
Amplification Factor	4.5	-		_	

^{*}This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system


MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Supply Voltage	770	volts
Peak Positive-Pulse Plate Voltage#	6500	volts
Peak Negative-Pulse Plate Voltage	1500	volts
Grid-No.2 Voltage	220	volts
Peak Negative-Pulse Grid-No.1 Voltage	330	volts
Average Cathode Current	400	mA
Peak Cathode Current	1500	mA
Plate Dissipation•	30	watts
Grid-No.2 Input	5	watts
Bulb Temperature (At hottest point)	260	*C
MAXIMUM CIRCUIT VALUE		

Grid-No.1-Circuit Resistance 1

Refer to chart at end of section.

6KN8/6RHH8

megohm



MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6KR8

Miniature type used in television receiver applications. The triode unit is used as a general-purpose amplifier; the pentode unit is used as a video amplifier. Outlines section, 6E; requires miniature 9-contact socket. Type 10KR8 is identical with type 6KR8 except for heater ratings.

arr The

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	6.3 0.75	10.5 0.45 11	volts ampere seconds
Heater-Cathode Voltage: Peak value Average value	±200 max	±200 max	volts
	100 max	100 max	volts

^{*} Grid No.2 connected to plate.

[#] Pulse duration must not exceed 15% of one horizontal scanning cycle (10 microseconds).

• A bias resistor or other means is required to protect the tube in absence of excitation.

Class A, Amplifier

oraco ra rampa				
MAXIMUM RATINGS (Design-Maximum Values)		de Unit	Pentode Unit	
Plate Voltage			330	volts
Grid-No.2 (Screen-Grid) Supply Voltage		330	330	volts
Grid-No.2 Voltage			e curve page 30	
Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value		0	0	volts
Plate Dissipation		2	5	watts
Grid-No.2 Input:		2	5	Watts
For voltages up to 165 volts			1.1	watts
For voltages between 165 and 330 volts		— See	e curve page 30	0
CHARACTERISTICS	Trio	de Unit	Pentode Unit	
Plate Supply Voltage	125	35	200	volts
Grid-No.2 Supply Voltage		100	100	volts
Grid-No.1 Voltage	-	Ŏ		volts
Cathode-Bias Resistor	68		82	ohms
Amplification Factor	46		02	Onnie
Plate Resistance (Approx.)	4400	_	60000	ohms
Transconductance	10400		20000	
				μmhos
Plate Current	15	54	19.5	mĄ
Grid-No.2 Current	_	13.5	3	mA
Grid-No.1 Voltage (Approx.) for plate current				
of 10 μA	8	_	-	volts
Grid-No.1 Voltage (Approx.) for plate current				
of 100 μA	-	_	6.3	volts
MAXIMUM CIRCUIT VALUES				
Grid-No.1-Circuit Resistance:	70	. 3. 77. *4	D 4. 1. 11-14	
			Pentode Unit	
For fixed-bias operation		0.5	0.5	megoḥm
For cathode-bias operation		1	1	megohm

6KS6

For replacement use type 6BN6/6KS6.

OFFE

6KT6 3KT6, 4KT6

SEMIREMOTE-CUTOFF PENTODE

Miniature type with frame grid used as if-amplifier tube in television receivers utilizing an intermediate frequency in the order of 40 MHz. Outlines section, 6B; requires miniature 9-contact socket. Types 3KT6 and 4KT6 are identical with type 6KT6 except for heater ratings.



9PM

cute


ARTE


Heater Voltage (ac/dc)	3.5 0.6 11	4.5 0.45 11	6.3 0.3	volts ampere seconds
Heater-Cathode Voltage: Peak value Average value		±200 max 100 max		
Direct Interelectrode Capacitances: Grid No.1 to Plate		0.0	19 max	pF
Grid No.1 to Cathode, Heater, Grid No.2, Grid Internal Shield		:	9.5	рF
Plate to Cathode, Heater, Grid No.2, Grid No. Internal Shield			3	pF

Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	
Plate Voltage	330 volts
Grid-No.3 (Suppressor-Grid) Voltage	0 volts
Grid-No.2 (Screen-Grid) Supply Voltage	330 volts
Grid-No.2 Voltage	See curve page 300
Grid-No.1 (Control-Grid) Voltage	0 volts
Plate Dissipation	3.1 watts
Grid-No.2 Input:	
For grid-No.2 voltages up to 165 volts	0.6 watt
For grid-No.2 voltages between 165 and 330 volts	See curve page 300

CHARACTERISTICS Plate Supply Voltage	125	170	volts
Grid-No.3 Voltage	0	Ö	volts
Grid-No.2 Supply Voltage	125	170	volts
Cathode-Bias Resistor	56	56	ohms
Plate Resistor	160000		ohms
Transconductance	18000	_	μmhos
Plate Current	17		mA
Grid-No.2 Current	4.2	_	mA
Grid-No.1 Voltage (Approx.) for transconductance of 10 µmhos		22	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	=	0.25	megohm megohm





HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

6KT8

Miniature type used in color and black-and-white television receiver applications. The pentode unit is used as an if-amplifier tube, and the triode unit as a sync-separator or voltage-amplifier tube. Outlines section, 6B; requires miniature 9-contact socket.

	6.3	volts
	0.6	ampere
	$\pm 200~\mathrm{max}$	volts
	100 max	volts
Unshielded	Shielded	
3	3	рF
3.2	3. 2	\mathbf{pF}
1.6	2.4	\mathbf{pF}
0.046 max	0.030 max	\mathbf{pF}
7.5	7.5	рF
2.2	2.8	\mathbf{pF}
0.018 max	0.003 max	\mathbf{pF}
0.006 max	0.002 max	pF
	3 3.2 1.6 0.046 max 7.5 2.2 0.018 max	

Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit	Pentode Unit	
Plate Voltage	330	330	volts
Grid-No.2 (Screen-Grid) Supply Voltage		330	volts
Grid-No.2 Voltage	Sec	curve page 300	

Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation	0 1	0 2.5	volts watts
For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330 volts	_	0.55 See curve page	watt e 300
CHARACTERISTICS			
Plate Voltage	250	125	volts
Grid-No.2 Voltage	_	125	volts
Grid-No.1 Voltage	—2	—1	volts
Amplification Factor	100		
Plate Resistance (Approx.)	31500	150000	ohms
Transconductance	3200	10000	μ mh os
Plate Current	1.8	12	mA
Grid-No.2 Current	_	4.5	mA
Grid-No.1 Voltage (Approx.) for plate current of			
20 μΑ	-3.5	7	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
For fixed-bias operation	0.5	0.5	megohm
For cathode-bias operation	1	1	megohm

6KU8

Refer to chart at end of section.

6KV6

Refer to chart at end of section.

17KV6A

16.8

6KV6A 17KV6A. 22KV6A

BEAM POWER TUBE

6KV6A

6.3

Novar type used for high-voltage pulse- or shunt-regulator applications in color television receivers. Outlines section, 31D; requires novar 9-contact socket. Types 17KV6A and 22KV6A are identical with type 6KV6A except for heater ratings.



9QU

volts

22KV6A

22

Heater Current Heater Warm-up Time	1.6	0.6 11	0.45 11	amperes seconds
Heater-Cathode Voltage: Peak value	+200 max	+200 max -500 max 100 max	+200 max 500 max 100 max	volts volts
Average value Direct Interelectrode Capacitances (Approx.): Grid No.1 to Plate	100 max	0.6		pF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3		22	2	pF
and Grid No.3		;)	рF
Class A ₁ A	mplifier			
CHARACTERISTICS				
Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage Triode Amplification Factor# Plate Resistance (Approx.)			140 0 140 24.5 4 10000	volts volts volts volts ohms
Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage for plate current of 1 mA	 	440 = 30 =	6000 40 2.4 —42	μmhos mA mA volts

High-Voltage-Pulse Shunt Regulator For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum	ı Values))
---------------------------------	-----------	---

Heater Voltage (ac/dc)

DC Plate Supply Voltage (Ib = 0 mA)	900	volts
Peak Positive-Pulse Plate Voltage	6500	volts


megohm

Peak Negative-Pulse Plate Voltage	1500	volts
Peak Positive-Pulse Grid-No.2 Voltage	600	volts
DC Grid-No.3 Voltage	75	volts
DC Grid-No.2 Voltage	220	volts
DC Grid-No.1 Voltage, Negative-bias value	250	volts
Peak Negative-Pulse Grid-No.1 Voltage	330	volts
Peak Cathode Current	950	mA
Average Cathode Current	275	mA
Plate Dissipation1	28●	watts
Grid-No.2 Input	2	watts
Bulb Temperature (At hottest point)	240	$^{\circ}\mathrm{c}$
MAXIMUM CIRCUIT VALUE		

MAXIMUM CIRCUIT VALUE Grid-No.1-Circuit Resistance:

* This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

- A Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). ‡ Adequate circuit precautions must be taken to protect the tube in the absence of grid-No.1 bias.
- Plate dissipations up to 32 watts maximum are permissible for short periods of time provided the maximum envelope-temperature rating is not exceeded. This condition may exist under high-line voltage, zero picture tube beam current.



HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

6KV8

- See curve page 300

Miniature type with frame-grid pentode unit used in black-and-white television receivers. The triode unit is used in general-purpose voltage-amplifier, sync-separator, and sound-if-amplifier applications. The pentode unit is used as a video-output tube. Outlines section, 6E; requires miniature 9-contact socket. For curves of

average plate characteristics for triode unit, refer to type 6AW8A. Type 11KV8 is identical with type 6KV8 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage: Peak value Average value	6KV8 6.3 0.775 — ±200 max 100 max	11KV8 10.9 0.45 11 ±200 max 100 max	volts ampere seconds volts volts
Direct Interelectrode Capacitances (Approx.):			
Triode Unit: Grid to Plate		3.7	рF
Grid to Cathode, Heater, Pentode Cathode, Pentod and Internal Shield		2.5	рF
Plate to Cathode, Heater, Pentode Cathode, Pentod	de Grid No.3.		
and Internal Shield		2.4 0.015 max	рF
Pentode Unit: Grid No.1 to Plate		0.12 max	рF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.	o.3, and	***************************************	-
Internal Shield	and	13	\mathbf{pF}
Internal Shield		4.8	рF
Pentode Plate to Triode Plate		0.17 max	\mathbf{pF}
Class A, Amplific	er		
MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit P	entode Unit	
Plate Voltage	300	300	volts
Grid-No.2 (Screen-Grid) Supply Voltage	_	300	volts
Grid-No.2 Voltage		curve page 300	_
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	ō	volts
Plate Dissipation	1	5	watts
Grid-No.2 Input: For Grid-No.2 voltages up to 150 volts		1	watt
rot Giratio, 2 volumes up to 150 volus		4	wall

For Grid-No.2 voltages between 150 and 300 volts

Triode Unit Pentode Unit

0.1


0.25

megohm

megohm

0.5

CHARACTERISTICS	Triode U	nit Pen	tode Unit	
Plate Supply Voltage	200	125	200	volts
Grid-No.2 Supply Voltage		125	125	volts
Grid-No.1 Supply Voltage	2	0	0	volts
Cathode-Bias Resistor		82	68	ohms
Amplification Factor	70		_	
Plate Resistance (Approx.)	17500	55000	75000	ohms
Transconductance	4000	21000	23000	μmhos
Plate Current	4	16.5	20	mA
Grid-No.2 Current	_	3.1	3.5	mA
Grid-No.1 Voltage (Approx.) for plate current of				
100 μΑ	4.5	-4.2	-4.2	volts
MAXIMUM CIRCUIT VALUES				



6KY6

Grid-No.1-Circuit Resistance:

For fixed-bias operation

For cathode-bias operation

Refer to chart at end of section.


6KY8

Refer to chart at end of section.

6KY8A

HIGH-MU TRIODE— BEAM POWER TUBE

Novar type used in combined vertical-deflection-oscillator and vertical-deflection-amplifier applications in black-and-white television receivers having low-voltage "B" supplies. Outlines section, 30A; requires novar 9-contact socket. Type 15KY8A is identical with type 6KY8A except for heater ratings.




Heater Voltage (ac/dc)	6KY8A 6.3	15 KY8A 15	volts
Heater Current	1.1	0.45	amperes
Heater Warm-up Time (Average)	-	11	seconds
Peak value	$\pm 200 \text{ max}$	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances (Approx.): Triode Unit:			
Grid to Plate		0.44	рF
Grid to Cathode and Heater		16	pF
Plate to Cathode and HeaterPentode Unit:		้า	pF
Grid No.1 to Plate		0.048	рF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No. Plate to Cathode, Heater, Grid No.2, and Grid No.3		2.6 0.28	pF pF

Class	Δ	Δmn	lifier

CHARACTERISTICS	Triode Unit	В	eam Powe	r Unit	•
Plate Voltage	250	50	135	120	volts
Grid-No.2 (Screen-Grid) Voltage		120	120	*	volts
Grid-No.1 (Control-Grid) Voltage	3	0	—10	—10	volts
Amplification Factor	64		_	7	
Plate Resistance (Approx.)	40000	_	18000	_	ohms
Transconductance	1600		8400	_	μ mhos
Plate Current	1.4	170•	39	_	mA
Grid-No.2 Current		20•	3		mA
Grid-No.1 Voltage (Approx.) for plate					
current of 1 mA	-	_	24	_	volts

- Triode connection, grid No.2 connected to plate at socket.
- $^{\bullet}$ This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.



Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit Oscillator	Beam Power Unit Amplifier	
DC Plate Voltage	330	300	volts
(Absolute Maximum)	_	2200†	volts
DC Grid-No.2 Voltage	_	150	volts
Peak Negative-Pulse Grid-No.1 Voltage	400	250	volts
Peak Cathode Current	77	200	mA
Average Cathode Current	22	60	mA
Plate Dissipation	1.5	12	watts
Grid-No.2 Input	_	1.9	watts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			

Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds). † Under no conditions should this maximum value be exceeded.



9FZ

For grid-resistor-bias operation

MEDIUM-MU TRIODE---SHARP-CUTOFF PENTODE

6KZ8 5KZ8, 9KZ8

megohms

2.2

Miniature type used as combined oscillator and mixer in vhf color and black-and-white television receivers. Outlines section, 6B; requires miniature 9-contact socket. Types 5KZ8 and 9KZ8 are identical with type 6KZ8 except for heater ratings.

2.2

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage: Peak value Average value		6KZ8 6.3 0.45 11 ±200 max 100 max	9KZ8 9.45 0.3 11 ±200 max 100 max	volts ampere seconds volts volts
Direct Interelectrode Capacitances:*				
Triode Unit: Grid to Plate			1.6	pF
Grid to Triode Cathode, Pentode Cathode, No.3, and Heater	Heater, Pent	ode Grid	3.2	ρF
Plate to Triode Cathode, Pentode Cathode, No.3, and Heater			1.8	p F
Pentode Unit: Grid No.1 to Plate			0.01 max	p F
Grid No.1 to Cathode, Heater, Grid No.2, Internal Shield	Grid No.3,	and	5.5	рF
Plate to Cathode, Heater, Grid No.2, Grid Internal Shield	No.3, and		3.4 3.2#	pF pF
With automal chiefd connected to eathede				

- * With external shield connected to cathode.
- # With external shield cornected to ground.

Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Triode Uni	t Pentode Uni	t
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage		330 330	volts volts
Grid-No.2 Voltage Grid No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation	0 2.5	See curve page 0 2.5	300 volts watts
Grid-No.2 Input: For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330 volts		0.55 See curve page	watt
CHARACTERISTICS	,	occ carve page	
Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage	125 —1	125 125 —1	volts volts volt
Amplification Factor Plate Resistance (Approx.) Transconductance	46 5400 8500	200000 7500	ohms µmhos
Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of	13.5	12 4	mA mA
10 µA	8	8	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:	Triode Unit	Pentode Unit	
For fixed-bias operation	0.25 0.5	0.25 0.5	megohm megohm


6L5G

Refer to chart at end of section.

6L6 6L6GC

BEAM POWER TUBE

Metal type 6L6 and glass octal type 6L6GC are used in the output stage of audio amplifying equipment, especially units designed to have ample reserve of power-delivering ability. Outlines section, 4 and 19D, respectively; require octal socket. These tubes, like other power-handling tubes, should be adequately ventilated. Type 6L6GC can be used in place of type 6L6 and may be supplied with pin 1 omitted.



* With pin 1 connected to pin 8.

Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage: Peak value Average value	6L6	6.3 0.9 6L6GC ±200 max 100 max	volts ampere volts volts
Direct Interelectrode Capacitances (Approx.): Grid No.1 to Plate	0.4*	0.6	pF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3	10*	10	pF
Plate to Cathode, Heater, Grid No.2, and Grid No.3	12*	6.5	pF

Class A, Amplifier

MAXIMUM RATINGS	Desig	6L6 gn-Center Values	6L6GC Design Ma Values	aximum
Plate Voltage		360 270	500 450▲	volts volts
Plate Dissipation Grid-No.2 Input		19 2.5	30 5	watts watts
TYPICAL OPERATION				
Plate Voltage	250	300	350	volts
Grid-No.2 Voltage	250	200	250	volts
Grid-No.1 (Control-Grid) Voltage	-14	-12.5	18	volts
Peak AF Grid-No.1 Voltage	14	12.5	18	volts
Zero-Signal Plate_Current	72	48	54	mĄ
Maximum-Signal Plate Current	79	55	66	mĄ
Zero-Signal Grid-No.2 Current	_ 5	2.5	2.5	mA
Maximum-Signal Grid-No.2 Current	7.3	4.7	7	,mA
Time reconstance (represent)	22500	35000	33000	oḥms
Transconductance	6000	5300	5200	μmhos
Load Resistance	2500	4500	4200	ohms
Total Harmonic Distortion	10	11	15	per cent
Maximum-Signal Power Output	6.5	6.5	10.8	watts

 $^{^{\}rm A}$ In push-pull circuits where grid No.2 of each tube is connected to a tap on the plate winding of the output transformer, this maximum rating is 500 volts.

Class A. Amplifier (Triode Connection)†


MAXIMUM RATINGS	Design- Center Values		
Plate Voltage	275	450	volts
Plate Dissipation (Total)	19	30	watts
TYPICAL OPERATION			
Plate Voltage		250	volts
Grid-No.1 Voltage		20	volts
Peak AF Grid-No.1 Voltage		20	volts
Zero-Signal Plate Current		40	mA
Maximum-Signal Plate Current		44	mA
Plate Resistance (Approx.)		1700	ohms
Amplification Factor		8	
Transconductance		4700	μmhos
Load Resistance		5000	ohms
Total Harmonic Distortion		5	per cent
Maximum-Signal Power Output		1.4	watts
† Grid No.2 connected to plate.			

Push-Pull Class A, Amplifier

MAXIMUM RATINGS (Same as for Class A₁ Amplifier)

TYPICAL OPERATION (Values are for two tubes)

Plate Voltage	250	270	volts
Grid-No.2 Voltage	250 16	$^{270}_{-17.5}$	volts volts
Peak AF Grid-No.1-to-Grid-No.1 Voltage	3 2	35	volts
Zero-Signal Plate Current	120	134	mA
Maximum-Signal Plate Current	140	155	mA
Zero-Signal Grid-No.2 Current	10	11	mA
Maximum-Signal Grid-No.2 Current	16	17	mA
Effective Load Resistance (Plate-to-plate)	5000	5000	o hms
Total Harmonic Distortion	2	2	per cent
Maximum-Signal Power Output	14.5	17.5	watts



Push-Pull Class AB, Amplifier

MUMIXAM	RATINGS	(Same	as	for	Class	A۱	Amplifier)
MINALIMICAM	MAIMUS	(Junio	uэ	101	Class	\sim	Willburger?

TYPICAL OPERATION (Values are for two tubes)		61.6	6L6GC	
Plate_Voltage	360	360	450	volts
Grid-No.2 Voltage	270	270	400	volts
Grid-No.1 Voltage	-22.5	-22.5	-37	volts
Peak AF Grid-No.1-to-Grid-No.1 Voltage	45	45	70	volts
Zero-Signal Plate Current	88	88	116	mA
Maximum-Signal Plate Current	132	140	210	mA.
Zero-Signal Grid-No.2 Current	5	5	5.6	mA
Maximum-Signal Grid-No.2 Current	15	11	22	mA
Effective Load Resistance (Plate-to-plate)	6600	3800	5600	ohms
Total Harmonic Distortion	2	2	1.8	per cent
Maximum-Signal Power Output	$26.\overline{5}$	18	55	watts

Push-Pull Class AB₂ Amplifier

MAXIMUM RATINGS (Same as for Class A ₁ Amplifier)
TYPICAL OPERATION (Values are for two tubes)	

Plate Voltage	360	360	volts
Grid-No.2 Voltage	225	270	volts
Grid-No.1 Voltage	18	22.5	volts
Peak AF Grid-No.1-to-Grid-No.1 Voltage	52	72	volts
Zero-Signal Plate Current	78	88	mA
Maximum-Signal Plate Current	142	205	mA.
Zero-Signal Grid-No.2 Current	3.5	5	m A
Maximum-Signal Grid-No.2 Current	11	16	mA
Effective Load Resistance (Plate-to-plate)	6000	3800	ohms
Total Harmonic Distortion	2	2	per cent
Maximum-Signal Power Output	31	47	watts

MAXIMUM CIRCUIT VALUES Grid-No. 1-Circuit Resistance:


(ii id-140.1-Circuit itesistance:			
For fixed-bias operation		0.1	megohm
For cathode-bias operatio	n	0.5	megohm

616G Refer to chart at end of section.

616GB Refer to chart at end of section.

6L7 Refer to chart at end of section.

617G Refer to chart at end of section.



12JF

BEAM POWER TUBE

6LB6

Duodecar type used as horizontal-deflection amplifier in color and black-and-white television receivers. Outlines section, 16E; requires duodecar 12-contact socket.

Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage:	6.3 2.25	volts amperes
Peak value Average value Direct Interelectrode Capacitances:	±200 max 100 max	volts volts
Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 Plate to Cathode, Heater, Grid No.2, and Grid No.3	0.44 33 18	pF pF pF

Class A. Amplifier

CHARACTERISTICS	Triode* Connection	Pen	tode Conne	ction	
Peak Positive-Pulse Plate Voltage		5000			volts
Plate Voltage	125	_	50	150	volts
Grid-No.3 (Suppressor Grid)		Conne	cted to cath	ode at sock	et
Grid-No.2 Voltage	125	110	110	110	volts
Grid-No.1 Voltage	25		_	20	volts
Plate Resistance (Approx.)				6600	ohms
Transconductance				13400	μmhos
Plate Current		_	560±	105	mA.
Grid-No.2 Current	_	_	46±	2	mA
Grid-No.1 Voltage (Approx.) for			•		
plate current of 1 mA	_	125		-40	volts
Amplification Factor	4		_	_	

^{*} Grid No.2 tied to plate.

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Supply Voltage	990	volts
Peak Positive Pulse Plate Voltage# (Absolute Maximum Value)	7000	volts
Peak Negative-Pulse Plate Voltage	100	volts
Grid-No.3 Voltage, Positive-bias value	Ò	volts
Grid-No.2 Voltage	200	volts
Peak Negative Grid-No.1 Voltage	300	volts
Peak Cathode Current	1100	mA
Average Cathode Current	315	mA
Plate Dissipation (Absolute Maximum Value)	30	watts
Grid-No.2 Input	5	watts
Bulb Temperature (At hottest point)	200	"°C

MAXIMUM CIRCUIT VALUES

Grid-No.1-Circuit Resistance:

With feedback-type high voltage regulation With shunt-type high voltage regulation (switching mode) Grid-No.3-Circuit Resistance	$1.2 \\ 10 \\ 0$	megohms megohms ohms
--	------------------	----------------------------

[#] Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

[‡] This value may be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

[•] A bias resistor or other means is required to protect the tube in absence of excitation.

6LC8

6LC8

HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in color and black-and-white television receiver applications. Pentode unit is used in noise-immune gated-agc-amplifier circuits, and the triode unit in sync-separator circuits. Outlines section, 6E; requires miniature 9-contact socket. Type 8LC8 is identical with type 6LC8 except for heater ratings. For curves of average plate characteristics, refer to type 6KA8.




Heater Voltage (ac/dc)	6.3	8.4	volts
Heater Current	0.6	0.45	ampere
Heater Warm-up Time (Average)	11	11	seconds
Heater-Cathode Voltage:		1.000	•.
Peak value	±200 max		volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances: Triode Unit:			
Grid to Plate		2.2	рF
Grid to Cathode, Heater, Pentode Grid No.3, and Inte		2.8	ρF
Plate to Cathode, Heater, Pentode Grid No.3, and Inte		2.2	pF
Pentode Unit:			-
Grid No.1 to Plate		0.10 max	pF
Grid No.1 to Cathode, Heater, Grid No.3, Triode Ca	athode, and		=
Internal Shield		10	рF
Grid No.3, Triode Cathode, and Internal Shield to P	late	3.4	рF
Grid No.1 to Grid No.3, Triode Cathode, and Interna	ıl Shield	0.36	pF
Grid No.3, Triode Cathode, and Internal Shield to Plat			
Heater, Grid No.1, and Grid No.2		12.5	рF
Olace A Amulitian	_		
Class A, Amplifier			
MAXIMUM RATINGS (Design-Maximum Values)		Triode Unit	
Plate Voltage		300	volts
Grid Voltage:	· · · · · · · · · · · · · · ·	300	VOILS
Positive-bias value		0	volts
Negative-bias value		50	volts
Plate Dissipation		1.1	watts
	Triode Unit		***************************************
		Pentode Unit	14
Plate Supply Voltage	200	150	volts volts
Grid-No.2 Supply Voltage		100	volts
Grid-No.1 Voltage	— <u>z</u>	180	ohms
Cathode-Bias Resistor	70	180	onns
Amplification Factor Plate Resistance (Approx.)	17500	100000	ohms
Transconductance, Grid No.1 to Plate	4000	4400	μ mh os
Transconductance, Grid No.3 to Plate	4000	600	μmhos
Plate Current	4	4	mA
Grid-No.2 Current		2.8	mA
Grid-No.1 Voltage (Approx.):		2.0	11122
For plate current of 10 μ A	5		volts
For plate current of 20 μ A		-4	volts
Grid-No.3 Voltage (Approx.) for plate current of		•	
20 μA	_	7*	volts
MAXIMUM CIRCUIT VALUES		•	****
		T-1-3- TT-14	
Grid-Circuit Resistance:		Triode Unit	
For fixed-bias operation		0.25	megohm
For cathode-bias operation		1	megohm
* With no external connection to triode plate and triode	grid.		

Gated AGC Amplifier and Noise Inverter

For operation in a 525-line, 30-frame system	l .
MAXIMUM RATINGS (Design-Maximum Values)	Pentode Unit
DC Plate Voltage	300 volts
Peak Positive-Pulse Plate Voltage#	600 volts
Grid-No.3 (Control-Grid) Voltage:	
Positive-bias value	
Negative-bias value	100 volts
Grid-No.2 (Screen-Grid) Supply Voltage	300 volts
Grid-No.2 Voltage	See curve page 300
Grid-No.1 (Control-Grid) Voltage:	
Positive-bias value	0 volts
Negative-bias value	50 volts

Plate Dissipation	2	watts
Grid-No.2 Input: For grid-No.2 voltages up to 150 volts	1.1 See	watts curve page 300
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	$0.5 \\ 1$	megohm megohm
# Pulse duration must not exceed 15% of a horizontal scanning cycle	(10	microseconds).



TWIN PENTODE

6LE8 10LE8, 15LE8

Miniature type used as combined color demodulator and matrix amplifier in color television receivers utilizing high-level demodulation systems. Oùtlines section, 6G; requires miniature 9-contact socket. Types 10LE8 and 15LE8 are identical with type 6LE8 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage: Peak value	6.3 1 0.76 0	LE8 15LE 0.0 15.0 .45 0.3 11 11 300 max	volts ampere seconds volts
Average value Direct Interelectrode Capacitances:	+100		volts
Plate (Each Unit) to All Other Electrodes Grid No.1 to All Other Electrodes		3.7 15.5 6 2.7 0.1	pF pF pF pF
Class A, Amplifi	er		
MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage (Each Unit) Grid-No.2 (Screen-Grid) Voltage Plate Dissipation (Each Unit) Grid-No.2 Input		300 150 2 2	volts volts watts watts
CHARACTERISTICS			
Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.1 (Voltage Grid-No.1 (Control-Grid) Voltage, Negative-bias value Transconductance (Approx.) Plate Resistance (Approx.) Plate Current Grid-No.2 Current Grid-No.1 Voltage for plate current of 20 µA Grid-No.1 Voltage for plate current of 100 µA Grid-No.3 Voltage for plate current of 20 µA Grid-No.3 Voltage for plate current of 100 µA Grid-No.3 Voltage for plate current of 100 µA	G1 Control 100 0 100 2.5 5800 50000 8 157.26.3	Ga Control 100 0 100 2.5 350 50000 7.6 14.5 17.4 16.5	volts volts volts volts µmhos ohms mA volts volts volts
For replacement use type 6LF6/6LX	6.	6LF	6



BEAM POWER TUBE

6LF6/6LX6

Duodecar type used as horizontal deflection amplifier in color television receivers. Outlines section, 16F; requires duodecar 12-contact socket. Type 20LF6 is identical with type 6LF6/6LX6 except for heater ratings.

12GW


Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage	6LF6/ 6LX6 6.3 2.0 ±275 max	20LF6 20 0.6 ±200 max	volts ampere volts
Class A. Amplifie	r		
CHARACTERISTICS			
Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage Plate Current Grid-No.2 Current	50 0 175 10 800 70	160 0 160 0 1400 45	volts volts volts volts mA mA
Horizontal_Deflection An	nplifier		
For operation in a 525-line, 30-fi	rame system		
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage Peak Positive-Pulse Plate Voltage# Plate Dissipation Grid-No.3 Voltage Grid-No.2 Voltage Grid-No.2 Input Beam Plates Circuit Resistor Peak Negative-Pulse Grid-No.1 Voltage Bulb Temperatures		990 8000 40 50 275 9 10000 550 300	volts volts watts volts volts watts ohms volts °C

Pulse duration must not exceed 22% of a horizontal scanning cycle (18 microseconds).

6LF8

HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in video-amplifier stages of color and black-and-white television receivers. Outlines section, 6E; requires miniature 9-contact socket.



Class A Amplifier		
Internal Shield Pentode Grid No.1 to Triode Plate Pentode Plate to Triode Plate	0.008 max 0.15 max	pF pF pF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and	3.6	-
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield	10	pF
Grid No.1 to Plate	0.06 max	рF
and Internal Shield	1.8	pF
and Internal Shield	3.2	$p\mathbf{F}$
Grid to Plate	2.2	pF
Direct Interelectrode Capacitances: Triode Unit:		
Average value	100 max	volts
Heater-Cathode Voltage: Peak value	±200 max	volts
Heater Warm-up Time (Average)	îi	seconds
Heater Current	0.6	ampere
Heater Voltage (ac/dc)	6.3	volts

MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage	Triode Unit Pentode Unit 330 330 330	volts volts
Grid-No.2 Voltage	- See curve page 300	
Positive-bias value	4 0	volts
Negative-bias value	5555	volts mA
Plate Dissipation	1.1 3.75	watts
Grid-No.2 Input:		
For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330 volts	- 1.1 - See curve page 300	watts

CHARACTERISTICS Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Current Grid-No.1 Voltage (Approx.) for plate current of 20 µA	200 	40 3 40 10000 4000 11 2.7	75 150 0 	100 150 2.5 	volts volts volts ohms µmhos mA mA volts
20 25 6RID VOLTS Ec-4 3 3 3 4 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	GRID N	60 PEI	1 1	OLTS = 150	OLTS EC1=0 -1 -2 -1 -3 -4 35 300 400 OLTS 92cs-12398T

MAXIMUM CIRCUIT VALUES


Grid-No.1-Circuit Resistance:
For fixed-bias operation
For cathode-bias operation
This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Refer to chart at end of section. For replacement use type 6LJ6A/6LH6A.

6LH6A

Refer to chart at end of section.

6LJ6



BEAM TRIODE

6LJ6A/ 6LH6A

11

megohms

Glass octal type used for the shunt regulation of highvoltage, low-current power supplies in color and blackand-white television receivers. Outlines section, 21D; requires octal socket. For high-voltage and X-ray safety considerations, refer to page 93.

ting to page to.		
Heater Voltage (ac/dc)	6.3	volts
Heater Current	0.2	ampere
Heater Cathode Voltage + not recommended.	450*	volts
Direct Interelectrode Capacitances:		
Grid to Plate	1	pF
Grid to Cathode and Heater	2.6	ρF
Plate to Cathode and Heater	i	p F pF
* Series impedance should be used with the cathode to limit the cathod prolonged short-circuit conditions to 450 mA.	e current	
Charact Valtage Daniel to Control		

Shunt Voltage-Regulator Service MAXIMUM RATINGS (Design-Maximum Values)

Equivalent Resistance of Unregulated Supply

Plate Voltage	27000	volts
Negative Grid Voltage	135	volts
Peak Negative Grid Voltage	440	volts
Plate Dissipation	40	watta
Average Plate Current	1.5	mA
TYPICAL OPERATION		
Unregulated DC Supply Voltage	26000	ltm

DC Reference Voltage	200	volts
Equivalent Resistance of Reference Supply	1000	ohms
Effective Grid-Plate Transconductance	200	μ mhos
DC Plate Current for Load Current of 0 mA	1000	$\mu \mathbf{A}$
DC Plate Current for Load Current of 1 mA	45	μA volts
Regulated DC Output Voltage for Load Current of 0 mA	25000	
Regulated DC Ouput Voltage for Load Current of 1 mA	24500	volts
MAXIMUM CIRCUIT VALUE		
Grid-Circuit Resistance:		
For use with "Flyback Transformer" high voltage supply	3	megohms
X-RADIATION CHARACTERISTIC		
X-Radiation, Maximum:		
Statistical value controlled on a lot sampling basis	0.5	mR/hr

For interval of 20 seconds maximum during equipment warm-up period.


Caution-Operation of this tube outside of the maximum values indicated above may result in either temporary or permanent changes in the X-radiation characteristic of the tube. Equipment design must be such that these maximum values are not exceeded.

6LJ8

Heater Voltage (ac/dc)

MEDIUM-MU TRIODE-SHARP-CUTOFF PENTODE

Miniature type used as a combined oscillator and mixer in vhf television receivers. Outlines section, 6B; requires 9-contact socket. Types 4LJ8 and 5LJ8 are identical with type 6LJ8 except for heater ratings.



LJ8	
6.3	volts
0.4	ampere
	seconds

Heater Current
Heater Warm-up Time (Average)
Heater-Cathode Voltage:
Peak value 0.6 0.45 re ds ±200 max ±200 max ±200 max volts Average value 100 max 100 max 100 max volts

4.3

5.6

Class A. Amplifier


Oldoo III Illinoi	•		
MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit	Pentode Un	it
Plate Voltage	280	280	volts
Grid-No.2 (Screen-Grid) Supply Voltage		280	volts
Grid-No.2 Voltage		See curve pag	e 300
Cathode Current	20	20	mA
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	0	volts
Plate Dissipation	2	2	watts
Grid-No.2 Input:			
For grid-No.2 voltages up to 140 volts		0.5	watts
For grid-No.2 voltages between 140 and 280 volts		See curve pag	ze 300
CHARACTERISTICS			
Plate Voltage	125	125	volts
Grid-No.2 Voltage		125	volts
Cathode-Bias Resistor	68	33	oh ms
Amplification Factor	40		
Plate Resistance (Approx.)	5000	125000	ohms
Transconductance	8000	13000	μ mhos
Plate Current	13	12	mĄ
Grid-No.2 Current	_	3.5	mA
Grid-No.1 Voltage (Approx.) for plate current of			
30 μA	6.5	4	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
For fixed-bias operation	1	0.5	megohm
For cathode-bias operation	0.5	0.25	megohm

MEDIUM-MU TRIODE-SEMI-**6LM8** REMOTE-CUTOFF PENTODE

Miniature type used in color and black-and-white tele-c2p vision receiver applications. The pentode unit is used in burst-amplifier circuits, and the triode unit as a general-purpose amplifier tube. Outlines section, 6B; requires miniature 9-contact socket.



Heater Voltage (ac/dc)		6.3	volts
Heater Current Heater-Cathode Voltage:		0.45	ampere
Peak value	<i></i>	±200 m	ax volts
Average value		100 m	ax volts
Triode Unit: Grid to Plate Grid to Cathode, Heater, Pentode Cathode, Pentode	Crid No.	1.8	$p\mathbf{F}$
and Internal Shield			$p\mathbf{F}$
and Internal Shield		1.9	pF
Grid No.1 to Plate	No.3. au	0.015 m	ax pF
Internal Shield Plate to Cathode, Heater, Grid No.2, Grid No.3, an		5. 5	р F
Shield Heater to Cathode (Each Unit)		3.8	pF pF
Class A, Amplifier		· · · · ·	7 -
MAXIMUM RATINGS (Design-Maximum Values)	Triode U	nit Pentode U	nit
Plate Voltage	330	350	volts
Grid-No.2 (Screen-Grid) Supply Voltage	_	330 See curve pa	volts
Grid-No.1 (Control-Grid) Voltage, Positive-bias value		ose curve par	ge 300 volts
Plate Dissipation	2.5	2.5	volts
Grid-No.2 Input:			
For grid-No.2 voltages up to 165 volts	-	0.55	watts
For grid-No.2 voltages between 165 and 330 volts	_	See curve pa	ge 300
CHARACTERISTICS			
Plate Voltage	125	125	volts
Grid-No.2 Voltage	_	125	volts
Grid No.1 Voltage	1	2	volts
Amplification Factor	46	150000	
Plate Resistance (Approx.)	5400 8500	150000 6000	ohms
Plate Current	13.5	12	μmhos mA
Grid-No.2 Current	10.0	4	mA
Grid-No.1 Voltage (Approx.) for plate current of		*	11171
10 μA	8	—14	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
For fixed-bias operation	0.5	0.25	megohm
For cathode-bias operation	1	0.5	megohm
	PE 6LM8	1/7/9/ 7	// * /
30 PENTODE UNIT GRID-No.2 VOL.TS=125 TRI	ODE UNIT	$I \cap I \cap I$	1/6/
1b0 ω 30		7 7 7 7	17 17T
	0/	1 / 1 / 1 /	1/9/
25 GRID-No. VOLTS EC = 0.5		 	/ / / /
	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	1//////	
20 ≤ 20 ≤ 20	6/-	V / / / /	-/-/-/-/- //
I I I I I I I I I I I I I I I I I I I	5/	<i>K</i> / / / /	1 / // // // /
25 GRID-No.I VOLTS EC1 = 0.5	18/1		1/1/1/
$ \mathbf{I}_{\mathbf{b}} $ $ \mathbf{I}_{\mathbf{b}} $ $ -2 $ $ \mathbf{I}_{\mathbf{b}} $	0//	I / I / I / I	144//10
10 -25 JA 10	œ/ /	Y	リノオノベ
10	9 / /		11111
- V:1<	x /\/	1//////	ソ人ノメシ
25 GRID-NoI VOLTS ECI = -0.5 20 GRID-NoI VOLTS ECI = -0.5 20 GRID-NoI VOLTS ECI = -0.5 20 GRID-NoI VOLTS ECI = -0.5 21 July 15 July 15 July 16 Jul	1//	*/*///	
5	<i>X/</i> 1/	X/X///	1/1/-
0 100 200 300 PLATE VOLTS 92CS-12560T	100	200 3	300 400
tects tamin sharings		PLATE VOLT	9 205-104211



MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6LN8/ LCF80

Miniature type used in frequency-changer service in television receivers. Outlines section, 6B; requires miniature 9-contact socket.

Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage		6 0.45 ±100 max	volts ampere volts
Class A, Amplifie	r		
MAXIMUM RATINGS (Design-Maximum Values) Plate Supply Voltage Plate Voltage	Triode Unit 550 250	Pentode Unit 550 250	volts volts
Grid-No.2 (Screen-Grid) Supply Voltage		550	volts
With cathode current of 14 mA	_	175 200	volts volts
Cathode Current Plate Dissipation	14 1.5	14 1.7	mA watts
Grid-No.2 Input: With plate dissipation greater than 1.2 watts With plate dissipation less than 1.2 watts	-	0.5 0.75	watt watt
CHARACTERISTICS			
Plate Voltage Grid-No.2 Voltage	100	170 170	volts volts
Grid-No.1 Voltage	2	<u>2</u>	volts
Amplification Factor Mu-Factor, Grid No.2 to Grid No.1	20	47	_
Plate Resistance (Approx.) Transconductance	5000	0.4 6200	megohm µmhos
Plate Current Grid-No.2 Current	14	10 2.8	mA mA
Input Resistance at frequency of 50 MHz Equivalent Noise Resistance	_	0.01 1500	megohm ohms
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance:			
For cathode-bias operation	0.5 0.5	0.5 1	megohm megqhm

6LQ6 6LQ6/6JE6B 6LQ6/6JE6C

For replacement use type 6MJ6/6LQ6/6JE6C.

6LO8

6LQ8

MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used in color and black-and-white television receiver applications. The pentode unit is used as a video output tube. The triode unit is used in sync separator and sound-if circuits. Outlines section, 6E; requires miniature 9-contact socket. Type 11LQ8 is identical with type 6LQ8 except for heater ratings.




9DX

11LQ8

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time Heater-Cathode Voltage:	6.3 0.7 —	10.9 0.45 11	volts ampere seconds
	200 max 100 max	±200 max 100 max	volts volts
Direct Interelectrode Capacitances: Triode Unit:			
Grid to Plate Grid to Triode Cathode, Pentode Cathode, Heater, Pent		2.8	pF
Grid No.3, and Internal Shield Plate to Triode Cathode, Pentode Cathode, Heater, Pen		4.2	рF
Grid No.3, and Internal Shield		2.4	pF
Pentode Unit: Grid No.1 to Plate		0.12 max	pF
Grid No.1 to Cathode Heater, Grid No.2, Grid No.3, an Internal Shield		14	pF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield		4.8	рF
Triode Grid to Pentode Plate Pentode Plate to Triode Plate		0.015 max 0.17 max	pF pF

Class A, Ampli	ifier			
MAXIMUM RATINGS (Design-Maximum Values)	Trio	de Unit 300	Pentode Unit	volts
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage		— _e ,	300 e curve page	volts
Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias valu Plate Dissipation		0 2	e carve page 0 5	volts watts
Grid-No.2 Input: For grid-No.2 voltages up to 150 volts For grid-No.2 voltages between 150 and 300 volt	S	— — Se	1 e curve page	300 watts
			tode Unit	
Plate Supply Voltage	125	125 125	200 125	volts volts
Grid-No.2 Supply Voltage Cathode-Bias Resistor Amblification Factor	68 46	82	68 —	ohms
Plate Resistance (Approx.)	4400	55000	75000	ohms
Transconductance	10400 15	21000 16.5	23000 20	μmhos mA
Crid-No 2 Current	_	3.1	3. 5	mA.
Grid-No.1 Voltage(Approx.) for plate current of 100 µA	6	-4.2	4.2	volts
MAXIMUM CIRCUIT VALUES				
Grid-No.1-Circuit Resistance:			Pentode Unit	
For fixed-bias operation For cathode-bias operation	•	0.5 1	0.1 0.25	megohm megohm
	•	•	0.20	megonin
	TYPE 6LQ8	3/ 7/	777	7
GRID-No.2 VOLTS = 125		$\Psi / + f$	////	9,
3 25 3 25 3 25 3 25 3 25 3 25 3 25 3 25	2	//	/ / //	 /_
Z 1 60		'	· / / /	$Y \mathcal{I} = \mathbb{I}$
GRID-No. 2 VOLTS - 125 S W W 80 O W W 90 O W W 90 O W W 90 O W 90	8		////	/%/
ST GRID-No.I VOLIS	1/			
10 P P P P P P P P P P P P P P P P P P P	//			*/%-
1 _b -1.5	HH			
0 100 200 300 400	Ю		00 300 TE VOLTS	400 9205-12616TI



92C5-1375IT

PLATE VOLTS

BEAM POWER TUBE

35LR6

Duodecar type used as horizontal-deflection amplifier in color and black-and-white television receivers. An integral radiator-fin design dissipates heat uniformly. Outlines section, 16E; requires duodecar 12-contact socket. Type 35LR6 is identical with type 6LR6 except for heater ratings.

Heater Arrangement Heater Voltage (ac/dc) Heater Current Heater Warm-up_Time (Average)	Parallel	Series	volts
	6.3	35	amperes
	2.5	0.45±0.03	seconds
Heater-Cathode Voltage: Peak value Average value	±200 max	±200 max	volts
	100 max	100 max	volts

Class A. Amplifier

	Triodett		Pentode Coni	nect	ion		
CHARACTERISTICS	Connection						
Plate Voltage	. 125	60	175		60		volts
Grid-No.3 (Suppressor Grid) Voltage			Connected	to	cathode	at	
Grid-No.2 (Screen-Grid) Voltage		115	110		110		volts
Grid-No.1 (Control-Grid) Voltage	20	0	20		0		volts
Plate Resistance (Approx.)			5300				ohms

Transconductance (Grid No.1 to Plate) Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for	=	740† 38†	16000 140 2.4	700 35	μmhos mA mA
plate current of 1 mA	_	_	42		volts
Current) Triode Amplification Factor	3.5	19.5:1	=	20:1	

† This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.
†† Grid No. 2 connected to plate.

Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Supply Voltage	990	volts
Peak Positive-Plate Pulse Voltage (Absolute Maximum)	7500	volts
Peak Negative-Pulse Plate Voltage	1100	volts
Positive Grid-No.3 Voltage	75	volts
DC Grid-No.2 Voltage	220	volts
Peak Negative-Pulse Grid-No.1 Voltage	330	volts
Average Cathode Current	375	mA
Peak Cathode Current	1300	mA
Plate Dissipation	30	watts
Grid-No.2 Input	5	watts
Bulb Temperature (At hottest point)	250	°C
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance:		
Bias feedback high-voltage regulation DC or pulse shunt high-voltage regulation	0.47 10	megohm megohm

6LR8 21LR8, 31LR8

HIGH-MU TRIODE—BEAM POWER TUBE

Novar type used in combined vertical-deflectionoscillator and vertical-deflection-amplifier applications in color and black-and-white television receivers. Outlines section, 17E; requires novar 9-contact socket. Types 21LR8 and 31LR8 are identical with type 6LR8 except for heater ratings.



9QT

Heater Voltage Heater Current Heater Warn-up Time Heater-Cathode Voltage:	6LR8 6.3 1.5	21 LR8 21 0.45 11	31.5 0.3 11	volts ampere seconds
Peak value	±200 max	$\pm 200~{ m max}$	$\pm 200~\mathrm{max}$	volts
Average value	100 max	100 max	100 max	volts
Clas	s A, Amplif	ier		
CHARACTERISTICS	Triode Unit	Beam Power	Unit	
Plate Voltage	250	45 135	120	volts
Grid-No.2 (Screen-Grid) Voltage		125 120	120•	volts

Grid-No.2 (Screen-Grid) Voltage		125	120	120•	volts
Grid-No.1 (Control-Grid) Voltage	-4	Ō	10	10	volts
Amplification Factor	58			6.5	
Plate Resistance Approx.)	14000		14000		ohms
Transconductance	4100		9200		μ mhos
Plate Current	2.6	200=	51	-	· mA
Grid-No.2 Current		200 -	3	_	mA
Grid-No.1 Voltage:					
For plate current of 10 μA	-6.6		_	-	v ol ts
For plate current of 100 µA	·—		28		volts
For plate current of 1 mA			24	_	volts


[•] Triode connection, Grid No.2 connected to plate at socket.

This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Vertical-Deflection Oscillator and Amplifier For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit Oscillator	Beam Power Ur Amplifier	it
Plate Voltage	400	400	volts
Grid-No.2 Voltage		300	volts
Peak Positive-Pulse Plate Voltage#	_	2500	volts
Peak Negative-Pulse Grid-No.1 Voltage	400	250	volts
Peak Cathode Current	105	260	mA
Average Cathode Current	30	75	mA
Peak Power Output	2.5	_	watts
Plate Dissipation!	2.5	14	watts
Grid-No.2 Inputt	_	2.75	watts
Bulb Temperature	_	210	°C
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
For fixed-bias operation	_		megohm
For authode-higg operation	2.2	2.2	negohms

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). 1 A bias resistor or other means is required to protect the tube in absence of excitation.



MAXIMUM RATINGS (Design-Maximum Values) Plate Current (Continuous Operation) ...

Tube Voltage Drop for plate current of 20 mA

CHARACTERISTICS, Instantaneous Value

Heater Voltage Heater

TWIN DIODE-SHARP-CUTOFF PENTODE 8LT8, 11LT8

6LT8

Miniature type used in television receiver applications. The pentode unit is used in low-frequency horizontaloscillator applications. The diode units are used in horizontal afc discriminator circuits. Outlines section, 6B; requires miniature 9-contact socket. Types 8LT8 and 11LT8 are identical with type 6LT8 except for heater ratings.

8LT8

11LT8

mΑ


volts

Heater Current	0.6	0.45	0.315	ampere
Heater Warm-up Time (Average) Heater-Cathode Voltage:	11	11	11	seconds
Peak value	±200 max 100 max	±200 max 100 max	±200 max 100 max	volts volts
Pentode Unit as	Class A. A	mplifier		
MAXIMUM RATINGS (Design-Maximum Value	es)			
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bi- Plate Dissipation Grid-No.2 Input:	as value		330 330 See curv 0 3.1	volts volts e page 300 volts watts
For grid-No 2 voltages up to 165 volts. For grid-No.2 voltages between 165 and			0.65 See curv	watt e page 300
CHARACTERISTICS				
Plate Voltage Grid No.3 (Suppressor Grid) Grid-No.2 Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current MAXIMUM CIRCUIT VALUE	nt of 20 μA		125 56 200000 13000 10 3.4 3.5	volts ground volts ohms ohms µmhos mA volts
Grid-No.1-Circuit Resistance, for cathode-bias	operation .		1	megohm
Diode Unit	(Each Uni	it)		

6LU8

HIGH-MU TRIODE.... **BEAM POWER TUBE**

Duodecar type used as a combined vertical-deflection oscillator and vertical-deflection amplifier in color television receivers. Outlines section, 15D; requires duodecar 12-contact socket. Types 16LU8A and 21LU8 are identical with type 6LU8 except for heater ratings.



Heater Voltage Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	6.3 1.5	16LU8A 16 0.6 11	21 LU8 21 0.45 11	volts amperes seconds
Peak value	±200 max	±200 max	±200 max	volts
	100 max	100 max	100 max	volts

Class A, Amplifier					
CHARACTERISTICS	Triode Unit	Bean	n Power 1	Unit	
Plate Voltage	250	45	135	120	volts
Grid-No.2 (Screen-Grid) Voltage		125	120	120•	volts
Grid-No.1 (Control-Grid) Voltage	4	0	10	10	volts
Amplification Factor	58	_	_	6.5	
Plate Resistance (Approx.)	16 0 00	_	12000	_	ohms
Transconductance	3600		9300		μmhos
Plate Current	2.3	200 • •	56	_	mA
Grid-No.2 Current		20 • •	3		mA
Grid-No.1 Voltage (Approx.):					
For plate current of 10 μ A	-6.6	_		_	volta
For plate current of 100 μA	_		30	_	volts
For plate current of 1 mA	-	_	26	_	volts

· Triode connection, Grid No.2 connected to plate at socket.

•• This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Vertical-Deflection Oscillator and Amplifier For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit Oscillator	Beam Power Amplifie	
Plate Voltage	400	400	volts
Grid-No.2 Voltage	-	300	volts
Peak Positive-Pulse Plate Voltage#	_	2500	volts
Peak Negative-Pulse Grid-No.1 Voltage	400	250	volts
Plate Dissipation	2.5	14	watts
Peak Cathode Current	105	260	mA.
Average Cathode Current	30	75	mA
Grid-No.2 Input	_	2.75	watts
Bulb Temperature (At hottest point)		210	°C
MAXIMUM CIRCUIT VALUES Grid-Circuit Resistance:			
For fixed-bias operation		1	megohm
For cathode-bias operation	2.2	2.2	megohms

Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). • A bias resistor or other means is required to protect the tube in absence of excitation.

6LX6

For replacement use type 6LF6/6LX6.

6LX8/LCF802


Refer to type 6JW8/ECF802.

6LY8

cept for heater ratings.

HIGH-MU TRIODE-SHARP-CUTOFF PENTODE

Miniature type used in color and black-and-white television receiver applications. The pentode unit is used as a video amplifier, and the triode unit for generalpurpose use. Outlines section, 6E; requires 9-contact socket. Type 10LY8 is identical with type 6LY8 ex-




9DX

Heater Voltage Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	6LY8 6.3 0.75	10LY 10.5 0.45		volts ampere seconds
Peak value Average value	$^{\pm 200~\text{max}}_{100~\text{max}}$		max max	volts volts
Class A. Amplifi	er			
MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage	Triode Un 330	it Pento 33 33	0	volts
Grid-No.2 (Screen-Grid) Supply Voltage	_			volts
Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation	0		e page 0 5	volts watts
Grid-No.2 Input:		,	,	Watts
For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330 volts	_	See curve		watts
CHARACTERISTICS				
Plate Voltage Grid-No.2 Voltage	250	35 100	200 100	volts volts
Grid-No.1 Voltage	-2.0	Õ		volts
Cathode-Bias Resistor	_	_	82	ohms
Amplification Factor	100	_		
Plate Resistance (Approx.)	59000		60000	ohms
Transconductance	1700		20000	μmhos
Plate Current	1.0	54	19.5	mĄ
Grid-No.2 Current		13.5	3	mA
of 10 µA Grid-No.I Voltage (Approx.) for plate current	5	_	_	volts
of 100 μ A	_		6.3	volts
MAXIMUM CIRCUIT VALUES			0.0	10.00
Grid-No.1-Circuit Resistance:				
For fixed-bias operation	0.5	0.5	;	megohm
For cathode-bias operation	1	1		megohm
Dafan to shout at and of western				•

Refer to chart at end of section.

6LZ6



HIGH-MU TWIN TRIODE—SHARP-CUTOFF PENTODE

6M11

Duodecar type used in television receiver applications. The triode units are used in sync-separator and agcamplifier circuits; the pentode unit is used in if-amplifier circuits. Outlines section, 8B; requires duodecar 12-contact socket.

Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage:	6.3 0.77	volts ampere
Peak value Average value Direct Interelectrode Capacitances: **	±200 max 100 max	volts volts
Triode Units:		
Grid to Plate	1.8	$\mathbf{p}\mathbf{F}$
Grid to Triode Cathode, Pentode Cathode, Heater, Pentode		-
Grid No.3, and Internal Shield	3.4	pF
Grid No.3, and Internal Shield	0.8	pF
Grid No.1 to Plate	0.03	рF
Grid No.1 to Cathode, Grid No.2, Grid No.3, and Internal Shield	12	pF
Plate to Cathode, Grid No.2, Grid No.3, and Internal Shield	2.8	pF
44 37717		

•• With external shield connected to pentode cathode, grid No.3, and internal shield.

Class A. Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Triode U	nit Pentode Unit	
Plate Voltage	330	330	volts
Grid-No.2 (Screen-Grid) Supply Voltage	_	330	volts
Grid-No.2 Voltage		See curve page	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	0	volts
Plate Dissipation	2.25	3.1	watts
Grid-No.2 Input:			
For voltages up to 165 volts		0.65	watt
For voltages between 165 and 330 volts		See curve page	300

CHARACTERISTICS			
Plate Supply Voltage	125	125	volts
Grid-No.2 Supply Voltage	_	125	volts
Cathode-Bias Resistor	125	56	ohms
Amplification Factor	58		
Plate Resistance (Approx.)	7250	200000	ohms
Transconductance	8000	13000	μ mhos
Plate Current	8	11	m A
Grid-No.2 Current		3.4	m A
Grid-No.1 Voltage (Approx.) for plate current			
of 20 μA	_	-3.5	volts
Grid-No.1 Voltage (Approx.) for plate current			
of 50 μA	-4.5	_	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance, for cathode-bias			
operation	0.68	1	megohm

6MA6

Refer to chart at end of section.


5MB8

6MB8

Heater Arrangement

HIGH-MU TRIODE SHARP-CUTOFF PENTODE

Miniature type with frame-grid pentode unit used in color television receivers. The triode unit is used in video-amplifier applications. The pentode unit is used in burst-amplifier service. Outlines section, 6B; requires miniature 9-contact socket. Type 5MB8 is identical with type 6MB8 except for heater ratings.



6MB8


Parallel

Wester Wellers (- /de)	5.6	2 0 0	
Heater Voltage (ac/dc)		6.3	volts
Heater Current	0.45	0.4	ampere
Heater Warm-up Time	11	_	seconds
Heater-Cathode Voltage:			
Peak value	±200 max	$\pm 200 \text{ max}$	volts
Average value	100 max	100 max	volts
		100 max	¥0163
Class A ₁ Amplifi	er		
MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit	Pentode Unit	
Plate Voltage	280	280	volts
Grid-No.2 (Screen-Grid) Supply Voltage			volts
G.: 1 N. a. D.: 1. W. I		280	
Grid-No.2 Pulse Voltage		300	volts
Grid-No.2 Voltage		See curve page	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	0	volt
Plate Dissipation	2	2	watts
Cathode Current	20	20	mA
Grid-No.2 Input		0.5	watt
CHARACTERISTICS		0.0	
Plate Voltage	125	125	volts
Grid-No.2 Voltage		125	volts
Grid-No.1 Voltage	0	0	volt
Cathode-Bias Resistor	68	33	ohm
Plate Current	13	ĭĎ	mA
Grid-No.2 Current		2.8	mA
	8000	12000	μmhos
Transconductance		12000	μπημοσ
Amplification Factor	40		
Plate Resistance (Approx.)	5000	125000	ohms
Grid-No.1 Voltage for plate current of 100 µA	5		volts
Grid-No.1 Voltage for plate current of 50 µA		3	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:	Triode Unit	Pentode Unit	
	0.5	0.25	megohm
For fixed-bias operation	V.0		
For cathode-bias operation	1	0.5	megohm


6MD8

MEDIUM-MU TRIPLE TRIODE

Novar type used in matrixing circuits of color and black-and-white television receivers. Outlines section, 11E; requires novar 9-contact socket. Type 12MD8 is identical with type 6MD8 except for heater ratings.



Heater Arrangement Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:		6MD8 Parallel 6.3 0.9	12MD8 Series 12.6 0.45 11	volts ampere seconds
Peak value		±200 max 100 max	±200 max 100 max	volts volts
	Unit No.1	Unit No.2	Unit No.3	
Direct Interelectrode Capacitances (Approx.): Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater	3.6 0.48	3 3.6 0.48	3 3.4 0.36	pF pF pF
Class A ₁ Amplifier (Ea	ach L	Init)		
MAXIMUM RATINGS (Design-Maximum Values)				
Plate Voltage Grid Voltage, Positive-bias value Plate Dissipation CHARACTERISTICS			330 0 3	volts volts watts
Plate Voltage Grid Voltage Amplification Factor	. 		250 10.5 17	volts volts
Plate Resistance (Approx.)			5500	ohms



Transconductance	3100	μ mhos
Plate Current	11.5	mA
Plate Current for grid voltage of -14 volts		mA
Grid Voltage (Approx.) for plate current of 50 μ A	23	volts
MAXIMUM CIRCUIT VALUE		
Grid-Circuit Resistance for fixed-bias operation	1	marahm



BEAM POWER TUBE

6ME6

Novar types used as horizontal-deflection amplifier in color and black-and-white television receivers. Outlines section, 32C; require novar 9-contact socket.

Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage:	6.3 ±0.6 2.3	volts amperes
Peak value Average value	±200 max 100 max	volts volts
Direct Interelectrode Capacitances: Grid No.1 to Plate	0.6	ρF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3	22	
Plate to Cathode, Heater, Grid No.2.		pF -
and Grid No.3	11	рF

Class A. Amplifier

CHARACTERISTICS	Triode* Connection		Pentode Connec	ction	
Peak Positive-Pulse Plate Voltage#		5000			volts
Plate Voltage	125		55	175	volts
Grid-No.3 (Suppressor-Grid)			-		
Voltage		0	30	30	volts
Grid-No.2 (Screen-Grid) Voltage	125	125	125	125	volts
Grid-No.1 (Control-Grid) Voltage			0	-25	volts
Plate Resistance (Approx.)	_			5800	ohms
Transconductance				9600	umhos
Plate Current			580±	130	m A
Grid-No.2 Current			40Í	2.8	mA
Grid-No.1 Voltage for plate current			•		
of 1 mA		125		-44	volts
Amplification Factor	3.5				

- * Grid No.3 and grid No.2 connected, respectively, to cathode and plate at socket.
- This value may be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Harizantal Deflection Amplifier

norizontal-Denection Ampliner		
For operation in a 525-line, 30-frame system		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Supply Voltage	990	volts
Peak Positive-Pulse Plate Voltage#	7500	volts
Peak Negative-Pulse Plate Voltage	1100	volts
Grid-No.3 Voltage	75	volts
Grid-No.2 Voltage	220	volts
Peak Negative-Pulse Grid-No.1 Voltage	330	volts
Peak Cathode Current	1200	mA
Average Cathode Current	350	mA
Plate Dissipation°	30	watts
Plate Dissipation (Temporary overload)	200	watts
Grid-No.2 Input	5	watts
Envelope Temperature (At hottest point)	250	"°°C
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance for Cathode Bias		
(with min. $R\kappa = 100\Omega$)	1.0	megohm
Grid-leak Bias (with signal peak clamped to zero bias)	10.0	megohms
Sild-lead Dies (with signal peak claimped to selo bias)	10.0	megonius


- # Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).
- For horizontal-deflection service, a positive voltage may be applied to grid-No.3 to minimize "snivets" interference in both vhf and uhf television receivers. A typical value is 30 volts.
- A bias resistor or other means is required to protect the tube in absence of excitation.
- A Total continuous or accumulated time not to exceed 40 seconds.

Fixed Bias (where positive grid current is not drawn)

6ME8

TWO-PLATE **BEAM-DEFLECTION TUBE**

Miniature type used for color-demodulator applications in color television receivers and a variety of other switching and gate applications. Outlines section, 6E; requires miniature 9-contact socket. Pin 5 should be connected directly to ground. The 6ME8 should be so located in the equipment that it is not subjected to stray magnetic fields.



0.47


megohm

Heater Voltage (ac/dc) 6,3 vo	lts
Heater Current 0.3 amp	ere
Direct Interelectrode Capacitances:	
Grid No.1 to All Other Electrodes Except Plates 7.5	рF
	ρF
Either Deflecting Electrode to All Other Electrodes 6	pΓ
Plate No.1 to Plate No.2 0.4	pF pF
Deflecting Electrode No.1 to Deflecting Electrode No.2 0.4	рF
Grid No.1 to Deflecting Electrode No.1 0.07 max	ρF
Grid No.1 to Deflecting Electrode No.2 0.1 max	ρF

CHADACTERISTICS

Color TV Demodulator


MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage (Each Plate)	400	volts
Peak Deflecting-Electrode Voltage (Each Electrode)	±200	volts
Deflecting-Electrode Voltage (Each Electrode)	100	volts
Grid-No.3 (Accelerating-Grid) Voltage	400	volts
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	volts
Cathode Current	30	mA
Plate Dissipation (Each Plate)	2	watts
Grid-No.3 Input	2	watts
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.1	megohm
For cathode-bias operation	0.25	megohm



Class A. Amplifier

CHARACTERISTICS		
Plate-No.2 Supply Voltage	250	volts
Plate No.2	Connected to	Plate No.1
Plate-No.1 Supply Voltage	250	volts
Grid-No.3 Supply Voltage	350	volts
Grid-No.1 Supply Voltage	0	volts
Deflecting-Electrode-No.2 Supply Voltage	75	volts
Deflecting-Electrode-No.1 Supply Voltage	75	volts
Cathode-Bias Resistor	390	ohms
Transconductance, Grid No.1 to both plates	4400	μ mhos
Total Plate Current	14.5	mA.
Grid-No.3 Current	0.7	mA
Grid-No.1 Voltage for total plate current of 10 µA	—16	volts
Deflecting-Electrode Switching Voltage*	30 max	volts
Voltage Difference between Deflecting Electrodes for equal		
plate currents	0	volts
Plate-No.1 Current with Deflecting-Electrode-No.1 Voltage = 55V		
and Deflecting-Electrode-No.2 Voltage = 95V	1.3 max	m A
Plate-No.2 Current with Deflecting-Electrode-No.1 Voltage = 95V		
and Deflecting-Electrode-No.2 Voltage == 55V	1.3 max	mA.
Deflecting-Electrode-No.1 Current with Deflecting-Electrode-No.1		
Voltage = 125V and Deflecting-Electrode-No.2 Voltage = 25V	0.04 max	mA.
Deflecting-Electrode-No.2 Current with Deflecting-Electrode-No.1		
Voltage = 25V and Deflecting-Electrode-No.2 Voltage = 125V	0.04 max	mA.

^{*}Defined as the total voltage change from 75 volts on either deflecting electrode with an equal and opposite change on the other deflecting electrode required to switch the plate current from one plate to the other.



6MF8


of 10 μA Grid-No.1 Voltage for plate current

of 100 µA

Grid Circuit Resistance: For fixed-bias operation

HIGH-MU TRIODE— BEAM POWER TUBE

Duodecar type used in combined vertical-deflection-oscillator and vertical-deflection-amplifier applications in color television receivers. Outlines section, 15D; requires duodecar 12-contact socket. Type 15MF8 is identical with type 6MF8 except for heater ratings.



12DZ

- -65

volts

volts

megohm

Heater Voltage Heater Current Heater-Cathode Voltage:	6MF8 6.3 1.4	15MF8 14.7 0.6	volts amperes
Peak value	± 200 max 100 max	±200 max 100 max	volts volts
Class A. Amplifier	r		


Triode Beam Power CHARACTERISTICS Unit Unit Grid-No.1 (Control-Grid) Voltage
Grid-No.1 (Control-Grid) Voltage 250 60 250 volts 250 250 volts -20 n volts Plate Current 2.6 200 ħΩ mA Grid-No.2 Current 20 3.5 mА Transconductance 4100 4100 μm**hos** Amplification Factor KΩ Plate Resistance (Approx.)
Grid-No.1 Voltage for plate current 14000 5000 ohms

> Vertical-Deflection Oscillator and Amplifier For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Peak Positive Pulse Plate Voltage# Grid-No.2 Voltage Plate Dissipation* Grid-No.2 Dissipation* Average Cathode Current Peak Cathode Current Peak Cathode Turent Peak Power Output Bulb Temperature	Triode Unit Oscillator 400 — 400 2.5 30 105 2.5	Unit Amplifier 400 2500 300 — 12 2.75 75 260 — 200	volts volts volts volts watts watts mA mA watts
MAXIMUM CIRCUIT VALUES			

For cathode-bias operation 2.2 2.2 megohms # Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).

Fruise duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds). A bias resistor or other means is required to protect the tube in absence of excitation.



MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6MG8

Miniature type used in horizontal-deflection circuits and for agc-amplifier or sync-separator applications in television receivers. Outlines section, 6B; requires miniature 9-contact socket. Heater: volts, 6.3; ampere, 0.45; maximum heater-cathode volts, ±200 peak, 100 average.

Class A. Amplifier

CHARACTERISTICS Plate Voltage Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage Cathode-Bias Resistor Plate Current Grid-No.2 Current Transconductance Plate Resistance (Approx.) Amplification Factor Grid-No.1 Voltage for plate current of 10 \(\mu\text{A}\) Horizontal-Deflection A	150 ————————————————————————————————————	Pentode Unit 170 170 -2 10 2.8 6200 400 47	volts volts volts ohms mA mA µmhos kohms
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage Grid-No.2 Supply Voltage Plate Dissipation Cathode Current	330 2.5 14	330 300 2 14	volts volts watts mA
Grid-No.2 Input: For plate dissipation more than 1.2 watts For plate dissipation less than 1.2 watts MAXIMUM CIRCUIT VALUES	_	0.5 0.75	watt watt
Grid-No.1 Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.5 0.5	0.5 1	megohm megohm
For replacement use type 6J6A.		6МНН:	3



BEAM POWER TUBE

6MJ6/ 6LQ6/6JE6C

24LO6/24JE6C, 31LO6

Novar types used as horizontal-deflection amplifier in color and black-and-white television receivers. Outlines section, 32C; requires novar 9-contact socket. Types 24LQ6/24JE6C, and 31LQ6 are identical with type 6MJ6/6LQ6/6JE6C except for heater ratings.

	01477.0\			
Heater Voltage (ac/dc)	6LQ6/6JE6C	24LQ6/24JE6C	31 LQ6	
Heater Current	6.3	24	31	volts
Heater Warm-up Time	2.3	0.6	0.45	amperes
Heater-Cathode Voltage:		11	11	seconds
Peak value	$\pm 200~\mathrm{max}$	$\pm 200 \text{ max}$	±200 max	volts
Average value	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances:				
Grid No.1 to Plate			0.6	pF
Grid No.1 to Cathode, Heater, Grid No.				=
and Grid No.3			22	pF
Plate to Cathode, Heater, Grid No.2,				_
and Grid No.3			11	\mathbf{pF}
				_

Class A. Amplifier

. . . .

Connection		Pentode Connec	tion	
	5000			volts
145		60	175	volts
	30	30	30	volts
145	145	145	145	volts
-35		0	-35	volts
			7000	ohms
	_		7500	μmhos
		710‡	95	mA
	145 	Connection 5000 145 30 145 145 -35 -	Connection Pentode Connect 145 - 60 30 30 145 145 145 -35 - 0 - - -	Connection Pentode Connection 145 5000 - 60 175 - 30 30 30 145 145 145 145 -35 - 0 -35 - - 7000 - 7500

Grid-No.2 Current		-	55‡	2.4	mA
of 1 mA	2.8	125	_	-60	volts

* Grid No.3 and grid No.2 connected, respectively, to cathode and plate at socket.

‡ This value may be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.


Horizontal-Deflection Amplifier


For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum values)		
Plate Supply Voltage	990	volts
Peak Positive-Pulse Plate Voltage#	7500	volts
Peak Negative-Pulse Plate Voltage	1100	volts
Grid-No.3 Voltage	75	volts
Grid-No.2 Voltage	220	volts
Peak Negative-Pulse Grid-No.1 Voltage	3 30	volts
Peak Cathode Current	1200	mA
Average Cathode Current	350	mA
Plate Dissipation O	30	watts
Plate Dissipation (Temporary overload)	200	watts
Grid-No.2 Input	5	watts
Envelope Temperature (At hottest point)	250	$^{\circ}\mathrm{c}$
MAXIMUM CIRCUIT VALUES		

Grid-No.1-Circuit Resistance:

- For horizontal-deflection service, a positive voltage may be applied to grid-No.3 to minimize "snivets" interference in both vhf and uhf television receivers. A typical value is 30 volts.
- O A bias resistor or other means is required to protect the tube in absence of excitation.
- ▲ Total continuous or accumulated time not to exceed 40 seconds.






6MJ8

MEDIUM-MU TRIPLE TRIODE


Duodecar type used in matrixing-amplifier circuits of color and black-and-white television receivers. Outlines section, 8D; requires duodecar 12-contact socket.

			12HG	
Heater Voltage Heater Current Heater-Cathode Voltage:			6.3 0.9	volts ampere
Peak value Average value			±200 max 100 max	volts volts
Direct Interelectrode Capacitances: Grid to Plate	Unit No.1	Unit No.2	Unit No.3	
Grid to Cathode and Heater Plate to Cathode and Heater	2.8 2.9 0.36	2.8 2.9 0.6	2.8 3 0.7	pF pF pF



Class A. Amplifier (Each Unit)

MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage Grid Voltage, Positive-bias value Plate Dissipation	330 0 3	volts volts watts
CHARACTERISTICS		
Plate Voltage Grid Voltage Plate Current Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current for grid voltage of —14 volts Grid Voltage for plate current of 50 µA	10 17 5600 3000 4	volts volts mA ohms µmhos mA volts
MAXIMUM CIRCUIT VALUE		
Grid-Circuit Resistance, for fixed-bias operation	1	megohm



Refer to chart at end of section. For replacement use type 6MK8A.

6MK8



Peak positive value

DC negative value DC positive value

SHARP-CUTOFF TWIN PENTODE

6MK8A


volts


volts volts

Miniature type used in sync-separator, clipper, agc, and low-level color-demodulator circuits in television receivers. Outlines section, 6E; requires miniature 9-contact socket.

order borner.		
Heater Voltage	6.3	volts
Heater Current	0.3	ampere
Heater-Cathode Voltage:		
Peak value	$\pm 200 \text{ max}$	volts
Average value	100 max	volts
Direct Interelectrode Capacitances:		
Grid No.3 to Plate (Each Section)	2	pF pF pF
Grid No.1 to All Electrodes	6	pF
Grid No.3 (Each Section) to All Electrodes	3.6	pF
Plate (Each Section) to All Electrodes	3	pF
Grid No.3 (Section 1) to Grid No.3 (Section 2)	0.015 max	pF
Class A ₁ Amplifier		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage (Each Unit)	300	volts
Grid-No.3 (Suppressor-Grid) Voltage (Each Unit)		

Grid-No.2 (Screen-Grid) Voltage		150	volts
Grid-No.1 (Control-Grid) Voltage, Negative-bias value		50	volts
Cathode Current		12	mA
Plate Dissipation (Each Section)			watts
Grid-No.2 Input			watt
-			
MAXIMUM PLATE CURRENT RATIO (Balance): 6MK8/	A 1.2 to 1;	4MK8 - 1.3	to 1
Plate Voltage		100	volts
Grid-No.2 Voltage		67.5	volts
Grid-No.1 Voltage			volts
Grid-No.3 Voltage		01.5	volts
Grid-No.1 Resistance		0.68	megohm
Grid-No.1 Resistance		0.68	megonm
CHARACTERISTICS With One Unit Opera	ting•		
Plate Voltage	100	100	volts
Grid-No.3 Voltage	100	100	volts
Grid-No.2 Voltage	67.5	67.5	volts
Grid-No.1 Voltage	01.0	07.0 *	volts
Transconductance, Grid No.3 to Plate	v	-	
		450	μ mhos
Transconductance, Grid No.1 to Plate	1100		μ mhos
Plate Current		2	m A
Grid-No.3 Voltage (Approx.) for plate current			
of 100 μA	-	3.5	volts
Grid-No.1 Voltage (Approx.) for plate current			
of 100 μA		-2.3	volts
With Both Units Oper	ating		
Plate Voltage (Each Unit)	100	100	volts
Grid-No.3 Voltage (Each Unit)	10	100	volts
Grid-No.2 Voltage	67.5	67.5	volts
Cuid No. 1 Voltage	07.0	61.5	Voits
Grid-No.1 Voltage	-	-	
Plate Current (Each Section)		2	mA.
Cathode Current	7.1	8.5	mA.
Grid-No.2 Current	7	4.4	mA





MAXIMUM CIRCUIT VALUES		
Grid-No.3-Circuit Resistance (Each Unit) Grid-No.1-Circuit Resistance		megohm megohm
• With plate and grid No.3 of other unit grounded. * Grid current	adjusted for	100 μA dc.

, IC GTI

Refer to chart at end of section.

HIGH-MU TRIPLE TRIODE

SMN8

6ML8

Duodecar type used for matrix-amplifier applications in color television receivers. Outlines section, 8D; requires duodecar 12-contact socket. Type 9MN8 is identical with type 6MN8 except for heater ratings.

quires duodecar 12-contact			
12HU tical with type 6MN8 excep	ot for heat	er ratings	•
Heater Voltage Heater Current	6MN8 6.3 0.9	9MN8 9.5 0.6	volts ampere
neater Cutrent		11	seconds
Heater-Cathode Voltage: Peak value Average value Direct Interelectrode Capacitances: Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater 0.33	±200 max ±100 max Unit No.2 2.6 4.6 0.57		volts volts pF pF pF
Class A ₁ Amplifier (Each MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Grid Voltage, Positive-bias value Plate Dissipation		330 0 3	volts volt watts
CHARACTERISTICS			
Plate Voltage Grid Voltage Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid Voltage (Approx.) for plate current of 50 \(\mu A \)	125 —1 47 6250 7500 11 —5	200 4 40 10000 4000 4.8 11	volts volts ohms µmhos mA volts
MAXIMUM CIRCUIT VALUE			
Grid-Circuit Resistance, for fixed-bias operation		1	megohm



MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6MQ8

Miniature type used in color and black-and-white television receiver applications. The pentode unit is used in band-pass-amplifier applications. The triode unit is used in video-amplifier, sync-separator, color-killer-control, matrix-amplifier, and blanker applications. Outlines section, 6B; requires miniature 9-contact

socket. Type 5MQ8 is identical with type 6MQ8 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time Heater Cathode Voltage:	5MQ8 5.6 0.6 11	6.3 0.535	volts ampere seconds
Peak value	±200 max 100 max	±200 max 100 max	volts volts
Direct Interelectrode Capacitances: Triode Unit:			_
Grid to Plate		1.7	pF
Grid to Triode Cathode, Pentode Cathode, Heater, Pentode Grid No.3, and Internal Shield		3	рF

			рF
	0.045		pF
	7.5		рF
	2.2		рF
ier			
Triode Unit	Pentode	Unit	
330	330		volts
~~~			volts
		page	
			volt
2.1	2.5		watts
-	0.55		watt
		page	
109	100		megohms
Triode Unit	Pentode	Unit	
150	125		volts
			volts
			ohms
			kohms
	10000		μmhos
18	12		mA
	4.5		mA
	Triode Unit	2.2  Priode Unit Pentode  330 330 330  See curve  0 2.7 2.5  0.55  109 See curve  100  Triode Unit Pentode  150 125  56 62  40 150  8500 10000  18 12	2.2    Sec

### **6MU8**

MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance:


#### MEDIUM-MU TRIODE— SEMIREMOTE-CUTOFF PENTODE

0.5 0.5

Miniature type used in color and black-and-white television receiver applications. The pentode unit is used in burst-amplifier circuits, and the triode unit as a general amplifier tube. Outlines section, 6E; requires miniature 9-contact socket.

Heater Voltage

For fixed-bias operation
For cathode-bias operation



 $0.25 \\ 0.5$ 

megohms

megohms

volts

#### 9AE

6.3

Heater Current		0.6	ampere
Heater Warm-up Time Heater-Cathode Voltage:		11	seconds
Peak value		$\pm 200 \text{ max}$	volts
Average value		100 max	volts
Biret Interded 1 Occasion	With	Without	
Direct Interelectrode Capacitances: Triode Unit:	Shield	Shield	
Grid to Plate	2.2	2.2	pF
Grid to Cathode, Heater, Pentode Cathode,			-
Pentode Grid No.3, and Internal Shield	3.2	3	рF
Plate to Cathode, Heater, Pentode Cathode, Pentode Grid No.3, and Internal Shield	3.4	2.2	рF
Pentode Unit:	0.4	4.4	pr
Grid No.1 to Plate	0.05	0.05	pF
Grid No.1 to Cathode, Heater, Grid No.2,			•
Grid No.3, and Internal Shield	9	9	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3,			
and Internal Shield Heater to Triode Cathode	4.4	3.6	pF
	4.8	4.4	_
Heater to Pentode Cathode	7.5	5.5	$\mathbf{pF}$
Pentode Grid No.1 to Triode Plate	0.2	0.17	$\mathbf{pF}$
Pentode Plate to Triode Plate	<b>0</b> .008	0.09	pF

#### Class A₁ Amplifier

MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage	Triode Unit	Pentode Unit	volts
Grid-No.2 (Screen-Grid) Supply Voltage		330	volts
		See curve page	
Grid-No.2 Voltage	0	Oee curve page	volts
Grid-No.1 (Control-Grid) Voltage, Positive-bias value			
Grid-No.2 Input	2.5	3.75	watts
Plate Dissipation		1.1	watts
CHARACTERISTICS	Triode Unit	Pentode Unit	
Plate Voltage	125	150	volts
Grid-No.2 Voltage		150	volts
Grid-No.1 Voltage	—1		volts
Cathode Bias Resistor		150	ohms
Plate Current	11.5	19	mA
Grid-No.2 Current		4.2	mA
Transconductance	6000	9000	μmhos
Amplification Factor	35		•
Plate Resistance (Approx.)	5800	165000	ohms
Grid-No.1 Voltage (Approx.) for plate current of 10 µA	5.8	_	volts
Grid-No.1 Voltage (Approx.) for plate current of 20 µA	_	9.5	volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	$\substack{0.5\\1}$	0.25 1	megohm megohm



9DX

### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

### 6MV8

Miniature type used for general-purpose applications. The pentode unit is used as an if-amplifier, and the triode unit as a sync-separator or voltage amplifier. Outlines section, 6B; requires miniature 9-contact socket. Heater: volts, 6.3; ampere, 0.6; maximum heatercathode volts, ±200 peak, 100 average.

#### Class A₁ Amplifier

MAXIMUM RATINGS (Design-Maximum Values)  Plate Voltage Grid-No. 2 (Screen-Grid) Supply Voltage Grid-No. 1 (Control-Grid) Voltage, Positive bias value Plate Dissipation Grid-No. 2 Input	Triode Unit 330 0 1	Pentode	volts volts 300 volts watts watts
CHARACTERISTICS  Plate Voltage Grid-No. 2 Voltage Grid-No. 1 Voltage  Plate Current Grid-No. 2 Current Transconductance Amplification Factor Plate Resistance (Approx.) Grid-No. 1 Voltage (Approx.) for plate current of 20 µA	250 —	125 —1 Pentode Unit 13 4 9000 — 150000 —6	volts volts volts mA mA μmhos ohms volts
MAXIMUM CIRCUIT VALUES Grid-No. 1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.5 1		megohms megohms

6N7 6N7GT	Refer to chart at end of section.
6P5GT	Refer to chart at end of section.
6P7G	Refer to chart at end of section.
6Q7 6Q7G 6Q7GT	Refer to chart at end of section.
6Q11	Refer to chart at end of section. For replacement use type 6K11/6Q11.
6R7 6R7G 6R7GT	Refer to chart at end of section.
6RHH2	For replacement use type 6BC8/6BZ8.
6RHH8	For replacement use type 6KN8/6RHH8.
6RK19	For replacement use type 6BR3/6RK19.
6RP22	Refer to chart at end of section.
654	Refer to chart at end of section.

654A MEDIUM-MU TRIODE		0,0
Miniature type used as vertical-deflection amplific color and black-and-white television receivers. Out section, 6E; requires miniature 9-contact socket.		9, 9,
Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	0.6 11	volts ampere seconds
Peak value		volts volts
Direct Interelectrode Capacitances (Approx.): Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater	4.2	pF pF pF
Class A. Amplifier		
CHARACTERISTICS Plate Voltage Grid Voltage Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Plate Current for grid voltage of - 15 volts Grid Voltage (Approx.) for plate current of 50 µA	837004500244	volts volts ohms μmhos mA mA volts
Vertical-Deflection Amplifier		
For operation in a 525-line, 30-frame sy MAXIMUM RATINGS (Design-Maximum Values)	ystem	
DC Plate Voltage Peak Positive-Pulse Plate Voltage# Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation	2200 250 105 30	volts volts volts mA mA watts

#### MAXIMUM CIRCUIT VALUE

Grid-Circuit	Resistance,	for	cathode-bias	operation	 	2.2	megohms
	_						

# Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).

Refer to chart at end of section.	6S7 6S7G
Refer to chart at end of section.	6S8GT
Refer to chart at end of section.	6SA7 6SA7GT
Refer to chart at end of section.	6SB7Y
Refer to chart at end of section.	6SC7
Refer to chart at end of section.	6\$F5 6 <b>\$F</b> 5 <b>G</b> T
Refer to chart at end of section.	6SF7
Refer to chart at end of section.	6SG7
Refer to chart at end of section.	6SH <i>7</i>
Refer to chart at end of section.	6SJ7 6SJ7GT
Refer to chart at end of section.	6SK7 6SK7GT




Plate Current

#### HIGH-MU TWIN TRIODE

6SL7GT

12SL7GT

2.3

m A

Glass octal type used as phase inverter in radio equipment. Each unit may also be used in resistance-coupled amplifier circuits. Outlines section, 13D; requires octal socket. Except for the common heater, each triode unit is independent of the other. For typical operation as

6SL7GT

phase inverter or resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Type 12SL7GT is identical with type 6SL7GT except for heater ratings.

Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage	6.3 0.3 ±90 max	12.6 0.15 ±90 max	volts ampere volts
Direct Interelectrode Capacitances (Approx.):° Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater	Unit No.1 2.8 3 3.8	Unit No.2 2.8 3.4 3.2	pF pF pF
With external shield connected to cathode.			
Class A, Amplifier			
MAXIMUM RATINGS (Design-Center Values)			
Plate Voltage Grid Voltage, Positive-blas value Plate Dissipation		300 0 1	volts volts watt
CHARACTERISTICS			
Plate Voltage Grid Voltage Ampification Factor		$\begin{array}{c} 250 \\2 \\ 70 \end{array}$	volts volts
Plate Resistance (Approx.) Transconductance		44000 1600	ohms μmhos

6SN7GTA

Refer to chart at end of section.

#### 6SN7GTB MEDIUM-MU TWIN TRIODE

#### 12SN7GTA

Grid-Circuit Resistance ......

Glass octal type used as combined vertical oscillator and vertical-deflection amplifier, and as horizontal-deflection oscillator, in color and black-and-white television receivers. Each unit may also be used in multivibrator or resistance-coupled amplifier circuits in radio equipment. Outlines section, 13D; requires octal



BRD

socket. Except for the common heater, each triode unit is independent of the other. For typical operation as resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Type 12SN7GTA is identical with type 6SN7GTB except for heater ratings.

type opiniars encopt for measure ratings.			
	6SN7CTR	12SN7GTA	
Heater Voltage (ac/dc)	6.3	12.6	volts
Heater Current	0.6	0.3	ampere
Heater Warm-up Time (Average)	11		seconds
Heater-Cathode Voltage:	••		occomas
Peak value	+200 ma	c ±200 max	volts
Average value	100 max		volts
Direct Interelectrode Capacitances (Approx.):	Unit No.1	Unit No.2	
Grid to Plate	4.0	3.8	р <b>F</b>
Grid to Cathode and Heater	2.2	2.6	pF
Plate to Cathode and Heater	0.7	0.7	pF
	***	V. 1	pr
Class A, Amplifier (Each	Unit)		
MAXIMUM RATINGS (Design-Center Values)			
Plate Voltage		450	volts
Cathode Current		20	mA
Plate Dissipation:			
For either plate		5	watts
For both plates with both units operating		7.5	watts
CHARACTERISTICS			
Plate Voltage	90	250	volts
Grid Voltage	0	<del>8</del>	volts
Amplification Factor	20	20	VOICE
Plate Resistance (Approx.)	6700	7700	ohms
Transconductance	3000	2600	μmhos
Plate Current	10	9	mA
Plate Current for grid voltage of -12.5 volts		1.3	mA.
Grid Voltage (Approx.) for plate current of 10 $\mu$ A	7	-18	volts
MAXIMUM CIRCUIT VALUE			
Grid-Circuit Resistance, for fixed-bias operation		1	megohm
Grid-Great Resistance, for fixed-bias operation		•	megomin
Oscillator (Each Uni	t)		
For operation in a 525-line, 30-fra	me system		
- · · · · · · · · · · · · · · · · · · ·	Vertical-	Horizontal-	
	Deflection	Deflection	
MAXIMUM RATINGS (Design-Center Values)	Oscillator	Oscillator	
DC Plate Voltage	450	450	volts
Peak Negative-Pulse Grid Voltage	400	600	volts
Peak Cathode Current	70	300	mA
Average Cathode Current	20	20	mA
Plate Dissipation:			
For either plate	5	5	watts
For both plates with both units operating	7.5	7.5	watts
MAXIMUM CIRCUIT VALUES			
maximum united the second	0.0	0.0	

# Vertical-Deflection Amplifier (Each Unit) For operation in a 525-line, 30-frame system


2.2

2.2


megohms

MAXIMUM RATINGS (Design-Center Values)		
DC Plate Voltage	450	volts
Peak Positive-Pulse Plate Voltage# (Absolute maximum)	1500•	volts
Peak Negative-Pulse Grid Voltage	250	volts
D. J. C. D. J. Comment	70	m A

Average Cathode Current	20	mA
Plate Dissipation:	_	
For either plate	5	watts
For both plates with both units operating	7.5	watts
MAXIMUM CIRCUIT VALUE		
Grid-Circuit Resistance, for cathode-bias operation	2.2	megohms
# Pulse duration must not exceed 15% of a vertical cycle (2.5 milliseco	nds).	



Refer to chart at end of section.	6SQ/ 6SQ7GT
Refer to chart at end of section.	6SR7
Refer to chart at end of section.	6SS7
Refer to chart at end of section.	6ST7
Refer to chart at end of section.	6 <b>SZ</b> 7
Refer to chart at end of section. For replacement use type 6AF4A.	6T4
Refer to chart at end of section.	6T7G
Refer to chart at end of section.	618



#### TRIPLE DIODE— HIGH-MU TRIODE


**6T8A** 

Miniature type used as combined audio amplifier, AM detector, and FM detector in AM/FM radio receivers. Diode unit No.1 is used for AM detection, and diode units No.2 and No.3 are used for FM detection. Outlines section, 6B; requires miniature 9-contact socket. For typical operation as resistance-coupled amplifier,

refer to Resistance-Coupled Amplifier section. Types 5T8 and 19T8 are identical with type 6T8A except for heater ratings.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	0.6	6.3 0.45 11	18.9 0.15 11	volts ampere seconds
Peak value Average value			±90 max	volts volts

Direct Interelectrode Capacitances:	Unshielded	Shielded	
Triode Unit:			
Grid to Plate	1.7	1.7	рF
Heater	1.6	1.7	pF
Plate to Cathode, Internal Shield (pin 7), and	2.0		<i>D</i> 2
Heater	1.2	2.4	рF
Diode Units:			
Diode-No.1 Plate to Cathode, Internal Shield (pin 7), and Heater	3.8	3.8	pF
Diode-No.2 Plate to Cathode, Internal Shield	0.0	0.0	DI.
(pin 3), and Heater	3.8	3.8*	рF
Diode-No.3 Plate to Cathode, Internal Shield	3.4	3.6	- 100
(pin 7), and Heater	0.4	3.0	pF
Other Electrodes, and Heater	7.5	8.5	рF
Triode Grid to any Diode Plate	0.034 max	0.034 max	pF
<ul> <li>With external shield connected to pin 7 except as noted</li> <li>With external shield connected to pin 3.</li> <li>With external shield connected to pins 4 and 5.</li> </ul>			
Triode Unit as Class A, A	Amplifier		
MAXIMUM RATINGS (Design-Maximum Values)	-		
Plate Voltage		330	volts
Grid Voltage, Positive-bias value		0	volts
Plate Dissipation		1.1	watts
CHARACTERISTICS			
Plate Voltage	100	250	volts
Grid Voltage	1	3 70	volts
Amplification Factor	70 54000	58000	ohms
Plate Resistance (Approx.) Transconductance	1300	1200	μmhos
Plate Current	0.8	1	mA
Diade Units			
Dione Outre			



6T9

MAXIMUM RATING (Design-Maximum Values)

Refer to chart at end of section.

#### 6T10 10T10, 12T10

#### BEAM POWER TUBE— SHARP-CUTOFF PENTODE

Duodecar type used as combined FM detector and audio-frequency output amplifier in color and black-and-white television receivers. The beam power unit is used in af output stages, and the sharp-cutoff, dual-control pentode unit is used as an FM detector. Outlines section, 8C; requires duodecar 12-contact socket. For maximum ratings and characteristics, refer to type 6AL11. Types 10T10 and 12T10 are identical with type 6T10 except for heater ratings.



5.5

mA

	6T10	10 <b>T</b> 10	12T10	
Heater Voltage (ac/dc)	6.3	9.8	12.6	volts
Heater Current	0.95	0.6	0.45	amperes
Heater Warm-up Time (Average)		ïi	11	seconds
Heater-Cathode Voltage:				
Peak value	$\pm 200~\mathrm{max}$	±200 max	±200 max	volts
Average value	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances:				
Unit No.1:			0.00	- 10
Grid No.1 to Plate			0.22	pF
Grid No.1 to Cathode, Heater, Grid No.	.2, Grid No.3,	and Internal		
Shield			11	pF
Plate to Cathode, Heater, Grid No.2	Crid No 3	and Internal		-
			10	ρF
Shield			10	DE.
Unit No.2:				_
Grid No.1 to Plate			0.032	pF
Grid No.3 to Plate			3	pF
Grid No.1 to Cathode, Heater, Grid No.			•	
				-17
Shield	<i></i> .		6.5	ρF
Grid No.3 to Cathode, Heater, Grid N	Io.1. Grid No.2	2. Plate. and		
Internal Shield			7.5	ρF
			0.12	ρF
Grid No.1 to Grid No.3				
Plate of Unit No.1 to Plate of Unit	No.Z		0.13	рF

Refer to chart at end of section.	605
Refer to chart at end of section.	6U7G
Refer to chart at end of section. For replacement use type 6U8A/6KD8.	6U8
For replacement use type 6U8A/6KD8.	6U8A



#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6U8A/ 6KD8

5U8, 9U8A

Miniature types used as combined oscillator and mixer tube in color and black-and-white television receivers utilizing an intermediate frequency in the order of 40 MHz. Outlines section, 6B; require miniature 9-contact socket. Type 5U8 is identical with type 6U8A/6KD8 except for heater ratings.

5U8	6U8A/6KD8	9U8A	
Heater Voltage (ac/dc) 4.7	6.3	9.45	volts
Heater Current 0.6	0.45	0.3	ampere
Heater Warm-up Time (Average) 11	11	11	seconds
Heater-Cathode Voltage:			
Peak value	$\pm 200 \text{ max}$	±200 max	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances:	Unshielded	Shielded*	
Triode Unit:	Ousmended	Dilleinea.	
Grid to Plate	1.8	1.8	_E
Grid to Cathode, Heater, Pentode Cathode,	1.8	1.0	рF
Pentode Grid No.3, and Internal Shield	2.8	2.8	_10
Plate to Cathode, Heater, Pentode Cathode,	2.0	4.0	рF
Pentode Grid No.3, and Internal Shield	1.5	2	-10
Pentode Unit:	1.5	4	рF
Grid No.1 to Plate	0.010 max	0.006 max	- 13
	0.010 max	U.UUG MAX	рF
Grid No.1 to Cathode, Heater, Grid No.2,		-	- 13
Grid No.3, and Internal Shield	5	5	рF
Plate to Cathode, Heater, Grid No.2,	0.0		_
Grid No.3, and Internal Shield	2.6	3.5	₽ <b>F</b>
Triode Cathode to Heater	8	3•	рF
Pentode Cathode, Pentode Grid No.3, and	_	_	_
Internal Shield	3	8•	₽ <b>F</b>
Pentode Grid No.1 to Triode Plate	0.2 max		ρF
Pentode Plate to Triode Plate	0.1 max	0.02 max	рF
A With external shield connected to min 4 except as	motod		

[▲] With external shield connected to pin 4 except as noted.

[·] With external shield connected to pin 6.

#### Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit	Pentode U	nit
Plate Voltage	330	330	volts
Grid-No.2 (Screen-Grid) Supply Voltage	_	330	volts
Grid-No.2 Voltage	9	See curve pa	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	0	volts
Plate Dissipation	2.5	Ÿ	
Grid-No.2 Input:	2.5	3	watts
For grid-No.2 voltages up to 165 volts	_	0.55	watt
For grid-No.2 voltages between 165 and 330 volts	<del>-</del> :	See curve pa	
CHARACTERISTICS			
Plate Voltage	125	125	volts
Grid-No2 Voltage		110	volts
Grid-No.1 Voltage	—1	1	volts
Amplification Factor	40		VOIG
Plate Resistance (Approx.)	40	0.2	megohm
Transconductance (Approx.)	7700		
	7500	5000	$\mu$ mhos
Plate Current	13.5	9.5	mĄ
Grid-No.2 Current		3.5	m A
Grid-No.1 Voltage (Approx.) for plate current of			
20 μΑ	9	8	volts


6U9/ECF201

Refer to chart at end of section.

### **6U10**

#### THREE-UNIT TRIODE


Duodecar type used in amplifier applications. Units No.1 and No.3 are medium-mu triode units, and unit No.2 is a high-mu triode unit. Outlines section, 8A; requires duodecar 12-contact socket. Heater: volts x13(3) (ac/dc), 6.3; amperes, 0.6; warm-up time (average), 11 seconds; maximum heater-cathode volts,  $\pm 275$  (peak) for units 1 and 3;  $\pm 200$  (peak) for unit 2; 100 (average) for each unit.



#### Class A. Amplifier

MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage DC Grid Voltage:	Units Nos. 1 and 3 330	Unit No.2 330	volts
Positive-bias value Negative-bias value Average Cathode Current Plate Dissipation	0 50 20 2	0 50 1	volts volts mA watts
CHARACTERISTICS  Plate Voltage Grid Voltage Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid Voltage (Approx.): For plate current of 100 µA For plate current of 35 µA	200	200	volts
	6	1.5	volts
	17.5	90	ohms
	7700	61000	µmhos
	2300	1600	mA
	9.6	1.2	volts
	15	3	volts
MAXIMUM CIRCUIT VALUES Grid-Circuit Resistance: For fixed-bias operation For cathode-bias operation	1	0.5	megohm
	2.2	1°	megohms

^{*} This value may reach 10 megohms provided the plate-supply voltage and load resistance are such that the plate dissipation can never exceed 0.5 watt.



# 6V6 6V6GTA

#### **BEAM POWER TUBE**

12V6GT

12V6CT

Metal type 6V6 and glass octal type 6V6GTA are used as output amplifiers in automobile, battery-operated, and other receivers in which reduced plate-current drain is desirable. Outlines section, 2B and 13D, respectively; require octal socket. These tubes are equiva-

6V6CTA

7AC spectively; require octal socket. These tubes are equivalent in performance to type 6AQ5A. Refer to type 6AQ5A for average plate characteristic curves. Type 12V6GT is identical with type 6V6GTA except for heater ratings.

	6 V 6	6V6GTA	12V6GT	
Heater Voltage (ac/dc)	6.3	6.3	12.6	volts
Heater Current	0.45	0.45	0.225	ampere
Heater Warm-up Time (Average) Heater-Cathode Voltage: Peak value		11	_	seconds
Average value	±200 max 100 max	±200 max 100 max	±200 max 100 max	volts volts
The same of the sa	100 max	6V6°	6V6GTA	VOICS
Direct Interelectrode Capacitances (Approx.):		D V D	DVDGTA	
Grid No.1 to Plate		0.3	0.7	рF
Grid No.1 to Cathode, Heater, Grid No.2,	and			-
Grid No.3  Plate to Cathode, Heater, Grid No.2, and	 I	10	9	рF
Grid No.3		11	7.5	рF
'With shell connected to cathode.				
Class A, A	mplifier			
MAXIMUM RATINGS (Design-Maximum Values)				
Plate Voltage			350	volts
Grid-No.2 (Screen-Grid) Voltage			315	volts
Plate Dissipation			14	watts
Grid-No.2 Input			2.2	watts
TYPICAL OPERATION				
Plate Voltage			315	volts
Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage	180		225	volts
Peak AF Grid-No.1 Voltage	8.5		$-13 \\ 13$	volts volts
Zero-Signal Plate Current	29		34	mA
Maximum-Signal Plate Current	30		35	mA
Zero-Signal Grid-No.2 Current		4.5	2.2	m A
Maximum-Signal Grid-No.2 Current			6	_mA
Plate Resistance (Approx.) Transconductance	50000		80000 3750	ohms
Load Resistance	5500		8500	μmhos ohms
Total Harmonic Distortion	Ś		12	per cent
Maximum-Signal Power Output			5.5	watts
CHARACTERISTICS (Triode Connection)				
Plate Voltage			250	volts
Grid-No.1 (Control-Grid) Voltage			12.5	volts
Plate Resistance (Approx.)			9.8 1960	ohms
Transconductance			5000	μmhos
Plate Current			49.5	m A
Grid-No.1 Voltage (Approx.) for plate current	of 0.5 mA		36	volts
▲ Grid No.2 connected to plate.				
Push-Pull Class	A. Ampli	fier		
MAXIMUM RATINGS (Same as for Class At Am				
TYPICAL OPERATION (Values are for two tube	-			
Plate Voltage	•	250	285	volts
Grid-No.2 Voltage		250	285	volts
Grid-No.1 (Control-Grid) Voltage		15	· <b>-19</b>	volts
Peak AF Grid-No.1-to-Grid-No.1 Voltage		30	38	volts
Zero-Signal Plate Current		70	70	m A
Maximum-Signal Plate Current		79	92	mA
Zero-Signal Grid-No.2 Current  Maximum-Signal Grid-No.2 Current		5 13	4 13.5	m A m A
maximum-bignar dim-140,2 Curtent		10	10.0	mA

Effective Load Resistance (Plate-to-Plate)	10000 5 10	8000 3.5 14	ohms per cent watts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation		0.1 0.5	megohm megohm
Vertical-Deflection Amplifier (Triode	Connec	ction)≜	
For operation in a 525-line, 30-frame			
MAXIMUM RATINGS (Design-Maximum Values)	,	_	
DC Plate Voltage		350	volts
Peak Positive-Pulse Plate Voltage#		1200 275	volts volts
Peak Negative-Pulse Grid-No.1 (Control-Grid) Voltage		115	m A
		40	mA
Average Cathode Current		10	watts
Plate Dissipation		10	***************************************
MAXIMUM CIRCUIT VALUE			
Grid-No.1-Circuit Resistance, for cathode-bias operation		2.2	megohms

[▲] Grid No.2 connected to plate.

# Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).

Refer to chart at end of section. 6V6GT

Refer to chart at end of section. **6V6GTY** 

Refer to chart at end of section. **6V7G** 

Refer to chart at end of section. 6W4GT

## 6W6GT

#### **BEAM POWER TUBE**

6W6GT

Glass octal type used in the audio output stage of radio and color and black-and-white television receivers. Triode-connected, it is used as a vertical-deflection amplifier in television receivers. Outlines section, 13D; requires octal socket. This type may be supplied with pin No.1 omitted. Type 12W6GT is identical with type 6W6GT except for heater ratings.



7AC

12W6GT

	011001	1244001	
Heater Voltage (ac/dc)	6.3	12.6	volts
Heater Current	1.2	0.6	ampere
Heater Warm-up Time (Average)	_	11	seconds
Heater-Cathode Voltage:			
		1+200 max	
Peak value	$\pm 200~\mathrm{max}$	-300 max	volts
		+100 max	
Average value	100 max	-200 max	volts
Direct Interelectrode Capacitances (Approx.):		( - DOO HIBA	
Grid No.1 to Plate		0.8	рF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid	No 3	15	pF
Plate to Cathode, Heater, Grid No.2, and Grid No.3		9	
Tiale to Cathode, Heater, Grid 140.2, and Grid 140.5	• • • • • • • • • • • • • • • • • • • •	9	pF
Class A, Amplifier	•		
MAYIMIM BATINGS (Design Maximum Values)			
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage		330	volts
Grid-No.2 (Screen-Grid) Voltage		165	volts
Plate Dissipation		12	watts
Grid-No.2 Input		1.35	watts
TYPICAL OPERATION			
Plate Supply Voltage	110	200	volts
Grid-No.2 Supply Voltage	110	125	volts
Grid-No.1 (Control-Grid) Voltage	-7.5		volts
Cathode-Bias Resistor		180	ohms
Peak AF Grid-No.1 Voltage	7.5	8.5	volts
Zero-Signal Plate Current	49	46	mA
Maximum-Signal Plate Current	50	47	mA
Zero-Signal Grid-No.2 Current	4	2.2	mA
Maximum-Signal Grid-No.2 Current	10	8.5	mA
Plate Resistance (Approx.)	13000	28000	ohms

Transconductance Load Resistance Total Harmonic Distortion (Approx.) Maximum-Signal Power Output CHARACTERISTICS (Triode Connection)*	8000 2000 10 2.1	8000 4000 10 3.8	μmhos ohms per cent watts
Plate Voltage Grid-No.1 Voltage Amplification Factor		225 30 6.2	volts volts
Plate Resistance (Approx.) Transconductance Plate Current		1600 3800 22	ohms µmhos mA
Grid No.1 Voltage (Approx.) for plate current of 0.5 mA MAXIMUM CIRCUIT VALUES Grid-No.1 Circuit Resistance:		42	volts
For fixed-bias operation For cathode-bias operation		0.1 0.5	megohm megohm

^{*} Grid No.2 connected to plate.


#### Vertical-Deflection Amplifier


For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)	Triode Connection*	Pentode Connection	
DC Plate Voltage	330	330	volts
Peak Positive-Pulse Plate Voltage#	1200	1500	volts
DC Grid No.2 (Screen-Grid) Voltage		165	volts
Peak Negative-Pulse Grid-No.1 Voltage	275	275	volts
Peak Cathode Current	195	195	m A
Average Cathode Current	65	65	mA
Plate Dissipation	8.5	8	watts
Grid-No.2 Input	_	1.2	watts
MAXIMUM CIRCUIT VALUE			
Grid-No.1-Circuit Resistance, for cathode-bias operation	2.2	2.2	megohms

^{*} Grid No.2 connected to plate.


[#] Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).





Refer to chart at end of section.

**6W7G** 



# FULL-WAVE VACUUM RECTIFIER

6X4

Miniature type used in power supply of automobile and ac-operated radio receivers. Equivalent in performance to larger type 6X5GT. Outlines section, 5D; requires miniature 7-contact socket. This tube, like other power-handling tubes, should be adequately ventilated. For discussion of Rating Chart and Operation

Characteristics, refer to Interpretation of Tube Data. Type 12X4 is identical with type 6X4 except for heater ratings.

Heater Voltage (ac/de) Heater Current	6.34 0.6	12X4 12.6 0.3	volts ampere
Heater-Cathode Voltage: Peak value Average value	+200,	450 max	volts
	100 s	max	volts


A When the heater is operated from a 3-cell (nominal-6-volt) storage-battery source, the permissible heater-voltage range is from 5 to 8 volts.

#### **Full-Wave Rectifier**

MAXIMUM RATINGS (Design-Maximum Values)	
Peak Inverse Plate Voltage	1250 volts
Steady-State Peak Plate Current (Per Plate)	245mA
AC Plate Supply Voltage (Per Plate, rms)	See Rating Chart
DC Output Voltage (At filter input)†	350 volts
Average Output Current (Each plate) †	45 mA
Hot-Switching Transient Plate Current	#


 $\uparrow$  This rating applies when the 6X4 is used in vibrator operation with a minimum duty cycle of 75 per cent.

# If hot-switching is regularly required in operation, the use of choke-input circuits is recommended. Such circuits limit the hot-switching current to a value no higher than that of the peak plate current. When capacitor-input circuits are used, a maximum peak current value per plate of 1.1 amperes during the initial cycles of the hot-switching transient should not be exceeded.



TYPICAL OPERATION Filter Input	Sine Wave C		Vibrator Operation Capacitor	
AC Plate Supply Voltage (Each plate, rms).	. 325	400	- <u> </u>	volts
Filter Input Capacitor			10	$\mu$ F
Effective Plate Supply Impedance (Each plate)				ohms
Filter Input Choke	. —	10	-	henries
Average Output Current	. 70	70	70	mA
DC Output Voltage at Input to Filter (Approx.		340	240	volts

[·] AC plate supply voltage is measured without load.




Refer to chart at end of section.

6X4W

Refer to chart at end of section.

6X5



# FULL-WAVE VACUUM RECTIFIER

6X5GT

Glass octal type used in power supply of automobile and ac-operated receivers. Outlines section, 13D; requires octal socket. This type may be supplied with pin No.1 omitted. For maximum ratings, and typical operation, refer to type 6X4.

Refer to chart at end of section.

6X8



#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

6X8A

19X8

Miniature type used as combined oscillator and mixer tube in television receivers utilizing an intermediate frequency in the order of 40 MHz and in AM/FM receivers. Outlines section, 6B; requires miniature 9-contact socket. Types 5X8 and 19X8 are identical with type 6X8A except for heater ratings.

6X8A


5X8


Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage: Peak value	4.7 0.6 11 ±200 max	6.3 0.45 11 ±200	18.4 0.15 — max ±200 ma	volts ampere seconds
Average value	100 max	100 ı	max 100 ma	x volts
Direct Interelectrode Capacitances: Triode Unit:	Unsh	ielded	Shielded*	
Grid to Plate		1.5	1.5	рF
Grid to Cathode and Heater		2	2.4	ρF
Plate to Cathode and Heater		0.5	1	pF
Pentode Unit:	_			_
Grid No.1 to Plate	. 0.	.09 max	0.06 max	pF
Grid No.1 to Cathode, Heater, Grid No.2, and				_
Grid No.3		4.6	4.8	рF
Plate to Cathode, Heater, Grid No.2, and Grid No.3		0.9	1.6	pF
Pentode Grid No.1 to Triode Plate		05 max	0.04 max	ρF
Pentode Plate to Triode Plate		05 max		pF
Heater to Cathode	. (	5.5	6.5•	рF

- *With external shield connected to cathode except as noted.
- · Wilth external shield connected to pentode plate.

#### Class A, Amplifier

MANUAL DATINGS (S. )			
MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit	Pentode U	nit
Plate Voltage	275	275	volts
Grid No.2 (Screen-Grid) Supply Voltage		275	volts
Grid-No.2 Voltage	S	ee curve pa	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	0	volts
Plate Dissipation	1.7	2.3	watts
Grid-No.2 Input:		2.0	WALLS
For grid-No.2 voltages up to 137.5 volts		0.45	watt
For grid-No.2 voltages between 137.5 and 275 volts	q	e curve par	
To sell tion formates between 101.5 and 210 voics	bi	e curve par	ge 300
CHARACTERISTICS			
Plate Voltage	125	125	volts
Grid No.3			ode at socket
Grid-No.2 Voltage	Conne	125	
Grid-No.1 Voltage	<u>-1</u>		volts
Amplification Factor		1	volt
Plata Posistanas (Annuas)	40		
Plate Resistance (Approx.)	6000	300000	ohms
Transconductance	6500	5500	μmhos
Plate Current	12	9	m A
Grid-No.2 Current		2.2	mA
Grid-No.1 Voltage (Approx.) for plate current of			
20 μΑ	7	<b>6.</b> 5	<b>v</b> ol <b>ts</b>





## 6X9/ ECF200

#### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE

Miniature type used as if-amplifier tube in television receivers. Outlines section 6B, except has 10-pin base; requires miniature 10-contact socket.

G3p,IS (5) (6) Pp GIp(3) (6) Pp Kp(2) (9) PT KT (6) GT
-----------------------------------------------------------------

10K

Heater Voltage	6.3	volts
Heater Current	0.41	ampere
Peak Heater-Cathode Voltage	±150 max	volts
Direct Interelectrode Capacitances:		
Triode Unit:		
Plate to All Other Elements (except grid)	3	рF
Grid to All Other Elements (except plate)	2.5	pF pF
Plate to Grid	2	ρF
Pentode Unit:		• -
Plate to All Other Elements (except grid No.1)	3.5	рF
Grid No.1 to All Other Elements (except plate)	6.5	рF
Grid No.1 to Cathode	4	ρF
Plate to Grid No.1	< 6.5	pF
Grid No.1 to Grid No.2	1.8	pF


Pentode Grid No.1 to Triode Plate Pentode Grid No.1 to Triode Grid Pentode Plate to Triode Plate		${<}^{15}_{<1.2}_{<1.5}$	pF pF pF
Class A, Amplif	ier		
MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit	Pentode Unit	
Plate Supply Voltage	550	550	volts
Plate Voltage	250	250	volts
Peak Plate Voltage	600		volts
Grid-No.2 (Screen-Grid) Supply Voltage		550	volts
Grid-No.2 Voltage	_	250	volts
Cathode Current	18	18	mA.
Plate Dissipation	1.5	2.1	watts
Grid-No.2 Input		0.7	watt
CHARACTERISTICS			
Plate Voltage	170	160	volts
Grid-No.3 (Suppressor-Grid) Voltage		Õ	volts
Grid-No.2 Voltage		135	volts
Grid-No.1 (Control-Grid) Voltage	1	1.7	volts
Mu Factor, Grid-No.1 to Grid-No.2		55	
Amplification Factor	55		
Transconductance	4800	14000	umhos.
Plate Current	8.5	13	m A
Grid-No.2 Current		5	mA
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance	1	1	megohm
ATTILL		4 40 1	

With a maximum duty factor of 0.18 and maximum pulse duration of 18 microseconds.

Refer to chart at end of section.

Heater Voltage (ac/dc)
Heater Current

6Y5



#### **BEAM POWER TUBE**

# 6Y6GA/ 6Y6G

1.25

volts

amperes

Glass octal type used as output amplifier in radio receivers and in rf-operated, high-voltage power supplies in television equipment. Outlines section, 19B; requires octal socket.

Peak Heater-Cathode Voltage	±180 max	volts
Direct Interelectrode Capacitances (Approx.):		
Grid No.1 to Plate	0.7	$\mathbf{pF}$
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3	12	p <b>F</b>
Plate to Cathode, Heater, Grid No.2, and Grid No.3	7.5	$\mathbf{pF}$
Class A, Amplifier		
MAXIMUM RATINGS (Design-Center Values)		
Plate Voltage	200	volts
Grid-No.2 (Screen-Grid) Supply Voltage	200	volts
Grid-No.2 Voltage		page 300
Plate Dissipation	12.5	watts
Grid-No.2 Input:		
For grid-No.2 voltages up to 100 volts	1.75	watts
For grid-No.2 voltages between 100 and 200 volts	See curve	page 300
TYPICAL OPERATION		
Plate Voltage	200	volts
Grid-No.2 Voltage	135	volts
Grid-No.1 (Control-Grid) Voltage13.5	14	volts
Peak AF Grid-No.1 Voltage	14	volts
Zero-Signal Plate Current	61	mA
Maximum-Signal Plate Current	66	mA
Zero-Signal Grid-No.2 Current	2.2	mA
Maximum-Signal Grid-No.2 Current	9	mA
Plate Resistance (Approx.) 9300	18300	ohms
Transconductance	7100	$\mu$ mhos
Load Resistance	2600	ohms
Total Harmonic Distortion 10	10	per cent
Maximum-Signal Power Output	6	watts

#### MAXIMUM CIRCUIT VALUES

Grid-No.1-Circuit Resistance:
For fixed-bias operation
For cathode-bias operation
0.1 megohm
For cathode-bias operation
0.5 megohm

6Y6GT

For replacement use type 6Y6GA/6Y6G.

6Y7G

Refer to chart at end of section.

**6Y9** 

Refer to chart at end of section. For replacement use type 6Y9/EFL200.


6**Y**9/

## 6Y9/EFL200

17Y9

#### **DUAL PENTODE**

Miniature type for use in color and black-and-white television receiver applications. Unit No. 1 is used as a video output pentode, and unit No. 2 as a sound if amplifier, agc amplifier, or sync separator. Outlines section, 6L, except has 10-pin base; requires miniature 10-contact socket. Type 17Y9 is identical with type 6Y9/EFL200 except for heater ratings.



10L

EFI	L200 17¥9	
Heater Voltage 6	5.3 16.5	volts
Heater Current	.8 0.3	ampere
Peak Heater-Cathode Voltage ±2	00 ±200	volts
Direct Interelectrode Capacitances:		
Unit No.1:		
Plate to All Other Elements (except grid No.1)		рF
Grid No.1 to All Other Elements (except plate)		
Plate to Grid No.1	95	
Unit No.2:		•
Plate to All Other Elements (except grid No.1)	11	ρF
Grid No.1 to All Other Elements (except plate)	10	pF
Plate to Grid No.1	140	pF
Grid No.1 to Heater	<100	
Plate to Plate		
Grid to Grid		pF
Plate (Unit No.1) to Grid No.1 (Unit No.2)		
Plate (Unit No.2) to Grid No.1 (Unit No.2)		pF

#### Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Unit No.1	Unit No.2	
Plate Supply Voltage	550	550	volts
Plate Voltage	250	250	volts
Grid-No.2 (Screen-Grid) Supply Voltage	550	550	volts
Grid-No.2 Voltage	250	250	volts
Cathode Current	60	15	mA
Plate Dissipation	5	1.5	watts
Grid-No.2 Input	2.5	0.5	watts
CHARACTERISTICS			
Plate Voltage	170	150	volts
Grid-No.2 Voltage	170	150	volts
Grid-No.1 (Control-Grid) Voltage	-2.6	2.3	volts
Mu Factor, Grid-No.1 to Grid-No.2	38	35	
Internal Resistance	40	160	kohms
Transconductance	21000	850 <b>0</b>	$\mu$ mhos
Plate Current	30	10	mA
Grid-No.2 Current	6.5	3	mA
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance	1	1	megohm

Refer to chart at end of section. For replacement use type 84/6Z4.

Refer to chart at end of section.



#### POWER PENTODE— GATED-BEAM DISCRIMINATOR


6Z10/6J10 10Z10, 13Z10/13J10

Duodecar types used as a combined limiter, discriminator, and audio power-output tube in FM radio and television receivers. Outlines section, 8C; require duodecar 12-contact socket. Types 10Z10, and 13Z10/13J10 are identical with type 6Z10/6J10 except for heater ratings.

IZBI	neater rating	s.			
Heater Voltage (ac/dc) Heater Current Heater Warm-up Time Heater-Cathode Voltage Peak value		6Z10/6J10 6.3 0.95 — ±200 max	10Z10 10 0.6 11 ±200 max	13Z10/13J10 13.2 0.45 11 ±200 max	volts ampere seconds volts
Average value		100 max	100 max	100 max	volts
Direct Interelectrode Ca Pentode Unit:	•			0.000	
Grid No.1 to Grid Grid No.1 to Catho	de, Heater, Grid	No.2, Grid N	o.3, Plate,	0.009	pF
and Internal Shi Grid No.3 to Catho	de. Heater. Grid	No.1, Grid No.	.2, Plate,	4.4	pF
and Internal Shi Beam Power Unit:				3.2	pF
Grid No.1 to Plate Grid No.1 to Catho Plate to Cathode, H	de, Heater, Grid leater, Grid No.2,	No.2, and Gri and Grid No.	d No.3	0.22 11 7.5	pF pF pF
Gate	d-Beam Unit a	ıs Limiter an	d Discrimir	nator	
MAXIMUM RATINGS (	Design-Maximum	Values)			
Plate Supply Voltage				330	volts
Grid-No.2 Voltage Grid-No.1 Voltage, Peak				330	volts
Average Cathode Curren	opositive value			60 13	volts mA
CHARACTERISTICS	It			19	шх
Plate Voltage			135 135	135	volts
Grid-No.3 (Suppressor-G			4 4	Õ	volts
Grid-No.2 (Screen-Grid)			280	280	volts
Grid-No 2 Voltage			75 —	_	volts
Grid No. 1 (Control-Gr	id) Voltage		0 0	0	volts
Grid-No.2 Resistor	N	<i></i>	— 33	33	kohms
Transconductance, Grid	No.1 to Plate	· · · · · · · · · ·		360 700	$\mu$ mhos $\mu$ mhos
Transconductance, Grid Average Plate Current	No.3 to Plate		_ 5	100	μinnos m A
Grid-No.2 Current			4.5	_	mA
Grid No.1 Voltage (App	orox.) for plate c	urrent of			
20 μA Grid No.3 Voltage (App				4	volts
20 μA				-4	volts
	Pentode Unit	as Class A	Amplifier		
MAXIMUM RATINGS (D	esign-Maximum	Values)			
Plate Voltage				275	volts
Grid-No.2 (Screen-Grid)	Voltage			275	volts
Plate Dissipation Grid-No.2 Input	• • • • • • • • • • • • • • • • • • • •		• • • • • • • • • • • •	$^{10}_{\ 2}$	watts watts
TYPICAL OPERATION				4	Watts
Plate Voltage			<b></b>	250	volts
Grid-No.2 Voltage				250	volts
Grid-No.1 (Control-Grid)	) Voltage			8	volts
Peak AF Grid-No.1 Volt	age			8	volts
Zero-Signal Plate Curre	nt			35	mA
Maximum-Signal Plate Czero-Signal Grid-No.2 C	Current	• • • • • • • • • • • • • • • •		39 3	m A m A
Maximum-Signal Grid-N	o? Current			13	mA
Plate Resistance (Appro	o.2 Carrent			0.1	megohm
Transconductance	,			6500	μmhos
Load Resistance				5000	ohms
Total Harmonic Distorti	ion (Approx.)			8.5	per cent
Maximum-Signal Power				4.2	watts
MAXIMUM CIRCUIT VA					
Grid-No.1-Circuit Resista				0.25	megohm
For fixed-bias opera For cathode-bias opera	eration			0.25	megonm megohm

6ZY5G	Refer to chart at end of section.
7A4	Refer to chart at end of section.
7A5	Refer to chart at end of section.
7A6	Refer to chart at end of section.
7A7	Refer to chart at end of section.
7A8	Refer to chart at end of section.
7AD7	Refer to chart at end of section.
7AF7	Refer to chart at end of section.
7AG7	Refer to chart at end of section.
7AH7	Refer to chart at end of section.
7AU7	Refer to type 12AU7A.
<b>7B4</b>	Refer to chart at end of section.
7B5	Refer to chart at end of section.
7B6	Refer to chart at end of section.
7B7	Refer to chart at end of section.
7B8	Refer to chart at end of section.
<b>7C5</b>	Refer to chart at end of section.
<b>7C6</b>	Refer to chart at end of section.
<b>7C7</b>	Refer to chart at end of section.
7DJ8/PCC88	Refer to chart at end of section.
7E6	Refer to chart at end of section.
7E7	Refer to chart at end of section.
7EY6	Refer to chart at end of section.
7 <b>F</b> 7	Refer to chart at end of section.
7F8	Refer to chart at end of section.
7G7	Refer to chart at end of section.
7 <b>G</b> \$7	Refer to type 6GS7.

Refer to chart at end of section.	7H7
Refer to chart at end of section.	7HG8
Refer to type 6HG8/ECF86.	7HG8/PCF86
Refer to chart at end of section.	<b>7J7</b>
Refer to chart at end of section.	7K7




### SHARP-CUTOFF PENTODE

# **7KY6**


Miniature type with frame grid used as video output amplifier in color and black-and-white television receivers. Outlines secton, 6E; requires miniature 9-contact socket.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time Heater-Cathode Voltage:	7.3 0.45 11	volts ampere seconds
Peak value Average value Direct Interelectrode Capacitances:	±200 max 100 max	volts volts
Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2,	0.16 max	pF
Grid No.3, and Internal Shield	14	рF
Grid No.3, and Internal Shield	6	pF
Class A ₁ Amplifier		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage	330 330 See curve	volts volts page 300
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0 9	volts watts
Grid-No.2 Input: For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330 volts	1 See curve	watt page 300
CHARACTERISTICS		
Plate Supply Voltage Grid-No.3 Voltage Grid-No.2 Supply Voltage Grid-No.1 Supply Voltage Grid-No.1 Supply Voltage	200 to cathode a 135 0	volts it socket volts volts



Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 100 \(mu\)A	47 40000 30000 30 5.2 4.5	ohms ohms µmhos mA mA volts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	$\begin{array}{c} 0.1 \\ 0.25 \end{array}$	megohm megohm

7KZ6	Refer to chart at end of section.
7L7	Refer to chart at end of section.
7N7	Refer to chart at end of section.
7Q7	Refer to chart at end of section.
7R7	Refer to chart at end of section.
<b>7</b> \$ <b>7</b>	Refer to chart at end of section.
7 <b>V</b> 7	Refer to chart at end of section.
7W7	Refer to chart at end of section.
7X7	Refer to chart at end of section.
7Y4	Refer to chart at end of section.
7 <b>Z</b> 4	Refer to chart at end of section.
8A8	For replacement use type 9A8/PCF80.
8AC10	Refer to type 6AC10.
8AL9	Refer to chart at end of section.
8AR11	Refer to type 6AR11.
8UA8	Refer to chart at end of section.
A8WA8	Refer to type 6AW8A.
8B8	Refer to type 16A8/PCL82.
8B10	Refer to type 6B10.
8BA8A	Refer to type 6BA8A.
8BA11	Refer to type 6BA11.
8BH8	Refer to chart at end of section.



### **DUAL PENTODE**

# 8BM11

Duodecar type used as if amplifier in television receivers. Unit No.1 is a semiremote-cutoff pentode, and unit No. 2 is a sharp-cutoff pentode. Outlines section, 8B; requires duodecar 12-contact socket. Heater: volts (ac/dc), 8.4; amperes, 0.45; maximum heater-cathode volts,  $\pm 200$  peak, 100 average.

MAXIMUM RATINGS (Design-Maximum Values)	Unit No.1	Unit No.2	
Plate Voltage	160	160	volts
Grid-No.3 (Suppressor-Grid) Voltage	0	0	volts
Grid-No.2 (Screen-Grid) Voltage	160	160	volts
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	0	volts
Plate Dissipation	2.2	2.2	watts
Grid-No.2 Input	0.55	0.55	watt
CHARACTERISTICS			
Plate Supply Voltage	125	125	volts
Grid No.3		ected to catho	
Grid-No.2 Voltage	125	125	volts
Cathode-Bias Resistor	56	120	ohms
Plate Resistance (Approx.)	220000	300000	ohms
Transconductance	8800	8500	$\mu$ mhos
Plate Current	14	9	· mA
Grid-No.2 Current	3.6	2.5	m A
Grid-No.1 Voltage (Approx.) for plate current of			
20 μΑ	_	5.5	volts
Grid-No.1 Voltage (Approx.) for transconductance of			
50 μmho	16.5		volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance, for cathode-bias			
operation	1	0.25	mekohm

Refer to type 6BN8.


**8BN8** 

Refer to chart at end of section.

8BN11

Refer to type 6BQ5.

8BQ5



# SEMIREMOTE-CUTOFF DUAL PENTODE

8BQ11

16BQ11

Duodecar type used as intermediate-frequency amplifier in television receivers. Outlines section, 8B; requires duodecar 12-contact socket. Types 11BQ11 and 16BQ11 are identical with type 8BQ11 except for heater ratings.

11RQ11


Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	8.4 0.6 11	11.2 0.45 11	16 0.315	volts ampere seconds
Heater-Cathode Voltage: Peak value Average value	±200 max 100 max	±200 max 100 max	±200 max 100 max	volts volts
Direct Interelectrode Capacitances: Grid No.1 to Plate		Unit No.1 0.022	Unit No.2 0.024	pF
Grid No.3, and Internal Shield Plate to Cathode. Heater, Grid No.2,		10	_	pF
and Internal Shield		2.8	-	pF
Grid No.3, Grid No.3 of Unit Internal Shield	No.1, and		11	рF

8BO11

Plate to Cathode, Heater, Grid No.2, Grid No.3, Grid No.3 of Unit No.1, and Internal Shield. Plate of Unit No.1 to Plate of Unit No.2		. 0.002 . 0.008	DF DF DF DF DF
Class A. Amplifier			
MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage	Unit No.1	Unit No.2	
Grid-No.3 (Suppressor-Grid) Voltage	330	330	volts
Grid-No.2 (Screen-Grid) Supply Voltage	330	0	volts
Grid-No.2 Voltage	330	330	volts
Grid-No.1 (Control-Grid) Voltage, Positive-bias value		urve page 300	
Plate Dissipation	0 (	O O	volts
Grid-No.2 Input:	3.1	3.Ĭ	watts
For grid-No.2 voltages up to 165 volts	0.65	0.65	watt
For grid-No.2 voltages between 165 and 330 volts		urve page 300	
CHARACTERISTICS	200	aric page out	
Plate Supply Voltage	125	125	volta
Grid No.3		ected to catho	
Grid-No.2 Voltage	125	125	volts
Cathode-Bias Resistor	56	56	ohms
Plate Resistance (Approx.)	0.2	0.2	megohm
Transconductance	10500	13000	μmhos
Plate Current	11	11	mA
Grid-No.2 Current	3.5	3.8	mA
Grid-No.1 Voltage (Approx.) for plate current			
of 20 μA		3	volts
Grid-No.1 Voltage (Approx.) for transconductance			
of 50 μmho	15		volts
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance, for cathode-bias			
operation	1	0.25	megohm
-	-		

### 8BU11 MEDIUM-MU TWIN TRIODE— SHARP-CUTOFF PENTODE

Duodecar type used in television receiver applications. Outlines section, 8C; requires duodecar 12-contact socket. Heater: volts (ac/dc), 7.8; amperes, 0.6; warm-up time, 11 seconds, maximum heater-cathode volts,  $\pm 200$  peak, 100 average.




Each

#### Class A. Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Pentode Unit	Triode Unit	
Plate Voltage		330	volts
Grid-No.2 (Screen-Grid) Supply Voltage			volts
Grid-No.2 Voltage		300	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	0	volts
Plate Dissipation	2.5	1.8	watts
Grid-No.2 Input:	2.0		
For grid-No.2 voltages up to 165 volts	0.55		watt
For grid-No.2 voltages between 165 and 330 volts		300	
CHARACTERISTICS	Dec da-ve puge	•••	
	*05	105	
Plate Supply Voltage	125	125	volts
Grid-No.2 Voltage	125		volts
Grid-No.1 Voltage	1	_	volts
Cathode-Bias Resistor	-	68	ohms
Amplification Factor	-	43	
Plate Resistance (Approx.)	200000	<b>5000</b> 0	ohms
Transconductance	7500	8600	μm hos
Plate Current	12	13.5	mA
Grid-No.2 Current	4		mA
Grid Voltage (Approx.) for plate current of 100 µA		8	volts
Grid-No.1 Voltage (Approx.) for plate current			
of 30 μA	8	_	volts
MAXIMUM CIRCUIT VALUES	-		
Grid-No.1-Circuit Resistance:			
For fixed-bias operation	0.5	0.5	megohm
For cathode-bias operation	1	1	megohm

Refer to chart at end of section.	8CB11
For replacement use type 8FQ7/8CG7.	8CG7
Refer to type 6CM7.	8CM7
Refer to chart at end of section.	8CN7
Refer to type 6CS7.	8C\$7
Refer to type 6CW5/EL86.	8CW5/XL86
Refer to type 6CW5.	8CW5
Refer to type 6CX8.	8CX8
Refer to chart at end of section. For replacement use type 8GN8/8EB8.	8EB8
Refer to type 6EM5.	8EM5
Refer to chart at end of section.	8ET7
Refer to chart at end of section.	8FQ7
Refer to type 6FQ7/6CG7.	8FQ7/8CG7
Refer to chart at end of section.	8GJ7
Refer to type 6GJ7/ECF801.	8GJ7/PCF801
Refer to type 6GN8.	8GN8 8GN8/8EB8
Refer to type 6GU7.	8GU7
Refer to type 6JU8A.	A8UL8
Refer to type 6JV8.	81 <b>/</b> 8
Refer to type 6KA8.	8KA8
Refer to type 6LC8.	8FC8
Refer to type 6LT8.	8LT8
Refer to chart at end of section.	9 <b>A</b> 8



### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

9A8/ PCF80

Miniature type used as combined oscillator and mixer tubes in vhf color and black-and-white television receivers. Outlines section, 6B; requires miniature 9-contact socket. Heater: volts (ac/dc), 9; amperes, 0.3; maximum heater-cathode volts, +100, -200 peak; -120 average.

Class A. Amplifie	CI	ass	Α.	Am	m	lifie	r
-------------------	----	-----	----	----	---	-------	---

MAXIMUM RATINGS (Design-Center Values)	Triode Unit	Pentode Unit	
Plate Supply Voltage	550	550	volts
Plate Voltage	250	250	volts
Grid-No.2 (Screen-Grid) Voltage		175	volts
Cathode Current	14	14	mA
Plate Dissipation	1.5	1.7	watts
Grid-No.2 Input	_	0.5	watt


CHARACTERISTICS Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid-No 2 Current	100 -2 20 5000 14	170 170 2 47* 0.4 6200 10 2.8	volts volts volts megohm µmhos mA mA
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation * Grid No.2 to Grid No.1.	0.5	0.5	megohm
	0.5	1	megohm

9AH9	Refer to chart at end of section.
9AK10	Refer to chart at end of section.
9AM10	Refer to chart at end of section.
9AQ8/PCC85	Refer to chart at end of section.
9AU7	Refer to type 12AU7A.
9BJ11	Refer to chart at end of section.
9BR7	Refer to chart at end of section.
9CL8	Refer to chart at end of section.
9EA8	Refer to chart at end of section.
9GH8A	Refer to type 6GH8A.
9GV8	Refer to chart at end of section.
9GV8/XCL85	Refer to type 6GV8/ECL85.
9JW8/PCF802	Refer to type 6JW8/ECF802.
9KC6	Refer to chart at end of section.

# **9KX6**

### SHARP-CUTOFF PENTODE

Miniature type with frame grid used as video output amplifier in color and black-and-white television receivers. Outlines section, 6E; requires miniature 9-contact socket. Heater: volts, 8.7; amperes, 0.45; warm-up time, 11 seconds; maximum heater-cathode volts, ±200 peak, 100 average.



#### Class A. Amplifier


MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	400	volts
Grid-No.3 (Suppressor-Grid) Voltage, Positive value		volts
Grid-No.2 (Screen-Grid) Supply Voltage		
Grid-No.2 Voltage	See curve	page 300
Grid-No.1 (Control-Grid) Voltage, Positive value	0	volts
Plate Dissipation	11.5	watts
Grid-No.2 Input	1.5	watts
CHARACTERISTICS		

OHARAGI ERIOTIOS			
Plate Voltage	250	50	volts
Grid-No.3 Voltage		to cathode	
Grid-No.2 Supply Voltage	150	125	volts
Grid-No.1 Voltage	0	0	volts

Refer to type 6KZ8.  Refer to chart at end of section.	9KZ8 9LA6 9MN8	
Refer to chart at end of section.		
	9MN8	
Refer to type 6MN8.		
For replacement use type 10DE7.	9RAL1	
Refer to type 6U8A.	9U8A	
Refer to chart at end of section.	10	
Refer to type 6AL11.	10AL11	
Refer to type 6BQ5.	10BQ5	
Refer to chart at end of section.	10C8	
Refer to chart at end of section.	10CW5	
Refer to type 6CW5/EL86.	10CW5/LL8	36
Refer to type 6DE7.	10DE7	
Refer to type 6DR7.	10DR7	
Refer to chart at end of section.	10DX8	
Refer to type 6DX8/ECL84.	10DX8/LCL	84
Refer to chart at end of section.	10EG7	
Refer to type 6EM7.	10EM7	
Refer to type 6EW7.	10EW7	
Refer to chart at end of section.	10GF7	
Refer to type 6GF7A.	10GF7A	
Refer to type 6GK6.	10GK6	
Refer to type 6GN8.	10GN8	
Refer to type 6GV8/ECL85.	OGV8/LCL	<b>B</b> 5
Refer to type 6HF8.	10HF8	
Refer to chart at end of section.	10JA5	
Refer to type 10JA8/10LZ8	10JA8	

# 10JA8/ 10LZ8

#### HIGH-MU TRIODE— SHARP-CUTOFF PENTODE



9DX


Miniature type used in color and black-and-white television receiver applications. The triode unit is used as a sync separator, sync clipper, and phase inverter; the


pentode unit is used as a video amplifier. Outlines section, 6E; requires miniature 9-contact socket.

Heater Voltage (ac/dc)	10.5	volts
Heater Current	0.45	ampere
Heater Warm-up Time	11	seconds
Heater-Cathode Voltage:		
Peak value	$\pm 200 \text{ max}$	volts
Average value	100 max	volts
Direct Interelectrode Capacitances:		
Triode Unit:		
Grid to Plate	4	рF
Grid to Cathode, Pentode Cathode, Heater, Pentode Grid No.3,		
and Internal Shield	2.6	рF
Plate to Cathode, Pentode Cathode, Heater, Pentode Grid No.3,		
and Internal Shield	2.6	рF
Pentode Unit:		
Grid No.1 to Plate	0.1  max	рF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and		
Internal Shield	11	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and		
Internal Shield	4.4	рF
Grid No.1 to Triode Plate	0. <b>0</b> 05 max	$\mathbf{pF}$
Plate to Triode Grid	0.018 max	pF
Plate to Triode Plate	0.17 max	pF

#### Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Triode Unit	Pentode Unit	
Plate Voltage	300	330	volts
Grid-No.2 (Screen-Grid) Supply Voltage		330	volts
Grid-No.2 Voltage	- 8	See curve page 300	
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	0	volts
Plate Dissipation	1	5	watts
Grid-No.2 Input:			
For Grid-No.2 voltages up to 165 volts		1.5	watts
For Grid-No.2 voltages between 165 and 330 volts	8	See curve page 300	ı






HARACTERISTICS Tr		riode Unit Pentod		Pentode U	e Unit	
Plate Voltage	135	200	30	135	200	volts
Grid-No.2 Voltage		_	135	135	135	volts
Grid-No.1 Voltage	2	<b>—2</b>	0	1.5	1.5	volts
Amplification Factor	60	70				
Plate Resistance	39000	19000	_	66000	70000	ohms
Transconductance	1550	3700	_	12600	14000	μmhos

Plate Current		3.5	32• 14•	17 4.2		mA mA
Grid-No.1 Voltage (Approx.) for plate current of 10 μA MAXIMUM CIRCUIT VALUES	-4.8	7	_	5	5	volts
Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation			0.5		Pentode Unit 0.25 1	megohm megohm

 This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

Refer to type 6JT8.

10JT8



#### MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE 10JY8

Miniature type used in television receiver applications. The pentode unit is used as a video amplifier, and the triode unit as a sync separator. Outlines section, 6E; requires miniature 9-contact socket. Heater: volts (ac/dc), 10.5; amperes, 0.45; warm-up time (average), 11 seconds; maximum heater-cathode volts, ±200 peak,

100 average (-300 peak, -200 average for triode unit).

### Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Triode Uni			14
Plate Voltage	330	330		volts
Grid-No.2 (Screen-Grid) Supply Voltage		330		volts
Grid-No.2 Voltage		See curv		
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0 2		0 5	volts
Plate Dissipation	Z	•	3	watts
Grid-No.2 Input:				
For Grid-No.2 voltages up to 165 volts		2 1.3		watts
For Grid-No.2 voltages between 165 and 330 volts	_	See curv	e page 3	300
CHARACTERISTICS				
Plate Voltage	125	50	200	volts
Grid-No.2 Voltage	·	150	150	volts
Grid-No.1 Voltage		_ 0		volts
Cathode-Bias Resistor	68		100	ohms
Amplification Factor	46	_		
Plate Resistance (Approx.)	4400	_	55000	ohms
Transconductance	10400	-	11000	$\mu$ mhos
Plate Current	15	60•	24	mA
Grid-No.2 Current		18=	4.8	mA
Grid Voltage (Approx.) for plate current of 10 \( \mu A \)	—8	_	—10	volts
MAXIMUM CIRCUIT VALUES				
Grid-No.1-Circuit Resistance:				
For fixed-bias operation	0.5	0.23	5	megohm
For cathode-bias operation	1	1	l	megohm
• This value can be measured by a method involving a maximum ratings of the tube will not be exceeded.	a recurrent	wavefor	m such	that the

Refer to type 6KR8.	10KR8
Refer to type 6KU8.	10KU8
Refer to chart at end of section.	10LB8
Refer to type 6LE8.	10LE8
Refer to chart at end of section.	10LW8
Refer to type 6LY8.	10LY8
Refer to chart at end of section. For replacement use type 10JA8/10LZ8.	10LZ8
Refer to type 6T10.	10110

10Z10

Refer to type 6Z10.

11

Refer to chart at end of section.

11AF9

Refer to type 6AF9.


11AR11

Refer to type 6AR11.

## 11BM8

#### HIGH-MU TRIODE— **POWER PENTODE**

Miniature type used as vertical deflection oscillator or af amplifier and vertical deflection amplifier or af nower amplifier in television receivers. Outlines section. 6G: requires miniature 9-contact socket. This type is identical with type 16A8/PCL82 except for the following items:



9EX

volts

10.7

0.45

Heater Voltage Heater Current


Refer to type 8BQ11.

### IIBTII

11BQ11

#### **DUAL TRIODE**— SHARP-CUTOFF PENTODE

Duodecar type used in television receiver applications. The triode units are used for general-purpose applica- 670 tions; the pentode unit is used in video-amplifier service. Outlines section, 8B; requires duodecar 12contact socket. Heater: volts (ac/dc), 10.7; amperes. 0.6; warm-up time (average), 11 seconds; maximum heater-cathode volts, ±200 peak, 100 average.



12**GS** 

#### Class A. Amplifier

#### MAXIMUM RATINGS (Design-Maximum Values)

	Unit No. 1	Triode Unit No. 2		ntode Init	
Plate Voltage	330	330	1	165	volts
Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage,	_	_	1	165	volts
Positive-bias value	0	0		0	volts
Plate Dissipation	1.5	2		3.5	watts
Grid-No.2 Input	-			1.5	watts
CHARACTERISTICS					
Plate Voltage	200	200	35	150	volts
Grid-No.2 Voltage	_	<del></del>	100	100	volts
Grid-No.1 Voltage		_	0		volts
Cathode-Bias Resistor	270	470		82	ohms
Amplification Factor	69	40		<u> </u>	
Plate Resistance (Approx.)	12500	7600	_	51000	ohms
Transconductance	5500	5300	_	19000	μmhos
Plate Current	7.1	7.2	54	17.4	mA
Grid-No.2 Current	-		13.5	3.2	mA
Grid-No.1 Voltage (Approx.) for					
plate current of 100 $\mu$ A	-	8	_	6.6	volts
Grid-No.1 Voltage (Approx.) for					
plate current of 50 $\mu A$	5.5	_	_		volts

#### MAXIMUM CIRCUIT VALUES

Grid-No.1-Circuit Resistance:	Triode Unit No. 1	Triode Unit No. 2	Pentode Unit	
For fixed-bias operation For cathode-bias operation	0.5	0.5	0.05	megohm
	1	1	0.1	megohm


Refer to chart at end of section.	11CA11
Refer to chart at end of section.	11CF11
Refer to chart at end of section.	11CH11
Refer to chart at end of section.	11CY7
Refer to type 6DS5.	11DS5
Refer to type 6FY7.	11FY7



# SHARP-CUTOFF PENTODE 11HM7

Miniature type with frame grid used as video output amplifier in color television receivers. Outlines section, 6E; requires miniature 9-contact socket.

Heater Arrangement Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage:	Series 11 0.3	Parallel 5.5 0.6	volts ampere
Peak value Average value Direct Interelectrode Capacitances:		±200 max 100 max	volts volts
Grid No.1 to Plate	• • • • • • • •	0.15 max	$\mathbf{pF}$
and Internal Shield	• • • • • • •	14	$p\mathbf{F}$
and Internal Shield	• • • • • • •	Б	$p\mathbf{F}$
Class A, Amplifier			
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input:		330 330 See curve 0 7	volts volts page 300 volts watts
For grid-No.2 voltages up to 165 volts		1 See curve	watt page 300



CHARACIERISTICS		
Plate Supply Voltage	200	volts
Grid-No.3 Voltage	0	volts
Grid-No.2 Voltage	135	volts
Cathode-Bias Resistor	47	ohms

Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 100 µA	40000 30000 30 5.2 —4.5	ohms µmhos mA mA volts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.1 0.25	megohm megohm

11JE8 Refer to chart at end of section.

11LQ8 Refer to type 6KV8.

Refer to type 6LQ8.

Refer to type 6LT8.

# 11MS8

For fixed-bias operation

#### HIGH-MU TRIODE— BEAM POWER TUBE

Miniature type used in combined vertical-deflection-oscillator and vertical-deflection-amplifier applications in black-and-white television receivers. Outlines section, 6G; requires miniature 9-contact socket. Heater: volts, 11.6; ampere, 0.45; warm-up time (approx.), 11 seconds; maximum heater-cathode volts,  $\pm 200$  peak, 100 average.



megohm

megohms

#### Class A, Amplifier

CHARACTERISTICS	Triode Unit		Beam Power Unit		
Plate Voltage	100	100	120	volts	7
Grid-No. 1 (Control-Grid) Voltage	_		110	volts	
Grid-No. 1 (Control-Grid) Voltage	0.85	0	—10	volts	
Plate Current	` 5	10	50	mA	
Grid-No. 2 Current			3	mA	
Transconductance	5 <b>5</b> 00	7000	8500	$\mu$ mhos	
Amplification Factor*	60	63	5.8		
Plate Resistance (Approx.)	11	9	13	kilohms	

#### Vertical-Deflection Oscillator and Amplifier

#### For operation in a 525-line, 30-frame system MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Peak Positive Pulse Plate Voltage# Grid-No. 2 Voltage Grid-No. 1 Voltage 250 volts 2000 volts 200 volte 0 volts Plate Dissipation Grid-No. 2 Input 6 watts vatts Average Cathode Current ..... mΑ MAXIMUM CIRCUIT VALUES Grid-No. 1 Circuit Resistance megohm Grid-No. 1 Circuit Resistance:

# Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).

* Grid-No. 2 connected to plate at socket.

For cathode-bias operation .....

11Y9 Refer to chart at end of section.

11Y9/LFL200 Refer to chart at end of section.

12A5 Refer to chart at end of section.

12A6 Refer to chart at end of section.

Refer to chart at end of section.	12A6Y
Refer to chart at end of section.	12A7
Refer to chart at end of section.	12A8G1



MAXIMUM RATINGS (Design-Center Values)

For fixed-bias operation

For cathode-bias operation . . .

#### **BEAM POWER TUBE**

# **12AB5**

0.1

0.5

megohm

megohm

Miniature type used in the output stage of automobile radio receivers operating from a 12-volt storage battery. Outlines section, 6E; requires miniature 9-contact socket.

Heater-Voltage Range (ac/dc).  Heater Current (Approx.) at 12.6 volts  Peak Heater-Cathode Voltage	10 to 15.9 0.2 ±90 max	volts ampere volts
Direct Interelectrode Capacitances: Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 Plate to Cathode, Heater, Grid No.2, and Grid No.3	0.7 max 8 8.5	pF pF pF
a Few language life it is recommended that the heater he enquated wit	hin the walte	~~ "nnm~

• For longest life, it is recommended that the heater be operated within the voltage range of 11 to 14 volts.


### Class A, Amplifier

MAXIMOM RATINGS (Design-Center Values)		
Plate Voltage	315	volts
Grid-No.2 (Screen-Grid) Voltage	285	volts
Plate Dissipation	12	watts
Grid-No.2 Input	2	watts
Bulb Temperature (At hottest point)	250	°C
TYPICAL OPERATION WITH 12.6 VOLTS ON HEATER		
Plate Supply Voltage	250	volts
Grid-No.2 Supply Voltage	250	volts
Grid-No.1 (Control-Grid) Voltage	-12.5	volts
Cathode-Bias Resistor		ohms
Peak AF Grid-No.1 Voltage	12.5	volts
Zero-Signal Plate Current	45	mA
Maximum-Signal Plate Current	47	mA
Zero-Signal Grid-No.2 Current	4.5	mA
Maximum-Signal Grid-No.2 Current	7	mA
Plate Resistance (Approx.) 75000	50000	ohms
Transconductance	4100	μmhos
Load Resistance 6000	5000	ohms
Total Harmonic Distortion	8	per cent
Maximum-Signal Power Output 3.3	4.5	watts
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.1	megohm
For cathode-bias operation	0.5	megohm
3 Or Chamber Operation	3.0	cgonni

#### Push-Pull Class AB, Amplifier

# MAXIMUM RATINGS (Same as for Single-Tube Class A₁ Amplifier) TYPICAL OPERATION WITH 12.6 VOLTS ON HEATER (Values are for two tubes) Plate Voltage 250

Plate Voltage	250	volts
Grid-No.2 Voltage	250	volts
Grid-No.1 Voltage	—15	volts
Peak AF Grid-No.1-to-Grid-No.1 Voltage		volts
Zero-Signal Plate Current	70	mA
Maximum-Signal Plate Current	79	mA
Zero-Signal Grid-No.2 Current		mA
Maximum-Signal Grid-No.2 Current		mA
Effective Load Resistance (Plate-to-Plate)		ohms
Total Harmonic Distortion		per cent
Maximum-Signal Power Output	10	watts
MAXIMUM CIRCUIT VALUES		
Crid-No 1-Circuit Resistance:		




12AC6 Refer to chart at end of section. 12AC10A Refer to type 6AC10 12AD6 Refer to chart at end of section. 12AE6 Refer to chart at end of section. 12AE6A 12AE7 Refer to chart at end of section.

#### BEAM POWER TUBE-12AE10 SHARP-CUTOFF PENTODE

Duodecar type used as combined FM detector and audio-frequency output amplifier in television receivers. The beam power unit is used in af output stages and the pentode unit as an FM detector. Outlines section, 8C; requires duodecar 12-contact socket. Heater: volts (ac/dc), 12.6; amperes, 0.45; warm-up time (average), 11 seconds; maximum heater-cathode volts, ±200 peak, 100 average.

For cathode-bias operation




megohm

- com i ener ent se enace Mi Ampinion		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	165	volts
Grid-No.2 (Screen-Grid) Voltage	150	volts
Cathode Current	60	mA
Plate Dissipation	6	watts
Grid-No.2 Input	1.25	watta
TYPICAL OPERATION		
Plate Voltage	145	volts
Grid-No.2 Voltage	110	volts
Grid-No.1 (Control-Grid) Voltage	7	volts
Peak AF Grid-No.1 Voltage	7	volts
Zero-Signal Plate Current	34	mA
Maximum-Signal Plate Current	39	mA
Zero-Signal Grid-No.2 Current	6.5	mA
Maximum-Signal Grid-No.2 Current	9.3	mA
Plate Resistance (Approx.)	33000	ohms
Transconductance	5600	μmhos
Load Resistance	2500	ohms
Total Harmonic Distortion (Approx.)	12	per cent
Maximum-Signal Power Output	1.45	watts
MAXIMUM CIRCUIT VALUE		
Grid-No.1-Circuit Resistance:		

Beam Power Unit as Class A. Amplifier

Pentode Unit as Class A. Amplitter	
CHARACTERISTICS	
Plate Voltage	150 volts
Grid-No.3 (Suppressor-Grid) Voltage	0 volts
Grid-No.2 Voltage	100 volts
Cathode-Bias Resistor	560 ohms
Plate Resistance (Approx.)	0.15 megohm
Transconductance, Grid No.1 Transconductance, Grid No.3	1000 μmhos
Transconductance, Grid No.3	400 μmhos
Plate Current	1.3 mA
Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 $\mu$ A	2 mA -4.5 volts
Grid-No.3 Voltage (Approx.) for plate current of 10 $\mu$ A	-4.5 volts
Grid-No.5 voitage (Approx.) for place current of to \$\mu \text{A}	-4.5 Voits
Pentode Unit as FM Detector	
MAXIMUM RATINGS (Design-Maximum Values)	
Plate Voltage	330 volts
Grid-No.3 Voltage	28 volts
Grid-No.2 Supply Voltage	_330 volts
Grid-No.2 Voltage	See curve page 300
Grid-No.1 Voltage, Positive-bias value	0 volts
Plate Dissipation	1.7 watts
Grid-No.2 Input	1.1 watts
	12AF3
Refer to type 6AF3.	12AF3/12BR3/
•	
	12010
	12RK19
Refer to chart at end of section.	12RK19 12AF6
Refer to chart at end of section.	
	12AF6
Refer to chart at end of section.  Refer to chart at end of section.	
	12AF6
Refer to chart at end of section.	12AF6 12AH7GT
	12AF6
Refer to chart at end of section.	12AF6 12AH7GT
Refer to chart at end of section.  Refer to chart at end of section.	12AF6 12AH7GT 12AJ6
Refer to chart at end of section.	12AF6 12AH7GT
Refer to chart at end of section.  Refer to chart at end of section.  Refer to type 6AL5.	12AF6 12AH7GT 12AJ6 12AL5
Refer to chart at end of section.  Refer to chart at end of section.	12AF6 12AH7GT 12AJ6
Refer to chart at end of section.  Refer to chart at end of section.  Refer to type 6AL5.	12AF6 12AH7GT 12AJ6 12AL5
Refer to chart at end of section.  Refer to chart at end of section.  Refer to type 6AL5.  Refer to chart at end of section.	12AF6 12AH7GT 12AJ6 12AL5 12AL8
Refer to chart at end of section.  Refer to chart at end of section.  Refer to type 6AL5.	12AF6 12AH7GT 12AJ6 12AL5
Refer to chart at end of section.  Refer to chart at end of section.  Refer to type 6AL5.  Refer to chart at end of section.	12AF6 12AH7GT 12AJ6 12AL5 12AL8
Refer to chart at end of section.  Refer to chart at end of section.  Refer to type 6AL5.  Refer to chart at end of section.  Refer to type 6AL11.	12AF6 12AH7GT 12AJ6 12AL5 12AL8 12AL11
Refer to chart at end of section.  Refer to chart at end of section.  Refer to type 6AL5.  Refer to chart at end of section.	12AF6 12AH7GT 12AJ6 12AL5 12AL8
Refer to chart at end of section.  Refer to chart at end of section.  Refer to type 6AL5.  Refer to chart at end of section.  Refer to type 6AL11.	12AF6 12AH7GT 12AJ6 12AL5 12AL8 12AL11 12AQ5
Refer to chart at end of section.  Refer to chart at end of section.  Refer to type 6AL5.  Refer to chart at end of section.  Refer to type 6AL11.  Refer to type 6AQ5A.	12AF6 12AH7GT 12AJ6 12AL5 12AL8 12AL11
Refer to chart at end of section.  Refer to chart at end of section.  Refer to type 6AL5.  Refer to chart at end of section.  Refer to type 6AL11.	12AF6 12AH7GT 12AJ6 12AL5 12AL8 12AL11 12AQ5
Refer to chart at end of section.  Refer to chart at end of section.  Refer to type 6AL5.  Refer to chart at end of section.  Refer to type 6AL11.  Refer to type 6AQ5A.	12AF6 12AH7GT 12AJ6 12AL5 12AL8 12AL11 12AQ5




**HIGH-MU TWIN TRIODE** 

12AT7/ ECC81

Miniature types used as push-pull cathode-drive amplifiers or frequency converters in the FM and television broadcast bands. Outlines section, 6B; require miniature 9-contact socket. Each triode unit is independent of the other except for the common heater. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section.

Heater Arrangement:	Series	Parallel	
Heater Voltage (ac/dc)	12.6	6.3	volts
Heater Current	0.15	0.3	ampere
Peak Heater-Cathode Voltage		±90 max	volts

Direct Interelectrode Capacitances: Grid-Drive Operation: Grid to Plate (Each unit)		
Grid to Cathode and Heater (Each unit)	1.5	₽F
Plate to Cathode and Heater:	2.2	рF
Unit No.1		
Unit No 9	0.5	p <b>F</b>
Unit No.2 Cathode-Drive Operation:	0.4	pF
Cathode to Plate (Each unit)	0.2	рF
Cathode to Grid and Heater (Each unit)	4.6	pF
Plate to Grid and Heater (Each unit)	1.8	pF
Heater to Cathode (Each Unit)	2.4	pF
Class A. Amplifier (Each Unit)		
MAXIMUM AND MINIMUM RATINGS (Design-Center Values)	•	
Plate Voltage	300	volts
Grid Voltage, Negative-bias value	50	volts
Plate Dissipation	2.5	watts
	2.0	Watts



CHARACTERISTICS			
Plate Supply Voltage	100	250	volts
Cathode-Bias Resistor	270	200	ohms
Amplification Factor	60	60	
Plate Resistance (Approx.)	15000	10900	ohms
Transconductance	4000	5500	μmhos
Grid Voltage (Approx.) for plate current of 10 µA	5	12	volts
Plate Current	3.7	10	mA

12AT7WA 12AT7WB 12AU6

Refer to chart at end of section. Refer to chart at end of section.

Refer to type 6AU6A.

12AU7


Refer to chart at end of section. For replacement use type 12AU7A/ECC82.

**12AU7A** For replacement use type 12AU7A/ECC82.

12AU7A/ ECC82


MEDIUM-MU TWIN TRIODE

7AU7, 9AU7 Miniature types used as phase inverters or push-pull amplifiers in ac/dc radio equipment and as multivibrators or oscillators in industrial control devices. Also used as combined



vertical oscillators and vertical-deflection amplifiers, and as horizontaldeflection oscillators, in color and black-and-white television receivers. Outlines section, 6B; require miniature 9-contact socket. Each triode unit is independent of the other except for the common heater. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. Types 7AU7 and 9AU7 are identical with type 12AU7 and 12AU7A/ECC82 except for heater ratings.

ECC82 except for heater ratings.		• • • • • • • • • • • • • • • • • • • •		
			12AU 12AU7	'A/
Heater Voltage(ac/dc):	7AU7	9AU		
Series Parallel Heater Current:	3.5	9.4 4.7	12.6 6.3	volts volts
Series	0.3	0.225	0.15	ampere
Parallel Heater Warm-up Time (Parallel, Average) Heater-Cathode Voltage:	0.6 11	0.45 11	0.3	ampere seconds
Peak value	100 max	100	max ±200 max 100 i Jnit No.2	max volts max volts
Direct Interelectrode Capacitances (Approx.): Grid to Plate		1.5	1.5	рF
Grid to Cathode and Heater Plate to Cathode and Heater		1.6 0.5	1.6 0.35	pF pF
Class A. Amplifier (Each Unit Ur	less Oth	erwise	Specified	)
MAXIMUM RATINGS (Design-Maximum Values)				
Plate Voltage Cathode Current Plate Dissipation:	• • • • • • • • • •		330 22	volts mA
Each Plate Both Plates (Both units operating)	· · · · · · · · · · · · · · · · · · ·		2.75 5.5	watts watts
CHARACTERISTICS				
Plate Voltage Grid Voltage	1	00	250	volts
Grid Voltage	1	9.5	8.5 17	volts
Plate Resistance (Approx.)	62	50	7700	ohms
Transconductance	31	100 1.8	2200 10.5	μmhos mA
Plate Current Grid Voltage (Approx.) for plate current of 10 $\mu$	A.	<u></u>	24	volts
MAXIMUM CIRCUIT VALUES				
Grid-Circuit Resistance: For fixed-bias operation For cathode-bias operation			0.25 1	megohm megohm
Oscillator (Each Unit Unless	Otherwi	se Spe	cified)	
For operation in a 525-line,	Ver	tical-	Horizontal- Defiection	
MAXIMUM RATINGS (Design-Maximum Values) DC Plate Voltage	Osci	llator 30	Oscillator 330	74
DC Plate Voltage Peak Negative-Pulse Grid Voltage	. 4	30 40	660	volts volts
Peak Cathode Current		66	330	mA
Average Cathode Current	•	22	22	mA
Each Plate	. 2.		2.75	watts
Both Plates (Both units operating)	. 5	.5	5.5	watts
MAXIMUM CIRCUIT VALUES				
	0	.2	2.2	
Grid-Circuit Resistance	. 4		2.2	megohms
Vertical-Deflection Amplifier (Each Unit	Unless	Otherv		_
Vertical-Deflection Amplifier (Each Unit For operation in a 525-line,	Unless	Otherv		_
Vertical-Deflection Amplifier (Each Unit For operation in a 525-line, MAXIMUM RATINGS (Design-Maximum Values) DC Plate Voltage	Unless 30-frame	Otherv system	vise Spec	ified)
Vertical-Deflection Amplifier (Each Unit For operation in a 525-line, MAXIMUM RATINGS (Design-Maximum Values) DC Plate Voltage Peak Positive-Pulse Plate Voltage#	Unless 30-frame	Otherv system	vise Spec	ified)  volts
Vertical-Deflection Amplifier (Each Unit For operation in a 525-line, MAXIMUM RATINGS (Design-Maximum Values) DC Plate Voltage Peak Positive-Pulse Plate Voltage# Peak Negative-Pulse Grid Voltage	Unless 30-frame	Otherv system	330 1200 275	ified)  volts  volts  volts
Vertical-Deflection Amplifier (Each Unit For operation in a 525-line, MAXIMUM RATINGS (Design-Maximum Values) DC Plate Voltage Peak Positive-Pulse Plate Voltage# Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current	Unless 30-frame	Otherv system	vise Spec	ified)  volts
Vertical-Deflection Amplifier (Each Unit For operation in a 525-line, MAXIMUM RATINGS (Design-Maximum Values) DC Plate Voltage Peak Positive-Pulse Plate Voltage# Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation:	Unless 30-frame	Otherv	330 1200 275 66 22	volts volts volts mA mA
Vertical-Deflection Amplifier (Each Unit For operation in a 525-line, MAXIMUM RATINGS (Design-Maximum Values) DC Plate Voltage Peak Positive-Pulse Plate Voltage# Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current	Unless 30-frame	Otherv	vise Spec	volts volts volts mA
Vertical-Deflection Amplifier (Each Unit For operation in a 525-line, MAXIMUM RATINGS (Design-Maximum Values) DC Plate Voltage Peak Positive-Pulse Plate Voltage# Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation: Each Plate	Unless 30-frame	Otherv	330 1200 275 66 22 275	volts volts volts mA mA
Vertical-Deflection Amplifier (Each Unit For operation in a 525-line, MAXIMUM RATINGS (Design-Maximum Values) DC Plate Voltage Peak Positive-Pulse Plate Voltage# Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation: Each Plate Both Plates (Both units operating) MAXIMUM CIRCUIT VALUE	Unless 30-frame	Otherv system	330 1200 275 66 22 275	volts volts volts mA volts watts
Vertical-Deflection Amplifier (Each Unit For operation in a 525-line, MAXIMUM RATINGS (Design-Maximum Values) DC Plate Voltage Peak Positive-Pulse Plate Voltage# Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation: Each Plate Both Plates (Both units operating)	Unless 30-frame	Otherv system	330 1200 275 66 22 275 5.5	volts volts volts mA volts watts



12AV5GA

Refer to type 6AV5GA.

12AV6

Refer to type 6AV6.

12AV7

Refer to chart at end of section.

12AW6

Refer to chart at end of section.

12AX3

Refer to type 6AX3.

12AX4GT 12AX4GTA

Refer to chart at end of section.

12AX4GTB

Refer to type 6AX4GTB.

12AX7


Refer to chart at end of section. For replacement use type 12AX7A/ECC83.

**12AX7A** 

For replacement use type 12AX7A/ECC83.

# 12AX7A/ ECC83

### HIGH-MU TWIN TRIODE



Miniature types used as phase inverters or twin resistance-coupled amplifiers in radio equipment. Outlines 9A section, 6B; require miniature 9-contact socket. Each triode unit is independent of the other except for common heater. For characteristics and curves, refer to type 6AV6. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section.

Heater Arrangement: Heater Voltage (ac/dc) Heater Current Heater-Catnode-Voltage:	Series 12.6 0.15	Parallel 6.3 0.3	volts ampere
Peak value		±200 max 100 max	volts volts
Direct Interelectrode Capacitances (Approx.): Grid to Plate	Unit No.1 1.7 1.6 0.46	Unit No.2 1.7 1.6 0.34	pF pF pF

#### Class A. Amplifier (Each Unit)

MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	330	volts
Grid Voltage:		_
Negative-bias value	55	volts
Positive-bias value		volts
Plate Dissipation	1.2	watts
EQUIVALENT-NOISE AND HUM VOLTAGE (References To Grid, Each	Unit)•	
Average Value	1.8	$\mu V$ rms

• Measured in "true rms" units under the following conditions: Heater voltage (parallel connection), 6.3 volts ac; center tap of heater transformer grounded; plate supply voltage, 250 volts dc: plate load resistor, 100000 ohms; cathode resistor, 2700 ohms bypassed by 100- $\mu$ F capacitor; grid resistor, 0 ohms; and amplifier covering frequency range between 25 and 10000 Hz.


Refer to chart at end of section.

**12AY3** 

Refer to type 6AY3B.

**12AY3A** 

### MEDIUM-MU TWIN TRIODE 12AY7




Miniature type used in the first stages of high-gain audio-frequency amplifiers. Outlines section, 6B; requires miniature 9-contact socket. Each triode unit is independent of the other except for the common heater. Use of the 12.6-volt connection with an ac heater supply is not recommended for applications involving low hum. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section.

Meater Arrangement:	Series	Parallel	
Heater Voltage (ac/dc)	12.6	6.3	volts
Heater Current	0.15	0.3	ampere
Peak Heater-Cathode Voltage	0.10	±90 max	volts
Direct Interded On the	·····	90 max	VOIUS
Direct Interelectrode Capacitances (Approx., Each Uni	t)		
Grid to Plate		1.3	pF
Grid to Cathode and Heater		1.3	pF
Plate to Cathode and Heater		0.6	pF
		0.0	P-
Class A, Amplifier (Eac	ch Unit)		
MAXIMUM RATINGS (Design-Center Values)			
Plate Voltage		300	volts
Grid Voltage:	• • • • • • • • • • •	000	VOIUS
Negative-bias value		50	74
Destination that			volts
Positive-bias value		.0	volts
Cathode Current		10	mA
Plate Dissipation		1.5	watts
CHARACTERISTICS			
			_
Plate Voltage		250	volts
Grid Voltage		4	volts
Amplification Factor		40	
Plate Resistance		22800	ohms
Transconductance	• • • • • • • • • • • • • • • • • • • •	1750	μmhos
Plata Current			
Plate Current	• • • • • • • • • •	3	m _i A
Grid Voltage (Approx.) for plate current of 10 mA		11	volts

Refer to chart at end of section.

12AZ7



### HIGH-MU TWIN TRIODE

**12AZ7A** 

Miniature type used in direct-coupled cathode-drive rf amplifier circuits of vhf color and black-and-white television tuners. Outlines section, 6B; requires miniature 9-contact socket. For characteristics as class  $A_i$  amplifier, refer to miniature type 12AT7.

Heater Voltage (ac/dc):			
Series		12.6	volts
Parallel		6.3	voits.
Heater Current:			
Series		0.225	ampere
Parallel		0.45	ampere
Heater Warm-up Time (Average)		11	seconds
Heater-Cathode Voltage:			
Peak value		±200 max	volts
Average value		100 max	volts
Direct Interelectrode Capacitance (Approx.):	Unshielded	Shielded*	
Grid to Plate (Each unit)	2	1.9	рF
Grid to Cathode and Heater (Each unit)	2.6	2.8	ρF
Plate to Cathode and Heater:			
Unit No.1	0.44	1.4	pF
Unit No.2	0.36	1.6	pF
4 With external shield connected to cathode of unit under	test.		
Class A, Amplifier (Each	Unit)		
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage		330	volts
Grid Voltage, Negative-bias value		55	volts
Plate Dissipation		2.5	watts
MAXIMUM CIRCUIT VALUES (Each Unit)			
Grid-Circuit Resistance:			
For fixed-bias operation		0.25	megohm
For cathode-bias operation		ĭ	megohm
101 Chulouc-plas Operation,		-	gomii

# 12B4A

### LOW-MU TRIODE

Miniature type used as vertical-deflection amplifier in television receivers. Outlines section, 6E; requires miniature 9-contact socket.



9AG

550


1000†

volts volts

	Series	Parallel	
Heater Voltage	12.6	6.3	volts
Heater Current	0.3	0.6	ampere
Heater Warm-up Time		11	seconds
Heater-Cathode Voltage:			
Peak value		$\pm 200 \text{ max}$	volts
Average value		100 max	volts
Direct Interelectrode Capacitances:			
Grid to Plate		4.8	рF
Grid to Cathode and Heater		5	рF
Plate to Cathode and Heater		1.5	р <b>F</b>
Class A, Amplifier			
MAXIMUM RATINGS (Design-Center Values)			
Plate Voltage		550	volts
Grid Voltage, Negative-bias value		50	volts
Plate Dissipation		5.5	watts
		0.0	
CHARACTERISTICS			
Plate Voltage		150	volts
Grid Voltage		17.5	volts
Amplification Factor		6.5	
Plate Resistance (Approx.)		1030	oḥms
Transconductance		6300	μmhos
Plate Current	<b></b>	34	mA
Plate Current for grid voltage of -23 volts	· · · · · · · · · · ·	9.6	mA
Grid Voltage (Approx.) for plate current of 200 µA	• • • • • • •	32	volts
MAXIMUM CIRCUIT VALUES			
Grid-Circuit Resistance:			
For fixed-bias operation		0.47	megohm
For cathode-bias operation		2.2	megohms
Vertical-Deflection Ample	ifier		
For operation in a 525-line, 30-fra	me system		
MAXIMUM RATINGS (Design-Center Values)			
MANAGE TATIFFE (200) P. COLICE TATIFFE			14 -

Peak Negative-Pulse Grid Voltage Peak Cathode Current Average Cathode Current Plate Dissipation	250 105 30 5.5	volts mA mA watts
MAXIMUM CIRCUIT VALUE Grid-Circuit Resistance, for cathode-bias operation	2.2	megohms
# Pulse duration must not exceed 15% of a vertical scanning cycle † Under no circumstances should this absolute value be exceeded.	(2.5 millise	conds).

Refer to chart at end of section.	12B8GT
Refer to type 6BA6.	12BA6
Refer to chart at end of section.	12BA7
Refer to chart at end of section.	12BD6
Refer to type 6BE3.	12BE3
Refer to type 6BE6.	12BE6
Refer to chart at end of section.	12BF6
Refer to type 6BF11.	12BF11
Refer to chart at end of section.	12BH7



# MEDIUM-MU TWIN TRIODE 12BH7A

Miniature type used as combined vertical-deflection amplifier and vertical oscillator, and as horizontal-deflection oscillator, in television receivers, and in phase-inverter and multivibrator circuits. Outlines section, 6E; requires miniature 9-contact socket. Each triode unit is independent of the other except for the common heater.

D---11-1

Heater Arrangement: Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage: Peak value Average value		Parallel 6.3 0.6 11 ±200 max 100 max	volts ampere seconds volts volts
Direct Interelectrode Capacitances (Approx.): Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater Plate of Unit No.1 to Plate of Unit No.2	Unit No.1 2.6 3.2 0.5	Unit No.2 2.6 3.2 0.4	pF pF pF
Class A, Amplifier (Each	Unit)		
MAXIMUM RATINGS (Design-Center Values) Plate Voltage		300	volts
Grid Voltage: Negative-bias value Positive-bias value Cathode Current		50 0 20	volts volts mA
Plate Dissipation: Each Plate Both plates (Both units operating) CHARACTERISTICS		3.5 7	watts watts
Plate Voltage Grid Voltage Amplification Factor		250 10.5 16.5	volts volts
Plate Resistance (Approx.) Transconductance Plate Current Plate Current for grid voltage of —14 volts Grid Voltage (Approx.) for plate current of 50 µA		5300 3100 11.5 4 —23	ohms μmhos mA mA vol <b>ts</b>

#### MAXIMUM CIRCUIT VALUES

Grid-Circuit Resistance:		
For fixed-bias operation	0.25	megohm
For cathode-bias operation	1	megohm

#### Oscillator (Each Unit)


#### For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Center Values)	Deflection Oscillator	Deflection Oscillator	14
DC Plate Voltage	450	450	volts
Peak Negative-Pulse Grid Voltage	400	600	volts
Peak Cathode Current	70	300	mA
Average Cathode Current	20	20	mA
Plate Dissipation: Each Plate Both Plates (Both units operating)	3.5 7	3.5 7	watts watts
MAXIMUM CIRCUIT VALUES Grid-Circuit Resistance	2.2	2.2	megohms

#### Vertical-Deflection Amplifier (Each Unit)

For operation in a 525-line, 30-frame system

For operation in a partime, or itame system		
MAXIMUM RATINGS (Design-Center Values)		
DC Plate Voltage	450	volts
Peak Positive-Pulse Plate Voltage# (Absolute maximum)	1500*	volts
Peak Negative-Pulse Grid Voltage	250	volts
Peak Cathode Current	70	mĄ
Average Cathode Current	20	mA
Plate Dissipation:		
Each Plate	<b>3.</b> <u>5</u>	watts
Both Plates (Both units operating)	7	watts



#### MAXIMUM CIRCUIT VALUE

Grid-Circuit Resistance for cathode-bias operation .......... 2.2 megohms

# Pulse duration must not exceed 15% of a vertical scanning cycle (2.5 milliseconds).

12BK5 Refer to chart at end of section.

12BL6 Refer to chart at end of section.

12BN6 Refer to chart at end of section.

12BQ6GTB/12CU6 Refer to type 6BQ6GTB/6CU6.

12BR3 For replacement use type 12AF3/12BR3/12RK19.


12BR7 Refer to chart at end of section.

Refer to chart at end of section.

For replacement use type 12BS3A/12DW4A.

^{*} Under no circumstances should this absolute value be exceeded.

For replacement use type 12BS3A/12DW4A.	12B\$3A
Refer to type 6BS3A.  Refer to chart at end of section.	12BS3A/12DW4A
Refer to chart at end of section.	12BT3
For replacement use type 12BY7A/12BV7/12DQ7.	12BV7
Refer to type 6BV11.	12BV11
Refer to chart at end of section.	12BW4
Refer to chart at end of section. For replacement use type 12BY7A/12BV7/12DQ7.	12BY7
For replacement use type 12BY7A/12BV7/12DQ7.	12BY7A




### SHARP-CUTOFF PENTODE

# 12BY7A/ 12BV7/ 12DQ7

Miniature types used as video amplifier in television receivers. Outlines section, 6E; require miniature 9-contact socket.

<b>.</b>			
Heater Arrangement: Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	Series 12.6 0.3	Parallel 6.3 0.6 11	volts ampere seconds
Heater-Cathode Voltage:			50001145
Peak value		±200 max	volts
Average value		100 max	volts
Direct Interelectrode Capacitances:			
Grid No.1 to Plate		0.063	рF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3	3,		
and Internal Shield		10.2	рF
Plate to Cathode, Heater, Grid No.2, and Internal Shi	ield	3.5	рF
Class A. Amplifier MAXIMUM RATINGS (Design-Maximum Values)			
Plate Supply Voltage		330	volts
Grid-No.3 (Suppressor-Grid) Voltage, Positive value		000	volts
Grid-No.2 (Screen-Grid) Voltage		190	volts
Grid-No.1 (Control-Grid) Voltage			
Negative-bias value		55	volts
Positive-bias value		0	volts
Plate Dissipation		6.5	watts
Grid-No.2 Input		1.2	watts



CHARACTERISTICS Plate Supply Voltage Grid No.3 Grid-No.2 Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 20 \(\mu\)A	Connect	250 ed to catho 180 100 93000 11000 26 5.75 —11.6	volts de at socket volts ohms ohms
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation		0.25	megohm megohm

12BZ6	Refer to type 6BZ6.
12BZ7	Refer to chart at end of section.
12C5	Refer to type 6CU5.
12C8	Refer to chart at end of section.
12CA5	Refer to type 6CA5.
12CK3	Refer to chart at end of section.
12CL3	Refer to type 6CL3.
12CN5	Refer to chart at end of section.
12CR6	Refer to chart at end of section.
12CS6	Refer to type 6CS6.

# **12CT3**

HALF-WAVE **VACUUM RECTIFIER** 

17CT3, 25CT3 Miniature type used as damper tube in horizontaldeflection circuits of black-and-white and small-screen color television receivers. Outlines section, 6H; requires miniature 9-contact socket. Socket terminals 1, 3, 7, and 8 should not be used as tie points for externalcircuit components. This tube, like other power-handling



tubes, should be adequately ventilated. Types 17CT3 and 25CT3 are identical with type 12CT3 except for heater ratings.

	1ZCT3	17C13	Z5CT3	
Heater Voltage (ac/dc)	6.3	16.8	25.3	volts
Heater Current	0.6	0.45	0.3	amperes
Heater Warm-up Time (Average)	11	11	11	seconds
	11	11	11	seconds
Direct Interelectrode Capacitances (Approx.):				
Plate to Cathode and Heater			12	рF
Cathode to Plate and Heater			9.5	
				рF
Heater to Cathode			2.8	$\mathbf{pF}$
Da 0.				
Damper Se	ilaice			
For operation in a 525-lis	. 10.			
	ic, sv-iiam	e system		
MAXIMUM RATINGS (Design-Maximum Values)				
Peak Inverse Plate Voltage#			5000	volts
Peak Plate Current			1200	mA
Average Plate Current			250	mA
Plate Dissipation			4.75	watts
Heater-Cathode Voltage:				
Peak value		+800	5000	volts
Average value			900	volts
Bulb Temperature (At hottest point)			220	vo.c
build remperature (At noticest point)	• • • • • • • • • • • • • • • • • • •		ZZU	.0
CHARACTERISTICS, Instantaneous Value				
• • • • • • • • • • • • • • • • • • • •				
Tube Voltage Drop for plate current of \$50 mA			16	volts

# Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

Refer to chart at end of section.	12CT8
Refer to type 6CU5.	12CU5/12C5
For replacement use type 12BQ6GTB/12CU6.	12CU6
Refer to chart at end of section.	12CX6
Refer to chart at end of section.	12D4
Refer to chart at end of section.	12DB5
Refer to chart at end of section.	12DE8
Refer to type 6DK6.	12DK6
Refer to chart at end of section.	12DK7
Refer to chart at end of section.	12DL8
Refer to chart at end of section.	12DM4 12DM4A
Refer to chart at end of section.	12DQ6A
Refer to chart at end of section.	1000/0
For replacement use type 12GW6/12DQ6B.	12DQ6B
Refer to chart at end of section. For replacement use type 12BY7A/12BV7/12DQ	7. 12DQ7
Different Death And Death	12D\$7
Refer to chart at end of section.	12DS7A
Refer to type 6DT5.	12DT5
Refer to type 6DT8.	12DT8
Refer to chart at end of section.	12DU7
Refer to chart at end of section.	12DV8
Refer to chart at end of section. For replacement use type 12BS3A/12DW4A.	12DW4A
Refer to chart at end of section.	12DW7
Refer to chart at end of section.	12DY8
Refer to chart at end of section. For replacement use type 12EK6/12DZ6/12EA6.	12DZ6
Refer to chart at end of section. For replacement use type 12EK6/12DZ6/12EA6.	12EA6
Refer to chart at end of section.	12EC8
Refer to chart at end of section.	12ED5
Refer to chart at end of section.	12EG6
Refer to chart at end of section.	12EH5
Refer to chart at end of section.	12EK6/12DZ6/12EA6
Refer to chart at end of section.	12EL6
Refer to chart at end of section.	12EM6
Refer to chart at end of section.	12EN6
Refer to chart at end of section.	12EQ7
Refer to chart at end of section.	12F5GT
Refer to chart at end of section.	12F8


12FK6	Refer to chart at end of section.
12FM6	Refer to chart at end of section.
12FQ7	Refer to type 6FQ7/6CG7.
12FQ8	Refer to chart at end of section.
12FR8	Refer to chart at end of section.
12FV7	Refer to chart at end of section.

### POWER PENTODE

12FX5


19FX5

Miniature type used in output stages of audio amplifiers. Outlines section, 5D; requires miniature 7-contact socket. Types 19FX5 and 60FX5 are identical with type 12FX5 except for heater ratings.



60FX5

	12FX5	19FX5	60FX5	
Heater Voltage (ac/dc)	12.6	18.9	60	volts
Heater Current	0.45	0.3	0.1	ampere
Heater Warm-up Time (Average)	11	11		seconds
Heater-Cathode Voltage:				beconds
Peak value	$\pm 200 \text{ max}$	±200 max	±200 max	volts
Average value	100 max	100 max	100 max	volts
Direct Interelectrode Capacitances (Appr	ox.):	200 111011	100 Hisk	VOILS
Grid No.1 to Plate	, -		0.65	рF
Grid No 1 to Cathode, Heater, Grid	No 2 and Gr	id No 3	17	pr pF
Plate to Cathode, Heater, Grid No.2,	and Grid No.	3	9	pF pF
	una Giia 210.		3	pr
Class	A, Amplific	er		
MAXIMUM RATINGS (Design-Maximum \	/alues)			
Plate Voltage			150	volts
Grid-No.2 (Screen-Grid) Voltage			180	volts
Plate Dissipation			5.5	watts
Grid-No.2 Input			2	watts
Bulb Temperature (At hottest point)			225	
TYPICAL OPERATION			220	U
Plate Supply Voltage			110	volts
Grid-No.2 Supply Voltage			115	volts
Cathode-Bias Resistor			62	
Peak AF Grid-No.1 Voltage			3	ohms
Zero-Signal Plate Current			36	volts
Maximum-Signal Plate Current			36 35	mA
Zero-Signal Grid No.2 Current		· · · · · · · · · · · · · · ·		mĄ
Maximum-Signal Grid No.2 Current	• • • • • • • • • • • • •	· · · · · · · · · · · · · · ·	10	mĄ
			12	_, mA
_			17500	ohms
			13500	μmhos
Load Resistance			3000	ohms



Total Harmonic Distortion Maximum-Signal Power Output MAXIMUM CIRCUIT VALUES	8 1.3	per cent watts
Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.1 0.5	megohm megohm
Refer to chart at end of section.	12F	
Refer to chart at end of section.	120	6A6
For replacement use type 12BQ6GTB/12CU6.	120	<b>3</b> B3
For replacement use type 12GW6/12DQ6B.		986 98 <i>7</i>
Refer to chart at end of section.	120	€C6
Refer to type 6GE5.	120	GE5
Refer to chart at end of section.	120	<b>3</b> J5
Refer to type 6GJ5A.	12G	J5A
Refer to chart at end of section.	120	N7
Refer to chart at end of section. For replacement use type 12HG7/12GN7A.	12G	N7A
Refer to chart at end of section.	12G	
Refer to type 6GW6/6DQ6B.	2GW6/	12DQ6B
Refer to chart at end of section.	121	H6



### SHARP-CUTOFF PENTODE

Refer to type 38HE7.
For replacement use type 12HG7/12GN7A.

# 12HG7/ 12GN7A

12HE7

12HG7

Miniature types with frame grid used as video amplifier in color and black-and-white television receivers.

Outlines section, 6E; require 9-contact miniature socket.

Heater Arrangement:	Series	Parallel	
Heater Voltage (ac/dc)	12.6	6.3	volts
Heater Current	0.26	0.52	ampere


megohm

megohm

0.1 0.25

9BF

**		
Heater-Cathode Voltage: Peak value Average value Direct Interelectrode Canacitances:	±200 max 100 max	volts volts
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and	0.15 max	pF
Internal Shield Plate to Cathode, Heater, Grid No.2, Grid No.3, and	14 max	pF
Internal Shield	4.4 max	pF
Class A, Amplifier		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	400	volts
Grid-No.2 (Screen-Grid) Supply Voltage	330	volts
Grid-No.2 Voltage	See curve	e page 300
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	volts
Plate Dissipation	10	watts
Grid-No.2 Input:	_	
For Grid-No.2 voltages up to 165 volts	2 1	watt
For Grid-No.2 voltages between 165 and 330 volts	See curve	e page 300
CHARACTERISTICS		
Plate Supply Voltage	300	volts
Grid No.3 (Suppressor Grid)	ected to cathod	e at socket
Grid-No.2 Supply Voltage	135	volts
Grid No.1 Connected to negative		le resistor
Cathode Resistor	47	ohms
Plate Resistance (Approx.)	60000	ohms
Transconductance	32000	µmhos
Plate Current	31	mÅ
Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 100 µA	4.8 4.5	m,A
min-root voicage (Approx.) for place current of 100 μA	4.5	volts
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
Par Coul him annualism		



# 12HL7 SHARP-CUTOFF PENTODE

Miniature type with frame grid used as a video output amplifier in color television receivers. Outlines section, 6E; requires miniature 9-contact socket.

For fixed-bias operation ..... For cathode-bias operation ...

Heater	Arrangen	nent	Series	Parallel	
Heater	Voltage		12.6	6.3	volts
Heater	Current	***************************************	0.3	0.6	ampere

Heater-Cathode Voltage:		
Peak value	ax ±200 ma: ax 100 ma:	x volts x volts
Direct Interelectrode Conscitance:		pF
Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield	15	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and Internal Shield	6	pF
Class A ₁ Amplifier		
MAXIMUM RATINGS (Design-Maximum Values)	400	volts
Plate Voltage Grid-No.3 (Suppressor-Grid) Voltage, Positive-bias value Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.2 Voltage Grid-No.2 (Grid) Voltage Grid-No.2 (Grid) Voltage Grid-No.2 (Grid) Voltage	330	volts volts
Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value	See cur	rve page 300 volt
Plate Dissipation Grid-No.2 Input	10	watts watt
CHARACTERISTICS		
Grid-No.3 Voltage, Referred to negative end of	<b>50 2</b> 50	volts
Grid-No.2 Voltage	0 <b>2</b> 5 150	volts volts
Cathoge Resistor (Dybassed)	0 0 122	volts ohms
Plate Current Grid-No.2 Current	76 <b>2</b> 5 32 6	mA mA
Grid-No.2 Current Transconductance, Grid No.1 to Plate Plate Resistance (Approx.) Grid-No.1 Voltage (Approx.) for plate current of 100 µA	21000 55000	μmhos ohms
of 160 µA	<b>—7.2</b>	volts
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.1 0.25	megohm megohm
Refer to chart at end of section.	12J	5GT
Refer to chart at end of section.	12J	7GT
Refer to chart at end of section.	12	18
Refer to chart at end of section.	12.	B6
Refer to type 6JB6A.	12JI	36A
Refer to chart at end of section.	12J	F5
Refer to type 6JN6.	12J	N6
Refer to chart at end of section.	12J	
Refer to type 6JQ6.	12J	
Refer to chart at end of section.	12	
Refer to type 6JT6A.	12J1	
Refer to chart at end of section.	121	
Refer to chart at end of section.	12K7	_
Refer to chart at end of section.	121	
Refer to chart at end of section.	12K	
Refer to chart at end of section.	1216	_
Refer to type 6MD8.	12M	
Refer to chart at end of section.	12Q7	_
Refer to chart at end of section.	12	₹5

13**GF7A** 

Refer to chart at end of section. 12RK19 For replacement use type 12AF3/12BR3/12RK19. 12S8GT Refer to chart at end of section. 12SA7 Refer to chart at end of section. 125A7GT 12SC7 Refer to chart at end of section. 12SF5 Refer to chart at end of section. 12SF5GT Refer to chart at end of section. 12SF7 Refer to chart at end of section. 12SG7 Refer to chart at end of section. 12SH7 12SJ7 Refer to chart at end of section. 12SJ7GT 12SK7 Refer to chart at end of section. 12**SK7GT** 12SL7GT Refer to type 6SL7GT. 12SN7GT Refer to chart at end of section. 12SN7GTA Refer to type 6SN7GTB. 12SQ7 Refer to chart at end of section. 125Q7GT 12SR7 Refer to chart at end of section. 12SR7GT Refer to chart at end of section. 12SW7 Refer to chart at end of section. 12SY7 Refer to type 6T10. 12TIO **12U7** Refer to chart at end of section. 12V6GT Refer to type 6V6. 12W6GT Refer to type 6W6GT. 12X4 Refer to type 6X4. 12**Z**3 Refer to chart at end of section. 13CW4 Refer to type 6CW4. 13DE7 Refer to type 6DE7. 13DR7 Refer to type 6DR7. Refer to chart at end of section. 13EM7 For replacement use type 13EM7/15EA7. Refer to type 6EM7/6EA7. 13EM7/15EA7 13FD7 Refer to type 6FD7. 13FM7 Refer to type 6FM7. 13FM7/15FM7 Refer to chart at end of section. 13GB5 13GB5/XL500 Refer to type 6GB5/EL500.

Refer to type 6GF7A.

Refer to chart at end of section. For replacement use type 13Z10/13J10.

13J10

Refer to type 6JZ8.

13JZ8



12EZ

MAXIMUM RATINGS (Design-Maximum Values)

#### BEAM POWER TUBE— SHARP-CUTOFF PENTODE

13V10

Duodecar type used as combined FM detector and audio-frequency output amplifier in television receivers. The beam power unit is used in af output stages and the pentode unit as an FM detector. Outlines section, 8C; requires duodecar 12-contact socket. Heater: volts (ac/dc), 13.2; amperes, 0.45; average warm-up time, 11 seconds; maximum heater-cathode volts,  $\pm 200$  peak, 100 average.

Beam Po	wer Unit	as Class	: <b>Α</b> .	Amplifier
---------	----------	----------	--------------	-----------

MAXIMUM RATINGS (Design-Maximum values)		
Plate Voltage	165	volts
Grid-No.2 (Screen-Grid) Voltage	150	volts
Cathode Current	65	mA
Plate Dissipation	6.5	watts
Grid-No.2 Input	1.8	watts
TYPICAL OPERATION		
		•
Plate Voltage	145	volts
Grid-No.2 Voltage	125	volts
Grid-No.1 (Control-Grid) Voltage	-6	volts
Peak AF Grid-No.1 Voltage	6	volts
Zero-Signal Plate Current	34	mA.
Maximum-Signal Plate Current	36	mA
Zero-Signal Grid-No.2 Current	2.2	mA
Maximum-Signal Grid-No.2 Current	5.5	mA
Plate Resistance (Approx.)	0.058	megohm
Transconductance	6400	μmhos
Load Resistance	3000	ohms
Total Harmonic Distortion (Approx.)	7	per cent
Maximum-Signal Power Output	1.5	watts
	1.0	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.25	megohm
For cathode-bias operation	0.5	megohm
Pentode Unit as Class A, Amplifier		
•		
CHARACTERISTICS	150	14
CHARACTERISTICS Plate Supply Voltage	150	volts
CHARACTERISTICS Plate Supply Voltage	0	volts
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage	0 100	volts volts
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor	0 100 560	volts volts ohms
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.)	0 100 560 0.15	volts volts ohms megohm
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate	0 100 560 0.15 1000	volts volts ohms megohm µmhos
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.)	0 100 560 0.15 1000 400	volts volts ohms megohm
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate	0 100 560 0.15 1000 400 1.3	volts volts ohms megohm µmhos
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.3 to Plate Plate Current Grid-No.2 Current	0 100 560 0.15 1000 400	volts volts ohms megohm μmhos μmhos
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.3 to Plate Plate Current	0 100 560 0.15 1000 400 1.3 2 4.5	volts volts ohms megohm μmhos μmhos mA
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.3 to Plate Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 µA	0 100 560 0.15 1000 400 1.3 2	$\begin{array}{c} { m volts} \\ { m volts} \\ { m ohms} \\ { m megohm} \\ { m } { m } { m } { m mhos} \\ { m } { m mhos} \\ { m mA} \\ { m mA} \end{array}$
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.3 to Plate Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 µA Grid-No.3 Voltage (Approx.) for plate current of 10 µA	0 100 560 0.15 1000 400 1.3 2 4.5	volts volts ohms megohm μmhos μmhos mA wolts
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.3 to Plate Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 µA	0 100 560 0.15 1000 400 1.3 2 4.5	volts volts ohms megohm μmhos μmhos mA wolts
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.3 to Plate Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 µA Grid-No.3 Voltage (Approx.) for plate current of 10 µA Pentode Unit as FM Detector	0 100 560 0.15 1000 400 1.3 2 4.5	volts volts ohms megohm μmhos μmhos mA wolts
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.3 to Plate Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 µA Grid-No.3 Voltage (Approx.) for plate current of 10 µA  Pentode Unit as FM Detector MAXIMUM RATINGS (Design-Maximum Values)	100 560 0.15 1000 400 1.3 2 4.5	volts volts volts ohms megohm µmhos µmhos mA mA volts
CHARACTERISTICS Plate Supply Voltage Grid-No.2 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.1 to Plate Order Current Grid-No.2 Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 µA Grid-No.3 Voltage (Approx.) for plate current of 10 µA  Pentode Unit as FM Detector MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage	100 560 0.15 1000 400 1.3 2 4.5 4.5	volts volts volts ohms megohm µmhos mA volts volts
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.3 to Plate Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 µA Grid-No.3 Voltage (Approx.) for plate current of 10 µA  Pentode Unit as FM Detector MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Grid-No.3 Voltage	0 100 560 0.15 1000 400 1.3 2 -4.5 -4.5	volts volts volts ohms megohm µmhos mA mA volts volts
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.3 to Plate Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 µA Grid-No.3 Voltage (Approx.) for plate current of 10 µA  Pentode Unit as FM Detector MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Grid-No.3 Voltage Grid-No.2 Supply Voltage	0 100 560 0.15 1000 400 1.3 2 -4.5 -4.5	volts volts ohms megohm µmhos mA volts volts volts volts volts
CHARACTERISTICS Plate Supply Voltage Grid-No.2 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.1 to Plate Ourrent Grid-No.1 (Voltage (Approx.) for plate current of 10 µA Grid-No.3 Voltage (Approx.) for plate current of 10 µA  Pentode Unit as FM Detector MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Grid-No.3 Voltage Grid-No.3 Voltage Grid-No.2 Supply Voltage Grid-No.2 Supply Voltage Grid-No.2 Voltage	0 100 560 0.15 1000 400 1.3 2 -4.5 -4.5	volts volts ohms megohm µmhos mA mA volts volts volts volts volts
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.3 to Plate Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 µA Grid-No.3 Voltage (Approx.) for plate current of 10 µA  Pentode Unit as FM Detector MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Grid-No.3 Voltage Grid-No.2 Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value	100 550 0.15 1000 400 1.3 2 -4.5 -4.5	volts volts ohms megohm  µmhos µmhos mA volts
CHARACTERISTICS Plate Supply Voltage Grid-No.2 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.3 to Plate Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 µA Grid-No.3 Voltage (Approx.) for plate current of 10 µA  Pentode Unit as FM Detector MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Grid-No.3 Voltage Grid-No.2 Supply Voltage Grid-No.2 Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation	0 100 560 0.15 1000 400 1.3 2 -4.5 -4.5	volts volts ohms megohm µmhos mA mA volts volts volts volts volts
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.1 to Plate Transconductance, Grid No.1 to Plate Grid-No.1 Voltage (Approx.) for plate current of 10 µA Grid-No.3 Voltage (Approx.) for plate current of 10 µA  Pentode Unit as FM Detector MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Grid-No.3 Voltage Grid-No.3 Voltage Grid-No.2 Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input:	330 28 330 See curv	volts volts ohms megohm  µmhos µmhos mA volts
CHARACTERISTICS Plate Supply Voltage Grid-No.2 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.3 to Plate Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate current of 10 µA Grid-No.3 Voltage (Approx.) for plate current of 10 µA  Pentode Unit as FM Detector  MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Grid-No.3 Voltage Grid-No.2 Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 165 volts	100 560 0.15 1000 400 1.3 2 -4.5 -4.5 330 28 330 See curv 1.7	volts volts ohms megohm µmhos mA volts volts volts volts volts watts watts
CHARACTERISTICS Plate Supply Voltage Grid-No.3 (Suppressor-Grid) Voltage Grid-No.2 (Screen-Grid) Supply Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance, Grid No.1 to Plate Transconductance, Grid No.1 to Plate Transconductance, Grid No.1 to Plate Grid-No.1 Voltage (Approx.) for plate current of 10 µA Grid-No.3 Voltage (Approx.) for plate current of 10 µA  Pentode Unit as FM Detector MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Grid-No.3 Voltage Grid-No.3 Voltage Grid-No.2 Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input:	100 560 0.15 1000 400 1.3 2 -4.5 -4.5 330 28 330 See curv 1.7	volts volts ohms megohm  µmhos µmhos mA  mA  volts volts  volts volts volts volts volts volts volts volts volts volts volts volts volts volts volts volts volts volts volts

Refer to chart at end of section.

13Z10/13J10

13Z10


Refer to type 6Z10/6J10.

14A4	Refer to chart at end of section.
14A5	Refer to chart at end of section.
14A7	Refer to chart at end of section.
14AF7	Refer to chart at end of section.
14B6	Refer to chart at end of section.
14B8	Refer to chart at end of section.

# 14BL11

#### DUAL TRIODE— SHARP-CUTOFF PENTODE

Duodecar type used in television receiver applications. The pentode unit is used for video amplifier service, and the triode units for general-purpose use. Outlines section, 8B; requires duodecar 12-contact socket. Heater: volts (ac/dc), 14.2; amperes, 0.45; average warm-up time 11 seconds; maximum heater-cathode volts, ±200 peak, 100 average.



**12GC** 


#### Class A, Amplifier

MANUAL DATINGS (D. See Manifester Melica)	Triode	Triode		ntode	
MAXIMUM RATINGS (Design-Maximum Values)	Unit No.1			nit	
Plate Voltage	330	330		50	volts
Grid-No.2 (Screen-Grid) Voltage	_		1	25	volts
Grid-No.1 (Control-Grid) Voltage, Positive-bias	_				
value	0	0 2		0	volts
Plate Dissipation	1.5	2		2.5	watts
Grid-No.2 Input	-	_	1.	25	watts
CHARACTERISTICS					
Plate Voltage	200	200	35	200	volts
Grid-No.2 Voltage			100	100	volts
Grid-No.1 Voltage		_	Õ		volts
Cathode-Bias Resistor	470	270	_	82	ohms
Amplification Factor	40	69	_		OLINE
Plate Resistance (Approx.)	7600	12500	_	70000	ohms
Transconductance	5300	5500	_	19000	μmhos
Plate Current	7.2	7.1	40	16	mA
Grid-No.2 Current	1.2		13	3	mA
Grid-No.1 Voltage (Approx.) for plate current			10	J	шл
	8	5.5			
of 100 μA	<del></del> 8	o.o	_	<b>—</b> 5.5	volts
MAXIMUM CIRCUIT VALUES					
Grid-No.1-Circuit Resistance:					
For fixed-bias operation	0.5	0.5	Ð	.1	megohm
For cathode-bias operation	ĭ	ĩ	0.		megohm
	-	-	•		

## 14BR11

#### DUAL TRIODE— SHARP-CUTOFF PENTODE

Duodecar type used in television receiver applications. Kp,63p The high-mu triode unit No. 1 is used for general-purpose use, the medium-mu triode unit No. 2 for sync separator service, and the pentode unit for video amplifier service. Outlines section, 8C; requires duodecar 12-contact socket. Heater: volts (ac/dc), 14.2; amperes, 0.45; warm-up time, 11 seconds; maximum heater-cathode volts, ±200 peak, 100 average.



12GL

Class A, Ampl	lifier			
MAXIMUM RATINGS (Design-Maximum Values)		Triode Unit No.2	Unit	
Plate Voltage	330	330	330 330	võlts volts
Grid-No.2 Voltage	_		See curve	page 300
Grid-No.1 (Control-Grid) Voltage, Positive-bias	0	0	0	volts
Plate DissipationGrid-No.2 Input:	1.5	2	4	watts
For grid-No.2 voltages up to 165 volts For grid-No.2 voltages between 165 and 330	_	_	1.1	watts
volts		_	See curve	page 300
CHARACTERISTICS	000	000	. 105	volts
Plate Voltage	200 —	18		volts
Grid-No.1 Voltage	<u>_2</u>	220 -	0 — — 100	volts ohms
Amplification Factor	68	41 -	_ =	_
Plate-Resistance (Approx.)	12400 5500	9400 - 4400 -	- 45000 - 10400	ohms µmhos
Plate Current	7	9.2 3	17	mA mA
Grid-No.2 Current	_	1	3 4	
of 100 μA	5.5	-6.5 -	6	volts
MAXIMUM CIRCUIT VALUES				
Grid-No.1-Circuit Resistance: For fixed-bias operation	0.5	0.5	1	megohm
For cathode-bias operation	1	1	1	megohm
Refer to chart at end of section	n.		14C5	
Refer to chart at end of section	n.		14C7	
Refer to chart at end of section	n.		14E6	
Refer to chart at end of section	n.		14E7	
Refer to chart at end of section	n.		14F7	
Refer to chart at end of section	n.		14F8	
Refer to chart at end of section	n.		14GT8	3
Refer to chart at end of section	n.		14H7	
Refer to chart at end of section	n.		14J <i>7</i>	
Refer to chart at end of section	n.		14JG8	3
Refer to chart at end of section	n.		14N7	
Refer to chart at end of section	n.		14Q7	
Refer to chart at end of section	n.		14R7	
Refer to chart at end of section	n.		15	
Refer to type 6AF11.			15AF11	J
Refer to chart at end of section	1.		15BD1	1
Refer to chart at end of section	n.		15BD11.	A

Refer to type 6CW5/EL86. 15DQ8 Refer to chart at end of section.

15CW5 15CW5/PL84


Refer to chart at end of section.

# 15DQ8/ PCL84

15EA7

#### HIGH-MU TRIODE-SHARP-CUTOFF PENTODE

Miniature type used in color and black-and-white television receiver applications. The triode unit is used as a sync-separator, sync-amplifier, keyed-agc, or noise-suppressor tube. The pentode unit is used as a video-



output tube. Outlines section, 6E; require 9-contact socket.	GT 9H	G _{2p}		
Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage			$^{15}_{0.3}_{\pm 200~{ m max}}$	volts ampere volts
Class A, Amp	lifie	er		
MAXIMUM RATINGS (Design-Maximum Values)		Triode Unit	Pentode Unit	
Plate Supply Voltage	į	550	550	volts
0.1 mA•		600	_	volts
Plate Voltage		250	250	volts
Grid-No.2 (Screen-Grid) Supply Voltage		_	550	volts
Grid-No.2 Voltage			250	volts
Cathode Current		12	40	mA.
Plate Dissipation	•	1	1.7	watts
Grid-No.2 Input	•		1.7	watts
Triode CHARACTERISTICS Unit		Pentode U	nit	
Plate Voltage	170		200	volts
Grid-No.2 Voltage	170		220	volts
Grid-No.1 Voltage1.7	-2.		3.4	volts
Amplification Factor 65	_			
Mu-Factor, Grid-No.2 to Grid-No.1 —	3€	36	36	
Plate Resistance (Approx.) —	0.1	0.13	0.15	megohm
	11000		10000	$\mu$ mhos
Plate Current 3	18		18	mĄ
Grid-No.2 Current —	3	3	3	mA
TYPICAL OPERATION OF PENTODE UNIT AS VIDEO	o ou	TPUT TUBI	<b>:</b>	
Plate Supply Voltage	17	0 200	220	volts
Series Plate Resistor	3000		3000	ohms
Grid-No.2 Voltage	170		<b>2</b> 20	volts
Grid-No.1 Voltage			-3.3	volts
	10409		9700	μmhos
Plate Current	18		18	mĄ
Grid-No.2 Current	3.3	2 3.1	3.1	mA
MAXIMUM CIRCUIT VALUES				
Grid-No.1-Circuit Resistance:			Pentode Unit	
For fixed-bias operation		1	1	megohm
For cathode-bias operation	-	3	2	megohms
• With maximum duty factor of 0.18 and maximum p	ulse	duration of	18 microsecor	ıds.

15 <b>EW</b> 7	Refer to type 6EW7.				
15FM7	Refer to chart at end of section. For replacement use type 13FM7/15FM7.				
15FY7	Refer to type 6FY7.				
15HB6	Refer to chart at end of section.				

For replacement use type 13EM7/15EA7.


Refer to chart at end of section. 15KY8

**15KY8A** Refer to type 6KY8A. 15LE8 Refer to chart at end of section. Refer to type 6MF8.

15MF8

Refer to chart at end of section. For replacement use type 16A8/PCL82.

16A8



9EX


#### HIGH-MU TRIODE— POWER PENTODE

16A8/ PCL82

Gap Miniature type used in television receiver applications. The triode unit is used as a vertical oscillator or as an af amplifier, and the pentode unit is used as a vertical output tube or as an audio output tube. Outlines section, 6G; requires miniature 9-contact socket. Type 8B8 is identical with type 16A8/PCL82 except for heater ratings.

				B8	16A8/I		
Heater Voltage			8		16		volts
Heater Current			0.6		0.3		ampere
Heater-Cathode Voltage				±200		9	volts
Cla	ss A, A	Amplifie	er .				
MAXIMUM RATINGS (Design-Maximum Values)				Triode Unit Pentode Unit			
Plate Supply Voltage				50	550		volts
Peak Plate Voltage			600		2500		volts
Plate Voltage			250		250		volts
Peak Inverse Plate Voltage					500		volts
Grid-No.2 (Screen-Grid) Supply Voltage			-		550		volts
Grid-No.2 Voltage					250		volts
Cathode Current			15		50		mA.
Plate Dissipation (Frame Output)			_		5		watts
Plate Dissipation (Audio Output)					7		watts
Grid-No.2 Input					1.8 3.2		watts
Peak Grid-No.2 Input							watts
	Triode						
CHARACTERISTICS	Unit	P	entode Unit				
Plate Voltage	100	100	170	200	200		volts
Grid-No.2 Voltage	_	100	170	200	200		volts
Grid-No.1 Voltage	0	—6	-11.5	-12.5	16		volts
Amplification Factor	70				_		
Mu Factor, Grid No.2 to Grid No.1		10	9.5	9.5	9.5		
Plate Resistance		15000	16000	20500	20000		ohms
Transconductance	2500	6800	7500	6800	6400		$\mu$ mhos
Plate Current	3.5	26	41	35	7		mA
Grid-No.2 Current	_	5	8	6.5	35		mA.
MAXIMUM CIRCUIT VALUES							
Grid-No.1-Circuit Resistance:							
For fixed-bias operation	1			1			megohm
For cathode-bias operation 3				2			megohms
Title	-	_					

[·] With a maximum duty factor of 0.04 and maximum pulse duration of 0.8 milliseconds.



#### DUAL TRIODE— BEAM POWER TUBE

16AK9

Duodecar type used in vertical-deflection-amplifier, vertical oscillator and sync-clipper applications, in color television receivers. Outlines section, 15A; requires duodecar 12-contact socket. Heater: volts (ac/dc), 16.4; amperes, 0.6; average warm-up time, 11 seconds; maximum heater-cathode volts, ±200 peak, 100 average.

Class A. Amplifier

CHARACTERISTICS	Triode Unit No. 1	Triode Unit No.2		n Power nit	
Plate Voltage	. 150	150	60	150	volts
Grid-No.2 (Screen-Grid) Voltage	. —	_	125	150	volts
Grid-No.1 (Control-Grid) Voltage	2	5	0	14	volts
Plate Resistance (Approx.)	. 11000	8500		16400	ohms
Transconductance		2350		6200	$\mu$ mhos
Plate Current	. 5.4	5.5	140	49	mA
Grid-No.2 Current			18	3.5	mA
Grid-No.1 Voltage (Approx.) for plate					
current of 100 μA		11	_	33	volts
Amplification Factor	43	20	_		

#### Vertical-Deflection Oscillator and Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS	Triode	Triode	Beam Power	
(Design-Maximum Values)	Unit No. 1	Unit No. 2	Unit	
, ,	Amplifier	Oscillator	Amplifier	
Plate Voltage	. 330	330	350	volts
Peak Positive-Pulse Plate Voltage#			2500	volts
Grid-No.2 Voltage	. —		250	volts
Peak Negative-Pulse Grid-No.1 Voltage	. —	400	150	volts
Grid Voltage, Positive-bias value	. 0		_	volt
Plate Dissipation	. 1.25	1	10	watts
Grid-No.2 Input		_	2	watts
Peak Plate Current		70	245	mA.
Average Plate Current		20	80	mA
Peak Grid-No.2 Current			245	mA
Average Grid-No.2 Current	. —		80	m A
MAXIMUM CIRCUIT VALUES				
Grid-No.1 Circuit Resistance:		_	_	_
For fixed-bias operation		1	1	megohm
For degenerative-bias operation*	. –	2.2	2.2	megohms

- # Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).
- A cathode resistor or any feedback system which achieves an equivalent reduction in gain.

16AQ3

Refer to chart at end of section. For replacement use type 16AQ3/XY88.

16**AQ**3/ **XY88** 

DIODE

Miniature type used as booster diodes in line-time-

base circuits of transformerless television receivers.

9CB
Outlines section, 7D; requires miniature 9-contact socket. Type 20AQ3/ LY88 is identical with type 16AQ3/XY88 except for heater ratings.

Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage	16AQ3/ XY88 16.4 0.6 6600	20AQ3/ LY88 20.2 0.45 6600	volts ampere volts
MAXIMUM RATINGS (Design-Center Values)			
Supply Voltage at zero current		550	volts
Supply Voltage		250	volts
Peak Plate Current		55 <b>0</b>	mA
Average Plate Current		220	m A
Plate Dissipation		5	watts
Peak Negative-Pulse Plate Voltage*		6000#	volts

^{*} Under no conditions should an absolute maximum value of 7500 volts be exceeded.

[#] The pulse duration must not exceed 22 per cent of a cycle, or a maximum of 18 microseconds

17CT3

Refer to chart at end of section.	16BX11
Refer to type 6GK6.	16GK6
Refer to type 6GY5.	16GY5
Refer to chart at end of section.	16KA6
Refer to type 6LU8.	16LU8A
Refer to chart at end of section.	17AB10 17AB10/17X10
Refer to type 6AX3.	17AX3
Refer to chart at end of section.	17AX4GT
Refer to type 6AX4GTB.	17AX4GTA
Refer to chart at end of section.	17AY3
Refer to type 6AY3B.	17AY3A
Refer to chart at end of section.	17BB14
Refer to type 6BE3.	17BE3
Refer to type 6BE3.	17BE3/17BZ3
Refer to type 6BF11.	17BF11
Refer to chart at end of section.	17BH3 17BH3A
Refer to chart at end of section.	17BQ6GTB
Refer to chart at end of section.	17BR3
Refer to type 6BR3/6RK19.	17BR3/17RK19
Refer to chart at end of section.	17BS3
Refer to type 6BS3A.	17BS3A 17BS3A/17DW4A
Refer to type 22BW3.	17BW3
Refer to chart at end of section. For replacement use type 17BE3/17BZ3.	17B <b>Z</b> 3
Refer to chart at end of section. For replacement use type 17CU5/17C5.	17C5
Refer to type 6C9.	17C9
Refer to chart at end of section.	17CK3
Refer to chart at end of section.	17CL3
	.,

Refer to type 12CT3.

17CU5 For replacement use type 17CU5/17C5. 17CU5/17C5 Refer to type 6CU5. 17D4 Refer to chart at end of section. 17DE4 Refer to type 6DE4/6CQ4. 17DM4 Refer to chart at end of section. 17DM4A Refer to type 6DM4A/6DA4. 17DQ6A Refer to chart at end of section. Refer to chart at end of section. 17DW4A

For replacement use type 17BS3A/17DW4A.

Refer to chart at end of section.

### 17EW8/ HCC85

17EW8

### HIGH-MU TWIN TRIODE

Miniature type used in rf-amplifier and oscillator-mixer circuits in FM and AM radio receivers. Outlines section. 6B: requires miniature 9-contact socket.



Heater Voltage	17,5	volts
Heater Current	0.15	ampere
Peak Heater-Cathode Voltage	$\pm 90 \text{ max}$	volts
Direct Interelectrode Capacitances:		
Plate to Grid (Each Unit)	1.5	pF
Plate to Cathode (Each Unit)	0.18	pF
Plate to Cathode, Heater, and Internal Shield (Each Unit)	1.2	pF
Grid to Cathode, Heater, and Internal Shield (Each Unit)	3	pF
Plate of Unit No.1 to Plate of Unit No.2	0.04 max	pF
Grid of Unit No.1 to Grid of Unit No.2	0.003 max	pF
Plate of Unit No.1 to Grid of Unit No.2	0.008 max	pF
Plate of Unit No.2 to Grid of Unit No.1	0.008 max	pF
Plate of Unit No.1 to Cathode of Unit No.2	0.008 max	pF
Plate of Unit No.2 to Cathode of Unit No.1	0.008 max	pF
Grid of Unit No.1 to Triode of Unit No.2	0.003 max	$\mathbf{p}\mathbf{F}$
Grid of Unit No.2 to Triode of Unit No.1	0.003 max	pF

### Class A. Amplifier (Each Unit)

Class A: Ampiner (	Each Of	111.7		
MAXIMUM RATINGS (Design-Maximum Values)				
Plate Voltage Grid-Voltage, Negative-bias Value Cathode Current Plate Dissipation			250 100 15 2.5	volts volts mA watts
CHARACTERISTICS				
Plate_Voltage	100	170	200	volts
Grid Voltage	1.1*	-1.5	-2.1	volts
Amplification Factor	50	50	48	_
Transconductance	4600	6200	5800	$\mu$ mhos
Plate Current	4.5	10	10	mA
MAXIMUM CIRCUIT VALUE				
Grid-Circuit Resistance			1	megohm

^{*} Should not be used if grid current is not permissible.

Refer to chart at end of section.	17GJ5
Refer to type 6GJ5A.	17GJ5A
Refer to chart at end of section.	17GT5
Refer to type 6GT5A.	17GT5A
Refer to type 6GV5.	17GV5
Refer to chart at end of section.	17GW6/17DQ6B
Refer to chart at end of section.	17H3
Refer to chart at end of section.	17HB25
Refer to chart at end of section.	17JB6
Refer to type 6JB6A.	1 <i>7</i> JB6A
Refer to type 6JF6.	17JF6
Refer to chart at end of section.	1 <i>7</i> JG6
Refer to type 6JG6A.	17JG6A
Refer to chart at end of section.	17JM6
Refer to type 6JM6A.	17JM6A
Refer to type 6JN6.	17JN6
Refer to type 6JQ6.	1 <i>7</i> JQ6
Refer to type 6JR6.	17JR6
Refer to chart at end of section.	1 <i>7</i> JT6
Refer to type 6JT6A.	17JT6A
Refer to type 6JZ8.	1 <i>7</i> JZ8
Refer to chart at end of section.	17KV6
Refer to type 6KV6A.	17KV6A
Refer to chart at end of section. For replacement use type 15KY8A.	1 <i>7</i> LD8
For replacement use type 17BR3/17RK19.	17RK 19
Refer to chart at end of section. For replacement use type 17AB10/17X10.	17X10
Refer to type 6Y9/EFL200.	17Y9
Refer to chart at end of section.	17Z3/PY81
Refer to chart at end of section.	18A5
Refer to chart at end of section.	18AJ10
Refer to chart at end of section.	18FW6 18FW6A
Refer to chart at end of section.	18FX6 18FX6A
Refer to chart at end of section.	18FY6 18FY6A

Refer to chart at end of section. 18GB5 Refer to type 6GB5/EL500. 18GB5/LL500 18GD6A Refer to chart at end of section. 18GV8/PCL85 Refer to type 6GV8/ECL85. 19 Refer to chart at end of section. 19AU4 Refer to chart at end of section. 19AU4GTA Refer to chart at end of section. 19BG6G Refer to chart at end of section. 19BG6GA 19CG3 For replacement use type 19CG3/19DQ3. 19CG3/19DQ3 Refer to type 6CG3.

19CL8A

Refer to chart at end of section. For replacement use type 19JN8/19CL8A.

19DE3

Refer to chart at end of section.

### 19DK3

### HALF-WAVE VACUUM RECTIFIER

Novar type used as a damper tube in television receivers. Outlines section, 35A; requires novar 9-contact socket. Socket terminals 1. 3. 6. 8 and 9. should not be used as tie points.



9	S	G
9	S	G

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average)	19 0.6 11	volts ampere seconds
Direct Interelectrode Capacitances: Cathode to Plate and Heater Plate to Cathode and Heater Heater to Cathode	22.0 13.6 1.1	pF pF pF
Damper Service		

For operation in a 525-line, 30-frame system		
Peak Inverse Plate Voltage# Peak Plate Current Average Plate Current Plate Dissipation Bulb Temperature (At hottest point)	6500 1200 400 9 220	volts mA mA watts °C
Heater-Cathode Voltage:   Peak value	6500 900	volts volts
CHARACTERISTIC, Instantaneous Value	25	volts

# Pulse duration must not exceed 15% of a horizontal scanning cycle.

19DQ3

For replacement use type 19CG3/19DQ3.


19EA8

Refer to type 6EA8.

19EZ8

Refer to chart at end of section.

Refer to type 12FX5.	19FX5
Refer to chart at end of section.	19 <b>GQ</b> 7
Refer to chart at end of section.	19HR6
Refer to chart at end of section.	19HS6
Refer to chart at end of section.	19HV8
Refer to chart at end of section.	19J6
Refer to chart at end of section.	19JN8
Refer to type 6JN8.	19JN8/19CL8A
Refer to chart at end of section.	19KG8
For replacement use type 18GD6A.	19MR9
For replacement use type 18FW6A.	19MR19
Refer to chart at end of section.	19Q9
Refer to type 6X8A.	19X8
Refer to chart at end of section.	20
Refer to type 16AQ3/XY88.	20AQ3/LY88
Refer to chart at end of section.	20EQ7
Refer to chart at end of section.	20EZ7
Refer to type 6LF6/6LX6.	20LF6
Refer to chart at end of section.	21EX6
Refer to type 6GY5.	21GY5
Refer to chart at end of section.	21HB5



#### BEAM POWER TUBE

### 21HB5A

Duodecar type used as horizontal-deflection amplifier in television receivers. Outlines section, 15B; requires duodecar 12-contact socket. For maximum ratings, refer to type 6HB5. Heater: volts (ac/dc), 21; amperes, 0.45; warm-up time (average), 11 seconds; maximum heater-cathode volts,  $\pm 200$  peak, 100 average.

#### Class A. Amplifier

CHARACTERISTICS	Pento	ode Conne	ction	Triode* Connection	
Plate Voltage	5000	50	130	130	volts
Grid-No.2 (Screen-Grid) Voltage	130	130	130	130	volts.
Grid-No.1 (Control-Grid) Voltage	-	0	20	<b>—20</b>	volta
Amplification Factor	_	_	_	4.8	
Plate Resistance (Approx.)			3900		ohma
Transconductance		_	9000		μmhos

Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for	Ξ	450 <b>-</b> 29-	46 1.8	=	mA mA
plate current of 1 mA	64		32		volta

^{*} Grid-No.2 tied to plate

21HJ5 Refer to chart at end of section.


21JS6A For replacement use type 23JS6A.

21JV6 Refer to chart at end of section.

### 21JZ6

#### **BEAM POWER TUBE**

Duodecar type used as horizontal-deflection amplifier in television receivers. Outlines section, 39A; requires duodecar 12-contact socket. Heater: volts (ac/dc), 21; amperes, 0.45; average warm-up time, 11 seconds; maximum heater-cathode volts,  $\pm 200$  peak, 100 average.



#### Class A. Amplifier

	Triode	•			
CHARACTERISTICS	Connection	n Pen	tode Conne	ction	
Plate Voltage	13)	5000	50	130	volts
Grid No.3 (Suppressor Grid)		Connected	to cathode	at socket	
Grid-No.2 (Screen-Grid) Voltage		130	130	130	volts
Grid-No.1 (Control-Grid) Voltage	20		0	20	volts
Amplification Factor	4.8				
Plate Resistance (Approx.)				9900	ohms
Transconductance				9000	μmhos
Plate Current			450	46	mA
Grid-No.2 Current	_		29	1.8	mA
Grid-No.1 Voltage (Approx.) for plate					
current of 1.0 mA	_	64		<del>-32</del>	volts

A Grid No.2 connected to plate.


Grid-No.1-Circuit Resistance

### Horizontal-Deflection Amplifier For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values) Plate Supply Voltage
Peak Positive-Pulse Plate Voltage#
Peak Negative-Pulse Plate Voltage 770 volts 6500 volts 1500 volta Peak Negative-Pulse Plate Voltage
DC Grid-No.3 Voltage, Positive-bias value
Grid-No.1 Voltage, Negative-bias value
Peak Negative-Pulse Grid-No.1 Voltage
Peak Cathode Current 70 volts **2**20 volts 55 volts 330 volts 800 mA ge Cathode Current Dissipation 230 Average mA 18 watts ....... Grid-No.2 Input Bulb Temperature (At hottest point) MAXIMUM CIRCUIT VALUE

A bias resistor or other means is required to protect the tube in absence of excitation. Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.



#### **BEAM POWER TUBE**

### **21KA6**

Duodecar type used as horizontal-deflection amplifier in television receivers. Outlines section, 16A; requires duodecar 12-contact socket. A separate connection is provided for grid No.3 to minimize "snivets."

#### **12GH**

Heater Voltage Heater Current Heater Warm-up Time Heater-Cathode Voltage: Peak value Average value				21 0.45 11 ±200 max 100 max	volts ampere seconds volts
Cla	ass A, An	nplifier			
CHARACTERISTICS		-			
Plate VoltageGrid-No.3 (Suppressor-Grid)	5000	60	60	130	volts .
Voltage	0	0	25	0	volts
Grid-No.2 (Screen-Grid) Voltage	130	130	130	130	volts
Grid-No.1 (Control-Grid) Voltage		0	0	20	volts
Plate Resistance (Approx.)	_		_	11000	ohms
Transconductance	-			9100	$\mu$ mhos
Plate Current	_	410°	410*	50	mA.
Grid-No.3 Current	_	<del></del> .	2	. <del></del>	mA
Grid-No.2 Current for Grid-No.1 Voltage (Approx.) for		24*	23*	1.75	mA
plate current of 1 mA	66		_	-33	volts
Triode Amplification Factor	~		-	4.7	

^{*}This value may be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

#### Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Supply Voltage	770	volts
Peak Positive-Puise Plate Voltage#	65 <b>00</b>	volts
Peak Negative-Pulse Plate Voltage	1500	volts
Grid-No.3 Voltage, Positive-bias value	70	volts
Grid-No.2 Voltage	220	volts
Grid-No.1 Voltage, Negative-bias value	55	volts
Peak Negative-Pulse Grid-No.1 Voltage	330	volts
Average Cathode Current	230	mA
Peak Cathode Current	800	mA.
Plate Dissipation	18	watts
Grid-No.2 Input	3.5	watts
Bulb Temperature (At hottest point)	220	•c
MAXIMUM CIRCUIT VALUE		
Grid-No.1-Circuit Resistance	1	megohm

[#] Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).



#### **BEAM POWER TUBE**

21KQ6

Magnoval type used as horizontal-deflection amplifier in television receivers. Outlines section, 40A; requires magnoval 9-contact socket. Type 29KQ6/PL521 is identical with type 21KQ6 except for heater ratings.

	21KQ6	29KQ6/PL521	
Heater Voltage	21.5 0.45	29 0.3	volts ampere

Heater-Cathode Voltage: Peak value Average value	±240 ±240	±240 ±240	volts volts
Class A. Amplifier			
CHARACTERISTICS			
Plate Voltage	40	50	volts
Grid-No.3 (Suppressor-Grid) Voltage	0	0	volts
Grid-No.2 (Screen-Grid) Voltage	135	200	volts
Grid-No.1 (Control-Grid) Voltage	0	12	
Plate Current	450	550‡	mA
Grid-No.2 Current	35	50±	mA
Grid-No.1 Voltage for plate current of 50 µA	—55 max.	`	volts

† This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

#### Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)

#### MAXIMUM CIRCUIT VALUES

Grid-No.1-Circuit Resistance	0.5	megohm
Grid-No.1-Circuit Resistance, for horizontal-deflection circuit	2.2	megohms

# Pulse duration must not exceed 22% of a horizontal scanning cycle (18 microseconds).


21LG6

Refer to chart at end of section.

### 21LG6A

#### **BEAM POWER TUBE**

Duodecar type used as horizontal-deflection amplifier in color television receivers. Outlines section, 16B; requires duodecar 12-contact socket. Heater: volts, 21; ampere, 0.6; maximum heater-cathode volts, ±200 peak, 100 average.



#### Class A. Amplifier

CHARACTERISTICS	Triode* Connection	Pentode Connection			
Plate Voltage	. 125	6000	50	175	volts
Grid-No.2 (Screen-Grid) Voltage	. 125	125	125	125	volts
Grid-No.1 (Control-Grid) Voltage	.      —25		0	23	vol <b>ts</b>
Plate Resistance (Approx.)			_	7500	oh <b>ms</b>
Transconductance		_		11500	μmhos
Plate Current			600	90	mA
Grid-No.2 Current	. —		42	1.7	mA
Grid-No.1 Voltage (Approx.) for plate	e				
current of 1 mA		115		45	volts
Amplification Factor	3.6				

#### Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM KATINGS (Design-Maximum values)		
DC Plate Supply Voltage	900	volts
Peak Positive-Pulse Plate Voltage#	7500	volts
Peak Negative-Pulse Plate Voltage	100	volts

volts

volts

250 300

Plate Dissipation Grid-No.2 Input Average Cathode Current Peak Cathode Current Bulb Temperature	28 5 315 1100 250	watts watts mA mA °C
MAXIMUM CIRCUIT VALUES		
Grid-No.1 Circuit Resistance:  With feedback type high voltage regulation  With should true high soltage regulation (switching mode)	1.8	megohms megohms


Grid-No.2 Voltage
Grid-No.1 Voltage, Negative-bias value

* Grid-No. 2 tied to plate.

# Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

A bias resistor or other means is required to protect the tube in absence of excitation.

Refer to type 6LR8.	21LR8
Refer to type 6LU8.	21LU8
Refer to chart at end of section.	21MY8
Refer to chart at end of section.	22
Refer to chart at end of section.	22BH3
Refer to chart at end of section.	22BH3A



# HALF-WAVE VACUUM RECTIFIER

## **22BW3**

Duodecar type used as damper tube in horizontal-deflection circuits of television receivers. Outlines section, 8D; requires duodecar 12-contact socket. Type 17BW3 is identical with type 22BW3 except for heater ratings.

WA., WM ( (1.)	17BW3 16.8	22BW3 22.4	14
Heater Voltage (ac/dc)			volts
Heater Current	0.6	0.45	ampere
Heater Warm-up Time	11	11	seconds
Direct Interelectrode Capacitances:			
Cathode to Heater and Plate		8.5	рF
Plate to Cathode and Heater		6	ρF
Heater to Cathode		3.8	ρF
meater to Cathode		0.0	pr.
Damper Service			
For operation in a 525-line, 30-fram	ne system		
MAXIMUM RATINGS (Design-Maximum Values)	-		
Peak Inverse Plate Voltage#		5000	voits
Peak Plate Current	· · · · · · · · · · · · ·	1100	mA
		175	mA
Average Plate Current			
Plate Dissipation	• • • • • • • •	6.5	watts
Heater-Cathode Voltage:			
Peak value	+300	5000	volts
Average value	+100	<b>—900</b>	volts
CHARACTERISTICS, Instantaneous Value			
Tube Voltage Drop for plate current of 350 mA		32	volts
# Pulse duration must not exceed 15% of one horizontal	scanning of	cycle (10 m	ncroseconds).


Refer to type 6DE4/6CQ4.	22DE4
Refer to type 6JF6.	22JF6
Refer to chart at end of section.	22JG6
Refer to type 6JG6A.	22JG6A

22JR6 Refer to type 6JR6.
22JU6 Refer to type 6JU6.
22KM6 Refer to type 6KM6.
22KV6A Refer to type 6KV6A.
23J56A Refer to type 6JS6C.

23**Z**9

#### DUAL TRIODE— BEAM POWER TUBE

Duodecar type used in combined vertical-deflection-oscillator and vertical-deflection-amplifier applications in television receivers. Outlines section, 8B; requires duodecar 12-contact socket. Heater: volts (ac/dc), 23; amperes, 0.45; average warm-up time, 11 seconds; maximum heater-cathode volts, ±200 peak, 100 average.



12GZ

#### Class A. Amplifier

	Triode	Triode		m Power	
CHARACTERISTICS	Unit No.1	Unit No.2	1	Init	
Plate Voltage	150	150	45	120	volts
Grid-No.2 (Screen-Grid) Voltage			110	110	volts
Grid-No.1 (Control-Grid) Voltage	<b>—2</b>	5	0	8	volts
Amplification Factor	43	20			
Plate Resistance (Approx.)	11000	8500		11700	ohms
Transconductance	3900	2350		7100	μmhos
Plate Current	5.4	5.5	122	46	m.A.
Grid-No.2 Current	-	_	16.5	3.5	mA
Grid-No.1 Voltage (Approx.) for plate current of 100 $\mu$ A	_	_		25	volts
current of 10 $\mu$ A	-5.7	11			volts

## Vertical-Deflection Oscillator and Amplifier For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Peak Positive-Pulse Plate Voltage# Grid-No.2 Voltage Peak Negative-Pulse Grid-No.1 Voltage Grid Voltage, Positive-bias value	Triode Unit No.1 Amplifier 330 — — —	Triode Unit No.2 Oscillator 250 400	Beam Po Unit Amplific 250 2000 200 150	
Plate Dissipation	125	1	7	watts
Grid-No.2 Input	-		1.8	watts
Peak Cathode Current	_		245	mA
Average Cathode Current		_	70	mA
Peak Plate Current		70		m.A
Average Plate Current	_	20	_	$\mathbf{m}\mathbf{A}$
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance:		_		_
For fixed-bias operation	0.5	1	1	megohm

# Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

24A

Refer to chart at end of section.

24BF11

Refer to type 6BF11.

24JE6A

Refer to chart at end of section. For replacement use type 24LQ6/24JE6C.

24JE6C

For replacement use type 24LQ6/24JE6C.

**24JZ8** 

Refer to type 6JZ8.


For replacement use type 24LQ6/24JE6C.	24LQ6
Refer to type 6MJ6/6LQ6/6JE6C.	24LQ6/24JE6C
Refer to chart at end of section.	24LZ6
P. 6 . 1 . 1 . 1 . 1 . 1	25A6
Refer to chart at end of section.	25A6GT
Refer to chart at end of section.	25A7GT
Refer to chart at end of section.	25AC5GT
Refer to type 6AV5GA.	25AV5GA
Refer to chart at end of section.	25AX4GT
Refer to chart at end of section.	25B5
Refer to chart at end of section.	25B6G
Refer to chart at end of section.	25B8GT
Refer to chart at end of section.	25BK5
Refer to chart at end of section.	25BQ6GT
Refer to type 6BQ6GTB/6CU6.	25BQ6GTB/25CU6
Refer to type 50C5.	25C5
Refer to chart at end of section.	25C6G
Refer to chart at end of section. For replacement use type 25C5.	25CA5
Refer to chart at end of section.	25CD6GA
Refer to type 6CD6GA.	25CD6GB
Refer to type 6CG3.	25CG3
Refer to chart at end of section.	25CK3
Refer to chart at end of section.	25CM3
Refer to type 12CT3.	25CT3
Refer to type 6BQ6GTB/6CU6.	25CU6
Refer to type 6DL3.	25DL3
Refer to chart at end of section.	25DN6
Refer to chart at end of section.	25E5/PL36
Refer to chart at end of section.	25EC6
Refer to type 6EH5.	25EH5
Refer to chart at end of section.	25F5A
Refer to chart at end of section.	25HX5
Refer to chart at end of section.	25JQ6
Refer to type 6JZ8.	25JZ8
Refer to chart at end of section.	2516

25L6GT/25W6GT	Refer to chart at end of section.
25N6G	Refer to chart at end of section.
25W4GT	Refer to chart at end of section.
25W6GT	For replacement use type 25L6GT/25W6GT Refer to chart at end of section.
25Y5	Refer to chart at end of section.
<b>25Z</b> 5	Refer to chart at end of section.
25Z6 25Z6GT	Refer to chart at end of section.
26	Refer to chart at end of section.
26A6	Refer to chart at end of section.
26A7GT	Refer to chart at end of section.
26C6	Refer to chart at end of section.
26D6	Refer to chart at end of section.

### **26HU5**

#### **BEAM POWER TUBE**

Glass octal type used as horizontal-deflection amplifier in color television receivers. Outlines section, 21B; requires octal socket. Heater: volts (ac/dc), 26; ampere, 0.6; warm-up time (average), 11 seconds; maximum heater-cathode volts,  $\pm 200$  peak, 100 average.



•	lass		A	-1	:6:	~-	
	iass	A۱	ΑП	OI	III	er	

CHARACTERISTICS	Triode‡ Connection				
Plate Voltage	. 150	45	60	175	volts
Grid-No.2 (Screen-Grid) Voltage	. 150	160	110	110	volts
Grid-No.1 (Control-Grid) Voltage	. —22.5	0	0	21	volts
Plate Resistance (Approx.)			_	6000	ohms
Transconductance	. <del>-</del>			14000	μmhos
Plate Current		1100*	750 -	125	mA
Grid-No.2 Current		110-	42=	3.3	mA
Grid-No.1 Voltage (Approx.) for plate curren	t				
of 1 mA				40	volts
Amplification Factor	. 4		_	_	

t Grid No.2 tied to plate.

This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

#### Horizontal-Deflection Amplifier

#### For operation in a 525-line, 30-frame system

#### MAXIMUM RATINGS (Design-Maximum Values)

DC Plate Supply Voltage	990	volts
Peak Positive Pulse Plate Voltage#	7000	volts
Grid-No.2 Voltage	250	volts
Grid-No.1 Voltage, Negative-bias value	250	volts
Plate Dissipation* (Absolute-maximum value)	33	watts
Grid-No.2 Input	5	watts
Average Cathode Current	400	mA
Peak Cathode Current	1400	mA
Bulb Temperature (At hottest point)	250	°Ċ


#Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). A bias resistor or other means is required to protect the tube in absence of excitation.

#### MAXIMUM CIRCUIT VALUES

Grid-No.1-Circuit Resistance: megohms megohms

Refer to chart at end of section.

**26LW6** 



#### **BEAM POWER TUBE**

26LX6

Duodecar type used as a horizontal-deflection amplifier in color and black-and-white television receivers. Outlines section, 16C; requires duodecar 12-contact socket. Heater: volts (ac/dc), 26; ampere, 0.6; warm-up time, 11 seconds; maximum heater-cathode volts, ±200 peak. 100 average.

#### Class A₁ Amplifier

	Triode*				
CHARACTERISTICS	Connection	Pen	tode Connec	tion	
Plate Voltage		5000	45	175	volts
Grid-No. 3 (Suppressor-Grid)			Connected	to cathode	at socket
Grid-No. 2 (Screen-Grid) Voltage		110	160	110	volts
Grid-No. 1 (Control-Grid) Voltage			0	21	volts
Plate Resistance (Approx.)		_		6000	ohms
Transconductance			_	14000	$\mu$ mhos
Plate Current			1100‡	125	mA
Grid-No. 2 Current	. —		11C‡	3.3	mA.
Grid-No. 1 Voltage (Approx.) for plate					
current of 1 mA		125	_		volts
Amplification Factor	. 4	_	_	-	

#### Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system MAYIMIM DATINGS (Design Mayimum Values)

MAXIMUM RATINGS (Design-Maximum values)		
DC Plate Supply Voltage Peak Positive Pulse Plate Voltage# (Absolute Maximum Value) Peak Negative-Pulse Plate Voltage Grid-No. 3 Voltage, Positive-bias value Grid-No. 2 Voltage Peak Negative Grid-No. 1 Voltage Peak Regative Grid-No. 1 Voltage Peak Cathode Current Average Cathode Current Plate Dissipation (Absolute Maximum Value) Grid-No. 2 Input	990 7000 100 0 250 250 1400 400 33	volts volts volts volts volts volts mA mA watts watts
Bulb Temperature (At hottest point)	240	°C
MAXIMUM CIRCUIT VALUES		

Grid-No.1-Circuit Resistance:  With feedback-type high voltage regulation With shunt-type high voltage regulation (switching mode) Grid-No.3-Circuit Resistance			megohms megohms ohms
MIMIMUM RECOMMENDED GRID DRIVE			
Peak Positive Pulse Plate Voltage Peak Negative Grid-No. 1 Voltage for grid-No. 2 voltage	5000	6000	volts
of 150 volts	-190	210	volts

Peak Negative Grid-No. 1 Voltage for grid-No. 2 voltage of 200 volts ... -210 -235 volts Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). A bias resistor or other means is required to protect the tube in absence of excitation.

Grid-No. 2 tied to plate.

This value may be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

27

27GB5/PL500

Refer to chart at end of section. Refer to type 6GB5/EL500.


Refer to chart at end of section.

29KQ6/PL521

29LE6

#### **BEAM POWER TUBE**

Magnoval type used as horizontal-deflection amplifier in television receivers. Outlines section, 40A; requires magnoval 9-contact socket.



	9RJ
volts ampere	29 0.3
volts	+240

volts

±240

#### Class A. Amplifier

#### CHARACTERISTICS

Peak value ... Average value

•			
Plate Voltage	40	50	volts
Grid-No.3 (Suppressor-Grid) Voltage	0	0	volts
Grid-No.2 (Screen-Grid) Voltage	135	200	volts
Grid-No.1 (Control-Grid) Voltage	0	12	
Plate Current	450	550‡	mA
Grid-No.2 Current	35	50‡	mA
Grid-No.1 Voltage for plate current of 50 µA	55 max.	'	volts

[†] This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

#### Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	275	volts
Peak Positive-Pulse Plate Voltage#	6500	volts
Peak Negative-Pulse Plate Voltage#	1650	volts
Grid-No.3 Voltage	70	volts
Grid-No.2 Voltage	275	volts
Peak Negative-Pulse Grid-No.1 Voltage	330	volts
Average Cathode Current	275	mA
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance	0.5	megohm
Grid-No.1-Circuit Resistance, for horizontal-deflection circuit	2.2	megohms

[#] Pulse duration must not exceed 22% of a horizontal scanning cycle (18 microseconds).

30

Refer to chart at end of section.

30AE3/ PY88

#### DIODE

Miniature type used as booster diodes in line-timebase circuits of transformerless television receivers. Outlines section, 7D; requires miniature 9-contact socket. Heater: volts (ac/dc), 30; amperes, 0.3; maximum heater-cathode volts, 6600 peak.



9CB

MUMIXAN	RATINGS	(Design-Center	Values)

Supply Voltage at zero current	550	volts
upply Voltage Peak Plate Current	250 550	volts mA
eak Flate Current	000	*****

Average Plate Current	220	mA
Plate Dissipation	5 6000#	watts volts

* Under no conditions should an absolute maximum value of 7500 volts be exceeded.

# The pulse duration must not exceed 22 per cent of a cycle, or a maximum of 18 microseconds.

Refer to chart at end of section.	30AG11
Refer to chart at end of section.	30JZ6
Refer to type 6KD6.	30KD6
Refer to chart at end of section.	30MB6
Refer to chart at end of section.	31
Refer to chart at end of section.	31AL10
Refer to chart at end of section.	31JS6A
Refer to type 6JS6C.	31JS6C
Refer to type 6MJ6/6LQ6/6JE6C.	31LQ6
Refer to type 6LR8.	31LR8



#### **BEAM POWER TUBE**

31LZ6

Novar type used for horizontal-deflection amplifier in color television receivers. Outlines section, 32C; requires novar 9-contact socket.

Heater Voltage (ac/dc)		volts
Heater Current	0.45	ampere
Heater Warm-up Time	11	seconds
Heater-Cathode Voltage:		
Peak value	$\pm 200 \text{ max}$	volts
Average value	100 max	volts
Direct Interelectrode Capacitances:		
Grid No.1 to Plate	0.6	pF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3	22	pF
Plate to Cathode, Heater, Grid No.2, and Grid No.3	11	pF

#### Class A. Amplifier

	Triode†	_			
CHARACTERISTICS	Connection	Pen	tode Conn	ection	
Plate Voltage	125		55	175	volts
Peak Positive-Pulse Plate Voltage#		5000			volts
Grid No.3 (Suppressor Grid)		30	30	30	volts
Grid-No.2 (Screen-Grid) Voltage	125	130	125	125	volts
Grid-No.1 (Control-Grid) Voltage	25	_	0	25	volts
Amplification Factor	3	_			
Plate Resistance (Approx.)				6000	oh <b>ms</b>
Transconductance				11000	$\mu$ mhos
Plate Current	_	_	800††	140	mA
Grid-No.2 Current	_		56††	2	m A
Grid-No.1 Voltage for plate current					
of 1 mA		—125		50	volts

#### Horizontal-Deflection Amplifier

#### For operation in a 525-line, 30-frame system

### MAXIMUM RATINGS (Design-Maximum Values) DC Plate Supply Voltage

DC Plate Supply Voltage	990	volts
Peak Positive-Pulse Plate Voltage#	7500	volts
Peak Negative-Pulse late Voltage	1100	volts
DC Grid-No.3 Voltage	75	volts

DC Grid-No.2 Voltage Peak Negative-Pulse Grid-No.1 Voltage	220 330	vol <b>ts</b> vol <b>ts</b>
Peak Cathode Current Average Cathode Current	1200 350	mA mA
Grid-No.2 Input Plate Dissipation==	5 30	watts watts
Bulb Temperature (At hottest point)	240	""°C


#### MAXIMUM CIRCUIT VALUES


Grid-No.1-Circuit Resistance:		
For cathode-bias operation	1	mego <b>hm</b>
For grid-leak-bias operation	10	megohms
For fixed-bias operation	0.47	megohm

- # Pulse duration must not exceed 15% of one horizontal scanning cycle (10 microseconds).
  † Grid No.2 connected to plate.
  † This value can be measured by a method involving a recurrent waveform such that the
- maximum ratings of the tube will not be exceeded.

  In this service, a positive value may be applied to grid No.3 to minimize "snivets" interference; a typical value for this voltage is 30 volts.

A bias resistor or other means is required to protect the tube in absence of excitation.





32	Refer to chart at end of section.
32ET5 32ET5A	Refer to chart at end of section.
32HQ7	Refer to chart at end of section.
3217GT	Refer to chart at end of section.
33	Refer to chart at end of section.
33GT7	Refer to chart at end of section.
33GY7	Refer to chart at end of section.

### 33GY7A DIODE—BEAM POWER TUBE

50GY7A

Duodecar type used as combined damper diode and horizontal-deflection amplifier in television receivers. Socket terminals 1, 3, 6 and 7 should not be used as tie points. Outlines section, 15A; requires duodecar 12-contact socket. Type 50GY7A is identical with type 33GY7A except for heater ratings.



12FN

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	33GY7A 33.6 0.45 11	50GY7A 50 0.3 11	volts ampere seconds
Peak value Average value		±200 max 100 max	volts volts
Beam Power Unit as Class	A. Amplifier		

Beam	Power	Unit	as	Class	A ₁	Amplifier

CHARACTERISTICS	Pento	de Conne	ection	Connection	
Plate Voltage	5000	60	130	130	volts
Grid-No.2 (Screen-Grid) Voltage	130	130	130	130	volta
Grid-No.1 (Control-Grid) Voltage		0	-22.5	22.5	volts
Amplification Factor	_	_		4	
Plate Resistance (Approx.)	_	-	10000	_	ohms
Transconductance	_	_	6500	_	μmhos
Plate Current	_	320 -	48	_	· mA
Grid-No.2 Current		22=	2.9		mA.
Grid-No.1 Voltage (Approx.) for plate					
current of 1 mA	80		40	_	volts
* Grid No.2 tied to plate.					

[•] This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

#### Beam Power Unit as Horizontal-Deflection Amplifier

For operation in a 525-line, 50-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
DC Plate Supply Voltage	400	volts
Peak Positive-Pulse Plate Voltage#	5000	volts
Peak Negative-Pulse Plate Voltage	0	volts
DC Grid-No.2 Voltage	150	volts
DC Grid-No.1 Voltage	55	volts
Peak Negative-Pulse Grid-No.1 Voltage	330	volts
Peak Cathode Current	540	mA
Average Cathode Current	155	mA.
Plate Dissipation;	9	watts
Grid-No.2 Input	8	watts

#### 

l megohm

# Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds). † A bias resistor or other means is required to protect the tube in absence of excitation.

### Damper Service (Diode Unit)

For operation in a 525-line, 30-frame system

MAXIMUM KATINGS (Design-Maximum values)		
Peak Inverse Plate Voltage#	4200	volts
Peak Plate Current	810	mA.
Average Plate Current	135	mA
Plate Dissipation	3.8	watts
Heater-Cathode Voltage:	_	
Peak value	4200	volts
Average value	-400	volts
Bulb Temperature (At hottest point)	200	$^{\circ}\mathrm{C}$
CHARACTERISTICS, Instantaneous Value		

Refer to type 6JR6.	33JR6
Refer to chart at end of section.	331/6
Refer to chart at end of section.	34
Refer to type 6CE3/6CD3/6DT3.	34CE3
Refer to chart at end of section.	34CM3

34GD5	Refer to chart at end of section.
34GD5A	Refer to chart at end of section.
34R3	Refer to chart at end of section.
35	Refer to chart at end of section.
35A5	Refer to chart at end of section.
35B5	Refer to chart at end of section.

### 35C5

#### **BEAM POWER TUBE**

Miniature type used in output stage of compact, ac/dc radio receivers. Outlines section, 5D; requires miniature 7-contact socket. This tube, like other power-handling tubes, should be adequately ventilated. Except for terminal connections and slightly higher ratings, type 35C5 is equivalent in performance to miniature type 35B5 and, within its maximum ratings, to glass octal type 35L6GT.



7	CV
•	L.V


* =		
Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage:	35 0.15	volts ampere
Peak value Average value	±200 max 100 max	volts volts
Direct Interelectrode Capacitances (Approx.):		
Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 Plate to Cathode, Heater, Grid No.2, and Grid No.3	0.6 12 9	pF pF pF
Class A, Amplifier		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	150	volts
Grid-No.2 (Screen-Grid) Voltage	130	volts
Plate Dissipation	5.2	watts
Grid-No.2 Input Bulb Temperature (At hottest point)	$\frac{1.1}{250}$	watts °C
	250	C
TYPICAL OPERATION Plate Voltage	110	volts
Grid-No.2 Voltage	110	volts
Grid-No.1 (Control-Grid) Voltage	7.5	volts
Peak AF Grid-No.1 Voltage	7.5	volts
Zero-Signal Plate Current	40	mA
Maximum-Signal Plate Current	41	mA
Zero-Signal Grid-No.2 Current	3	mĄ
Maximum-Signal Grid-No.2 Current	7	mA
Plate Resistance (Approx.)	13000 5800	ohms μmhos
Transconductance Load Resistance	2500	ohms
Total Harmonic Distortion	10	per cent
Maximum-Signal Power Output	1.5	watts
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.1	megohm
For cathode-bias operation	0.5	megohm
•		

#### Installation and Application


The 35-volt heater is designed to operate under the normal conditions of line-voltage variation without materially affecting the performance or serviceability of the 35C5. For operation of the 35C5 in series with other types having 0.15-ampere rating, the current in the heater circuit should be adjusted to 0.15 ampere for the normal supply voltage.

In a series-heater circuit of the "dc-power line" type employing several 0.15-ampere types and one or two 35C5s, the heater(s) of the 35C5(s) should be placed on the positive side of the line. Under these conditions, heater-cathode voltage of the 35C5 must not exceed the value given under maximum ratings. In a series-heater circuit of the "universal" type employing rectifier tube 35W4, one or two 35C5s and several 0.15-ampere types, it is recommended that the heater(s) of the 35C5(s) be placed in the circuit so that the higher values of heater-cathode bias will be impressed on the 35C5(s) rather than on the other 0.15-ampere types. This is accomplished by arranging the 35C5(s) on the side of the supply line which is connected to the cathode of the rectifier, i.e., the positive terminal of the rectified voltage supply. Between this side of the line and the 35C5(s), any necessary auxiliary resistance and the heater of the 35W4 are connected in series.

As a power amplifier (class A₁), the 35C5 is recommended for use either singly or in push-pull combination in the power-output stage of ac/dc receivers. The operating values shown under typical operation have been determined on the basis that grid-No.1 current does not flow during any part of the input cycle.



Refer to chart at end of section.	35DZ8
Refer to chart at end of section.	35EH5
Refer to chart at end of section.	35GL6
Refer to chart at end of section.	35L6GT
Refer to type 6LR6.	35LR6



#### HALF-WAVE VACUUM RECTIFIER

35W4

Miniature type used in power supply of ac/dc receivers. Outlines section, 5D; requires miniature 7-contact socket. This type is equivalent in performance to glass-octal type 35Z5GT. The heater is provided with a tap for operation of a panel lamp.

Heater Voltage (ac/dc): Entire Heater (pins 3 and 4) Panel Lamp Section (pins 4 and 6)	* 35 7.5	** 32 5.5	volts volts
Heater Current:  Between Pins 3 and 4  Between Pins 3 and 6  Peak Heater-Cathode Voltage	0.15 —	0.15 ±360 max	ampere ampere volts


[•] Without panel lamp.

#### Half-Wave Rectifier

MAXIMUM RATINGS (Design-Maximum Values) Peak Inverse Plate Voltage Peak Plate Current Average Output Current:  With Panel Lamp and { No Shunting Resistor Without Panel Lamp Panel-Lamp-Section Voltage:	tor		•	360 660 66 100 110	volts mA mA mA
When Panel Lamp Fails AC Plate-Supply Voltage (rms) Filter-Input Capacitor Minimum Total Effective Plate-Supply Impedance Panel-Lamp Shunting Resistor Average Output Current	117 40 15 60	117 40 15 300 70	117 40 15 150 80	17 117 40 15 100 90	volts volts  µF ohms ohms ohms


[†] No.40 or No.47 panel lamp used in circuit given below with capacitor-input filter.

#### Installation and Application



For heater considerations, refer to miniature type 35C5.

With the panel lamp connected as shown in the diagram, the drop across R and all heaters (with panel lamp) should equal 117 volts at 0.15 ampere. The shunting resistor R, is required when dc output current exceeds 60 milliamperes. Values of R, for dc output currents greater than 60 milliamperes are given in tabulated data.




TYPICAL OPERATION WITHOUT PANEL LAMP		
AC Plate-Supply Voltage (rms)	117	volts
Filter-Input Capacitor	40	μ <b>F</b> o <b>hms</b>
Minimum Total Effective Plate-Supply Impedance	15	ohms
Average Output Current	100	mA
DC Output Voltage at Input to Filter (Approx.):		
At half-load current (50 mA)	135	volts
At full-load current (100 mA)	120	volts
Voltage Regulation (Approx.):		
Half-load to full-load current	15	volts
MAXIMUM CIRCUIT VALUES		
Panel-Lamp Shunting Resistor:*		
For dc output current of \begin{cases} 70 & mA &	800 400 250	ohms ohms ohms

^{*} Required when dc output current is greater than 60 milliamperes.

^{**} With No.40 or No.47 panel lamp.

Refer to chart at end of section.	35Y4
Refer to chart at end of section.	35 <b>Z</b> 3
Refer to chart at end of section.	35Z4GT



MAXIMUM RATINGS (Design-Center Values)

#### HALF-WAVE **VACUUM RECTIFIER**

35**Z**5**G**T

Glass octal type used in power supply of ac/dc receivers. The heater is provided with a tap for operation of a panel lamp. Outlines section, 13D; requires octal socket. This type may be supplied with pin No.1 omitted. For installation and application considerations, refer to miniature type 35W4.

	•			
Heater Voltage (ac/dc):		•	**	
Entire Heater (pins 2 and	17)	35	32	volts
Panel Lamp Section (pins	2 and 3)	35 7.5	5.5	volts
Heater Current:	•			
Between Pins 2 and 7		0.15	_	ampere
Between Pins 3 and 7		-	0.15	ampere
Peak Heater-Cathode Voltage			$\pm 350 \text{ max}$	volts
* Without panel lamp.				
** With No.40 or No.47 panel	lamp.			
	Half Ways Posti	liar		

#### Half-Wave Rectifier

MAXIMON KATHES (Design Center Val	403)					
Peak Inverse Plate Voltage			<b></b>	. 70	00	volts
Peak Plate Current				. 60	00	$\mathbf{m}\mathbf{A}$
Average Output Current:						
With Panel Lamp and { No Shunti Shunting	ng Res	istor	<i></i>	. €	60	mA.
with Panel Lamp and Shunting	Resistor			. 9	0	mA.
Without Panel Lamp					00	mA
Panel-Lamp-Section Voltage (rms):						
When Panel Lamp Fails				. 1	.5	volts
TYPICAL OPERATION WITH PANEL LAMP	<b>&gt;</b> +					
	•					
AC Plate-Supply Voltage (rms)	117	117	117	117	235	volts
Filter-Input Capacitor	40	40	40	40	40	$\mu$ F
Minimum Total Effective Plate-						
Supply Impedance	15	15	15	15	100	ohms
Panel-Lamp Shunting Resistor		300	150	100	_	ohms
Average Output Current	60	70	80	90	60	mA

† No.40 or No.47 panel lamp used in circuit with capacitor-input filter given under type 35W4. TYPICAL OPERATION WITHOUT PANEL LAMPS

TITIONE OF ENATION MILITORY CAME EAST			
AC Plate-Supply Voltage (rms)	117	235	volts
Filter-Input Capacitor	40	40	$\mu \mathbf{F}$
Minimum Total Effective Plate-Supply Impedance	15	100	ohms
Average Output Current	100	100	mA
DC Output Voltage at Input to Filter (Approx.):			
At half-load current (50 mA)	140	280	volts
At full-load current (100 mA)	120	235	volts
Voltage Regulaton (Approx.):			
Half-load to full-load current	20	45	<b>v</b> olts
MAXIMUM CIRCUIT VALUES			
Panel-Lamp Shunting Resistor :			
For dc ouptut current of 80 mA		800	ohms
For dc ouptut current of 80 mA		400	ohms
90 mA		250	ohms

· Required when de output current is greater than 60 milliamperes.

Refer to chart at end of section.

36 **36AM3 36AM3A 36AM3B** 

Refer to chart at end of section.

36KD6/40KD6

Refer to type 6KD6.



#### 9QL

#### **BEAM POWER TUBE**


### 36MC6


Novar type used for horizontal-deflection amplifier in color television receivers. Outlines section, 18D; requires novar 9-contact socket.

Heater Voltage (ac/dc) Heater Current	36 0.45	volts ampere
Heater-Cathode Voltage:	0.40	Ampere
Peak value	$\pm 200 \text{ max}$	volts
Average value	100 max	volts
Direct Interelectrode Capacitances:	• •	-
Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2 and Grid No.3	1.0	pF
Plate to Cathode, Heater, Grid No.2, and Grid No.3	40 16	pF pF
Thate to Cathode, Heater, Grid 140.2, and Grid 140.3	10	рr

#### Class A. Amplifier

0114040770107100	Triodet					
CHARACTERISTICS	Connection		Pentode	Connection	1	
Plate Voltage	175		45	60	175	volts
Peak Positive-Pulse Plate Voltage#		5000		_		volts
Grid No.3 (Suppressor Grid)	_	30	30	30	30	volts
Grid-No.2 (Screen-Grid) Voltage	175	110	110	110	110	volts
Grid-No.1 (Control-Grid) Voltage	21	_	0	0	21	volts
Amplification Factor	4			-	_	
Plate Resistance (Approx.)		_			6000	ohms
Transconductance					14000	$\mu$ mhos
Plate Current		_	1100††	750††	125	mA
Grid-No.2 Current		_	110††	42††	3.3	mA
Grid-No.1 Voltage for plate current						
of 1 mA		-125		_	40	volts





#### Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system

MAXIMUM KATINGS (Design-Maximum Values)		
DC Plate Supply Voltage	990	volts
Peak Positive-Pulse Plate Voltage#	7500	volts
Peak Negative-Pulse Plate Voltage	1100	volts
DC Grid-No.3 Voltage	75	volts
DC Grid-No.2 Voltage	250	volts

Peak Negative-Pulse Grid-No.1 Voltage Peak Cathode Current Average Cathode Current Grid-No.2 Input Plate Dissipation Bulb Temperature (At hottest point)	330 1400 400 5 33 250	volts mA mA watts watts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For cathode-bias operation For grid-leak-bias operation For fixed-bias operation	1 10 0.47	megohm megohms megohm

# Pulse duration must not exceed 15% of one horizontal scanning cycle (10 microseconds).

† Grid No.2 connected to plate.

†† This value can be measured by a method involving a recurrent waveform such that the maximum ratings of the tube will not be exceeded.

In this service, a positive value may be applied to grid No.3 to minimize "snivets" interference; a typical value for this voltage is 30 volts.


■■ A bias resistor or other means is required to protect the tube in absence of excitation.

Refer to chart at end of section.

37

Refer to chart at end of section.

38



### DIODE—BEAM POWER TUBE 38HE7

Duodecar type used in television receiver applications. The diode unit is used for damper service and the beam power unit for horizontal-deflection amplifier service. Outlines section, 15D; requires duodecar 12-contact socket. Heater: volts (ac/dc), 37.8; amperes, 0.45; warm-up time, 11 seconds; maximum heater-cathode volts, ±200 peak, 100 average.

#### Beam Power Unit As Class A. Amplifier

				Triode**	
CHARACTERISTICS	Pentoc	le Connec	tion	Connection	
Plate Voltage	5000	50	130	130	volts
Grid-No.2 (Screen-Grid) Voltage	130	130	130	130	volts
Grid-No.1 (Control-Grid) Voltage	_	0	22	22	volts
Plate Resistance (Approx.)	_	_	6200	_	ohms
Transconductance			8800	_	$\mu$ mhos
Plate Current		450	60		$\mathbf{m}\mathbf{A}$
Grid-No.2 Current	-	40	2.8	_	mA
Grid-No.1 Voltage (Approx.) for plate	00		20		14
current of 1 mA	80		39		volts
Amplification Factor		_	_	4.2	

** Grid No.2 tied to plate.

#### Beam Power Unit as Horizontal-Deflection Amplifier

For operation in a 525-line, 30-frame system MAXIMUM RATINGS (Design-Maximum Ratings) Plate Voltage
Peak Positive-Pulse Plate Voltage#
Peak Negative-Pulse Plate Voltage
Grid-No.2 Voltage

Negative-pulse Negative-plas value 500 volts ,,...... 5000 volts volts 15Ŏ volts DC Grid-No.1 Voltage, Negative-bias value
Peak Negative-Pulse Grid-No.1 Voltage 55 volts 330 volts 230 mA Average Cathode Current ............ Peak Cathode Current
Plate Dissipation† 800 mA watta 3.5 Grid-No.2 Input watta MAXIMUM CIRCUIT VALUE megohm Grid-No.1-Circuit Resistance

† A bias resistor or other means is required to protect the tube in absence of excitation.


#### Damper Service-Diode Unit

For operation in a 525-line, 30-frame system		
MAXIMUM RATINGS (Design-Maximum Values)		•
Peak Inverse Plate Voltage#	4200	volts
Peak Plate Current	1200	mA
Average Plate Current	200	mA
Heater-Cathode Voltage:		
Peak value	4200	volts
Average value +100	500	volts
Bulb Temperature (at hottest point)	200	°C
CHARACTERISTICS, Instantaneous Value		-
Tube Voltage Drop for plate current of 350 mA	21	volts

# Pulse duration must not exceed 15% of a horizontal scanning cycle (10 microseconds).

DIODE—BEAM POWER TUBE

Duodecar type used in television receiver applications. The diode unit is used for damper service and the beam power unit for horizontal-deflection amplifier service. Outlines section, 15D; requires duodecar 12contact socket. Type 53HK7 is identical with 38HK7 except for heater ratings.



1

megohm

38HK7 53HK7 Heater Voltage (ac/dc) ...... 53.2 volts 0.45 0.315 ampere 11 seconds ±200 max  $\pm 200 \text{ max}$ volt Average value
Direct Interelectrode Capacitances (Approx.): 100 max 100 max volts Diode Unit: 10 Heater to Cathode 2 Beam Power Unit: eam rower onto.

Grid No.1 to Plate

Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3

Plate to Cathode, Heater, Grid No.2, and Grid No.3 0.38 8

#### Beam Power Unit as Class A, Amplifier

	Triode**				
CHARACTERISTICS	Connection	Pen	tode Conr	ection	
Plate Voltage	130	3500	50	130	volts
Grid-No.2 (Screen-Grid) Voltage	130	130	130	130	volts
Grid-No.1 (Control-Grid) Voltage	22		Ŏ	22	volts
Amplification Factor	4.2				******
Plate Resistance			_	6200	ohms
Transconductance		_		8800	µmhos
Plate Current		_	450	60	mA
Grid-No.2 Current	_		40	2.8	mA
Grid-No.1 Voltage (Approx.) for plate current of 1 mA	_	66		39	volts
MAXIMUM CIRCUIT VALUE					
Grid-No.1-Circuit Resistance		. <b></b>		1	megohm

** Grid No.2 tied to plate.

#### Beam Power Unit as Horizontal-Deflection Amplifier For operation in a 525-line, 30-frame system

MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	500	volts
Peak Positive-Pulse Plate Voltage	5000	volts
Peak Negative-Pulse Plate Voltage	0	volts
Grid-No.2 Voltage	150	volts
DC Grid-No.1 Voitage, Negative-bias value	55	volts
Peak Negative-Pulse Grid-No.1 Voltage	330	volts
Average Cathode Current	230	mA
Peak Cathode Current	800	mA
Plate Dissipation†	10	watts
Grid-No.2 Input	3.5	watts

39/44

МΛ	YI	MI	114	CIP	CHIT	VAI	HE

Grid-No.1-Circuit	Resistance	1 megohm
† A bias resistor	or other means is required to protect the tube in	absence of excitation.

For operation in a 525-line,	ov almane by been		
MAXIMUM RATINGS (Design-Maximum Values)			_
Peak Inverse Plate Voltage#		4200	<b>v</b> ol
Peak Plate Current		1200	m
Average Plate Current		200	m.
Heater-Cathode Voltage:			
Peak value	. +200	3700	vol
Average value		500	vol
Bulb Temperature (At hottest point)		200	•
HARACTERISTIC, Instantaneous Value			
Tube Voltage Drop for plate current of 350 mA		16	vol

Refer to chart at end of section.

. 07/ 17	recici to chair at the or become.		
. 40	Refer to chart at end of section.		
. 40KP4	Refer to chart at end of section. For replacement use type 36KD6/40KD6.	F	]
40KG6A/PL5	Refer to type 6KG6A/EL509.		
. 41	Refer to chart at end of section.		
. 42	Refer to chart at end of section.		
. 42EC4A/PY5	Refer to chart at end of section.		
42KN6	Refer to type 6KN6.		
. 43	Refer to chart at end of section.		
. 45	Refer to chart at end of section.		
. <b>45Z3</b>	Refer to chart at end of section.		
. 45Z5GT	Refer to chart at end of section.		
. 46	Refer to chart at end of section.		
. 47	Refer to chart at end of section.		
. 48	Refer to chart at end of section.		
. 49	Refer to chart at end of section.		
. 50	Refer to chart at end of section.		
. 50A5	Refer to chart at end of section.		
. 50B5	Refer to chart at end of section.		
50BM8/UCL	Refer to type 6BM8/ECL82.		


# 50C5

#### **BEAM POWER TUBE**

Miniature type used in output stage of compact, ac/dc radio receivers. Outlines section, 5D; requires miniature 7-contact socket. This tube, like other power-handling tubes, should be adequately ventilated. Within its maximum ratings, type 50C5 is equivalent in performance to glass octal type 50L6GT. Type 25C5 is identical with type 50C5 except for heater ratings.



Heater Voltage (ac/dc)	25C5 25	50C5 50	volts
Heater Current	0.3		
Heater-Cathode Voltage:	0.5	0.15	ampere
			7.
Peak value	$\pm 200 \text{ max}$	±200 max	volts
Average value	100 max	100 max	volts
Direct Interelectrode Capacitances (Approx.):			
Grid No.1 to Plate		0.6	рF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.	.3	13	pF
Plate to Cathode, Heater, Grid No.2, and Grid No.3		8.5	pF
		***	-
Class A ₁ Amplifier			
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage		150	volts
Grid-No.2 (Screen-Grid) Voltage		130	volts
Grid-No.1 (Control-Grid) Voltage, Positive-bias value		100	volts
Plate Dissipation		7	watts
Grid-No.2 Input		1.4	
			watts °C
Bulb Temperature (At hottest point)	• • • • • • • •	220	-0
TYPICAL OPERATION			
Plate Voltage		120	volts
Grid-No.2 Voltage		110	volts
Grid-No.1 (Control-Grid) Voltage			volts
GIIG-MO.1 (COMMON-GIIG) FULLAGE		0	A0103



Peak AF Grid-No.1 Voltage	8	volts
Zero-Signal Plate Current	49	mA.
Maximum-Signal Plate Current	50	mA
Zero-Signal Grid-No.2 Current	4	mA.
Maximum-Signal Grid-No.2 Current	8.5	mA.
Plate Resistance (Approx.)	10000	o <b>hms</b>
Transconductance	7500	$\mu$ mhos
Load Resistance	2500	ohms
Total Harmonic Distortion	10	per cent
Maximum-Signal Power Output	2.3	watts
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.1	megohm
For cathode-bias operation	0.5	megohm


#### Installation and Application

The 50-volt heater is designed to operate under the normal conditions of line voltage variation without materially affecting the performance or serviceability of the 50C5. For operation of the 50C5 in series with other types having 0.15-ampere rating, the current in the heater circuit should be adjusted to 0.15 ampere for the normal supply voltage.

In a series-heater circuit of the "dc power line" type employing several 0.15-ampere types and one or two 50C5s, the heater(s) of the 50C5(s) should be placed on the positive side of the line. Under these conditions, heater-cathode voltage of the 50C5 must not exceed the value given under maximum ratings. In a series-heater circuit of the "universal" type employing rectifier tube 35W4, one or two 50C5s, and several 0.15-ampere types, it is recommended that the heater(s) of the 50C5(s) be placed in the circuit so that the higher values of heater-cathode bias will be impressed on the 50C5(s) rather than on the other 0.15-ampere types. This is accomplished by arranging the 50C5(s) on the side of the supply line which is connected to the cathode of the rectifier, i.e., the positive terminal of the rectified voltage supply. Between this side of the line and the 50C5(s), any necessary auxiliary resistance and the heater of the 35W4 are connected in series.

As a power amplifier (class  $A_1$ ), the 50C5 is recommended for use either singly or in push-pull combination in the power-output stage of "ac/dc" receivers. The operating values shown under typical operation have been determined on the basis that grid-No. 1 current does not flow during any part of the input cycle.

Refer to chart at end of section.	50C6G
Refer to chart at end of section.	50DC4
Refer to type 6EH5.	50EH5
Refer to chart at end of section.	50FE5
Refer to chart at end of section.	50FK5
Refer to type 33GY7A.	50GY7A
Refer to chart at end of section	50HCA



#### POWER PENTODE

50HK6

Miniature type used in audio-frequency power-output stage of radio receivers. Outlines section, 5D; requires miniature 7-contact socket. The heater is provided with a tap for operation of a panel lamp. Heater: volts (ac/dc), 50; amperes, 0.15; tap volts (without panel lamp), 7; maximum heater-cathode volts, ±200 peak, 100 average.

#### Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage Grid-No.2 (Screen-Grid) Voltage	150 130	volts volts
Plate Dissipation Grid-No.2 Input	5.5 1.1	watts watts
RMS Heater-Tap Voltage When Panel Lamp Fails	14	volts

TYPICAL OPERATION AND CHARACTERISTICS		
Plate Voltage	110	volts
Grid-No.2 Voltage	110	volts
Grid-No.1 (Control-Grid) Voltage	-7.5	volts
Peak AF Grid-No.1 Voltage	7.5	volts
Zero-Signal Plate Current	49	mA
Maximum-Signal Plate Current	50	m A
Zero-Signal Grid-No.2 Current	4	mA
Maximum-Signal Grid-No.2 Current	8.5	mA
Plate Resistance (Approx.)	10000	oh <b>m</b> s
Transconductance	7500	$\mu$ mhos
Load Resistance	2500	ohms
Total Harmoric Distortion (Approx.)	9	per cent
Maximum-Signal Power Output	1.9	watts
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.1	megohm
For cathode-bias operation	0.5	megohm

50JY6

Refer to chart at end of section.

## 50L6GT

25L6GT

#### **BEAM POWER TUBE**

Glass octal type used in output stage of ac/dc radio receivers. Outlines section, 13D; requires octal socket. This type may be supplied with pin No.1 omitted. Refer to miniature type 50C5 for installation and application information. Type 25L6GT is identical with type 50L6GT except for heater ratings.

MAXIMUM RATINGS (Design-Center Values)



7AC

	25L6GT	50 L 6 G T	
Heater Voltage (ac/dc)	25	50	volts
Heater Current	0.3	0.15	ampere
Peak Heater-Cathode Voltage	$\pm 90 \text{ max}$	$\pm 90$ max	voits
Direct Interelectrode Capacitances (Approx.):			
Grid No.1 to Plate		0.6	pF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.		15	рF
Plate to Cathode, Heater, Grid No.2, and Grid No.3		9.5	рF

#### Class A. Amplifier

Plate Voitage		200	volts
Grid-No.2 (Screen-Grid) Voltage		125	volts
Plate Dissipation		10	watts
Grid-No.2 Input		1.25	watts
TYPICAL OPERATION	Fixed Bias	Cathode Bias	
Plate Supply Voltage	110	200	volts
Grid-No.2 Supply Voltage	110	125	volts
Grid-No.1 (Control-Grid) Voltage	-7.5		volts
Peak AF Grid-No.1 Voltage	7.5	8.0	volts
Cathode-Bias Resistor	_	180	ohms
Zero-Signal Plate Current	49	46	mA
Maximum-Signal Plate Current	50	47	mA
Zero-Signal Grid-No.2 Current	4	2.2	mA
Maximum-Signal Grid-No.2 Current	10	8.5	mA
Plate Resistance (Approx.)	13000	28000	ohms
Transconductance	3000	8000	$\mu$ mhos
Load Resistance	2000	4000	oh ms
Total Harmonic Distortion	10	10	per cent
Maximum-Signal Power Output	2.1	3.8	watts

50X6

Refer to chart at end of section.

**50Y6GT** 

Refer to chart at end of section.

Refer to chart at end of section.	50Y7GT
Refer to chart at end of section.	50Z7G
Refer to chart at end of section.	53
Refer to type 38HK7.	53HK7
Refer to type 12FX5.	60FX5
Refer to chart at end of section.	70L7GT
Refer to chart at end of section.	75
Refer to chart at end of section.	78
Refer to chart at end of section.	80
Refer to chart at end of section.	83
Refer to chart at end of section.	84/6 <b>Z</b> 4
Refer to chart at end of section.	117L7GT/M7GT
Refer to chart at end of section.	117N7GT
Refer to chart at end of section.	117P7GT
Refer to chart at end of section.	117 <b>Z</b> 3
Refer to chart at end of section.	117 <b>Z4</b> GT
Refer to chart at end of section.	117Z6GT
Refer to chart at end of section.	407A
Refer to chart at end of section.	408A
Refer to chart at end of section.	884
Refer to chart at end of section.	955
Refer to chart at end of section.	959
Refer to chart at end of section.	991
Refer to chart at end of section.	1612
Refer to chart at end of section.	1614
Refer to chart at end of section.	1619
Refer to chart at end of section.	1620
Refer to chart at end of section.	1621
Refer to chart at end of section.	1622
Refer to chart at end of section.	1629
Refer to chart at end of section.	1635

2050

#### **GAS THYRATRON**

Glass octal type gas tetrode thyratron for use in relay and grid-controlled-rectifier service. Outlines section, 22; requires octal socket. For maximum ratings and typical operating conditions refer to type 2050A.



e	•	•
0	0	э

Heater Voltage (ac/dc)		6.3 0.60	Max. 6.9 0.66	volts ampere
Heating Time, prior to tube conduction  Direct Interelectrode Capictances (Approx.):	10	_	-	sec
Grid No. 1 to Anode Input Output			0.26 4.2 3.6	pF pF pF

# 2050A

### GAS THYRATRON

Glass octal type gas tetrode thyratron for use in relay and grid-controlled-rectifier service. Outlines section, 13C; requires octal socket.



#### 6BS

Heater Voltage (ac/dc) Heater Current	$^{6.3\ \pm 10\%}_{0.6}$	volts ampere
Peak Heater-Cathode Voltage:	0.0	ampere
Heater negative with respect to cathode Heater positive with respect to cathode	100 max 25 max	volts volts
Cathode:		
Minimum heating time prior to tube conduction  Direct Interelectrode Capacitances (Approx.):	10	seconds
Grid No. 1 to anode	0.15	рF
Grid No. 1 to cathode and grid No. 2	2.2	pF
Ionization Time (Approx.):		-
For dc anode volts = 100, grid-No. 1 volts (square-wave pulse)		
= 50, peak anode amperes during conduction = 1	0.5	μз
Deionization Time (Approx.):		•
With dc anode volts = $125$ , grid-No. 1 volts = $-250$ , grid-No. 1		
resistor (ohms) = $1000$ , dc anode amperes = $0.1$	50	μз
With dc anode volts = 125, grid-No. 1 volts = $-10$ , grid-No. 1		-
resistor (ohms) = 1000, dc anode amperes = 0.1	100	μs
Maximum Critical Grid-No. 1 Current for dc anode supply volts		
$(rms) = 460$ , average anode amperes $= 0.1 \dots$	0.5	$\mu \mathbf{A}$
Anode Voltage Drop (Approx.)	8	volts
Grid-No. 1 Control Ratio (Approx.) for grid-No. 1 resistor (ohms)		
= 0, grid No. 2 connected to cathode at socket	250	
Grid-No. 2 Control Ratio (Approx.) for grid-No. 1 resistor (ohms)		
= 0, grid-No. 2 resistor (ohms) = 0, grid No. 1 connected to		
cathode at socket	800	

## Relay and Grid-Controlled Rectifier Service For anode supply frequency of 60 Hz

#### MAXIMUM RATINGS (Absolute-Maximum Values)

Peak Anode Voltage:			
Forward	180	650	volts
Inverse	360	1300	volts
Grid-No. 2 (Shield-Grid) Voltage:			
Peak, before tube conduction	100	-100	volts
Average*, during tube conduction	10	10	volts
Grid-No, 1 (Control-Grid) Voltage:			
Peak, before tube conduction	250	250	volts
Average*, during tube conduction	—10	-10	volts
Cathode Current:			
Peak	1	1	ampere
Average*	0.2	0.1	ampere
Fault, for duration of 0.1 second maximum	10	10	amperes

Grid-No. 2 Current:

Average*	+0.01	+0.01	ampere
Grid-No. 1 Current:     Average*	+0.01	+0.01	ampere
Ambient-Temperature Range	-75  to  +90	-75  to  +90	°c
TYPICAL OPERATION FOR RELAY SERVICE			
RMS Anode Voltage	117	400	
Grid No. 2	Con	nected to catho	de at socket
RMS Grid-No. 1 Bias Voltage⁴	5	_	volts
DC Grid-No. 1 Voltage		6 6	volts
Peak Grid-No. 1 Signal Voltage	5	6	volts
Grid-No. 1 Circuit Resistance	1	1	megohm
Anode-Circuit Resistance†	1200	2000	ohms
MAXIMUM CIRCUIT VALUES			
Grid-No. 1-Circuit Resistance:			
For average anode current below 0.1 ampere		10	megohms
For average anode current above 0.1 ampere			megohms
* Averaged over any interval of 30 seconds maximum.			


Approximately 180° out of phase with the anode voltage.

† Sufficient resistance, including the tube load, must be used under any conditions of operation to prevent exceeding the current ratings.

#### **Operating Considerations**

The heater is designed to operate on either ac or dc at 6.3 volts. Regardless of the heater-voltage supply used the heater voltage must never be allowed to deviate from its rated range. Heater operation outside of this voltage range will impair tube performance and may cause tube failure. Low heater voltage causes low cathode temperature with resultant cathode sputtering and consequent destruction of the cathode; high heater voltage causes high cathode temperature with resultant heating of the grid and consequent grid emission which produces unpredictable shifts in the critical grid-No. 1 voltage for conduction.

The cathode should be allowed to reach normal operating temperature before anode current is drawn. The delay period should not be less than 10 seconds after application of heater voltage. Unless this recommendation is followed, the cathode will be damaged.



The shield grid (grid No. 2) is normally connected to the cathode at socket. It may, however, be used as a control electrode because the control characteristic of grid No. 1 may be shifted by varying the potential of grid

No. 2. As grid No. 2 is made negative, the grid-No. 1 characteristic is shifted in the positive direction. The use of grid No. 2 as the control electrode (with grid No. 1 connected to cathode at socket) has the advantage of increased sensitivity but consideration must be given to the higher preconduction current, higher capacitance to anode, and less stability of operation.

A grid-No. 1 resistor having a value as high as 10 megohms to give circuit sensitivity can be used with the 2050-A because its control-grid current is very low. However, when a high value of grid resistor is used, care should be taken to keep the tube base and socket clean and dry in order to make the effect of leakage currents between the control-grid base pin and anode base pin very small.

Sufficient anode-circuit resistance, including the tube load, must be used under any conditions of operation to prevent exceeding the current ratings

of the tube.

2076/5R4GB	Refer to chart at end of section.			
2076/5R4GYB	For replacement use type 2076/5R4GB.			
2081/6AW8A	Refer to chart at end of section.			
2082/12AY7	Refer to chart at end of section.			
5636	Refer to chart at end of section.			
5639	Refer to chart at end of section.			
5642	Refer to chart at end of section.			

### **VOLTAGE-REFERENCE TUBE**

Miniature type cold-cathode, glow-discharge voltagereference tube for use in dc power supplies. Outlines section, 5C; requires miniature 7-contact socket.

MAXIMUM RATINGS (Absolute-Maximum Values)



#### 5B0

DC Operating Current (Continuous) DC Operating Current (Continuous) Ambient Temperature Range			3.5 1.5 55 to 90	mA mA °C
CHARACTERISTICS AND OPERATION RANGE VALUES	•			
	Min.	Av.	Max.	
DC Starting Voltage		107	115*	volts
At 1.5 mA	83	85	87	volts
At 2.5 mA	83.5	85.5	87.5	volts
At 3,5 mA	84.5	86.5	88.5	volts
Regulation (1.5 mA to 3.5 mA)		_	3	volts
Temperature coefficient of Operating Voltage (over				
ambient temperature range of -55 to 90°C)		4	_	mV/°C
Percentage Variation of Operating Voltage:				
During first 300 hours of life		-	0.1	per cent
During subsequent 1000 hours of life		_	0.1	per cent
Short-term (100 hours)				
Variation of Operating Voltage after first 300				
hours of life	_	_	0.05	per cent
Instantaneous Voltage				_
Fluctuation (Voltage jump);	_		0.1	volt
CIRCUIT VALUES				
Shunt Capacitor Series Resistor		_ <u>_</u>	0.02	$\mu {f F}$

- * A de supply voltage of 115 volts minimum should be provided to insure "starting" throughout tube life.
- DC operating current = 2.5 mA.
- After initial 3-minute warm-up period.
- † Defined as the maximum instantaneous voltage fluctuation at any current level within the operating current range.
- ‡ A series resistor must always be used with the 5651A. The resistance value must be chosen so that (1) the maximum current rating of 3.5 mA is not exceeded at the highest anodesupply voltage employed, and (2) the minimum current rating of 1.5 mA is always exceeded when the anode-supply voltage is at its lowest value.

#### Installation and Application

Make no connection to pins 3 and 6. Any potentials applied to these pins may cause erratic tube performance. The three pin terminals for the cathode (pins 2, 4, and 7) and the two for the anode (pins 1 and 5) offer the equipment designer several different possibilities for connection of the 5651A. Any pair of interconnected pins can be used as a jumper connection to a circuit common to either the cathode or to the anode. The use of such a jumper connection provides a means for opening the circuit to protect circuit components when the 5651A is removed from its socket. Under no circumstances should the current through any pair of interconnected pins exceed one ampere.

If the load for the regulated power supply is disconnected either directly or by removing the 5651A from its socket, the rectifier capacitors will charge to the rectifier peak voltage. It is important, therefore, that these capacitors be rated to withstand such voltage.

A warm-up period of 3 minutes should be allowed each time the equipment is turned on to insure minimum voltage drift of the 5651A.

When a shunt capacitor is used with the 5651A, its value should be limited to 0.02  $\mu$ F. A large value of capacitance may cause the tube to oscillate and thus give unstable performance.

Shielding should be utilized for the 5651A to insure maximum stability when the tube is operated in the presence of strong rf or magnetic fields.

Refer to chart at end of section.

5651WA



#### SHARP-CUTOFF PENTODE

5654

INDUSTRIAL TYPE

Miniature type sharp-cutoff pentode used in RF and IF broad-band applications at frequencies up to 400 mHz. Outlines section, 5B; requires miniature 7-contact socket.

7BD

Heater Voltage (ac/dc) Heater Current	$^{6.3}_{0.175}^{\pm 10\%}$	volts ampere
Heater-Cathode Voltage: Peak value Direct Interelectrode Capacitances:	±100	volts
Grid No.1 to Plate Input	0.020 max. 4.0	pF pF
Output	2.85	pF

#### Class A₁ Amplifier

MAXIMUM RATINGS (Absolute-Maximum Values)		
Plate Voltage	200	volts
Grid-No.2 (Screen) Voltage	155	volts

Grid-No.2 Input	1.85 0.55 20	watts watt mA
TYPICAL OPERATION AND CHAR	ACTERISTICS	
Plate Voltage Grid-No.2 Voltage Cathode-Bias Resistor Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage (Approx.) for	120 120 180 180 0.30 0.50 5000 5100 7.5 7.7 2.5 2.4	volts volts ohms megohm μmhos mA volts
MAXIMUM CIRCUIT VALUE		
Grid-No.1-Circuit Resistance	0.5	megohm
Special	Ratings & Performance Data	
SHOCK RATING Impact Acceleration	500 max	. g
FATIGUE RATING		
Vibrational Acceleration	2.5 max	. g
HEATER CYCLING LIFE PERFOR	MANCE 2000 min.	cycles
oyeles of anterimeters operation	2000 Hills	Cycles
5654W	Refer to chart at end of section.	
5654/6AK5W/ 6096	Refer to chart at end of section.	
5663	Refer to chart at end of section.	
5670	Refer to chart at end of section.	
5670WA	Refer to chart at end of section.	
5672	Refer to chart at end of section.	
, 5678	Refer to chart at end of section.	
5686	Refer to chart at end of section.	
5687	Refer to chart at end of section.	
5691	Refer to chart at end of section.	
5692	Refer to chart at end of section.	
F / O O	TO 6 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	

INDUSTRIAL TYPE

5693

#### **THYRATRON**

Refer to chart at end of section.

Miniature type gas-tetrode thyratron for use in counter-circuit relay applications. Outlines section, 5B; requires miniature 7-contact socket.

"30"
k@\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\
c ₁
7RN


HA (502

Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage:	6.3 0.150
Peak	! 25 100

volts ampere

volts

Cathode:		
Minimum Heating Time, prior to tube conduction  Direct Interelectrode Capacitances (Approx.):	10	seconds
Grid No.1 to Anode	0.03	ъF
Input	1.8	ρF
Output	0.54	ρF
Ionization Time (Approx.):	V.U.2	-
For conditions: dc anode volts = 100; grid-No.1 square-pulse volts = +50; peak cathode amperes during conduction = 0.150	0.5	
Deionization Time (Approx.):	0.5	μs
For conditions: dc anode volts = 500; grid-No.1 volts = -100, grid-No.1 resistor (ohms) = 1000; dc cathode amperes	0.5	
= $0.025$ For conditions: dc anode volts = $500$ ; grid-No.1 volts = $-13$ ;	25	μs
grid-No.1 resistor (ohms) = 1000; dc cathode amperes		
= 0.025 (onms) = 1000; ac cathode amperes	40	
Maximum Critical Grid-No.1 Current, with ac anode-supply volts	40	μs
(rms) = 350, and average cathode amperes = 0.025	0.5	μA
Anode Voltage Drop (Approx.)	10	volts
Grid-No.1 Control Ratio (Approx.) with grid-No.1 resistor (meg-	••	******
ohms = 0; $grid-No.2$ $volts = 0$	250	
Grid-No.2 Control Ratio (Approx.) with grid-No.1 volts = 0, grid-		
Mt - O ( - N ) O		
No.2 resistor (ohms) = 0	15	
Relay and Grid-Controlled Rectifier Service	==	
	==	
Relay and Grid-Controlled Rectifier Servi	==	
Relay and Grid-Controlled Rectifier Servi MAXIMUM RATINGS (Absolute-Maximum Values) Peak Anode Voltage:	ice	volte
Relay and Grid-Controlled Rectifier Servi MAXIMUM RATINGS (Absolute-Maximum Values) Peak Anode Voltage: Forward	500	volts
Relay and Grid-Controlled Rectifier Servi MAXIMUM RATINGS (Absolute-Maximum Values) Peak Anode Voltage:	ice	volts volts
Relay and Grid-Controlled Rectifier Servi MAXIMUM RATINGS (Absolute-Maximum Values)  Peak Anode Voltage: Forward Inverse Grid-No.2 (Shield-Grid) Voltage: Peak, before anode conduction	500	
Relay and Grid-Controlled Rectifier Servi MAXIMUM RATINGS (Absolute-Maximum Values)  Peak Anode Voltage: Forward Inverse Grid-No.2 (Shield-Grid) Voltage: Peak, before anode conduction Average, during anode conduction	500 500	volts
Relay and Grid-Controlled Rectifier Servi MAXIMUM RATINGS (Absolute-Maximum Values)  Peak Anode Voltage: Forward Inverse Grid-No.2 (Shield-Grid) Voltage: Peak, before anode conduction Average, during anode conduction Grid-No.1 (Control-Grid) Voltage:	500 500 —50	volts volts
Relay and Grid-Controlled Rectifier Servi  MAXIMUM RATINGS (Absolute-Maximum Values)  Peak Anode Voltage:     Forward     Inverse Grid-No.2 (Shield-Grid) Voltage:     Peak, before anode conduction     Average, during anode conduction= Grid-No.1 (Control-Grid) Voltage:     Peak, before anode conduction	500 500 50 10	volts volts
Relay and Grid-Controlled Rectifier Servi MAXIMUM RATINGS (Absolute-Maximum Values)  Peak Anode Voltage: Forward Inverse Grid-No.2 (Shield-Grid) Voltage: Peak, before anode conduction Average, during anode conduction Grid-No.1 (Control-Grid) Voltage: Peak, before anode conduction Average, during anode conduction Average, during anode conduction	500 500 —50 —10	volts volts volts
Relay and Grid-Controlled Rectifier Servi  MAXIMUM RATINGS (Absolute-Maximum Values)  Peak Anode Voltage:     Forward     Inverse Grid-No.2 (Shield-Grid) Voltage:     Peak, before anode conduction     Average, during anode conduction Grid-No.1 (Control-Grid) Voltage:     Peak, before anode conduction Average, during anode conduction Average, during anode conduction Cathode Current:	500 500 50 10 100	volts volts volts volts volts
Relay and Grid-Controlled Rectifier Servi  MAXIMUM RATINGS (Absolute-Maximum Values)  Peak Anode Voltage:     Forward     Inverse Grid-No.2 (Shield-Grid) Voltage:     Peak, before anode conduction     Average, during anode conduction Grid-No.1 (Control-Grid) Voltage:     Peak, before anode conduction Average, during anode conduction Cathode Current:     Peak	500 500 50 10 100 10	volts volts volts volts volts
Relay and Grid-Controlled Rectifier Servi  MAXIMUM RATINGS (Absolute-Maximum Values)  Peak Anode Voltage: Forward Inverse Grid-No.2 (Shield-Grid) Voltage: Peak, before anode conduction Average, during anode conduction Grid-No.1 (Control-Grid) Voltage: Peak, before anode conduction Average, during anode conduction Average, during anode conduction  Cathode Current: Peak Average	500 500 -50 -10 -100 -10 100 25	volts volts volts volts volts volts mA mA
Relay and Grid-Controlled Rectifier Servi  MAXIMUM RATINGS (Absolute-Maximum Values)  Peak Anode Voltage:     Forward     Inverse Grid-No.2 (Shield-Grid) Voltage:     Peak, before anode conduction     Average, during anode conduction Grid-No.1 (Control-Grid) Voltage:     Peak, before anode conduction Average, during anode conduction Average, during anode conduction  Cathode Current:     Peak     Average Surge, for duration of 0.1 sec. max.	500 500 50 10 100 10	volts volts volts volts volts
Relay and Grid-Controlled Rectifier Servi MAXIMUM RATINGS (Absolute-Maximum Values)  Peak Anode Voltage: Forward Inverse Grid-No.2 (Shield-Grid) Voltage: Peak, before anode conduction Average, during anode conduction Grid-No.1 (Control-Grid) Voltage: Peak, before anode conduction Average, during anode conduction Cathode Current: Peak Average Surge, for duration of 0.1 sec. max. Grid-No.2 Current:	500 500 -50 -10 -100 -10 100 25 2	volts volts volts volts volts mA mA amperes
Relay and Grid-Controlled Rectifier Servi  MAXIMUM RATINGS (Absolute-Maximum Values)  Peak Anode Voltage: Forward Inverse Grid-No.2 (Shield-Grid) Voltage: Peak, before anode conduction Average, during anode conduction Grid-No.1 (Control-Grid) Voltage: Peak, before anode conduction Average, during anode conduction Cathode Current: Peak Average Surge, for duration of 0.1 sec. max.  Grid-No.2 Current: Average*	500 500 -50 -10 -100 -10 100 25	volts volts volts volts volts volts mA mA
Relay and Grid-Controlled Rectifier Servi  MAXIMUM RATINGS (Absolute-Maximum Values)  Peak Anode Voltage:     Forward     Inverse     Grid-No.2 (Shield-Grid) Voltage:     Peak, before anode conduction     Average, during anode conduction Grid-No.1 (Control-Grid) Voltage:     Peak, before anode conduction Average, during anode conduction Cathode Current:     Peak     Average     Surge, for duration of 0.1 sec. max.  Grid-No.2 Current:     Average Grid-No.2 Current:     Average Grid-No.1 Current:	500 500 -50 -10 -100 -10 100 25 2	volts volts volts volts volts volts amA mA amperes mA
Relay and Grid-Controlled Rectifier Servi  MAXIMUM RATINGS (Absolute-Maximum Values)  Peak Anode Voltage:     Forward     Inverse     Grid-No.2 (Shield-Grid) Voltage:     Peak, before anode conduction     Average, during anode conduction Grid-No.1 (Control-Grid) Voltage:     Peak, before anode conduction Average, during anode conduction Cathode Current:     Peak     Average     Surge, for duration of 0.1 sec. max.  Grid-No.2 Current:     Average Grid-No.2 Current:     Average Grid-No.1 Current:	500 500 50 10 100 10 100 25 2	volts volts volts volts volts mA mA amperes



#### TYPICAL OPERATING CONDITIONS FOR RELAY SERVICE

RMS Anode Voltage Grid No.2 ( RMS Grid-No.1 Bias Voltage Peak Grid-No.1 Signal Voltage Grid-No.1-Circuit Resistance Anode-Circuit Resistance	Connected	to cathode 5 5	
MAXIMUM CIRCUIT VALUE			
Grid-No.1-Circuit Resistance		10	megohms

Averaged over any interval of 30 sec. max.

Approximately 180° out of phase with the anode voltage.


*Sufficient resistance, including the tube load, must be used under any conditions of operation to prevent exceeding the current ratings.

5696A	Refer to chart at end of section.
5718	Refer to chart at end of section.
5719	Refer to chart at end of section.
5725	Refer to chart at end of section.
5725/6AS6W	Refer to chart at end of section.
5726	Refer to chart at end of section.
5726/6AL5W	Refer to chart at end of section.
5726/6AL5W/ 6097	Refer to chart at end of section.

INDUSTRIAL TYPE

## **GAS THYRATRON**

Miniature type "Premium" gas-tetrode thyratron for use in relay, grid-controlled rectifier and pulse-modulator applications. Outlines section, 5C; requires miniature 7-contact socket.



#### **7BN**

Heater Voltage (ac/dc)	$6.3 \pm 10\%$	volts
Heater Current	0.6	ampere
Cathode:  Minimum heating time prior to tube conduction  Direct Interelectrode Capacitances (Approx.):	20	seconds
Grid No.1 to anode	0.026	pF
Grid No.1 to cathode, grid No.2, and heater	2.4	pF
Anode to cathode, grid No.2, and heater	1.6	pF
	1.0	pr
Ionization Time (Approx.):		
For dc anode volts = 100, grid-No.1 volts (square-wave pulse)	0.5	
= 50, peak anode amperes during conduction = 0.5	0.0	μs
Deionization Time (Approx.):		
For dc anode volts = 125, dc anode amperes = 0.1, grid-No.1		
resistor (ohms) = 1000, and grid-No.1 volts = -100	35	μs
For dc anode volts = 125, dc anode amperes = 0.1, grid-No.1		
resistor (ohms) = 1000, and grid-No.1 volts = $-100$	75	μв
Maximum Critical Grid-No.1 Current:		
For anode-supply volts (rms) = 460, and average anode amperes		
= 0.1	0.5	μA
Anode Voltage Drop (Approx.)	8	volts
Grid-No.1 Control Ratio (Approx.) with grid-No.1 resistor (meg-		
ohms) = 0, grid-No.2 volts = 0	250	
Grid-No.2 Control Ratio (Approx.) with grid-No.1 resistor (meg-	200	
Grid-No.2 Control Ratio (Approx.) with grid-No.1 resistor (meg-		
ohms) = 0, grid-No.2 resistor (megohms) = 0, grid-No.1 volts	1000	
= 0	1000	

### Relay and Grid-Controlled Rectifier Service

#### MAXIMUM RATINGS (Absolute-Maximum Values)

For anode-supply frequency of 60 Hz

You anode-supply frequency of ov 112		
Peak Anode Voltage: Forward	650	volts
Inverse Grid-No.2 (Shield-Grid) Voltage:	1300	volts
Peak, before tube conduction  Averages, during tube conduction	100 10	volts
Grid-No.1 (Control-Grid) Voltage:		volts
Peak, before tube conduction	—100 —10	volts volts
Cathode Current: Peak	0.5	ampere
Average	0.1	ampere
Fault, for duration of 0.1 second max	10	amperes
Average Grid-No.1 Current:	10	mA
Average Heater-Cathode Voltage:	10	mA
Peak		volts
Bulb Temperature (At hottest point on bulb surface) Ambient Temperature	150 75	°C
TYPICAL OPERATION FOR RELAY SERVICE		
RMS Anode Voltage 117	400	volts
Grid-No.2 Voltage	0	volts
RMS Grid-No.1 Bias Voltage 5 DC Grid-No.1 Bias Voltage	6	volts volts
Peak Grid-No.1 Signal Voltage 5	6	volts
Grid-No.1-Circuit Resistance	1	megohm
Anode-Circuit Resistance# 1200	2000	ohms
MAXIMUM CIRCUIT VALUE		
Grid-No.1-Circuit Resistance	10	megohms

#### Pulse-Modulated Service

For rectangular-wave shapes, duty cycle of 0.001 max., pulse duration of 5  $\mu s$  max., and pulse-repetition rate of 500 pps max.

#### MAXIMUM RATINGS (Absolute-Maximum Values)

Peak Anode Voltage:		
Forward	500	volts
Inverse	100	volts
Grid-No.2 (Shield-Grid) Voltage:		
Peak, before tube conduction	50	volts
Average, during tube conduction	10	volts
Grid-No.1 (Control-Grid) Voltage:	• •	
Peak, before tube conduction	-100	volts
Average, during tube conduction	<u>_10</u>	volts
Cathode Current:	10	¥0163
Peak	10	amperes
	10	m A
Average	10	
Rate of change	100	A/μs
Peak Grid-No.2 Current	20	A/μs mA
Peak Grid-No.2 Current	20	mA
Peak Grid-No.2 Current Peak Grid-No.1 Current Heater-Cathode Voltage:	20	mA
Peak Grid-No.2 Current Peak Grid-No.1 Current Heater-Cathode Voltage: Peak	20 20 ±0	mA mA volt
Peak Grid-No.2 Current Peak Grid-No.1 Current Heater-Cathode Voltage: Peak Bulb Temperature (At hottest point on bulb surface)	20 20 ±0 150	mA mA volt
Peak Grid-No.2 Current Peak Grid-No.1 Current Heater-Cathode Voltage: Peak	20 20 ±0	mA mA volt

#### MAXIMUM CIRCUIT VALUES

Grid-No.1-Circuit	Resistance	 0.5	megohm
Grid-No.2-Circuit	Resistance	 {25000 max. } 2000 min.	ohms ohms

^{*} For pulse-modulator service, tolerance is +10%, -5%.

Averaged over any interval of 30 seconds maximum.

Approximately 180° out of phase with the anode voltage.

* Sufficient resistance, including the tube load, must be used under any conditions of operation to prevent exceeding the current ratings.

## **Special Ratings and Performance Data**

SHOCK RATING		•
Impact Acceleration	750 max.	g
FATIGUE RATING		
Vibrational Acceleration	2.5 max.	g
HEATER-CYCLING LIFE PERFORMANCE		
Cycles of Intermittent Operation	2000 min.	cycles

## Operating Considerations

Sufficient anode-circuit resistance, including the tube load, must be used under any conditions of operation to prevent exceeding the current ratings of the tube.

Curve shown under type 2D21 also applies to type 5727

5734	Refer to chart at end of section.
5749	Refer to chart at end of section.
5749/6BA6W	Refer to chart at end of section.
5750	Refer to chart at end of section.

# 5/5 I

Heater Arrangement:


SHOCK RATING

Impact Acceleration .....

## HIGH-MU TWIN TRIODE

Series


Miniature type "Premium" high-mu twin triode used as a phase inverter and as a high gain amplifier in industrial control devices. Outlines section, 6B; requires miniature 9-contact socket.



600 max.

Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage:	$\begin{array}{c} 12.6 \pm 10\% \\ 0.175 \end{array}$	$^{6.3}_{0.350} \pm 10\%$	volts ampere
Peak		±100 max.	volts
Class A, Amplifier (	Each Unit)		
MAXIMUM RATINGS (Design-Maximum Values)			
Plate VoltageGrid Voltage:		330	volts
Negative-bias value		55	volts
Positive-bias value		0	volt
Plate Dissipation Bulb Temperature (At hottest point on bulb surface)	· · · · · · · · · · · · · · · · · · ·	0.8 165	watt *C
		100	Ü
CHARACTERISTICS			
Plate Voltage	100	250	volts
Grid Voltage		3	volts
Amplification Factor		70	
Plate Resistance		58000	ohms
Transconductance	1200	1200	$\mu$ mhos
Plate Current	0.9	1.0	mA
Special Ratings & Perf	ormance Data		

FATIGUE RATING		
Vibrational Acceleration	2.5 max.	g
LOW-FREQUENCY VIBRATION PERFORMANCE		4
RMS Output Voltage	100 max.	mV
HEATER-CYCLING LIFE PERFORMANCE		
Cycles of Intermittent Operation	2000 min.	cycles



Refer to chart at end of section.

5751WA



## VHF BEAM POWER TUBE

**つ/0**5 NDUSTRIAL TYPE

Miniature type VHF beam power amplifier for use in low-power mobile transmitters and the low-power stages of larger fixed station transmitters. Outlines section, 6E; requires miniature 9-contact socket.


Heater Voltage (ac/dc) Heater Current		volts ampere
Heater-Cathode Voltage: Peak Transconductance for plate current of 45 mA	$\pm 100 \text{ max.} $	volts μmhos
Mu-Factor, Grid No.2 to Grid No.1  Direct Interelectrode Capacitances:	16	
Grid No.1 to Plate Input Output	0.3 max 9.5 4.5	pF pF pF

## Plate-Modulated RF Power Amplifier—Class C Telephony

Carrier conditions per tube for use with a max. modulation factor of 1.0

	CCS•	ICAS●●	
MAXIMUM RATINGS (Absolute-Maximum Values)			
DC Plate Voltage	250	300	volts
DC Grid-No.3 (Suppressor) Voltage	0	0	volts
DC Grid-No.2 (Screen) Voltage	250	250	volts
DC Grid-No.1 (Control-Grid) Voltage	125	125	volts
DC Plate Current	40	50	mA
DC Grid-No.2 Current	15	15	mA
DC Grid-No.1 Current	5	5	mA
Plate Input	10	15	watts
Grid-No.2 Input	1.5	1.5	watts
Plate Dissipaton	8	12	watts
Bulb Temperature (At hottest point on bulb surface)	250	250	•c

2001 2020			
TYPICAL OPERATION UP TO 30 MHz			
DC Plate Voltage	250	300	nt nankåt
Grid No.3	250	l to cathode 250	e at socket volts
DC Grid-No.2 Voltage‡ DC Grid-No.1 Voltage*	—39 -	-42.5	volts
From a grid resistor of		18000	ohms
Peak RF Grid-No.1 Voltage	46.5	53.5	volts
DC Plate Current DC Grid-No.2 Current	40 5.6	50 6	mA mA
DC Grid-No.1 Current (Approx.)	1	2.4	mA
Driving Power (Approx.)	0.05	0.15	watt
Useful Power Output (Approx.)	6.4■	10■	watts
MAXIMUM CIRCUIT VALUE			
Grid-No.1-Circuit Resistance	0.1	0.1	megohm
RF Power Amplifier & Oscillator—Class and RF Power Amplifier—Class C FM 1	•	phy ^o	
	eichiinii		
MAXIMUM RATINGS (Absolute-Maximum Values)			
		CAS.	
DC Plate Voltage	300	350	volts
DC Grid-No.3 (Suppressor) Voltage DC Grid-No.2 (Screen) Voltage	0 250	0 250	volts
DC Grid-No.1 (Control-Grid) Voltage		—125	volts volts
DC Plate Current	50	50	mA
DC Grid-No.2 Current	15	15	mA
DC Grid-No.1 Current	5	.5	mA
Plate Input Grid-No.2 Input	15 2	17 2	watts watts
Plate Dissipation	12	13.5	watts
Bulb Temperature (At hottest point on bulb surface)	250	250	""°C
TYPICAL OPERATION UP TO 30 MHz			
DC Plate Voltage	300	350	volts
Grid No.3		to cathode	
DC Grid-No.2 Voltage	250	250 -28.5	volts volts
DC Grid-No.1 Voltage [®] From a grid resistor of		-28.8 .8000	ohms
Peak RF Grid-No.1 Voltage	37.5	37	volts
DC Plate Current	50	48.5	mA
DC Grid-No.2 Current	6.6	6.2	mĄ
DC Grid-No.1 Current (Approx.)	1.6 0.1	$\begin{array}{c} 1.6 \\ 0.1 \end{array}$	mA watts
DC Grid-No.1 Current (Approx.) Driving Power (Approx.) Useful Power Output (Approx.)	10.3■	12=	watts
TYPICAL OPERATION AT 50 MHz			
DC Plate Voltage	300		volts
Grid No.3 DC Grid-No.2 Voltage	Connected 250	to cathode	at socket volts
DC Grid-No.1 Voltage	<del>6</del> 0	_	volts
From a grid resistor of	22000	_	ohms
Peak RF Grid-No.1 Voltage	80	<b>→</b>	volts
DC Plate Current	50	-	mA.
DC Grid-No.1 Current (Approx)	5 3	_	mA mA
DC Grid-No.1 Current (Approx.) Driving Power (Approx.)	0.35		watt
Useful Power Output (Approx.)	7■	_	watts
MAYIMIM OIDOUT VALUE			
MAXIMUM CIRCUIT VALUE		_	_
Grid-No.1-Circuit Resistance	0.1	0.1	megohm
Frequency Multiplier			
MANUALINA DOCA DATINICO (Abaalisha Massimum Valura)			
MAXIMUM CCS● RATINGS (Absolute-Maximum Values)			_
DC Plate Voltage		300	volts
DC Grid No.3 (Suppressor) Voltage		0 250	volts
DC Grid-No.2 (Screen) Voltage		250 -125	volts volts
DC Grid-No.1 (Control-Grid) Voltage DC Plate Current		50	mA
DC Grid-No.2 Current		15	mA
DC Grid-No.1 Current		5	mA
Plate Input		15	watts
Grid-No.2 Input Plate Dissipation		$\frac{2}{12}$	watts watts
Bulb Temperature (At hottest point on bulb surface)		250	wa cc
- · · · · · · · · · · · · · · · · · · ·			



#### TYPICAL OPERATION

<b></b>	Doubler to 175 MHz	to 175 l	
DC Plate Voltage	. 300	300	volts
Grid No.3	Connected	to cathode	at socket
DC Grid-No.2 Voltage	. *		volts
DC Grid-No.1 Voltage⊕	75	100	volts
From grid resistor of	75000	100000	ohms
Peak RF Grid-No.1 Voltage	95	120	volts
DC Plate Current	40	35	mA
DC Grid-No.2 Current	4	5	mA
DC Grid-No.1 Current (Approx.)	i	ĭ	mA
Driving Power (Approx.)		0.6	watt
Useful Power Output (Approx.)	2.1■	1.3■	watts
MANUFACTOR OFFICE VALUE OF	_		

MAXIMUM CIRCUIT VALUE (For maximum rated conditions) Grid-No.1-Circuit Resistance .....

0.1 0.1

t Obtained preferably from a separate source modulated with the plate supply, or from the modulated plate supply through a series resistor.

* Obtained from grid-No.1 resistor or from a combination of grid-No.1 resistor with either

fixed supply or cathode resistor.

□ Key down conditions per tube without amplitude modulation. Modulation essentially negative may be used if the positive peak of the audio-frequency envelope does not exceed 115% of the carrier conditions.


Obtained from a fixed supply, or by a grid-No.1 resistor of value shown.

This value of useful power is measured at load of output circuit. Continuous Commercial Service.

Intermittent Commercial and Amateur Service.
 Obtained from plate supply of 300 volts through a series resistor of 12500 ohms.

Refer to chart at end of section.

5783



## MEDIUM-MU TWIN TRIODE


INDUSTRIAL TYPE

Miniature type "Premium" medium-mu twin triode used in a wide variety of applications including mixers. oscillators, multivibrators and synchronizing amplifiers in industrial control equipment. Outlines section, 6B; requires miniature 9-contact socket.

Heater Arrangement Heater Voltage (ac/dc) Heater Current	Series $12.6 \pm 10\%$ $0.175$	Parallel 6.3 ±10% 0.350	volts ampere
Heater-Cathode Voltage: Peak value	±100 max	±100 max	volts
Direct Interelectrode Capacitances (Approx.)	Unit No	. 1 Unit No. 2	
Grid to Plate			pF
Grid to Cathode and Heater		1.6	pF pF
Plate to Cathode and Heater	0.5	0.4	pF

## Class A, Amplifier (Each Unit Unless Otherwise Specified)

MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage Cathode Current Plate Dissipation:		330 22	volts mA
Each Plate Both Plates (Both units operating) Bulb Temperature (At hottest point on bulb surface)		3.0 6.0 165	watts watts °C
CHARACTERISTICS			
Plate Voltage Grid Voltage Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current Grid Voltage (Approx.) for plate current of 10 \(\mu\)A	100 0 19.5 6250 3100 11.8	250 8.5 17 7700 2200 10.5 22	volts volts ohms μmhos mA volts
MAXIMUM CIRCUIT VALUES			
Grid-Circuit Resistance: For fixed-bias operation For cathode-bias operation		0.25 1	megohm megohm



# TYPICAL OPERATION AS RESISTANCE-COUPLED AMPLIFIER See RESISTANCE-COUPLED AMPLIFIER CHART type 12AU7A conditions

## Special Ratings & Performance Data

SHOCK RATING Impact Acceleration	600 max.	g
FATIGUE RATING Vibrational Acceleration	2.5 max.	g
LOW-FREQUENCY VIBRATION PERFORMANCE RMS Output Voltage	100 max.	mV
HEATER-CYCLING LIFE PERFORMANCE Cycles of Intermittent Operation	2000 min.	cycles
AUDIO-FREQUENCY NOISE AND MICROPHONIC PERFORMANCE RMS Output Voltage	100 max.	mV



## GLOW-DISCHARGE TRIODE

INDUSTRIAL

5879

Miniature type, cold-cathode, glow discharge triode for use primarily as a relay control tube in "on-off" low current electrical circuits. Outlines section. 5C: requires miniature 7-contact socket.

#### MAXIMUM RATINGS▲ (Absolute-Maximum Values)

For 1	First-Q	uadrant	Operation	Only
-------	---------	---------	-----------	------

Peak Anode and Starter-Electrode Voltage:		
Inverse Forward	200 200	volts volts
Cathode Current: Peak Average* Peak Starter-Electrode Current:	100 25	mA mA
With starter-electrode voltage positive Ambient Temperature	100 60 to +75	mA °C
TYPICAL OPERATING CONDITIONS For Relay Service with 60-Hz Supply		
AC Anode Supply Voltage (RMS)	117	volts
Max. Peak Positive Pre-Firing Voltage Min. Peak Positive Triggering Voltage Min. Firing Voltage (Sum of In-Phase Instantaneous Pre-Firing	70 35	volts volts
Voltage and Instantaneous Triggering Voltage)	105	volts
▲ These ratings apply to the 5823 when it is operated from a power	r supply having	a fre-

quency of 60 Hz.

Averaged over any interval of 15 seconds max.

Refer to chart at end of section.	5824
Refer to chart at end of section.	5840
Refer to chart at end of section.	5840W
Refer to chart at end of section.	5842/417A
Refer to chart at end of section.	5844
Refer to chart at end of section.	5847/404A



## SHARP-CUTOFF PENTODE

Miniature type used as audio amplifier in the input stages of medium-gain public-address systems, home sound recorders, and audio systems. Outlines section. 6B; requires miniature 9-contact socket. For operation as resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section.


Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage	6.3 0.15 ±100 max	volts ampere volts
Direct Interelectrode Capacitances:		
Pentode Connection:		
Grid No.1 to Plate	0.11  max	pF pF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3	2.7	рF
Plate to Cathode, Heater, Grid No.2, and Grid No.3	2.4	ρF
Triode Connection*:		•
Grid No.1 to Plate	1.4	nF
Grid No.1 to Cathode and Heater	1.4	pF pF
Plate to Cathode and Heater	0.85	ρF


^{*} Grid No.2 and grid No.3 connected to plate.

## Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Value	es) C	Triode onnection*		
Grid-No.2 (Screen-Grid) Voltage		275	330	volts
		See	curve page 300	
Grid-No.2 Supply Voltage			330	volts
Negative-bias value		55	55	volts
Positive-bias value		0	0	volts
Plate Dissipation		1.7	1.25	watts
Grid-No.2 Input:				
For grid-No.2 voltages up to 165 volts			0.25	watt
For grid-No.2 voltages between 165 and 300 volts		See	curve page 300	***************************************
CHARACTERISTICS				
Plate Voltage	100	250	250	volts
Grid No.3			onnected to catho	
Grid-No.2 Voltage			100	volts
Grid-No.1 Voltage	3	8	<u>—3</u>	volts
Amplification Factor	21	21		40169
Plate Resistance (Approx.)	0.017	0.0137	2	megohms
Transconductance	1240	1530	1000	μmhos
Plate Current	2.2	5.5	1.8	μmnos mA
Grid-No.2 Current	2.2	0.0		
Grid-No.1 Voltage (Approx.) for plate	_		0.4	mA
current of 10 $\mu$ A	-	_	8	volts
MAXIMUM CIRCUIT VALUE				
Grid-No.1-Circuit Resistance			2.2	megohms

^{*} Grid No.2 and grid No.3 connected to plate.






5881	Refer	to	chart	at	end	of	section.
5896	Refer	to	chart	at	end	of	section.
5899	Refer	to	chart	at	end	of	section.
5902	Refer	to	chart	at	end	of	section.
5915	Refer	to	chart	at	end	of	section.


5963
INDUSTRIAL

## MEDIUM-MU TWIN TRIODE

Miniature type medium-mu twin triode used for "on-off" control applications involving long periods of operation under cutoff conditions. Outlines section, 6B; requires miniature 9-contact socket.



TECHNICAL DATA			411
Heater Arrangement Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage: Peak value Direct Interelectrode Capacitances (Approx.):  Grid to Plate	1.	0.30 ±90 max. o. 1 Unit No. 2 5 1.5	volts ampere volts
Grid to Cathode and Heater Plate to Cathode and Heater Grid of Unit No.1 to grid of Unit No.2	0.		pF pF pF
Frequency Divider in Comp and "On-Off" Control S Values are for Each U	Service	ce	
MAXIMUM RATINGS (Absolute-Maximum Values)			
Plate VoltageGrid Voltage:			volts
Negative bias value Positive bias value Peak negative value Plate Dissipation Grid Input Cathode Current: Peak DC Bulb Temperature (At hottest point on bulb surface) TYPICAL OPERATION AS FREQUENCY HALFER		0 200 2.5 0.5 100 20 ±90 max	volts volts volts watts mA mA c. volts
	Cuto	ff Zero-Bias	
Plate-Supply Voltage Grid Voltage Plate-Circuit Resistance Grid-Circuit Resistance Plate Current	Condit 150 —15 20000 47000	ion Condition 150 0 20000 47000	volts volts ohms ohms mA
MAXIMUM CIRCUIT VALUES			
Grid-Circuit Resistance: For fixed-bias operation For cathode-bias operation		0.5 1	megohm megohm
Class A. Amplier (Eac	ch Unit)		
CHARACTERISTICS			
Plate Voltage Grid Voltage Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current		67.5 0 21 6600 3200 8.5	volts volts ohms µmhos mA
Refer to chart at end of section.		5964	



## MEDIUM-MU TWIN TRIODE

Miniature type medium-mu twin triode used for "on-off" control applications involving long periods of operation under cutoff conditions. Outlines section, 6B; requires miniature 9-contact socket.

Heater Arrangement Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage:	Series $12.6 \pm 10\%$ $0.225$	Parallel $6.3 \pm 10\%$ $0.45$	volts ampere
Peak value Average value	$\pm 200$ max.	±200 max.	volts
	$\pm 100$ max.	±100 max.	volts

Direct Interelectrode Capacitances (Approx.)	Unit No.	Unit No	. 2
Grid to Plate	3.0	3.0	рF
Grid to Cathode and Heater	3.8	3.8	pF
Plate to Cathode and Heater	0.5	0.38	рF
Plate of Unit No.1 to plate of Unit No.2	0.5	5	pF
Frequency Divider in Computer S	Service		
and "On-Off" Control Service  Values are for Each Unit			
1			
MAXIMUM RATINGS (Absolute-Maximum Values)		0.00	
Plate VoltageGrid Voltage:		330	volts
Negative bias value		150	volts
Plate Dissipation		2.4	watts
Total for both units		4.4	watts
DC Cathode Current Bulb Temperature (At hottest point on bulb surface)		16.5 165	mA °C
Build Temperature (At noticest point on build surface)		100	C
TYPICAL OPERATION IN COMPUTER SERVICE			
	Cutoff	Conduction	•
	Condition	Condition	
Plate Supply Voltage	150	150	volts
Plate Load Resistor	7200	7200	ohms
Plate Current	_	10.5	mA
Grid Voltage (Approx.) for grid current of 140 µA		less t	han 1 volt
Grid Voltage (Approx.) for plate current of 150 µA	-5.5		volts
Difference in Grid Voltage Between Units (For plate current			volts
of 150 μA per unit)	1.5	_	voits
MAXIMUM CIRCUIT VALUES			
Grid-Circuit Resistance:			
For fixed-bias operation		0.1	megohm
For cathode-bias operation		0.5	megohm
Tot carrious perusion		•••	8
Class A, Amplifier (Each U	Jnit)		
CHARACTERISTICS	•		
Plate Supply Voltage		150	volts
Cathode-Bias Resistor		220	ohms
Amplification Factor		47	344415
Plate Resistance		7250	ohms
Transconductance		6500	$\mu$ mhos
Plate Current			
Grid Voltage (Approx.) for plate current of 150 $\mu$ A		8.2 —5.5	m A volts

Refer to chart at end of section. 6005 Refer to chart at end of section. 6005/6AQ5W 6005/6AQ5W/ Refer to chart at end of section. 6095

6012

## **GAS THYRATRON**

Glass octal negative-control gas-tetrode thyratron for use in relay and grid-controlled rectifier applications. Outlines section, 36; requires octal socket.

<u></u>
c13/
N B G2
RCO 2

	Min.	AV.	Max.	
Heater Voltage (ac/dc)	5.7	6.3	6.9	volts
Heater Current		2.6	2.85 am	peres
Heater-Cathode Voltage:				
Peak		+25	100 max.	volts
Cathode:				
Minimum heating time prior to tube conduction		30	se	conds
Maximum outage time without reheating		5	se	conds
Direct Interelectrode Capacitances (Approx.):				
Grid No.1 to Anode		0.23		pF
Grid No.1 to Cathode, Grid No.2, and Heater		5.8		pF pF
Anode to Cathode, Grid No.2, and Heater		3.9		рF

M:-

Ionization Time (Approx.):  For conditions: dc anode volts = 100, grid-No.2 volts = 0, grid-No.1 square-pulse volts = +50, and peak anode amperes during conduction = 5  Deionization Time (Approx.)  Maximum Critical Grid-No.1 Current:	0.5	μs See Table I
For conditions: ac anode-supply volts = 460 (rms), and average anode amperes = 0.5	3	$\mu$ A
Anode Voltage Drop (Approx.) Grid-No.1 Control Ratio (Approx.):	10	volts
For conditions: grid-No.1 resistor (megohms) = 0, grid-No.2 resistor (megohms) = 0, and grid-No.2 volts = 0	150	
For conditions: grid-No.1 resistor (megohms) = 0, grid-No.2 resistor (megohms) = 0, and grid-No. volts = 0	650	
Relay and Grid-Controlled Rectifier Servi	ce	
For Anode-Supply Frequency of 60 Hz		
MAXIMUM RATINGS (Absolute-Maximum Values) Peak Anode Voltage:		
Forward	650	volts
Inverse	1300	volts
Grid-No.2 (Shield-Grid) Voltage:		
Peak, before tube conduction	100	volts
Average#, during tube conduction	10	volts
Grid-No.1 (Control-Grid) Voltage:		
Peak, before tube conduction	200	volts
Average#, during tube conduction	—10	volts
Cathode Current:		
Peak	5	amperes
Average# Fault, for duration of 0.1 second max,	0.5 20	ampere
Average Grid-No.2 Current#	+0.05	amperes ampere
Average Grid-No.1 Current#	+0.05	ampere
Ambient-Temperature Range	—75 to +90	
	.5 (0   00	•
MAXIMUM CIRCUIT VALUE Grid-No.1-Circuit Resistance	2	
Grid-No.1-Circuit Resistance # Averaged over any interval of 30 seconds maximum.	4	megohms




Table 1

DC Anode Volts	12	5	25	i0	R _{g1}	E _{CC1}	R _{g2} *	Ecc.,
DC Anode Amperes	0.5	1.0	0.5	1.0	MΩ		ohms	
DEIONIZATION TIME	175 350 650	225 375 700	450	275 475 1200	0.001 0.1 2	13	1000	0
μS (Approx.)	100 125 250	125 150 275	100 150 275	125 175 300	0.001 0.1 2	100	1000	0


^{*} Series resistor between grid No.2 and cathode.

6021	Refer to chart at end of section.
6072	Refer to chart at end of section.
6072A	Refer to chart at end of section.
6073	Refer to chart at end of section,
6073/0A2	Refer to chart at end of section.
6074	Refer to chart at end of section.
6074/0B2	Refer to chart at end of section.

OUSU INDUSTRIAL TYPE

## LOW-MU TWIN POWER TRIODE

Glass octal type used as a regulator tube in dc power supply units and in projection television booster scanning applications. Outlines section, 36; requires octal socket.



Heater Voltage Heater Current	6.3 ±10% 2.5	volts amperes
Heater-Cathode Voltage:#		
Peak Direct Interelectrode Capacitances (Approx.)	$\pm 300$ max.	volts
Grid to Plate (each unit)	8	рF
Input (each unit)	6	pF
Output (each unit)	2.2	$\mathbf{p}\mathbf{F}$
Heater to Cathode (each unit)	11	pF
Grid of Unit No.1 to Grid of Unit No.2	0.5	pF
Plate of Unit No.1 to Plate of Unit No.2	2	ρF
		-

CHARACTERISTICS		
Plate-Supply Voltage	135	volts
Cathode-Bias Resistor	250	ohms
Amplification Factor	2	
Plate Resistance	280 7000	ohms µmhos
Transconductance	125	μmnos m A
riate Current	123	шА

Class A. Amplifier (Each Unit)

## DC Amplifier (Each Unit)

MAXIMUM RATINGS (Absolute-Maximum Values)		
Plate Voltage Plate Current Plate Dissipation Bulb Temperature (At hottest point on bulb surface)	250 125 13 200	volts mA watts °C

MAXIMUM	CIRCUIT	VALUES
---------	---------	--------

Grid-Circuit Resistance: For cathode-bias operation For fixed-bias operation□ For combined fixed and cathode-bias operation*	0.1 0.1	megohm megohm megohm
Booster Scanning Service (Each Unit)		
MAXIMUM RATINGS (Absolute-Maximum Values)		
For operation in a 525-line, 30-frame system		
Peak Negative-Pulse Plate Voltage  Peak Negative-Pulse Grid Voltage  DC Plate Current  Plate Dissipation	3000 2300 125 13	volts volts mA watts

#### MAXIMUM CIRCUIT VALUES (For maximum rated conditions)

Grid-Circuit	Resistance:
Ciria-Circuit	ItCSIG GMITTEC +

SHOCK RATING


For cathode-bias operation 1 megohm
For fixed-bias operation not recommended

- When fixed bias is used, the plate circuit should contain a protective resistance to provide a minimum drop of 15 volts dc at the normal operating conditions.
   When combined fixed and cathode-bias is used, the cathode-bias portion should have a
- minimum value of 7.5 volts dc at the normal operating conditions.

   Pulse duration must not exceed 15 per cent of one horizontal scanning cycle (10 micro-
- seconds).
  # Operation of this tube is not recommended with a damper pulse between heater and cathode.

### Special Ratings & Performance Data

Impact Acceleration	450 max.	g
FATIGUE RATING Vibrational Acceleration	2.5 max.	g
LOW-FREQUENCY VIBRATION PERFORMANCE	200 max.	mV



Refer to chart at end of section.

Refer to chart at end of section.

Refer to chart at end of section.

6082

Refer to chart at end of section.

6101

Refer to chart at end of section.

6101/6J6WA

Refer to chart at end of section.


6111

6112	Refer to chart at end of section.
6136	Refer to chart at end of section.
6186	Refer to chart at end of section.
6186/6AG5WA	Refer to chart at end of section.
6186W	Refer to chart at end of section.
6189	Refer to chart at end of section.
6197	Refer to chart at end of section.

## 6201 INDUSTRIAI


## HIGH-MU TWIN TRIODE

Miniature type used in mixer, oscillator, and amplifier applications at frequencies up to 300 MHz. Outlines section, 6B; requires miniature 9-contact socket. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section, type 12AT7 conditions.




9A

Peak Heater-Cathode Voltage Direct Interelectrode Capacitances (Approx.): Grid-Drive Operation:		Parallel 6.3 0.3 ±100 max.	volts ampere volts
Grid to Plate (Each unit) Grid to Cathode and Heater (Each unit) Plate to Cathode and Heater:		1.6 2.5	pF pF
Unit No.1 Unit No.2 Heater to Cathode (Each unit) Cathode-Drive Operation;		0.45 0.38 2.8	pF pF pF
Cathode to Plate (Unit No.1) Cathode to Plate (Unit No.2) Cathode to Grid and Heater (Each unit) Plate to Grid and Heater (Unit No.1) Plate to Grid and Heater (Unit No.2)		0.2 0.24 5 1.9 1.8	pF pF pF pF
Class A, Amplifier (Each		1.0	p <u>r</u>
MAXIMUM RATINGS (Absolute-Maximum Values)	Onic		
Plate Voltage		330	volts
Negative bias value Positive bias value Plate Dissipation Bulb Temperature (At hottest point on bulb surface)		55 0 2.75 180	volts volt watts °C
MAXIMUM CIRCUIT VALUES			
Grid-Circuit Resistance: For fixed-bias operation For cathode-bias operation		0.25 1.0	megohm megohm
CHARACTERISTICS			
Plate Supply Voltage Cathode-Bias Resistor Amplification Factor	100 270 57	250 200 60	volts ohms
Plate Resistance (Approx.) Transconductance Grid Voltage (Approx.) for plate current of 10 \(\mu A\). Plate Current	14300 4000 5 3.3	10900 5500 —12 10	ohms µmhos volts mA



## Special Ratings & Performance Data

SHOCK RATING Impact Acceleration FATIGUE RATING Vibrational Acceleration LOW-FREQUENCY VIBRATION PERFORMANCE RMS Output Voltage	600 max. 2.5 max. 100 max.	g mV
HEATER-CYCLING LIFE PERFORMANCE Cycles of Intermittent Operation AUDIO-FREQUENCY NOISE AND MICROPHONIC PERFORMANCE	2000 min.	cycles
RMS Output Voltage	100 max.	mV
Refer to chart at end of section.	6202	
Refer to chart at end of section.	6206	
Refer to chart at end of section.	6211	
Refer to chart at end of section.	6336A	
Refer to chart at end of section.	6350	
Refer to chart at end of section.	6360 6360A	
Refer to chart at end of section.	6386	
Refer to chart at end of section.	6417	
Refer to chart at end of section.	6485	



## **BEAM POWER TUBE**

INDUSTRIAL TYPE

Glass octal type used in the output stages of highfidelity audio amplifiers. Outlines section, 27C; requires octal socket. This tube should be adequately ventilated.

Heater Voltage (ac/dc)	6.3	volts
Heater Current	1.6	amperes
Peak Heater-Cathode Voltage:	-	
Heater negative with respect to cathode	300 max.	volts
Heater positive with respect to cathode	200* max.	volts

Direct Interelectrode Capacitances (Approx.): Grid No.1 to plate		0.85	рF
Grid No.1 to cathode and grid No.3, grid No.2, ba	se sleeve		-
and heater		14.0	pF
Plate to cathode & grid No.3, grid No.2, base sleeve, a	nd heater	12.0	pF
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
For fixed-bias operation		0.05	megohm
For cathode-bias operation		0.25	megohm
Class A, AF Power Ampl	ifier		
MAXIMUM RATINGS (Design-Center Values)			
Plate Voltage		600	volts
Grid-No.2 (Screen-Grid) Voltage		400	volts
Grid-No.1 (Control-Grid) Voltage:		100	70163
Negative-bias value		300	volts
Positive-bias value		0	volt
Cathode Current		175	mA
Grid-No.2 Input		6	watts
Plate Dissipation		35	watts
Bulb Temperature (At hottest point on bulb surface)		250	$^{\circ}\mathrm{c}$
TYPICAL OPERATION AND CHARACTERISTICS			
Plate Voltage	250	400	volts
Grid-No.2 Voltage	250	225	volts
Grid-No.1 Voltage	14	-16.5	volts
Peak AF Grid-No.1 Voltage	14	16.5	volts
Zero-Signal Plate Current	140	87	mĄ
MaxSignal Plate Current	150	105	mĄ
Zero-Signal Grid-No.2 Current	12	4	mĄ
MaxSignal Grid-No.2 Current	28	18	mA
	12000 11000	27000 9000	ohms µmhos
Load Resistance	1500	3000	μmnos ohms
Total Harmonic Distortion	7	13.5	%
MaxSignal Power Output	12.5	20	watts

#### Class A. Push-Pull AF Power Amplifier

MAXIMUM RATINGS (Design-Center Values)

Same as for Class A1 AF POWER AMPLIFIER

#### TYPICAL OPERATION AND CHARACTERISTICS

Values are for 2 tubes

		xed ias	Cathode Bias	
Plate Supply Voltage	400	600	400	volts
Grid-No.2 Supply Voltage	275	300	300	volts
Grid-No.1 Voltage	23	31	_	volts
Cathode Resistor			140	ohms
Peak AF Grid-No.1-to-Grid-No.1 Voltage	46	62	53	volts
Zero-Signal Plate Current	180	115	166	mA
MaxSignal Plate Current	270	273	190	mA
Zero-Signal Grid-No.2 Current	9	4	7.5	mA
MaxSignal Grid-No.2 Current	44	41	39	mA
Effective Load Resistance (Plate to plate)	3500	5000	4500	ohms
Total Harmonic Distortion	3	2.5	4	%
MaxSignal Power Output	55	100	41	watts

^{*} The dc component must not exceed 100 vlots.

6626/0A2WA

Refer to chart at end of section.

6660/6BA6

Refer to chart at end of section.

## 6661/6BH6

## SHARP-CUTOFF PENTODE

INDUSTRIAL TYPE

Miniature type used as an rf amplifier particularly in mobile equipment where low heater-current drain is important. It is particularly useful in high-frequency, wide-band applications. Outlines section, 5C; requires miniature 7-contact socket.



Heater Voltage (ac/dc)	6.3 ±	:20% volts
Heater Current	0.15	ampere
Peak Heater-Cathode Voltage	±100 m	ax. yolts
Direct Interelectrode Capacitances:	0.0035 n	ax. pF
Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and	0.0035 n	iax. pr
Internal Shield	5.4	pF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and		· .
Internal Shield	4.4	pF
Class A ₁ Amplifier		
MAXIMUM RATINGS (Design-Maximum Values)		
Plata Voltaga	330	volts
Grid-No.2 (Screen-Grid) Voltage		urve page 300
Grid-No.2 Supply Voltage	330	volts
Grid-No.1 (Control-Grid) Voltage:		-14
Negative-bias value Positive-bias value	55 0	volts volt
Plate Dissipation	3.3	watts
Grid-No.2 Input:	0.0	
For Grid-No.2 voltages up to 165 volts	0.55	watt
For Grid-No.2 voltages between 165 and 300 volts	See c	urve page 300
CHARACTERISTICS		
Plate Voltage	250	volts
Grid No.3 Connec		
Grid-No.2 Voltage	150	volts ohms
Cathode Resistor Plate Resistance (Approx.)	100 1.4	megohms
Transconductance	4600	μmhos
Plate Current	7.4	m A
Grid-No.2 Current	2.6	mA.
Grid-No.1 Voltage (Approx.) for plate current of 10 $\mu$ A	<b>—7.7</b>	volts
TRANSCONDUCTANCE AT REDUCED HEATER VOLTAGE		
Average Value	3600	$\mu$ mhos
With heater volts = 5, plate supply volts = 250, grid No.3 connected to cathode at socket, grid-No.2 supply volts = 150, and cathode resistor (ohms) bypassed = 100.		

Refer to chart at end of section. 6662/6BJ6

Refer to chart at end of section.

6663/6AL5

Refer to chart at end of section.

6664/6AB4



## **BEAM POWER TUBE**

6669/ 6AQ5A INDUSTRIAL

7BZ

Miniature type used as output amplifier primarily in mobile communications equipment. Outlines section, 5D; requires miniature 7-contact socket.

Heater Voltage (ac/dc) Heater Current Heater Warm-up Time (Average) Heater-Cathode Voltage:	6.3 ±20% 0.45 11	volts ampere seconds
Peak value Direct Interelectrode Capacitances (Approx.):	±100 max.	volts
Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 Plate to Cathode, Heater, Grid No.2, and Grid No.3	0.4 8 8.5	pF pF pF

### Class A. Amplifier

Class A. Ampimer		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage Grid-No.2 (Screen-Grid) Voltage Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point on bulb surface)	250 250 12 2 225	volts volts watts watts °C
TYPICAL OPERATION AND CHARACTERISTICS		
Plate Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage Peak AF Grid-No.1 Voltage Zero-Signal Plate Current MaxSignal Plate Current Zero-Signal Grid-No.2 Current MaxSignal Grid-No.2 Current Plate Resistance (Approx.) Transconductance Load Resistance Total Harmonic Distortion MaxSignal Power Output	250 250 -12.5 12.5 47 4.5 7 52000 4100 5000 8 4.5	volts volts volts volts mA mA mA ohms
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation  Class AB, Amplifier	0.1 0.5	megohm megohm
MAXIMUM RATINGS (Same as for Class At Amplifier)		
TYPICAL PUSH-PULL OPERATION		
Unless otherwise specified, values are for 2 tubes		
Plate Voltage Grid-No.1 Voltage Grid-No.1 (Control-Grid) Voltage Peak AF Grid-No.1-to-Grid-No.1 Voltage Zero-Signal Plate Current MaxSignal Plate Current Zero-Signal Grid-No.2 Current MaxSignal Grid-No.2 Current Effective Load Resistance (Plate to plate) Total Harmonic Distortion MaxSignal Power Output	250 250 250 15 30 70 79 5 13 10000 5	volts volts volts volts mA mA mA ohms % watts
MAXIMUM CIRCUIT VALUES (Same as for Class A1 Amplifier)		
POWER OUTPUT AT REDUCED HEATER VOLTAGE		
Average Value  With heater volts = 5, plate volts = 250, grid-No.2 volts = 250, grid-No.1 volts = -12.5, rms signal volts = 8.8, and load resistance (ohms) = 5000.	4.1	watts

6676/6CB6A

Refer to chart at end of section.

6677/6CL6

Refer to chart at end of section.

6678/6U8A


Refer to chart at end of section.

6679/12AT7


HIGH-MU TWIN TRIODE

INDUSTRIAL TYPE

Miniature type used as a mixer, oscillator or amplifier in mobile communications equipment. Outlines section, 6B; requires miniature 9-contact socket. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section, type 12AT7 conditions.




	Series 12.6 ±20% 0.15	Parallel 6.3 ±20% 0.3 ±100 max.	volts ampere volts
Grid to Plate (Each unit) Grid to Cathode and Heater (Each unit) Plate to Cathode and Heater;		1.5 2.2	pF pF
Unit No.1 Unit No.2 Cathode-Drive Operation:		0.5 0.4	pF pF
Cathode to Plate (Each unit) Cathode to Grid and Heater (Each unit) Plate to Grid and Heater (Each unit) Heater to Cathode (Each unit)		0.2 4.6 1.8 2.4	pF pF pF pF
Class A, Amplifier (Each MAXIMUM RATINGS (Design-Maximum Values)	Unit)		
Plate Voltage Grid Voltage:		330	volts
Negative bias value Positive bias value Plate Dissipation		55 0 2.8	volts volt watts
CHARACTERISTICS			
Plate Supply Voltage Cathode-Bias Resistor Amplification Factor		250 200 60	volts ohms
Plate Resistance (Approx.) Transconductance Grid Voltage (Approx.) for plate current of 10 μA Plate Current		10900 5500 —12 10	ohms µmhos volts mA
TRANSCONDUCTANCE AT REDUCED HEATER VOLTAGE		10	ma
Average Value (Each unit)  With heater volts = 10 (Series connection), plate st = 250, and cathode resistor (ohms) bypassed = 200	apply volts	4400	μmhos



## MEDIUM-MU TWIN TRIODE

6680/ 12AU7A

> INDUSTRIAL TYPE



Miniature type used as a phase inverter or push-pull amplifier in mobile communications equipment. Outlines section, 6B; requires miniature 9-contact socket. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section, type 12AU7A conditions.


Heater Arrangement Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage: Peak value Average value Direct Interelectrode Capacitances (Approx.): Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater	Unit No. 1 1.5 1.6 0.4	1.5 1.6 0.32	volts ampere volts volts pF pF pF
Class A ₁ Amplifier (Each Unit Unless	Otherwise \$	specified)	
MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage Grid Voltage, positive-bias value		330 0	volts volt
Plate Dissipation: Each Plate Both Plates (Both units operating)		3 6	watts watts
CHARACTERISTICS			
Plate Voltage Grid Voltage Amplification Factor	0	250 8.5 17	volts volts
Plate Resistance (Approx.)	6500	7700	ohms
Transconductance Plate Current		2200 10.5	μmhos mA
Grid Voltage (Approx.) for plate current of 10 $\mu$ A		-24	volts
MAXIMUM CIRCUIT VALUES Grid-Circuit Resistance:			_
For fixed-bias operation For cathode-bias operation		0.25 1	megohm megohm
TRANSCONDUCTANCE AT REDUCED HEATER VOLTAG Average Value (Each unit)  With heater volts = 10 (Series connection), plate and grid volts = -8.5.		1750	μ <b>mh</b> os

## 6681/ 12AX7A

## HIGH-MU TWIN TRIODE

INDUSTRIAL TYPE

Miniature type used as a phase inverter or twin resistance-coupled amplifier in mobile communications equipment. Outlines section, 6B; requires miniature 9-contact socket. For typical operation as a resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section, type 12AX7A conditions.



Heater Arrangement: Heater Voltage (ac/dc)	Series .2.6 ±20% ).15	Parallel 6.3 ±20% 0.3	volts ampere
Heater-Cathode Voltage: Peak value Average value Direct Interelectrode Capacitances (Approx.): Grid to Plate Grid to Cathode and Heater Plate to Cathode and Heater	Unit No. 1 1.7 1.6	±200 max. 100 max. Unit No. 2 1.7 1.6 0.34	volts volts pF pF pF

## Class A. Amplifier (Each Unit)

MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	330	volts
Grid Voltage: Negative-bias value	55	volts
Positive-bias value	$0 \\ 1.1$	volt watts

#### CHARACTERISTICS

Plate Voltage Grid Voltage	100 1	250 2	volts volts
Amplification Factor Plate Resistance (Approx.) Transconductance	100 80000 1250	100 62500 1600	ohms umhos
Plate Current	0.5	1.2	mA

Refer to chart at end of section. 6686 Refer to chart at end of section. 6688A Refer to chart at end of section. 6887 Refer to chart at end of section. 6922/E88CC



## TWIN-POWER PENTODE

Miniature type twin power-pentode intended for use in communications equipment as a push-pull rf poweramplifier or frequency-multiplier at frequencies up to 500 MHz. Outlines section. 6E: requires miniature 9contact socket.

Heater arrangement	Series	Parallel	
Heater Voltage (ac/dc)	$12.6 \pm 10\%$	$6.3 \pm 10\%$	volts
Heater Current		0.6	ampere
Peak Heater-Cathode Voltage		$\pm 100 \text{ max}$ .	volts
Bulb Temperature (At hottest point on bulb surface)		225 max.	۰C
Direct Interelectrode Capacitances (Approx., Each Uni	t):		
Grid No.1 to Plate		0.15	рF
Grid No.1 to Cathode & Grid No.3, Grid No.2, and H	eater	6.4	pF
Plate to Cathode & Grid No.3, Grid No.2, and Hea	ter	1.6	pF
Transconductance (Each Unit) for dc plate volts = 1	50, dc grid-		
No.2 volts $=$ 150, and dc plate mA $=$ 25		10500	μmhos
Mu-Factor, grid No.2 to grid No.1 (Each Unit) for de			
= 150, dc grid No.2 volts = 150, and dc plate mA	= 25	31	

## Push-Pull RF Amplifier & Oscillator—Class C Telegraphy®

## Push-Pull RF Power Amplifier—Class C FM Telephony

Values are on a per-tube basis unless otherwise specified

#### MAXIMUM RATINGS (Absolute-Maximum Values)

MAXIMUM RATINGS (Absolute-maximum values)			
	Up to CCS*	500 MHz ICAS◆	
DC Plate Voltage	250	250	volts
DC Grid-No.2 (Screen-Grid) Voltage	200	200	volts
DC Grid-No.1 (Control-Grid) Voltage	-100	-100	volts
DC Plate Current	90	100	mA
DC Grid-No.1 Current	6	8	mA
DC Cathode Current	190	120	mA
Plate Input	12	14	watts
Grid-No.2 Input	3	3.5	watts
Grid-No.1 Input	0.2	0.24	watt
Plate Dissipation	6	7.5	watts
Title Dissipation	U	1.0	Walts
TYPICAL OPERATION			
		0 MHz	
DC Plate Voltage	180	200	volts
DC Grid-No.2 Voltage	180	200	volts
DC Grid-No.1 Voltage	20	20	volts
From grid resistor for each grid No.1 of	27000	27000	ohms
Peak-to-Peak RF Grid-No.1 Voltage	50	50	volts
DC Plate Current	55	60	mA
DC Grid-No.2 Current	12.5	14	mA
DC Grid-No.1 Current	1.5	1.5	mA
Driver Power Output (Approx.)	1.2	1.2	watts
Useful Power Output (Approx.)	5	6	watts
Oberti I over Output (Approx.)	ð	v	WHITS

#### Plate-Modulated Push-Pull RF Power Amplifier—Class C Telephony Carrier conditions per tube for use with a maximum modulation factor of 1 Values are on a per-tube basis

#### MAXIMUM RATINGS (Absolute-Maximum Values)

•	Up to	500 MHz	
	CCS*	ICAS♦	
DC Plate Voltage	200	200	volts
DC Grid-No.2 (Screen-Grid) Voltage	200	200	volts
DC Grid-No.1 (Control-Grid) Voltage	100	100	volts
DC Plate Current	64	80	mA
DC Grid-No.1 Current	6	8	mA
DC Cathode Current	80	96	m A
Plate Input	8	10	watts
Grid-No.2 Input	2	2.3	watts
Grid-No.1 Input	0.2	0.24	watt
Plate Dissipation	4	5	watts

#### TYPICAL OPERATION


		OU MHZ	
DC Plate Voltage	180	180	volts
DC Grid-No.2 Voltage	180	180	volts
DC Grid-No.1 Voltage	20	20	volts
From grid resistor for each grid No.1 of	68000	27000	ohms
Peak-to-Peak RF Grid-No.1 Voltage	45	50	volts
DC Plate Current	40	55	m A
DC Grid-No.2 Current	9.5	12.5	mA
DC Grid-No.1 Current	0.6	1.5	mA
Driver Power Output (Approx.)	1	1.2	watts
Useful Power Output (Approx.)	3.5	5	watts

## Frequency Tripler—Class C

Values are on a per-tube basis

#### MAXIMUM RATINGS (Absolute-Maximum Values)

	Up to	500 MHz	
	CCS*	ICAS♦	
DC Plate Voltage	250	250	volts
DC Grid-No.2 (Screen-Grid) Voltage	200	200	volts
DC Grid-No.1 (Control-Grid) Voltage	100	—100	volts
DC Plate Current	60	80	mA
DC Grid-No.1 Current	6	8	mA
DC Cathode Current	70	80	mA
Plate Input	8	10	watts
Grid-No.2 Input	3	3.5	watts
Grid-No.1 Input	0.2	0.24	watt
Plate Dissipation	6	7.5	watts



#### TYPICAL OPERATION

	Up to 500 MHz		
DC Plate Voltage	180	200	volts
DC Grid-No.2 Voltage (Approx.)	180	190	volts
Through resistor of	1200	1200	ohms
DC Grid-No.1 Voltage	74	74	volts
From grid resistor for each grid No.1 of	. 82000	82000	ohms
Peak-to-Peak RF Grid-No.1 Voltage	165	165	volts
DC Plate Current	40	46	mA
DC Grid-No.2 Current	9.7	11	mA
DC Grid-No.1 Current	1.8	1.8	mA
Driver Power Output (Approx.)	1.1	1.1	watts
Useful Power Output (Approx.)	1.8	2.2	watts

- Key-down conditions per tube without amplitude modulation. Amplitude modulation essentially negative may be used if the positive peak of the audio-frequency envelope does not exceed 115% of the carrier conditions.
- * Continuous Commercial Service.
- Intermittent Commercial and Amateur Service.
- Inis value of useful power is measured at load of output circuit.



## **BEAM POWER TUBE**

6973

Miniature type used as power amplifier in compact high-fidelity audio equipment. Outlines section, 6G; requires miniature 9-contact socket.


Heater Voltage (ac/dc) Heater Current					$\substack{6.3\\0.45}$	volts ampere
Heater-Cathode Voltage: Peak value Average value					±200 max 100 max	volts volts
Direct Interelectrode Capacitances; Grid-No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2 Plate to Cathode Heater, Grid No.2	No.2, a	nd G	rid No.3	3	0.4 max 9 6	pF pF pF
•	s A, A			· · · · · · · · · ·	v	ν.
	,					
CHARACTERISTICS						
Plate Voltage					250	volts
Grid-No.2 (Screen-Grid) Voltage					250	volts
Grid-No.1 (Control-Grid) Voltage					<del>-15</del>	volts
Plate Resistance (Approx.)					73000	ohms
Transconductance					4800	μmhos
Plate Current					46 3.5	m A m A
Grid-No.2 Current Grid-No.1 Voltage (Approx.) for plate cu		-6 16	30 A		40	volts
Grid-No.1 voltage (Approx.) for plate co	urrent	or 10	υυ μ.κ		40	voits
Push-Pull	Class	AB,	Ampli	fier		
ALANIAMIA BATINGO (D. C. Alani						
	Values	١				
MAXIMUM RATINGS (Design-Maximum \					440	volte
Plate Voltage					440 330	volts
Plate Voltage	<b></b> .				330	volts
Plate Voltage Grid-No.2 Voltage Plate Dissipation		· · · · · · · · · · · · ·	<i>.</i>		330 12	volts watts
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input		· · · · · · · · · · · · · · · · · · ·			330	volts
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point)		· · · · · · · · · · · · · · · · · · ·			330 12 2	volts watts watts
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input	o tube	es)			330 12 2 250	volts watts watts
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point) TYPICAL OPERATION (Values are for tw	o tube	es) xed B	ias	Cath	330 12 2 250 ode Bias	volts watts watts °C
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point) TYPICAL OPERATION (Values are for tw Plate Supply Voltage	o tube	es) <b>xed B</b> 350	ias 400	Cath	330 12 2 250 ode Bias 310	volts watts watts °C
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point) TYPICAL OPERATION (Values are for tw Plate Supply Voltage Grid-No.2 Supply Voltage	70 tube Fix 250 250	es) <b>xed B</b> 350 280	ias 400 290	Cath	330 12 2 250 ode Bias	volts watts watts °C  volts volts
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point) TYPICAL OPERATION (Values are for tw Plate Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage	70 tube Fix 250 250	es) <b>xed B</b> 350	ias 400	Cath	330 12 2 250 ode Bias 310 310	volts watts watts °C
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point) TYPICAL OPERATION (Values are for tw Plate Supply Voltage Grid-No.2 Supply Voltage	70 tube Fix 250 250 —15	es) <b>xed B</b> 350 280	400 290 —25	Cath 300 300	330 12 2 250 ode Bias 310 310	volts watts watts volts volts volts
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point) TYPICAL OPERATION (Values are for tw Plate Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Cathode-Bias Resistor	70 tube Fix 250 250 —15	es) <b>xed B</b> 350 280	400 290 —25	Cath 300 300	330 12 2 250 ode Bias 310 310	volts watts watts volts volts volts
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point) TYPICAL OPERATION (Values are for tw Plate Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to- Grid-No.1 Voltage Zero-Signal Plate Current	70 tube Fix 250 250 —15	es) <b>xed B</b> 350 280 —22	400 290 —25	Cath 300 300 	330 12 2 250 ode Bias 310 310 270	volts watts watts °C  volts volts volts ohms
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point) TYPICAL OPERATION (Values are for tw Plate Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to- Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current	70 tube Fix 250 250 —15	280 280 222 44 58	400 290 —25 — 50 50	Cath 300 300 230	330 12 2 250 <b>ode Bias</b> 310 310 270	volts watts watts °C  volts volts volts ohms
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point) TYPICAL OPERATION (Values are for tw Plate Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to- Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current	70 tube Fix 250 250 —15 —30 92 105	280 280 222 44 58 106 3.5	400 290 —25 — 50 50 107 2.5	Cath 300 300  230 48 80 96 6	330 12 2 250 ode Bias 310 310 270 55 77 92 5	volts watts watts °C volts volts volts ohms volts mA mA
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point) TYPICAL OPERATION (Values are for tw Plate Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to- Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current	70 tube Fin 250 250 —15 —30 92 105	280 280 222 44 58	400 290 —25 — 50 50	Cath 300 300 230 48 80 96	330 12 2 250 <b>ode Bias</b> 310 310 270 55 77	volts watts watts °C  volts volts volts ohms  volts mA
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point) TYPICAL OPERATION (Values are for tw Plate Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to- Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Maximum-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Effective Load Resistance	zo tube Fix 250 250 —15 —30 92 105 7 16	280 280 280 222 44 58 106 3.5	\$\frac{400}{290}\$ \$\therefore 25\$ \$\frac{50}{50}\$ \$107\$ \$2.5\$ \$13.7	Cath 300 300 230 48 80 96 6 14	330 12 2 250 <b>ode Bias</b> 310 310 270 55 77 92 5	volts watts watts °C  volts volts volts ohms  volts mA mA mA
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point) TYPICAL OPERATION (Values are for tw  Plate Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to- Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Effective Load Resistance (Plate-to-plate)	70 tube Fis 250 250 —15 —15 7 16 8000 7	280 280 222 44 58 106 3.5 14	\$\frac{400}{290}\$ \$\text{-25}\$ \$\text{-50}\$ \$50\$ \$50\$ \$107\$ \$2.5\$ \$13.7\$ \$8000	Cath 300 300 230 48 80 96 6 14	330 12 2 250 <b>ode Bias</b> 310 310 270 55 77 92 5 14	volts watts watts volts volts volts volts ohms  volts mA mA mA ohms
Plate Voltage Grid-No.2 Voltage Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point) TYPICAL OPERATION (Values are for tw Plate Supply Voltage Grid-No.1 Voltage Grid-No.1 Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to- Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Maximum-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Effective Load Resistance (Plate-to-plate) Total Harmonic Distortion	zo tube Fix 250 250 —15 —30 92 105 7 16	280 280 280 222 44 58 106 3.5	\$\frac{400}{290}\$ \$\therefore 25\$ \$\frac{50}{50}\$ \$107\$ \$2.5\$ \$13.7	Cath 300 300 230 48 80 96 6 14	330 12 2 250 <b>ode Bias</b> 310 310 270 55 77 92 5	volts watts watts °C  volts volts volts ohms  volts mA mA mA

## MAXIMUM CIRCUIT VALUES

rid-No.1-Circuit Resistance:		
For fixed-bias operation	0.5	megohm
For cathode-bias operation	1	megohm

#### Push-Pull Class AB, Amplifier

Grid No.2 of Each Tube Connected to Tap on Plate	Winding of	Output Tran	nsfor <b>me</b> r
MAXIMUM RATINGS (Design-Maximum Values)			
Plate and Grid-No.2 Supply Voltage		410	volts
Plate Dissipation		12	watts
Grid-No.2 Input		1.75	watts
Bulb Temperature (At hottest point)		250	or C
			•
TYPICAL OPERATION (Values are for two tubes)	Fixed Bias	Cathode Bias	,
Plate Supply Voltage	375	370	volts
Grid-No.2 Supply Voltage	•	#	volts
Grid-No.1 Voltage.	-33.5		volts
Cathode-Bias Resistor		355	ohms
Peak AF Grid-No.1-to-Grid-No.1 Voltage	67	62	volts
Zero-Signal Cathode Current	62	74	mA
Maximum-Signal Cathode Current	95	84	mA
Effective Load Resistance (Plate-to-plate)	12500	13000	ohms
Total Harmonic Distortion	1.5	1.2	per cent
Maximum-Signal Power Output	18.5	15	watts
	10.0	10	***************************************
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance:			
For fixed-bias operation		0.1	megohm
For cathode-bias operation		1	megohm



* Obtained from taps on the primary winding of the output transformer. The taps are located on each side of the center tap (B+) so as to apply 50 per cent of the plate signal voltage to grid No.2 of each output tube.

# Obtained from taps on the primary winding of the output transformer. The taps are located on each side of the center tap (B+) so as to supply 43 per cent of the plate signal voltage to grid No.2 of each output tube.

• The type of input-coupling network used should not introduce too much resistance in the grid-No.1 circuit. Transformer- or impedance-coupling devices are recommended.


6977

Refer to chart at end of section.

## 7025

## HIGH-MU TWIN TRIODE

Miniature type used as phase inverter or resistancecoupled amplifier in high-quality, high-fidelity audio amplifiers. Outlines section, 6B; requires miniature 9contact socket. This type is identical with miniature type 12AX7A except that it has a controlled equivalent noise and hum characteristic. For operation as resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section.



-- 5

Ec:*0

300

15

EC1 -20

92CS-9389T

EQUIVALENT-NOISE AND HUM VOLTAGE REFERENCED TO GRID (	Each Unit)	
Average Value (rms)†	1.8	$\mu \nabla$
Maximum Value (rms)	7	"V

† Measured in "true rms" units under following conditions: heater volts (ac), 6.3 (parallel connection); center tap of heater transformer connected to ground; plate supply volts, 250; plate load resistor, 2700 ohms; cathode-bypass capacitor, 100  $\mu F$ ; grid resistor, 0 ohms; and amplifier covering frequency range between 25 to 10000 cycles per second.

· Same conditions as for "Average Value" except cathode resistor is unbypassed and grid resistor is 0.05 megohm,

Refer to chart at end of section.

7027



## **BEAM POWER TUBE**

7027A

Glass octal type used in push-pull power amplifier circuits of high-fidelity audio equipment. Outlines section.

62 0 K, 63	cuits of high-fid						
	9F; requires oct						r power-
8HY	handling tubes, s	snould	be ade	quatery	ventii	ated.	
Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage					6.3 0.9		volts ampere
Peak value						max max	volts volts
Grid No.1 to Plat Grid No.1 to Cathod	e le, Heater, Grid No.2 leater, Grid No.2, an	and C	irid No.3		1.5 10 7.5	)	pF pF pF
	Class A	Amp	lifier				
CHARACTERISTICS		•					
Plate Voltage	Voltage				250 250		volts volts
Grid-No.1 (Control-Grid	) Voltage				-14		volts
Plate Resistance (Appr	ox.)				22500		oh <b>ms</b>
Transconductance					6000		μmhos
Plate Current					72 5		mA mA
Grid-No.2 Current		• • • • • • •		• • • • • • •		•	mz
	Push-Pull Cia	cc AR	Amnli	fier			
			Turkti				
MAXIMUM RATINGS (D							•.
					600 500		volts volts
Grid-No.2 Voltage Plate Dissipation					35		watts
Grid-No.2 Input					5		watts
Grid-No.2 Input					•		
TYPICAL OPERATION (\	/alues are for two ti	ubes)					
		Fixed B			athode l		
Plate Supply Voltage		450	540	400	380	425	volts
Grid-No.2 Supply Volta		350 30•	400 —38•	300	380	415	volts volts
Grid-No.1 Voltage Cathode-Bias Resistor		30•		200	180	200	ohms
Peak AF Grid-No.1-to-Gi		60	76	57	68.5	86	volts
Zero-Signal Plate Curr		95	100	112	138	150	mA
Maximum-Signal Plate		194	220	128	170	196	mA
Zero-Signal Grid-No.2		3.4	5	7	5.6	8	mA
Maximum-Signal Grid-N	o.2 Current 17	19.2	21.4	16	20	20	mA
Effective Load Resistance	e						
	6600	6000	6500	6600	4500	3800	ohms
Total Harmonic Distort Maximum-Signal Power		1.5 50	2 76	2 32	3.5 36	44	per cent watts
19wor isingic-mumilian	Output 04	00	10	02	•••	7.9	*******
MAXIMUM CIRCUIT VAI	LUES						
Grid-No.1-Circuit Resista	nce:						
For fixed-bias opera					0.1		megohm
For cathode-bias op	eration				0.5		megohm

· The type of input coupling network used should not introduce too much resistance in the

grid-No.1 circuit. Transformer- or impedance-coupling devices are recommended.


## Push-Pull Class AB, Amplifier


Grid No.2 of Each Tube Connected to Tap on Plate Winding of	Output Transformer
MAXIMUM RATINGS (Design-Maximum Values)	
Plate and Grid-No.2 Supply Voltage	600

Plate and Grid-No.2 Supply Voltage Plate Dissipation Grid-No.2 Input	600 35 4.5	volts watts watts
TYPICAL OPERATION (Values are for two tubes)		
Plate Supply Voltage Grid-No.2 Supply Voltage Cathode-Bias Resistor Peak AF Grid-No.1-to-Grid-No.1 Voltage Zero-Signal Cathode Current Maximum-Signal Cathode Current Effective Load Resistance (Plate to plate) Total Harmonic Distortion Maximum-Signal Power Output	410 220 68 134 155 8000 1.6 24	volts volts ohms volts mA mA ohms per cent watts
MAYIMIM CIRCUIT VALUE		

^{*} Obtained from taps on the primary winding of the output transformer. The taps are located on each side of the center tap (B+) so as to apply 43 per cent of the plate signal voltage to grid No.2 of each output tube.

Grid-No.1-Circuit Resistance, for cathode-bias operation





0.5

megohm

7044	Refer t	to	chart	at	end	of	section.
7054	Refer t	to	chart	at	end	of	section.
7055	Refer t	to	chart	at	end	of	section.
7056	Refer t	to	chart	at	end	of	section.
7057	Refer t	to	chart	at	end	of	section.
7058	Refer t	to	chart	at	end	of	section.

INDUSTRIAL TYPE

## MEDIUM-MU TRIODE-SHARP-CUTOFF PENTODE

Miniature type medium-mu triode sharp-cutoff pentode for use as a combined oscillator and mixer in mobile communications equipment. Outlines section, 6B; requires miniature 9-contact socket.



Heater Voltage		
Heater Current	Volts	

12 to 15 0.195 $\pm 120 \text{ max}.$ 

volts ampere volts

	Unshielded	Shielded	
Direct Interelectrode Capacitances:			
Triode Unit:			_
Grid to Plate	1.7	1.7	pF
Grid to Cathode, Heater	2.7	2.7	$\mathbf{pF}$
Plate to Cathode, Heater	0.4	1	рF
Pentode Unit:			
Grid No.1 to Plate	0.15 max.	0.007 max.	рF
Grid No.1 to Cathode, Heater, Grid No.2, Grid			
No.3, and Internal Shield	5	5	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3,			
and Internal Shield	2.5	3.4	рF
Heater to Cathode	3	3■	pF
			-

- Use With external shield connected to cathode of unit under test except as noted.
- With external shield connected to ground.

## Class A. Amplifier


### MAXIMUM RATINGS (Design-Maximum Values)


Plate Voltage Grid-No.2 (Screen-Grid) Supply Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage, Positive-bias value Plate Dissipation Grid-No.2 Input: For grid-No.2 voltages up to 150 volts	300 — 0 2.5	t Pentode Unit 300 300 See curve page 30 2.8	volt watts watt
For grid-No.2 voltages between 150 and 300 volts		See curve page 30	0
MAXIMUM CIRCUIT VALUES			
Grid-No 1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.5 1	$\begin{array}{c} 0.5 \\ 1 \end{array}$	megohm megohm
CHARACTERISTICS			
Heater Voltage Plate Supply Voltage Grid-No.2 Voltage Cathode-Bias Resistor Amplification Factor	13.5 $150$ $ 56$ $40$	13.5 250 110 68	volts volts volts ohms
Plate Resistance (Approx.) Transconductance Plate Current Grid-No.2 Current Grid-No.1 Voltage for plate current of 10 μA	4700 8500 18 12	400000 5200 10 3.5 10	ohms μmhos mA mA volts

## Special Ratings & Performance Data

## HEATER-CYCLING LIFE PERFORMANCE Cycles of Intermittent Operation

LOW-FREQUENCY VIBRATION PERFORMANCE		
RMS Output Voltage, Triode Unit RMS Output Voltage, Pentode Unit	150 max. 250 max	mV mV





2000 min.

eveles

7060 Refer to chart at end of section.
7061 Refer to chart at end of section.
7167 Refer to chart at end of section.

7189

Transconductance

## **POWER PENTODE**



40000

11300

48

5.5

ohms

mA

mΑ

μmhos

Miniature type used as power amplifier tube in high-fidelity audio equipment. Outlines section, 6G; requires miniature 9-contact socket.

Plate Resistance (Approx.)

Plate Current
Grid-No.2 Current

Heater Voltage ...... volts Heater Current
Peak Heater-Cathode Voltage
Direct Interelectrode Capacitances (Approx.): 0.76 .......... ampere ±100 max volta Grid No.1 to Plate 0.5 ρF Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3

Plate to Cathode, Heater, Grid-No.2, and Grid No.3

Grid No.1 to Heater 10.8 ρF 6.5 Class A. Amplifier CHARACTERISTICS Plate Voltage ... 250 volts Plate Voltage
Grid-No.2 (Screen-Grid) Voltage
Grid-No.1 (Control-Grid) Voltage
Mu-Factor, Grid No.2 to Grid No.1 250 volts --7.3 volts 19.5

#### Push-Pull Class AB, Amplifier

.....


MAXIMUM RATINGS (Design-Center Values)		Grid-No.2 Special Connection•	
Plate Voltage	400	375	volts
Grid-No.2 Voltage	300	•	volts
Cathode Current	65	65	mA
Plate Dissipation	12	12	watts
Zero-Signal Grid-No.2 Input	2	2	watts
Maximum-Signal Grid-No.2 Input	Ĭ.	<u> </u>	watts
	,	•	**********
TYPICAL OPERATION (Values are for two tubes)			_
Plate Supply Voltage		375	volts
Plate Voltage	400		volts
Grid-No.2 Supply Voltage	_	•	
Grid-No.2 Voltage	300	•	volts
Grid-No.1 Voltage	15		volts
Cathode-Bias Resistor	_	220	ohms
Peak AF Grid-No.1 Voltage	14.8	17.7	volts
Zero-Signal Plate Current	15	70	m A
Maximum-Signal Plate Current	105	81	m A
Zero-Signal Grid-No.2 Current	1.6	•	mA.
Maximum-Signal Grid-No.2 Current	25	•	m A
Effective Load Resistance (Plate-to-plate)	8000	11000	ohms
Total Harmonic Distortion	4	3	per cent
Maximum-Signal Power Output	24	16.5	watts
MAXIMUM CIRCUIT VALUES	Fixed Bias	Cathode Bias	
Grid-No.1-Circuit Resistance	0.3	1	megohm

[·] Grid No.2 of each tube connected to tap on plate winding of output transformer.

[•] Obtained from taps on primary winding of the output transformer. The taps are located on each side of the center tap (B+) so as to supply 43 per cent of the plate signal voltage to grid No.2 of each output tube.

## MEDIUM-MU TRIODE— SHARP-CUTOFF PENTODE

7199



Miniature type used in high-quality, high-fidelity audio equipment, particularly in phase splitters, tone-control amplifiers, and high-gain voltage amplifiers. Outlines section, 6B; requires miniature 9-contact socket. For operation as resistance-coupled amplifier, refer to Resistance-Coupled Amplifier section. In direct-coupled voltage-amplifier phase-splitter circuits, the pentode unit should drive the triode unit.

Heater Voltage (ac/dc) Heater Current	6.3 0.45	volts ampere
Heater-Cathode Voltage:	0.40	ampere
Peak value	$\pm 200 \text{ max}$	volts
Average value	100 max	volts
Direct Interelectrode Capacitances:		*
Triode Unit:		
Grid to Plate	2	пF
Grid to Cathode and Heater	2.3	pF
Plate to Cathode and Heater	0.3	ρF
l'entode Unit:	0.0	PT
Grid No.1 to Plate	0.06 max	ρF
Grid No.1 to Cathode, Heater, Grid No.2, Grid No.3, and	o.oo max	P.
Internal Shield	5	рF
Plate to Cathode, Heater, Grid No.2, Grid No.3, and	U	pr
Internal Shield	2	рF
		-

#### EQUIVALENT-NOISE AND HUM VOLTAGE REFERENCED TO GRID


	Triode Unit	Pentode Unit	
Median Value (rms)	10†	35∙	μV
Maximum Value (rms)	150÷	100•	μV


† Measured in "true rms" units under the following conditions: heater volts (ac), 6.3; center tap of heater transformer connected to ground; plate-supply volts, 250; plate load resistor, 0.1 megohm; cathode resistor, 1500 ohms; grid resistor, 0.05 megohm; and amplifier covering frequency range between 25 and 10000 cycles per second.

• Same conditions as for triode unit except: grid-No.2 supply volts, 250; grid-No.2 resistor, 0.33 megohm; grid-No.2-bypass capacitor, 0.22  $\mu F$ ; cathode resistor, 1200 ohms; and grid-No.1 resistor, 0.05 megohm.

#### Class A, Amplifier

MAXIMUM RATINGS (Design-Maximum Values)	Triode U	nit Pentode	Unit	
Plate Voltage	330	330		volts
Grid-No.2 (Screen-Grid) Voltage	_	See curve	nave 300	
Grid-No.2 Supply Voltage		330	,	volts
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	000		volts
Plate Dissipation	2.4			watts
Grid-No.2 Input:	***	•,		watta
For grid-No.2 voltages up to 165 volts		0.6		watt
For grid-No.2 voltages between 165 and 330 volts		See curve i	age 300	





CHARACTERISTICS	Triode Unit	Pento	de Unit	
Plate Supply Voltage	215	100	220	volts
Grid-No.2 Supply Voltage		50	130	volts
Grid-No.1 Voltage	8.5	_		volts
Cathode-Bias Resistor		1000	62	ohms
Amplification Factor	17	_	_	
Plate Resistance (Approx.)	0.0081	1	0.4	megohm
Transconductance	2100	1500	7000	µmhos
Plate Current	9	1.1	12.5	mA
Grid-No.2 Current	_	0.35	3.5	mA
Grid-No.1 Voltage (Approx.) for plate current				
of 10 μA	40	-4		volts
MAXIMUM CIRCUIT VALUES Grid-No.:-Circuit Resistance:*	Triode	Unit l	Pentode Unit	
For fixed-bias operation	0.	5	0.25	megahm


If either unit is operated at maximum rated conditions, grid-No.1-circuit resistance for both units should not exceed the stated value.

## 7247

## **DUAL TRIODE**

Miniature type used for combined first- and secondstage audio preamplification in high-fidelity phonograph or tape equipment. Tube has high-mu unit and mediummu unit. Outline 8B, Outlines section. Tube requires miniature nine-contact socket and may be operated in any position. Heater: volts (ac/dc), 12.6 (series), 6.3 (parallel); amperes, 0.15 (series), 0.3 (parallel).

For cathode-bias operation .....



Unit No.2

TT-24

merchm

### Class A, Amplifier

MAXIMUM RATINGS (	Design-Maximum	Values)
-------------------	----------------	---------

	No.1	Unit No.2	
Plate Voltage	330	330	volts
Negative-bias value		55	volts
Positive-bias value		0 22	volts mA
Plate Dissipation Heater-Cathode-Voltage:	1.2	3	watts
Peak value		±200 max 100 max	vol <b>ts</b> volts
CHARACTERISTICS			

100	250	100	250	volts
1	2	0	8.5	volts
100	100	20	17	
80000	62500	6500	7700	oh ms
1250	1600	3100	2200	$\mu$ mhos
0.5	1.2	11.8	10.5	mA
			24	volts
	100 1 100 80000 1250	$\begin{array}{ccc} -1 & -2 \\ 100 & 100 \\ 80000 & 62500 \\ 1250 & 1600 \end{array}$	$\begin{array}{ccccc} 100 & 250 & 100 \\1 &2 & 0 \\ 100 & 100 & 20 \\ 80000 & 62500 & 6500 \\ 1250 & 1600 & 3100 \end{array}$	$\begin{array}{cccccccccccccccccccccccccccccccccccc$

Unit No.1

TT-24

## MAXIMUM CIRCUIT VALUES

Grid-Circuit Resistance:	No.1	No.2	
For fixed-bias operation	15 max	0.5  max	megohms
For cathode-bias operation		1 max	megohm
HUM GUTPUT VOLTAGE			

Average Value (rms, cathode bypassed) 1.8 #volts Maximum Value (rms, cathode unbypassed). #volts

[&]quot;The dc component must not exceed 100 volts.

Measured in "true rms" units under the following conditions: heater volts (ac), 6.3 (parallel connection); center tap of heater transformer connected to ground; dc plate supply volts, 250; plate load resistor, 0.1 megohm; cathode resistor, 2700 ohms; cathode-bypass capacitor, 100 \(\mu f\); grid resistor, 0 ohms; amplifier covering frequency range of 25 to 10000 cps.


[·] Same conditions as above, except that cathode resistor is unbypassed and grid resistor is 0.05 megohm.

Refer to chart at end of section.

7258

Refer to chart at end of section.

7308



## **POWER PENTODE**

Glass octal type used in the power-output stage of TH high-fidelity audio-frequency amplifier systems. Outlines section, 13F; requires octal socket. Heater: volts (ac/dc), 6.3; amperes, 0.8; maximum heater-cathode volts,  $\pm 200$  peak, 100 average.

## Class A, Amplifier

5.005 M ₁		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage	500	volts
Grid-No.2 (Screen-Grid) Voltage	400	volts
Grid-No.1 (Control-Grid) Voltage, Positive-bias value	0	volts
Average Cathode Current	100	$\mathbf{m}\mathbf{A}$
Plate Dissipation	18	watts
DC Grid-No.2 Input	3.5●	volts
TYPICAL OPERATION AND CHARACTERISTICS		
Plate Voltage	250	volts
Grid-No.2 Voltage	225	volts
Grid-No.1 Voltage	-15	volts
Peak AF Grid-No.1 Voltage	15	volts
Plate Resistance (Approx.)	42000	ohms
Transconductance	7600	$\mu$ mhos
Zero-Signal Plate Current	62	mA
Maximum Signal Plate Current	74	mA
Zero-Signal Grid-No.2 Current	3.2	m A
Maximum-Signal Grid-No.2 Current	16.5	m A
Load Resistance	2500	ohms
Total Harmonic Distortion (Approx.)	15	per cent
Maximum-Signal Power Output	9	watts
Grid-No.1 Voltage (Approx.) for plate current of 500 μA	35	volts
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance:		
For fixed-bias operation	0.3	megohm
For cathode-bias operation	1	megohm
· Grid-No.2 input may reach 7 watts during peak levels of speech and	music sign	als.

### Push-Pull Class AB, Amplifier


#### MAXIMUM RATINGS (Same as for class A₁ amplifier)

#### TYPICAL OPERATION (Values are for two tubes)

Plate Voltage	300	400	volts
Grid-No.2 Voltage	250	300	volts
Grid-No.1 Voltage	-21	34	volts
Peak AF Grid-No.1 Voltage	42	60	volts
Zero-Signal Plate Current	100	56	m A
Maximum-Signal Plate Current	185	175	mA
Zero-Signal Grid-No.2 Current	5.5	3.5	m A
Maximum-Signal Grid-No.2 Current	24	24	m A
Effective Load Resistance (Plate-to-plate)	4000	- 5000	ohms
Total Harmonic Distortion	2	6	per cent
Maximum-Signal Power Output	28.5	40	watts

## 7408

## **BEAM POWER TUBE**



7AC

volts

megohm

350

Glass octal type used as output amplifier tube in highquality sound systems. Outlines section, 13D; requires octal socket.

MAXIMUM RATINGS (Design-Maximum Values)
Plate Voltage

Heater Voltage (ac/dc) Heater Current Heater-Cathode Voltage:	$\substack{6.3\\0.45}$	volts ampere
Peak value Average value Direct Interelectrode Capacitances:	±200 100	volts volts
Grid No.1 to Plate Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3 Plate to Cathode, Heater, Grid No.2, and Grid No.3	0.7 9 7.5	pF pF pF

## Class A. Amplifier

Grid-No.2 (Screen-Grid) Voltage		315	volts
Grid-No.2 Input		2.2	watts
Plate Dissipation		14	watts
TYPICAL OPERATION AND CHARACTERISTICS			
Plate Voltage	60	250	volts
Grid-No.2 Voltage	250	250	volts
Grid-No.1 (Control-Grid) Voltage	0	12.5	volts
Peak AF Grid-No.1 Voltage	_	12.5	volts
Zero-Signal Plate Current	100•	45	mA
Maximum-Signal Plate Current		47	mA
Zero-Signal Grid-No.2 Current	22•	4.5	mA
Maximum-Signal Grid-No.2 Current	_	7	mA
Plate Resistance (Approx.)	_	50000	ohms
Transconductance	_	4100	umhos
Load Resistance		5000	ohms
Total Harmonic Distortion		7	per cent
Maximum-Signal Power Output		4.5	watts
MAXIMUM CIRCUIT VALUES			


## 7543

HUM OUTPUT VOLTAGE

Grid-No.1-Circuit Resistance: For fixed-bias operation

## **SHARP-CUTOFF PENTODE**

Miniature type used in compact audio equipment. Outlines section, 5C; requires miniature 7-contact socket. This type is identical with miniature type 6AU6A except that it has a controlled hum characteristic.



Average Value, (rms, cathode bypassed) 1.2† millivolts Average Value (rms, cathode unbypassed) 0.9• millivolt

Average value (rms, cathode analypassed)

The Measured in "true rms" units under the following conditions: heater volts (ac), 6.3; center tap of heater transformer connected to ground; plate and grid-No.2 supply volts, 250; plate load resistor, 0.27 megohm; grid No.3 and internal shield connected to cathode at socket; grid-No.2 resistor, 0.68 megohm; grid-No.1 resistor, 0.1 megohm; cathode resistor, 1000 ohms; grid resistor of following stage, 10 megohms; and stage gain, 340.

[·] Same conditions as above except that cathode resistor is unbypassed and stage gain is 110.



## **BEAM POWER TUBE**

## 7551

INDUSTRIAL TYPE

Miniature type for use as a class C radio-frequency amplifier, oscillator, and frequency-multiplier up to 175 MHz in mobile communications epuipment. Outlines section, 6E; requires miniature 9-contact socket. Curves shown under type 7558 also apply to the 7551.

Direct Interelectrode Capacitances: Grid No.1 to Plate Grid No.1 to Cathode, Grid No.3, Grid No.2 and Heater Plate to Cathode, Grid No.3, Grid No.2 and Heater Bulb Temperature (At hottest point on bulb surface)	13.5 ±1.5 0.36 ±100 max. 0.15 max. 10 5.5 225 max.	volts ampere volts pF pF pF	
MAXIMUM CIRCUIT VALUE			
Grid-No.1-Circuit Resistance—CCS or ICAS operation	0.1	megohm	
Class A, Amplifier			
CHARACTERISTICS			
•	10 5	volts	
Heater Voltage Plate Voltage	13.5 250	volts	
Grid No.3 Connected		at socket	
Grid-No.2 Voltage	250	volts	
Grid-No.1 Voltage	18 8.7	volts	
Mu-Factor, Grid No.2 to Grid No.1  Transconductance	5300	μmhos	
Plate Current	40	mA	
Grid-No.2 Current	3	mA	
AF Power Amplifier & Modulator—Class AB,   MAXIMUM CCS® RATINGS (Absolute-Maximum Values)			
DC Plate Voltage	375	volts	
Grid No.3 (Suppressor Grid)	0	volt	
DC Grid-No.2 (Screen-Grid) Voltage	300	volts	
MaxSignal DC Plate Current MaxSignal Plate Input	70 21	mA watts	
MaxSignal Grid-No.2 Input	2	watts	
Plate Dissipation	10	watts	
TYPICAL CCS PUSH-PULL OPERATION			
Values are for 2 tubes			
·	13.5	volts	
Heater Voltage DC Plate Voltage	300	volts	
	d to cathode		
DC Grid-No.2 Voltage§	250	volts	
DC Grid-No.1 Voltages	21	volts	
Peak AF Grid-No.1-to-Grid-No.1 Voltage	40 40	volts mA	
MaxSignal DC Plate Current	125	mA	
Zero-Signal DC Grid-No.2 Current	2	mA	
MaxSignal DC Grid-No.2 Current	14	mA	
Effective Load Resistance (Plate to plate)  MaxSignal Driving Power	5000 0	ohms watts	
Total Harmonic Distortion	5	%	
MaxSignal Power Output (Approx.)	20.5	watts	

# RF Power Amplifier & Oscillator—Class C Telegraphy? and RF Power Amplifier—Class C FM Telephony

MAXIMUM RATINGS (Absolute-Maximum Values)

	CCŠ•	ICAS••	
DC Plate Voltage	375	375	volts
Grid No.3 (Suppressor Grid)	0	0	volt

Un to 175 MHz

10011	TUDODAVANG	I ODD 10	ANUAD
DC Grid-No.2 (Screen-Grid) Voltage DC Grid-No.1 (Control-Grid) Voltage DC Plate Current DC Grid-No.2 Current DC Grid-No.1 Current Plate Input Grid-No.2 Input Plate Dissipation	300 	300 125 80 15 5 24 2	volts volts mA mA mA watts watts watts
TYPICAL OPERATION			
As amplifier at 175 M Heater Voltage DC Plate Voltage Grid No.3 DC Grid-No.1 Voltage DC Grid-No.1 Voltage Peak RF Grid-No.1 Voltage DC Plate Current DC Grid-No.2 Current DC Grid-No.1 Current (Approx.) Driver Power Output (Approx.) Useful Power Output (Approx.)*	CCS● 13.5 13.5 250 300 Connected 200 200 —40 —42 47 52 60 70 3.7 3.7 1.5 2.1 1 1 6.5 8.5	300 to cathode 250 —55 62 80 5.1 1.6 1.5	volts volts volts volts volts mA mA watts watts
Plate-Modulated RF Power Amplifie	r—Class C Te	elephony	
Carrier conditions per tube for use with a max			
MAXIMUM RATINGS (Absolute-Maximum Values)	Up to 175 CCS●	MHz ICAS••	
DC Plate Voltage Grid No.3 (Suppressor Grid) DC Grid-No.2 (Screen-Grid) Voltage DC Grid-No.1 (Control-Grid) oltage DC Plate Current DC Grid-No.2 Current DC Grid-No.1 Current Plate Input Grid-No.2 Input Plate Dissipation	300 0 300 125 60 10 5 15 1.4	300 0 300 	volts volt volts volts mA mA watts watts watts
TYPICAL OPERATION  Heater Voltage DC Plate Voltage Grid No.3 DC Grid-No.2 Voltage▲ DC Grid-No.1 Voltage▲ From a grid-No.1 resistor of RF Grid-No.1 Voltage DC Plate Current DC Grid-No.2 Current DC Grid-No.2 Current (Approx.) Driving Power (Approx.)▲▲ Useful Power Output*	At 175 13.5 250 Connected 250 —70 33000 75 60 2.5 2.1 1 6.5	MHz 13.5 250 to cathode 250 -75 33000 80 70 3 2.3 1 7.5	volts volts at socket volts volts ohms volts mA mA watt watts
Frequency Multip	lier		
MAXIMUM RATINGS (Absolute-Maximum Values)			
DC Plate Voltage Grid No.3 (Suppressor Grid) DC Grid-No.2 (Screen-Grid) Voltage DC Grid-No.1 (Control-Grid) Voltage DC Bate Current DC Grid-No.2 Current DC Grid-No.1 Current Plate Input Grid-No.2 Input Plate Dissipation	CCS• 375 0 300125 50 15 15 2 10	ICAS • • 375 0 300 125 60 15 5 15 2 12	volts volts volts volts mA mA watts watts
TYPICAL OPERATION As doubler to 175 MHz			
TYPICAL OPERATION  Heater Voltage DC Plate Voltage Grid No.3 DC Grid-No.1 Voltage DC Grid-No.1 Voltage From a grid-No.1 resistor of Peak RF Grid-No.1 Voltage	13.5 250 Connected 200 —53 53000 60	13.5 250 to cathode 250 66 44000 74	volts at socket volts volts ohms volts

DC Plate Current DC Grid-No.2 Current DC Grid-No.1 Current (Approx.) Driving Power (Approx.) Useful Power Output*	50 2.6 1 0.4 3	60 3.5 1.5 0.6 4.5	mA mA mA watt watts
As tripler to 175 MHz			
Heater Voltage	13.5	13.5	volts
DC Plate Voltage	200	250	volts
Grid No.3	Connected	to cathode	at socket
DC Grid No.2 Voltage	200	250	volts
DC Grid-No.1 Voltage⊕⊕	90	120	volts
From a grid-No.1 resistor of	50000	70000	ohms
Peak RF Grid-No.1 Voltage	105	130	volts
DC Plate Current	50	60	mA
DC Grid-No.2 Current	3	3.9	mA
DC Grid-No.1 Current (Approx.)	1.85	1.7	mA
Driving Power (Approx.)	0.4	0.6	watt
Useful Power Output*	1.4	2.3	watts


- Subscript 1 indicates that grid-No.1 current does not flow during any part of the input cycle.
- Continuous Commercial Service.
- •• Intermittent Commercial and Amateur Service.
- Averaged over any audio-frequency cycle of sine-wave form.
- † Key-down conditions per tube without amplitude modulation. Amplitude modulation essentially negative may be used if the positive peak of the audio-frequency envelope does not exceed 115% of the carrier conditions.
- § Obtained preferably from a fixed supply.
- Obtained preferably from a separate source or from the plate-voltage supply with a voltage divider. If a series resistor is used, it should be adjustable to obtain the desired operating plate current after initial tuning adjustments are completed.
- **Obtained from a grid-No.1 resistor or from a combination of grid-No.1 resistor with either fixed supply or cathode resistor.
- ▲▲Driver stage is required to supply tube losses and rf-circuit losses. The driver stage should be designed to provide an excess of power above the indicated values to take care of variations in line voltage, components, initial tube characteristics, and tube characteristics during life.
- Measured at load.
- ▲ Obtained preferably from a separate source modulated along with the plate supply, or from the modulated plate supply through a series resistor. It is recommended that this resistor be adjustable to obtain the desired operating plate current after initial tuning adjustments are made.
- * Obtained from a grid-No.1 resistor or from a combination of grid-No.1 resistor with either fixed supply or cathode resistor. The combination of grid-No.1 resistor and fixed supply has the advantage of not only protecting the tube from damage through loss of excitation but also of minimizing distortion by bias-supply compensation.

## Special Ratings & Performance Data

HEATER-CYCLING LIFE PERFORMANCE		
Cycles of Intermittent Operation	2000 min.	cycles
LOW-FREQUENCY VIBRATION PERFORMANCE		
RMS Output Voltage	200 max.	mV


## BEAM POWER TUBE


7558
INDUSTRIAL
TYPE



Miniature type for use as a class C radio-frequency amplifier, oscillator, and frequency-multiplier up to 175 MHz in mobile communications equipment. Outlines section, 6E; requires miniature 9-contact socket. This type is identical with type 7551 except for heater voltage and current. Special ratings and performance data for the 7551 do not apply to the 7558.

Heater	Voltage	 $6.3 \pm 5\%$	volts
Heater	Current	 0.8	ampere





## 7581A

## **BEAM POWER TUBE**


Glass octal type used in af power-amplifier applications. Outlines section, 19D; requires octal socket. For typical operation as push-pull class  $A_1$ , class  $AB_1$ , and class  $AB_2$  amplifier, refer to type 6L6GC. This tube, like other power-handling tubes, should be adequately ventilated. Heater: volts (ac/dc), 6.3; amperes, 0.9; maximum heater-cathode volts,  $\pm 200$ .

MAXIMUM RATINGS (Same as for Class At Amplifier)

TYPICAL OPERATION

Plate Voltage
Grid-No.1 Voltage

Peak AF Grid-No.1 Voltage



volts

#### Class A. Amplifier

MAXIMUM RATINGS (Design-Maximum Values) Plate Voltage Grid-No.2 (Screen-Grid) Voltage Plate Dissipation Grid-No.2 Input	Triode Connection* 450 — 35	Pentode Connectio 500 450# 35 5	
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.1 0.5	0.1 0.5	megohm megohm
Class A ₁ Amplifier (Pentode of MAXIMUM RATINGS (Same as for Class A ₁ Amplifier) TYPICAL OPERATION	•		
Plate Voltage Grid-No.2 Voltage Grid-No.1 Voltage Plate Resistance (Approx.)	70 300 0▲	$250 \\ 250 \\14 \\ 22500$	volts volts volts ohms
Transconductance Plate Current Grid-Mo.2 Current Load Resistance	210 25	6000 72 5 2500	μmhos mA mA ohms
Total Harmonic Distortion Maximum-Signal Power Output  Class A: Amplifier (Triode C	onnection)	10 6.5	per cent watts

Amplification Factor	8	
Plate Resistance (Approx.)	1700	ohms
Transconductance	4700	$\mu$ mhos
Zero-Signal Plate Current		mĄ
Maximum-Signal Plate Current	5000	mA ohms
Load Resistance Total Harmonic Distortion (Approx.)		per cent
Maximum-Signal Power Output		watts

^{*} Grid No.2 connected to plate.



## MEDIUM-MU TRIODE

7586
INDUSTRIAL

Nuvistor type, medium-mu general purpose triode for use as an amplifier or oscillator at frequencies extending into the UHF region. Outlines section, 1; requires nuvistor socket.

IZAU MUVISCOI SOCKEC.		
Heater Voltage (ac/dc) Heater Current Peak Heater-Cathode Voltage Direct Interelectrode Capacitance (Approx.):	0.135 ±100 max.	volts ampere volts
Grid to Plate Grid to Cathode, Heater, and Shell Plate to Cathode, Heater, and Shell Plate to Cathode Heater to Cathode		pF pF pF pF
Industrial Service		
MAXIMUM RATINGS (Absolute-Maximum Values)		
For operation at any altitu	de	
Plate Supply Voltage Plate Voltage Grid Voltage: Negative-bias value Peak-positive value		volts volts volts volts
Grid Current Cathode Current Plate Dissipation		mA mA watt
MAXIMUM CIRCUIT VALUES		
Grid-Circuit Resistance:  For fixed-bias operation  For cathode-bias operation		megohm megohm
• For operation at metal-shell temperature of 150°C. For operatures, see Grid-Circuit Resistance Rating Chart.	operation at other metal-s	hell tem-

## Class A. Amplifier

#### CHARACTERISTICS


		75	volts
26.5	40		volts
0	0	0	volt
		100	ohms
31	35	35	
0.5	.5	_	megohm
4400	3000	3000	ohms
7000	11500	11500	μmhos
2.8	7.5	10.5	· mA
-	_	-7	volts
	$0.\overline{5} \\ 4400 \\ 7000$	$\begin{array}{cccc} 0 & 0 \\ \hline 31 & 35 \\ 0.5 & .5 \\ 4400 & 3000 \\ 7000 & 11500 \end{array}$	$\begin{array}{cccccccccccccccccccccccccccccccccccc$


[#]In push-pull circuits where grid No.2 of each tube is connected to a tap on the plate winding of the output transformer, this maximum rating is 500 volts.

[▲] Applied for short interval (2 seconds) so as not to damage tube.

## Special Ratings & Performance Data

SHOCK RATING Peak Impact Acceleration	1000 max.	,
FATIGUE RATING	1000 111211	•
Peak Vibrational Acceleration	2.5 max.	g






7587 INDUSTRIAL TYPE	ARP-CUTOFF TETRODE		
Nuvistor type sharp-cutoff use in a wide variety of lines section, 1A1; require	general-purpose tetrode for industrial applications. Outes nuvistor socket.	INDEX + LARGE • + SHORT PE 12AS	E LUG N—IC
Heater Current	S:	$6.3 \pm 0.6$ $0.150$ $\pm 100 \text{ max}.$	volts ampere volts
Grid No.1 to Plate Grid No.1 to Cathode, Grid N Plate to Cathode, Grid No.2,	o.2, Shell, and Heater Shell, and Heater	0.015 max. 7.0 1.4 1.4	pF pF pF pF
MAXIMUM RATINGS (Absolute-N	Industrial Service taximum Values) For operation at any altitude		
Plate Voltage	Voltage	330 250 330 110	volts volts volts volts
Negative-bias value Peak-positive value Cathode Current Grid-No.1 Current Grid-No.2 Input		55 2 20 2 0.2 2.2	volts volts mA mA watt watts
MAXIMUM CIRCUIT VALUES  Grid-Circuit Resistance:		2.2	watts
For fixed-bias operation	mperature up to 150°C.	0.5 1	megohm megohm

#### Class A. Amplifier

CHARACTERISTICS		
Plate Supply Voltage	125	volts
Grid-No.2 Supply Voltage	50	volts
Cathode Resistor	68	ohms
Plate Resistance (Approx.)	0.2	megohm
Transconductance	10600	μmhos
Plate Current	10	· mA
Grid-No.2 Current	2.7	m A
Grid-No.1 Voltage (Approx.) for plate $\mu A = 10$	4.5	volts




#### Special Ratings & Performance Data

SHOCK RATING		
Impact Acceleration,	1000 max.	g
FATIGUE RATING		
Vibrational Acceleration	2.5 max.	g

Refer to chart at end of section.

7591



## **POWER PENTODE**

7591A

Glass octal type used as audio-frequency power-output tube in high-quality audio applications. Outlines section, 13D; requires octal socket. Heater: volts (ac/dc), 6.3; amperes, 0.8; maximum heater-cathode volts,  $\pm 200$  peak, 100 average.

### Class A, Amplifier

Class A, Ampliner		
MAXIMUM RATINGS (Design-Maximum Values)		
Plate Voltage Grid-No.2 (Screen-Grid) Voltage Cathode Current Plate Dissipation Grid-No.2 Input	550 440 90 19 3.3•	volts volts mA watts watts
TYPICAL OPERATION AND CHARACTERISTICS		
Plate Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage Peak AF Grid-No.1 Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current	300 300 	volts volts volts volts mA mA
Zero-Signal Grid-No.2 Current		mA

Maximum-Signal Grid-No.2 Current Triode Amplification Factor® Plate Resistance (Approx.) Transconductance Load Resistance Total Harmonic Distortion Maximum-Signal Power Output	29000 10200 3000 13	mA ohms µmhos ohms per cent watts
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation		megohm megohm

· Grid-No.2 input may reach 6 watts during peak levels of speech and music signals.

* Triode connection, grid No.2 connected to plate.

#### Push-Pull Class AB, Amplifier

#### MAXIMUM RATINGS (Same as for Class A₁ Amplifier)

TYPICAL OPERATION (Values are for two tubes)	Fixe	d Bias	Cathode Bias	
Plate Supply Voltage	350	450	450	volts
Grid-No.2 Supply Voltage	350	400	400	volts
Grid-No.1 Supply Voltage	-15.5	21	_	volts
Cathode-Bias Resistor				
(Common to both cathodes)		_	200	ohms
Peak AF Grid-No.1-to-Grid-No.1 Voltage	31	42	28	volts
Zero-Signal Plate Current	92	66	82	mA
Maximum-Signal Plate Current	130	144	94	mA
Zero-Signal Grid-No.2 Current	13	9.4	11.5	mA
Maximum-Signal Grid-No.2 Current	28.6	30	22	mA
Effective Load Resistance (Plate-to-plate)	6600	6600	9000	ohms
Total Harmonic Distortion	2	1.5	2	per cent
Maximum-Signal Power Output	30	45	28	watts

7695 Refer to chart at end of section.
7717/6CY5 Refer to chart at end of section.
7724/14GT8 Refer to chart at end of section.
7788 Refer to chart at end of section.

7868

## **POWER PENTODE**

Novar type used in output stages of high-fidelity audio amplifiers and radio receivers. Outlines section, 11C or 30D; requires novar 9-contact socket. This tube, like other power-handling tubes, should be adequately ventilated.



Heater Voltage (ac/dc)	6.3	volts
Heater Current	0.8	ampere
Heater-Cathode Voltage:		-
Peak value	±200 max	volts
Average value	100 max	volts
Direct Interelectrode Capacitances (Approx.):		
Grid No.1 to Plate	0.15	ρF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3	11	ρF
Plate to Cathode, Heater, Grid No.2, and Grid No.3	4.4	ή̈F


#### Class A, Amplifier

#### MAXIMUM RATINGS (Design-Maximum Values)

Plate Voltage Grid-No.2 (Screen-Grid) Voltage Average Cathode Current Plate Dissipation Grid-No.2 Input Bulb Temperature (At hottest point)	
---------------------------------------------------------------------------------------------------------------------------------------------	--

TYPICAL	OPERATION	AND	CHARACTERISTICS

ITTIONE OF ENATION AND OFFICE CONTROLLED		
Plate Supply Voltage	300	volts
Grid-No.2 Voltage	300	volts
Grid-No.1 (Control-Grid) Voltage	10	volts
Peak AF Grid-No.1 Voltage	10	volts
Zero-Signal Plate Current	60	mA
Maximum-Signal Plate Current	75	m A
Zero-Signal Grid-No.2 Current	8	mĄ
Maximum-Signal Grid-No.2 Current	15	mA
Plate Resistance (Approx.)	29000	ohms
Transconductance	10200	$\mu$ mhos
Effective Load Resistance	3000	ohms
Total Harmonic Distortion	13	per cent
Maximum-Signal Power Output	11	watts



#### MAXIMUM CIRCUIT VALUES

Grid-No.1-Circuit Resistance:

For fixed-bias operation

For cathode-bias operation

1 megohm

- In push-pull circuits where the grid No.2 of each tube is connected to a tap on the plate winding of the output transformer, this maximum rating is 440 volts.
- · Grid No.2 input may reach 6 watts during peak levels of speech and music signals.

### Push-Pull Class AB, Amplifier

MAXIMUM RATINGS (Same as for class A₁ amplifier)
TYPICAL OPERATION (Values are for two tubes)

		,				Cathode	!
			Fixe	d Bias		Bias	
Plate Supply Voltage	300	350	400	450	450	450	volts
Grid-No.2 Supply Voltage	300	350	350	350	400	400	volts
Grid-No.1 Voltage	12.5	15.5	16	16.5	21		volts
Cathode-Bias Resistor (Common							
to both cathodes)	_	-	_	_	-	170	ohms
Peak AF Grid-No.1-to-							
Grid-No.1 Voltage	25	31	32	33	42	31	volts
Zero-Signal Plate Current	14	72	64	60	40	86	mA
Maximum-Signal Plate Current	116	130	135	142	145	94	mA
Zero-Signal Grid-No.2 Current	10	9.5	8	7.2	5	10	mA
Maximum-Signal Grid-No.2							
Current	28	32	28	26	30	20	mA
Effective Load Resistance							
(Plate-to-plate)	6600	6600	6600	6600	6600	10000	ohms
Total Harmonic Distortion	5	2.5	2	2.5	5	2	per cent
Maximum-Signal Power Output	24	30	34	38	44	28	watts

#### Push-Pull Class AB, Amplifier

Grid No.2 of Each Tube Connected to Tap on Plate Winding of Output Transformer® MAXIMUM RATINGS (Same as for class A₁ amplifier)

TYPICAL OPERATION (Values are for two tubes)	Fixed Bias	Cathode Bias	
Plate Supply Voltage	400	425	volts
Grid-No.2 Supply Voltage	•	•	volts
Grid-No.1 Voltage	20.5	_	volts
Cathode-Bias Resistor (Common to both cathodes)	_	185	ohms

volts

1000 max.

25 max

Peak AF Grid-No.1-to-Grid-No.1 Voltage	41	42	volts
Zero-Signal Plate Current	60	88	mA
Maximum-Signal Plate Current	115	100	mA
Zero-Signal Grid-No.2 Current	8	12	m A
Maximum-Signal Grid-No.2 Current	18	16	mA
Effective Load Resistance (Plate-to-plate)	6600	6600	ohms
Total Harmonic Distortion	2.5	3.5	per cent
Maximum-Signal Power Output	23	21	watts

• Grid No.2 supply voltage is obtained from taps on the primary winding of the output transformer. The taps are located on each side of the center tap (B+) so as to apply 50 per cent of the plate signal voltage to the grid No.2 of each output tube.

7895 INDUSTRIAL

SHOCK RATING Impact Acceleration

FATIGUE RATING


## HIGH-MU TRIODE

Nuvistor type high-mu triode for use in a wide variety

INDEX=LARGE LUG of industrial applications. Outlines section, 1; requires . SHORT PIN-IC nuvistor socket. Heater Voltage (ac/dc)
Heater Current 6.3 ±10% wolta 0.135ampere Heater Current
Peak Heater-Cathode Voltage
Direct Interelectrode Capacitances (Approx.): ±100 max. volts Grid to Plate
Grid to Cathode, Shell, and Heater
Plate to Cathode, Shell, and Heater
Plate to Cathode 0.9 рF рF 4.2 1.7 ρF 0.22 Heater to Cathode pΓ Industrial Service MAXIMUM RATINGS (Absolute-Maximum Values) For operation at any altitude Plate Supply Voltage
Plate Voltage
Grid Voltage: 330 volts 110 volts Negative-bias value volts Peak-positive value ..... volts Grid Current  $\tilde{2}$ mA Plate Current mA Cathode Current mAPlate Dissipation watt MAXIMUM CIRCUIT VALUES Grid-Circuit Resistance:* For fixed-bias operation megohm For cathode-bias operation megohm * For operation at metal-shell temperature up to 150°C. Class A. Amplifier CHARACTERISTICS Plate Supply Voltage
Grid Supply Voltage
Cathode Resistor 110 volts volts 15Ŏ ∩hma Amplification Factor 64 Plate Resistance (Approx.) 6800 ohms Transconductance 9400 μmhos Plate Current
Grid Voltage (Approx.) for plate  $\mu A = 10$  ...... mA

Special Ratings & Performance Data

Vibrational Acceleration .....



Refer to chart at end of section.

7898



#### **BEAM POWER TUBE**

7905

Miniature quick-heating-filament beam power tube for use as an RF oscillator, amplifier and frequency multiplier in mobile communications equipment. Outlines section, 6E; requires miniature 9-contact socket.

9PB

CHARACTERISTICS

Operating Position Vertical, base up or down, or Horizontal with pins 2 and 8 in vertical plane Filament Voltage Filament Current Heating Time Direct Interelectrode Capacitances: Grid No.1 to Flate Grid No.1 to Filament, Grid No.3, and Grid No.2 Plate to Filament, Grid No.3, and Grid No.2 Bulb Temperature (At hottest point on bulb surface)	6.3 ±10% 0.65 Less than 0.14 max. 8.5 5.5 225 max.	ampere
MAXIMUM CIRCUIT VALUES Grid-No.1-Circuit Resistance	0.1	megohm

#### Class A. Amplifier

Plate Voltage Grid No.3 Connected Grid-No.2 Voltage	l to pin 1 at sock	et
Grid-No.1 Voltage Mu-Factor, Grid No.2 to Grid No.1	—6 vol	ts
Transconductance Plate Current Grid-No.2 Current	6700 μmh 36 m 2.5 m	

#### RF Power Amplifier & Oscillator—Class C Telegraphy^a and RF Power Amplifier—Class C FM Telephony

#### MAXIMUM ICAS^b RATINGS (Absolute-Maximum Values)


	Ur	) to 175 MHz	
DC Plate Voltage		300	volts
Grid No.3 (Suppressor Grid)	Connect	to pin 1 a	t socket
DC Grid-No.2 (Screen-Grid) Supply Voltage		300	volts
DC Grid-No.2 Voltage		250	volts
DC Grid-No.1 (Control-Grid) Voltage		125	volts
DC Plate Current		60	mĄ
DC Grid-No.2 Current		10	mA


DC Grid-No.1 Current		5	mA
Plate Input		18	watts
Grid-No.2 Input		1.5	watts
Plate Dissipation		10	watts
TVDICAL IGACI: ODEDATION:			
TYPICAL ICAS OPERATION			
As amplifier at 175 MHz			
DC Plate Voltage	300	300	volts
Grid No.3 DC Grid-No.2 Voltage ^d DC Grid-No.1 Voltage ^e from a grid-No.1 resistor of 18,000 ohms Deb. Deb. Co. in No.1, Voltage	Connected	to pin 1	at socket
DC Grid-No.1 Voltage ^e from a grid-No.1 resistor of	160	185	volts
18,000 ohms		39	volts
Peak RF Grid-No.1 Voltage DC Plate Current	41	43	volts
DC Grid-No.2 Current	$\frac{50}{2.5}$	60 4	mA mA
DC Grid-No.1 Current (Approx.)	2.0	2.2	mA
Driving Power ^t (Approx.)	1	1	watt
Useful Power Outputs (Approx.)	5.5	7	watts
Plate-Modulated RF Power Amplifier(	Class C Telo	ephony	
Carrier conditions per tube for use with a maximu			
•			
MAXIMUM ICAS ^b RATINGS (Absolute-Maximum Values)			
		to 175 MH	
DC Plate Voltage	Connect	250	volts
Orid No.3 DC Grid-No.2 Voltage DC Grid-No.1 Voltage	Connect	250 pin 1	volts
DC Grid-No.1 Voltage		-125	volts
DC Plate Current		60	mA
DC Grid-No.2 Current DC Grid-No.1 Current		10	mA mA
Plate Input		5 15	watts
Grid-No.2 Input		1.4 7	watts
Plate Dissipation		7	watts
TYPICAL ICAS OPERATION			
no ni . Tri		At 175 MH	
DC Plate Voltage Grid No.3	Coppost	250	volts
DC Grid-No.2 Voltageh	·····	250	volts
Orid No.3 DC Grid-No.2 Voltageh DC Grid-No.1 Voltagee from a grid-No.1 resistor of 33,000	ohms	70	volts
Peak RF Grid-No.1 Voltage		75 60	voits
DC Grid-No 2 Current		2.5	mA mA
DC Grid-No.1 Current (Approx.)		2.1	mA
DC Grid-No.1 Voltage Prom a grid-No.1 resistor of 35,000 Peak RF Grid-No.1 Voltage DC Plate Current DC Grid-No.2 Current DC Grid-No.1 Current (Approx.) Driving Power (Approx.)		1	watt
Useful Power Outputs (Approx.)		6.5	watts
Frequency Multiplier			
MAXIMUM ICAS ^b RATINGS (Absolute-Maximum Values)			
DC Plate Voltage		300	volts
Grid No.3 DC Grid-No.2 Supply Voltage DC Grid-No.2 Voltage DC Grid-No.1 Voltage	Connected	to pin 1	at socket
DC Grid-No.2 Supply Voltage		300	volts
DC Grid-No.1 Voltage		250 —125	volts
DC Plate Current	· · · · · · · · · · · · · · · · · · ·	123 50	mA
DC Plate Current DC Grid-No.2 Current DC Grid-No.1 Current		10	mA
DC Grid-No.1 Current		5 15	mA watts
Plate Input Grid-No.2 Input		1.5	watts
Plate Dissipation		10	watts
TYPICAL ICAS' OPERATION			
TYPICAL ICAS ^b OPERATION ^c As doubler to 175 MHz			
As doubler to 175 MHz		300	volts
As doubler to 175 MHz	250	300 to pin 1	volts at socket
As doubler to 175 MHz	250	300 to pin 1 : 215	
As doubler to 175 MHz  DC Plate Voltage Grid No.3  DC Grid-No.1 Voltage ^d DC Grid-No.1 Voltage ^e from a grid-No.1 resistor of	250 Connected 200	to pin 1 : 215	at socket volts
As doubler to 175 MHz  DC Plate Voltage Grid No.3  DC Grid-No.1 Voltage ^d DC Grid-No.1 Voltage ^e from a grid-No.1 resistor of	250 Connected 200 —53	to pin 1 : 215 —80	at socket
As doubler to 175 MHz  DC Plate Voltage Grid No.3  DC Grid-No.1 Voltage ^d DC Grid-No.1 Voltage ^e from a grid-No.1 resistor of	250 Connected 200 53 60 45	to pin 1 : 215 —80 87 50	at socket volts volts volts mA
As doubler to 175 MHz  DC Plate Voltage Grid No.3  DC Grid-No.1 Voltage ^d DC Grid-No.1 Voltage ^e from a grid-No.1 resistor of	250 Connected 200 53 60 45 3.4	to pin 1 : 215 80 87 50 3.4	at socket volts volts volts mA mA
As doubler to 175 MHz  DC Plate Voltage Grid No.3  DC Grid-No.2 Voltage ^d DC Grid-No.1 Voltage ^e from a grid-No.1 resistor of 53,000 ohms Peak RF Grid-No.1 Voltage  DC Plate Current DC Grid-No.2 Current DC Grid-No.1 Current (Approx.)	250 Connected 200 53 60 45 3.4	to pin 1 : 215 80 87 50 3.4 1.5	volts volts volts mA mA
As doubler to 175 MHz  DC Plate Voltage Grid No.3  DC Grid-No.1 Voltage ^d DC Grid-No.1 Voltage ^e from a grid-No.1 resistor of	250 Connected 200 53 60 45 3.4	to pin 1 : 215 80 87 50 3.4	at socket volts volts volts mA mA

#### As tripler to 175 MHz

DC Plate Voltage Grid No.3 DC Grid-No.2 Voltage ^d	250 Connected 180	250 to pin 225	volts 1 at socket volts
DC Grid-No.1 Voltage from a grid-No.1 resistor of:			
50,000 ohms	90		volts
60,000 ohms		-108	volts
Peak RF Grid-No.1 Voltage	105	118	volts
DC Plate Current	40	50	mA
DC Grid-No.2 Current	2.5	3.4	mA
DC Grid-No.1 Current (Approx.)	1.8	1.8	mA
Driving Power ^f (Approx.)	0.4	0.6	watt
Useful Power Outputs (Approx.)	1.4	2	watts

- * Key-down conditions per tube without amplitude modulation. Amplitude modulation essentially negative may be used if the positive peak of the audio-frequency envelope does not exceed 115 per cent of the carrier conditions.
- b Intermittent Commercial and Amateur Service.
- c Pins 4 and 5 at rf ground.
- Obtained preferably from a separate source or from the plate-voltage supply with a voltage divider. If a series resistor is used, it should be adjustable to permit obtaining the desired operating plate current after initial tuning adjustments are completed.
- Obtained from a grid-No.1 resistor, or from a combination of grid-No.1 resistor and either fixed supply or cathode resistor. The combination of grid-No.1 resistor and fixed supply has the advantage of not only protecting the tube from damage through loss of excitation but also of minimizing distortion by bias-supply compensation.
- ^t Driving power includes circuit losses and is the actual power measured at the input to the grid circuit.
- g Measured at load.
- h Obtained preferably from a separate source modulated along with the plate supply, or from the modulated plate supply through a series resistor. It is recommended that this resistor be adjustable to permit obtaining the desired operating plate current after initial tuning adjustments are made.





## **MEDIUM-MU TRIODE**

8056
INDUSTRIAL

Nuvistor type, medium-mu triode for use in low voltage industrial applications. Outlines section, 1; requires nuvistor socket.

Heater Voltage (ac/dc)	$6.3 \pm 0.6$	volts
Heater Current	0.135	ampere
Peak Heater-Cathode Voltage	$\pm 100$	volts

Direct Interelectrode Capacitances (Approx.): Grid to Plate Grid to Cathode, Shell, and Heater Plate to Cathode, Shell, and Heater Plate to Cathode Heater to Cathode		2.1 4.0 1.7 0.34 1.4	pF pF pF pF
Industrial Service			
MAXIMUM RATINGS (Absolute-Maximum Values)  For operation at any altitue	de		
Plate Voltage		50	volts
Grid Voltage: Negative-bias value Peak-positive value Grid Current Cathode Current Plate Dissipation		55 <b>2</b> 2 15 0.45	volts volts mA mA watt
TYPICAL OPERATION			
Plate Supply Voltage Grid Supply Voltage Grid Resistor Amplification Factor Plate Resistance (Approx.) Transconductance Plate Current	12 33000 12 1500 8000 5.5	24 0.7  12 1500 8000 9.5	volts volt ohms ohms µmhos mA
MAXIMUM CIRCUIT VALUES			
Grid-Circuit Resistance:*  For fixed-bias operation  For cathode-bias operation		10 10	megohms megohms

For operation at metal-shell temperatures up to 150°C. For operation at other metal-shell temperatures, see Grid-Circuit Resistance Rating Chart.

#### Class A, Amplifier

#### CHARACTERISTICS

	24 volts
Connected to negative	end of cathode resistor
	100 o <b>hms</b>
	1530 ohms
	7500 $\mu$ mhos
	8.7 mA
	—5 volts
	Connected to negative


#### **Special Ratings & Performance Data**


#### SHOCK RATING

Impact Acceleration 1000 max.

#### **FATIGUE RATING**


Vibrational Acceleration 2.5 max.





Refer to chart at end of section.

8058



## **POWER PENTODE**

Miniature type for use as a class C radio-frequency amplifier, oscillator and frequency multiplier up to 40 MHz in mobile communications equipment. Outlines section, 6B; requires miniature 9-contact socket.

Heater Voltage Heater Current Peak Heater-Cathode Voltage Direct Interelectrode Capacitances (Approx.): Grid No.1 to Plate Grid No.1 to all other Electrodes except Plate Plate to all other Electrodes except Grid No.1	$13.5 \pm 1.5$ $0.275$ $\pm 120$ max. $0.063$ $10.2$ $3.5$	volts ampere volts pF pF
Class A ₁ —AF Power Amplifier		
MAXIMUM RATINGS (Absolute-Maximum Values)		
Plate Voltage Grid-No.3 (Suppressor Grid) Conn Grid-No.2 (Screen-Grid) Voltage Grid-No.1 (Control-Grid) Voltage:	330 ected to cathode 180	volts at socket volts
Negative-bias value Positive-bias value Grid-No.2 Input Plate Dissipation	55 0 1 5	volts volt watt watts
MAXIMUM CIRCUIT VALUES		
Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation	0.1 0.25	megohm megohm
CHARACTERISTICS		
Heater Voltage Plate Supply Voltage	13.5 250	volts volts
Grid No.3	ected to cathode	at socket
Cathode Resistor	120	ohms
Plate Resistance (Approx.) Transconductance	$0.1 \\ 11500$	megohm µmhos
Plate Current	11900	mA
Grid-No.2 Current	3.5	mA
Grid-No.1 Voltage (Approx.) for plate $\mu A = 20$	10	volts

#### RF Power Amplifier & Oscillator-Class C Telegraphy* and RF Power Amplifier—Class C FM Telephony

#### MAXIMUM CCS^b RATINGS (Absolute-Maximum Values)

DC Plute Voltage		300 volts
DC Grid No.3 (Suppressor-Grid)	Connected	to cathode at socket
DC Grid-No.2 (Screen-Grid) Voltage		175 volts
DC Grid-No.1 (Control-Grid) Voltage:		
Negative-bias value		50 volts
DC Plate Current		33 mA
DC Grid-No,2 Current		5.5 mA
DC Grid-No.1 Current		3 mA
Grid-No.2 Input		1 watt
Plate Dissipation		5 watts

#### TYPICAL OPERATION

#### At frequencies up to 40 MHz

DC Plate Voltage	200		300	
Grid No.3			cathode :	at socket
DC Grid-No.2 Voltage	115	145	175	volts
DC Grid-No.1 Voltage	7	3	12	volts

0.1

megohm

Peak RF Grid-No.1 Voltage	9	11	16	volts
DC Plate Current	14.5	20	26	mA
DC Grid-No.2 Current	3	4.1	5.5	mA
DC Grid-No.1 Current (Approx.)		0.85	1	mA
MAXIMUM CIRCUIT VALUE				
Grid-No 1-Circuit Resistance			0.1	megohm

### Frequency Multiplier

MAXIMUM CCS^b RATINGS (Absolute-Maximum Values)

Same as for RF POWER AMPLIFIER & OSCILLATOR

#### TYPICAL OPERATION


#### As doubler up to 40 MHz

DC Plate Voltage	200	250	300	volts
Grid No.3	Conn	rected	to cathode	at socket
DC Grid-No.2 Voltage	115	145	175	volts
DC Grid-No.1 Voltage	16	20	25	volts
Peak RF Grid-No.1 Voltage	19	24	31	volts
DC Plate Current	11	15	20	mA
DC Grid-No.2 Current	2	3	4	mA
DC Grid-No.1 Current (Approx.)	0.3	0.45	0.6	mA
Driving Power (Approx.)	5	9	13	$\mathbf{m}\mathbf{W}$
Useful Power Output (Approx.)	1.4	1.9	2.5	watts

#### MAXIMUM CIRCUIT VALUE Grid-No.1-Circuit Resistance

* Key-down conditions per tube without amplitude modulation. Amplitude modulation essentially negative may be used if the positive peak of the audio-frequency envelope does not exceed 115 per cent of the carrier conditions.

⁶ Continuous Commercial Service.



# 8106 INDUSTRIAL

## **BEAM POWER TUBE**

Miniature type for use as a frequency multiplier and driver in mobile communications equipment. Outlines section, 6B; requires miniature 9-contact socket.

H 5 6 K, G3
623
K,G3 2 8 G2
P (1) (8) K,G3
9PL

Heater Voltage	$13.5 \pm 1.5$	volts
Heater Current Peak Heater-Cathode Voltage	$0.25 \pm 100 \text{ max.}$	ampere volts

Direct Interelectrode Capacitances:		
Grid No.1 to Plate	0.09	pF
Grid No.1 to Cathode, Heater, Grid No.2, and Grid No.3	10	pF
Plate to Cathode, Heater, Grid No.2, and Grid No.3	2.8	pF
Class A ₁ Amplifier		
MAXIMUM RATINGS (Absolute-Maximum Values)		
Plate Voltage	330	volts
Grid-No.2 (Screen-Grid) Voltage	300	volts
Grid-No.1 Voltage	-125	volts
Plate Dissipation	6.0	watts
Grid-No.1 Current	3.0	mĄ
Cathode Current	40	mA
TYPICAL OPERATION AND CHARACTERISTICS		
Plate Voltage	300	volts
Grid-No.2 Voltage	150	volts
Grid-No.1 (Control-Grid) Voltage	-3.5	volts
Plate Resistance (Approx.)	90000	ohms
Fransconductance	9000	$\mu$ mhos
Plate Current	16	mĄ
Grid-No.2 Current	3.2	mA
Grid-No.1 Voltage (Approx.) for plate $\mu A = 100$	—8	volts

Refer to chart at end of section.	8136
Refer to chart at end of section.	8203
Refer to chart at end of section.	8233



## 12AQ


## MEDIUM-MU TRIODE

8393

Nuvistor type, medium-mu general purpose triode for use as an amplifier or oscillator at frequencies extending into the UHF region. Outlines section, 1; requires nuvistor socket. The 8393 is the same as the 7586 ex-

Heater Voltage (ac/dc)	$13.5 \pm 1.4$	volts
Heater Current	0.060	ampere
Peak Heater-Cathode Voltage	$\pm 100$ max.	volts
Direct Interelectrode Capacitance (Approx.):		
Grid to Plate	2.4	рF
Grid to Cathode, Heater, and Shell		pF
Plate to Cathode, Heater, and Shell	1.6	pF
Plate to Cathode	0.26	pF
Heater to Cathode	1.7	pF

cept for the following items:



### **BEAM POWER TUBE**

8417

Glass octal type used as output amplifier in high-fidelity, high-power sound systems. Outlines section, 19J; requires octal socket. This tube, like other power-handling tubes, should be adequately ventilated. Heater: volts (ac/dc), 6.3; amperes, 1.6; maximum heater-cathode volts,  $\pm 200$  peak, 100 average.

Class A ₁ Amplifier MAXIMUM RATINGS (Design-Maximum Values)			
Plate Voltage Grid-No.2 (Screen-Grid) Voltage Cathode Current Plate Dissipation Grid-No.2 Input		660 500 200 35 5*	volts volts mA watts watts
CHARACTERISTICS			
Plate Voltage Grid-No.2 Voltage Grid-No.1 (Control-Grid) Voltage Grid-No.1 Voltage for plate current of 1 mA Plate Resistance Transconductance Plate Current Grid-No.2 Current Triode Amplification Factor		300 300 —12 —37 16000 23000 100 5.5 16.5	volts volts volts ohms μmhos mA mA
MAXIMUM CIRCUIT VALUES			
Grid-No.1-Circuit Resistance: For fixed-bias operation For cathode-bias operation		1 0.25	megohm megohm
Push-Pull Class AB, Ampli	fier		
MAXIMUM RATINGS (Same as for Class A ₁ Amplifier)			
TYPICAL OPERATION (Values are for two tubes)			
Plate Supply Voltage Grid-No.2 Supply Voltage Grid-No.1 Voltage Peak AF Grid-to-Grid Voltage Zero-Signal Plate Current Maximum-Signal Plate Current Zero-Signal Grid-No.2 Current Maximum-Signal Grid-No.2 Current Effective Load (Plate-to-Plate) Total Harmonic Distortion	400 275 —13 24 150 294 4.4 34 2800	560 300 15.5 31 100 270 3.4 31 4200	volts volts volts volts mA mA mA ohms
Total Harmonic Distortion  Maximum Signal Power Output	2.5 65	100 2	per cent watts

A bias resistor or other means is required to protect the tube in absence of excitation.

^{*} Grid-No.2 may reach 8 watts during peak levels of speech and music levels.

8532	Refer to chart at end of section.
8532/6J4WA	Refer to chart at end of section.
8532W	Refer to chart at end of section.
8627	Refer to chart at end of section.
8627A	Refer to chart at end of section.
8628	Refer to chart at end of section.
8808	Refer to chart at end of section.
8950	Refer to chart at end of section.
9001	Refer to chart at end of section.
9002	Refer to chart at end of section.
9003	Refer to chart at end of section.
9005	Refer to chart at end of section.
9006	Refer to chart at end of section.

Refer to type 1S2A/DY87.	DY87
Refer to type 6AK8/EABC8.	EABC80
Refer to type 6DC8/EBF89.	EBF89
Refer to type 6DL4/EC88.	EC88
Refer to type 6FY5/EC97.	EC97
Refer to type 12AT7/ECC81.	ECC81
Refer to type 12AU7A/ECC82.	ECC82
Refer to type 12AX7A/ECC83.	ECC83
Refer to type 6AQ8/ECC85.	ECC85
Refer to type 6ES8/ECC189.	ECC189
Refer to type 6BL8/ECF80.	ECF80
Refer to type 6HG8/ECF86.	ECF86
Refer to type 6X9/ECF200.	ECF200
Refer to type 6U9/ECF201.	ECF201
Refer to type 6GJ7/ECF801.	ECF801
Refer to type 6JW8/ECF802.	ECF802
Refer to type 6BM8/ECL82.	ECL82
Refer to type 6DX8/ECL84.	ECL84
Refer to type 6GV8/ECL85.	ECL85
Refer to type 6GW8/ECL86.	ECL86
Refer to type 6AM6/EF91.	EF91
Refer to type 6BA6/EF93.	EF93
Refer to type 6AK5/EF95.	EF95
Refer to type 6EH7/EF183.	€F183
Refer to type 6EJ7/EF184.	EF184
Refer to type 6X9/EFL200.	EFL200
Refer to type 6CA7/EL34.	EL34
Refer to type 6BQ5/EL84.	EL84
Refer to type 6CW5/EL86.	EL86
Refer to type 6DL5/EL95.	EL95
Refer to type 6GB5/EL500.	*EL500

PCL84

EL509	Refer to type 6KG6A/EL509.
ELL80	Refer to type 6HU8/ELL80.
EM84 EM84/6GFG6	Refer to chart at end of section.
EM87	Refer to type 6HU6/EM87.
EY88	Refer to type 6AL3/EY88.
EY500	Refer to type 6EC4A/EY500.
GZ34	Refer to type 5AR4/GZ34.
HCC85	Refer to type 17EW8/HCC85.
LCF80	Refer to type 6LN8/LCF80.
LCF86	Refer to type 5HG8/LCF86.
LCF201	Refer to type 5U9/LCF201.
LCF801	Refer to type 5GJ7/LCF801.
LCF802	Refer to type 6LX8/LCF802.
LCL84	Refer to type 10DX8/LCL84.
LCL85	Refer to type 10GV8/LCL85.
LF183	Refer to type 4EH7/LF183.
LF184	Refer to type 4EJ7/LF184.
LFL200	Refer to type 11Y9/LFL200.
LL86	Refer to type 10CW5/LL86.
LL500	Refer to type 18GB5/LL500.
LY88	Refer to type 20AQ3/LY88.
PC900	Refer to type 4HA5/PC900.
PCC85	Refer to type 9AQ8/PCC85.
PCC88	Refer to type 7DJ8/PCC88.
PCF80	Refer to type 9A8/PCF80.
PCF86	Refer to type 7HG8/PCF86.
PCF801	Refer to type 8GJ7/PCF801.
PCF802	Refer to type 9JW8/PCF802.
PCL82	Refer to type 16A8/PCL82.

Refer to type 15DQ8/PCL84.

Refer to type 6GV8/PCL85.	PCL85
Refer to type 25E5/PL36.	PL36
Refer to type 15CW5/PL84.	PL84
Refer to type 27GB5/PL500.	PL500
Refer to type 40KG6A/PL509.	PL509
Refer to type 29KQ6/PL521.	PL521
Refer to type 17Z3/PY81.	PY81
Refer to type 30AE3/PY88.	PY88
Refer to type 42EC4A/PY500.	PY500
Refer to type 50BM8/UCL82.	UCL82
Refer to type 4ES8/XCC189.	XCC189
Refer to type 4BL8/XCF80.	XCF80
Refer to type 4GJ7/XCF801.	XCF801
Refer to type 9GV8/XCL85.	XCL85
Refer to type 3EH7/XF183.	XF183
Refer to type 3EJ7/XF184.	XF184
Refer to type 8CW5/XL86.	XL86
Refer to type 13GB5/XL500.	XL500
Refer to type 16AQ3/XY88.	XY88
Refer to type 5ES8/YCC189.	YCC189

## Characteristics Entertainment and Industrial

Key to Chart: Type numbers shown in light face are discontinued types. Type numbers shown in bold face are available for replacement use, but are not recommended for new equipment design. Outline numbers refer to diagrams shown in

RCA Type	Name	Out- line	Terminal Dia- gram	Hea	ter or ent (F)	Use Values to right give operating conditions and characteristics for indicated typical us
				Volts	Ampere	- \$
OA2WA+	Glow-Discharge Tube	5D	5B0			Voltage Regulator
OA3A+	Glow-Discharge Tube	22 13C	4AJ			Voltage Regulator
OA4A+	Gas-Triode	22	4V			Relay Circuits
OB2WA+	Glow-Discharge Tube	5D	5B0			Voltage Regulator
0C2+	Glow-Discharge Tube	50	5B0			Voltage Regulator
OC3A+	Glow-Discharge Tube	13C	4AJ			Voltage Regulator
OD3A+	Glow-Discharge Tube	13C	4AJ			Voltage Regulator
0Z4	Full-Wave Gas Rectifier	2A	4R			Rectifier
0Z4G	Full-Wave Gas Rectifier	29D	4R			Rectifier
1A3	Diode	50	5AP	1.4	0.15	Rectifier
1A4P	Remote-Cutoff Pentade	24B	4M	2.0F	0.06	Class A Amplifier
1A5GT	Power Pentode	13D	6X	1.4F	0.05	Class A Amplifier
1A6	Pentagrid Converter	24B	8L	2.0F	0.06	Converter
1A7GT	Pentagrid Converter	14A	72	1.4F	0.05	Converter
1AC5	Power Converter	29A	8CP	1.25F	0.04	Class A Amplifier
★1AD2	Half-Wave Rectifier	9A	12 <b>GV</b>	1.25F	0.2	Pulsed Rectifier in TV Receivers
1AD5	Sharp-Cutoff Pentode	29A	SCP	1.25F	0.04	Class A Amplifier
1AX2	Half-Wave Rectifier	7A	9Y	1.4F	0.65	Pulsed Rectifier in TV Receivers
★1AY2	Half-Wave Rectifier	33A	1AY2	1.25F	0.2	Pulsed Rectifier in TV Receivers
★1B3GT	Half-Wave Rectifier	14E	3C	1.25F	0.2	Pulsed Rectifier in TV Receivers
1B4P	Sharp-Cutoff Pentode	24B	4 <b>M</b>	2.0F	0.06	Class A Amplifier
185/ To 25\$	win Diode—Medium-Mu Triode	22 or 13H	6M	2.0F	0.06	Triode Unit as Class A Amplifier
1B7GT	Pentagrid Converter	14A	72	1.4F	0.10	Converter
♦ Industrial	type	♣ See	Safety Pre	cautions at	t end of	this section.

[♦] Industrial type

[★] See Safety Precautions at end of this section.

## Chart for RCA Receiving Tubes

the Outlines section in the Manual (see Table of Contents on page two. Terminal diagrams are included in numerical-alphabetical order in Terminal Diagram section. (See Table of Contents).

	Grid Bias		Screen					Pov	Power		
Plate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Plate Cur- rent	AC Plate Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Load	Out- put	RCA Type	
Voits		Volts	mA	mΑ	Ohms	Micromhos		Ohms	Watts		
		For	other c	haracteri	istics, refe	r to Type O	A2			OA2WA	
75				5-40			_			OA3+ OA3A+	
130				25						OA4A+	
		For	other c		istics, refe	r to Type OI	B2			OB2WA*	
75				5-30						0C2+	
		For	other c		istics, refe	r to Type O	C3		-	OC3A+	
	<del></del>	For	other c	haracteri	istics, refe	r to Type Ol	03			OD3A+	
Start DC 0	ing-Supply Volta	age per Pla	te. 300	min. pea		Peak	Plate Curr	ent, 200 max ige, 300 max	. mA . volts	0Z4	
Start DC 0	ing-Supply Volta utput Current,	age per Pla 75 max., 30	ite, 300 ) min. m	min, pea A	k volts	DC O	utput Volta	ent, 200 max ige, 300 max		OZ4G	
	Max. Peak Pla Max. Peak Pla		Volts, 3	330			DC Output Peak Heati	mA, 0.5 er-Cathode V	olts. 140	1 <b>A</b> 3	
	man, tout the		other ch	aracteris	tics, refer	to Type 1D5				1A4P	
85 90	4.5V 4.5V	85 90	0.7 1.1	3.5 4.0	300000 300000	800 850		25000 25000	0.100 0.115	1A5GT	
135 1 <b>80</b>	— 3V — 3V	67.5 67.5	2.5 2.4	1.2 1.3	400000 500000	Anode-G 2.3 mA (	rid (2): 180 Oscillator-0	) max. volts Grid (1) Resi	stor.	1 <b>A6</b>	
90	0٧	45	0.7	0.6	600000	Oscillat	or-Grid (1)	volts, 1.2 n Resistor, 0. ond., 250 mi	2 ΜΩ	1A7GT	
45 67.5	— 3V — 4.5V	45 67.5	0.2 0.4	1.0 2.0	170000 150000	600 750		40000 25000	0.015 0.050	1AC5	
	Max. Peak I Max.	nverse Pla Peak Plate				Ма	x. Average	Plate mA,	0.5	1AD2	
30 67.5	0V 0V	30 67.5	0.16 0.75	0.45 1. <b>8</b> 5	700000 700000	430 735				1AD5	
Max.	Peak Inverse P Peak Plate mA.	iate Volts,	25000			Max.	Average Pl	ate mA, 0.5		1AX2	
	Max. Peak I					Max.	Average P	late mA, 0.5		1AY2	
	Peak Inverse P Peak Plate mA,		26000			Max.	Average Pl	ate mA, 0.5		1B3GT	
		For	r other o	haracter	istics, refe	r to Type 1E	5GP			1 <b>B4P</b>	
		Fo	r other o	haracter	istics, refe	er to Type 1	16G			1B5/ 25\$	
		Fo	r other o	haracter	istics, refe	er to Type 1A	A7GT			1B7GT	

	Name	Out- line	Terminal Dia- gram	Heater or Filament (F)		Use Values to right give oper ing conditions and charact istics for indicated typical u	
				Volts	Amperes	-	
★1BC2	Half-Wave Rectifier	7E	9RG	1.25	0.2	Pulsed Rectifier in TV Receivers	
★1BH2 <b>★1BH2A</b>	Half-Wave Rectifier	76	9RG	1.25	0.2	Flyback Rectifier in TV Receivers	
1C5GT	Power Pantode	13D	6X	1.4F	0.10	Class A Amplifier	
1C6	Pentagrid Converter	24B	6L	2.0F	0.12	Converter	
1C7G	Pentagrid Converter	23	7Z	2.0F	0.12	Converter	
1C21 +	Gas-Triode	13J	4٧			Relay Circuits	
1D5GP	Remote-Cutoff Pentode	23	5Y	2.0F	0.06	Class A Amplifier	
1D5GT	Remote-Cutoff Tetrode	23	5R	2.0F	0.06	Class A Amplifier	
1D7G	Pentagrid Converter	23	72	2.0F	0.06	Converter	
1D8GT	Diode-Triode-Power Pentode	14A	8AJ	1.4F	0.10	Pentode Unit as Class A Amplifier	
						Triode Unit as Class A Amplifier	
★1DG3	Half-Wave Rectifier	<b>14</b> J	8ND	1.25F	0.2	Pulsed Rectifier in TV Receivers	
IDN5 D	iode—Semiremote-Cutoff Pentode	5C	6BW	1.4F	0.5	Pentode Unit as Class A Amplifier	
1E5GP	Sharp-Cutoff Pentode	23	5Y	2.0F	0.06	Class A Amplifier	
1E7GT	Twin Power Pentode	13D	8C	2.0F	0.24	Class A Amplifier	
1E8	Pentagrid Converter	29A	8CN	1.25F	0.04	Converter	
1F4	Power Pentode	26	5K	2.0F	0.12	Class A Amplifier	
1F5G	Power Amplifier Pentode	25	6X	2.0F	0.12	Class A Amplifier	
1F6 T	win Diode—Sharp-Cutoff Pentode	23	6W	2.0F	0.06	Pentode Unit as Class A Amplifier	
1F7G T	win Diode—Sharp-Cutoff Pentode	23	7AF	2.0F	0.06	Pentode Unit as Class A Amplifier	
★1G3GT/ 1B3GT	Half-Wave Rectifier	14B	3C	1.25F	0.2	Pulsed Rectifier in TV Receivers	
1G4GT	Medium-Mu Triode	13D	58	1.4F	0.05	Class A Amplifier	
1G5G	Power Pentode	25	6X	2.0F	0.12	Class A Amplifier	
IG6GT	High-Mu Twin Power Triode	13D	7AB	1.4F	0.10	Class B Amplifier	
1H4G	Medium-Mu Triode	22	5\$	2.0F	0.06	Class A Amplifier Class B Amplifier	
1H5GT	Diode—High-Mu Triode	14A	5Z	1.4F	0.05	Triode Unit as Class A Amplifier	
	Twin Diode—Medium-Mu Triode	22	7AA	2.0F	0.06	Triode Unit as Class A Amplifier	
<b>★</b> 1J3	Half-Wave Rectifier	14E	3C	1.25F	0.2	Pulsed Rectifier in TV Receivers	
1J5G	Power Pentode	25	6X	2.0F	0.12	Class A Amplifier	
1J6G 1J6GT	Twin-Triode Amplifiers	22 13F	7AB	2.0F	0.24	Class B Amplifier	
<b>★</b> 1K3	Half-Wave Rectifier	14B	3C	1.25F	0.2	Pulsed Rectifier in TV Receivers	
11K3/ 113	Half-Wave Rectifier	14B	3C	1. <b>2</b> 5F	0.2	Pulsed Rectifier in TV Receivers	
	Pentode	5C	6AP	1,4F	0.05	RF Amplifier	

[♦] Industrial type

[★] See Safety Precautions at end of this section.

	Grid Bias or	IS	Screen Grid	Plate	AC Plate	Trans-	Ampli£	Р	ower	- no:
Plate	Cathode Resistor	Screen Grid	Cur- rent	Cur- rent	Resist- ance	Trans- Amplifi- conduct- cation ance Factor		Load	Out- put	RC/ Typ
Volts		Volts	mA	mA	Ohms	Micromhos		Ohms	Watts	
	Max. Peak Max.	inverse Pla Peak Plat	ite Volts e mA, 45	18000		Max	. Average	Plate mA,	0.5	1BC2
	Max. Peak Max.	Inverse Pla Peak Plat	ite Volts e mA, 45	, 18000				Plate mA,		1BH2 1BH2A
90	7.5V	90	3.5	7.8	115000	1550		8000	0.24	1C5GT
		Fo	r other c	haracter	istics, refe	to Type 1C	7 <b>G</b>			106
135 180	- 3V	67.5 67.5	2.5 2.0	1.3 1.5	600000 700000		Oscilláto	180 max or-Grid (1) ond., 325 m	Resistor.	1C7G
145	0			<b>2</b> 5						1C21 •
90 180	{ — 3V }	67.5 67.5	0. <del>9</del> 0.8	2.2 2.3	600000 1 M	720 750				1D5GF
						to Type 1D50				1D5GT
			other c	haracter	stics, refer	to Type 1A6	i			1D7G
90	9V	90	1.0	5.0		925		12000	0.200	1DOCT
90	0٧	_		1.1	43500	575	25			· 1D8GT
	Max. Peak Ir Max. Peak P			26000	_	Max	Average	Plate mA, (	).5	1DG3
67.5	OV	67.5	0.55	2.1	600000	630		_		1DN5
90 180	3V 3V	67.5 67.5	0.7 0.6	1.6 1.7	1 M 1.5 M	600 650				1E5GP
135	— 7.5V	135	3.5	10.5				24000	0.575	1E7GT
45 67.5	0V 0V	45 67.5	1.1 1.5	0.6 1.0	400000 400000			) Resistor, ond., 150 π		1E8
						to Type 1F50	3			1F4
90 135	— 3V — 4.5V	90 135	1.1 2.4	4.0 8.0	240000	1400	=	20000	0.11 0.31	1F5G
		For	other ch	aracteris	tics, refer	to Type 1F70	1			1 <b>F</b> 6
180	— 1.5V	67.5	0.7	2.2				_		1F7G
	Max. Peak II Max.	nverse Plat Peak Plate	te Volts, mA, 50	26000		Max	Average	Plate mA, (	).5	1G3GT/ 1B3GT
90	— 6V			2.3	10700	825	8.8			1G4GT
90 135	— 6V —13.5V	90 135	2.5 2.5	8.5 9.7	133000 160000	1500 1550		8500 9000	0.25 0.55	1G5G
90	OV		11					12000	0.350	1G6GT
1 <b>80</b> 157.5	—13.5V —15V			3.1 1.0 🗆	10300	900	9.3			1H4G
90				0.15	240000	275	65	8000	2.1†	1H5GT
35				0.8	35000	575	20			1H6G
N	lax. Peak Invers lax. Peak Plate	e Plate Vo	its, 2600	0 (Abs.)				Plate mA, 0	.5	1J3
35	—16.5V	135	2.0	7.0	105000	950		13500	0.45	1J5G
135 135	0V 3V				r Output is ted plate-to	for one tube	at	10000 10000	2.1 1.9	1J6G 1J6GT
N M	lax. Peak Invers lax. Peak Plate	e Plate Vo mA, 50	lts, 2600			··	Average	Plate mA, 0		1K3
	Max. Peak In		e Volts, mA, 50	26000		Max.	Average	Plate mA, 0	.5	1K3/ 1J3
90	0	90	2	4.5	350000	1025				1L4

[†] For two tubes at stated plate-to-plate load.

RCA Type	Name	Out- line	Terminal Dia- gram		iter or nent (F)	Use Values to right give operating conditions and characteristics for indicated typical use
			-	Voits	Amperes	<b>-</b>
1L6	Pentagrid Converter	5C	7DC	1.4F	0.05	Converter
1LA4	Power Pentode	12B	5AD	1.4F	0.05	Amplifier
1LA6	Pentagrid Converter	12B	7AK	1.4F	0.05	Converter
1LB4	Power Pentode	128	5AD	1.4F	0.05	Class A Amplifier
1LC5	Sharp-Cutoff Pentode	12B	7A0	1.4F	0.05	Class A Amplifier
1LC6	Pentagrid Converter	12B	7AK	1.4F	0.05	Converter
1LD5	Diode-Sharp-Cutoff Pentode	12B	6AX	1.4F	0.05	Pentode Unit as Class A Amplifier
1LE3	Medium-Mu Triode	12B	4AA	1.4F	0.05	Class A Amplifier
1LG5	Remote-Cutoff Pentode	12B	7A0	1.4F	0.05	Class A Amplifier
1LH4	Diode—High-Mu Triode	12B	5AG	1.4F	0.05	Triode Unit as Class A Amplifie
1LN5	Sharp-Cutoff Pentode	12B	7A0	1.4F	0.05	Class A Amplifier
★1N2A	Half-Wave Rectifier	19A	3C	1.25F	0.2	Pulsed Rectifier in TV Receiver
1N5GT	Sharp-Cutoff Pentode	14A	5Y	1.4F	0.05	Class A Amplifier
1N6G	Diode-Power Pentode	29A	7AM	1.4F	0.05	Pentode Unit as Class A Amplifier
1P5GT	Remote-Cutaff Pentode	14A	5Y	1.4F	0.05	Class A Amplifier
1Q5GT	Beam Power Tube	13D	6AF	1.4F	0.1	Class A Amplifier
1 <b>R</b> 5	Pentagrid Converter	5C	7AT	1.4F	0.05	Converter
★1S2A/ DY87	Half-Wave Rectifier	7 <b>F</b>	<b>GDT</b>	1.4	0.55	Pulsed Rectifier in TV Receivers
154	Power Pentode	5C	7AV	1.4F	0.1	Class A Amplifier
1\$5	Diode-Sharp-Cutoff Pentode	5C	6AU	1.4F	0.05	Pentode Unit as AF Amplifier
174	Remote-Cutoff Pentode	5C	6AR	1.4F	0.05	Class A Amplifier
1T5GT	Beam Power Tube	13D	6X	1.4F	0.05	Class A Amplifier
176	Diode—Sharp-Cutoff Pentode	29A	8DA	1.25F	0.04	Pentode Unit as Class A Amplifier
104	Sharp-Cutoff Pentode	5Ĉ	6AR	1.4F	0.05	Class A Amplifier
105	Diede-Sharp-Cutoff Pentode	5C	6BW	1.4F	0.05	Pentode Unit as Class A Amplifier
17	Half-Wave Rectifier	22 or 13H	46	6.3	0.3	With Capacitive-Input Filter
★1X2A	Half-Wave Rectifier	7A	<b>9</b> Y	1. <b>2</b> 5F	0.2	Pulsed Rectifier in TV Receiver
1X2B ★1X2B/ 1X2A	Half-Wave Rectifier	7A	9Y	1.25F	0.2	Pulsed Rectifier in TV Receivers
						Class A Amplifier
2A3	Power Triede	27B	4D	2.5F	2.5	Push-Pull Class AB ₁ Amplifier
2A5	Power Pentode	28	<b>6</b> B	2.5	1.75	Amplifier
2A6	Twin Diode—High-Mu Triode	24B	6G	2.5	0.8	Triode Unit as Amplifier
2A7	Pentagrid Converter	24B	7C	2.5	0.8	Converter

[★] See Safety Precautions at end of this section.

	Grid Bias or		Screer Grid	7 Plate	AC Plate	Trans-	Amplifi-	Pow	rer	- RC
Piate	Cathode Resistor	Screen Grid	Cur- rent	Cur- rent	Resist- ance	conduct- ance	cation Factor	Load	Out- put	Ty
Volts		Velts	mA	mA	Ohms	Micromhos		Ohms	Watts	
90	0V	45	0.6	0.5	650000	Anode-Grid Oscillator Conversion	Grid (1	max. volts ) Resistor, ond, 300 m	, 1.2 mA 0.2 MΩ nicromhos	11
		For	other c	haracterís	tics, refer	to Type 1A5	GT			11.4
90	0V	65	0.6	0.55	750000		n Transco	4 nd. (for grid- 10 micromhos		11.
		or other cl				ode Unit of 1	Type 1D80	ÌΤ		111
45 90	0V 0V	45 45	0.35 0.30	1.10 1.15	700000 1 M	750 775		=		110
45 90	0V 0V	35 35	0.75 0.70	0.70 0.75	300000 650000	Anode-Grid Oscillator- Conversion	-Grid (1)	Resistor,	1.4 mA 0.2 MΩ icromhos	11.0
90	0V	45	0.1	0.6	750000	575		<del></del>	_	11.0
90 90	_ 3V		=	4.5 1.4	11200 19000	1300 760	14.5 14.5			11.8
90 90	0V — 1.5V	45 90	0.4 0.9	1.7 3.7	1 M 500000	800 1150				1L0
30						to Type 1H50	GT			111
90	0V	90	0.35	1.6	1.1 M	800				1LN
Max.	. Peak Inverse P . Peak Plate mA,	50				Max.	Average	Plate mA, 0.5		1N2
0	V 90	0.3	1.2	1.5 M	750				90	1N5
90	4.5V	90	0.6	3.1	300000	800	<del>-</del>	25000	0.1	1N6
90	07	90	0.7	2.3	800000	750				1P5
110	6.6V	110	1.4	10	100000	2200		8000	0.4	1Q5
45 90	0V 0V	45 67.5	2.1 3.5	0.7 1.5	400000 500000	Conversi	on Transc	cond., 210 μπ cond., 280 μπ	ihos ihos	1R
	Max. Peak I Max.	nverse Pla Peak Plate				Max.	Average	Plate mA, 0.8	3	1S2 DY8
45 90	— 4.5V — 7V	45 67.5	0.8 1.4	3.8 7.4	100000 100000	1250 1575		8000 8000	0.065 0.27	18
							O V appl	ied through		18
45 90	0V 0V	45 67.5	0.7 1.4	1.7 3.5	350000 500000	700 900				11
90	— 6V	90	0.8	6.5	250000	1150		14000	0.17	115
45 67.5	0V	45 67.5	0.21 0.4	0.75 1.6	500000 400000	475 600				17
90	0V	90	0.50	1.1	1 M	900			=	10
67.5	OV	67.5	0.4	1.6	600000	625				10
	AC Plate Volts		j	Min. Tot	al Effective	e Plate-Sup	ply Impe	dance: Up t 325 volts, 75	o 117	1'
Max.	Peak Inverse Pi Peak Plate mA,	ate Volts.	20000	70.00, 0	J			Plate mA, 0.		1X2
IVIUA.	Max. Peak In		te Volts mA, 45	, 22000		Max.	Average	Plate mA, 0.	5	1X2 1X2 1X
				60.0	800	5250	4.2	2500	3.5	2A
50 00	—45V 780Ω□ —62V			80.0 □	_			5000 3000	10.0† 15.0†	Z.R.
		For	other c	80.0□	tics, refer	to Type 6F60	 G	3000 3000	10.0† 15.0†	2A!
00	780Ω□			80.0□ haracteris		to Type 6F60 to Type 6SQ		5000 3000		

[†] For two tubes at stated plate-to-plate load.

RCA Type	Name	Out- line	Terminal Dia- gram		ater or ment (F)	Use Values to right give operat- ing conditions and character- istics for indicated typical use
			•	Velts	Amperes	<del></del>
2AF4A 2AF4B	Medium-Mu Triode	5B	7DK	2.35	0.6	Class A Amplifier
★2AH2	Half-Wave Rectifier	9A	12DG	2.5	0.3	Pulsed Rectifier in TV Receivers
★2AS2	Half-Wave Rectifier	9B	12EW	2.5	0.33	Pulsed Rectifier in TV Receivers
2B7	Twin Diode—Remote-Cutoff Pentade	248	70	2.5	0.8	Pentode Unit as Amplifier
2BA2	Half-Wave Rectifier	6B	SU	1.8F	0.3	Flyback Rectifier in TV Receivers
<b>★2BJ2</b>	Half-Wave Rectifier	7A	9RT	2.3	0.3	Pulsed Rectifier in TV Receivers
★2BJ2A	Half-Wave Rectifier	7A	SRT	2.3	0.3	Pulsed Rectifier in TV Receivers
2BN4	Medium-Mu Triade	5C	7EG	2.3	0.6	Class A Amplifier
2D21W◆	Gas-Tetrode	5C	7BN	6.3	0.6	Thyratron
★2CN3A	Half-Wave Rectifier	14F	8MU	1.8	0.9	Flyback Rectifier in TV Receivers
2DZ4	Medium-Mu Triode	5B	7DK	2.35	0.6	Class A Amplifier
2E5	Electron-Ray Tube	22 or 13H	6R	2.5	0.8	Visual Indicator
2EN5	Twin Diade	5C	7FL	2.1	0.45	Horizontal Phase Detector
2ER5	High-Mu Triode	5C	7FP	2.3	0.6	Class A Amplifier
2FQ5A	High-Mu Triode	5C	7FP	2.3	0.6	Class A Amplifier
2GK5	High-Mu Triode	5C	7FP	2.3	0.6	Class A Amplifier
2GU5	Beam Hexode	5C	7GA	2.4	0.6	Class A Amplifier
★3A2	Half-Wave Rectifier	7A	9DT	3.15	0.22	Pulsed Rectifier in TV Receivers
★3A3 3A3/3B2	Half-Wave Rectifier	14E	8EZ	3.15	0.22	Pulsed Rectifier in TV Receivers
3A3A ★3A3A/ 3B2	Half-Wave Rectifier	14F	8EZ	3.15	0.22	Pulsed Rectifier in TV Receivers
<b>★</b> ЗАЗВ	Half-Wave Rectifier	14F	8EZ	3.15	0.22	Pulsed Rectifier in TV Receivers
3 <b>A</b> 4 •	Tetrode	5C	788	1.4F 2.8F	0.2 0.1	AF Power Amplifier
3A8GT	Diode-Triode—Pentode	296	8AS	1.4F 2.8F	0.1 0.05	Triode Unit as Class A Ampliner Pentode Unit as Class A Amplifier
3AF4A	Medium-Mu Triode	5B	7DK	3.15	0.45	Class A Amplifier
★3AT2	Half-Wave Rectifier	9B	12FV	3.15	0.22	Pulsed Rectifier in TV Receivers
3AV6	Twin Diode—High-Mu Triode	5C	7BT	3.15	0.6	Triode Unit as Class A Amplifier
3AW2	Half-Wave Rectifier	9B	12EW	3.15	0.39	Pulsed Rectifier in TV Receivers
3AW3	Half-Wave Rectifier	14B	8EZ	3.15	0.22	Pulsed Rectifier in TV Receivers
3B2	Half-Wave Rectifier	21C	8GH	3.15	0.22	Pulsed Rectifier in TV Service
3B4WA+	Beam Power Tube	5C	7CY	1.25F 2.50F	0.33 0.165	Class C Amplifier
3BA6	Remote-Cutoff Pentode	5C	78K	3.15	0.6	Class A Amplifier
3BC5	Sharp-Cutoff Pentode	5C	7BD	3.15	0.6	Class A Amplifier
3BE6	Pentagrió Converter	5C	7CH	3.15	0.6	Converter
Industria	ul tuno	4 500	Safaty Drag	autione	at end of t	his assiss

[♦] Industrial type

^{*} See Safety Precautions at end of this section.

	Grid Bias or		Screen Grid	Plate	AC Plate	Tease	Amn!:#	Powe	<u> </u>	— RCA
Piate	Cathode Resistor	Screen Grid	Cur- rent	Cur- rent	Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Load	Out- put	Туре
Voits		Volts	mA	mA	Ohms	Micromhos		Ohms	Watts	}
80	150Ω			17.5	2100	6500	13.5			2AF4/ 2AF4/
	Max. Peak	Inverse Pla Peak Plat				Ma	x. Average	Plate mA, 1	.5	2AH2
	Max. Peak		te Volts,	30000	·· <del>··</del> .	Ma	x. Average	Plate mA, 1.	5	2AS2
	тах.				istics, refe	r to Type 6B	8G			2B7
	Max. Peak	Inverse Piate	ate Volts	, 8250		Ma	x. Average	Plate mA, 0.	6	2BA2
	Max, Peak	Inverse Pla	te Volts	. 20000				e Plate mA,		2BJ2
	Max. Peak I		te Volts,					e Plate mA, 1		2BJ2A
150	Max. Peak F 220Ω	riate ma, 8		9	6300	6800	43			2BN4
130	22012	For	other ch			r to Type 2D				2D21W
						to Type 3CI				2CN3/
80				15	2000	6700	14			2DZ4
		Fo	other c	haracter	istics, refe	r to Type 6E	5			2E5
	. Peak Heater-C olts Not to Ex			)		Max.	DC Plate i	mA,5		2EN5
100	TOTAL NOT TO EX			aracteri	istics, refe	r to Type 6E	R5		_	2ER5
		For o	ther cha	racteris	tics, refer	to type 6	FQ5A			2FQ5Ā
		For oth	er chara	cteristic	s, refer to	Type 6GK5/	6FQ5A			2GK5
		For	other ch	aracteri	istics, refe	r to Type 6G	U5			2GU5
Max. Max.	Peak Inverse P Peak Plate mA	late Volts, , 80	18000			Max.	Average F	Plate mA, 1.5		3A2
Max. Max.	Peak Inverse F Peak Piate mA	Plate Volts, , 88	30000			Max.	Average P	late mA, 1.7		3A3 3A3/3B
lax. Pea	k Inverse Pla	ite Volts,	30000	·	May A	erage Plate	m4 2			3A3A 3A3A/
fax. Pea	k Plate mA,	100			MIGA. A	ciage riate	ma, z			3B2
	Max. Peak Max.	Inverse Pia Peak Plate	te Voits	, 38000		М	ax. Averag	e Plate mA, 2	:	3A3B
150	—8.4V	90	2.2	133	100000	1900		8000	0.7	3A4 <b>*</b>
90	07			0.2	200000	325	65			
90	07	90	0.5	1.5	800000	750		-	_	- 3A8GT
		For	other cha	aracteris	tics, refer	to Type 2Al				3AF4A
-	Max. Peak Max	Inverse Pla Peak Plat				Ma	x. Average	Plate mA, 1.	7	3AT2
					istics, refe	to Type 6A	V6			3AV6
		For	other cl	haracter	istics, refe	r to Type 3C	Z3			3AW2
		For o	ther char	racterist	ics, refer	to Type 3A3/	/3B2			3AW3
Max.	Peak Plate mA Total DC & Pea	, 80	Plate Vo	Ite 3500	On (Ahs )	Max.	DC Inverse	e Plate Volts, late mA, 1.1	25000	3B2
150	-38V	135	6.2	25					1.25	3B4WA+
100 250	68Ω 68Ω	100 100	4.4 4.2	10.8 11	250000 1 M	4300 4400			_	3BA6
100	180Ω	100	1.4	4.7	600000	4900				3BC5
250	Self-	150	2.1	7.5	800000	5700 Convers	ion Transc	ond., 475 μm		
250	Excited	100	6.8	2.9	1 M	00111010	ion Lianse	or, 20000 ohm	103	3 <b>BE</b> 6

RCA Type	Name	Out- line	Terminal Dia- gram		nter or nent (F)	Use Values to right give operating conditions and character istics for indicated typical use
			-	Volts	Amperes	_
★3BL2 ★3BL2A	Half-Wave Rectifier	98	12HK	3.3F	0.285	Pulsed Rectifier in TV Receivers
★3BM2	Half-Wave Rectifier	9B	12HK	3F	0.3	Pulsed Rectifier in TV Receivers
★3BN2 ★3BN2A	Half-Wave Rectifier	9B	12FV	3.15	0.3	Flyback Rectifiers in TV Receivers
3BN4	Medium-Mu Triode	5C	7EG	3.0	0.45	Class A Amplifier
★3BS2A	Half-Wave Rectifier	98	12HY	3.15	0.48	Flyback Rectifiers in TV Receivers
3BU8	Sharp-Cutoff Twin Pentode	6E	9FG	3.15	0.6	Class A Amplifier (With both sections operating
3BY6	Pentagrid Amplifier	5C	7CH	3.15	0.6	Class A Amplifier
★3CA3	Half-Wave Rectifier	14E	8MH	3.6	0.225	Pulsed Rectifier in TV Receivers
3CE5	Sharp-Cutoff Pentode	5C	7BD	3.15	0.6	Class A Amplifier
3CF6	Sharp-Cutoff Pentode	5C	7CM	3.15	0.6	Class A Amplifier
<b>★</b> 3CN3A	Half-Wave Rectifier	14F	8MU	3.15	0.48	Flyback Rectifiers in TV Receivers
★3CX3	Half-Wave Rectifier	14G	8MT	3.15	0.48	Pulsed Rectifier in TV Receivers
★3DA3/ 30H3	Half-Wave Rectifier	14G	8 <b>M</b> Y	3.15	0.48	Pulsed Rectifiers in TV Receivers
★ 3DR3	Half Wave Rectifier	29Q	8NL	3.15	0.3	Pulsed Rectifier in TV Receivers
★3DS3	Half-Wave Rectifier	29P	8NL	3.15	0.48	Pulsed Rectifier in TV Receivers
3DZ4	Medium-Mu Triode	5B	7DK	3.2	0.45	Class A Amplifier
3EA5	Sharp-Cutoff Tetrode	5C_	7EW	2.9	0.45	Class A Amplifier
3EJ7	Sharp-Cutoff Pentode	6C	DAR	3.4	0.6	Class A Amplifier
3FH5	High-Mu Triode	5C	7 <b>F</b> P	3.0	0.45	Class A Amplifier
3GS8 3GS8/ 3BU8	Sharp-Cutoff Twin Pentode	8E	9LW	3.15	0.6	Class A Amplifier (With both sections operating
3HA5	High-Mu Triode	5A	7GM	2.7	0.45	Class A Amplifier
3HS8	Sharp-Cutoff Twin Pentode	6E	9FG	3.15	0.6	Class A Amplifier (With both sections operating
3JC6	Sharp-Cutoff Pentode	6B	9PM	3.5	0.6	Class A Amplifier
3JD6	Sharp-Cutoff Pentode	6B	9PM	3.5	0.6	Class A Amplifier
3LF4	Beam Power Tube	12B	6BA	1.4F 2.8F	0.1 0.05	Class A Amplifier
3Q4	Power Pentode	5C	7BA	1.4F 2.8F	0.1 0.05	Class A Amplifier
3Q5GT	Beam Power Tube	13D	7AP	1.4F 2.8F	0.1 0.05	Class A Amplifier
<b>3</b> \$4	Power Pentode	5C	7BA	1.4F 2.8F	0.1 0.05	Class A Amplifier
<b>3V4</b>	Power Pentode	5C	<b>GBX</b>	1.4F 2.8F	0.1 0.05	Class A Amplifier
4BC5	Sharp-Cutoff Pentode	5C	7BD	4.2	0.45	Class A Amplifier
4BL8	Medium-Mu Triode— Sharp-Cutoff Pentode	6B	9DC	4.6	0.6	Triode Unit as Class A Amplifie Pentode Unit as Class A Amplifier
4BQ7A/ 4BZ7	Medium Mu Twin Triode	68	SAJ	4.2	0.6	Each Unit as Class A Amplifier
4BS8	Medium-Mu Twin-Triode	6B	9AJ	4.6	0.6	Class A Amplifier
4BU8	Sharp-Cutoff Twin Pentade	6E	9FG	4.2	0.45	Class A Amplifier

	Grid Bias		Screen	DI-4-	40 DI-2-	7	Am-1:#	Pow	er	- RCA
Plate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Plate Cur- rent	AC Plate Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Load	Out- put	Тура
Velts		Valts	mA	mA	Ohms	Micromhos	;	Ohms	Watts	
	Max. Peak Max.	Inverse Pla . Peak Plate	ite Volts, mA, 100	33000		N	lax. Averag	e Plate mA, 2		3BL2 3BL2A
		Inverse Pla Peak Plate		33000		N	lax. Averag	e Plate mA, 2	!	3BM2
	Max. Peak	Inverse Pla . Peak Plat	te Volts,	30000		Ma	ax. Average	Plate mA, 1.	7	3BN2 3BN2A
					stics, refer	to Type 6B	N4			3BN4
	Max. Peak Max.	Inverse Pla Peak Plate	te Volts, mA, 110	38000		Ma	ax. Average	Plate mA, 2.	2	3BS2A
100 100		67.5 67.5	6.5 3.3	2.2			_	_	_	3BU8
		For	other cha	racteris	stics, refer	to Type 6B	Y6			3BY6
	Max. Peak Max.	Inverse Pla Peak Plate	te Volts, mA, 100	30000		M	lax. Averag	e Plate mA, 2	!	3CA3
				racteris	tics, refer	to Type 60	E5			3CE5
					tics, refer	to Type 60	F6			3CF6
	Max. Peak Max.	Inverse Pla Peak Plate	te Voits, mA, 110	38000		Ma	ax. Average	Plate mA, 2.	2	3CN3A
		For oth	ner charac	teristic	s, refer to	Type 3DA3	/3DH3			3CX3
	Max. Peak Max.	Inverse Pla Peak Plate	te Volts, mA, 110	38000		Ma	ax. Average	Plate mA, 2.	2	3DA3/ 3DH3
	Max. Peak Max	inverse Plate Peak Plate	ate Volts, e mA, 100	38000		, h	Max. Averag	ge Plate mA, ;	2	3DR3
For	r other charact	terstics, ref	fer to typ	e 3DA3,	/3DH3					3DS3
		For	other cha	racteris	tics, refer	to Type 2D	Z4			3DZ4
250	<u>-1V</u>	140	0.95	10	150000	8000				3EA5
190 200	2.35V 2.5V	190 200	4.1 4.1	10 10	350000 350000	15000 15000		_=		3EJ7
		For	other cha	racteris	tics, refer	to Type 6F	H5			3FH5
		For oth	er charac	teristic	s, refer to	Type 4GS8/	4BU8			3GS8/ 3GS8/ 3BU8
135	87Ω	_	10	19 11.5	1000 5600	20000 14500	80 72			3HA5
100 100		67.5 67.5	7	2						3HS8
125	56Ω	125 125	3.2 3.4	13	180000	15000				3JC6
125	56Ω			14 aracteri	180000 istics, refe	16000 r to Type 6.	JD6			3JD6
		For	other ch	aracteri	istics, refe	to Type 30	15GT			3LF4
		For	other ch	aracteri	stics, refer	to Type 3V	/4			3Q4
110 110	6.6V 6.6V	110 110	1.4 1.1	10.0 8.5	100000 110000	2200 2000		8000 8000	0.40 0.33	3Q5GT
90	— 7V — 7V	67.5 67.5	1.4	7.4 6.1	100000 100000	1575 1425		8000 8000	0.27 0.235	3\$4
90	— 4.5V	90	2.1	9.5	100000	2150		10000	0.27	3 <b>V</b> 4
90 250	<u>— 4.5V</u> 180Ω	90 150	2.1	7.7	120000 800000	2000 5700	=	10000	0.24	4BC5
					line rofor	to Type 681	18			4BL8
_		For o	ther char	acterist	tics, refer	, pu				4010
						to Type 6B(				4BQ7A/ 4BQ7A/ 4BZ7
		For	other cha	racteris	tics, refer		Q7A			4BQ7A/

RCA Type	Name	Gut- line	Terminal Dia- gram	- 1	leater or lament (F)	<b>Use</b> Values to right give operat  ing conditions and character istics for indicated typical use
				Volts	Amperes	
4BZ7	Medium-Mu Twin Triode	63	9AJ	4.2	0.6	Each Unit as Class A Amplifier
4CY5	Sharp-Cutoff Tetrode	5C	7EW	4.5	0.3	Class A Amplifier
4DT6	Sharp-Cutoff Pentode	5C	7EN	4.2	0.45	Class A Amplifier
4EH7	Samiremote-Cutoff Pentode	6C	9AQ	4.4	0.45	Class A Amplifier
4EJ7	Sharp-Cutoff Pentode	6C	9AQ	4.4	0.45	Class A Amplifier
4ES8	Variable-Mu Twin-Triode	6B	IAE	4	0.6	Each Unit as Class A Amplifier Cascode-Type Amplifier
4ES8/ XCC189	Variable-Mu Twin Triode	6B	LAE	4	0.6	Each Unit as Class A Amplifier
4EW6	Sharp Cutoff Pentode	5C	7CM	4.2	0.6	Class A Amplifier
4GM6	Semiremote-Cutoff Pentode	5C	7CM	4.2	0.6	Class A Amplifier
4GS8	Sharp-Cutoff Pentode	6E	9LW	4.2	0.45	Class A Amplifier
4GS8/ 4BU8	Sharp-Cutoff Twin Pentode	8E	9LW	4.2	0.45	Class A Amplifier (With both sections operating)
46X7	Medium-Mu Triode Sharp-Cutoff Pentode	6B	SQA	4.2	0.6	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
4GZ5	Power Pentode	5C	7CV	4	0.6	Class A Amplifier
4HA5/ PC900	High-Mu Trlode	5A	7GM	3.9	0.3	Class A Amplifier
4HA7	Dual Triode	8A	12FQ	4.2	0.6	Each Unit as Class A Amplifier
4HA7/ 4HC7	Dual Triode	8A	12FQ	4.2	0.6	Class A Amplifier
4HC7	Dual Triode	30E	12FR	4.2	0.6	Each Unit as Class A Amplifier
4HM6	Sharp-Cutoff Pentode	6B	9PM	4.2	0.45	Class A Amplifier
4HT6	Semiremote-Cutoff Pentade	6B	9PM	4.2	0.45	Class A Amplifier
4JC6	Sharp-Cutoff Pentode	6B	9PM	4.5	0.45	Class A Amplifier
4KN8/ 4RHH8	Medium-Mu Twin-Triode	6B	9AJ	4.2	0.6	Class A Amplifier
4LU6	Sharp-Cutoff Pentode	5C	7CM	4,2	0.6	Class A Amplifier
5AS4	Full-Wave Rectifier	27A	5T	5.0F	3.0	With Capacitive-Input Filter
5AS8	Diode—Sharp-Cutoff Pentode	6B	9DS	4.7	0.6	Class A Amplifier
5AU4	Full-Wave Rectifier	196	5T	5.0F	3.75	With Capacitive-Input Filter
54160	Medium-Mu Triode					With Inductive-Input Filter Triode Unit as Class A Amplifier
5AV8	Sharp-Cutoff Pentode	6B	9DZ	4.7	0.6	Pentode Unit as Class A Amplifier
5AW4	Full-Wave Rectifier	19H	5T	5.0F	3.7	Rectifier
5AZ4	Full-Wave Rectifier	12C	5T	5.0F	2.0	Triada Unit os Oloss A Amelicar
5B8	Medium-Mu Triode— Sharp-Cutoff Pentode	6B	9EC	4.7	0.6	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
5BC3	Full-Wave Rectifier	170	<b>9QJ</b>	5F	3	With Capactive-Input Filter
						With Inductive-Input Filter  Triode Unit as Class A Amplifier
5BE8	Medium-Mu Triode—Sharp-Cutoff Pentode	68	SEG	4.7	0.6	Pentode Unit as Class A Amplifier

	Grid Bias		Screen	Plate	AC Plate	Trans-	Amplifi-	Power	RCA
Plate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Cur- rent	Resist- ance	conduct- ance	cation Factor	Load Out-	Туре
Volts		Volts	mA	mA	Ohms	Micromhos	3	Ohms Watts	
		For o	ther cha	racteris	tics, refer	to Type	6BZ7		4BZ7
125	— 1V	80	1.5	10	100000	8000			4CY5
150	56Ω	100	2.1	1.1	150000	515			4DT6
200	- 2	90	4.5	12	0.5	12500			4EH7
200	<b>— 2</b> .5	200	4.1	10	0.35	15000			4EJ7
		For	other cha	aracteris	tics, refer	to Type 6E	\$8		4ES8
		For o	ther char	acterist	cs, refer t	o Type 6ES	8/ECC189		4ES8/ XCC18
		Fo	or other	characte	ristics, ref	er to Type	6EW6		4EW6
		Fo	r other o	haracte	ristics, ref	er to Type	6GM6		4GM6_
				cteristic		Type 4GS8			4GS8
100		67.5	6.0	2.0			each section each section	<del></del>	- 4GS8/
100		67.5 : Grid	6.0 Current			icroampere		n, o	– 4BU8
						to Type 5G			46X7
		For	other cha	racteris	tics, refer	to Type 60	Z5		4GZ5
135	— 1V 0Ω			11.5 19		14500 20000	72 80		4HA5/
135 250	— 8.5			10.5	7700	2200	17		PC900 4HA7
250	<u> </u>			1.2	62500	1600	100		
		For	other cha	aracteris	tics, refer	to Type 4H	IA7		4HA7/ 4HC7
150 150	- 1 - 1			18	5200 53000	4400 1900	23 100		4HC7
130		For	other cha			to Type 6H			4HM6
125	56Ω	125	4	15	143000	14000			4HT6
			ther cha	racteris	tics, refer	to Type	6JC6		4106
		For other	er charac	teristics	s, refer to	Type 6KN8/	'6RНН8		4KN8/ 4RHH8
250	820Ω	<b>2</b> 50	2.3	9	280000	3900			4LU6
50 Max.	65Ω AC Volts per	250 Plate (RMS),	15 550	40 Max.	DC Output	mA, 300 e mA, 1000	Min.	Total Effect. Supply	5AS4
Max.	Peak Inverse		other ch			to Type 64		d. per Piate, 97 ohms	5AS8
Max.	DC Output m							Volts, 1400	37100
and	Total Effect. S DC Output m Peak Inverse	Supply Imped	. per Pia	te, 50 ol	hms	Max. P	Peak Plate m	A per Plate, 1075	- 5 <b>AU</b> 4
200	6V			13	5750	3300	19		- 5AV8
<b>20</b> 0	180Ω	150	2.8	9.5	300000	6200			
Max.	Peak Inverse						e mA per Pl	ate, 750	5AW4
		For rat	ings and			fer to Type			5AZ4
200	-6V 180Ω	150	2.8	13 9.5	5750 300000	3300 6200	19		- 5B8
Max Max	. AC Volts per Peak Inverse	Plate (RMS) Volts, 1700 Min. To	, 500 tal Effec			Max. Max er Plate, 2	1 ohms	e mA per Plate, 1000	- 5BC3
Max	. AC Volts per . Peak Inverse	Volts, 1700	•	ie of In	out Choke,	Max 10 henries		mA, 150 mA per Piate, 1000	
150	56Ω			18	5000	8500	40		5BE8
250	68Ω	110	3.5	10	400000	5200			JDE0

RCA Type	Hame	Out- line	Terminal Dia- gram	He	ater or ment (F)	Use  Values to right give operating conditions and characteristics for indicated typical use
				Voits	Amperes	
5BT8	Twin-Diode—Sharp-Cutoff Pentode	68	9FE	4.7	0.6	Class A Amplifier
5BW8	Twin-Diode— Sharp-Cutoff Pentode	68	9H K	4.7	0.6	Pentode Unit as Class A Amplifie
5CL8	Medium-Mu Triode—	<b>6</b> B	9FX	4.7	0.6	Triode Unit as Class A Amplifier
5CM8	High-Mu Triode—Sharp-Cutoff Pentode	<b>6</b> B	9FZ	4.7	0.6	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
5CQ8	Medium-Mu Triode— Sharp-Cutoff-Pentode	68	9 <b>6</b> E	4.7	0.6	Class A Amplifier
5DH8	High-Mu Triode—Sharp-Cutoff Pentode	6B	9EG	5.2	0.6	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
	<del> </del>					With Capacitive-Input Filter
5BJ4	Full-Wave Rectifier	19E	8KS	5.0	3.0	With Inductive-Input Filter
5ES8 5ES8/ YCC189	Variable-Mu Twin-Triode	6B	9AJ	.5.6	0.45	Each Unit as Class A Amplifier Cascode Type Amplifier
5EU8	Medium-Mu Triode— Sharp-Cutoff Pentode	6B	9JF	4.7	0.6	Class A Amplifier
5FV8	Medium-Mu Triode Sharp-Cutoff Pentode	6B	9FA	4.7	0.6	Class A Amplifier
5GJ7	Medium-Mu Triode Sharp-Cutoff Pentode	61	APE	5.6	0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
5GX6	Sharp-Cutoff Pentodo	50	7EN	4.7	0.6	Class A Amplifier
5GX7	Medium-Mu Triode— Sharp-Cutoff Pentode	6B	ADE	5.6	0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
5HA7	Dual Triode	8A	12FQ	5.6	0.45	Each Unit as Class A Amplifier
5HG8	Medium-Mu Triode— Sharp-Cutoff Pentode	68	9MP	5.3	0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
5JK6	Sharp-Cutoff Pentode	5C	7CM	4.9	0.45	Class A Amplifier
5JL6	Semiremote-Cutoff Pentode	5C	7CM	4.9	0.45	Class A Amplifier
5T4	Full-Wave Rectifier	4	ST	5.0F	0.0	With Capacitive-Input Filter
314	LAIL-MASS MEETINGS	•	31	3.01	2.0	With Inductive-Input Filter
5U4G	Full-Wave Rectifier	278	5T	5.0 <b>F</b>	3.0	With Capacitive-Input Filter
<b>509</b> / LCF201	Medium-Mu Triode— Sharp-Cutoff Pentode	6B	10K	5.9	0.45	Class A Amplifier
5V3	Full-Wave Rectifier	19E	5T	5.0F	3.8	With Capacitive-Input Filter
J1J	· mit. maid uspting.	13L		J.VI	J.0	With Inductive Input Filter
5V4G	Full Ways Past:Es-	AE	e1			With Capactive-Input Filter
J <b>74</b> U	Full-Wave Rectifier	25	5L	5	2	With Inductive-Input Filter

	Grid Bias		Screen	Diete	AC Dista	Trans	A1:5-	Pow	rer	- RC
Plate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Plate Cur- rent	AC Plate Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Load	Out- put	Tyj
/olts		Volts	mA	mA	Ohms	Micromhos		Ohms	Watts	
200	180Ω	150	2.8	9.5	300000	6200			<u> </u>	5B
		For	other c	harateri	stics, refer	to Type 68	W8			5 <b>B</b> \
25	— 1 <b>V</b>			14	5000	8000	40			5C
		ı	or other	charact	eristics, re	fer to 6CM8	1			5 <b>C</b> I
		For	other ch	aracteri	stics, refe	r to Type 60	Q8		-	5 <b>C</b>
50	390Ω			7.3	12000	4400	53			- 5DI
25	56Ω	125	3.8	13.5	150000	8600				- 30
	C Volts per Pi ax. Peak Invei				utput mA, 2 Peak Plate			'otal Effect. per Plate, 67		EN
AC M	Volts per Pla ax. Peak Inver	ate (RMS), 5	50	DC OL	itput mA, 2 Peak Plate	75 mA, 1000		. Value of I		- 50
- 1	ux. Teak inver	30 10/10, 17		IVIUA I	OUN TIBLE	, 1000		5.10 HOIL		5ES
		For oth	er charac	teristic	s, refer to	Type 6ES8/	ECC189			5ES
		For	other ch	aractori	etice rafa	r to Type 6E	119			5E
		For c	ther cha		tics, refer	to Type 6				5F\
<u>00</u> 70	<u> </u>	120	3	15 10	0.35	9000	<u>20</u> 55			5GJ
/0	- 1.2	120	<del>-</del>	10	0.33	3700				
50	180Ω	100	3	3.7	140000	(Grid-No. 1 to Plate) 750 (Grid-No.			-	5G
00				12.5		3 to Plate) 8700	40			
25 20	<u> </u>	90	2.8	13 8.5	4700	8500 13000			=	- 5 <b>G</b> )
25	17	125	2.5	8	200000	11000				
		For	other ch	aracteri	stics, refe	r to Type 4H	A7	· <del>-</del> .		5H.
		For	other cha	aracteris	stics, refer	to Type 6H	G8			5H
		For				r to Type 6J	K6			5)1
125	AC Volta per	60	450	12.5	. DC Outpu	15500		Total Effect	Cupaly	5)
Max.	AC Volts per Peak Inverse	Volts, 1550		Max	. Peak Plat	e mA, 675	lmpe	Total Effect. d. per Plate,	150 ohms	- 51
Max. Max.	AC Volts per Peak Inverse	Plate (RMS) Volts. 1550	, 550	Max Max	. DC Outpu . Peak Plat	t mA, 225 e mH, 675	'Mun.	Value of Inp 10 henrie	ut Choke, s	
Max. Max.	AC Volts per Peak Inverse	Plate (RMS) Volts, 1550	, 450	Max Max	. DC Outpu . Peak Plat	t mA, 225 e mA, 675	Min. Impe	Total Effect. d. per Plate,	Supply 170 ohms	5U4
			er charac			Type 6U9/E				5U9 LCF2
Max.	AC Volts per Peak Inverse	Volts, 1400 Min. To	tal Effec	t. Suppl	y Imped. p	Max. er Plate, 56	ohms	mA per Plat	te, 1 <b>20</b> 0	5V
	AC Volts per Peak Inverse	Volts, 1400		ie of In	out Choke,	Max.	DC Output Peak Plate	mA, 350 mA per Plat	ie, 1200	
Max. Max.	AC Volts per Peak Inverse	Plate (RMS) Volts, 1400	375			Max.	DC Output Peak Plate ohms	mA, 175 mA per Pla	te, 525	FV
Max. Max.	AC Volts per Peak Inverse	Plate (RMS) Volts, 1400	, 500		put Choke,	Max. Max.	DC Output	mA, 175 mA per Pla	te, 525	- 5V

Type	Name	Out- line	Terminal Dia- gram	Filan	eter or nent (F)	Values to right give operat- ing conditions and character- istics for indicated typical use
	Type  IVGGT Beam Power Tube  5W4 FUII-Wave Rectifier  5X4G FUII-Wave Rectifier  5Y4GA FUII-Wave Rectifier  5Y4GA FUII-Wave Rectifier  5Z3 FUII-Wave Rectifier  5Z4 FUII-Wave Rectifier  5Z4 FUII-Wave Rectifier  6A3 Power Triode  6A6 High-Mu Twin Power Triode  6A7 Pentagrid Converter  6A8 Pentagrid Converter  6A8 Pentagrid Converter  6A8 Pentagrid Pentode  AB5/ Electron-Ray Tube  6A67 Sharp-Cutoff Pentode  AC5GT High-Mu Power Triode  6AC7 Sharp-Cutoff Pentode  AC5GT Low-Mu Triode  AC5GT Low-Mu Triode  AC5GT Low-Mu Triode  AC5GT Twin-Input Triode  AC7GT Twin-Input Triode			Volts	Amperes	
	Beam Power Tube	130	7AC	4.7	0.6	Class A Amplifier
5W4GT		2B 13E	5T 5T	5.0F	1.5	With Capacitive-Input Filter
	Full-Wave Rectifier	27B	5Q	5.0F	3.0	
5Y4GA 5Y4GA 5Y4GT	Full-Wave Rectifier	25 19E 13E	5Q 5Q 5Q	5.0F	2.0	
5Z3	Full-Wave Rectifier	27B	4C	5.0F	3.0	
574	Full-Wave Rectifier	28	5L	5.0	2.0	With Capacitive-Input Filter
JLT	V 200 W210 W210					With Inductive-Input Filter
6A3	Power Triode	27B	4D	6.3F	1.0	Amplifier
6A6	High-Mu Twin Power Triode	28	78	6.3	0.8	Amplifier
6A7 6A7S	Pentagrid Converter	24B 24B	7C	6.3	0.3	Converter
<b>6A8</b> 6A8G 6A8GT	Pentagrid Converter	3 23 14A	8A 8A 8A	6.3	0.3	Converter
6AB5/ 6N5	Electron-Ray Tube	22 er 13H	6R	6.3	0.15	Visual Indicator
6AB7	Sharp-Cutoff Pentode	2A	8N	6.3	0.45	Class A Amplifier
6AC5GT	High-Mu Power Triade	13D	60	6.3	0.4	Class B Amplifier  Dynamic-Coupled Amplifier With 76 Driver
2407	Chara Cutoff Dantada	2A	8N	6.3	0.45	Class A Amplifier
						<del></del>
DAUDG	Electron-Kay Tube	29E	7AG	6.3	0.15	Visual Indicator
6AD7G	Low-Mu Triode—Power Pentode	25	BAY	6.3	0.85	Triode Unit as Class A Amplifie Pentode Unit as Class A Amplifier
6AE5GT	Low-Mu Triode	130	BQ	6.3	0.3	Class A Amplifier
6AE6G	Twin-Plate Control Tube	22	7AH	6.3	0.15	Remote Cutoff Triode
						Sharp-Cutoff Triode
6AE7GT	Twin-Input Triode	13D	7AX	6.3	0.5	Class A Amplifier
6AG7Y+	Power Pentode	28	8Y	6.3	0.65	Class A Amplifier
6AG11	Twin Diade—Twin Triode	BA	12DA	6.3	0.75	Each Triode as Class A Amplifie
6AH4GT	Low-Mu Triode	13D	BEL	6.3	0.75	Vertical Deflection Amplifier
6AH6	Sharp-Cutoff Pentode	5C	7BK	6.3	0.45	Class A Amplifier
6AH9	Medium-Mu Triode— Sharp-Cutoff Pentode	8B	12HJ	6.3	0.9	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifie
6AJ8/ ECH81	Triode-Heptode Converter	9CA	6E	6.3	0.3	Triode Unit as Oscillator Heptode Unit as Mixer
6AK8/ EABC80	Triple Diade— High-Mu Triode	6E	9E	6.3	0.45	Triode Unit as Class A Amplifier
CADUOU						
6AK10	High-Mu Triple Triode	8C	12FE	6.3	0.9	Each Unit as Class A Amplifier

[♦] Industrial Type

	Grid Bias		Screen	Dicto	An Dista	Trans	Amplifi		Power	RC
Piate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Plate Cur- rent	AC Plate Resist- ance	Trans- conduct- ance	cation Factor	- Load	Out- put	Тур
Volts		Volts	mA	mA	Ohms	Micromhos		Ohms	Watts	
		For	other ch	aracteri	stics, refer	to Type 6	V6GT		<u> </u>	5760
Max.	Peak Inverse \	/olts, 1400		Max.	DC Output	mA, 100		Max. Peak F	Plate mA,300	5W40
			For othe	r rating	s, refer to	Type 5U4G				5X40
		75 (5)(40)								5Y40
Max. Po	eak Plate mA, 3 eak Plate mA, 4	375 (5Y4G) 400 (5Y4GA	5Y4GT)			For othe	r ratings,	refer to Ty	pe 5Y3G	5Y4G
	•									5Y40
	O Valta nas Dia	+= (D14C)			s, refer to		Min	Total Effec	+ Cupply	5Z3
	C Volts per Pla eak Inverse Vo		350		C Output m. eak Plate m		Imp	. Total Effec ed. per Plat	e, 50 ohms	E7/
Max. A	C Volts per Pla eak Inverse Vol	te (RMS), !	500	Max. DO	Output m/ ak Plate m	A, 125		Value of II 5 henri	nput Choke,	- 5Z4
		For	other ch	aracteri	stics, refe	r to Type 6	B4G			6A3
		For	other ch	aracteri	stics, refer	to Type 6N	17GT			6A6
		Fo	r other c	haracter	istics, refe	er to Type 6	A8			6A7 6A7
250	<b>— 3V</b>	100	2.7	3.5	360000	Oscillato	id (2): r-Grid d., 550	(1) Res.	V, 4.0 mA Conversion	6A8 6A8
Plate &	Target Suppl	y = 135	volts. Tr	iode Pla	te Resisto	r = 0.25	MΩ Targ	et Current	= 2.0 mA	
Grid Bi	as, — 10.0 v	olts; Shad	ow Angi	e, 0°.	Bias, O vo	oits; Angle	, 90°; P	late Currer	it, 0.5 mA.	_ 6ABS
Plate & Grid Bi	Target Suppl as, — 15.5 v	y == 135 olts: Shad	volts. Ir ow Angle	10de PI e. 0°. i	ate Resisto Bias, O vo	or == 1.0   lts; Angle,	MΩ larg 90°; P	et Current late Curren	= 1.9 mA t, 0.13 mA	6NS
300	3V	200	3.2	12.5	700000	5000			_	6AB
250	07			5.0				10000	8.0†	
250	Average I	Plate Curre	nt of Dri	ver = 5	loped in co .5 milliamp 32 milliam	oupling circ peres peres	uit	7000	3.7	6AC5
300	160Ω	150	2.5	10.0	1 M	9000				6AC
Та	rget Voltage, 1 Current, 1.2	150 volts. ( mA Control	control-E -Electroc	lectrode le Volta:	Voltage, – ge, 75 volts	–50 volts; \$ s; Angle, 0°	Shadow A '; Target	ngle, 135°; Current, 3 r	Target nA	6AD6
250	25V			3.7	19000	325	6			
250	16.5V	250	6.5	34.0	80000	2500		7000	3.2	6AD7
95	—15V			7.0	3500	1200	4.2			6AE50
250	— 1.5V			6.5	25000	1000	25			
250 250	—35V — 1.5V			0.01 4.5	35000	950	33			- 6AE6
250 250	9.5V			0.01	33000	330				
250	13.5V			10.0	4650	3000	14			6AE70
		For	other ch	aracteri	stics, refer	to Type 6	AG7			6AG7
125	<b>—</b> 1V			7.5	8500	7800	66			6AG
Max.	DC Plate Volts DC Cathode ma	, 500 A 60			M	ax. Peak Po ax. Plate D	sitive-Pu	se Plate Vo	Its, 2000	6AH4
300	160Ω	150	2.5	10.0	500000	9000		, ,.o natts		GAHO
250	<b>—9V</b>			8	7300	2750	20			
250	122Ω	150	6	25	5500	21000				- 6AI
50 250	Grid Res.,	125 47000 ohn	32	76 4.5			illator Gr	id Current,	2004	6AJ8
250	—2V	-7/000 UIII	6.7	3.25	1M			cond., 775		ECHE
250	—3V			1	58000	1200	70			6AK8
100	—ĭŸ			0.8	54000	1300	7Ŏ			EABC
200	230Ω			10	7500	7000	53			6AK
Max.	Peak Inverse P Peak Plate mA,	late Volts,	7500 (AI	os.)		Max.	Plate Di	ssipation, 5 ater-Cathod	watts	6AL

RCA Type	Name	Out- line	Terminal Dia- gram		nter or nent (F)	Values to right give operat- ing conditions and character- istics for indicated typical use
			_	Volts	Amperes	_
6AL7GT	Electron-Ray Tube	13C	8CH	6.3	0.15	Visual Indicator
6AM4	High-Mu Triode	6A	9BX	6.3	0.225	Class A Amplifier
				6.3	0.45	Diode Unit
6AM8	Diede-Sharp-Cutoff Pentode	6B	9CY	6.3	0.45	Pentode Unit as Class A Amplifier
6AN4	High-Mu Triode	5B	7DK	6.3	0.225	Class A Amplifier
6AN5+	Beam Power Tube	5C	7BD	6.3	0.45	Class A Amplifier
6AN8	Medium-Mu Triode—Sharp-Cutoff Pentode	68	9DA	6.3 6.3	0.45 0.45	Pentrode Unit as Class A Amplifier Amplifier
6AQ5	Beam Power Tube	5D	7BZ	6.3 6.3	0.45	Single Tube Class A Amplifier
UNUJ	DEAM FUNCT THUE	70	706	6.3	0.45	Push-Pull Class A ₁ Amplifier
6AQ6	Twin-Diode—High-Mu Triode	5C	78T	6.3	0.15	Triode Unit as Class A Amplifier
6AQ7GT	Twin-Diode—High-Mu Triode	13D	8CK	6.3	0.3	Triode Unit as Class A Amplifier
6AQ8	High-Mu Twin Triode	68	JAJ	6.3	0.435	Each Unit as Class A Amplifier
6AR5	Power Pentode	5D	6CC	6.3	0.4	Class A Amplifier
6AR8	Beam-Deflection Tube	6E	9DP	6.3	0.3	Color TV Demodulator
6AS6+	Dual Control RF Pentode	5B	7CM	6.3	0.175	Class A Amplifier
6AS7GA	♦ Low-Mu Twin Triode	19E	8BD	6.3	2.5	Voltage Regulator
	Duel Triede Chara Cuteff					Dual Triode Unit as Class A Amplifier
6AS11	Dual Triode—Sharp-Cutoff Pentode	8B	12DP	6.3	1.05	Pentode Unit as Class A Amplifier
6AT8	Medium-Mu Triode	6B	9DW	6.3	0.45	Triode Unit as Class A Amplifie
6AU4GT	Half-Wave Rectifier	136	406	6.3	1.8	Television Damper Service
6AU6	Sharp-Cutoff Pentode	5C	7BK	6.3 6.3	0.3 0.3	Class A Amplifier
6AU7	Medium-Mu Twin Triode	6B	9A	3.15 6.3	0.6 0.3	Each Unit as Class A Amplifier
	Medium-Mu Triode-Sharp-Cutoff					Triode Unit as Class A Amplifie
6AU8	Pentode	<b>6E</b>	9DX	6.3	0.6	Pentode Unit as Class A Amplifier
6AV5GT	Beam Power Tube	13D	6CK	6.3	1.2	Horizontal Deflection Amplifier
6AV11	Medium-Mu Triple Triode	8A	12BY	6.3	0.6	Each Unit as Class A Amplifier
6AW8	High-Mu Triode—Sharp-Cutoff Pentode	βE	9DX	6.3	0.6	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
6AX4GT	Half-Wave Rectifier	13D	406	6.3	1.2	Television Damper Service
						Triode Unit as Class A Amplifier
6AX8	Medium-Mu Triode—Semiremote Cutoff Pentade	6B	9AE	6.3	0.45	Pentode Unit as Class A Amplifier
6AY3	Half-Wave Rectifier	11D	SHP	6.3	1.2	Television Damper Service
6AY11	Twin Diode-High-Mu Twin Triode	8A	12DA	6.3	0.69	Each Triode Unit as Class A Amplifier
6B4G	Power-Triode	27B	5\$	6.3F	1.0	Class A Amplifier
685	Direct-Coupled Power Triode	26	6AS	6.3	0.8	Class A Amplifier
686G	Twin-Diede-High-Mu Triode	23	77	6.3	0.3	Triode Unit as Amplifier

[♦] Industrial type

	Grid Bias or		Screen Grid	Plate	AC Plate	Trans-	Amplifi-	Pow	er	— RÈA
Plate	Cathode Resistor	Screen Grid	Cur- rent	Cur- rent	Resist- ance	conduct- ance	cation Factor	Load	Out- put	Турс
Veits		Volts	mA	mA	Ohms	Micromhos		Ohms	Watts	
Grid	et Voltage, 315 Voltage = 0 vo ode Bias Res.,	olts	annrox		Defle	Voltage for F ting-Electro tage, 0	attern Cu des—No.	toff, —7 volt 1, No. 2 and	s approx. No. 3	6AL70
200	100Ω			10	8700	9800	85			6AM
	м	ax. DC Pla	te mA, 5	Max.	Peak Hea	ter-Cathode	Volts, ±2	200		
125	56Ω	125	3.2	12.5		7800				6AM
200	100Ω	-		13	7000	10000	70			GAN
120	1 <b>20</b> Ω	120	12	35	12500	8000		2500	1.3	GANS
150	— 3V			15	4500	4700	31			- CAN
125	56Ω	125	3.8	12	170000	7800				- 6AN
180 250	8.5V 12.5V	180 250	3.0 4.5	29.0 45.0	50000 50000	3700 4100	_	5500 5000	2.0 4.5	_ 6AQ!
250	—15V	250	5.0	70.0	60000			10000	10.0†	0/10.
100	1V			0.8	61000	1150	70			GAQ
250 250	3V 2V			2.3	58000 44000	1200 1600	70 70			6AQ7
250	— 2.3V			10		5900	57			6AQ
250	— 2.3V —18V	250	5.5	32.0	90000	2300		7600	3,4	6AR
250	300Ω	250		10		4000		7000		6AR
120	2V	120	3.5	5.2	110000	3200		(EC3 = 0\	<i>(</i> )	6AS
							970	(200 - 0.		
200	220Ω	r vi	other tr	9.2	4400	to Type 6A 4400	41			6AS7G
200	_ 2V			7	12400	5500	68			– 6AS1
200	125	125	5.2	24	70000	10500				— DM31
125	— 1V			12	6000	6500	40			6AT8
Max.	Peak Inverse F Peak Plate mA	, 1050				Max.	Average Plate Dis	Plate mA, 17 sipation 6.0	5 watts	6AU4
100 250	150Ω 68Ω	100 150	2.1 4.3	5.0 10.6	500000 1 M	3900 5200				6AU
100	0V		-	11.8	6250	3500	19.5			6AU
250	8.5V			10.5	7700	2200 4900	17			UAU
150	150Ω	105	2.4	9	8200		40			- 6AU
200	82Ω DC Plate Volts	125	3.4	15	150000	7000	- Dules D			
	DC Cathode m				Max.	Plate Dissip	e-Puise P ation, 11	late Volts, 5: watts	NUU (ADS.)	6AV5
250 100	8.5V 0V			10.5 11.8	7700 6500	2200 3100	17 20			GAV
200	2V			4		4000	70			
150	150Ω	150	3.5	13	200000	9500				6AW
				current	characteri	stic with a	ontrolled			
Max.	Peak Inverse I Peak Plate mA	1. 750	, 4400			Peak Heater		VOITS: 1 +300	)0** )	6AX40
Max. 150	DC Plate mA, 560Ω	125		18	5000	component r 8500	nust not e	exceed 900 vo	ilts	
250	120Ω	110	3.5	10	400000	4800				GAX
Max.	Peak Inverse	Plate Volts				Plate Dissip	ation, 6.5	watts		
Max.	Peak Plate mA DC Plate mA	A, 1100				Peak Heater		(	- 5000 - 300	6AY
250	— 2V		_	1.2	52700	1900	100			6AY1
250	—45V			60	800	5250	4.2	2500	3.5	6B40
				h A :		- 4- Tue- CN				005
		FOI	r otner c	naracteri	stics, rete	r to Type 6N	bG			6B5

[†] For two tubes at stated plate to plate load.

RCA Type	Name	Out- line	Terminal Dia- gram		ater or ment (F)	<b>Use</b> Values to right give operating conditions and characteristics for indicated typical use
			•	Volts	Amperes	
6B7 6B7\$	Twin-Diode—Remote-Cutoff Pentode	24B 24B	70	6.3	0.3	Pentode Unit as Amplifier
6B8	Twin-Diode—Semiremote-Cutoff Pentode	3	8E	6.3	0.3	Pentode Unit as Amplifier
6B8G	Twin Diode—Semiremote-Cutoff Pentode	23	8E	6.3	0.3	Pentode Unit as Class A Amplifier
6BA3	Half-Wave Vacuum Rectifier	308	9H P	6.3	1.2	Television Damper Service
6BC5	Sharp-Cutoff Pentode	5C	7BD	6.3	0.3	Class A Amplifier
6BC7	Triple Diode	6B	9AX	6.3	0.45	Each Unit-Half-Wave Rectifier
<b>★</b> 6BD4	Sharp-Cutoff Beam Triode	21C	8FU	6.3	0.6	Voltage-Control
★6BD4A	Sharp-Cutoff Beam Triode	21C	8FU	6.3	0.6	Voltage-Control
6BD6	Remote-Cutoff Pentode	5C	7BK	6.3	0.3	Class A Amplifier
6BD11	Dual Triode— Sharp-Cutoff Pentode	88	12DP	6.3	1.05	Triode No. 1 as Class A Amplifier Triode No. 2 as Class A Amplifier Pentode Unit as Class A Amplifier
6BF5	Beam Power Tube	5D	78Z	6.3	1.2	Class A Amplifier
6BF6	Twin-Diode—Medium-Mu Triode	5C	7BT	6.3	0.3	Triode Unit as Class A Amplifier
<b>6BG6G</b> A	Beam Power Tube	28B 21B	5BT 5BT	6.3	0.9	Horizontal Deflection Amplifier
6BH3 <b>a</b>	Half-Wave Rectifier	110	9HP	6.3	1.6	Television Damper Service
6BH8	Medium-Mu Triode— Sharp-Cutoff Pentode	8E	90X	6.3	0.6	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
6BJ3	Half-Wave Rectifier	8C	12BL	6.3	1.2	Television Damper Service
6BJ6A	Remote-Cutoff Pentode	5C	7CM	6.3	0.15	Class A Amplifier
6BJ7	Triple Diode	<b>6B</b>	9AX	6.3	0.45	Each Unit—Half-Wave Rectifier
6BK4 ★6BK4A	Beam Triede	21B	86C	6.3	0.2	Voltage-Control
★6BK4B	Beam Triode	21B	860	6.3	0.2	Shunt Voltage Regulator
6BK5	Ecam Power Tube	6E	9BQ	6.3	1.2	Class A Amplifier
6BK7A	Medium-Mu Twin Triode	6B	9AJ	6.3 6.3	0.45 0.45	Each Unit as Class A Amplifier
6BL4	Half-Wave Rectifier	13F	8GB	6.3	3.0	Television Damper Service
6BL7GT	Medium-Mu Twin Triode	13D	8BD	6.3	1.5	Vertical Deflection Amplifier
6BL8	Medium-Mu Triode— Sharp-Cutoff Pentode	<b>6</b> B	9DC	6.3	0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
6BN4	Medium-Mu Triode	5C	726	6.3	0.2	Class A Amplifier
6BN6	Beam Tube	50	7DF	6.3	0.3	Limiter and Discriminator
BQ6GT	Beam Power Tube	14D	6AM	6.3	1.2	Horizontal Deflection Amplifier
6BQ7	Medium-Mu Twin Triode	6B	IAP	6.3	0.4	Each Unit as Class A Amplifier
6BR8 N	Aedium-Mu Triode—Sharp-Cutoff Pentode	6B	9FA	6.3 6.3	0.45 0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A

^{*} See Safety Precautions at end of this section.

	Grid Bias		Screen	<b>-</b> 4 -		<b>-</b>		Powe	<u>r</u>	— REA
Plate	or Cathode Resistor	Screen Grid	Erid Cur- rent	Plate Cur- rent	AC Plate Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Load	Out- put	Туре
Volts		Volts	mA	mA	Ohms	Micromhos		Ohms	Watts	
	Triode: Pia it Triode: Pia 700	ate Volts, ate Volts, 00 ohms: P	300 max; 300 max. ower Ou	Grid Vo ; Plate r tput, 4 v	ilts, 0; Plat nA, 45; Pla vatts	e mA, 8; AF te Res., 240	Signal Vo 00 ohms; I	lts (Peak), 21 Load Resistand	e,	6B7 6B7S
						r to Type 12			-	6B8
250		125	2.3	9	600000	1125				6B8G
Ma Ma	ax. Peak Invers ax. Peak Plate ax. DC Plate m	se Plate Vo mA, 1000	oits, 500	0		k Heater-Ca		s {-5000** s }+300 eed 900 Volts		6BA3
			her char	acteristi	cs, refer to	Type 6BC5,	/6CE5			6BC5
M: M:	ax. Peak Invers ax. Peak Plate	se Plate Vo	olts, 330		Min. T	Max. i otai Effect.	DC Output Plate Sup	mA, 12 ply impedance	. 560Ω	6BC7
	DC Plate Volts Unregulated DC		olte 400			Max.	DC Plate			6BD4
Max.	DC Plate Volts Unregulated DC	, 27000	0115, 400			Max.	DC Plate	mA, 1.5		6BD4A
Max.   250	Unregulated DC — 3V	Supply V	olts, 550 3.0	9.0	800000	2000	Plate Diss	ipation, 25.0	watts	6806
200	3V 2V	100		7	12400	5500	68		=	0000
200	220Ω			9,2	9400	4400	41			_ 6BD11
135	100Ω	135	4	17	45000	10400	_=			CDFE
110	→ 7.5V	110	4.0	36.0	12000	7500		2500 Power 0	1.9	6BF5
250	— 9V			9.5	8500	1900	16	300 mil		6BF6
Max.	DC Plate Volts DC Cathode mA	A, 110		Max Max	. Plate Dis	sipation, <b>2</b> 0	watts	, 6600 (Abs.)		6BG6G
Max. I	Peak Inverse P Peak Plate mA, DC Plate mA, 1	, 1100	, 5500		Max.	Plate Dissipa Peak Heater	r-Cathode	Valta [- 5	5500 300	6BH3 <b>A</b>
150 200	5V 82Ω	125	3.4	9.5 15	5150 150000	7000	17	_=_		- 6BH8
Ma	ax. Peak Invers ax. Peak Plate ax. DC Plate m	e Plate Vo			Max. Pea	k Heater-Cat		( <del>+</del> 300		6BJ3
100	1V	100	3.5	9	250000	3650				6BJ6A
Ma Ma	x. Peak Invers x. Peak Plate	e Plate Vo mA, 10	lts, 330		Max.	Max. I Peak Heater	DC Output Cathode V	mA, 1 olts, +100, -	_330	6BJ7
Max.	DC Plate Volts Unregulated DC	. 27000	olts, 600 ax. Plat	00 e Dissipa		Max. DC I	Plate mA.			6BK4 6BK4 <b>A</b>
	Max. D Max. Unregula	C Plate Vo	its, 2700	00 ts. 60000	)	Ma	x. Average	Plate mA, 1.	6 atts	6BK4B
250	— 5V	250	3.5	35	100000	8500		6500	3.5	6BK5
150	56Ω			18	4600	9300	43	Grid-No. for Cutof	1 Volts	6BK7A
Max. F	Peak Inverse P Peak Plate mA, DC Plate mA, 2	1200	4500 (A	bs.)		eak Heater-(		olts { -4500* +300		6BL4
Max. [	DC Plate Volts, DC Cathode mA	500	it), 60		Max, P	eak Positive	-Pulse Pla	te Volts, 2000 Unit), 10 wat	(Abs.)	6BL7GT
100	2V	-1		14	_=_	5000	20			- 6BL8
170	2V	170	2.8	10	400000	6200				
150	220Ω			9	6300	6800	43			6BN4
May	O Dinto Volto		er chara	cteristci		Type 6BN6/		to Volta EFOO	(Abe )	6BN6
Max. I	OC Plate Volts, OC Cathode mA	, 110			Max. P	eak Positive late Dissipal	tion, 11 w	te Volts, 5500 atts		6BQ6GT
150	220Ω			9.0	5800	6000	35	Grid-No. for Cutofi	1 Volts 1, —10	6BQ7
125	— 1 <b>V</b>			13.5	7500		40		=	- cpno
125	<b>— 1V</b>	110	3.5	9.5	200000	5000			_	6BR8

RCA Type	Name	Out- line	Terminal Dia- gram		nter or nent (F)	Use Values to right give operating conditions and characteristics for indicated typical use
			_	Volts	Amperes	<del>-</del>
68\$3	Half-Wave Rectifier	11D	9HP	6.3	1.2	Television Damper Service
6BS8	Medium-Mu Twin Triode	6B	9AJ	6.3	0.4	Each Unit as Class A Amplifier
6BV8	Twin Diode-Medium-Mu Triode	6B	9FJ	6.3	0.6	Triode Unit as Class A Amolifier
6BW4	Full-Wave Rectifier	6E	901	6.3	0.9	With Capacitive Input Filter
00114	Lait-Maac sectines	0.		0.3	0.3	With Inductive Input Filter
6BW8	Twin Diode— Sharp-Cutoff Pentode	6B	9H K	6.3	0.45	Pentode Unit as Class A Amplifie
						Vertical Deflection Oscillator
6BX7GT	Medium-Mu Twin Triode	13D	8BD	6.3	1.5	Vertical Deflection Amplifier
6BY5GA	Full-Wave Rectifier	188	6CN	6.3	1.6	Television Damper Service
6BY11	Beam Power Tube— Sharp-Cutoff Pentode	86	12EZ	6.3	1.2	Beam Unit as Class A Amplifier Pentode Unit as Class A Amplifie
6BZ7	Medium-Mu Twin Triode	6B	LAB	6.3	0.4	Each Unit as Class A Amplifier
6BZ8	Medium-Mu Twin Triode	6B	9AJ	6.3	0.4	Each Unit as Class A Amplifier
6C5GT	Medium-Mu Triode	2A 14A	6Q	6.3	0.3	Class A Amplifier
6C6	Sharp-Cutoff Pentode	24A	6F	6.3	0.3	Amplifier Detector
6C7	Twin-Diode—Medium-Mu Triode	24B	76	6.3	0.3	Triode Unit as Class A Amplifier
6C8G	Medium-Mu Twin-Triode	23	86	6.3	0.3	Each Unit as Class A Amplifier
6C10	High-Mu Triple Triode	8A	12BQ	6.3	0.6	Each Unit as Class A Amplifier
6CA7	Power Pentode		8ET	6.3	1.5	Class A Amplifier Push-Pull Class AB, Amplifier
6CB5	Beam Power Tube	28A	8GD	6.3	2.5	Horizontal Deflection Amplifier
6CB6	Sharp-Cutoff Pentode	5C	7CM	6.3	0.3	Class A Amplifier
6CD6G	Beam Power Tube	288	5BT	6.3	2.5	Horizontal Deflection Amplifier
6CE3	Half-Wave Vacuum Rectifier	86	12 <b>6</b> K	6.3	2.5	Television Damper Service
6CE5	Sharp-Cutoff Pentode	5C	7BD	6.3	0.3	Class A Amplifier
6CF6	Sharp-Cutoff Pentode	5C	7CM	6.3	0.3	Class A Amplifier
6CG3/ 6CD3	Half-Wave Rectifier	8F	12FX	6.3	1.8	Television Damper Service
6CG8	Medium-Mu Triode—Sharp-Cutoff Pentode	<b>6</b> B	9GF	6.3 6.3	0.45 0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
6CH8	Medium-Mu Triode—Sharp-Cutoff Pentode	€B	9FT	6.3	0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
6CK3	Half-Wave Vacuum Rectifier	308	9HP	6.3	1.2	Television Damper Service
6CK4	Low-Mu Triode	13F	81B	6.3	1.25	Vertical Deflection Amplifier
6CL8	Medium-Mu Triode—Sharp-Cutoff Tetrode	<b>6</b> B	9FX	6.3	0.45	Triode Unit as Class A Amplifier Tetrode Unit as Class A Amplifier

	Grid Bias		Screen			_		Po	wer	. 804	
Plate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Plate Cur- rent	AC Plate Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Load	Out- put	* RCA Type	
Velts		Yalts	mA	mA	Ohms	Micromhos		Ohms	Watts		
Max. Max. Max.	Peak Inverse Peak Plate mA DC Plate mA,	Plate Volts, 1, 1100 200	5000			Plate Dissipa Peak Heater-			5000 300	6BS3	
150	220Ω			10	5000	7200	36			6BS8	
200	330Ω			11	5900	5600	33			6BV8	
Max.	AC Volts per I Peak Inverse	Volts, 1275 Tota	Effect.	Supply	lmped. per	Max Plate, 82 of Max	. Peak Pla ms c. DC Out	out mA, 62.5 ate mA, per P put mA, 62.5		- 6BW4	
Max.	Peak Inverse	Volts, 1275	•	ue of In	put Choke.	Mai 10 henries	k. Peak Pi	iate mÁ per P	late, 350		
250	68Ω	110	3.5	10	250000	5200				6BW8	
Max.	DC Plate Volts	s, 500					Ma	ax. DC Cathod	e mA, 180		
Max.	DC Plate Volts DC Cath. mA,	s, 500	Max	. Peak F	ositive-Pul	se Plate Vol	ts, 2000 (	Abs.) e; 12 watts bo	th plates	-6BX7GT	
Max. Max.	Peak Inverse Peak Plate mA DC Plate mA,	Plate Volts, 1, 525	3000 (A	bs.)	Max.	Peak Heater-	Cathode V	/oits: { -450 +100		6BY5GA	
170	82Ω	140	3.9	74	33000	4900		2500	4	- 6BY11	
150	180Ω	100	3.4	2.8	110000	2500		(grid no. 1	to plate)		
150	220Ω			10	5300	6800	36			6BZ7	
125	100Ω			10	5600	8000	45			6BZ8	
250	— 8V	_	_	8.0	10000	2000	20			6C5 6C5GT	
For other characteristics, refer to Type 6J7											
250	<b>— 9</b> V			4.5	16000	1250	20			6C7	
250	4.5V			3.2	22500	1600	36			6C8G	
250	_2V			1.2	62500	1600	100			- 6C10	
100	<u>1V</u>			0.5	80000 15000	1250 11000	100	2000			
265 450	—13.5V 232Ω	250 450	15 20	120	13000	11000	=	2000 6500	40	- 6CA7	
Max.	DC Plate Voits DC Cathode m	s, 700		120	Max. Max.	Peak Positive Plate Dissipa	e-Pulse Pl	ate Volts, 680		6CB5	
125	56Ω	125	3.7	13	280000		_			6CB6	
Max. Max.	DC Plate Volts DC Cathode m	s, 700 A, 200			Max. Max.	Peak Positive Plate Dissipa	e-Pulse Pl Ition, 20 v	ate Volts, 700 watts	00	6CD6G	
		For other	charact	eristics,	refer to T	ype 6CE3/6C	D3/6DT3			6CE3	
125	1V	125	2.3	11	300000	7600				6CE5	
125	56Ω	125	3.7	12.5	300000	7800				6CF6	
	ak Inverse Plat ik Plate mA, 21				e mA, 350 issipation,	6.5 watts		r Cathode Vol	ts: ∫+300 1—5000	6CG3/ 6CD3	
100	— 1V			12	6000	6500	40			6CG8	
250	- 1V	125	2.2	9	300000	5500				ocua	
200	6V			13	5750	3300	19				
200	180Ω	150	2.8	9.5	300000	6200	_			6CH8	
N	lax. Peak Inver lax. Peak Plate lax. DC Plate n	mA, 1200	lts, 5200	)		ak Heater-Ca mponent mus		ts {-5200* +300 eed 900 volts		6CK3	
Max. Max.	DC Plate Volt: Peak Cathode	s, 550			Max. Max.	Peak Positiv Plate Dissipa	e-Pulse P ation, 12	late Volts, 20		6CK4	
125	<u> </u>			14	5000	8000	40			6CL8	
125	<b>— 1V</b>	1 <b>2</b> 5	4	12	120000	6000				UULÖ	

RCA Type	Name	Out- line	Terminal Dia- gram	Heater or Filament (F)		Use Values to right give operating conditions and characteristics for indicated typical use		
			_	Volts	Amperes	_		
6CM6	Beam Power Tube	6E	9CK	6.3	0.45	Class A Amplifier		
6CM8	High-Mu TriodeSharp-Cutoff Pentode	6B	9FZ	6.3	0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier		
6CQ4	Half-Wave Rectifier	13G	4CG	6.3	1.6	Television Damper Service		
6CR6	Diode-Remote-Cutoff Pentode	5C	7EA	6.3	0.3	Pentode Unit as Class A Amplifier		
6CT3	Half-Waye Rectifier	6Н	9RX	6.3	1.2	Television Damper Service		
6CU8	Medium-Mu Triode— Sharp-Cutoff Pentode	68	9GM	5.3	0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifie		
6CW5	Power Pentode	86	3CA	6.3	0.76	Vertical-Deflection Amplifier		
6D4+	Gas Triode	5C	5AY	6.3	0.25	Thyratron		
6D6	Remote-Cutoff Pentode	24A	6F	6.3	0.3	Amplifier Mixer		
6D7	Sharp-Cutoff Pentode	24A	7H	5.3	0.3	Amplifier Detector		
6D8G	Pentagrid Converter	23	8A	6.3	0.15	Converter		
6D10	High-Mu Triple Triode	8A	12BQ	6.3	0.45	Each Unit as Class A Amplifier		
6DA4	Half-Wave Rectifier	13D	4CE	6.3	1.2	Television Damper Service		
6DB5	Beam Power Tube	6F	9GR	6.3	1.2	Class A Amplifier		
6DC8	Twin Diode—Remote-Cutoff Pentode	6E	9HE	6.3	0.3	Class A Amplifier		
6DC8/ EBF89	Twin Diode-Semiremote Cutoff Pentode	6E	9HE	6.3	0.3	Pentode Unit as Class A Amplifier		
6DE4	Half-Wave Vacuum Rectifier	13 <b>G</b>	4CG	5.3	1.6	Television Damper Service		
6DL4/ EC88	High-Mu Triode	6M	9NY	6.3	0.165	Class A Amplifier		
6DL5 6DL5/ EL95	Power Pentode	5E	7DQ	6.3	0.2	Class A Amplifier		
6 <b>DM4</b> 6 <b>DM</b> 4A	Half-Wave Rectifier	13 <b>G</b>	4CG	6.3	1.2	Damper Service		
6DN6	Beam Power Tube	21B	5BT	6.3	2.5	Horizontal Deflection Amplifier		
6DQ4	Half-Wave Rectifier	13F	4C <b>G</b>	5.3	1.2	Damper Service		
6DQ6A 6DQ6B	Beam Power Tube	20	6AM	6.3	1.2	Horizontal Deflection Amplifier		
6DT6	Sharp-Cutoff Pentode	5C	7EN	6.3	0.3	Class A Amplifier		
6DW4	Half-Wave Rectifier	110	9HP	6.3	1.2	Television Damper Service		
6DW4A	Half-Wave Rectifier	110	9НР	6.3	1.2	Television Damper Service		
6DW5	Beam Power Tube	98	9C K	6.3	1.2	Vertical Deflection Amplifier		
6DX8	High-Mu Triode— Sharp-Cutoff Pentode	6E	энх	6.3	0.72	Triode Unit as Class A Amplifie Pentode Unit as Class A Amplifier		

		Grid Bias or		Scree Grid	n Plate	AC Plate	Trans-	Amelia.	P	ower	RCA
Piate	:	Cathode Resistor	Screen Grid	Cur- rent	Cur- rent	Resist- ance	conduct- ance	Amplifi- cation Factor	Load	Out- put	Турс
Volts	;		Volts	mA	mA	Ohms	Micrombos		Ohms	Watts	
250 250		12.5V 12.5V	250	4.5	- 49.5 45	1960 50000	5000 4100	9.8	(Triode C 5000	onnected) 8	6CM6
250		— 2V			1.8	50000	2000	100			6CM8
250	<u></u>	180Ω	150	2.8	9.5	600000	6200				- OUMU
Max. Max.	Peak Peak	Inverse P Plate mA,	1200	5500	Max. DC Max. Plat	Plate mA e Dissipa	, 190 tion, 6.5 v	Max. vatts Cath		ter {+300 -5500	6CQ4
250		2V	100	2.6	9.6	800000	2200				6CR6
		Max.	k inverse Pi Peak Plate Average Pla	mA, 1	<b>20</b> 0				ipaation, 6.9 Cathode Vol	( 5000	6CT3
125 125		<u>1</u> 56Ω	125	3.8	- 17 12	4100 170000	5800 7800	24			8039
М	ax. D	C Plate Vol	ts. 275	3.6	12	Max.	Peak Positi	ve-Pulse P	ate Volts, 2	200	6CW5
450			oltage drop		25	_	Plate Dissip Pak Anode C				6D4
		25 mA	16_Volt				er to Type 6				6D6
							er to Type (				6D7
250		- 3V	100	2.7	3.5	360000	Anode-G Oscillate Transcor	rid (2): 25 or-Grid (1) nd., 550 mi	0 max. vo Resistor. cromhos.	lts, 4 mA Conversion	6D80
125		—1V			4.2	13600	4200	57			6D1
Max. Max.	Peak Peak	Inverse P Plate mA	late Volts, , 900		Max. DC Max. Plate	Plate mA Dissipati		Max. tts Cathod	Peak Heater e Volts:	{+300 -4400	6DA
200	)	180Ω	. 125	2.2	46	28000	8000		4000	3.8	6DB
250		_ 2V	100	2.7	9	1 M	3800				6DC
200	)	—1.5V	100	3.3	11	600000	4500		<del>-</del>		6DC8 EBF8
			For o	ther ch	aracterist.	ics, refer	to Type 6DE	4/6CQ4			6DE
160		100Ω			- 12.5		13500	<b>6</b> 5			6DL4 EC8
200 250		230Ω 320Ω	200 250	4.2 4.5	23 24	_	_	=	8000 10000	2.3	6DL5 6DL5 EL95
IAI	IOA. F	eak neater-	Plate Volts —Cathode V —Cathode V	, 5000 olts, olts, +	Max. F -5000 (DC -300 (DC C	eak Plate Component omponent	mA, 1100 t Not to Exc Not to Exce	Max. DC eed 900 Vo ed 100 Vol	Plate mA, 1 olts) ts)	75	6DM 6DM
M	ax. D	C Plate Vol	ts, 700 mA, 200			Max. Max.	Peak Positi Plate Dissi	ve-Pulse P	late Volts, 6 watts	600 (Abs.)	6DN
M	lax. F		Volts, 5500	)				Max. DC	Plate mA, 1 te Dissipati	175 on. 6 watts	6DQ
M	lax. D	C Plate Vol C Cathode		Q6A) Q6B)		Max. Max.	Peak Positi Plate Dissi	ve-Pulse P	late Volts, 6		6DQ6
150		560Ω	100	2.1	1.1	150000	515				6DT6
M	ax. P	eak Inverse eak Plate m C Plate mA		, 5000			Plate Dissi Peak Heate		Volts: {-	- 5000 - 300	6DW
		Max	ik Inverse P c. Peak Plat Average Pla	e mA, i	1300				ssipation, 8. -Cathode Vo	( 5500	6DW
N N	Max. I	DC Plate Vo DC Cathode	lts, 330 mA, 65				Max. Pea Max. Pla	k Positive- le Dissipat	Pulse Plate ion, 11 watt	Volts, <b>22</b> 00 s	6DW
200 170		— 1.7V — 2.1V	170	3	3 18	100000	4000 11000	65			- 6DX8
200 220		2.9V 3.4V	200 220	3	18 18	130000 150000	10400 10000				- טאאני

RGA Type	Name	Out- line	Terminal Dia- gram	Fila	ater or ment (F)	Use  Values to right give operating conditions and characteristics for indicated typical use
				Volts	Amperes	
6DZ7	Twin Power Pentode	19B	8JP	6.3	1.52	Class A Amplifier  Both Units as Push-Pull Class AB ₁ Amplifier
6 <b>E</b> 6	Twin Power Amplifier	26	7B	6.3	0.6	Push-Pull Class A Amplifier
6E7	Remote-Cutoff Pentode	24A	7H	6.3	0.3	Amplifier
6EA4	High-Mu Triode	16D	12FA	6.3	0.2	Shunt Voltage Regulator
6EA5	Sharp-Cutoff Tetrode	5C	7 <b>EW</b>	6.3	0.2	Class A Amplifier
6EA7	Dual Triode	13B	8BD	6.3	1.05	Vertical Deflection Oscillator Vertical Deflection Amplifier
6EC4A/ EY500	Half-Wave Vacuum Rectifier	35C	6EC4	6.3	2.1	Television Damper Service
6EH4	Beam Triode	16E	12FA	6.3	0.2	Shunt Regulator
6EH7	Semiremote-Cutoff Pentode	60	9AQ	6.3	0.3	Class A Amplifier
6EH8	Medium-Mu Triode—Sharp-Cutoff Pentode	<b>6B</b>	ale	6.3	0.45	Triode Unit as Class A Amplifie Pentode Unit as Class A Amplifier
<b>★</b> 6EJ4A	Beam Triode	16G	12HC	6.3	0.2	Voltage Control
6EJ7	Sharp-Cutoff Pentode	6C	SAQ	6.3	0.3	Class A Amplifier
6EL4 6EL4A	Beam Triode	21D	8MW	6.3	0.2	Shunt Voltage Regulator
6EM7	Dual Triode	13A	8BD	6.3	0.925	Class A Amplifier
6EQ7	Diode—Remote-Cutoff Pentode	6E	9LQ	6.3		Pentode Unit as Class A Amplifier
6ES5	High-Mu Triode	5C	7FP	6.3	0.2	Class A Amplifier  Each Unit as Class A Amplifier
6E\$8	Variable-Mu Twin Triode	<b>SB</b>	9AJ	6.3	0.365	Cascode-Type Amplifier
6ET7	Twin Diode—— Sharp-Cutoff Pentode	6É	SLT	6.3	0.75	Pentode Unit as Class A Amplifier
6EU8	Medium-Mu Triode— Sharp-Cutoff Pentode	6B	SJF	6.3	0.45 F	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
6EV7	High-Mu Twin Triode	SE	9LP	6.3	0.6	Relay Control
6EX6	Beam Power Tube	21B	5BT	6.3	2.25	Horizontal Deflection Amplifier
6EY6	Beam Power Tube	13F	7AC	6.3	0.68	Vertical Deflection Amplifier
6EZ5	Beam Power Tube	13F	7AC	6.3	0.8	Vertical Deflection Amplifier
6EZ8	high-Mu Triple Triode	6B	9KA	6.3	0.45	Each Unit as Class A Amplifier
6F4+	Triede	acora	7BR	6.3	0.225	AF, RF Amplifier and Oscillator
<b>6F5</b> 6F5GT	High-Mu Triode	3 14A	5M 5M	6.3	0.3	Class A Amplifier
6F6		2B	70			Pentode Class A Amplifier
6F6GT	Power Pentode	25 13F	7\$ 7\$ 7\$	6.3	0.7	Triode□ Class A Amplifier Pentode Push-Pull Class A
6F7	Low-Mu Triode—Remote-Cutoff Pentade	24B	78	6.3	0.3	Amplifier Triode Unit as Class A Amplifier Pentode Unit as Class A
6F86	Medium-Mu Twin Triode	23	8 <b>G</b>	6.3	0.6	Amplifier Each Unit as Class A Amplifier
SFA7	Diode—Sharp-Cutoff, Twin-Plate Tetrode	6E	9MR	6.3		etrode Unit as Class A Amplifier
6FE5	Beam Power Tube	136	8KB	6.3	1.2	Class A Amplifier

[♦] Industrial type

^{*} See Safety Precautions at end of this section.

	Grid Bias or		Screen Grid	l Plate	AC Plate	Trans-	Amplifi-	Po	Wer	- RCA
Piate	Cathode Resistor	Screen Grid	Cur- rent	Cur- rent	Resist- ance	conduct- ance	cation Factor	Load	Out- put	Турс
Volts		Volts	mÅ	mA	Ohms	Micrombos		Ohms	Watts	
250	— 7.3V	250	5.5	48	38000	11300				- 4037
400 300	11V 120Ω	250 250	13 15	100 80	_		=	9000 9000	18 12	6DZ7
250	27.5V							14000	1.60†	6E6
			other c	haracteri		to Type 6U				6E7
Max. Max.	DC Plate Volts Unregulated Di	i, 27000 C Plate Su	pp!y Val	ts, 60000		ax. Plate Di ax. DC Plate		30 watts		6EA4
250	— 1V	140	0.95	10	150000	8000				6EA5
250	3			2	30000	2200	66			- 6EA7
175 M	—25 ax. Peak Inver	se Plate V	olts, 560	40	920	6000	5.5			6EC4A
M:	ax. Peak Plate ax. DC Plate m	mA, 800 A, 440				Max. Plate x. Peak Hea	ter-Cathode	n, 11 Watts Volts, —	6300	EY500
Max. DC G	Volts, 27000 Grid Volts, —13	35 N	nax. Pea Nax. DC	k Grid Vo Plate mA,	its, —440 1.6	Max. F	Plate Dissip	ation, 30 v	vatts	6EH4
200	<u> </u>	90	4.5	12	500000	12500				6EH7
125	<u> </u>			13.5		7500	40			6EH8
125	— 1V	125	4	12	170000	6000				
Ma Tyj	x. DC Plate Vo pical Unregulat	olts, 27000 ted DC Sup	piy Valt	s, 36000		Max. ( Max. Plate	C Plate m. Dissipation	A, 1.5 ı, 40 watts		6EJ4A
200	- 2.5V	200	4.1	10	350000	15000				6EJ7
		F	or other	characte	ristics, ref	er to Type (	SLJ6			6EL4
		For oth	er char	acteristic	s refer to	Type 6EM7/	SFA7			6EL4A 6EM7
100	0	100	3.5	9	250000	3800		2 megohms	hynassed)	6EQ
200	-1			10	8000	9000	75			6ES
90	— 1.2V		_	15	2500	12500				6ES8
180				15		12500				0000
200 60	100Ω 0V	150 150	5.5 18_	25 55	60000 (Ins	11500 tantaneous	plate knee	characteri:	stics)	6ET7
150 125	56Ω —1V	125	4	18 12	5000 80000	8500 6400	40			6EU8
250 150	0V 0V			18.5 10.0	Grid Vo	olts for Plate	μA 100 =	_9 2500 _5 78	)-ohm	6EV7
175	_30V	175	3.3	67	8500	7700			lay	6EX6
250	—17.5V	250	3	44	60000	4400				6EY6
250		250	3.5	43	50000	4100				6EZ5
125	<u>-1</u>			4.2	13600	4200	57			6EZ8
80	150Ω			13	2900	5800	17			6F4+
										6F5
100 <b>2</b> 50	— 1V — 2V			0.4 0. <b>9</b>	85000 66000	1150 1500	100 100			6F5GT
250 285	16.5V 20V	250 285	6.5 7.0	34.0 38.0	80000 78000	2500 2550		7000 7000	3.2 4.8	6F6
250	_20V		7.0	31.0	2600	2600	6.8	4000	0.85	6F6G
315	24V	285	12.0 🗆	62.0□				10000	11.0†	6F6GT
100	— 3V			3.5	16000	500	8			057
250	— 3V	100	1.5	6.5	850000	1100			_	6F7
		For	other c	haracteri	stics, refer	to Type 6J5				6F8 <b>G</b>
100 Use either	0 plate with un	100 used plate	3 ground	2.2 ed	130000	1900(With	2.2 megoh	m No.1 gri	id resistor)	6FA7

[†] For two tubes at stated plate-to-plate load.

RCA Type	Name	Out- line	Terminal Dia- gram		ater or nent (F)	Values to right give operating conditions and character istics for indicated typical use
			-	Yolts	Amperes	
6FG6/ EM84		R	efer to type	e EM84/6	FG6	
6FJ7	Medium-Mu Dual Triode	88	12BM	6.3	0.9	Unit No. 1 as Class A Amplifier Unit No. 2 as Class A Amplifier
6FM8	Twin Diade High-Mu Triode	6B	9KR	6.3	0.45	Triode Unit as Class A Amplifier
6FQ5A	High-Mu Triode	5C	7FP	6.3	0.18	Class A Amplifier
6FQ7	Medium-Mu Twin Triode	6E	9LP	6.3	0.6	Each Unit as Class A Amplifier
6FV6	Sharp-Cutoff Tetrode	5C	7FQ	6.3	0.2	Class A Amplifier
6FV8	Medium-Mu Triode—Sharp-Cutoff Pentode	68	9FA	6.3	0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
6FV8A	Medium-Mu Triode Sharp-Cutoff Pentode	6B	9FA	6.3	0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
6FW5	Beam Power Tube	19B	6CK	6.3	1.2	Horizontal Deflection Amplifier
6FW8	Medium-Mu Twin Triode	6B	9AJ	6.3	0.4	Each Unit as Class A Amplifier
6FY5/ EC97	High-Mu Triode	5C	7FP	6.3	0.2	Class A Amplifier
6G6G	Power Pentode	22	7\$	6.3	0.15	Pentode Class A Amplifier
6611	Beam Power Tube—Sharp-Cutoff Pentode	8B	12BU	6.3	1.2	Beam Power Unit as Class A Amplifier Pentode Unit as Class A
6GB5	Beam Power Tube	10E	SNH	6.3	1.38	Amplifier Horizontal Deflection Amplifier
6GF5	Beam Power Tube	8D	12BJ	6.3	1.2	Horizontal Deflection Amplifier
6GF7	Dual Triode	11A	9QD	6.3	0.985	Vertical Deflection Oscillator Vertical Deflection Amplifier
6GH8	Medium-Mu Triode—Sharp-Cutoff Pentode	6B	9AE	6.3	0.45	Triode Unit as Horiz. Defl. Osc.  Pentode Unit as Horiz. Defl. Osc.
6GJ5	Novar Beam Power Tube	18A	9QK	6.3	1.2	Horizontal Deflection Amplifier
6GJ7	Medium-Mu Triode— Sharp-Cutoff Pentode	61	APE	6.3	0.41	Pentode Unit as Class A Amplifier  Pentode Unit as Class A  Amplifier
6GJ8	Medium-Mu Triode—Sharp-Cutoff Pentode	6B	9AE	6.3	0.6	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
6GL7	Dual-Triode	13B	8BD	6.3	1.05	Unit 1 as Class A Amplifier Unit 2 as Class A Amplifier
6GM5	Power Pentode	10D	9MQ	6.3	8.0	Class A Amplifier
6GQ7	Triple Diode	6B	9QM	6.3	0.45	Each Unit as Half-Wave Rectifier
6GT5	Beam Power Tube	17B	9NZ	6.3	1.2	Horizontal Deflection Amplifier
6GU5	Beam Hexode	5C	7GA	6.3	0.22	Class A Amplifier
6GV8	High-Mu Triode Power Pentode	29	9LY	6.3	0.9	Triode Unit as Class A Amplifie Pentode Unit as Class A Amplifier
6GW6	Beam Power Tube	20A	6AM	6.3	1.2	Horizontal Deflection Amplifier
6GX6	Sharp-Cutoff Pentode	5C	7EN	6.3	0.45	Class A Amplifier

	Grid Blas		Screen	DI	10 51.1	<b>*</b>		Powe	er	
Plate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Plate Cur- rent	AC Plate Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Load	Out- put	RCA Typ
Volts		Voits	mA	mA	Ohms	Micromhos		Ohms	Watts	
									<u>'</u>	6FG6/ EM84
250 250	8 9.5		=	8 41	8000 2000	2500 7700	22.5 15.4			6FJ7
<b>2</b> 50	<b>—</b> 3		_	1	58000	1200	70			6FM
<b>13</b> 5	1.2			8.9	6300	12000	74			6FQ5A
250	— 8V			9	7700	2600	20			6FQ7
125	-1	80	1.5	10	100000	8000				6FV
125	<u> </u>	_=		14	5000	8000	40			6FV8
125	<u> </u>	<b>12</b> 5	4	12	200000	6500				
125	<u>-1</u>		<del></del>	12	5600	8000	45			6FV8A
125	— 1	125 Volta 770	4	12	20000	6500	Dulas Dista			
	Max. DC Plate Max. DC Catho	de mA, 61	0		Max. Pe	x. Plate Dis	ruise Plate sipation, 1	Volts, 6500 8 watts		6FW5
100	1.2V			15	2500	13000	33			6FW8
135	-17			11	<del></del>	13000	70		_	6FY5/ EC97
180	<u> </u>	180	2.5	15.0	175000	2300		10000	1.1	6G6G
120	<u> </u>	110	4	49	10000	7500		<b>2</b> 500	2.3	- 6G11
150	150Ω	150	3.5	15	20000	9500				•
	DC Plate Volts DC Cathode m				Max. Max.	Peak Positiv Plate Dissip	e-Pulse Pla ation, 17 v	ate Volts, 770 vatts	00	6GB5
Max. Max.	DC Plate Volts DC Cathode m/	, 770 1, 160			Max. Max.	Peak Positiv Plate Dissip	e-Pulse Plation, 9 wa	ate Voits, 500 atts	00	6GF5
Max. Max.	DC Plate Volts DC Cathode m	, 330 A. 22				Plate Dissip				
Max.	DC Plate Volts DC Cathode m	, 330			Max.	Peak Positiv	e-Pulse, P	late Volts, 15	00 (Abs.)	- 6 <b>GF</b> 7
	DC Plate Volts					Plate Dissip Max. Plate Di			<del></del>	
Max. Max.	DC Plate Volts Peak NegPuls	, 350 e Grid Vo	ts. 175	Max Max		hode mA, 30	0 Max.	. Plate ipation, 2.5 w	atte	- 6GH8
250	-22.5V	150	2.1	70	15000	7100				6GJ5
100	<u> </u>	_=		15		9000	20			- 6G17
170	— 1.2V	120	3	10	350000	11000	(Grid N	Factor, 55 <u>o.</u> 2 to Grid 1	No. 1)	0037
125	<u> </u>			13.5	5000	8500	40			- 6GJ8
125	<u> </u>	125	4.5	12	150000	7500				
250 175	—3V —25V			<b>2</b> <b>4</b> 6	30000 780	2200 6400	66 . 5			6GL7
300	—10V	300	8	60	29000	10200		3000	11	6GM5
	Max. Peak I Max. RMS P Max. Peak P	late Volts, late mA,	117			Max. Min. To Supply I	DC Average otal Effect mpedance,	e mA, 9 ive Plate 300 ohms		6GQ7
Max. Max. Max.	DC Plate Volts DC Cathode ma Plate Dissipat	, 770 A, 175 ion, 17.5 v	watts		max.	Peak NegP Grid-No. 2 V	ulse Grid-N /olts, 220	io, 1 Volts, - ate Volts, 650		6GT5
135	0.4V			9	67 <b>00</b> 0	15000				6GU5
100	— 0.8V			5	7600	6500	50		_	CUNO
170	<b>—15</b>	170	2.7	41	25000	7500				6GV8
250	-22.5V	150	2.1	70	15000	7100				6GW6
150	180Ω	100	3	3.7	140000	3700	(Gri	d No. 1 to pl	ate)	6GX6

6GZ5 Power  6HS 6H6GT Twin  6H6G HB6/ 6HB6/ 6HB6/ 6HB7 Medium-N 6HG5 Beam Po  6HG5 Beam Po  6HG5 Beam Po  6HJ5 Beam Po  6HJ5 Beam Po  6HJ5 Beam Po  6HK5 High-M 6HK5 Semiremote-C 6HR6 Semiremote-C 6HR6 Semiremote-C 6HU8/ ELL80 Twin F ELL80 High-Mu 6HZ5/ 6BU5 Beam 6HZ5/ 6JD5 Beam 6HZ8 High-Mu 5harp-Cutor 6JGWA+ 6J5 Medium-Mu 6J5GT Medium-Mu 6J6WB+ 6J7 6J7G Sharp-Cut 6J8G Triode-Hepto 6J9 High-Mu Triode-Hepto 6J9 High-Mu Triode-Hepto	Name	Out- line	Terminal Dia- gram	H	eater or ament (F)	Use Values to right give operating conditions and characteristics for indicated typical use
6GZ5 Power  SHS 6H6GT Twin  6H6G Power 6H86 Power 6H86 Power 6H85 Beam Po 6H6S Medium-M 6H15 Beam Po 6H15 Beam Po 6H15 Beam Po 6H18 Diode—Sharp-Cuto 6H15 Beam Po 6H18 Sharp-Cuto 6H15 Beam Po 6H18 Sharp-Cuto 6H15 Beam Po 6H18 Sharp-Cuto 6H15 Beam Po 6H18 Semiremote-C 6H18 Semiremote-C 6H18 Semiremote-C 6H18 Twin F 6H18 Twin F 6H18 Twin F 6J4 Triode-Hepto 6J6 SI6WA Medium-Mu 6J6 SI6WA Medium-Mu 6J6 SI6WA Medium-Mu 6J7 GJ7 Sharp-Cut 6J7 Sharp-Cut 6J8 Triode-Hepto 6J9 High-Mu Triode-Hepto 6J9 High-Mu Triode-Hepto				Volts	Amperes	···
6H66T Twin 6H66 Power 6H66 Power 6H66 Power 6H65 Beam Po 6H65 Beam Po 6H68 Medium-M 6H15 Beam Po 6H18 Diode—Sharp 6H18 Diode—Sharp 6H18 Sharp-Cuto 6H85 Beam Po 6H85 Beam Po 6H86 Semiremote-C 6H86 Semiremote-C 6H87 Electron 6H87 Electron 6H87 Electron 6H88 High-Mu 6H75 Beam 6H76 Sharp-Cuto 6J6 6J6WA Medium-Mu 6J76 Sharp-Cut 6J76 Sharp-Cut 6J76 Sharp-Cut 6J86 Triode-Hepto 6J9 High-Mu Ti	Mu Triple Triode	6B	9MB	6.3	0.45	Unit No. 1 as Class A Amplifier Units No. 2 and No. 3 as Class A Amplifier
6H6GT Twin 6H6G 6H86/ 6H86/ 6H86/ 6H07 Medium-A 6H65 Beam Po 6H68 Medium-M 6H15 Beam Po 6H16 Sharp-Cuto 6H75 Beam Po 6H76 Sharp-Cuto 6J6 6J6WA Medium-Mu 6J6WB Medium-Mu 6J76 Sharp-Cut 6J76 Sharp-Cut 6J76 Sharp-Cut 6J9 High-Mu Tri 6J9 High-Mu Tri 6J9 High-Mu Tri 6J9 High-Mu Tri	ower Pentode	5C	7CV	6.3	0.38	Class A Amplifier
6HB6 6HB6/ 6HB6/ 6HB6/ 6HB6/ 6HB6/ 6HB7  Medium-Machine-Sharp-Cut 6HG5  Beam Po 6HG8  Medium-Machine-Sharp-Cut 6HJ5  Beam Po 6HJ8  Diode—Sharp 6HK5  High-Machine-GHB6/ 6HB6  Semiremote-C 6HUB/ ELL80  GHV5  Beam 6HZ5/ 6JD5  Beam 6HZ5/ 6JB5  Medium-Machine-GHB6/ 6JGWA 6JGWA 6JGWA 6JGWA 6JGWA 6JGWA 6JGWA 6JGWA 6JGWA 6JGG 6JGG 6JGG 6JGG 6JGG 6JGG 6JGG 6JG		400	70			Voltage Doubler
6HB6/ 6HD7  Medium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modium-Modi	Twin Diode	29B 13D	7Q	6.3	0.3	Half-Wave Rectifier
6HA6 6HD7 Medium-M 6HG5 Beam Po 6HG8 Medium-M 6HG8 Medium-M 6HJ5 Beam Po 6HJ8 Diode—Sharp 6HK5 High-M 6HK5 Beam Po 6HK5 Beam Po 6HK6 Semiremote-C 6HU6/ EM87 Electron 6HU8/ 6HU8/ 6HU8/ 6HU8/ 6HU8/ 6HZ8 High-Mu 6HZ8 High-Mu 6JAWA Tri 6J6 6J6WA Medium-Mu 6J6 6J6WA Medium-Mu 6J7 6J7G Sharp-Cut 6J7G Sharp-Cut 6J9 High-Mu Tri 6J9 High-Mu 7						
6HG5 Beam Po 6HG8 Medium-Mu 6HJ5 Beam Po 6HJ8 Diode—Sharp-Cuto 6HJ8 Diode—Sharp 6HK5 High-M 6HK5 Beam Po 6HR6 Semiremote-C 6HU6/ Electron 6HU8/ Electron 6HU8/ Beam 6HV5 Beam 6HV5 Beam 6HV5 Beam 6HV5 Beam 6HV5 Beam 6HV5 Medium-Mu 6J6 6J6 6J6 6J6 6J6 6J6 6J6 6J6 6J6 6J	wer Pentode	66	WNE	6.3	0.76	Vertical Deflection Amplifier
6HG8 Sharp-Cute 6HJ5 Beam Pov 6HJ8 Diode—Sharp 6HK5 High-M 6HK5 Beam Po 6HK5 Beam Po 6HK6 Sharp-Cute 6HK6 Semiremote-C 6HU6/ Electron 6HU8/ Electron 6HU8/ Beam 6HZ5/ Beam 6HZ5/ Beam 6HZ5/ Beam 6HZ8 Sharp-Cute 6J4* 6J4* 6J55T Medium-Mu 6J6W8* 6J7 6J7G Sharp-Cute 6J7G Sharp-Cute 6J7G Sharp-Cute 6J7G Sharp-Cute 6J7G Sharp-Cute 6J9 High-Mu Triode-Hepte	ium-Mu Triode— p-Cutoff Pentode	68	<b>9Q</b> A	6.3	0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
6HJ5 Beam Por 6HJ8 Diode—Sharp 6HK5 High-M 6HK5 High-M 6HK6 Sharp-Cute 6HR6 Semiremote-C 6HR6 Semiremote-C 6HR6 Twin F 6HU8/ Electron 6HU8/ Beam 6HV5 Beam 6HV5 Beam 6HV5 Beam 6HV5 Beam 6HV5 Beam 6HV8 Sharp-Cute 6JA	m Power Tube	5D	7BZ	6.3	0.45	Class A Amplifier
6HJ8 Diode—Sharp 6HK5 High-M 6HK5 High-M 6HM6 Sharp-Cutt 6HR5 Beam Po 6HR6 Semiremote-C 6HU8/ Electron 6HU8/ Beam 6HV5 Beam 6HV5 Beam 6HZ8 High-Mu 6JA+ 6JA+ 6JA+ 6JA+ 6JA+ 6JB- 6JG 6JGWA+ 6JGWA+ 6JGWB+ 6J7	um-Mu Triode— -Cutoff Pentode	<b>6</b> B	9MP	6.3	0.34	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
6HK5 High-M 6HM6 Sharp-Cutt 6HR5 Beam Po 6HR6 Semiremote-C 6HU8/ Electron 6HU8/ Beam 6HV5 Beam 6HV5 Beam 6HZ8 High-Mu 6JA* 6JA* 6JA* 6JG 6JG 6JG 6JG 6JG 6JG 6JG 6JG 6JG 6J7	n Power Tube	15C	12FL	6.3	2. <b>2</b> 5	Horizontal Deflection Amplifier
GHMG Sharp-Cutt GHR5 Beam Po GHR6 Semiremote-C GHU6/ Electron GHU8/ Electron GHV5 Beam GHZ5/ GJD5 Beam GHZ8 High-Mu Sharp-Cutof GJ4+ GJ5- Medium-Mu GJ6-WA+ GJ6 GJ6- GJ6- GJ6- GJ7- GJ7- GJ7- GJ7- GJ7- GJ7- GJ7- GJ7	harp-Cutoff Pentode	6B	9CY	6.3	0.45	Pentode Unit as Class A Amplifier
6HR5 Beam Po 6HR6 Semiremote-C 6HUB/ Electron 6HUB/ Electron 6HUB/ Beam 6HV5 Beam 6HZ5/ 6JD5 High-Mu 6hZ8 High-Mu 6hZ8 Tri 6J4* 6J4* Tri 6J6 GJ6 6J6WA* Medium-Mu 6J6WB* GJ7 6J7G Sharp-Cut 6J7G Sharp-Cut 6J8G Triode-Hepte	gh-Mu Triode	5C	7GM	6.3	0.19	Class A Amplifier
GHR6 Semiremote-C GHUG/ EM87 Electron GHUB/ ELL80 Twin F GHZ5/ GHZ5/ GHZ8 High-Mu Sharp-Cutof GJ4+ GJ4WA+ GJ5T Medium-Mu GJ6WB+ GJ7 GJ7G Sharp-Cut GJ7GT Sharp-Cut GJ8G Triode-Hepto	-Cutoff Pentode	6B	9PM	6.3	0.3	Class A Amplifier
6HU6/ EM87  6HU8/ ELL80  6HV5  6HV5  6HZ5/ 6JD5  6HZ8  High-Mu Sharp-Cutori 6J4  6J5  6J5  6J6 6J6 6J6 6J6 6J6 6J6 6J7 6J7 6J7 6J	m Power Tube	5D	7BZ	6.3	0.45	Vertical-Deflection Amplifier
EM87  GHUB/ ELL80  GHV5  Beam  GHZ5/ GJD5  Beam  GHZ8  High-Mu Sharp-Cutor  GJ4  GJ4  GJ5  GJ5  GJ6  GJ6  GJ6  GJ6  GJ6  GJ6	ote-Cutoff Pentode	5C	7BK	6.3	0.45	Class A Amplifier
ELL80 6HV5 Beam 6HZ5/ 6JD5  6HZ8  Sharp-Cutof 6J4+ 6J4WA+ Tri 6J5 Medium- 6J6 6J6 6J6WA+ 6J6WB+ 6J7	ctron-Ray Tube	6N	9GA	6.3	0.3	Tuning Indicator
6HZ5/ 6JD5  6HZ8	win Pentode	66	9NJ	6.3	0.55	Power Amplifier
61D5 Beam 6HZ8 High-Mu 6144 Sharp-Cutor 6144 Tri 615 Medium- 616 Sh6WA 616WB 617G Sharp-Cut 617G Sharp-Cut 617G Sharp-Cut 618G Triode-Hepto	Beam Triode	15E	12GY	6.3	1.8	Class A Amplifier
614	leam Triode	15F	12GY	6.3	2.4	High Voltage Pulse Regulator
6J\$\text{6J5} \text{Medium-Mu} \\ 6J5 \\ 6J5\text{GJ6} \\ 6J6\text{Medium-Mu} \\ 6J6\text{Medium-Mu} \\ 6J7\text{G} \\ 6J7\text{G} \\ 6J7\text{G} \\ 6J8\text{G} \\ Triode-Hepto \\ 6J9 \text{High-Mu Ti}	-Mu Triode— Cutoff Pentode	10G	9DX	6.3	1.125	Triode Unit as Class A Amplifier  Pentode Unit as Class A Amplifier
6J5GT Medium- 6J6 6J6WA Medium-Mu 6J7G Sharp-Cut 6J7GT Sharp-Cut 6J8G Triode-Hepto	Triode	5C	7BQ	6.3	0.4	UHF Amplifier
616WA • Medium-Mu 616WB • 617 617G Sharp-Cut 617GT Triode-Hepte 619 High-Mu Ti	lium-Mu Triode	2A 13D	6Q	6.3	0.3	Class A Amplifier
616WB •  617 6176 6176 6176T  618G Triode-Hepto 619 High-Mu To				6.3	0.45	Each Unit as Class A Amplifier
6J7G Sharp-Cut 6J7GT Friode-Hepto 6J9 High-Mu Ti	n-Mu Twin Triede	5C	7BF	6.3	0.45	Push-Pull Class C Amplifier
6J9 High-Mu To	p-Cutoff Pentode	3 23 14A	7R 7R 7R	6.3	0.3	Pentode Class A RF Amplifier
	Heptode Converter	23	8H	6.3	0.3	Triode Unit as Oscillator
	Mu Triple Triode	6B	10G	6.3	0.45	Heptode Unit as Mixer Each Unit as Class A Amplifier
[[[]] Bandada Baa						Pentode Units as
	-Beam Power Tube	8B	12BT	6.3	0.95	Class A Amplifier Each Unit as
6J11 Sharp-Cutoff	utoff Twin Pentode	8A	12BW	6.3	0.8	Class A Amplifier

	Grid Bias or		Screen Grid	Plate	AC Plate	Trans.	Amnlif	Po	wer	- RCA
Piate	Cathode Resistor	Screen Grid	Cur- rent	Cur- rent	Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Load	Out- put	Туре
Voits		Volts	mA	mA	Ohms	Micromhos		Ohms	Watts	
125 125	220Ω —1V	=	=	4.5 4.5	14000 14000	4500 4500	63 63	=	_	6GY8
250 250	270Ω 270Ω (bypassed)	250 250	2.7 2.7	16 16	150000	8400		15000 15000	1.8 1.1	6GZ5
Max. Min.	. AC Supply Volt Total Effect. Pi	s per Plati ate-Supply	e (RMS), Imped.	117 per Plat	e: half-wave	Max.   2, 30 ohms; 1	DC Output full wave,	mA, 8. min. 15 ohms		6H6
Max.	AC Plate Volts DC Output mA,	(RMS), 150	)		Min. Total	Effective Pla ts, 15 ohms	te-Supply	Impedance:	up s	- 6H6GT
250 250	33Ω 100Ω	125 250	4.2 6.2	40 40	28000 24000	24000 20000	33		=	6HB6 6HB6/ 6HA6
100	<u>0v</u>			14	4880	8200	40			- 6HD7
125	—1V	ذ12	3.5	12		7000				יטווט
250 180	—12.5V —8.5V	250 180	4.5 3	45 <b>2</b> 9	52000 58000	4100 3700		5000 5500	4.5 2	6H65
100	<u> </u>			14		5500	17			- 6HG8
170	1.2V	150	3.3	10	350000	12000				01100
135	<u>22</u>	135	5.5	80	5000	10000	4.2			6HJ5
125	56Ω	125	3.6	11.5	200000	9300				6H18
135	<u>—1V</u>			12.5	5000	15000	75			6HK5
125 260	56Ω 19V	125 270	2.3	13	156000	3600				6HM6
50	0V	250	25	30 105						6HR5
200	68Ω	115	4.3	13.2	500000	8500				6HR6
Tr	iode Plate and F Triode Grid-Su	luorescent pply Volts	-Target ' = —10	Volts = to +15	250	Shado	w Section	= 0 to 0.83	3 inch	6HU6/ EM87
250	$160\Omega$	250	4.5	24	80000	6000		10000	3	6HU8/ Ell80
		Fo	r other	characte	ristics, ref	er to Type 6	H\$5			6HV5
	Max. Pulse Pla Max. Peak Plat	ite Volts, ! te mA, 325	5500		Max. Pe	Max. Plate D ak Heater-Ca	issipation, athode Vol	35 watts ts, <b>∔200</b> ,	-450	6HZ5/ 6JD5
200				3.5		4000	70			6HZ8
250	100	170	6	29	140000	12600				
150	$100\Omega$			15	4500	12000	55			6J4 + 6J4WA +
90 250	— 8V		_	10 9	6700 7700	3000 2600	20 20			615 6156T
100	50Ω (For	both units	)	8.5	7100	5300	38			616
150	—10V			30	Grid Cu Driving	rrent, 16 mA Power, 0.35	watt	<del></del>	3.5	6J6WA+
100 250	— 3V — 3V	100 100	0.5 0.5	2.0 2.0	1 M 1 M	1185 1225	=		_	<b>617</b> 617 <b>G</b> 617 <b>G</b> T
100 <b>250</b>	Triode-Grid 50000	ohms		4 5						6J8G
250 125	— 3V —1V	100	2.8	1.4	1.5 M			d., 290 mic	romhos	
		250		6 	11000	5200	57			6J <b>9</b>
250	<u></u>	<b>2</b> 50	2.5	35 	100000	6500		5000	4.2	6J10
125	56Ω	1 <b>2</b> 5	3.8	11	200000	13000				6J11

RCA Type	Name	Out- line	Terminal Dia- gram	Heater or Filament (F)		Use Values to right give operat- ing conditions and character- istics for indicated typical use
			-	Volts	Amperes	_
6JA5	Beam Power Tube	15D	12EY	6.3	1.0	Vertical Deflection Amplifier
6JB6	Beam Power Tube	18A	9QL	6.3	1.2	Horizontal Deflection Amplifier
6JC6	Sharp-Cutoff Pentode	6B	9PM	6.3	0.3	Class A Amplifier
6JE6	Beam Power Tube	32 D	9QL	6.3	2.5	Horizontal Deflection Amplifier
6JE6A	Beam Power Tube	32B	9QL	6.3	2.5	Horizontal Deflection Amplifier
6JE8	High-Mu Triode Sharp-Cutoff Pentode	6E	9DX	6.3	0.78	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifie
6JG6	Beam Power Tube	17B	9 <b>Q</b> U	6.3	1.6	Horizontal Deflection Amplifier
6JK6	Sharp-Cutoff Pentode	5C	7CM	6.3	0.35	Class A Amplifier
6JK8	Dual Triode	68	LAG	6.3	0.4	Unit No. 1 as Oscillator Unit No. 2 as RF Amplifier
6JM6	Beam Power Tube	39A	12FJ	6.3	1.2	Horizontal Deflection Amplifier
6JS6	Beam Power Tube	168	12FY	6.3	2.25	Horizontal Deflection Amplifier
6JS6A	Beam Power Tube	168	12FY	6.3	2.25	Horizontal Deflection Amplifier
6JT6	Beam Power Tube	170	9QU	6.3	1.2	Horizontal Deflection Amplifier
6JU8	Quadruple Diode	- 6E	SPQ	6.3	0.6	Phase Detector
6JZ6	Beam Power Tube	39A	12GD	6.3	1.5	Horizontal Deflection Amplifier
6K5GT	High-Mu Triode	14A	50	6.3	0.3	Class A Amplifier
<b>6K7</b> 6K7G 6K7GT	Remote-Cutoff Pentode	3 23 14A	7R 7R 7R	6.3	0.3	Class A Amplifier
6K8G	Triade-Hexade Converter	3 23	8 K 8 K	6.3	0.3	Triode Unit as Oscillator  Hexode Unit as Mixer
6K8GT			8N			
6K11 6K11/ 6Q11	Twin High-Mu Triode Medium-Mu Triode	8A	12BY	6.3	0.6	Twin Unit as Class A Amplifier Class A Amplifier
6KL8	Diode—Sharp-Cutoff Pentode	6E	9LQ	6.3	0.3	Pentode Unit as Class A Amplifier
6KN8/ 6RHH8	Medium-Mu Twin Triode	6B	LAG	6.3	0.4	Each Triode as Class A Amplifier
6KU8	Twin Diode— Shap-Cutoff Pentode	10A	9LT	6.3	0.725	Pentode Unit as Class A Amplifier
6KV6	Beam Power Tube	31D	9QU	6.3	1.6	High-Voltage-Pulse Shunt Regulator
6KY6	Sharp-Cutoff Pentode	6E	9GK	6.3	0.52	Class A Amplifier
6KY8	High-Mu Triode Beam Power Tube	11C	907	6.3	1.1	Triode Unit as Oscillator
	DEAM LAMEI IANG					Beam Power Unit as Amplifier
6L5G	Medium-Mu Triode	22	6Q	6.3	0.15	Class A Amplifier
el ec						Single-Tube Class A Amplifier
6L6G 6L6GB	Beam Power Tube	27B 1 <b>9</b> D	7AC 7AC	6.3	0.9	Push-Pull Class A Amplifier
						Push-Pull Class AB1 Amplifier
6L7	Pentagrid Mixer	3 23	7T	6.3	0.3	Mixer Service

	Grid Bias		Screen	Dic*-	An Blak	T	Amalie :	Power		- 804
Plate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Plate Cur- rent	AC Plate Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Load	Out- put	RCA Type
Volts		Valts	mA	mA	Ohms	Micromhos		Ohms	Watts	
135 45	—10V 0V	125 125	4.2 20	95 210	42000	10300 stantaneous	Plate Knee	characteri	istic	6JA5
Max.	DC Plate Volts	. 770		210	M	ax. Peak Ne	gPulse Gri	d-No. 1 Vo		CIDO
Max. Max.	Peak Cathode i Plate Dissipati	nA, 550 on, 17.5 w	atts			ax. Grid-No. ax. Peak Po			ts. 6500	6JB6
125	56Ω	125	3.2	13	0.18	15000				6JC6
						to Type 6JE				6JE6
175	25	125	2.8	130	5800	9600	3			6JE6A
200 250	2V 82Ω	170	4	4.5 22	140000	4200 12000	70 			. 6JE8
60	OV	170	12	48		tantaneous	Plate Knee	characteri	stic	. 0,20
		For	other ch	aracteris	tics, refer	to Type 6JG	6A			6JG6
<b>12</b> 5	68Ω	125	3.9	11.5	150000	18000				6JK6
100 135	—1V —1.2V	_		5.3 10	8000 5400	6800 13000	55 70			6JK8
			For other	r rating	s, refer to					6J <b>M6</b>
175	— <b>2</b> 5V	125	4.5	125	5600	11300	3			6186
175	—25	125	4.5	125	5600	11300	3			6JS6A
	_			r ratings	, refer to	Type 6JB6				6J <b>T6</b>
Max. Max	Peak Inverse P Peak Plate mA,	late Volts	, 300		M: M	ax. DC Outpu ax. Peak He	it mA, 9	Volte +	300	6JU8
130	20V	130	1.8	46	9900	9000	ater-Qatrioue	voits, _	300	C176
50	0V	130	29	450		tantaneous I	Plate Knee	characteri	stic	6JZ6
250	— 3V			1.1	50000	1400	70			6K5GT
250	3V	1 <b>2</b> 5	2.6	10.5	600000	1650				<b>6K7</b> 6K7G 6K7GT
100	Grid Res.,	50000 ohn	18	3.8	Triod	le-Grid & He	xode-Grid Cı	urrent, 0.1	5 mA	6K8
100 250	— 3V	100 100	6.2 6.0	2.3 2.5	400000 600000	Conversion Conversion	on Transcond	d., 325 mid d., 350 mid	cromhos cromhos	6K8G 6K8GT
250	2V			1.2	62500	1600	100			6K11
250	— 8.5V			10.5	7700	2200	17			6K11/ 6Q11
100	0	100	2.2	5.5	555000	4300	Grid-No. 1 rent	Volts for μ of 10 μA,	olate cur- 4.2	6KF8
110	<b>1</b> V	<del></del>		16	2800	16000	45			6KN8/ 6RHH8
		Fo	r other o	haracter	istics, refe	er to Type I	DKU8			6KU8
		Fo	r other o	haracter	istics, refe	er to Type 6	KV6A			6KV6
200	—18 <b>V</b>	135	5.2	30	40000	30000				6KY6
max. Max.	DC Plate Voits, DC Cathode mA	, 22			Max. Plate	Dissipation,	1.5 watts			01/1/0
Max. Max.	DC Plate Volts, DC Cathode mA	300			Max. Plate	Positive-Pul: Dissipation,	se Plate Vol 12 watts	ts, 2200 (	Abs.)	6KY8
250	— 9V			8.0	9000	1900	17			6L5G
250 2 <b>50</b>	—14V 168Ω	250 250	5.0 5.4	72.0 75.0	=		_	2500 2500	6.5 6.5	
270 27 <b>0</b>	—17.5V	270	11.0□	134.0 🗆				5000	17.5t	6L6G
360	124Ω□ —22.5V	270 270	5.0□	134.0 D				5000 6600	18.5† 26.5†	6L6GE
360	248Ω□	270	5.0 🗆	88.0 🗆				9000	24.5†	
	— 6V	150			Uscil	lator-Grid (N No. 3 Peak S	10. 3) Bras	—15 volts		6L7

[†] For two tubes at stated plate-to-plate load.

RCA Type	Name	Out- line	Terminal Dia- gram	Heater or Filament (F)		Values to right give operat- ing conditions and character- istics for indicated typical use
			_	Volts	Amperes	
6LB8	Medium-Mu Triode	10A	SDX	6.3	0.725	Triode Unit as Class A Amplifier
	Sharp-Cutoff Pentode					Pentode Unit as Class A Amplifier
6LH6A	Beam Triode	21D	8ML	6.3	0.2	Shunt Voltage Regulator
6LJ6	Beam Triode	21D	BMQ	6.3	0.2	Shunt Voltage Regulator
6LQ6/ 6JE6B	Beam Power Tube	32C	9QL	6.3	2.5	Horizontal Deflection Amplifier
6LZ6	Beam Power Tube	32C	9QL	6.3	2.3	Horizontal Deflection Amplifier
<b>★6MA6</b>	Beam Triode	21D	8NP	6.3	0.2	Shunt Voltage Regulator
6MK8	Sharp-Cutoff Pentode	6E	9FG	6.3	0.3	Class A Amplifier
6ML8	Medium-Mu Triple Triode	6B	9RQ	6.3	0.675	Class A Amplifier
6N6G	Direct-Coupled Power Triode	25	7AU	6.3	0.8	Class A Amplifier
6N7 6N7GT	Medium-Mu Twin Power Triode	2B 13D	8B 8B	6.3	0.8	Class A Amplifier (as Driver)  Class B Amplifier
6P5GT	Medium-Mu Triode	13D	6Q	6.3	0.3	Amplifier Detector
6P7G	Low-Mu Triode—Remote-Cutoff Pentode	23	76	6.3	0.3	Amplifier and Converter
<b>6Q7</b> 6Q7G 6Q7GT	Twin Diode High-Mu Triode	3 23 14A	7¥ 7V 7¥	6.3	0.3	Triode Unit as Class A Amplifier
6Q11	Twin High-Mu Triode— Medium-Mu Triode	8A	12BY	6.3	0.6	Twin Unit as Class A Amplifier Class A Amplifier
6R7 6R7G 6R7GT	Twin Diode—Medium-Mu Triode	3 23 14A	7¥ 7V 7V	6.3	0.3	Triode Unit as Class A Amplifier
6RP22	Power Pentode	6E	9BV	6.3	0.65	Class A Amplifier
684	Medium-Mu Triode	8E	9AC	6.3 6.3	0.6 0.6	Vertical Deflection Amplifier
6S7 6S7G	Remote-Cutoff Pentode	3 23	7R 7R	6.3	0.15	Class A Amplifier
6S8GT	Triple Diode—High-Mu Triode	14C	8CB	6.3	0.3	Triode Unit as Class A Amplifier
6SA7 6SA7GT	Pentagrid Converter	2A 13D	8R 8AD	6.3	0.3	Converter
6SB7Y	Pentagrid Converter	2A	8R	6.3	0.3	Mixer
6SC7	High-Mu Twin Triode	2A	85	6.3	0.3	Each Unit as Amplifier
<b>6SF5</b> 6SF5GT	High-Mu Triode	2A 13D	6AB 6AB	6.3	0.3	Class A Amplifier
6SF7	Diode—Remote-Cutoff Pentode	2A	7AZ	6.3	0.3	Pentode Unit as Class A Amplifier
6SG7	Semiremote-Cutoff Pentode	2A	8BK	6.3	0.3	Class A Amplifier
6SH7	Sharp-Cutoff Pentode	2A	8BK	6.3	0.3	Class A Amplifier
<b>6SJ7</b> 6SJ7GT	Sharp-Cutoff Pentode	2A 13D	8N 8N	6.3	0.3	Class A Amplifier
6SK7GT	Remote-Cutoff Pentode	2A 13D	8N 8N	6.3	0.3	Class A Amplifier
6SN7GT		13D		6.3	0.6	Each Unit as Class A Amplifier
6SN7 GTA	Medium-Mu Twin Triode	13D	8BD	6.3	0.6	Each Unit as Vertical Amplifier

	Grid Bias		Screen					Pov	rer	
Plate	or Cathode Resistor	Screen Grid	Grid Cur- rest	Plate Cur- rent	AC Plate Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Load	Out- put	RCA Type
Volts		Voits	mA	mA	Ohms	Micromhos		Ohms	Watts	
125	68Ω			13	6000	5000	30			- 41.04
200 50	82Ω 0V	100 100	3.5 18	17 55	5000 In	20000 stantaneous	Plate Kne	e characteri	stic —	6LB8
						fer to Type		ii		6LH6A
	Max. Max. Unregulat	Plate Volt	s, 27000 Supply Vo	its, 600	00	Ma Max.	x. Average Plate Diss	Plate mA, sipation, 40	1.6 Watts	6LJ6
175	35	145	2.4	95	7000	7500	2.8			6LQ6/ 6JE6B
		For	other cha	racteris	tics, refer	to Type 31L	<b>Z</b> 6			6LZ6
	Max. Plate	Volts, 30	000			Max. /	Average Pl	ate mA, 1.5 tion, 40 Wat	ts	6MA6
		For	other cha	racteris	tics, refer	to Type 6MI				6MK8
125	1V			11	6400	6700	43			6ML8
Outpu Triod	t Triode: Plate e: Plate Volts,	Volts, 300 300; Grid	); Plate 1 Volts, 0;	mA, 45; input P	Load, 7000 late mA, 8	ohms			4.0	6N6G
250 300	— 5V — 6V		_	6.0 7.0	11300 11000	3100 3200	35 35	20000 or more	exceeds 0.4	6N7
300	07	Power	Output I			i plate-to-pla		8000	10.0	- 6N7GT
250	13.5			5.0	9500		13.8			6P5GT
		Fo	r other c	haracter	istics, refe	r to Type 6f	7			6P7G
100	— 1V			0.8	58000	1200	70			<b>6Q7</b> 6Q7G
250	— 3V			1.1	58000	1200	70			6Q7GT
250 150	— 2V			1.2 22	62500 7000	1600 2500	100			- 6Q11
130	UV				7000	2300	10		<del></del>	6R7
250	— 9 <b>V</b>			9.5	8500	1900	16		_	6R7G 6R7GT
250	3V	150	8.5	22	55000	8500				6RP22
Max. Max.	DC Plate Volts DC Cathode m/	, 550 30			Max. Max.	Peak Positiv Plate Dissip	e-Pulse Pla ation, 8.5	ate Volts, 22 watts	200	6S4
250	<b>— 3V</b>	100	2.0	8.5	1 M	1750	—			6S7 6S7G
250	— 2V			0.9	91000	1100	100			6S8GT
250	Self- Excited	100	8.5	3.5	1.0			or, 20000 oh cond., 450 m		<b>6SA7</b> 6SA7G
100	— 1 <b>V</b>	100	10.2	3.6	500000	Grid-No Convers	. 1 Resisto	or, 20000 oh cond., 950 m	ms. icromhos	6SB7Y
250	2V			2.0	53000	1325	70			6SC7
250	2V			0.9	66000	1500	100			6SF5GT
100 250	_ 1V _ 1V	100 100	3.4 3.3	12.0 12.4	200000 700000	1975 2050				6SF7
100 250	— 1V — 2.5V	100 150	3.2 3.4	8.2 9.2	250000 1 M	4100 4000				6567
100 250	— 1V — 1V	100 150	2.1 4.1	5.3 10.8	350000 900000	4000 4900				6SH7
100	- 3V - 3V	100 100	0.9	2.9 3.0	700000 1 M	1575 1650				<b>6SJ7</b> 6SJ7G1
100		100	4.0	13.0	120000	2350			•	6SK7
250	— 3 <b>V</b>	100	2.6	9.2	800000	2000				6SK7GT
100 250	— 8V			10.0 9.0	6700 7700	3000 2600	20 20			6SN7GT - 6SN7
Max.	DC Plate Volts Peak Cathode	, 450 m 4 70	Max Max	. Plate i Peak F	Dissipation: Positive Pul	: 5 watts eit se Plate Vol	ner plate; ts. 1500	7.5 watts be	oth plates	GTA

RCA Type	Name	Out- line	Termina Dia- gram	He	eater or ement (F)	Use Values to right give operat- ing conditions and character- istics for indicated typical use
~				Volts	Amperes	
<b>6SQ7</b> 6SQ7GT	. Twin-DiodeHigh-Mu Triode	2A 13D	8Q 8Q	6.3	0.3	Triode Unit as Class A Amplifier
6SR7	Twin Diode-Medium-Mu Triode	2A	80	6.3	0.3	Triode Unit as Class A Amplifier
6887	Remote-Cutaff Pentade	2A	8N	6.3	0.15	Class A Amplifier
6817	Twin Dlode—Medium-Mu Triode	2A	8Q	6.3	0.15	Triode Unit as Amplifier
6SZ7	Twin Diode-High-Mu Triode	2A	80	6.3	0.15	Triode Unit as Class A Amplifier
CTA	Medium-Mu Triode	5D	7DK	6.3	0.225	Oscillator in UHF TV Receivers
6T4	Meatum-Ma Irlane	חכ	/UN	0.3	0.223	Class A Amplifier
6T7G	Twin Diode—High-Mu Triode	22	78	6.3	0.15	Triode Unit as Class A Amplifier
6T8	Triple Diode—High-Mu Triode	6B	9E	6.3 6.3	0.45 0.45	Triode Unit as Class A Amplifier
6T9	High-Mu Triode— Power Pentode	88	12FM	6.3	0.93	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
6U5	Electron-Ray Tube	13H	6R	6.3	0.3	Visual Indicator
6U7G	Remote-Cutoff Pentode	28J	7R	6.3	0.3	Class A Amplifier
6U8	Medium-Mu Triode—Sharp-Cutoff Pentode	6B	9AE	6.3	0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
6U9/ ECF201	Medium-Mu Triode Sharp-Cutoff Pentode	6B	10K	6.3	0.41	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
6V3A	Half Wave Rectifier	7B	9BD	6.3	1.75	Television Damper Service
6V6GT 6V6GTY	Beam Power Tube	13D	7AC	6.3	0.45	Single-Tube Class A Amplifier
6V7G	Twin Diade-Low-Mu Triode	23	7V	6.3	0.3	Push-Pull Class AB ₁ Amplifier
07/4	I WIN DIGUE-LOW-MG ITTOUS			0.3	0.3	Triode Unit as Amplifier
6W4GT	Half-Wave Rectifier	13D	4CG	6.3	1.2	Television Damper Service
6W7G	Sharp-Cutoff Pentode	23	7R	6.3	0.15	Class A Amplifier
6X4W+	Full-Wave Rectifier	5D	5BS	6.3	0.6	With Capacitive-Input Filter With Inductive-Input Filter
6X5	Full-Wave Rectifier	28	65	6.3	0.6	With Capacitive-Input Filter
						With Inductive-Input Filter
6X8	Medium-Mu Triode Sharp-Cutoff Pentode	<b>6</b> B	9AK	6.3	0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
6Y5	Full-Wave Rectifier	22 or 13H	<b>61</b>	6.3	0.8	With Capacitive-Input Filter
6Y7G	High-Mu Twin Power Triode	22	8B	6.3	0.6	Class B Amplifier
6Y9	Dual Pentode	6L	10L	6.3	0.8	Unit No. 1 as Class A Amplifier Unit No. 2 as Class A Amplifier
6Z4	Refer to type 84/624					<u></u>
6Z5	Full-Wave Rectifier	22	6K	12.6 6.3	0.8 0.4	With Capacitive-Input Filter
6Z7G	High-Mu Twin Power Triode	22	8B	6.3	0.3	Class B Amplifier
6Z10	Power Pentode Gated-Beam Discriminator	8C	12BT	6.3	0.95	Class A Amplifier
6ZY5G	Full-Wave Rectifier	22	65	6.3	0.3	With Capacitive-Input Filter
	<del></del>					

	Grid Bias or		Screen Grid	Plate	AC Plate	T	A1:5	Pow	er	_ na.
Plate	Cathode Resistor	Screen Grid	Cur- rent	Cur- rent	Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Load	Out- put	RCA Type
Volts		Volts	mA	mΑ	Ohms	Micromhos		Ohms	Watts	
100 250	— 1V — 2V			0.5 1.1	110000 85000	925 1175	100 100			<b>6SQ7</b> 6SQ7G
250	<b>— 9V</b>			9.5	8500	1900	16			6SR7
250	— 3V	100	2.0	9.0	1 M	1850				6SS7
		For	other ch			to Type 6SI				6ST7
100 250	1V 3V		_	0.8 1.0	54000 53000	1300 1200	70 70			6SZ7
Max. Max.	DC Plate Volts DC Cathode mA	, 200 30			Max. Max.	Grid mA, 8 Plate Dissi	nation 3	5 watts		6T4
80	150Ω			18		7000	13			_ 014
250 300	— 3V 4580Ω			1.2	62000 Resistor,	1050	65	Gain per stag	 e. 40	- 6T7G
100	— 1V			0.8	54000	1300	70	Stag	e, 40	6T8
250	<u> </u>			1.0	58000	1200	70			010
250 250	2V 8V	250	2.5	1.5 35	45000 100000	2100 6500	_	5000	4.2	6T9
Plate Grid	& Target Suppl Bias, —22 volts	y, 250 voli ; Shadow	ts. Triode Angle, 0°.	Plate R Bias, 0	esistor, 1.0 volts; Ang	MΩ Target le, 90°; Plat	Current, e Curren	4.0 mA t, 0.24 mA		6U5
250	3V	100	2.0	8.2	800000	1600				6U7G
125	1V			13.5		7500	40			 6U8
125	— 1V	110	3.5	9.5	200000	5000				
100	—2V —1.4V	110	<del></del>	14		5000	17	<del></del>		6U9/
160	••••	110	3	13		12000				ECF2 <b>0</b> 1
	. Peak Inverse I Max. Peak	Plate Volts	6, 6000 (A		Max.			te mA, 135 Volts: {-675 +300	0 (Abs.)	6V3A
	. Peak Inverse I	Plate Volts Plate mA,	800 (Al	ds.)	50000	Max. Ave Peak Heater 4100		Volts: $\begin{cases} -675 \\ +300 \end{cases}$		6V3A
Max 250 315 250	Max. Peak  —12.5V —13V —15V	Plate Volts Plate mA, 250 225 250	800 (Al 800 4.5 2.2	45.0 34.0 70.0		Max. Ave Peak Heater		Volts: {-675 +300 5000 8500	4.5 5.5 10.0†	
Max 250 315	Max. Peak	Plate Volts Plate mA, 250 225 250 285	800 (Al 800 4.5 2.2 5.0   4.0	45.0 34.0 70.0	50000 <b>80000</b>	Max. Ave Peak Heater 4100 3750		Volts: {-675 +300 5000 8500	4.5 5.5	6V3A 6V6GT 6V6GTY
Max 250 315 250 285	Peak Inverse I Max. Peak  -12.5V -13V -15V -19V	Plate Volts Plate mA, 250 225 250 285 For e Plate Vo	4.5 2.2 5.0 4.0 other chapter 4.0 ther chapter 3850	45.0 34.0 70.0	50000 80000  stics, refer	Max. Ave Peak Heater 4100 3750 to Type 85	r-Cathode	Voits: {-675 +300 5000 8500 10000 8000	4.5 5.5 10.0† 14.0†	6V3A 6V6GT
250 315 250 285	Max. Peak	Plate Volts Plate mA, 250 225 250 285 For e Plate Vo	4.5 2.2 5.0 d 4.0 d other characters of the char	45.0 34.0 70.0 aracteris	50000 80000 —— stics, refer Max. Pe	Max. Ave Peak Heater 4100 3750 ————————————————————————————————————	r-Cathode	Volts: {-675 +300 5000 8500 10000 8000	4.5 5.5 10.0† 14.0†	6V3A 6V6GT 6V6GTY 6V7G <b>6W4GT</b>
Max 250 315 250 285	Peak Inverse I Max. Peak  -12.5V -13V -15V -19V	Plate Volts Plate mA, 250 225 250 285  For e Plate Vo mA, 750 te mA, 125	6, 6000 (Al 800 4.5 2.2 5.0   4.0   other cha oits, 3850 6	45.0 34.0 70.0 aracteris	50000 80000 ——stics, refer Max, Pe	Max. Ave Peak Heater 4100 3750 to Type 85 Max. Plate D ak Heater-C.	issipation	Voits: {-675 +300 5000 8500 10000 8000	4.5 5.5 10.0† 14.0†	6V3A 6V6GT 6V6GTY 6V7G <b>6W4GT</b> 6W7G
Max 250 315 250 285 M M Max. /	Peak Inverse I Max. Peak  12.5V  13V  15V  19V  Ac Peak Inverse I Ac Peak Plate  ax. Average Pla  3V  AC Volts per Pla	Plate Volts Plate mA, 250 225 250 285 For e Plate VomA, 750 te mA, 125 100 For	4.5 2.2 5.0 d 4.0 d other cha	45.0 34.0 70.0 aracteris 2.0 racteris	50000 80000 stics, refer Max. Pe 1.5 M tics, refer	Max. Ave Peak Heater 4100 3750 to Type 85 Max. Plate D ak Heater-C. 1225 to Type 6X4 mA, 70	issipation athode Vo	Voits: {-675 +300 5000 8500 10000 8000 1, 3.5 watts oits, -2300, +	4.5 5.5 10.0† 14.0†	6V3A 6V6GT 6V6GTY 6V7G <b>6W4GT</b>
Max. J Max. J Max. J Max. J	Peak Inverse I Max. Peak	Plate Volts Plate mA, 250 225 250 285 For e Plate Vc mA, 750 tte mA, 12: 100 For ite (RMS), its, 1250 tte (RMS),	8, 6000 (Al 800 4.5 2.2 5.0 d 4.0 d other cha bits, 3850 5 0.5 other cha	45.0 34.0 70.0 70.0 aracteris  Max.   Max.   Max.   Max.	stics, refer  Max. Pe  1.5 M  tics, refer  DC Output Peak Plate	Max. Ave Peak Heater 4100 3750 to Type 85 Max. Plate D ak Heater-C. 1225 to Type 6X4 MA, 70 MA, 245 MA, 70 MA, 70 MA, 70 MA, 70	issipation athode Vo	Voits: {-675 +300 5000 8500 10000 8000 1, 3.5 watts oits, -2300, +	4.5 5.5 10.0† 14.0† -300 	6V3A 6V6GT 6V6GTY 6V7G <b>6W4GT</b> 6W7G
Max. 1 Ma	Peak Inverse I Max. Peak	Plate Volts Plate mA, 250 225 250 285 For e Plate Vc mA, 750 tte mA, 12: 100 For ite (RMS), its, 1250 tte (RMS),	8, 6000 (Al 800 4.5 2.2 5.0 degree 4.0 degree 618, 3850 5 0.5 other cha 325	45.0 34.0 70.0 70.0 aracteris  Max.   Max.   Max.   Max.   Max.	stics, refer  Max. Pe  1.5 M  tics, refer  O Output  Peak Plate  DC Output  Peak Plate	Max. Ave Peak Heater 4100 3750 to Type 85 fax. Plate D ak Heater-C. 1225 to Type 6X4 mA, 70 mA, 245 mA, 70 mA, 245	issipation athode Vi	Voits: {-675 +300 5000 8500 10000 8000 1, 3.5 watts olts, -2300, +	4.5 5.5 10.0† 14.0† -300 	6V3A 6V6GT 6V6GTY 6V7G 6W4GT 6W7G 6W4W •
Max. J Max. J Max. J Max. J	Peak Inverse I Max. Peak	Plate Volts Plate mA, 250 225 250 285 For e Plate Vc mA, 750 te mA, 750 100 For site (RMS), its, 1250 te (RMS), its, 1250	8, 6000 (Al 800 4.5 2.2 5.0 conter characteristics, 3850 5 0.5 other characteristics, 3850 6 0.5	45.0 34.0 70.0□ 70.0□ aracteris 2.0 racteris Max. Max. Max. Max.	50000 80000 Stics, refer Max. Pe 1.5 M tics, refer DC Output Peak Plate DC Output Peak Plate	Max. Ave Peak Heater 4100 3750 to Type 85 fax. Plate D ak Heater-C. 1225 to Type 6X4 mA, 70 mA, 245 mA, 70 mA, 245 6500	issipation athode Vo	Voits: {-675 +300 5000 8500 10000 8000 1, 3.5 watts oits, -2300, +	4.5 5.5 10.0† 14.0† -300 	6V3A 6V6GT 6V6GTY 6V7G 6W4GT 6W7G 6W4W •
Max. 250 315 250 285 M M 250 250 Max. 4 Max. 4 Max. 4	. Peak Inverse I Max. Peak	Plate Volts Plate mA, 250 225 250 285 For e Plate Ve mA, 750 te mA, 12: 100 For site (RMS), tits, 1250 tits (RMS),	8, 6000 (Al 800 4.5 2.2 5.0   100 other chailts, 3850 50.5 other chailts, 325 400   100 100 100 100 100 100 100 100	45.0 34.0 70.0 □ 70.0 □ aracteris 2.0 racteris Max. Max. Max. Max.	50000 80000 stics, refer Max, Pe 1.5 M tics, refer DC Output Peak Plate 6000 300000	Max. Ave Peak Heater 4100 3750  to Type 85  Max. Plate D ak Heater-C. 1225  to Type 6X4  MA, 70  MA, 245  MA, 70  MA, 245  MA, 245  MA, 245  6500  5500	issipation athode Vi	Voits: {-675 +300 5000 8500 10000 8000 1, 3.5 watts oits, -2300, +	4.5 5.5 10.0† 14.0† -300 	6V3A 6V6GT 6V6GTY 6V7G 6W4GT 6W7G 6X4W 6X5
Max. 250 315 250 285 M M 250 250 Max. 4 Max. 4 Max. 4	. Peak Inverse I Max. Peak	Plate Volts Plate mA, 250 225 250 For e Plate V mA, 750 tet (RMS), its, 1250 tet (RMS), its, 1250  125  Max. I Max. I	8, 6000 (Al 800  4.5 2.2 5.0□ other chalits, 3850  5.0  0.5  other cha 325  400  2.2  C Voits p OC Output	45.0 34.0 70.0	50000 80000 Stics, refer Max. Pe 1.5 M tics, refer DC Output Peak Plate DC Output Peak Plate 6000 300000 e (RMS), 35	Max. Ave Peak Heater 4100 3750 —— to Type 85 Max. Plate D ak Heater-C. 1225 to Type 6X4 mA, 70 mA, 245 mA, 70 mA, 245 6500 5500 —	issipation athode Vi	Voits: {-675 +300 5000 8500 10000 8000 1, 3.5 watts oits, -2300, +	4.5 5.5 10.0† 14.0† -300 	6V3A 6V6GT 6V6GTY 6V7G 6W4GT 6W7G 6X4W 6X5 6X8 6Y5
Max. 250 315 250 285 M M 250 285 Max. 7 Max. 7 Max. 7 Max. 7 Max. 7 25	. Peak Inverse I Max. Peak	Plate Volts Plate mA, 250 225 250 285 For e Plate VomA, 750 tet (RMS), lts, 1250 tet (RMS), lts, 1250  Max. I Max. I For	8, 6000 (Al 800  4.5 2.2 5.0□ other chalits, 3850  5.0 0.5 other cha 325  400  2.2 AC Volts p C Output other cha	45.0 34.0 70.0	50000 80000 stics, refer Max, Pe 1.5 M tics, refer DC Output Peak Plate 6000 300000	Max. Ave Peak Heater 4100 3750 —— to Type 85 Max. Plate D ak Heater-C. 1225 to Type 6X4 mA, 70 mA, 245 mA, 70 mA, 245 6500 5500 —	issipation athode Vi	Voits: {-675 +300 5000 8500 10000 8000 1, 3.5 watts oits, -2300, +	4.5 5.5 10.0† 14.0† -300 	6V3A  6V6GT 6V6GTY 6V7G 6W4GT 6W7G 6X4W  6X5 6X8 6Y5 6Y7G
Max. 1 Max. 1 Max. 1 Max. 225	Max. Peak  —12.5V —13V —15V —19V  Ac Peak Inverse in the peak inverse play. Peak Plate ax. Average Play  Ac Volts per Play  Ac	Plate Volts Plate mA, 250 225 250 285 For e Plate Vc mA, 750 te mA, 120 100 For ite (RMS), its, 1250 te (RMS), its, 1250 Tec (RMS)	5, 6000 (Al 800 4.5 2.2 5.0   4.0   other characteristics, 3850 5 0.5 other characteristics, 3850 6.5 2.2 C Volts p. C Output other characteristics	45.0 34.0 70.0□ 70.0□ aracteris  Max.   Max.   Max.   Max.   22 9 eer Plate mA, 50 racteris	50000 80000 Stics, refer Max. Pe 1.5 M tics, refer DC Output Peak Plate DC Output Peak Plate 6000 300000 e (RMS), 35	Max. Ave Peak Heater 4100 3750  to Type 85 Max. Plate D ak Heater-C. 1225 to Type 6X4 mA, 70 mA, 245 mA, 70 mA, 245 6500 5500 to Type 79	issipation athode Vo	Voits: {-675 +300 5000 8500 10000 8000 1, 3.5 watts oits, -2300, +	4.5 5.5 10.0† 14.0† -300 	6V3A 6V6GTY 6V7G 6W4GT 6W7G 6X4W 6X5 6X8 6Y5 6Y7G 6Y9
Max. 1 Max. 1 Max. 1 Max. 225	. Peak Inverse I Max. Peak	Plate Volts Plate mA, 250 225 250 E Plate vc mA, 750 te mA, 12: 100 For site (RMS), its, 1250 tts, 1250 125  Max. I Max. I For 170 150	8, 6000 (Al 800  4.5 2.2 5.0   4.0   other challes, 3850  5.0 5.0 0.5 other challes 325 400 2.2 AC Volts part of the challes 6.5 3.1	45.0 34.0 34.0 70.0 70.0 70.0 70.0 70.0 70.0 70.0 7	50000 80000  Stics, refer Max. Pe  1.5 M tics, refer DC Output Peak Plate 6000 300000 e (RMS), 35 tics, refer	Max. Ave Peak Heater 4100 3750  to Type 85  Max. Plate D ak Heater-C. 1225  to Type 6X4  MA, 70  MA, 245  MA, 245  MA, 245  6500  5500  to Type 79 21000 8500	issipation athode Vo	Voits: {-675 +300 5000 8500 10000 8000 1, 3.5 watts oits, -2300, +	4.5 5.5 10.0† 14.0† -300 	6V3A 6V6GTY 6V6GTY 6V7G 6W4GT 6W7G 6X5 6X8 6Y5 6Y7G 6Y9 6Z4
Max /	Max. Peak  —12.5V —13V —15V —19Y  Ac Peak Inverse in the peak Inverse in the peak Inverse Volts per Pla  Ac Volts per Pla  Peak Inverse Volts	Plate Volts Plate MA, 250 225 250 285 For e Plate VomA, 750 te (RMS), its, 1250 te (RMS), its, 1250 Max. 1 For 170 150 Max. A Max. C	8, 6000 (Al 800  4.5 2.2 5.0   d.0	45.0 34.0 70.0□ 70.0□ racteris Max. Max. Max. 12 9 er Plate mA, 50 0 er Plate mA, 60	50000 80000 Stics, refer Max. Pe 1.5 M tics, refer DC Output Peak Plate DC Output Peak Plate 6000 300000 e (RMS), 35 tics, refer  (RMS), 230	Max. Ave Peak Heater 4100 3750 —— to Type 85  Max. Plate D ak Heater-C. 1225 to Type 6X4 mA, 70 mA, 245 mA, 70 mA, 245 6500 5500 -0 to Type 79 21000 8500	issipation athode Vi	Voits: {-675 +300 5000 8500 10000 8000 1, 3.5 watts oits, -2300, +	4.5 5.5 10.0† 14.0† -300 	6V3A 6V6GTY 6V6GTY 6V7G 6W4GT 6W7G 6X4W 6X5 6X8 6Y5 6Y7G 6Y9 6Z4 6Z5
Max. 250 315 250 285 M M 250 250 Max. 4 Max. 4 Max. 4	Max. Peak  —12.5V —13V —15V —19Y  Ac Peak Inverse in the peak Inverse in the peak Inverse Volts per Pla  Ac Volts per Pla  Peak Inverse Volts	Plate Volts Plate MA, 250 225 250 285 For e Plate VomA, 750 te (RMS), its, 1250 te (RMS), its, 1250 Max. 1 For 170 150 Max. A Max. C	8, 6000 (Al 800  4.5 2.2 5.0   d.0	45.0 34.0 70.0□ 70.0□ racteris Max. Max. Max. 12 9 er Plate mA, 50 0 er Plate mA, 60	50000 80000 Stics, refer Max. Pe 1.5 M tics, refer DC Output Peak Plate DC Output Peak Plate 6000 300000 e (RMS), 35 tics, refer  (RMS), 230	Max. Ave Peak Heater 4100 3750  to Type 85  Max. Plate D ak Heater-C. 1225  to Type 6X4  MA, 70  MA, 245  MA, 245  MA, 245  6500  5500  to Type 79 21000 8500	issipation athode Vi	Voits: {-675 +300 5000 8500 10000 8000 1, 3.5 watts oits, -2300, + 	4.5 5.5 10.0† 14.0† -300 	6V3A 6V6GTY 6V6GTY 6V7G 6W4GT 6W7G 6X5 6X8 6Y5 6Y7G 6Y9 6Z4
Max /	Max. Peak  —12.5V —13V —15V —19Y  Ac Peak Inverse in the peak Inverse in the peak Inverse Volts per Pla  Ac Volts per Pla  Peak Inverse Volts	Plate Volts Plate MA, 250 225 250 For e Plate VC mA, 750 tet mA, 12: 100 For site (RMS), lts, 1250 tet (RMS), 1250 Max. 1 For 170 150 Max. A Max. C Power Outp	8, 6000 (Al 800  4.5 2.2 5.0 color char char char char char char char cha	45.0 34.0 70.0 70.0 70.0 70.0 70.0 70.0 70.0 7	50000 80000 Stics, refer Max. Pe 1.5 M tics, refer DC Output Peak Plate 6000 300000 e (RMS), 35 tics, refer (RMS), 234 e at stated	Max. Ave Peak Heater 4100 3750  to Type 85  Max. Plate D ak Heater-C 1225  to Type 6X4  MA, 70  MA, 245  MA, 70  MA, 245  125  TO Type 79 21000 8500  plate-to-pla ype 6Z10/6J	Min. Imper Min. 40	Voits: {-675 +300 5000 8500 10000 8000 1, 3.5 watts oits, -2300, + 	4.5 5.5 10.0† 14.0† -300 	6V3A 6V6GTY 6V6GTY 6V7G 6W4GT 6W7G 6X4W 6X5 6X8 6Y5 6Y7G 6Y9 6Z4 6Z5

[†] For two tubes at stated plate-to-plate load.

RCA Type	Name	Out- line	Terminal Dia- gram		ater or neut (F)	Use Values to right give operat- ing conditions and character- istics for indicated typical use
			•	Volts	Amperes	-
7A4	Medium-Mu Triode	12B	5AC	6.3	0.3	Amplifier
7A5	Beam Power Tube	12C	GAA	6.3	0.75	Class A Amplifier
7A6	Twin Diode	12B	7AJ	6.3	0.15	Detector Rectifier
7A7	Remote-Cutoff Pentode	12B	87	6.3	0.3	Class A Amplifier
7 <b>A</b> 8	Octode Converter	12B	80	6.3	0.15	Converter
7AD7	Power Pentode	12C	87	6.3	0.6	Class A Amplifier
7AF7	Medium-Mu Twin Triode	12B	8AC	6.3	0.3	Each Unit as Class A Amplifier
7AG7	Sharp-Cutoff Pentode	12B	87	6.3	0.15	Class A Amplifier
7AH7	Sharp-Cutoff Pentode	12B	87	6.3	0.15	Class A Amplifier
7B4	High-Mu Triode	12B	5AC	6.3	0.3	Amplifier
7B5	Power Pentode	12C	6A E	6.3	0.4	Class A Amplifier
7B6	Twin Diode—High-Mu Triode	12B	8W	6.3	0.3	Triode Unit as Amplifier
7B7	Remote-Cutoff Pentode	12B	8V	6.3	0.15	Class A Amplifier
7B8	Pentagrid Converter	12B	8X	6.3	0.3	Converter
7C5	Beam Power Tube	12C	6AA	6.3	0.45	Class A Amplifier
706	Twin Diode—High-Mu Triode	12B	8W	6.3	0.15	Triode Unit as Class A Amplifier
707	Sharp-Cutoff Pentode	12B	84	6.3	0.15	Class A Amplifier
7DJ8/ PCC88	Dual Triode	6B	9DE	7	0.3	Each Unit as Class A Amplifier
7E6	Twin Diode—Medium-Mu Triode	12B	8W	6.3	0.3	Triode Unit as Amplifier
7 <b>E</b> 7	Twin Diode—Remote-Cutoff Pentode	12B	8AE	6.3	0.3	Pentode Unit as Class A Amplifier
7EY6	Beam Power Tube	13F	7AC	7.2	0.6	Vertical Deflection Amplifier
7F7	High-Mu Twin Triode	12B	BAC	6.3	0.3	Each Unit as Amplifier
7F8	Medium-Mu Twin Triode	12A	BBW	6.3	0.3	Each Unit as Class A Amplifier
7G7	Sharp-Cutoff Pentode	12B	87	6.3	0.45	Class A Amplifier
7H7	Semiremote-Cutoff Pentode	12B	84	6.3	0.3	Class A Amplifier
7HG8	Medium-Mu Triode— Sharp-Cutoff Pentode	6B	SMP	7.2	0.3	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
7,17	Triode-Haptode Converter	12B	BBL	6.3	0.3	Triode Unit as Oscillator Heptode Unit as Mixer
7K7	Twin Diode—High-Mu Triode	12B	8BF	6.3	0.3	Triode Unit as Class A Amplifier
7KZ6	Sharp-Cutoff Pentode	6E	9GK	7.3	0.45	Class A Amplifier
7L7	Sharp-Cutoff Pentode	12B	84	6.3	0.3	Class A Amplifier
7N7	Medium-Mu Twin-Triode	12C	8AC	6.3	0.6	Each Unit as Class A Amplifier
707	Pentagrid Converter	128	8AL	6.3	0.3	Converter
7R7	Twin Diode—Remote-Cutoff Pentode	12B	8AE	6.3	0.3	Pentode Unit as Class A Amplifier
7\$7	Triode-Heptode Converter	12B	8BL	6.3	0.3	Triode Unit as Oscillator
777	Sharp-Cutoff Pentode	12B	8V	6.3	0.45	Heptode Unit as Mixer Class A Amplifier
7W7	Sharp-Cutoff Pentode	12B	8BJ	6.3	0.45	Class A Amplifier
7X7	Twin Diode—High-Mu Triode	12B	8BZ	6.3	0.45	Triode Unit as Class A Amplifier
7 <u>77</u>	Full-Wave Rectifier	12B	5AB	6.3	0.5	With Capacitive-Input Filter
/14	Full-Mare Rectifier	148	JAD	0.3	U.J	TITLE CAPACILIVE-INPUL FII(EF

	Grid Bias		Screen	Mists	AC Plate	Trans	Amplifi-	Pow	er	RCA
Plate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Plate Cur- rent	Resist- ance	Trans- conduct- ance	cation Factor	Load	Out- put	Туре
Volts		Volts	mA	mA	Ohms	Micrombos		Ohms	Watts	
		Fo	r other c	haracter	istics, refe	r to Type 6	J5		·	7A4
110 125	7.5V 9V	110 125	3.0 3.3	40.0 44.0	16000 17000	5800 6000		2500 2700	1.5 2.2	7A5
	. AC Voltage pe				17000		Output Curr	ent per plate		7A6
III GA	NO TOILUBE PE				stics, refer	to Type 6				7AF7
250	<b>— 3V</b>	100	3.2	3.0	700000	Anode-Gr Oscillator sion Tran	id (2): 250 -Grid No. scond., 550	max. volts, 1 Resistor. micromhos	4.2 mA Conver-	7A8
300	68Ω	150	7.0	28.0	300000	9500				7AD7
250	—10V			9.0	7600	2100	16			7AF7
250	250Ω	250	2.0	6.0	1 M	4200				7AG7
250	250Ω	250	1.9	6.8	1 M	3300				7AH7
		For	other ch	naracteri	stics, refer	to Type 65	SF5			7B4
		For	other ch	aracteri	stics, refer	to Type 6K	6GT			7B5
		For	other ci	aracteri	stics, refer	to Type 65	Q7			7B6
250	<b>— 3V</b>	100	1.7	8.5		750000	1750	_		7B7
						r to Type 6				7 <u>88</u>
		Foi	other c			r to Type 6				7C5
250	<u> </u>			1.3	100000	1000	100			7C6
250	<u> </u>	100	0.5	2.0	2 M	1300				7C7
90	1.3			15		12500	33			7DJ8/ PCC88
		For	other ch	aracteri	stics, refer	to Type 6E	F6			7E6
250	330Ω	100	1.6	7.5	700000	1300				7E7
		For	other ch	aracteri	stics, refer	to Type 6E	Y6			7EY6
		For c	ther cha	racteris	tics, refer t	to Type 6SL	7GT			7F7
250	500Ω			6.0		3300	48	_		7F8
250	2V	100	2.0	6.0	800000	4500				7G7
100 250	— 1.5V 180Ω	100 150	2.6 3.2	7.5 10.0	350000 800000	4000 4000				7H7
						to Type 6H	IG8			7HG8
250	5000	id Resistor	2.8	5.0				Current, 0.4		. 7,17
250 250	- 3V 2V	100	2.8	2.3	1.5 M 44000	1600	70	scond., 290 μ	mnos	7K7
250	75Ω	115	3.6	25	45000	24000				7KZ6
100	— 1V	100	2.4		100000	3000				7L7
250	— 1.5V	100	1.5	5.5 4.5	1 M	3100				
		For c	ther cha	racteris	tics, refer t	o Type 6SN				7N7
250	2V	100	8.5	3.5	1 M	Conve	no. 1 Kesi rsion Trans	stor, 20000 of scond., 450 µ	nms mhos	7Q7
250	1V	100	2.1	5.7	1 M	3200				7R7
100 250		id Resisto O ohms		3.0 5.0	=	_=	=	=		787
250	— 2V	100	3.0	1.8	1.25 M		rsion Trans	cond., 525 μr	nhos	
300	160Ω	150	3.9	10.0	300000	5800				7,97
		For	other c			to Type 7				7W7
250	<u> </u>			1.9	67000	1500	100			7X7
May	Peak Inverse	Volts, 1250	)	Max.	DC Output	mA,70	Max	. Peak Plate	mA, 180	7Y4

RCA Type	Mame	Out- tine	Terminal Dia- gram	He Filan	ater or neut (F)	Use Values to right give operat- ing conditions and character- istics for indicated typical use
			•	Voits	Ampere	<del></del>
724	Full-Wave Rectifier	12C	5AB	6.3	0.9	With Capacitive-Input Filter
8AL9	High-Mu Triode Sharp-Cutoff Pentode	8C	12HE	8.6	0.6	Triode Unit as Class A Amplifier
8BH8	Medium-Mu Triode		ADV			Pentode Unit as Class A Amplifier Triode Unit as Class A Amplifier
	Sharp-Cutoff Pentode Sharp-Cutoff Twin Pentode	6E 8B	9DX 12GF	8.4	0.45	Pentode Unit as Class A Amplifie  Each Unit as
8BN11 8CB11	Sharp-Cutoff		126F	8.4	0.6	Class A Amplifier
	Twin Pentode	8B		8.4	0.6	Each Unit as Class A Amplifier
8CN7	Twin Diode—High-Mu Triode	68	SEN	8.4	4.2	Triode Unit as Class A Amplifie
8EB8	High-Mu Triode Sharp-Cutoff Pentode	6E	9DX	6.3	0.75	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
8ET7	Twin Diode— Sharp-Cutoff Pentode	SE	9LT	8	0.6	Pentode Unit as Class A Amplifier
8FQ7	Medlum-Mu Twin Triode	6E	9LP	8.4	0.45	Vertical and Horizontal Deflection Oscillators
8GJ7	Medium-Mu Triode— Sharp-Cutoff Pentode	63	9QA	8	0.3	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
9 <b>A</b> 8	Medium-Mu Triode— Sharp-Cutoff Pentode	<b>6</b> B	9DC	9	0.3	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
9AH9	Medium-Mu Triode Sharp-Cutoff Pentode	8B	12HJ	8.8	0.6	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifie
9AK10	High-Mu Triple Triode	8C	12FE	9.5	0.6	Each Unit as Class A Amplifier
9AM10	High-Mu Triple Triode	8C	12FE	9.5	0.6	Each Unit as Class A Amplifier
9AQ8/ PCC85	High-Mu Twin Triode	6B	SDE	9.0	0.3	Each Unit as Class A Amplifier
9BJ11	Beam Power Tube Sharp-Cutoff Pentode	88	12FU	9.6	0.45	Beam Unit as Class A Amplifier Pentode Unit as Class A Amplifier
9BR7	Twin Diode—High-Mu Triode	63	9CF	4.7 9.4	0.6 0.3	Triode Unit as Class A Amplifier
9CL8	Medium-Mu Triode—Sharp-Cutoff Tetrode	68	9FX	9.5	0.3	Triode Unit as Class A Amplifier Tetrode Unit as Class A Amplifier
9EA8	Medium-Mu Triode— Sharp-Cutoff Pentode	6B	9AE	9.5	0.15	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
9GV8	High-Mu Triode Power Pentode	66	9LY	9.5	0.6	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
9KC6	Sharp-Cutoff Pentode	6E	9RF	8.7	0.45	Class A Amplifier
9LA6	Sharp-Cutoff Pentode	6E	3GK	8.7	0.45	Class A Amplifier
ABUE	Medium-Mu Triode— Sharp-Cutoff Pentode	6B	9AE	9.45	0.3	Class A Amplifier
10	Power Triade	27B	4D	7.5F	1.25	Class A Amplifier
10C8	High-Mu Triode—Sharp-Cutoff Pentode	6B	9DA	10.5	0.3	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
10CW5	Power Pentode	6 <b>G</b>	9CY	10.6	0.45	Vertical Deflection Amplifier
10DX8	Higk-Mu Triode— Sharp-Cutoff Pentode	6E	9HX	10.2	0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
10EG7	Dual Triode	13B	8BD	9.7	0.6	Class A Amplifier
10GF7	Dual Triode	11A	900	9.7	0.6	Vertical Deflection Amplifier Vertical Deflection Oscillator

	Grid Bias		Screen	DI-A	10 01-2	Yue	lmr!!#	Po	wer	- RCA
Plate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Plate Cur- rent	AC Plate Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Load	Out- put	Туре
Veits		Volts	mÅ	mÅ	Ohms	Micromhos		Ohms	Watts	
Max.	Peak Inverse	Volts, 1250		Max Max	x. DC Outpu . Peak Plat	t mA, 100 e mA, 300	Min. Impe	Total Effec d. per Plate	. Supply , 75 ohms	7Z4
200	270Ω			7.6	9200	6300	59	·—		- OALG
250 55	56Ω 0V	150 125	5.6 21	28 56	40000 In:	30000 stantaneous	Plate Knee	characteri	stic	- 8AL9
		For	other ch	aracteri	stics, refer	to Type 6Bi	18			8BH8
		Fo	or other	characte	ristics, ref	er to Type 6	BN11			8BN11
125	56Ω	125	3.8	11	200000	13000				8CB11
		For	other ch	aracteri	stics, refer	to Type 6C	17			8CN7
250		125	7	2 25	37000 75000	2700	100			- 8EB8
200	0977					12500 er to Type (				8ET7
	<del></del>									
		For	other ch	iaracteris	stics, refer	to Type 6FG	<del></del>			8FQ7
		For	other ch	aracteris	stics, refer	to Type 6G.	7			8GJ7
100	<u> — 2V</u>			14		5000	20	ctor. (Grid		9A8
170	2V	170	2.8	10	400000	6200	No. 2 to	Grid No. 1),	. 47	
		For	other ch	aracteris	tics, refer	to Type 6AH	9			9AH9
400	****	For	other ch			to Type 6AK				9AK10
100				8	9300	6900	64			9AM10
200	2V			10		5800	48			PCC85
125 110	120Ω 0V	125 110	2.5 6.8	8.5 5.8	40000 40000	9600 7500	(Grid	No. 1 = 10	1000Ω)	9BJ11
250	200Ω			10	10900	4000	60			9BR7
125	56Ω			15	5000	8000	40			
125	1V	125	4	12	100000	5800				9CL8
		Fo	or other	characte	ristics, ref	er to Type 6	EA8			9EA8
		For	other cha	racteris	tics, refer	to Type 6GV	8	<del></del>		9GV8
250 50	56Ω 0V	150 100	9 25	18 25	55000 Ins	24000 tantaneous I	(Ecs = 0 Plate Knee	V) characteris	tic	9KC6
50 250	0V 0V	125 150	32 6	76 25	55000	21000				9LA6
		Fo				er to Type 6	U8A			9U8A
425	-40V			18.0	5000	1600	8.0	10200	1.6	10
250	390Ω			7.3	12000	4400	53			1000
135	100Ω	135	3.2	11.5	190000	8000				1008
					refer to T	·	-			10CW5
						to Type 6DX				10DX8
						to Type 6EW	7			10EG7
					, refer to T					10GF7
		For	other ch	aracteris	tics, reter	to Type 6JA				10JA5

RCA Type	Name	Out- line	Terminal Dia- gram	He	eater or nment (F)	Values to right give opera- ing conditions and character istics for indicated typical us		
			-	Volts Ampe		res		
10JA8	High-Mu Triode Sharp-Cutoff Pentode	6E	9DX	10.5	0.45	Class A Amplifier		
10LB8	Medium-Mu Triode Sharp-Cutoff Pentode	10A	9DX	10.2	0.45	Class A Amplifier		
	High-Mu Triode					Triode Unit as Class A Amplifier		
10LW8	Sharp-Cutoff Pentode	6E	SDX	10.5	0.45	Pentode Unit as Class A Amplifie		
10LZ8	High-Mu Triode-	6E	9DX	10.5	0.45	Triode Unit as Class A Amplifie Pentode Unit		
	Sharp-Cutoff Pentode					as Class A Amplifier		
	Detector Amplifier	4F	4F	1.1F	0.25	Class A Amplifier		
11CA11	Dual Triode Sharp-Cutoff Pentode	6B	12HN	10.7	0.6	Triode Unit 1 as Class A Amplifier Triode Unit 2 as Class A Amplifier Pentode Unit as Class A Amplifier		
11CF11	Dual Triode Sharp-Cutoff Pentode	8B	12KW	10.7	0.6	Triode Unit 1 as Class A Amplifie Triode Unit 2 as Class A Amplifie Pentode Unit as Class A Amplifie		
11 <b>CH</b> 11	Dissimilar Double Triode Sharp-Cutoff Pentode	88	12 <b>G</b> 3	10.7	0.6	Triode Unit 1 as Class A Amplifier Triode Unit 2 as Class A Amplifier Pentode Unit as Class A Amplifier		
11CY7	Dual Triode	6E	9LG	11	0.45	Vertical Deflection Oscillator and Amplifier		
11JE8	High-Mu Triode Sharp-Cutoff Pentode	6E	9DK	10.9	0.45	Class A Amplifier		
441/0						Unit No. 1 as Class A Amplifier		
11Y9	Dual Pentode	6L	10L	11	0.45	Unit No. 2 as Class A Amplifier		
12 <b>A</b> 5	Power Pentode	22 or 13H	7F	6.3	0.6	Class A Amplifier		
12A6 + 12A6 Y +	Beam Power Tube	2B	7AC	12.6 12.6	0.3	Class A Amplifier		
12.0.						Pentode Unit as Class A		
12 <b>A</b> 7	Rectifier-Power Pentode	248	7K	12.6	0.3	Amplifier Half-Wave Rectifier		
12A8GT	Pentagrid Converter	14A	8A	12.6	0.15	Converter		
				10.0	0.15			
12AC6	Remote-Cutoff Pentode	5C	7BK	to 15.9	approx. at 12.6 V	Class A Amplifier		
12AD6	Pentagrid Converter	5C	7CH	10.0 to	0.15 approx.	Converter		
				15.9 10.0	at 12.6 V 0.15			
12 <b>AE</b> 6	Twin Diode—Medium-Mu Triode	5C	78T	to 15.9	approx. at 12.6 V	Triode Unit as Class A Amplifier		
12AE6A	Twin Diode-Medium-Mu Triode	5C	7BT	10.0 to	0.15 approx.	Triode Unit as Class A Amolifie		
			_	15.9	at 12.6 V	· · · · · · · · · · · · · · · · · · ·		
12 <b>AE</b> 7	Dual Triode	6B	9A	to 15.9	approx. at 12.6 V	Unit No. 2 as Class A Amplifier Unit No. 2 as Class A Amplifier		
12AF6	Remote-Cutoff Pentode	5C	7BK	10.0 to 15.9	0.15 approx. at 12.6 V			
12AH7	Medium-Mu Twin Triode	13C	8BE	12.6	0.15	Each Unit as Class A Amplifier		
GT		130		10.0		Lacii Unit as Class A Ampliner		
12AJ6	Twin Diode—Medium-Mu Triode	5¢	7BT	to	0.15 approx.	Triode Unit as Class A Amplifier		
♦ Industr	Sat Avea			15.9	at 12.6 V			

	Grid Bias		Screen Grid	Plate	AC Plate	Trans-	Amplifi-	Pew	er	RCA
Plate	or Cathode Resistor	Screen Grid	Cur- rent	Cur- rent	Resist- ance	conduct- ance	cation Factor	Load	Out- put	Туре
Voits		Volts	mA	mÅ	Ohms	Micromhos		Ohms	Watts	
		For oth	er chara	teristic	s, refer to	Type 10JA8	/10LZ8			10JA8
		For	other cl	aracteri	stics, refer	to Type 6L	B8	,		10LB8
200	—2V			2.6	18700	4000	75			- 101 WO
200 35	82Ω 0	100 100	2.8 12.5	16.5 <b>48</b>	60000 In	19000 Istantaneous	Plate Kne	e characteri	stic	10LW8
250	<b>— 2</b>			1.1	52000	2100	110			10170
200	0	140	2.5	12	150000	9500				10LZ8
135	—10.5V			3	15500	440				11
200	270Ω			7.6	9200	6300	59			
200	270Ω			7.1	12400	5500	69			11CA11
200 40	65Ω 0V	120 120	4.9 17.6	27.5 68	490000 Ins	21200 stantaneous	Plate Knee	characteris	tic	
200	270Ω			7.1	12400	5500	69	-		_
200	270Ω			7.6	9200	6300	59			11CF11
200 40	65Ω 0V	120 120	4.9 17.6	27.5 68	490000	21200 stantaneous	Plate Knee	characteris	tic	
200	270Ω			7.1	12500	5500	69			
200	470Ω			7.2	7600	5300	40			- -11 <b>CH1</b> 1
200 50	65Ω 0V	120 120	4.9	27.5	490000	20000	Dieta Kno		+ic	1.011
30	U¥		18 other ch	71 aracteris		to Type 60		e characteris	LIC	11CY7
					• •	to Type 6J				11JE8
170	0.0				,			mpl. Factor (	Grid-No.	
170	<b>— 2</b> .6	170	6.5	30		21000	1	to Grid-No.	2), 38	- 11Y9
150	2.3	150	3	10		8500		Ampl. Factor 1 to Grid No		
180	25V	180	8.0	45.0	35000	2400		3300	3.4	12A5
										12A6+
250	—12.5V	250	3.5	30	70000	3000		7000	3.4	12A6Y
135	—13.5V	135	2.5	9.0	100000	975		13500	0.55	- 12A7
	Maximum / Maximum	AC Plate DC Outout	Voltage Curren	 }		······	125 Vo	ilts, RMS		1211/
	- Huximum					to Type 6A		mamperes		12A8GT
								1 Supply Vo	Ite N )	
12.6	_	12.6	.2	.55	500000	730	Grid-No.	1 Res., 2.2	megohms	12AC6
12.6	Self-	12.6	1.5	0.45	1 M	Grid	-No. 1 Res	istor, 33000	ohms	12AD6
	excited					Collvers	Ston Italisc	ond., 260 mi	CLOUINGS	
12.6	0V			0.75	15000	1000	15			12AE6
	0V			1	13000	1300	16.7			12AE6/
12.6	Grid Res	. 1.5 megol	nms	1.9	3150	4000	13.0			
				7.5	985	6500	6.4			- 12AE7
12.6 12.6 12.6	Grid Re	3. I III C K V II				•	(0 (1 )	1 Cumple Va		
12.6		12.6	0.45	1.1	350000	1500	Grid-No.	1 Res., 2.2	Its, O ) megohms l	12AF6
12.6 12.6 12.6	Grid Re		0.45					1 Supply Vo 1 Res., 2.2	Its, 0 megohms}	12AF6 12AH7
12.6 12.6			0.45	7.6	350000 8 <b>40</b> 0	1500 1900	Grid-No. (Grid-No.	1 Res., 2.2	Its, 0 } megohms}	

RCA Type	Name	Out- line	Terminal Dia- gram		ater or ment (F)	Use Values to right give operat- ing conditions and character- istics for indicated typical use
				Volts	Amperes	•
						Triode Unit as Class A Amplifie
12AL8	Medium-Mu Triode—Power Tetrode	6E	296	10.0 to 15.9	0.55 approx. at 12.6 V	Tetrode Unit as Class A Amplifier
12AT7		68	9A	12.6 6.3	0.15 0.3	Class A Amplifier
12AU7	Medium-Mu Twin Triode	68	9A	6.3 12.6	0.3 0.15	Each Unit as Class A Amplifier
12AV7	Medium-Mu Twin Triode	6B	9A	6.3 12.6	0.45 0.225	Each Unit as Class A Amplifier
12AW6	Sharp-Cutoff Pentode	5C	7CM	12.6	0.15	Class A Amplifier
12AX4- GT 12AX4- GTA	Half-Wave Rectifier	13D 13D	4CG	12.6 12.6	0.6 0.6	Television Damper Service
12AX7	High-Mu Twin-Triode	6B	9A	6.3 12.6	0.3 0.15	Each Unit as Class A Amplifier
12AY3	Half-Wave Rectifier	11D	9HP	12.6	0.6	Television Damper Service
12AZ7	High-Mu Twin-Triode	6B	<b>9</b> A	6.3 12.6	0.45 0. <b>22</b> 5	Each Unit as Class A Amplifier
12B8GT	High-Mu Triode—Remote-Cutoff Pentode	_	8T	12.6	0.3	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
12BA7	Pentagrid Converter	6E	8CT	12.6	0.15	Converter
12BD6	Remote-Cutoff Pentode	5C	7BK	12.6	0.15	Class A Amplifier
12BF6	Twin Diode—Medium-Mu Triode	5C	7BT	12.6	0.15	Triode Unit as Class A Amplifier
12BH7	Medium-Mu Twin Triode	6E	9A	6.3 12.6	0.6 0.3	Vertical Deflection Amplifier
12BK5	Beam Power Tube	6E	9BQ	12.6	0.6	Class A Amplifier
12BL6	Remote-Cutoff Pentode	5C	7BK	10.0 to 15.9	0.15 approx. at 12.6V	Class A Amplifier
12BN6	Beam Tube	5D	7DF	12.6	0.15	Limiter and Discriminator
12BR7	Twin Diode—High-Mu Triode	68	9C F	6.3 12.6	0.45 0.225	Triode Unit as Class A Amplifier
12BS3	Half-Wave Rectifier	11D	9HP	12.6	0.6	Television Damper Service
12BT3	Half-Wave Rectifier	8C	12BL	12.6	0.45	Television Damper Service
12BV7	Sharp-Cutoff Pentode	6E	9BF	6.3 12.6	0.6 0.3	Class A Amplifier
12BW4	Full-Wave Rectifier	6E	901	6.3	0.9	With Capactive Input Filter With Inductive Input Filter
12BY7	Sharp-Cutoff Pentode	6E	9BF	6.3 12.6	0.6 0.3	Class A Amplifier
12BZ7	High-Mu Twin Triode	6E	9A	12.6	0.3	Each Unit as Class A Amplifier
12C8	Twin Diode—Semiremote-Cutoff Pentode	3	8E	12.6	0.15	Pentode Unit as RF Amplifier
12CK3	Half-Wave Rectifier	30B	SHP	12.6	0.6	Television Damper Service
12CN5	Remote-Cutoff Pentade	50	7CV	10.0 to 15.9	0.45 approx. at 12.6V	Class A Amplifier
12CR6	Diode-Remote-Cutoff Pentode	5C	7EA	6.3	0.3	Pentode Unit as Class A Amplifier
12CT8	Medium-Mu Triode—Sharp-Cutoff Pentode	6E	9DA	12.6	0.3	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier

[◆] Industrial Type

	Grid Bias		Screen	nt-4-	40 Bl-4-	Terra	A-n-11#	Pow	er	- RCA
Plate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Plate Cur- rent	AC Plate Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Load	Out- put	Туре
Voits		Volts	mA	mÅ	Ohms	Micromhos		Ohms	Watts	
12.6	— 0.9V (across 2.2	? megohm r	es.)	.5	13000	1000	13			
Grid-N	No. 2 (Control (across 2.2 m Io. 1 (Space-Ch cond. (Grid-No.	Grid) Volts egohm res. large Grid)	—.5 Voits, 12	2.6 µmhos	G	mpl. Factor rid-No. 1 mA ate Resistan	.75 PI	? to Plate) 7. ate mA, 40 ms		12AL8
		For	other ch	aracteris	atics, refer	to Type 12A	<b>.</b> T7		12 12	AT7WA+ AT7WB+
100 250	0V 8.5V		$\equiv$	11.8 10.5	6250 7700	3100 2200	19.5 17			12AU7
150	56Ω		_	18	4800	8500	41	Cutoff Vol	ts, —12	12AV7
_		For	other c	haracter	istics, refe	r to Type 6A	G5			12AW6
Max. Max. Max.	Peak Inverse F Peak Plate mA DC Plate mA	, 750	4400		Max. F DC cor	eak Heater-( nponent mus	Cathode Vo	olts: {4400 +300 ed 900 volts		12AX4- GT 12AX4- GTA
100 250	— 1V — 2V			0.5 1.2	80000 62500	1250 1600	100 100		_	12 <b>AX7</b>
			For othe		, refer to					12AY3
100 250	270Ω 200Ω	_	_	3.7 10.0	15000 10900	4000 5500	60 60			12AZ7
90	0V			2.8	37000	2400	90			- 120001
90	— 3V	90	2	7	200000	1800	—			12B8G1
		For	other ch	aracteri	stics, refer	to Type 68/	A7			12BA7
		For	other ch	aracteri	stics, refer	to Type 6Bi	06		-,,	12BD6
250	— 9V		16	190		8500		Power Or 300 milli	watts	12BF6
Max. Max.	DC Plate Volts DC Plate mA,	, 450 20		Abs: Max	olute Max. . Plate Dis	Peak Positiv sipation (Eac	e-Pulse Pi h Unit), 3	ate Volts, 15 .5 watts	00	12BH7
250	5V	250	3.5	35	100000	8500		6500	3.5	12BK5
12.6	Grid-No. 1 Supply Volts, 0	12.6	0.5	1,35	500000	1350	for	l and Grid-No transcond. of icromhos, —	. 3 Volts 10 5	12BL6
		For ot	her chara			Type 6BN6,				12BN6
100 250	270Ω <b>20</b> 0Ω	<del></del>	_	3.7 10	15000 10900	4000 5500	60 60			12BR7
					, refer to	Type 6BS3				12BS3
	Max. Peak Max.	Inverse Pl Peak Plate		Ó				Plate mA, 1 athode Volts	( 3300	12BT3
250 250	68Ω — 8V	150 180	6	27 0.5	85000	13000				12BV7
		F	or other	characte	eristics, ref	er to 6BW4				12BW4
250	100Ω	180	5.75	26	93000	11000		<del>-</del>		12BY7
250	<b>—2V</b>			2.5	31800	3200	100			12BZ7
250	— 3V	125	2.3	10	600000	1325				1208
		For	other cl	aracteri	stics, refer	to Type 6C	К3			12CK3
12.6		12.6	3.5	4.5	40000	3800	{Grid-No. {Grid-No.	1 Supply Vol 1 Res., 2.2 r	ts, 0 }	12CN5
		F	or other	characte	eristics, re	fer to Type	6CR6			12CR6
150	150Ω			9	8200	4900	40			10070
200	82Ω	125	3.4	15	150000	70 <b>0</b> 0				12CT8

RCA Type	Name	Out- line	Terminal Dia- gram	H	feater or lament (F)	Use  Values to right give operating conditions and character istics for indicated typical us
				Volts	Amperes	- <b>-</b>
12CX6	Remote-Cutoff Pentode	5C	7BK	10.0 to 15.9	0.15 approx. at 12.6V	Class A Amplifier
12D4	Half-Wave Rectifier	13D	4CG	12.6	0.6	Television Damper Service
12DB5	Beam Power Tube	6F	9GR	12.6	0.6	Class A Amplifier
12DE8	Diode-Remote-Cutoff Pentode	68	946	10.0 to 15.9	0.2 approx. at 12.6V	Pentode Unit as Class A Amplifier
12DK7	Twin Diode—Power Tetrode	6E	SHZ	10.0 to 15.9	0.5 approx. at 12.6V	Tetrode Unit as Class A Amplifier
12DL8	Twin Diode—Power Tetrode	6E	SHR	10.0 to 15.9	0.55 approx. at 12.6V	Tetrode Unit as Class A Amplifier
12DM4 12DM4A	Half-Wave Rectifier	13F 13G	4CG	12.6	0.6	Television Damper Service
12DQ6A	Beam Power Tube	20A	6AM	12.6	0.6	Horizontal Deflection Amplifier
12DQ6B	Beam Power Tube	20A	6AM	12.6	0.6	Horizontal Deflection Amplifier
12007	Power Pentode	6E	9BF	6.3 12.5	0.6 0.3	Class A Amplifier
<b>12DS7</b> 12DS7A	Twin Diode—Power Tetrode	GE GE	<b>9</b> 10	10.0 to 15.9	0.4 approx. at 12.6V	Tetrode Unit as Class A Amplifier
						Diode Units
12DU7	Twin Diode—Power Tetrade	68	aıx	10.0 to 15.9	0.25 approx. at 12.6V	Tetrode Unit as Class A Amplifier
12DV8	Twin Diode—Power Tetrode	βE	9HR	10.0 to 15.9	0.375 approx. at 12.6V	Class A Amplifier
12DW4A	Half-Wave Rectifier	110	9HP	12.6	0.6	Television Damper Service
12DW7	Dual Triode	6B	9A	12.6 6.3	0.15 0.3	Unit No. 2 as Class A Amplifier Unit No. 2 as Class A Amplifier
12DY8	Medium-Mu Triode— Remote-Cutoff Tetrode	<b>6</b> B	910	10.0 to 15.9	0.35 approx. at 12.6V	Triode Unit as Class A Amplifier Tetrode Unit as Signal Seeker Relay
12DZ6	Remote-Cutoff Pentode	5C	7BK	10.0 to 15.9	0.19 approx. at 12.6V	Class A Amplifier
12EA6	Remote-Cutoff Pentode	5C	7BK	10.0 to 15.9	0.19 approx. at 12.6V	Class A Amplifier
12EC8	Medium-Mu Triode—	88	9FA	10.0 to	0.225 approx.	Triode Unit as Class A Amplifier
	Semiremote-Cutoff Pentode			15.9	at 12.6V	Pentode Unit as Class A Amplifier
12ED5	Beam Power Tube	5D	7CV	12.6	0.45	Class A Amplifier
12EG6	Pentagrid Amplifier	5C	7CH	10.0 to 15.9	0.15 approx. at 12.6V	Class A Amplifier
12EH5	Power Pentode	5D	7CV	12.6	0.6	Push-Pull Class AB, Amplifier
12EK6/ 12DZ6/ 12E <b>A</b> 6	Remote-Cutoff Pentode	5C	TBK	10.0 to 15.9	0.19 approx. at 12.6V	Class A Amplifier
12EL6	Twin Diode—High-Mu Triode	5C	7FB	10.0 to 15.9	0.15 approx. at 12.6V	Class A Amplifier

	Grid Bias		Screen	l Blake	AC Blata	Trans	Amelië	P	ower	
Plate	or Catbode Resistor	Screen Grid	Grid Cur- rent	Plate Cur- rent	AC Plate Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Lead	Out- put	RCA Type
Volts		Volts	mA	mA	Ohms	Micromhos		Ohms	Watts	
12.6	Grid-No. 1 Supply Volts, 0	12.6	1.4	3	40000	3100		1 Volts of 10 μA,		12CX6
	Max. Peak Inver Max. Peak Plate Max. Average Pl	mA, 900		00	Max. F	eak Heater- Plate Di	Cathode Vo	•	), +300	1204
200	180Ω	125	2.2	46	28000	8000		4000	3.8	12DB5
12.6		12.6	0.5	1.3	300000	1500	Grid No. Grid-No.	1 Supply V 1 Res., 2.2	olts, 0 megohms	12DE8
12.6		12.6	1	6	4000	5000		3500	0.010	12DK7
12.6	Grid-No. 2 (Co (across 2. Grid-No. 1 (Sp Transcond. (G	.2 megohm ace-Charg	resistor e Grid) V	) /olts, 12.6	5	Ampl. Facto Grid-No. 1 n Plate Resist	nA, 75	Plate mA,		12DL8
		For	other cl	haracteris	tics, refer	to Type 6DM	14			12DM4 12DM4A
Max. Max.	DC Plate Volts DC Cathode mA	i, 140			Max.	. Peak Posit . Plate Dissi	ive-Pulse P pation, 15	late Volts, watts	6000 (Abs.)	12DQ6A
			or other	ratings,	refer to T	ype 6DQ6B				12DQ6B
<b>20</b> 0	68Ω	125	5.6	26	53000	10500				12 <b>DQ</b> 7
12.6	12.6V	0.5 (across 2.2 megohm resistor)	75 (Grid- No. 1)	35	500	19000 (Grid- No. 2 to Plate)	9.1 (Grid- No. 2 to Plate)	_		<b>12DS7</b> 12DS7A
		Dio	de Plate	mA, with	10 Volts	Applied, 3 m	ıA			
12.6	-	12.6	1.5	12	6000	6200		2700	0.025	12DU7
Grid-I Grid-I Trans	No. 2 (Control G No. 1 (Space-Ch cond. (Grid-No.	irid) Resistarge Grid) 2 to Plate	tor, 4.7 Volts, 1 ), 8500	megohms 2.6 umhos	Gri	pl. Factor ( d-No. 1 mA, ite Resistan	53 F	Plate mA, 9	6	12 <b>DV</b> 8
		Fo	r other	characteri	istics, refe	r to Type 61	OW4A			12DW4A
250	— 2V			1.2	62500		100			12DW7
250 12.6	<u> </u>			10.5	7700 10000	2000	17 20			
10		10				resistor 10		Piate Load	700 ohms	12 <b>DY</b> 8
15	— 6V	15		3 max.				Plate Load		12010
12.6	Grid-No.1 Supply Volts, 0	12.6	2.2	4.5	25000	3800				12DZ6
12.6		12.6	1.4	3.2	32000	3800	Grid-No. 1 Grid-No. 1	Supply Vol. Res., 10	its, 0 }	12EA6
12.6	4700Ω (Grid Res.)	_		2.4	6000	4700	<b>2</b> 5			
12.6		12.6	0.28	0.66	750000	2000	Grid No.	1 Res., 330	00 ohms	12EC8
1.25	_ 4 5V	125	7	37	14000	8500		4500	1.5	12ED5
	0.6V†	12.6	2.8	.55	150000	800‡	†Bias volt	Grid No. 3 & age across megohms	Plate res.	12EG6
12.6		100	110	47□				6000	3.8†	12EH5
12.6 140	68Ω	120								
	 	12.6	1.7	4	50000	4200	Grid-No. Grid-No. 2.	1 Supply \ 1 Res. (By 2 megohms	/olts, 0 passed),	12EK6/ 12DZ6/ 12EA6

[†] For two tubes at stated plate-to-plate load.

RCA Type	Name	Out- line	Terminal Dia- gram		ater er ment (F)	Use Values to right give operat- lng conditions and character- lstics for indicated typical use
				Volts	Amperes	•
12EM6	Diode—Power Tetrode	6E	9HV	10.0 to 15.9	0.5 approx. at 12.6V	Class A Amplifier
12EN6	Beam Power Tube	13D	7AC	12.6	0.6	Vertical Deflection Amplifier
12EQ7	Diode-Remote-Cutoff Pentode	6E	SLQ	12.6	0.15	Pentode Unit as Class A Amplifier
12F5GT	High-Mu Triode	14A	5M	12.6	0.15	Amplifier
12F8	Twin Diode—Remote-Cutoff Pentode	<b>6</b> B	9FH	10.0 to 15.9	0.15 approx. at 12.6V	Pentode Unit as Class A Amplifier
12FK6	Twin Diode—Low-Mu Triode	5C	7BT	10.0 to 15.9	0.15 approx. at 12.6 V	Triode Unit as Class A Amplifier
12FM6	Twin Diode-Medjum-Mu Triode	5C	7BT	10.0 to 15.9	0.15 approx. at 12.6V	Triode Unit as Class A Amplifier
12FQ8	High-Mu Twin Double-Plate Triode	6B	9KT	12.6	0.15	Each Unit as Class A Amplifier
12FR8	Diode—Medium-Mu Triode Remote-Cutoff Pentode	6K	9KU	12.6	0,32	Triode Unit as Class A Amplifier
12FV7	Medium-Mu Twin Triode	6E	SA	6.3 12.6	0.9 0.45	Each Unit as Class A Amplifier
1051/0	Medium-Mu Triode—Pentagrid		••••	10.0	0.3	Triode Unit as Class A Ampilfier
12FX8	Converter	6D	SKV	to 15.9	approx. at 12.6V	Pentagrid Unit as Converter
12FX8A	Medium-Mu Triode-Pentagrid Converter	6D	SKY	10.0 to 15.9	0.27 approx. at 12.6V	Triode Unit as Class A Amplifier Pentagrid Unit as Converter
12GA6	Pentagrid Converter	5C	7CH	10.0 to 15.9	0.15 approx. at 12.6V	Converter
12 <b>6</b> C6	Beam Power Tube	20A	8JX	12.6	0.6	Horizontal Deflection Amplifier
12GJ5	Beam Power Tube	18A	SOX	12.6	0.6	Horizontal Deflection Amplifier
12GN7 12GN7A	Sharp-Cutoff Pentode	8E	9BF	6.3 12.6	0.6 0.3	Class A Amplifier
12675 12GT5A	Beam Power Tube	178	9NZ	12.6	0.6	Harizantal Deflection Amplifier
12 <b>H</b> 6	Twin Diede	29B	7Q	12.6	0.15	Voltage Doubler Half-Wave Rectifier
12J5GT	Medium-Mu Triode	13D	60	12.6	0.15	Amplifier
12J7GT	Sharp-Cutoff Pentode	14A	7R	12.6	0.15	Amplifier
12J8	Twin Dlode—Power Tetrode	68	9 <b>G</b> C	10.0 to 15.9	0.325 approx. at 12.6V	Tetrode Unit as Class A Amplifier
12JB6	Beam Power Tube	18A	9QL	12.6	0.6	Horizontal-Deflection Amplifier
12JF5	Beam Power Tube	16A	12JH	12.6	0.6	Horizontal Deflection Amplifier
12JN8	Medium-Mu Triode— Sharp-Cutoff Pentode	6B	9FA	12.6	0.225	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
12JT6	Beam Power Tube	170	9QU	12.6	0.6	Horizontal Deflection Amplifier
12K5	Power Tetrode	5D	7EK	10.0 to 15.9	0.4 approx. at 12.6V	Class A Amplifier
12K7GT	Remote-Cutoff Pentode	14A	7R	12.6	0.15	Amplifier
12K8	Triode-Hexode Converter	3	8K	12.6	0.15	Oscillator Mixer

	Grld Bias		Screen	Bloke	AC DIsta	Trans-	Amplifi-	Pov	ver	- RCA
Plate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Plate Cur- rent	AC Plate Resist- ance	conduct- ance	cation Factor	Load	Out- put	Туре
/elts		Volts	mA	mA	Ohms	Micromhos		Ohms	Watts	
12.6	_	12.6	1	6	4000	5000	Grid-No.	1 Res., 2.2	megohms	12 <b>EM</b> 6
Max. Max.	Peak PosPulse Peak NegPulse Peak Cathode m	Voits, 12 Grid Vol	00 ts, <b>2</b> 50			Max. Max.	Plate Dissi DC Plate V	pation, 7 w olts, 300	atts	12EN6
max.	reak Cathode III			naracteri	stics, refe	to Type 6E	Q7			12 <b>EQ</b> 7
		For	other ch	aracteris	tics, refer	to Type 6F5	iGT			12F5GT
12.6	ov	12.6	0.38	1	330000	1000	Grid-No. cond. of	1 Volts f 10 micron	or trans- ihos, —5	12F8
12.6	Grid Suppl Grid Res. ( 2.2 me	y Voits, Bypassed gohms	0 ),	1.3	6200	1200	7.4			12FK6
12.6	0V			1	7700	1300	10			12F <b>M</b> 6
250	—1.5V	w	ith plate	1.5 not in	76000 use connec	1250 ted to groun	95 nd.		_	12FQ8
12.6	0.8V	12.6	0.7	1.9	400000	2700				12FR
100	— 2V			16	2250	9600	21.5			12FV7
12.6				1.3	7150	1400	10	Grid 2.2 me	gohms	- - 12FX8
12.6	_	12.6	1.25	0.29	500000	Grid N Convers	o. 3 Res., sion Transo	2.2 megoh cond., 300	ms μmhos	
12.6	<b>— 0.8</b>			1.3	7150	1400	10			- 12FX8A
12.6	0.5	12.6	1.25	0.29	500000	Convers	o. 3 Res., sion Transc	ond., 300	mhos μmhos	
12.6	1.6V	12.6	0.8	0.3	1 N		o. 1 Res., sion. Trans			12GA6
	DC Plate Volts, DC Cathode mA,					Max. Peak F Max. Plate	Positive-Pul	se Plate Vo 17.5 watts	Its, 6500	12GC6
W GA	. 00 02111000 11111		other c	haracteri	stics, refe	r to Type 6G		<del></del>		12GJ5
50 250	0V 0V	125 150	24 6.5	70 28	50000	36000	_			12GN7 12GN7A
Max.	DC Plate Volts,	770				Max. Peak Max. Plate	Positive-Pu Dissipation	ilse Plate 1. 17.5 wat	Volts, 6500	40075
Max. Min. Max	AC Supply Volts Total Effect. Pl AC Plate Volts (I DC Output mA, 8	per Plat ate-Supp RMS), 150	ly Imped )	117 . per Pl	ate: half-w	Max rave, 30 ohm lin. Total Eff	v DC Outou	t mA, 8. min e, 15 ohms e-Supply Im	n. pedance: u	
		For	other ch	aracteri	stics, refer	to Type 6J5	GT			12J5GT
		For	other ch	aracteris	tics, refer	to Type 6371	GT			12J7G1
12.6	<b>— 0V</b>	12.6	1.5	12	6000	5500	_	2700	0.02	12J8
				er rating		Type 6JB6	<del></del>			12,186
,	Max. DC Pla Max. DC Cat					x. Peak Posi Max. Plate	itive-Pulse Dissipation			12JF5
125 125	<u> 1V</u> 1V	125	4	13.5 12	5400 200000	8500 7500	46		_=	- 12JN8
Max Max	. DC Plate Supply . DC Cathode mA	Volts, 175	770		Max.	Peak Positiv Plate Dissip	ation, 17.5	watts		12JT6
DC F Grid	Plate Volts, 12.6 -No. 1 (Space- Ch Plate mA, 40	G arge Grid	rid-No. 2 I) Volts, No. 1 mA	(Contro 12.6 , 75	l Grid) Vol Ampli Trans		Plate R tor, Grid-No No. 2 to Pla	esistance, e . 2 to Plate te, 15000 µ	480 ohms 2, 7.2 mhos	12K5
					ristics, ref	er to Type 6	K7GT			12K7GT
		Fc	r other	characte	ristics, ref	er to Type 6	K8			12K8

RCA Type	Name	Sut- line	Termina Dia- gram		Heater or filament (F)	Use Values to right give operating conditions and character istics for indicated typical us
				Velts	Amperes	_
12KL8	Diode—Sharp-Cutoff Pentode	6E	SLQ	12.6	0.15	Pentode Unit as Class A Amplifier
12L6GT	Beam Power Tube	13B	7AC	12.6	0.6	Class A Amplifier
12Q7GT	Twin Diode-High-Mu Triode	14A	77	12.6	0.15	Triode Unit as Amplifier
12R5	Beam Power Tube	5D	7CV	12.6	0.6	Vertical Deflection Amplifier
12S8GT	Triple Diode—High-Mu Triode	14B	808	12.6	0.15	Triode Unit as Class A Amplifier
12SA7 12SA7 GT	Pentagrid Converter	2A 13D	8R 8AD	12.6	0.15	Converter
12SC7	High-Mu Twin Triode	2A	88	12.6	0.15	Each Unit as Class A Amplifier
12SF5 12SF5 GT	High-Mu Triode	2Å 13D	SAB SAB	12.6	0.15	Class A Amplifier
12SF7	Diode—Remote-Cutoff Pentode	2A	7AZ	12.6	0.15	Pentode Unit as Amplifier
12567	Semiremote-Cutoff Pentode	2A	8BK	12.6	0.15	Class A Amplifier
12SH7	Remote-Cutoff Pentode	3	8BK	12.6	0.15	Class A Amplifier
1 <b>2SJ7</b> 12SJ7 G <b>T</b>	Sharp-Cutoff Pentode	2A 13D	8N 8N	12.6	0.15	Class A Amplifier
12SK7 12SK7 GT	Remote-Cutoff Pentode	2A 13D	8N 8N	12.6	0.15	Class A Amplifier
12SN7 GT	Medium-Mu Twin Triode	13D	8BD	12.6	0.3	Each Unit as Class A Amplifier
12SQ7 12SQ7 GT	Twin Diode—High-Mu Triode	2A 13D	8Q 8Q	12.6	0.15	Triode Unit as Class A Amplifier
12SR7 12SR7 GT	Twin Diode—Medium-Mu Triode	2A 13D	8Q 8Q	12.6	0.15	Triode Unit as Class A Amplifier
2SW7+	Twin Diode—Medium-Mu Triode	2A	80	12.6	0.15	Triode Unit as Class A Amplifier
12SY7 *	Pentagrid Converter	2A	8R	12.6	0.15	Converter
12U7	Medium-Mu Twin Triode	6B	7CK	10.0 to 15.9	0.15 approx. at 12.6V	Each Unit as Class A Amplifier
12Z3	Half-Wave Rectifier	22	46	12.6	0.3	With Capacitive-Input Filter
13EM7	Dual Triode	13A	8BD	13	0.45	Unit No. 1 as Vertical Deflection Amplifier Unit No. 2 as
13GB5	Beam Power Tube	10E	ЭМН	13.3	0.6	Vertical Deflection Amplifier Horizontal Deflection Amplifier
13GF7	Dual Triode	11A	9QD	13.5	0.45	Vertical Deflection Amplifier  Vertical Deflection Oscillator
13J10	Power Pentode Gated-Beam Discriminator	8B	12BT	13.2	0.45	Pentode Unit as Class A Amplifier Beam Unit as Gated-Beam Discriminator
13Z10	Power Pentode Gated-Beam Discriminator	80	12BT	13.2	0.45	Class A Amplifier
14A4	Medium-Mu Triode	12B	5AC	12.6	0.15	Class A Amplifier
14A5	Beam Pewer Tube	12B	6AA	12.6	0.15	Class A Amplifier

[♦] Industrial Type

	Grid Bias		Screen	Disto	40 81-4-	Trans-	Amelia -	Po	wer	- RCA
Plate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Plate Cur- rent	AC Plate Resist- ance	conduct-	Amplifi- cation Factor	Lead	Out- put	Туре
Voits		Volts	mA	mA	Ohms	Micromhos		Ohms	Watts	
		Fo	or other o	haracter	istics, see	Type 6KL8			•	12KL8
110 200	— 7.5V 180Ω	110 125	4.0 2.2	49 46	13000 28000	8000 8000		2000 4000	2.1 3.8	12L6GT
200	10011					r to Type 60	7GT	1000		12 <b>Q7GT</b>
Max	c. DC Plate Volts c. Peak Cathode i c. Plate Dissipati	nA, 155	itts		Max.	Peak NegPi Grid-No. 2 V Peak Positiv	olts, 150			12 <b>R</b> 5
250	<b>— 2</b> V			0.9	91000	1100	100			12 <b>S</b> 8 <b>G</b> T
		Fo	or other c	haracteri	stics, refe	r to Type 6\$	<b>A</b> 7			12SA7 12SA7 GT
		Fo	r other c	haracteri	stics, refe	r to Type 6S	C7			12SC7
		Fo	ır other c	haracteri	stics, refe	r to Type 6S	F5			12SF5 12SF5 GT
-		Fo	r other c	haracteri	stics, refe	r to Type 6S	F7			12SF7
						to Type 6S				12567
		Fo	r other c	haracteri	stics, refe	to Type 6S	H7			12SH7
		Fo	r other c	haracteri	stics, refe	to Type 6S.	17			<b>12SJ7</b> 12SJ7 GT
		Fo	r other c	haracteri	stics, refer	to Type 6SI	(7			12SK7 12SK7 GT
		Fo	r other c	haracteri	stic <b>s</b> , refer	to Type 6J5	i			12SN7 GT
		For	r other cl	haracteris	stics, refer	to Type 6S(	17			1 <b>25Q7</b> 125Q7 GT
		Foi	r other cl	haracteris	stics, refer	to Type 6SF	27			12SR7 12SR7 GT
250	97			9.5	8500	1900	16			12SW7+
250	Self excited	100	8.5	3.5	1M	450	Grid-No.	1 resistor	= 20000Ω	12SY7+
12.6	0 <b>v</b>			1	1 <b>2</b> 5 <b>0</b> 0	1600	20	_		12U7
			M	lax. DC O	utput mA,5	5				12Z3
	DC Plate Voits, DC Cathode mA				Ma	x. Plate Diss	ipation, 1.	watts		13EM7
Max. Max.	DC Plate Volts, DC Cathode mA	330 50			Ma Ma	x. Peak Posi c. Plate Diss	tive-Pulse f ipation, 10	Plate Volts, watts	1500	13EW/
		F	or other	ratings,	refer to T	pe 6GB5				13GB5
		F	or other	ratings,	refer to T	pe 6GF7	•			13GF7
250	— 8V	250	2.5	35	100000	6500	<del></del>	5000	4.2	13J10
Max. Max.	Supply Volts, 33 Grid-No. 2 Volts	0 s, 110				c. Peak Posi x. DC Cathoo		. 1 Volts,	60	10110
		For otl	her chara	cteristic	s, refer to	Type 6Z10/6	J10		—	13Z10
			other ch	aracteris	tics, refer	to Type 6J5				14A4

RCA Type	Name	Out- line	Terminal Dia- gram	He	ater or ment (F)	Use  Values to right give operating conditions and characteristics for indicated typical use
				Volts	Ampere	 \$
14A7	Remote-Cutoff Pentode	128	87	12.6	0.15	Class A Amplifier
14AF7	Medium-Mu Twin-Triode	12B	8AC	12.6	0.15	Each Unit as Class A Amplifier
14B6	Twin Diode—High-Mu Triode	12B	BW	12.6	0.15	Triode Unit as Class A Amplifier
14B8	Pentagrid Converter	12B	8X	12.6	0.15	Converter
14C5	Beam Power Tube	12 <b>C</b>	6AA	12.6	0.225	Class A Amplifier
14C7	Sharp-Cutoff Pentode	12B	87	12.6	0.15	Class A Amplifier
14E6	Twin Diode—Medium-Mu Triode	128	8W	12.6	0.15	Triode Unit as Class A Amplifier
14E7	Twin Diode—Remote-Cutoff Pentode	12B	8AE	12.6	0.15	Pentode Unit as Class A Amplifier
14F7	High-Mu Twin Triode	12B	BAC	12.6	0.15	Each Unit as Class A Amplifier
14F8	Medium-Mu Twin Triode	12A	8BW	12.6	0.15	Each Unit as Class A Amplifier
14 <b>6</b> T8	Twin Diode Kigh-Mu Triode	6B	9XR	14	0.15	Triode Unit as Class A Amplifier
14H7	Semiremote-Cutoff Pentode	12B	87	12.6	0.15	Class A Amplifier
14J7	Triode-Heptode Converter	12B	88L	12.6	0.15	Converter
14JG8	Twin Diode—High-Mu Triode	68	9KR	14	0.15	Triode Unit as Class A Amplifier
14N7	Medium-Mu Twin Triode	12C	8AC	12.6	0.3	Each Unit as Class A Amplifier
14Q7	Pentagrid Converter	12B	8AL	12.6	0.15	Converter
14R7	Twin Diode-Remote-Cutoff Pentode	12B	8AE	12.6	0.15	Pentode Unit as Class A Amplifier
15	Sharp-Cutoff Pentode	24B	5F	2.0	0.22	Class A Amplifier
15BD11	Buel Triede					Dual Triode Unit as Class A Amplifier
15BD11A	Dual Triode— Sharp-Cutoff Pentode	8B	12DP	14.7	0.45	Pentode Unit as Class A Amplifier
15CW5	Power Pentode	6 <b>G</b>	9CV	15	0.3	Vertical Deflection Amplifier
	High-Mu Triode			<del></del>		Triode Unit as Class A Amplifier
15DQ8	Sharp-Cutoff Pentode	8E	9HX	15	0.3	Pentode Unit as Class A Amplifier
15FM7	Dual Triode	8C	12EJ	14.8	0.45	Vertical Deflection Oscillator and Amplifier
15HB6	Power Pentode	6G	9NW	14.7	0.3	Vertical Deflection Amplifier
15KY8	High-Mu Triode—	11C	9QT	15	0.45	Triode Unit as Oscillator
	Beam Power Tube					Beam Power Unit as Amplifier
15LE8	Twin Pentode	6G	9QZ	15	0.8	Class A Amplifier Triode Unit as Class A Amplifier
16A8	High-Mu Triode— Power Pentode	6 <b>G</b>	9EX	16	0.3	Pentode Unit as Class A Amplifier
16AQ3	Diode	7D	9CB	16.4	0.6	us orass A Ampirici
	High-Mu Triode				_	riode Unit 1 as Class A Amplifier
6BX11	Medium-Mu Triode Sharp-Cutoff Pentode	8B	12CA	16		Triode Unit 2 as Class A Amplifier Pentode Unit as Class A Amplifier
16KA6	Beam Power Tube	39A	12GH	15.8	0.6	Horizontal Deflection Amplifier
17AB10	Power Pentode					Pentode Unit as Class A Amplifier
7AB10/ 17X10	Gated-Beam Discriminator	8C	12BT	16.8	0.45	Beam Unit Gated-Beam Discriminator
17AX4	Half-Wave Rectifier	13D	4CG	16.8	0.45	Television Damper Service
GT						
17AY3	Half-Wave Rectifier	11D	9HP	16.8	0.45	Television Damper Service
17BB14	Beam Pentode	35B	НИЕ	16.8	0.45	Class A Amplifier

	Grid Bias		Screen Grid	Plate	AC Plate	Trans	Amplifi-	Power		— RCA
Piate	or Cathode Resistor	Screen Grid	Cur- rent	Cur- rent	Resist- ance	Trans- conduct- ance	cation Factor	Load	Out- put	Туре
Volts		Volts	mΑ	mΑ	Ohms	Micromhos		Ohms	Watts	
100 250	— 1V — 3V	100 100	4.0 2.6	13.0 9.2	120000 800000	2350 2000		<del></del>		14A7
						r to Type 7A	.F7			14AF7
						r to Type 6S				14B6
		Fo	other cl	haracter	istics, refe	r to Type 6A	8			1488
315	—13V	225	2.2	34.0	80000	3750		8500	5.5	14C5
		Fo	other cl	haracter	istics, refe	r to Type 6S	J7			14C7
		For	other cl	haracter	istics, refe	r to Type 6B	F6			14E6
250	330Ω	100	1.6	7.5	700000	1300				14E7
		For	other ch	naracteri	istics, refe	r to Type 6S	L7GT			14F7
250	500Ω			6.0		3300	48			14F8
250	3V			0.7	72000	1000	72			14GT
	•	For	other ch	naracteri	istics, refe	r to Type 7H	7			14H7
		For	other cl	haracter	istics, refe	r to Type 7J	7			14J7
250	— 2V			2	41000	2200	90			14JG8
•		For	other ch	aracteri		r to Type 6SI				14N7
						to Type 6S				1407
		For	other ch	aracteri	stics, refe	to Type 7R	7			14R7
135	— 1.5V	67.5	0.3	1.85	800000	750				15
200	2000			7 9.2	12400 9400	5500	68	-		150011
200 135	220Ω 100	135	4	17	45000	4400 10400	41			15BD11 <b>15BD11</b>
	100			_						150145
200	1.7	· · · · · ·	or other	ratings,	refer to T	4000	65			15CW5
200	— 1. <i>i</i> — 3.4	220	3	18	150000	10000	03			15DQ8
	- 3.4									
			r other c	haracter	istics, refe	er to Type 6	FM7 			15FM7
	DC Plate Volts, Peak Positive-P		Volts, 23	500	Ma	x. Plate Diss	ipation, 1	0 watts		15HB6
		F	or other	ratings,	refer to T	ype 6KY8				15KY8
		Fo	r other c	haracter	ristics, ref	er to Type 6	LE8			15LE8
100	0			3.5		2500	70			13220
200	16	200	7	35	20000	6400				16 <b>A</b> 8
Max.	Supply Volts, 2 DC Plate mA, 2	50						te Volts, — 600	10	16AQ3
150	150Ω			11	6800	ate Dissipati 6200	42			
	150Ω			7.6	8400	6800	57			- - 16BX11
150	56Ω	125 125	3.8 9.2	12 20	100000 Ins	11300 stantaneous	Plate Knee	characteristic		IODAI
150 125 35								Characteristic		16 <b>KA</b> 6
125	0 <b>v</b>			aracteri	stics, refe	. 10 1366 71	VAO			
125 35			other ch	aracteri 36	stics, refe 30000	8600		3000	2.4	
125 35 145	−6V KV	For 110 , 330	other ch	_	30000	8600 x. Peak Posi	tive Grid I	No. 1 Volts, 60	2.4	17AB10
125 35 145 Ma	−6V −6V ax. Supply Volts ax. Grid No. 2 V	For 110 , 330 olts, 330	other ch	_	30000 Ma	8600 x. Peak Posi Max. Do	tive Grid I Cathode	No. 1 Volts, 60 mA, 13	2.4	17AB10 1 <b>7AB10</b> , <b>17X10</b>
125 35 145 Max. Max.	—6V  ax. Supply Volts ax. Grid No. 2 V  Peak Inverse Plate mA,	For 110 , 330 olts, 330 ate Volts, 4	other ch	_	30000 Ma Max. Pe	8600 IX. Peak Posi Max. Do eak Heater-C	tive Grid I C Cathode athode Vol	No. 1 Volts, 60 mA, 13 ts: { -4000 +300	2.4	17AB10 17AB10, 17X10 17AX4
125 35 145 Max. Max.	—6V  —6V  ax. Supply Volts ax. Grid No. 2 V  Peak Inverse Pl	For 110 , 330 olts, 330 ate Volts, 4 750	other ch 3	36	30000 Ma Max. Pe	8600 x. Peak Posi Max. Do eak Heater-Ca ponent must	tive Grid I C Cathode athode Vol	No. 1 Volts, 60 mA, 13 ts: { -4000 +300	2.4	17AB10 1 <b>7AB10</b> , <b>17X10</b>

RCA Type	Name	Out- line	Termina Dła- gram	He	ater or ment (F)	Use Values to right give operating conditions and character istics for indicated typical us
				Volts	Amperes	_
17BH3 17BH3A	Half-Wave Rectifier	11D	9HP	17	0.6	Television Damper Service
17BQ6GTE	Beam Power Tube	14D	6AM	16.8	0.45	Horizontal Deflection Amplifier
17BR3	Half-Wave Rectifier	78	9CB	16.8	0.45	Television Damper Service
17B\$3	Half-Wave Rectifier	11D	9HP	16.8	0.45	Television Damper Service
17BZ3	Half-Wave Rectifier	8D	12FX	16.8	0.45	Television Damper Service
17CK3	Half-Wave Rectifier	30B	9HP	16.8	0.45	Television Damper Service
17D4	Half-Wave Rectifier	13D	4CG	16.8	0.45	Television Damper Service
17DM4	Half-Wave Rectifier	13 <b>G</b>	4CG	16.8	0.45	Television Damper Service
17DQ6A	Beam Power Tube	20	EAM	16.8	0.45	Horizontal Deflection Amplifie
17DW4A	Half-Wave Rectifier	11D	9HP	16.8	0.45	Television Damper Service
17EW8	High-Mu Twin Triode	6B	9AJ	17.5	0.15	Each Unit as Class A Amplifie
17GJ5	Novar-Beam Power Tube	18A	9QK	16.8	0.45	Horizontal Deflection Amplifie
17GT5	Beam Power Tube	17B	9NZ	16.8	0.45	Horizontal Deflection Amplifie
17H3	Half-Wave Rectifier	6E	9FK	17.5	0.3	Television Damper Service
17HB25	Beam Pentode	35	17HB25	16.8	0.45	Horizontal Deflection Amplific
17JB6	Beam Power Tube	18A	9QL	16.8	0.45	Horizontal Deflection Amplifie
17JG6	Beam Power Tube	17B	<b>90</b> U	16.8	0.6	Horizontal Deflection Amplifie
17JT6	Beam Power Tube	17C	900	16.8	0.45	Horizontal Deflection Amplifie
17KV6	Beam Power Tube	31D	<b>9Q</b> U	16.8	0.6	High-Voltage-Pulse Shunt Regulator
17LD8 M	edium-Mu Triode—Sharp-Cutoff Pentode	10F	9QT	16.8	0.45	Triode Unit as Class A Amplifie Pentode Unit as Class A Amplifier
17X10	Pentode—Beam Power Tube	8C	12BT	16.8	0.45	Beam Power Unit as Class A Amplifier
17Z3/ PY81	Half-Wave Rectifier	7H	9CB	17	0.3	Television Damper Service
18A5	Beam Power Tube	13F	6CK	18.5	0.3	Horizontal Deflection Amplifier
18AJ10	Beam Power Tube Sharp-Cutoff Pentode	8C	12EZ	18	0.315	Beam Unit as Class A Amplifier Pentode Unit as FM Detector
18FW6 1 <b>8FW6A</b>	Remote-Cutoff Pentode	5C	7CC	18.0	0.1	Class A Amplifier
18FX6 1 <b>8FX6A</b>	Pentagrid Converter	50	7CH	18.0	0.1	Converter
18FY6 1 <b>8FY6A</b>	Twin Diode—High-Mu Triode	5C	7BT	18.0	0.1	Triode Unit as Class A Amplifier
18GB5	Beam Power Tube	35B	HNE	18	0.45	Horizontal Deflection Amplifier
8GD6A	Sharp-Cutoff Pentode	5C	7BK	18	0.1	Class A Amplifier
19	High-Mu Twin Power Triode	22 or 13H	6C	2.0F	0.26	Amplifier
19AU4 19AU4 GTA	Half-Wave Rectifier	13 <b>G</b>	4CG	18.9	0.6	Television Damper Service
9BG6G 19BG6 GA	Beam Power Tube	27B	5BT	18.9	0.3	Horizontal Deflection Amplifier

— RCA	wer_	Pov		<b></b> -				Scree		Grid Bias	
Type	Out- put	Load	Amplifi- cation Factor	Trans- induct- ance	Plate ist- c ce	-	P) C	Grid Cur- rent	Screen Grid	or Cathode Resistor	Plate
	Watts	Ohms		cromhos	ms M		1	mА	Volts		Volts
17BH3	-			e 6BH3	er to Ty	ıgs,	ner ra	For ot			
7BQ6GT	1		/6CU6	6BQ6GTB	r to Typ	CS, I	cteri	er char	For other		
17BR3	J +300		Max. Pe		A, 200	Plat	Max. D	00 1	Volts, 550	Inverse Plate	lax. Peak
17BS3	<u>5500</u>	Voits: 1	Cathode		pátion, 6 er to Typ				0	Plate mA, 120	lax. Peak
17BZ3	1500 300	( A	on, 6.5 w athode Vol	e Dissipat	lax. Plat	,80,	101 10		late Volts 1200	eak Inverse P eak Plate mA,	Max. I Max. I
17CK3			3	Type 6CK	refer to	erist	chara	rother	For		
1704	, ,		<b>.</b>	Type 12D	refer to	erist	chara	r other	For		
17DM4					r to Typ	ıgs,	ier ra	For ot			
17DQ6	0 (Abs.)	e Volts, 6000 tts	Pulse Plat ion, 15 wa	c Positive- e Dissipat	Max. Pea Max. Plai				700 140	C Plate Volts, C Cathode mA	Max. I
17DW4				o Type 6D		teris	char	or othe		<u> </u>	Trian, t
17EW8			50 48	1600 800			10	_		- 1.1V - 2.1V	100 200
17GJ5			40		er to Typ	ngs.		For o		<u>— 2.1V</u>	200
17GT5					r to Ty		_	-			
17H3	_		mA, 75 on, 3 wat							ak Inverse P	
17HB2					nax. Flai	7000	Volts	e Plate		eak Plate mA, ax. Peak Posi	
17JB6	atts	oation, 13 W	late Dissi		- A- T				rage Cath	Max. Ave	
17JG6				ype 17JG6	er to Ty	<u>-</u> -			For		
17JT6				<del></del>					701		
	For other ratings, refer to Type 6JT6  For other characteristics, refer to Type 6KV6A										
17KV6					<u> </u>			or othe			
17LD8			21.5	1900	300					<u> — 5V</u>	150
				7100	700		46	4	110	<u> </u>	120
17X10		3000		600	000		36	3	110	6V	145
17Z3/ PY81	500	+220,45		eater-Cath			00	oits, 50	mA, 450	. Peak Invers . Peak Plate	Ma
18 <b>A5</b>		olts 3000 :s	e Plate V oп, 9 wati	( PosPul: e Dissipat	Max. Pea Max. Plai				350 , 90	C Plate Volts, C Cathode mA	Max. ( Max. (
18AJ1	1.45	2500 No. 3 Volts	Grid	5600 2400	000		ž	6.5 3.5	110 100	7V 180Ω	145 150
18FW6				4400	000		11	4.4	100	68Ω	100
18FX6 18FX6	ns nhos	r, 20000 ohm ond., 480 μπ	1 Resisto on Transc	Grid No Convers	000		-	6.2	100	— 1.5V	100
18FY6 <b>18FY6</b>			100	1300	000		(			<u> </u>	100
18GB5			L500	e 6GB5/E	er to Ty	tics,	racte	her cha	For ot		
18GD6				4300	000	<u>_</u>		2	100	150Ω	100
19			Γ	Type 1J6G	refer to	risti	charac	other	For		
19AU4 19AU4 GTA			<u>-</u>	SAU4GTA		•					<del></del> .
19BG60 19BG6 GA	) (Abs.)	Volts, 6600	Pulse Plate on, 20 wat	Positive-	lax. Pea				700 t 110 m/	Plate Volts, Plate Currer	Max. [

RCA Type	Name	Out- line	Terminal Dia- gram		ater or ment (F)	Use Values to right give operating conditions and characteristics for indicated typical use
				Volts	Amperes	-
19CL8A	Medium-Mu Triode— Sharp-Cutoff Tetrode	6B	9FX	18.9	0.15	Triode Unit as Class A Amplifie Tetrode Unit as Class A Amplifie Pentode Unit as
19DE3	Half-Wave Rectifier	9D	12HX	19	0.6	Television Damper Service
19EZ8	High-Mu Triple Triode	6B	9XA	18.9	0.15	Each Unit as Class A Amplifier
19GQ7	Triple Diode	6B	9QM	18.9	0.15	Each Unit as Half-Wave Rectifier
19HR6	Semiremote-Cutoff Pentode	5C	7BK	18.9	0.15	Class A Amplifier
19HS6	Sharp-Cutoff Pentode	5C	78 K	18.4	0.15	Class A Amplifier
19HV8	High-Mu Triode Sharp-Cutoff Pentode	68	9FA	18.9	0.15	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
19J6	Medium-Mu Twin Triode	5C	7BF	18.9	0.15	Each Unit as Class A Amplifier
19JN8	Medium-Mu Triode— Sharp-Cutoff Pentode	6B	9FA	18.9	0.15	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
19KG8	Medium-Mu Triode Sharp-Cutoff Pentode	6B	9LY	18.9	0.15	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
19Q9	Medium-Mu Triode Semiremote-Cutoff Pentode	<b>6</b> B	10H	18.9	0.15	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
19X8	Medium-Mu Triode— Sharp-Cutoff Pentode	6B	9AK	18.4	0.15	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
20	Power Triode		4D	3.3F	0.132	Class A Amplifier
20EQ7	Diode—Remote-Cutoff Pentode	6E	9LQ	20.0	0.1	Pentode Unit as Class A Amplifier
20EZ7	High-Mu Twin Triode	6B	9PG	20	0.1	Each Unit as Class A Amplifier
21EX6	Beam Power Tube	21B	5BT	21.5	0.6	Horizontal Deflection Amplifier
21HB5	Beam Power Tube	15B	12BJ	21	0.45	Horizontal Deflection Amplifier
21HJ5	Beam Power Tube	15C	12FL	21.5	0.6	Horizontal Deflection Amplifier
21,176	Beam Power Tube	15B	12FK	21	0.45	Horizontal Deflection Amplifier
21LG6	Beam Power Tube	16B	12HL	21	0.6	Horizontal Deflection Amplifier
21MY8	High-Mu Triode Beam Power Tube	15D	12DZ	21	0.45	Triode Unit as Class A Amplifier Beam Unit as Class A Amplifier
22	Sharp-Cutoff Tetrode	29K	4K	3.3F	0.132	Screen-Grid RF Amplifier
22BH3 22BH3A	Half-Wave Rectifier	11D	9HP	22.4	0.45	Television Damper Service
22JG6	Beam Power Tube	17B	900	22	0.45	Horizontal Deflection Amplifier
24A	Sharp-Cutoff Tetrode	29K	5E	2.5	1.75	Screen-Grid RF Amplifier
24JE6A	Beam Power Tube	32B	9QL	24	0.6	Horizontal Deflection Amplifier
24LZ6	Beam Power Tube	32C	9QL	24	0.6	Horizontal Deflection Amplifier
25A6 25A6GT	Power Pentode	2B 13D	7S 7S	25.0	0.3	Class A Amplifier
25A7GT	Rectifier—Power Pentode	13D	8F	25.0	0.3	Pentode Unit as Class A Amplifier Half-Wave Rectifier
25AC5 GT	High-Mu Power Triode	13D	6Q	25.0	0.3	Amplifier

	Grid Bias		Screen			_		F	ower	
Piate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Plate Cur- rent	AC Plate Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Load	Out- put	RCA Type
Volts		Voits	mA	mA	Ohms	Micromhos		Ohms	Watts	
125	-1			14	5000	8000	40			100101
125	- 1	125	4	12	200000	6500				19CL8/
	ax. Peak Invers ax. Peak Plate		olts, 5000	)	Ma	Max. Av x. Heater-Ca	erage Plat ithode Volt		-5000	19DE3
		F	or other	charact	eristics, re	fer to Type	6EZ8			19EZ
						to Type 6G				19GQ7
	0V		other ch	aracteri	stics, refer	to Type 6H	R6 50			19HR6
75 150	07	75 75	2.8	8.8	500000	9500				19HS6
100 125	—1V —1V	125	4	0.8 12	54000 200000	1300 6500	70			19HV8
100	50Ω (For the specifi	both units ed conditio	at ins)	8.5	7100	5300	38			1936
125	<u> </u>			13.5	5400	8500	46			10180
125	<b>–</b> 1	125	4	12	200000	7500				19JN8
125 125	1V 1V	125	4	13.5 12	5400 200000	8500 7500	46		=	19KG8
125 125	—1V —1V	125	4	14 12	5000 200000	8000 6500	40	=		19Q9
		For	other ch	aracteri	stics, refe	r to Type 6)	(8			19 <b>X8</b>
135	—22.5V			6.5	6300	525	3.3	6500	0.110	20
		For	other ch	aracteri	stics, refer	to Type 6E	Q7			20EQ7
250	2V			1.2	62500	1600	100			20EZ7
May	DC Blota Sunn	lu Valta 7		r rating	s, refer to		-d 8 or	<u> </u>		21EX6
Max.	DC Plate Supp Peak Positive-	Puise Plate	Volts, 6	6000	M	ax. DC Cath ax. Plate Di	ode ma, 23 ssipation	N 18 watts		21H <b>B5</b>
Max.	DC Plate Suppl Peak Positive-I	Pulse_Plat <u>e</u>	0 Volts, 7	7000	М М	ax. DC Cath ax. Plate Di	ssipation,	24 watts		21HJ5
Max. DC Max. Pea	Plate Supply \ ak Positive Pul:	/olts, 770 se Plate Vo	olts, 6000	)		Max. F	x. DC Cath Plate Dissi	ode mA, 23 pation, 18 v	0 vatts	21,170
	Max. Max. Ave	DC Plate V grage Catho	olts, 900	315		Max.	Plate Dissi	ipation, 28 ulse Plate	Watts	21LG6
250	4V		<u> </u>	2.3	16000	3600	58		7000	
135 45	10 0V	120 125	3 20	56 <b>200</b>	12000 In	9300 stantaneous	Plate Kne	e character	istic	21MY8
135	— 1.5V	67.5	1.3 (Max.)	3.7	325000	500				22
					refer to 1					22BH3 22BH3A
			ther cha	racteris		to Type 22JG	6A			22JG6
250	— 3V	90	(Max.)	4.0	600000	1050				24A
		DC Plate V rage Catho				Max. Peak Max. I	Positive-Pi Plate Dissi	ulse Plate \ pation, 30 \	/olts, 7500 Watts	24JE6A
		For	other ch	aracteri	stics, refer	to Type 311	<b>Z</b> 6			24LZ6
95	15V	<b>9</b> 5	4	20	45000	2000		4500	0.9	25A6 25A6GT
100	—15V	100	4.0	20.5	50000	1800		4500	0.77	25A7
Max.	AC Plate Volts	(RMS), 117		Max. Do	Output m	<b>A,</b> 75	Max.Peak	Plate mA, 4	50	GT
110	+15V (6	irid mA, 7)		15	15200	3800	58		_	25AC5 GT

RCA Type	Name	Out- line	Terminal Dia- gram	Į Fi	leater or lament (F)	Values to right give operating conditions and characteristics for indicated typical use
				Volts	Amperes	•
25AX4 GT	Half-Wave Rectifier	13D	4CG	<b>2</b> 5	0.3	Television Damper Service
2585	Direct-Coupled Power Amplifier	_	60	25.0	0.3	Amplifier
25B6G	Power Pentode	25	78	25.0	0.3	Class A Amplifier
25B8GT	High-Mu Triode—Remote-Cutoff Pentode	13D	8T	25.0	0.15	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
25BK5	Beam Power Tube	6E	9BQ	25	0.3	Class A Amplifier
25BQ6 GT	Beam Power Tube	14D	6AM	<b>2</b> 5.0	0.3	Horizontal Deflection Amplifier
25C6G	Beam Power Tube	25	7AC	25.0	0.3	Class A Amplifier
25CA5	Beam Power Tube	5D	7CV	<b>2</b> 5	0.3	Class A Amplifier
25CD6 GA	Beam Power Tube	21B	5BT	25	0.6	Horizontal Deflection Amplifier
25CK3	Half-Wave Rectifier	30B	9HP	25.2	0.3	Television Damper Service
25CM3	Half-Wave Rectifier	30B	SHP	25	0.6	Television Damper Service
25DN6	Beam Power Tube	21	5BT	25	0.6	Horizontal Deflection Amplifier
25E5/ PL36	Beam Power Tube	14K	8GT	25	0.3	Horizontal Deflection Amplifier
25EC6	Beam Power Tube	21A	5BT	25.0	0.6	Horizontal Deflection Amplifier
25F5A	Beam Power Tube	5D	7CV	25	0.15	Class A Amplifier
25HX5	Beam Power Tube	10F	9SB	25	0.3	Vertical Deflection Amplifier
25JQ6	Beam Power Tube with Integral Diode	6 <b>G</b>	9RA	25.2	0.3	Vertical Deflection Amplifier
25L6	Beam Power Tube	2B	7AC	25.0	0.3	Amplifier
25L6GT <b>25L6GT/</b> <b>25W6GT</b>	Beam Power Tube	13D	7AC	25.0	0.3	Amplifier
25N6G	Direct-Caupled Power Amplifier	_	7W	25.0	0.3	Class A Amplifier
25W4GT	Half-Wave Rectifier	13D	4CG	25.0	0.3	Television Damper Service
25W6GT	Beam Power Tube	13D	7AC	25	0.3	Class A Amplifier
25Y5	Rectifier-Doubler	22 or 13H	6E	<b>2</b> 5.0	0.3	Half-Wave Rectifier
25Z5	Rectifier-Doubler	22 or 13H	6E	25.0	0.3	Rectifier-Doubler
2576	B	2B	7Q	25.0	0.3	Voltage Doubler
25Z6GT	Rectifier-Doubler	13D	70	25.0 25.0	0.3 0.3	Half-Wave Rectifier
26	Medium-Mu Triode	26	4D	1.5F	1.05	Class A Amplifier
26A6 +	Remote-Cutoff Pentode	5C	7BK	<b>2</b> 6.5	0.07	Class A Amplifier
26A7GT+	Twin Power Pentode	13G	8BU	26.5	0.6	Class A Amplifier
26C6+	Twin Diode—Medium-Mu Triode	5C	7BT	26.5	0.07	Triode Unit as Class A Amplifier
2606+	Pentagrid Converter	5C	7CH	26.5	0.07	Converter
26LW6	Beam Power Tube	29N	8NC	26	0,6	Horizontal Deflection Amplifier

[♦] Industrial Type

	Grid Bias		Screen	Dieta	AC Plate	Trans	Amnlif	P1	DWET	- RCA
Plate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Plate Cur- rent	Resist- ance	Trans- conduct- ance	Amplifi- cation Factor		Out- put	Тур
Valts		Velts	mA	mA	Ohms	Micromhos		Ohms	Watts	
		For	other cl	naracteri	stics, refe	r to Type 6A	X4GTB		<del>-'</del>	25AX4 GT
		For	other ch	aracteris	tics, refer	to Type 25N	6G			2585
200	—23V	135	1.8	62.0	18000	5000		2500	7.1	25B6G
100	<u> </u>			0.6	75000	1500	112			_25B8G
100		100	2.0	7.6	185000	2000				
			other ch			to Type 6BI				25BK5
Max. Max.	DC Plate Volts DC Cathode mA	, 600 l, 112.5		Abso Max	ilute Max. . Plate Dis:	Peak Positiv sipation, 11	e-Pulse Pl Watts	ate Volts, 6	000 (Abs.)	25BQ6 GT
		For	other ch	aracteri	stics, refer	to Type 6Y	6G			25060
110 125	4V 4,5V	110 125	3.5 4	32 37	16000 15000	8100 9200		3500 4500	1.1 1.5	25CA5
	DC Plate Voits					itive-Plus Pl	ate Vois.			25CD6
Max.	DC Plate mA, 2	200		Max	. Plate Dis	sipation, 20	Watts			GA
		<del></del>				to Type 6C				25CK3
						r to Type 60				25CM3
				aracteris	itics, reter	to Type 6DI				25DN(
Max. Max.	DC Plate Supply Peak Positive P	/ Volts, 55 Juise Plate	0 Volts, 7	000		Max. DO Max. Plate	C Cathode Dissipati	mA, 200 on, 10 watts	;	25E5/ PL36
Max.	DC Plate Volts DC Cathode mA	, 700				Peak Positi Plate Dissi	ve-Pulse F	Plate Volts,		25EC6
110	7.5V	110	3.8	43	13000	6400		2500	1.5	25F5/
100 40	8.2√ 0V	100 100	7 19	100 240	5000	14000 stantaneous	Plate Kne	e character	istic	25HX5
-10						fer to Type	-			25JQ6
110	7.5V	110	4	49	13000	9000		2000	2.1	25L6
200	<u> </u>	110	2	50	30000	• 9500		3000	4.3	25L6G
		For	other cha	aracteris	tics, refer	to Type 50L(	GT .			25L6G1 25W6G
Outp	out Triode: Plate de: Plate Volts,	Volts, 18	); Plate	mA, 46; A-F Sign	Load, 4000	ohms Peak), 29.7:	Plate mA.	5.8	3.8	25N60
Max	. Peak Inverse F	late Volts				Peak Heater-		olts. / —500	(Abs.)	0511140
Max. Max	, Peak Plate mA , DC Plate mA,	, 750 125				mponent mu		1 + 200		25W4G
225	-30			22	1600	3800	6.2			25W6G
			Max.	DC Outp	ut mA per	Plate, 75				25Y5
			For other	er rating	s, refer to	Type 25Z6				2575
Max	. AC Volts per F . DC Output mA	Plate (RMS	), 117	Min. Way	. Total Effe	ctive Plate- ; Full-Wave,	Supply Imp	pedance: Ha	lf-	25Z6
Max	. AC Volts per F . DC Output mA	Plate (RMS	), 235 75	Min	. Total Effe	ct. Supply I O volts, 40 c	mped. per	Plate: at 1.	17 voits	25Z6G
180	—14.5V		,,,,	6.2	7300	1150	8.3			26
250	125Ω	100	4.0	10.5	1M	4000				26A6
<b>26</b> .5	4.5V	26.5	1.9	20	(each)   unit	5700		1500	180mW	26A7GT
250	9V			9.5	8300	1900	16			26C6
250	Self excited	100	7.8	3.0	1M	475	Grid-No.	1 resistor =	= <b>20000</b> Ω	26D6
	Peak Positive F		Volts, 7	500		Max. Do	Cathode	mA, 400 on, 40 watts		26LW6
max.	Peak Cathode n	A, 1400				max. Fiate	DISSIDATIO	JII, 40 Walls		

RCA Type	Mame	Out- line	Terminal Dia- gram		Heater or iament (F)	Use Values to right give opera- ing conditions and characte istics for indicated typical us
				Volts	Amperes	<del></del>
27	Low-Mu Triode	22 or 13H	5A	2.5	1.75	Class A Amplifier
29KQ6/ PL521	Beam Power Tube	35A	9RJ	29	0.3	Horizontal Deflection Amplifier
30	Medium-Mu Triode	22 or 13H	4D	2.0F	0.06	Amplifier
30JZ6	Beam Power Tube	39A	1260	30	0.3	Horizontal Deflection Amplifier
30AG11	Twin Diode—Twin-Triode	8A	12DA	30	0.15	Each Trìode as Class A Amplifier
<b>30M</b> B6	Beam Power Tube	16H	12FY	30	0.45	Horizontal Deflection Amplifier
31	Power Triode	22 or 13H	40	2.0F	0.13	Class A Amplifier
31AL10	Dual Medium-Mu Triode Beam Power Tube	8C	12HR	31.5	0.315	Triode No. 1 as Class A Amplifier Triode No. 2 as Class A Amplifier Beam Unit as Class A Amplifier
31JS6A	Beam Power Tube	168	12FY	31.5	0.45	Horizontal Deflection Amplifier
32	Sharp-Cutoff Tetrode	29K	4K	2.0F	0.06	Class A Amplifier
32ET5A	Power Pentode	5D	7C <b>V</b>	32.0	0.1	Class A Amplifier
32HQ7	Damper Diode Beam Power Tube	15A	12HT	32.6	0.315	Diode Unit as Television Damper Service
	BEAM FUNCI TUDE					Beam Unit as Horizontal Deflection Amplifier
32L7GT	Rectifier-Beam Power Tube	14A	8Z	32.5	0.3	Class A Amplifier
				JE.J		Half-Wave Rectifier
33	Power Pentode	25	5K	2.0F	0.26	Class A Amplifier
<b>336</b> T7	Damper Diode	15A	12FC	33.6	0.45	Diode Unit as Television Damper Service
	Beam Power Tube				0.43	Beam Unit as Horizontal Deflection Amplifier
33GY7	Diode—Beam Power Tube	15A	12FN	33.6	0.45	Diode Unit as Television Damper Service Beam Power Unit as
						Horizontal Deflection Amplifier
33,146	Beam Power Tube	15B	12FK	33	0.3	Horizontal Deflection Amplifier
34	Remote-Cutoff Pentode	29K	4M	2.0F	0.06	Screen-Grid RF Amplifier
34CM3	Half-Wave Rectifier	30B	9HP	33.5	0.45	Television Damper Service
34GD5 <b>34GD5A</b>	Beam Power Tube	50	7C <b>V</b>	34.0	0.1	Class A Amplifier
34R3	Half-Wave Rectifier	70	9CB	34	0.15	Television Damper Service
35	Remote-Cutoff Tetrode	29K	5E	2.5	1.75	Screen-Grid RF Amplifier
35A5	Beam Power Tube	12C	6AA	35.0	0.15	Single-Tube Class A Amplifier
35B5	Beam Power Tube	5D	7BZ	35.0	0.15	Class A Amplifier
35DZ8	High-Mu Triode—Power Pentode	6H	9JE	35.0	0.15	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifier
35EH5	Power Pentode	5D	7CV	35	0.15	Class A Amplifier
35GL6	Beam Power Tube	5D	7FZ	35.0	0.15	Class A Amplifier
35L6GT	Beam Power Tube	13D	7AC	35	0.15	Class A Amplifier

	Grid Bias or		Screen Grid	Plate	AC Plate	Trans-	Amplifi-	P	ower	- RCA
Plate	Cathode Resistor	Screen Grid	Cur- rent	Cur- rent	Resist- ance	conduct- ance	cation Factor	Load	Out- put	Турс
Volts		Volts	mA	mA	Ohms	Micromhos		Ohms	Watts	
250	<b>—21V</b>			5.2	9250	975	9.0		_	27
Max. Max.	. DC Plate Volts, . Peak Positive P	275 ulse Plate	Volts, 65	00		Max, Plate Max, DC	Dissipation Cathode i	n, 17 watts nA, <b>2</b> 75	I	29KQ6/ PL521
		For	other cha	racteris	tic <b>s,</b> refer	to Type 1H4	G			30
						to Type 6JZ				30JZ6
May	DO Bloto Volto		other cha	racterist	ics, refer	to Type 6AG				30AG11
Max. Max.	DC Plate Volts, Peak Positive P	ulse Plate	Volts, 80	00		Max. Plate Max. DC	Cathode i	1, 38 watts nA, 400		30MB6
180	30V		_	1 <b>2</b> .3	3600	1050	3.8	5700	0.375	31
150	2V			5.4	11000	3900				_
_150 120	—5V —8V	110	<del></del> _	5.5	8500	2350				- 31AL10
40	—8V 0	110 110	3.5 16.5	46 122	11700 Ins	7100 tantaneous	Plate Knee	character	istic	
	175	For ot	her chara	ecteristi		to Type 6JS				31JS6A
180 (Max.)	— 3V	67.5	0.4	1.7	1 M	650	_			32
· · · ·	— 7.5V	110	2.8	30	21500	5500		2800	1.2	32ET5 32ET5A
110						Max. Plate [	Vicalnotion	2.0		
Max.	Peak Inverse Pla		3300		May D	Max. Hate L	nssipation	, J.8 Watts	2200	
Max. Max. Max.	Peak Plate mA, DC Plate Supply	600 Volts, 400	)		Max. Pe	ak Heater-C Max. DC	athode Vol Cathode m	ts, +200, A, 125	-3300	32HQ7
Max. Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu	600 Volts, 400 Ise Plate \	) Volts, 400		Max. Pe	eak Heater-C Max. DC Max. Plate	athode Vol Cathode m	ts, +200, A, 125 , 7 watts		32HQ7
Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu  — 7V  Maximu	Volts, 400 lse Plate \ 90	/olts, 400 2.0	27.0	Max. Pe	Max. DC Max. Plate 4800	athode Vol Cathode m Dissipation	ts, +200, A, 125 , 7 watts 2600	— <b>3300</b>	<b>32HQ7</b> 32L7GT
Max. Max. Max. Max. 90	Peak Plate mA, DC Plate Supply Peak Positive-Pu  7V  Maximu Maximu	Volts, 400 Volts, 400 Ilse Plate V 90 m AC Pla m DC Out	Volts, 400 2.0 te Voltag put Curre	27.0 ent	17000	Max. DC Max. DC Max. Plate 4800 125	athode Vol Cathode m Dissipation	ts, +200, A, 125 , 7 watts 2600 IMS eres	1.0	32L7GT
Max. Max. Max. Max. 90	Peak Plate mA, DC Plate Supply Peak Positive-Pu  7V  Maximu  Maximu  —18V	Volts, 400 lise Plate V 90 m AC Pla m DC Out	Volts, 400 2.0 te Voltag put Curre 5.0	27.0	17000 55000	Max. DC Max. Plate  4800  125  1750	athode Vol Cathode m Dissipation ————————————————————————————————————	ts, +200, IA, 125 I, 7 watts 2600 IMS Ieres 6000		
Max. Max. Max. 90	Peak Plate mA, IDC Plate Supply Peak Positive-Pu 7V Maximu Maximu -18V Peak Inverse Pla Peak Plate mA, 7	Volts, 400 lse Plate V 90 m AC Plam DC Out 180 te Volts, 2750	Volts, 400 2.0 te Voltag put Curre 5.0	27.0 ent	17000 55000	Max. DC Max. Plate  4800  1750  Max. Plate D  Ak Heater-Cake	athode Vol Cathode m Dissipation Volts, R Milliamp Sissipation, athode Vol	ts, +200, A, 125 , 7 watts 2600  MS eres 6000  3.5 watts ts, +200,	1.0	32L7GT 33
Max. Max. Max. 90 180 Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu  7V Maximu Maximu	Volts, 400 lise Plate \( \) 90 m AC Plam DC Out  180 te Volts, 2750 Volts, 400	Volts, 400 2.0 te Voltag put Curre 5.0	27.0 ent	17000 55000 Max. Pe	Max. DC Max. Plate  4800  1750  Max. Plate D  Ak Heater-Cake	athode Vol Cathode m Dissipation Volts, R Milliamp issipation, athode Vol Cathode m	ts, +200, A, 125 , 7 watts 2600  MS eres 6000 3.5 watts ts, +200, A, 140	1.0	32L7GT
Max. Max. Max. Max. 90 180 Max. Max. Max. Max.	Peak Plate mm, DC Plate Supply Peak Positive-Pu — 7V  Maximu Maximu —18V  Peak Inverse Pla Peak Plate mm, DC Plate Supply Peak Positive Pla Peak Inverse Pl	Volts, 400 lse Plate V 90 m AC Pla m DC Out 180 te Volts, 2 750 Volts, 400 ate Volts, late Volts,	Volts, 400 2.0 te Voltag put Curre 5.0 2500	27.0 ent	17000 55000 Max. Pe	AMX. DC  MAX. Plate  4800  1750  Max. Plate below 60  1750  Max. Plate D  Max. DC  Max. DC  Max. Plate D  Max. Plate I  Max. DC  Max. Plate D  Max. Plate Diss	athode Vol Cathode in Dissipation Si Volts, R Milliamp Sissipation, athode Vol Cathode in Dissipation, 3.	ts, +200, A, 125 , 7 watts 2600 EMS eres 6000 3.5 watts ts, +200, A, 140 , 9 watts 8 watts	1.0 1.4 —2500	32L7GT 33
Max. Max. Max. 90 180 Max. Max. Max. Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu — 7V  Maximu — 18V Peak Inverse Pla Peak Plate MA, DC Plate Supply Peak Inverse Pla Peak Inverse Pla Peak Inverse Pla Peak Plate MA,	Volts, 400 lse Plate V 90 m AC Plam DC Out; 180 te Volts, 2750 Volts, 400 ate Volts, late Volts, 810	Volts, 400 2.0 2.0 te Voltag put Curre 5.0 2500 3500 4200	27.0 ent	17000 17000 55000 Max. Pe	MAX. DC MAX. Plate  4800  1750  Max. Plate D  60  1750  Max. Plate D  Max. Plate D  Max. Plate D  K. Plate Diss  C. Peak Heat	athode Vol Cathode in Dissipation  Volts, R Milliamp  issipation, athode Vol Cathode m Dissipation ipation, 3.	ts, +200, A, 125 , 7 watts 2600 EMS eres 6000 3.5 watts ts, +200, A, 140 , 9 watts 8 watts	1.0	3217GT 33 33GT7
Max. Max. Max. 90 180 Max. Max. Max. Max. Max.	Peak Plate mmA, DC Plate Supply Peak Positive-Pu — 7V  Maximu Maximu —18V  Peak Inverse Pla Peak Plate mmA, DC Plate Supply Peak Plate mmA, DC Plate Supply	Volts, 400 lise Plate Volts, 400 m AC Plam DC Outing 180 te Volts, 20 Yolts, 400 ate Volts, 810  Volts, 400 Volts, 400	Volts, 400 2.0 te Voltag put Curre 5.0 5500	27.0 ent	17000  55000  Max. Pe  Max. Max	Max. DC Max. Plate  4800  1750  Max. Plate Dak Heater-Ca Max. Plate Dak Heater-Ca Max. DC Cathod.	athode Vol Cathode m Dissipation Volts, R Milliamp Issipation, athode Vol Cathode m Dissipation, 3. er-Cathode e mA. 155	ts, +200, 1A, 125, 17 watts 2600 1MS eres 6000 3.5 watts ts, +200, A, 140 A, 140 8 watts Volts:  {	1.0 1.4 —2500	32L7GT 33
Max. Max. Max. 90 180 Max. Max. Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu — 7V  Maximu — 18V Peak Inverse Pla Peak Plate MA, DC Plate Supply Peak Inverse Pla Peak Inverse Pla Peak Inverse Pla Peak Plate MA,	Volts, 400 Wolts, 400 Bo AC Plam DC Outp 180 te Volts, 400 Volts, 400 ate Volts, 400	Volts, 4000 2.0 te Voltag put Curre 5.0 5500 4200 Volts, 500	27.0 ent22.0	17000  55000  Max. Pe  May  May  Max  Max	MAX. DC MAX. Plate  4800  1750  Max. Plate D  60  1750  Max. Plate D  Max. Plate D  Max. Plate D  C. Plate Diss  C. Peak Heat	athode vol Cathode m Dissipation  i Volts, R Milliamp  issipation, athode wol Cathode m Dissipation ipation, 3. er-Cathode e mA, 155 pation, 9	ts, +200, 1A, 125, 17 watts 2600 1MS eres 6000 3.5 watts ts, +200, A, 140 A, 140 8 watts Volts:  {	1.0 1.4 —2500	3217GT 33 33GT7 33GY7
Max. Max. Max. 90 180 Max. Max. Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu — 7V  Maximu Maximu —18V Peak Inverse Pla Peak Plate MA, DC Plate Supply Peak Inverse Pla Peak Inverse Pla Peak Inverse Pla Peak Positive Pla DC Plate Supply Peak Positive-Pu — 3V	Volts, 400 Wolts, 400 Bo AC Plam DC Outp 180 te Volts, 400 Volts, 400 ate Volts, 400	Volts, 4000 2.0 te Voltag put Curre 5.0 5500 4200 Volts, 500	27.0 e nt 22.0 20 00 acteristi	17000  55000  Max. Pe  May Max Max Max Cs, refer to	Max. Pide 4800  1750  Max. Plate 1750  Max. Plate 1860  1750  Max. Plate Dak Heater-Camax. DC Max. Plate Dissis. Peak Heater. DC Cathod. Plate Dissis Type 21JV6	athode vol Cathode m Dissipation  i Volts, R Milliamp  issipation, athode wol Cathode m Dissipation ipation, 3. er-Cathode e mA, 155 pation, 9	ts, +200, 1A, 125, 17 watts 2600 1MS eres 6000 3.5 watts ts, +200, A, 140 A, 140 8 watts Volts:  {	1.0 1.4 —2500	321.7GT 33 336T7 33GY7 33JV6
Max. Max. Max. 90 180 Max. Max. Max. Max. Max. Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu Maximu  — 18V Peak Inverse Pla Peak Plate MA, DC Plate Supply Peak Positive Pla Peak Inverse Pla Peak Inverse Pla DC Plate Supply Peak Positive Pla DC Plate Supply Peak Positive-Pu	600 Volts, 400 Sise Plate V 90 m AC Plam DC Outp 180 te Volts, 400 ate Volts, 400 ate Volts, 400 volts, 400 volts, 400 sise Plate For o 67.5	Volts, 400 2.0 te Voltag put Curre 5.0 2500 4200  Volts, 500 ther chara	27.0 e nt	17000  55000  Max. Pe  May  Max  Max  Max  Max  Max	Max. Plate  4800  1750  Max. Plate  4800  1750  Max. Plate D  Max. Plate D  Max. Plate D  Max. Plate D  C. Plate Diss  C. Plate Diss  D. Cathod  Plate Diss  D Type 21JV6	athode vol Cathode m Dissipation Wolts, R Milliamp issipation, athode vol Cathode m Dissipation ipation, 3. er-Cathode e mA, 155 pation, 9 v	ts, +200, 1A, 125, 17 watts 2600 1MS eres 6000 3.5 watts ts, +200, A, 140 A, 140 8 watts Volts:  {	1.0 1.4 —2500	3217GT 33 33GT7 33GY7 33JV6 34
Max. Max. Max. 90 180 Max. Max. Max. Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu Maximu Maximu  -18V Peak Inverse Pla Peak Plate mA, DC Plate Supply Peak Plate mA, DC Plate Supply Peak Positive-Pu  - 3V min.	600 Volts, 400 See Plate V 90 m AC Plam DC Outy 180 te Volts, 400 ate For 0 67.5	voits, 400 2.0 te Voitag put Curre 5.0 2500 3500 4200 Voits, 500 ther char:	27.0 e	17000  55000  Max. Pe  Maa  Maa  Max  Max  Cs, refer tu  1 M	Max. Plate   4800   1750   Max. Plate   4800   1750   Max. Plate Dak Heater-Cs   Max. Plate Dak Heater-Cs   Max. Plate Diss   C. Plate Diss	athode vol Cathode m Dissipation Wolts, R Milliamp issipation, athode vol Cathode m Dissipation ipation, 3. er-Cathode e mA, 155 pation, 9 v	ts, +200, IA, 125 A, 125 B, 7 watts 2600 IMS eres 6000 3.5 watts ts, +200, A, 140 A, 140 B, 9 watts Wolts:  watts	1.0 1.4 -2500 -4200 +200	321.7GT 33 336T7 33GY7 33JV6
Max. Max. 90  180  Max. Max. Max. Max. Max. Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu Maximu  — 18V Peak Inverse Pla Peak Plate mA, DC Plate Supply Peak Positive Pl Peak Positive-Pu  — 3V min.  — 7.5V	600  Volts, 400  90  m AC Plam  DC Out  180  te Volts, 2750  Volts, 400 ate Volts, 400 ate Volts, 400 ate Volts, 400 ate For 0  67.5  For 110	volts, 400 2.0 te Voltag put Curre 5.0 2500 3500 4200 Volts, 500 ther char:	27.0 e nt	17000  55000  Max. Pe  May  Max  Max  Max  Max  Max	Max. DC Max. Plate  4800  1750  1750  Max. Plate D  Max. Plate D  Max. Plate D  C. Plate Diss  DC Cathod. Plate Diss  Type 21JV6  620  to Type 6C	athode Vol Cathode m Dissipation Williamp issipation, issipation Cathode m Dissipation ipation, 3. er-Cathode e mA, 155 pation, 9 v	ts, +200, IA, 125 7 watts 2600 IMS eres 6000 3.5 watts ts, +200, A, 140 9 watts Watts  Watts  2500	1.0 1.4 -2500 -4200 +200	3217GT 33 33GT7 33GY7 33JV6 34 34CM3
Max. Max. Max. Max. Max. Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu — 7V  Maximu Maximu — 18V Peak Inverse Pla Peak Plate Supply Peak Plate Supply Peak Positive Pla — 3V min.  — 7.5V Peak Inverse Pla Peak Positive-Pu Peak Plate MA, Peak Plate MA,	600 Volts, 400 90 m AC Plam DC Outpl 180 te Volts, 400 ate Volts, 400 ate Volts, 400 lise Plate For o 67.5 For	volts, 400 2.0 te Voltag put Curre 5.0 2500 3500 4200 Volts, 500 ther char:	27.0 e	17000  55000  Max. Pe  Maa  Maa  Max  Max  Cs, refer tu  1 M	Max. DC Max. Plate  4800  1750  1750  Max. Plate D  Max. Plate D  Max. Plate D  C. Plate Diss  DC Cathod. Plate Diss  Type 21JV6  620  to Type 6C	athode vol Cathode m Dissipation Wolts, R Milliamp issipation, athode vol Cathode m Dissipation ipation, 3. er-Cathode e mA, 155 pation, 9 v	ts, +200, IA, 125 7 watts 2600 IMS eres 6000 3.5 watts ts, +200, A, 140 9 watts Watts  Watts  2500	1.0 1.4 -2500 -4200 +200	3217GT 33 336T7 33GY7 33JV6 34 34CM3 34GD5
Max. Max. Max. Max. Max. Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu — 7V  Maximu Maximu — 18V Peak Inverse Pla Peak Plate MA, DC Plate Supply Peak Inverse Pla Peak Inverse Pla Peak Positive Pla — 3V min.  — 7.5V Peak Inverse Plate	600 Volts, 400 90 m AC Plam DC Outy 180 te Volts, 400 ate Volts, 4	volts, 400 2.0 te Voltag put Curre 5.0 2500 3500 4200 Volts, 500 ther char:	27.0 e	17000  55000  Max. Pe  Maa  Maa  Max  Max  Cs, refer tu  1 M	Max. DC Max. Plate  4800  1750  1750  Max. Plate D  Max. Plate D  Max. Plate D  C. Plate Diss  DC Cathod. Plate Diss  Type 21JV6  620  to Type 6C	athode Vol Cathode m Dissipation Williamp issipation, issipation Cathode m Dissipation ipation, 3. er-Cathode e mA, 155 pation, 9 v	ts, +200, IA, 125 7 watts 2600 IMS eres 6000 3.5 watts ts, +200, A, 140 9 watts Watts  Watts  2500	1.0 1.4 -2500 -4200 +200	3217GI 33 33GT7 33GY7 33JV6 34 34CM3 34GD5 44GD5A
Max. Max. Max. Max. Max. Max. Max. Max.	Peak Plate MA,  DC Plate Supply Peak Positive-Pu  Maximu  —18V  Peak Inverse Plat Peak Plate MA, DC Plate Supply Peak Positive Plate MA, DC Plate Supply Peak Positive-Pu  — 3V  Maximu  — 7.5V  Peak Inverse Plate MA,  — 3V  Peak Plate MA,  — 3V	600 Volts, 400 Sie Plate V 90 m AC Plam DC Outy 180 te Volts, 400 ate Volts, 410 be Volts, 400 ate Volts, 400 a	volts, 4000 2.0 te Voltag put Curre 5.0 2500 2500 4200 Volts, 500 ther chars 1.0 other ch 3 3 5500	27.0 e	17000  55000  Max. Pe  Max. Pe  Max. Max  Max  Max  Stics, refer tu  1 M  Stics, refer	Max. DC (Max. DC Cathod Dissipation of the Dissipat	athode Vol Cathode m Dissipation Williamp  issipation, a Cathode m Dissipation, 3. er-Cathode e mA, 155 pation, 9 v  M3  Cathode m/	ts, +200, IA, 125 7 watts 2600 IMS eres 6000 3.5 watts ts, +200, A, 140 9 watts Watts  Watts  2500	1.0 1.4 -2500 -4200 +200	33L7GT 33 33GY7 33GY7 33JV6 34 34GM3 34GD5 44GD5A 34R3
Max. Max. Max. Max. Max. Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu  - 7V  Maximu  - 18V  Peak Inverse Pla Peak Plate MA, DC Plate Supply Peak Positive Pla  Peak Inverse Pla Peak Inverse Pla Peak Plate MA,  - 3V min.  - 7.5V  Peak Inverse Plate A Plate MA, - 3V min.	600 Volts, 400 90 m AC Plam DC Outy 180 te Volts, 400 ate Volts, 4	volts, 400 2.0 te Voltag put Curre 5.0 2500 3500 4200 Volts, 500 ther char: 1.0 cother char: 500 2.5 cother char:	27.0 e	17000  55000  Max. Pe  Maa  Maa  Max  Cs, refer tu  1 M  stics, refer  13000	Max. Plate  4800  1750  Max. Plate  1750  Max. Plate Dak Heater-Co  Max. Plate Dak Heater-Co  Max. Plate Diss  C. Plate Diss  C. Plate Diss  D. DC Cathod  Plate Diss  Type 21JV6  620  to Type 6Cl  5700  Max. DC (  1050  Type 35L6  Type 35C5	athode Vol Cathode m Dissipation Williamp  issipation, a Cathode m Dissipation, 3. er-Cathode e mA, 155 pation, 9 v  M3  Cathode m/	ts, +200, IA, 125 7 watts 2600 IMS eres 6000 3.5 watts ts, +200, A, 140 9 watts Watts  Watts  2500	1.0 1.4 -2500 -4200 +200	33L7GT 33 33GY7 33GY7 33JV6 34CM3 34GD5 4GD5A 34R3 35
Max. Max. Max. Max. Max. Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu  - 7V  Maximu  -18V  Peak Inverse Pla Peak Plate mA, DC Plate Supply Peak Positive Pla Peak Inverse Pla Peak Inverse Pla Peak Plate mA, DC Plate Supply Peak Positive-Pu  - 3V min.  - 7.5V  Peak Inverse Plat Peak Plate mA, 4  - 3V min.	600 Volts, 400 90 m AC Plam DC Outy 180 te Volts, 400 ate Volts, 400 for 0 67.5 For 110 te Volts, 450 90 For 0	volts, 400 2.0 te Voltag put Curre 5.0 2500 3500 4200 Volts, 500 ther chars 1.0 cother chars 500 2.5 cother chars	27.0 e	17000  55000  Max. Pe  Maa  Maa  Max  Cs, refer tu  1 M  stics, refer  13000	Max. Plate   4800   1750   4800   1750   4800   1750   4800   1750   4800   1750   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   4800   480	athode Vol Cathode m Dissipation Williamp  issipation, a Cathode m Dissipation, 3. er-Cathode e mA, 155 pation, 9 v  M3  Cathode m/	ts, +200, IA, 125 7 watts 2600 IMS eres 6000 3.5 watts ts, +200, A, 140 9 watts Watts  Watts  2500	1.0 1.4 -2500 -4200 +200	331761 33336177 336177 331976 34 34CM3 34CM3 34GD5 44GD5A 34R3 35 35A5 35A5 35A5
Max. Max. Max. Max. Max. Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu  - 7V  Maximu  -18V  Peak Inverse Pla Peak Plate mA, DC Plate Supply Peak Positive Pla Peak Inverse Pla Peak Inverse Pla Peak Plate mA, DC Plate Supply Peak Positive-Pu  - 3V  min.  - 7.5V  Peak Inverse Plat Peak Plate mA, 4  - 3V  min.	600 Volts, 400 90 m AC Plam DC Out) 180 te Volts, 400 ate Volts, 4	volts, 4000 2.0 te Voltag put Curre 5.0 2500 2500 4200 Volts, 500 ther chars 1.0 other ch 3 3 5500 2.5 other chars ther chars 6 4	27.0 e	17000  55000  Max. Pe  Max. Pe  Max. Max  Max  Cs, refer tu  1 M  stics, refer  13000  ics, refer t	Max. Plate 14800  1750  Max. Plate 1750  Max. Plate Dak Heater-Community Max. Plate Dak Heater-Community Max. Plate Dak Heater-Community Max. Plate Dissipation of Plate Dissipation of Type 6Cl  5700  Max. DC Community Max. DC Co	athode Vol Cathode m Dissipation Wolts, R Williamp Willia	ts, +200, IA, 125 7 watts 2600 IMS eres 6000 3.5 watts ts, +200, A, 140 9 watts Watts  Watts  2500	1.0 1.4 -2500 -4200 +200	33L7GT 33 33GY7 33GY7 33JV6 34CM3 34GD5A 4GD5A 34R3 35 35A5
Max. Max. Max. Max. Max. Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu  - 7V  Maximu  -18V  Peak Inverse Pla Peak Plate mA, DC Plate Supply Peak Positive Pla Peak Inverse Pla Peak Inverse Pla Peak Plate mA, DC Plate Supply Peak Positive-Pu  - 3V  min.  - 7.5V  Peak Inverse Plat Peak Plate mA, 4  - 3V  min.	600 Volts, 400 90 m AC Plam DC Out) 180 te Volts, 400 ate Volts, 400 for 50 For 0 For 0 110 120 120 115 7	Volts, 400  2.0  te Voltag put Curre  5.0  2500  3500  4200  Volts, 500  ther chars  1.0  other ch  3	27.0 e	17000  55000  Max. Pe  Max Max  Max  Max  Stics, refer to 11000  ics, refer t	Max. Plate 1 4800 1750 Max. Plate 2 4800 1750 Max. Plate 3 4800 1750 Max. Plate 1 4800 Max. Plate 1 4800 Max. Plate 1 50 Max. Plate 1 50 Max. Plate 1 50 Max. Plate 1 50 Max. Plate 5 50 Max. Plate 5 50 Max. DC 4 50 Max. DC 6 1050 Ma	athode Vol Cathode m Dissipation Wolts, R Williamp Willia	ts, +200, IA, 125 IA, 125 IA, 125 IA, 125 IA, 126 IA, 126 IA, 126 IA, 140 IA, 150 IA,	1.0  1.4  -2500  -4200 +200  1.4  3  -2.0  1.2	33L7GT 33 33GY7 33GY7 33JV6 34CM3 34GD5 4GD5A 34R3 35 35A5 35B5 35DZ8
Max. Max. Max. Max. Max. Max. Max. Max.	Peak Plate mA, DC Plate Supply Peak Positive-Pu  - 7V  Maximu  -18V  Peak Inverse Pla Peak Plate mA, DC Plate Supply Peak Positive Pla Peak Inverse Pla Peak Inverse Pla Peak Plate mA, DC Plate Supply Peak Positive-Pu  - 3V  min.  - 7.5V  Peak Inverse Plat Peak Plate mA, 4  - 3V  min.	600 Volts, 400 90 m AC Plam DC Out) 180 te Volts, 400 ate Volts, 400 for 50 For 0 For 0 110 120 120 115 7	Volts, 400  2.0  te Voltag put Curre  5.0  2500  3500  4200  Volts, 500  ther chars  1.0  other ch  3  3  500  2.5  other chars  ther chars  6  4  7.2  3  3	27.0 e	Max. Pe  17000  55000  Max. Pe  Maa  Maa  Max  Cs, refer tu  1 M  stics, refer t  1 cs, refer t	Max. Plate   4800   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   1750   175	athode Vol Cathode m Dissipation Wolts, R Williamp Willia	ts, +200, IA, 125 A, 125 B, 7 watts 2600 IMS eres 6000 3.5 watts ts, +200, A, 140 B, 9 watts Watts  2500 A, 150  2500	1.0  1.4  -2500  -4200 +200  1.4  3  -2.0	33L7GT 33 33GY7 33GY7 33JV6 34GD5 4GD5A 34GD5 35G5 35A5 35B5 35DZ8

RCA Type	Name	Out- line		H	eater or iment (F)	Values to right give operat- ing conditions and character- istics for indicated typical use
				Velts	Amperes	_
35Y4	Half-Wave Rectifier Heater Tap for Pilot	12C	5AL Pilot Betw	35.0 een Pins	0.15 1 and 4	With Capacitive-Input Filter
35Z3	Half-Wave Rectifier	12C	4Z	35.0	0.15	With Capacitive-Input Filter
35Z4GT	Half-Wave Rectifier	130	5AA	35.0	0.15	With Capacitive-Input Filter
36	Sharp-Cutoff Tetrode	24B	5E	6.3	0.3	Screen-Grid RF Amplifier
36AM3	Half-Wave Rectifier	5D	5BQ	36.0	0.1	With Capacitive-Input Filter
36AM3A <b>36AM3B</b>	Half-Wave Rectifier	5D	5BQ	36.0	0.1	With Capacitive-Input Filter
37	Medium-Mu Triode	22 of 13H	5A	6.3	0.3	Class A Amplifier
38	Power Pentade	24B	5F	6.3	0.3	Class A Amplifier
39/44	Remote-Cutoff Pentode	24B	5F	6.3	0.3	Class A Amplifier
40	Medium-Mu Triode	26	4D	5.0F	0.25	Class A Amplifier
40KD6	Beam Power Tube	16C	126W	40	0.45	Horizontal Deflection Amplifie
41	Power Pentode	22 01 13H	6B	6.3	0.4	Amplifier
42	Power Pentode	28	6B	6,3	0.7	Amplifier
42EC4A/ PY500	Half-Wave Rectifier	35C	SEC4	42	0.3	Television Damper Service
43	Power Pentode	28	6B	25.0	0.3	Amplifier
45	Power Triode	26	4D	2.5F	1.5	Class A Amplifier
45Z3	Half-Wave Rectifier	5C	5AM	45.0	0.075	Half-Wave Rectifier
45Z5GT	Half-Wave Rectifier Heater Tap for Pilot	13D	6AD Pilot Betwe	45.0 een Pins	0.15 2 and 3	With Capacitive-Input Filter
46	Dual-Grid Power Amplifier	27B	5C	2.5F	1.75	Class A Amplifler
47	Power Pentode	27B	5B	2.5F	1.75	Class A Amplifier
48	Power Tetrode	27B	6A	30.0	0.4	Class A Amplifier
49	Dual-Grid Power Amplifier	26	5C	2.0F	0.12	Class A Amplifier
50	Power Triode	29L	4D	7.5F	1.25	Class A Amplifier
50A5	Beam Power Tube	12C	6AA	50.0	0.15	Class A Amplifier
50B5	Beam Power Tube	<b>5</b> D	7BZ	50	0.15	Class A Amplifier
50C6G	Beam Power Tube	25	7AC	50.0	0.15	Single-Tube Class A Amplifier
50DC4	Half-Wave Rectifier	5D	5BQ	50	0.15	With Capacitive-Input Filter
50FE5	Beam Power Tube	136	SKB	50.0	0.15	Class A Amplifier
50FK5	Power Pentode	5D	7CV	50.0	0.1	Class A Amplifier
<b>50</b> HC6	Power Pentode	5D	7FZ	50	0.15	Class A Amplifier
50JY6	Beam Power Tube	14 <b>L</b>	9MG	50	0.5	Horizontal Deflection Amplifier
50X6	Rectifier-Doubler	12C	70X	50.0	0.15	Rectifier-Doubler
OY6GT	Rectifier-Doubler	130	70	50.0	0.15	Rectifier-Doubler
50Y7GT	Rectifier-Doubler	13D	8AN Pilot Betwe	50.0	0.15	Voltage Doubler
	Heater Tap for Pilot			en rins t	J dilu /	Half-Wave Rectifier
60Z7G	Rectifier-Doubler Heater Tap for Pilot	22	8AN Pilot Betwe	50.0 en Pins 6	0.15 5 and 7	Voltage Doubler Half-Wave Rectifier
53	High-Mu Twin Power Triode	26	7B	2.5	2.0	Amplifier

Plate Volts  Max. DC (100 - 250 - 250 - 250 - 250 - 250 - 250 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 275 - 27	Output mA,  1.5V 3V Voits (RMS Output mA, Plate Voits Output mA, Plate Voits Output mA, -18V -25V -3V -3V	55 90 ), 117 82 (RMS), 120 82  250 90  For	1.7  3.8  1.4  or other cl	7.5 22.0 5.8 0.2 character	efer to Tyr. Total Effes, 15 ohms 550000 550000 Max. f Tube \ Max. f Tube \ 8400 100000 1.0 150000 eristics, refe	ctive Plate- ; at 235 volt 850 1080 Peak Inverse /oltage Drop	Volts, 365 for Plate  Volts, 365 for Plate  9.2  30  6KD6  6GGT	mA, 150, 20	volts	36 36AM3 36AM3 37 38 39/44 40 40KD6 41 42
Max. DC (100 - 250 - 250 - 250 { 180 - 275 - Max. Peak	- 1.5V - 3V Volts (RMS Output mA, Plate Volts Output mA, -18V -25V - 3V min.	For othe	1.7  3.8  1.4  or other cl	maracter atings, r Min volt 1.8 3.2 7.5 22.0 5.8 0.2 character haracter	efer to Tyr. Total Effes, 15 ohms, 550000 550000 Max. F Tube \ Max. F Tube \ 100000 1.0 150000 eristics, refeistics, refeistic	er to Type 35 the 35Z5GT ctive Plate- ctive	Volts, 365 for Plate  Volts, 365 for Plate  9.2  30  6KD6  6GGT	mA, 150, 20	to 117  volts  volts	35Z3 35Z4G1 36 36AM3 36AM3 37 38 39/44 40 40KD6 41 42 42EC4A
100	- 1.5V - 3V Volts (RMS Output mA, Plate Volts Output mA, -18V -25V - 3V min.	55 90 ), 117 82 (RMS), 120 82  250 90  For	1.7  3.8  1.4  or other cl	7.5 22.0 5.8 0.2 character	efer to Tyr. Total Effes, 15 ohms 550000 550000 Max. f Tube \ Max. f Tube \ 8400 100000 1.0 150000 eristics, refe	ne 35Z5GT citive Plate- ; at 235 volt 850 1080 Peak Inverse Poltage Drop Peak Inverse Poltage Drop 1100 1200 1050 200 fer to Type 68	Volts, 365 for Plate  Volts, 365 for Plate  9.2  30  6KD6  6GGT	mA, 150, 20 mA, 150, 16	volts	35Z3 35Z4G1 36 36AM3 36AM3 37 38 39/44 40 40KD6 41 42 42EC4A
100	- 1.5V - 3V Volts (RMS Output mA, Plate Volts Output mA, -18V -25V - 3V min.	100  55 90 1, 117 82 (RMS), 120 82  250 90  For For othe	3.8 1.4 pr other cl	7.5 22.0 5.8 0.2 character	Total Effe, 15 ohms 550000 Max. F Tube \ Max. F Tube \ 100000 1.0 150000 ristics, refeistics, refe	ctive Plate- ; at 235 volt 850 1080 Peak Inverse Poltage Drop 1100 1200 1050 200 fer to Type 6F	volts, 365 for Plate Volts, 365 for Plate 9.2 30 6KD6 6GT	mA, 150, 20 mA, 150, 16	volts	35Z4G 36 36AM3 36AM3 37 38 39/44 40 40KD6 41 42 42EC4A
100	- 1.5V - 3V Volts (RMS Output mA, Plate Volts Output mA, -18V -25V - 3V min.	55 90 90 90 90 90 90 90 90 90 90 90 90 90	3.8 1.4 ———————————————————————————————————	7.5 22.0 5.8 0.2 character	s, 15 ohms 550000 Max. F Tube \( \) Max. F Tube \( \) 8400  100000  1.0  150000  ristics, refe	; at 235 volt 850 1080 Peak Inverse Poltage Drop Peak Inverse Poltage Drop 1100 1200 1050 200 fer to Type 64 r to Type 64	volts, 365 for Plate Volts, 365 for Plate 9.2 30 6KD6 6GT	mA, 150, 20 mA, 150, 16	volts	36 36AM3 36AM3 37 38 39/44 40 40KD6 41 42 42EC4A
250 AC Plate Max. DC Max. AC Max. DC Max. AC Max. BC Max. Peak	- 3V Volts (RMS Output mA, Plate Volts Output mA, -18V -25V - 3V min.	90 90 117 82 (RMS), 120 82 250 90 For	3.8 1.4 ———————————————————————————————————	7.5 22.0 5.8 0.2 character	550000  Max. f Tube \  Max. f Tube \  8400  100000  1.0  150000  ristics, refe  istics, refe	1080 Peak Inverse foltage Drop Peak Inverse foltage Drop Peak Inverse foltage Drop 1100 1200 1050 200 fer to Type 64 r to Type 64	9.2  30 6KD6 6GT	mA, 150, 20 mA, 150, 16	volts	36AM3 36AM3/36AM3 37 38 39/44 40 40KD6 41 42 42EC4A
Max. DC ( Max. AC ( Max. DC ( 250 - 250 - 250 { 180 -  275 - Max. Peak	Output mA, Plate Volts Output mA, -18V -25V - 3V min.	82 (RMS), 120 82	3.8  1.4  or other cl other cl	22.0 5.8 0.2 character haracter	Max. F Tube \ 8400 100000 1.0 150000 eristics, refe	/oltage Drop Peak Inverse /oltage Drop 1100 1200 1050 200 fer to Type 6W r to Type 6W r to Type 6W	9.2  30 6KD6 6GT	mA, 150, 20 mA, 150, 16	volts	36AM3/36AM3/37 38 39/44 40 40KD6 41 42 42EC4A
Max. DC (250 - 250 - 250 { 180 - 275 - Max. Peak	Dutput mA, -18V -25V - 3V } min. }	250 90 ——————————————————————————————————	3.8  1.4  or other cl other cl	22.0 5.8 0.2 character haracter	Max. f Tube \ 8400 100000 1.0 150000 eristics, refe istics, refe	Peak Inverse /oltage Drop 1100 1200 1050 200 fer to Type 6k r to Type 6k	9.2  30 6KD6 6GT	m <b>A, 1</b> 50, 16	volts	36AM3 37 38 39/44 40 40KD6 41 42 42EC4A
250 - 250 { 180 -	-25V 3V }	90 For For Other	1.4  or other of other of other of character	22.0 5.8 0.2 character haracter	100000  1.0  150000 eristics, refeistics, refe	1200 1050 200 fer to Type 6 r to Type 6F	30 6KD6 6GT	10000	2.50	38 39/44 40 40KD6 41 42 42EC4A
250 { 180 - 275 - Max. Peak	— 3V }	90 For For Other	1.4  or other of other of other of character	5.8 0.2 characte haracter	1.0 150000 eristics, refe istics, refe	1050 200 fer to Type 6% r to Type 6% r to Type 6F	6GT	10000	2.50	39/44 40 40KD6 41 42 42EC4A
275 – Max. Peak	min.	For othe	or other other cl other cl	0.2 characte haracter	150000 eristics, refe istics, refe	200 fer to Type or to Type 6K r to Type 6F	6GT			40 40KD6 41 42 42EC4A
275 – Max. Peak	_ 3V	For For	other cl	characte haracter haracter	ristics, refe istics, refe istics, refe	fer to Type 6 r to Type 6 r to Type 6F	6GT			40KD6 41 42 42EC4A
Max, Peak		For For	other cl	haracter haracter	istics, refe	r to Type 6F r to Type 6F	6GT			41 42 42EC4A
Max, Peak		For othe	other cl	haracter	istics, refe	r to Type 6F	6G			42 42EC4A
Max, Peak		For othe	r charac							42EC4A
Max, Peak				teristics	, refer to	Type 6EC4A/	EY500			
Max, Peak		For								1 1300
Max, Peak			other cl	haracter	istics, refe	r to Type 25	<b>A</b> 6			43
·	_56V			36.0	1700	2050	3.5	4600	2.00	45
· · · · · · · · · · · · · · · · · · ·	( Inverse V	olts, 350	N	lax. DC	Output mA	, 65	Max. Peal	Plate mA,	390	4523
		For	other ra	itings, r	efer to Typ	e 35Z5GT				45Z5GT
	_33V			22	2380	2350	5.6	6400	1.25	46
	450Ω	250	6.0	31	60000	2500		7000	2.7	47
125	-20V	100	9.5	56		3900		1500	2.5	48
135 -	-20V			6.0	4175	1125	4.7	11000	0.17	49
450 -	84V		ther obs	55	1800	2100	3.8	4350	4.6	50
						to Type 50L6 to Type 500				50A5
	-13.5V	135	3.5	58	9300	7000		2000	3.6	50B5
	-14V Olts (RMS)	135	2.2	61	18300	7100	= .	2600	6	50C6G
Max. Feak	Inverse Pla	ate Volts, 3	330			Max. Pe	utput mA, ak Plate п	110 1A, 720		50DC4
		For	other cha	aracteris	tics, refer	to Type 6FE	5			50FE5
110	62Ω	115	8.5	32	14000	12800		3000	1.2	50FK5
110	62Ω	115	11.5	42	11000	14600		3000	1.4	50HC6
	late Volts, Positive-Pu	2/5 ulse Plate \	Volts, 77	00		Max. DC Max. Plate	Cathode n Dissipation	nA, 220 i, 13 watts		50JY6
		Fo	or other	ratings,	refer to Ty					50X6
						ype 25Z6GT				50Y6GT
lax. AC Volts lax. DC Outpu lax. AC Volts lax. DC Outpu	ut mA, 65 per Plate	(RMS), 235	Min. volts,	Total Ef 15 ohm	fec. Plate-S s; at 150 v		L per Plate		ms	- 50Y7GT
					utput mA, mA per Pl					- 50Z7G
		For				to Type 6N	7			53

RCA Type	Name	Out- line	Terminal Dia- gram	He	nter or ment (F)	Use Values to right give operating conditions and characteristics for indicated typical us
				Veits	Amperes	-
70L7GT	Rectifier-Beam Power Tube	13F	444	70.0	0.15	Amplifier Unit as Class A Amplifier
702741				,0.0	0.13	Half-Wave Rectifier
75	Twin Diode-High-Mu Triede	248	66	6.3	0.3	Amplifier
78	Remote-Cutoff Pentode	24B	BF	6.3	0.3	Amplifier Mixer
	# 44 MA # AT# =	40				With Capacitive-Input Filter
80	Full-Wave Rectifier	28	40	5.0F	2.0	With Inductive-Input Filter
83+	Full-Wave Mercury- Vapor Rectifier	278	4C	5.0	3.0	With Capacitive-Input Filter With Inductive-Input Filter
84/6Z4	Full-Wave Rectifier	22 er	5D	6.3	0.5	With Capacitive-Input Filter
04/024	LBII-MSAE VECTIVEL	13H	עכ	6.3	0.5	With Inductive-Input Filter
117L7	Rectifier-Beam Power Tube	13F	840	117	0.09	Amplifier Unit as Class A Amplifier Half-Wave Rectifier
GT/ M7GT	KECTHEL-DESK LAMEL 1886	131	440	117	0.03	
117N7	Rectifier-Beam Power Tube	13F	EAV	117	0.09	Amplifier Unit as Class A Amplifier
GT	Rectines-Deam rewel labe				0.05	Half-Wave Rectifier
117P7 <b>GT</b>	Rectifier-Beam Power Tube	13F	<b>BAV</b>	117	0.09	
11723	Half-Wave Rectifier	5D	4CB	117	0.04	With Capacitive-Input Filter
117Z4 GT	Half-Wave Rectifier	29F	5AA	117	0.04	With Capacitive-Input Filter
11776						Voltage Doubler
GT	Rectifier-Daubler	130	70	117	0.075	Half-Wave Rectifier
407A+	Medium-Mu Twin Triode	6A	487A	40 20	0.05 0.1	Class A Amplifier
408A+	Sharp-Cutoff Pentede	5B	7BD	20	0.05	Class A Amplifier
884 +	Gas Triode	22	602	6.3	0.6	Relaxation Oscillator Grid-Controlled Rectifier
955+	Medium-Mu Triade	acora	58C	6.3	0.15	AF and RF Amplifier
959+	Pentode	acern	5BE	1.25F	0.05	Class A Amplifier
991 +	Glew-Discharge Tube	Double Contact Cande- labra	991			Voltage Regulator
1612+	Pentagrid Amplifier	3	71	6.3	0.3	Class A Amplifier
1614+	Beam Power Tube	4	7\$	6.3	0.9	Class A, AB Amplifier
1619+	Beam Power Tube	4	7AW	2.5F	2.0	Class AB, C Amplifier
1620+	Sharp-Cutoff Pentode	3	7R	6.3	0.3	Class A Amplifier
1621+	Power Pentode	28	75	6.3	0.7	Class A Amplifier
1622+	Beam Power Tabe	194	75	6.3	0.9	Class AB, C Amplifier Visual Indicator
1629+	Electron-Ray Tube High-Mu Twin Power-Triode	13H 13D	7AL 8B	6.3	0.15	Power Amplifier
1635* 2076/	Full-Wave Rectifier	17D	5T	5F	2	1 one: Subtine
5R4GB+						

[♦] Industrial type

	Grid Bias ar		Screen Grid	Plate	AC Plate	Trans-	Amelia.	Po	wer	— 'RCJ
Plate	Cathode	Screen Grid	Car- rest	Cur- reut	Resist-	conduct-	Amplifi- cation Factor		Out-	Typ
Veits		Volts	mA	mA	Ohms	Micrombos	;	Ohms	Watts	
110	— 7.5V	110	3.0	40.0	15000	7500		2000	1.8	~~.
Max. Po	Bak Inverse Volts	, 350 Min.	Max Total E	r. DC Out	put mA, 70 e-Supply i	mped., 15 (	Max. Peak	Piate mA, 42	0	– 70L7G
						to Type 65				75
AC Vall	a nor Diaka (DMC					r to Type 6		T.A.1 PW		78
Max. Pe	s per Plate (RMS ak Inverse Volts,	), 350 , 1400		max. real	t mA, 125 k Plate m/	<b>1, 440</b>	tmpe	Total Effect ed. per Plate,	50 ohms	- 88
Max. Pe	s per Piate (RMS ak inverse Volts	), 500 , 1400		Max. DC ( Max. Peal	Output mA k Plate m/	, 125 1, 440	Min.	Value of inp 10 henrie	ut Choke, s	•
Max. AC	Volts per plate Volts per plate	(RMS) 450 (RMS) 500	_		DC Output 225mA DC Output	•	Cond	ienser = 40 oke = 3 hen	μF (max. ries (min.	} 83+
AC Voits	per Plate (RMS)	, 325		DC Output			Ţ	tal Effect. S	upply	
AC Volta	ak Inverse Volts, per Plate (RMS)	. 450		Max. DC (	Plate mA Output mA,	60		d. per Plate, Value of Ing	out	· 84/6Z4
105	ak Inverse Volts, — 5.2V	1250	4	Max. Peak 43	Plate mA	, 180 5300		hoke, 10 hei 4000	0.85	117L7
	Plate Volts (RM				utput mA,		Min.	Total Effect.		GT/
Mam. Pe	ak Inverse Volts	, 350		Max. Peak	Plate mA	, 450	Suppl	y Imped., 15	ohms	M7GT
100	— 6V	100	5	51	16000	7000		3000	1.2	117N7
Max. Per	Plate Volts (RM: ak inverse Volts,	350		Max. DC C Max. Peak	utput mA, Plate mA	, 450		Total Effect. y Impedance,		GT ——
		For othe	er charac	teristics,	refer to 1	ype 117L7/	M7GT			117P7
Max. Pea	k Inverse Volts,				utput mA,			Total Effect.	Plate-	GT
May Dan	h I V-14-	050	N	lax. Peak	Plate mA,	540	Suppl	/ Imped., 20	ohm\$	11723
Max. Pea	k Inverse Volts,	350	N	lax. DC O lax. Peak	utput mA, Plate mA,	540		Total Effect.  / Imped., 30		117Z4 GT
AC Volts DC Outpu	per Plate (RMS), it mA, 60	117	Min Hal	. Total Ei f-Wave, 30	fective Plants of the Plants o	ate-Supply I III-Wave, 15	mpedance ohms	per Plate:		117Z6
AC Volts	per Plate (RMS) it mA per Plate,	, <b>2</b> 35 60	Min volt	. Total ts, 15 ohn	Effect.	Supply im	ped. per hms: at 23	Plate: At 5 volts, 100	117 ohms	GT
150	240Ω			8.2	6350	5500	35	(each un		407A+
120	200Ω	120	2.2	7	340000	5000		_		488A+
	300 max 350 max			300 max (	(peak)	Average Ar	node Curre	nt = 75 mA	(max.)	884+
250	<u>-7</u>			6.3	11400	2200	25			955+
135	3	67.5	0.4	1.7	800000	600	_			959+
48-67				2				_	_	991 +
250	-3	100	6.5	5.3	600000	1100	Grid-No	.3 Bias = -	-3V	1612+
		For othe	r charact	teristics,	refer to T	ype 6L6, 6L	6GC	-		1614*
300	—10	200	4	44	8800				3	1619+
	······					to Type 6J7				1620+
					<del> </del>	p Type 6F60 pe 6L6, 6L				1621 <b>*</b> 1622 <b>*</b>
	···					o Type 6E5	000			1629+
300	0			6.6		*(plate to p	plate)	12000°		1635
					to Type	5R4GB. Hori	zontal	<del>-</del>	2	076/
	ОР	erating pos	SILION PE	dottez biu	s I and 4	in vertical	piane.			R4GB*
		For ot	her chara	acteristics	s, refer to	Type 6AW8	l			1981/  W&A+

RCA Type	Name	Out- line	Terminal Dia- gram	Hea	nter or nent (F)	Use Values to right give opera ing conditions and characte istics for indicated typical u
			•	Volts	Amperes	-
2082/ 12AY7 *	Medium-Mu Twin Triode	6B	9A	12.6 6.3	0.15 0.3	Class A Amplifier
5636+	Sharp-Cutoff Pentode	submin- iature	8DC	6.3	0.15	Class A Amplifier
5639 +	Semiremote-Cutoff Pentode	submin- iature	8DE	6.3	0.45	Class A Amplifier
5642*	Half-Wave Rectifier	submin- iature	5642	1.25F	0.2	Pulsed Rectifier Service
5651WA+	Glow Discharge Tube	5C	5B0			Voltage Reference
5654/ 6AK5W/ 6096 * 5654W *	Sharp-Cutoff Pentode	5B	7BD	6.3	0.175	Class A Amplifier
5663+	Gas-Tetrode	5A	6CE	6.3	0.15	Thyratron
<b>5670 +</b> 5670WA <b>+</b>	Medium-Mu Twin Triode	6A	8C)	6.3	0.35	Class A Amplifier
5672+	Power Pentode	submin- iature	5672	1.25	0.05	Class A Amplifier
5678 *	RF Pentode	submin- iature	5678	1.25	0.05	Class A Amplifier
5686 +	Beam Power Tube	6B	96	6.3	0.35	Class A Amplifier
5687 +	Medium-Mu Twin Triode	6B	9H	12.6 6.3	0.45 0.9	Class A Amplifier
5691 +	High-Mu Twin Triode	13A	8BD	6.3	0.6	Class A Amplifier
5692+	Medium-Mu Twin Triade	13A	8BD	6.3	0.6	Class A Amplifier
5693 +	Sharp-Cutoff Pentode	8N	2A	6.3	0.3	Class A Amplifier
5696A +	Gas Tetrode	5B	7BN	6.3	0.15	Relay Applications
5718+	Medium-Mu Triode	submin- iature	80 K	6.3	0.15	Class A Amplifier
5719◆	High-Mu Triode	submin- iature	8DK	6.3	0.15	Class A Amplifier
<b>5725 •</b> 5725/ 6AS6W •	Sharp-Cutoff Pentode	5B	7CM	6.3	0.175	Class A Amplifier
5726 • 5726 / 6AL5W / 6097 • 5726 / 6AL5W •	Twin Diode	5B	6BT	6.3	0.3	Half-Wave Rectifier
5734 * N	lechano-Electronic Transducer	5734	5734	6.3	0.15	Vibration Measurements*
<b>5749</b> • 5749/ 6BA6W •	Remote-Cutoff Pentode	5C	7BK	6.3	0.3	Class A Amplifier
5750+	Pentagrid Converter	5C	7CH	6.3	0.3	Converter
5751WA+	High-Mu Twin Triode	6B	9A	12.6 6.3	0.15 0.3	Class A Amplifier
5783◆	Glow Discharge Tube	submin- iature	5783			Voltage Reference
5814WA •	Medium-Mu Twin Triode	6B	9A	12.6 6.3	0.15 0.3	Class A Amplifier
5824+	Power Pentode	25	75	25	0.3	Class A Amplifier
5840 <b>*</b> 5840 <b>*</b>	Sharp-Cutoff Pentode	submin- iature	8DE	6.3	0.15	Class A Amplifier

[♦] Industrial type

RCA	rer	Pow	Amnlis.	Trans	AC Plate	Plate	Screen		Grid Bias	
Туре	Out- put	Load	Amplifi- cation Factor	Trans- conduct- ance	Resist- ance	Cur- rent	Grid Cur- rent	Screen Grid	or Cathode Resistor	Plate
;	Watts	Ohms		Micromhos	Ohms	mA	mA	Volts		Voits
2082/ 12AY7+	·		Y7	to Type 12A	ics, refer	racterist	other cha	For o	_	
5636 +		=3V	EC3 =	1950	50000	4	5.8	100	150Ω	100
5639◆				9000	50000	21	4	100	100Ω	150
5642*	rolts	mA = 30 vo	drop at 4	Tube		0.15				8000
5651WA4			1A	to Type 565	tics, refer	racteris	other cha	For		
5654/ 6AK5W/ 6096 • 5654W •			64	to Type 565	tics, refer	aracteris	other ch	For		
5653+						20	2	5	—10 V	500
<b>5670 •</b> 5670WA <b>•</b>		unit)	(each	5500	6400	8.2			240Ω	150
5672+	.065	20000		650		3.25	1.1	67.5	6.5V	67.5
5678+				1100	1M	1.8	0.48	67.5	0	67.5
5686 +	2.7	9000		3100	45000	27	3	250	—12.5V	250
5687 *	ınit)	(each ur	16	5400	3000	12			—12.5V	250
5691+	ınit)	(each ui	70	1600	44000	2.3			2	250
5692+	ınit)	(each ui	20	2200	9100	6.5			<b>—9V</b>	250
5693 +	= 0V)	(Grid-No.3		1650		3	0.83	100	<b>—3V</b>	250
5696A+			)6 	to Type 569	tics, refer	aracteris	other ch	For		
5718+			27	6500	4150	13			180Ω	150
5719◆			70	2300	30500	1.85			$\Omega$ 086	150
<b>5725</b>	= 0V)	(Grid-No.3		3200		5.2	3.5	120	2V	120
5726 • 5726 / 6AL5W / 6097 • 5726 / 6AL5W •			.5	to Type 6Al	tics, refer	aracteris	other cha	For		
5734+		7500		275	7200	1.5			0V	300
<b>5749 •</b> 5749/ 6BA6W •		<u>-                                    </u>	16	to Type 68/	tics, refer	aracteris	other cha		,000 cycles pe	Up to 12
5750+			6	to Type 6B	tics, refer	aracteris	other cha	For		
751WA+	Ē	_	1	to Type 575	tics, refer	aracteris	other ch	For		
5783◆						1.5	_			85
814WA+	5		1A	to Type 581	ics, refer	racteris	other cha	For (		
5824+			6G	to Type 25B	ics, refer	racterist	other cha	For o		
5840				5000			2.4			

RCA Type	Name	Out- line	Terminal Dia- gram	Heater or		Values to right give oper ing conditions and charact istics for indicated typical is	
				Volts	Amperes	•	
5842/ 417A*	Medium-Mu Triode	6A	97	6.3	0.3	Class A Amplifier	
5844 <b>*</b>	Medium-Mu Twin Triode	5C	7BF	6.3	0.3	Class A Amplifier	
5847/ 404A+	Sharp-Cutoff Pentode	6A	9X	6.3	0.3	Class A Amplifier	
5881 *	Beam Power Tube	29M	7AC	6.3	0.9	Class A Amplifier	
5896 *	Twin Diode	submin- jature	BDJ	6.3	0.3	Full-Wave Rectifier	
5899 +	Semiremote-Cutoff Pentode	søbmin- jature	8DE	6.3	0.15	Class A Amplifier	
5902*	Beam Power Pentode	submin- iature	8DE	6.3	0.45	Class A Amplifier	
5915+	Pentagrid Amplifier	5C	7CH	6.3	0.3	Class A Amplifier	
5964 *	Medium-Ma Twin Triode	5C	78 <i>F</i>	6.3	0.45	Class A Amplifier	
6805 • 6005/6AQ5W 6095 • 6005/6AQ5 •	Beam Power Tube	50	7 <b>8</b> Z	6.3	0.45	Class A Amplifier	
6021+	Medium-Mu Twin Triode	submin- iature	8DG	6.3	0.3	Class A Amplifier	
6872+ 6972A+	Medium-Ma Twin Triode	6B	9A	6.3 12.6	0.15 0.3	Class A Amplifier	
6073* 6073/ 0A2*	Glow-Discharge Tube	5D	5B0			Voltage Regulator	
6074+ 6074/ 0B2+	Glow-Discharge Tube	50	5B0			Voltage Regulator	
6080WA+	Low-Ma Twin Triode	36	8BD	6.3	<b>2</b> .5	Voltage Regulator	
6082+	Low-Mu Twin Trisde	36	8BD	26.5	0.6	Voltage Regulator	
6101 + 6101/ 6J6WA +	Medium-Mu Twin Triode	5 <b>C</b>	7BF	6.3	0.45	Class A Amplifier	
6111*	Medium-Mu Twin Triode	submin iature		6.3	0.3	Class A Amplifier	
6112*	High-Mu Twin Triode	submin jature		6.3	0.3	Class A Amplifier	
6136+	Sharp-Cutoff Pentode	5C	78K	6.3	0.3	Class A Amplifier	
6186+ 6186/ 6AG5WA+ 6186W+	Sharp-Cutoff Pentode	50	780	6.3	0.3	Class A Amplifier	
6189+	Medium-Mu Twin Triode	6B	9A	12.6 6.3	0.15 0.3	Class A Amplifier	
6197+	Power Pentode	6E	9B <b>Y</b>	6.3	0.65	Class A Amplifier	
6202+	Twin Diode	50	5BS	6.3	0.6	Full-Wave Rectifier	
6206◆	Semiremate-Cutoff Pentode	submin iature	- BDC	6.3	0.15	Class A Amplifier	
6211+	Medium-Mu Twin Triode	6B	9A	12.6	0.15 0.3	Class A Amplifier	

[•] Industrial type

	Grid Bias or		Screen Grid	Plate	AC Plate	Trans-	Amplifi-	Powe	er	RCA
Plate	Cathode Resistor	Screen Grid	Cur- rent	Cur- rent	Resist- ance	conduct- ance	cation Factor	Load	Out- put	Туре
Volts		Volts	mA	mA	Ohms	Micromhos		Ohms	Watts	
150	60Ω			25	1700	25000	43			5842/ 417 <b>A</b> +
100	470Ω			4.8	7950	3400	27	(each	ınit)	5844 +
160	600Ω* *with 8.5	160 V in series		13		12500				5847/ 494A+
250 350	—14V —18V	250 250	4.3 2.5	75 53	30000 48000	6100 5200	=	2500 4200	6.7 11.3	5881 +
	150 RMS eac	ch plate		DC	Output Cu	rrent = 18	mA			5896+
100	120Ω	100	2.2	7.2	260000	4500				5899+
100	270Ω	100	2.2	30	15000	4200		3000	1	5902◆
67.5	0٧	67.5				2000 1100		4 voltage == - 4 voltage ==	4 volts) 0 volts)	5915+
100	50Ω* * Common to	both units		9.5	6500	6000	39	(each		5964+
		For o	other ch	aracteris	tics, refer	to Type 6A	Q5A			6005 + 6005/ 6AQ5W 6095 + 6005/ 6AQ5 +
100	150Ω			6.5	6500	5400	35			6021 +
250	4V			3	25000	1750	44			6072* 6072A*
		For	other c	haracteri	istics, refe	r to Type O	A2			6073+ 6073/ 0A2+
		For	other c	haracteri	istics, refe	r to Type O	B2			6074 <b>*</b> 6074/ 0B2 <b>*</b>
		For	other cl	naracteri	stics, refe	r to Type 60	)80		6	• AW080
		For	other ch	aracteri	stics, refe	to Type 60	180			6882*
		For	other ch	aracteri	stics, refe	r to Type 6J	6 <b>A</b>			<b>6101 •</b> 6101/ 616WA <b>•</b>
100	220Ω			8.5	4000	5000	20			6111+
150	820Ω			1.75		2500	70			6112*
		For o	ther ch	aracteris	tics, refer	to Type 6A	U6A			6136+
		For	other ch	aracteris	stics, refer	to Type 6A	. <b>G</b> 5		6	6186+ 6186/ AG5WA+ 6186W+
	<del></del>	For o	ther cha	racterist	ics, refer	to Type 12A	U7A			6189+
250	<b>—3V</b>	250	70	30	90000	11000				6197+
325 450	RMS, 4 μF ing RMS, 8 henry	put filter input chok	e	50 (e: 50 (e:	ach plate) ach plate)					6202+
	120Ω	100	2.2	7.2	260000	4500				6206◆
100										

6336A * 6350 *		line	Dia- gram	Heater er Filament (F)		Values to right give opera ing conditions and character istics for indicated typical us	
6350 +				Volts	Amperes	•	
	Low-Mu Twin Triode	37	8B0	6.3	5.0	Class A Amplifier	
6360+	Medium-Mu Twin Triode	6E	9CZ	12.6 6.3	0.3 0.6	Class A Amplifier	
6360A+	Twin Tetrode	66	6360	12.6 6.3	0.41 0.82	Class AB ₁ Power Amplifier	
6386+	Medium-Mu Twin Triode	6A	8CJ	6.3	0.35	Class A Amplifier	
8417*	VHF Beam Power Tube	6E	9 K	12.6	0.375	RF Power Amplifier	
6485+	Sharp-Cutoff Pentode	5C	700	6.3	0.45	Class A Amplifier	
6626/ 0A2WA+	Glow-Discharge Tube	5D	5B0			Voltage Regulator	
6660/ 6BA6+	Remote-Cutoff Pentode	5C	7BK	6.3	0.3	Class A Amplifier	
6662/ 6BJ6+	Remote-Cutoff Pentode	5C	7CM	6.3	0.15	Class A Amplifier	
6663/ 6AL5+	Twig Diode	58	68T	6.3	0.3	Half-Wave Rectifier	
6664/ 6AB4+	High-Mu Trìode	5C	5C E	6.3	0.15	Class A Amplifier	
6676/ 6CB6A+	Sharp-Cutoff Pentode	5C	7CM	6.3	0.3	Class A Amplifier	
6677/ 6CL6+	Power Pentode	6E	9BV	6.3	0.65	Class A Amplifier	
6678/ 6U8A+	Medium-Mu Triode Sharp-Cutoff Pentode	6B	SAE	6.3	0.45	Triode Unit as Class A Amplifier Pentode Unit as Class A Amplifie	
6686+	Power Pentode	6E	SAU	6.3	0.375	Class A Amplifier	
6688A+	Sharp-Cutoff Pentode	6A	SEQ	6.3	0.3	Class A Amplifier	
6887◆	Twin Diode	5A	6BT	6.3	0.2	Half-Wave Rectifier	
6922/ E88CC+	Medium-Mu Twin Triode	6B	9AJ	6.3	0.3	Class A Amplifier	
6977 +	Indicator Triode	submin- iature	6977	1.0F	0.03	Logic Level Indicator	
7027	Beam Power-Tube	19F	8HY	6.3	0.9	Push-Pull Class AB1 Amplifier	
						Push-Pull Class AB1 Amplifier	
7044 *	Medium-Mu Twin Triode	6E	9H	6.3	0.9	Class A Amplifier	
7054+	Power Pentode	6B_	96 K	13.5	0.275	Class A Amplifier	
7055*	Twin Diode	5B 5C	6BT 7CM	13.5	0.155	Half-Wave Rectifier Class A Amplifier	
7056 <del>*</del> 7057 <b>*</b>	Sharp-Cutoff Pentode  Medium-Mu Twin Triode	6B	9AJ	13.5	0.15	Class A Amplifier	
7058 +	High-Mu Twin Triode	6B	SEP	13.5	0.155	Class A Amplifier	
7060+	Medium-Mu Triode	68	9DA	13.5	0.133	Triode Unit as Class A Amplifier	
7061 +	Power Pentode  Beam Power Tube		SEU	13.5	0.21	Pentode Unit as Class A Amplifie  Class A Amplifier	
7167+	Sharp-Cutoff Tetrode	5C	7EW	13.5	0.09	VHF Class A Amplifier	
7258+	Medium-Mu Triode	6B	9DA	13.5	0.21	Triode Unit as Class A Amplifier	
	Sharp-Cutoff Pentode Medium-Mu Twin Triode	5B	9AJ	6.3	0.335	Pentode Unit as Class A Amplifie  Class A Amplifier	
7308+	Beam Deflection Tube		9KS	6.3	0.35	Class A Amplifier	
7360*	DESM DEMECTION (406		349	0.3		Class A Ampiriel	

[♦] Industrial type

RC	wer	Po	nplifi- —	Tranc A	AC Plate	Plate	Screen		Grid Bias	
Тур	Out- put	Load	ation actor	conduct- c	Resist- ance	Cur- rent	Grid Cur- rent	Screen Grid	or Cathode Resistor	Plate
	Watts	Ohms		Micromhos	Ohms	mA	mA	Volts		Valts
6336	unit)	(each	2.7	13500	200				200Ω	190
6350	unit)	(each	18	4600	3900	11			—5V	150
6360 <i>l</i>		100 plate to		3300 -		30	1.2	200	21.5V	300
6386			17	4000	4250	9.6			200Ω	100
_6417				to Type 5763	stics, refer	haracteri	other c	For		
6485				to Type 6AH6	tics, refer	aracteri	other cl	For		
6626 0A2W				to Type OA2	stics, refe	haracteri	r other c	Fo		_
6660 6BA6				to Type 68A6	stics, refer	aracteri	other cl	For		
6662 6BJ6				to Type 68J6	stics, refer	naracteri	other c	For		
6AL5 6663				to Type 6AL5	stics, refer	aracteri	other cl	For		
6664 6AB4		-		to Type 6AB4	tics, refer	aracteri	other ch	For		
6676 6CB6				o Type 6CB6A	tics, refer	aracteris	other ch	For		
6677 6CL6				to Type 6CL6	stics, refer	 naracteri	other cl	For		
6678				to Type 6U8A	stics, refer	aracteri	other ch	For		
6886 6886	1	15000		11000	300000	20	5.3	210	120Ω	210
	Its	= 0 vol	.3 voltage	16500 grid-N		13	3.3	160	630Ω	190
EE SS		voltage :	i 1 ciinniv			13	J.J			
	= +9 volt			giiu-ii	90000	DC Bla		nlata		300 1/1
6887 <b>6922</b>	_ 73 1010			= 10 mA max	te Current			plate	AS (max.) each	100
6887 6922 E88C0	_ 73 1010	(each		giiu-ii		15			680Ω	100
6887 <b>6922</b>	unit)	(each		= 10 mA max		15 585μΑ 5μΑ		 R _E = 1	680Ω 3V	50
6887 6922 E88C0 6977	unit)	(each		= 10 mA max		15 585μΑ 5μΑ 95 □	3.4□	$R_{g} = 1$	680Ω OV —3V —30V	50 450
6887 6922 E88C0	unit)  50† 32† 36†	(each		= 10 mA max		15 585μΑ 5μΑ 95□ 112□ 138□	3.4 □ 7 □ 5.6 □	 R _E = 1	0V -3V -30V 200Ω 180Ω	50 450 400 380
6887 6922 E88C0 6977	unit)  50† 32† 36† 24†	(each 6000 6600 4500 8000	33	12500	te Current	15 585μΑ 5μΑ 95□ 112□ 138□ 138□	3.4 🗆 7 🗆	$R_g = 1$ $350$ $300$	680Ω OV —3V —30V 200Ω 180Ω 220Ω	50 450 400 380 410
6887 6922 E88C0 6977	unit)  50† 32† 36† 24†	(each	33	12500		15 585μΑ 5μΑ 95 □ 112 □ 138 □ 1A, 134 36	3.4 □ 7 □ 5.6 □ Cath. n	R _g = 1 350 300 380	0V -3V -30V 200Ω 180Ω	50 450 400 380
6887 6922 E88C0 6977 7027	unit)  50† 32† 36† 24†	(each 6000 6600 4500 8000	33	12500		15 585μΑ 5μΑ 95□ 112□ 138□ nA, 134 36 acteristi	3.4	R _g = 1  350  300  380  For of	680Ω OV —3V —30V 200Ω 180Ω 220Ω —2V	50 450 400 380 410 120
6887 6922 E88C0 6977 7027 7044 7054	unit)  50† 32† 36† 24†	(each 6000 6600 4500 8000	33	12500	te Current	15 585μΑ 5μΑ 95□ 112□ 138□ nA, 134 36 acteristi	3.4	R _g = 1  350  300  380  For of	680Ω OV —3V —30V 200Ω 180Ω 220Ω	50 450 400 380 410 120
6887 6922 E88C0 6977 7027 7044 7054 7055	unit)  50† 32† 36† 24† unit)	(each 6000 6600 4500 8000	33	12500 ———————————————————————————————————	te Current	15 585μΑ 5μΑ 95 1 112 1 138 1 1A, 134 36 acteristi	3.4	$R_{g} = 1$ $350$ $300$ $380$ —  For of late	680Ω  OV —3V —3V 200Ω 180Ω 220Ω —2V  7 RMS each pla	50 450 400 380 410 120
6887 6922 E88C0 6977 7027 7044 7054 7055 7056	unit)  50† 32† 36† 24† unit)	(each 6000 6600 4500 8000 (each	21	12500	1750 cs, refer to current 9 m	15  585μΑ 5μΑ 95□ 112□ 138□ 1A, 134 36 acteristi DC plate 9.5	3.4	$R_{g} = 1$ $350$ $300$ $380$ —  For of late	680Ω  OV —3V —3V 200Ω 180Ω 220Ω —2V  17 RMS each pla 180Ω	50 450 400 380 410 120
6887 6922 E88C0 6977 7027 7044 7054 7055 7056	unit)  50† 32† 36† 24† unit)	(each 6000 6500 4500 8000 (each	21 54	12500 12500 12500 Type 8077/70 A. 6200 6800 1650 4900	1750 cs, refer to current 9 m 600000 61000 8200	15  585µA  5µA  95□  112□  138□  134  36  acteristi  DC plate  9.5  10  1.25	3.4	R _E = 1 350 300 380 ——— For otate 150	680Ω  OV —3V 200Ω 180Ω 220Ω —2V  17 RMS each pla 180Ω 220Ω —2V 150Ω	50 450 400 380 410 120 1 200 150 250 150
6887 6922 E88C0 6977 7027 7044 7054 7055 7056 7057	unit)  50† 32† 36† 24† unit)	(each 6000 6500 4500 8000 (each	21 54 36 000	12500	1750 cs, refer to current 9 m 600000 5300 61000	15  585μA  5μA  95□  112□  138□  1A, 134  36  acteristi  DC plate  9.5  10  1.25	3.4	$R_{g} = 1$ $350$ $300$ $380$ —  For of late	680Ω  OV —3V —30V 200Ω 180Ω 220Ω —2V  17 RMS each pla 180Ω 220Ω —2V	50 450 400 380 410 120 150 250 150 200
6887 6922 E88C0 6977 7027 7044 7054 7055 7056 7057 7058	unit)  50† 32† 36† 24† unit)  unit)	(each	21 54 36 000	12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 125000 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500	1750 cs, refer to current 9 n 600000 5300 61000 8200 150000	15  585 μ A 5 μ A 95 □ 112 □ 138 □ 138 □ 134 36 acteristi DC plate 9.5 10 1.25 9 15	3.4	R _E = 1 350 300 380 For of	680Ω  OV —3V —3V 200Ω 180Ω 220Ω —2V  17 RMS each pla 180Ω 220Ω —2V  150Ω 82Ω	50 450 400 380 410 120 1 200 150 250 150
6887 6922 E88C0 6977 7027 7044 7054 7055 7056 7057 7058 7060	unit)  50† 32† 36† 24† unit)  unit)	(each	21 54 36 000	12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 1250 125	1750 25, refer to current 9 r 600000 5300 61000 8200 150000 125000	15  585 μA 5 μA 95 □ 112 □ 138 □ 1A, 134 36 acteristi DC plate 9.5 10 1.25 9 15 35.5	3.4   7   7   5.6   Cath. n   ther char   2.8     3.4   9   1.4	R _E = 1 350 300 380 ——————————————————————————————	680Ω  OV —3V —30V 200Ω 180Ω 220Ω —2V  17 RMS each pla 180Ω 220Ω —2V  150Ω 82Ω —10V	50 450 400 380 410 120 1 200 150 250 150 200 200
6887 6922 E88C0 6977 7024 7054 7055 7056 7057 7061 7167	unit)  50† 32† 36† 24† unit)  unit)	(each	33 33 33 33 34 35 36 36 36 36 36 36 36 36 36 36 36 36 36	12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 125000 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500 12500	1750 cs, refer to courrent 9 m 600000 8200 150000 60000 125000 tics, refer to courrent 9 m 600000 60000 60000 60000 focus 150000 focus 1500000 focus 150000 focus 150000 focus 150000 focus 150000 focus 1500000 focus 150000 focus 1500000 focus 150000 focus 150000 focus 1500000 focus 1500000 f	15  585µA 5µA 5µA 95□ 112□ 138□ 43 36 acteristi DC plate 9.5 10 1.25 9 15 35.5 10 gracteris	3.4	R _E = 1 350 300 380 For of ate 150 125 200 80 For	680Ω  OV —3V —30V 200Ω 180Ω 220Ω —2V  17 RMS each pla 180Ω 220Ω —2V  150Ω 82Ω —10V	50 450 400 380 410 120 1 200 150 250 150 200 200

[†] For two tubes at stated plate-to-plate load.

RCA Type	Name	Out- line	Terminal Dia- gram	Heater or Filament (F)		Use Values to right give opering conditions and characteristics for indicated typical u	
			•	Velts	Amperes	-	
7591	Beam Pewer Tube	13D	8KQ	6.3	0.8	Class A Amplifier Push-Pull Class AB1 Amplifier	
7695	Beam Power Tabe	13D	9PX	50	0.15	Class A Amplifier Push-Pull Class AB ₁ Amplifier	
7717/ 6CY5*	Sharp-Cutoff Tetrode	5C	7EW	6.3	0.2	Class A Amplifier	
7724/ 14GT8*	Twin-Diade High-Mu Triode	€B	9KR	14	0.15	Triode Unit as Class A Amplifie	
7788*	Pentode	6B	9NK	6.3	0.34	Class A Amplifier	
7898+	High-Mu Twin Triode	6B	SEP	13.5	0.15	Class A Amplifier	
8058+	Nuvistor, High-Ma Triode	141	12CT	6.3	0.135	Class A Amplifier	
8136+	Sharp-Cutoff Pentode	5C	7CM	6.3	0.3	Class A Amplifier	
8203+	Nuvister, Power Triede	1	12AQ	6.3	0.16	Class A Amplifier	
8233*	Pentade	11A	SPZ	6.3	0.6	Class A Amplifier	
8532 * 8532/ 6J4WA * 8532W *	Hig <b>h-Mu</b> Trìode	5C	7BQ	6.3	0.4	Class A Amplifier	
8627 * 8627 A *	Nuvister, Power Triede	1A2	12CT	6.3	0.15	Class A Amplifier	
8628+	Nuvistor, High-Mu Triade	1	12AQ	6.3	0.1	Class A Amplifier	
8808*	Nuvistor, High-Mu Triode	1A3	8888	6.3	0.34	Class A Amplifier	
8950+	Beam Power Tube	16E	8958	13.0	1.1	Class A Amplifier	
9001+	Detector Amplifier Pentode	5F	7RD	6.3	0.15	Class A Amplifier	
9002+	Medium-Mu Triode	5F	78\$	6.3	0.15	Detector; Amplifier, Oscillator	
9003+	RF Pentade	5F	78P	6.3	0.15	Class A Amplifier	
9005*	UHF Diode	acorn	5BG	3.6	0.165	Half-Wave Rectifier	
9006+	UHF Diede	5F	6BH	6.3	0.15	Half-Wave Rectifier	
EM84/. 6FG6	Electron—Ray Tube	6F	SEA	6.3	0.27	Visual Indicator	

[◆] Industrial type

#### SAFETY PRECAUTIONS

Electron tubes that operate at potentials exceeding several thousand volts may emit X-radiation.

The high voltages associated with these devices result in production of X-radiation which may constitute a health hazard on prolonged exposure at close range unless the tube is adequately shielded. Equipment design must provide for this shielding.

	Grid Bias		Screen			<b>T</b>	4125	Po	wer	- RCA
Plate	or Cathode Resistor	Screen Grid	Grid Cur- rent	Piate Cur- rent	AC Plate Resist- ance	Trans- conduct- ance	Amplifi- cation Factor	Load	Out-	Тур
Velts		Volts	mÅ	mA	Ohms	Micrombos	1	Ohms	Watts	
300	—10V	300	8	60	29000	10200		3000	11	- 7591
450	200Ω	400	11.50	8 <b>2</b> □				9000	28†	7551
130	—11V	130	5	100	7000	11000		1100	4.5	- 7695
140	50Ω	140	9□	21012				1500	10†	7717
		For	other cl	naracteris	stics, refer	to Type 6	CY5			7717/ 6CY5
	<del></del>	For	other ch	aracteris	tics, refer	to Type 14	GT8			7724, 14GT8
135	360Ω	165	5	35		50000	58			7788
250	200Ω			10	10900	5500	60	(eac	h unit)	7898
110	47Ω			10	5600	12400	70	(000		8058
110	4/14	For	other cl			to Type 6				8136
150	560Ω	701	Other Ci	7	5000	6000	30			8203
	3V	125	5.5	50	20000	45000				82334
125	3V	125	5.5		20000	45000				8532
										8532
150	100Ω		_	13.5	4800	11000	52.5			6J4WA
										8532W
110	47Ω			11.5	5400	13000	 70			8627
110	4/12			11.5	3400	13000	70			8627A
120	200Ω			1.5	41000	3100	127			8628
200	68Ω			15	6400	18000	100			8808
175	-21V	110	2.0	120		16000				8950
250	—3V	100	0.7	2.0	1 MΩ min.	1400				9001
250	—7 <b>Y</b>			6.3	11400	2200	25			9002
250	—3V	100	2.7	6.7	700000	1800		_		9003
117 RM	S max.				DC Out	out Current	1.0 mA ma	ax.		9005
270 RM	S				DC Out	out Current	5.0 mA			9006
Triode	Plate Supply N Plate Resistan Grid-Supply Vo Max. Leng	ce, 1 MΩ olts,22	Part of		late mA, 0. when triod	.06	luorescent- riode-Grid F luorescent tor = 0, 1.	Resistance, Target mA,	0.47 MΩ	EM84, 6FG6

† For two tubes at stated plate to plate load.

□ For two tubes.

### SAFETY PRECAUTIONS

Precautions must be exercised during the servicing of equipment employing these devices to assure that the high voltage is adjusted to the recommended value and that any shielding components are restored to their intended positions before the equipment is operated.

Caution: Operation of this tube outside of the maximum values indicated may result in either temporary or permanent changes in the X-radiation characteristics of the tube. Equipment design must be such that these maximum values are not exceeded.

Note: For Safety Precautions that apply to all tubes, refer to page 93.

# Terminal Diagram Designations for Receiving Tubes

T HE following pages contain comprehensive listings of domestic and foreign entertainment and industrial receiving tubes cross-referenced to a particular terminal diagram designation.

The first index gives the terminal diagram designations in numericalalphabetical sequence and lists the tube types having the same diagram.

The second index lists receiving tube types in numerical-alphabeticalnumerical sequence and gives the terminal diagram designation for each type.

These indexes can be used as an initial approach to tube interchangeability for types not listed in the Replacement Guides. Identical terminal diagram designations, however, do not imply interchangeability. Before any interchangeability is attempted, a comparison must be made of all essential data, including maximum ratings, performance characteristics and mechanical characteristics. Many types listed in these indexes are currently in RCA's line and data for them are included in this manual. For those tube types not currently in RCA's line, it may be necessary to consult other data sources.

The pin or terminal connections associated with the terminal diagram designations are given in the chart III. TERMINAL CONNECTIONS, immediately following the indexes.

## I. TERMINAL DIAGRAM DESIGNATION vs. TYPE NUMBER

1AY2	4CG	4D	4R	5AM
1AY2	6AU4GT	6A3	OZ4A	45Z3
1AY2A	6AU4GTA	10	OZ4G	
	6AX4GT	20		5AP
3C	6AX4GTB	26	4 <b>V</b>	1 <b>A</b> 3
1B3GT	6CQ4	30	1 <b>C2</b> 1	DA90
IG3GT/1B3GT	6DA4	31	0A4G	
1G3GTA/1B3GT	6DE4	40		5AY
1J3	6DM4A	45	5A	6D4
1K3/1J3	6GK17	50	27	
1K3A/1J3	6W4GT		37	5B
1N2A	12AX4GT	4F		47
8016	12AX4GTA	11	5AA	
DY30	12AX4GTB	••	35Z4GT	5BC
U41_	12D4	4G	117Z4GT	955
ЯŘ	12DM4	1V	U74	
4AA	12DM4A	A61	U76	5BE
1LE3	17AX4GT	PY81		959
ILLJ	17AX4GTA	PY83	5AB	
441	17D4	PY88	7Y4	5BG
4AJ	17DE4	PY800	724	9005
0A3	17D <b>M</b> 4	V153		
0A3A	17DM4A	¥133	5AC	5B0
003	19AU4	4K	7B4	5651A
0C3A	19AU4GTA	22	14A4	5651WA
0D3	22DE4	32		6073
OD3A	25AX4GT	J2 [,]	5AD	6073/0 <b>A</b> 2
40	25W4GT	414	1LA4	6074
4C		4 <b>M</b>	1LB4	6074/ <b>0B</b> 2
5Z3	10 K	1A4P		6626/0A2WA
80	4CK	1B4P	5AG	0 <b>A</b> 2
83	5823	34	1LH4	0A2WA
				0B2
4CB	4D	4R	5AL	OB2WA
117 <b>Z</b> 3	2A3	0Z4	35 <b>Y</b> 4	0C2

5 <b>BQ</b>	5E	5 <b>Y</b>	6AM	6BW
35W4	35	1E5GP	25CU6	1 <b>DN</b> 5
36AM3 36AM3A	36 15	1N5GT 1P5GT	HD94 HD96	1U5 DAF92
36AM3B	13	DF33	11030	DAI 32
50DC4	5F	Ž14	6AR	6BX
HY90	38		1 <u>L</u> 4	3V4
EDC .	39/44	52	1T4 1U4	DL94
<b>5BS</b> 6X4	5K	1H5GT HD14	DE91	N19
6X4W	1F4	IIDIT	DF904	6C
12X4	33	6A	W17	19
6202	5L	48	6AS	
EZ90 EZ900	5V4G	6AA	6B5	6CC
HZ90	5V4GA	7 <b>A</b> 5		6AR5
U78		7C5	6AU	6CE
U707	5 <b>M</b>	14A5	1\$5 AD17	5663
VSM70	6F5 6F5GT	1405	DAF91	5000
_>> ENY	12F5GT	32A5 50A5		6CK
<b>5BT</b> 6B <b>G</b> 6G	H63	EL22	6AX	6AU5GT
6CD6G		KT81	1LD5	6AV5GA
6CD6GA	<b>5Q</b>	N148	68	6AV5GT 6FW5
6DN6	5X4G 5Y4G	6AB	2 <b>A</b> 5	12AV5GA
6EX6	5Y4GA	6SF5	41	25AV5GA
19BG6G 19BG6GA	5Y4GT	12SF5	42 43	
21EX6	5R	12SF5GT	43	6CN
25CD6GA	1D5GT	CAD	6BA	6BY5GA
25CD6GB	1G4GT	GAD 35Z5GT	3LF4	600
25DN6 25EC6	5S	45Z5GT	6BG	<b>6CO</b> 6012
23500	1H4G		6C4	0012
5C	6B4G	6AE	EC90	6D
46	5T	7 <b>B</b> 5	L77	2585
49	2T4	6AF	M8080 QA2401	
6485	5AS4	1Q5GT	QL77	6E
8136	5AS4A	6414	V741	6AJ8/ECH81 25Y5
5CE	5AU4	6AM 6BQ6GT	enu	2575 25Z5
6AB4	5AW4 5AZ4	6BQ6GTB/6CU6	<b>6BH</b> 9006	2020
6664/6AB4	5R4GB	6CU6	3000	6EC4
EC92	5R4GYB	6DQ6A	6BS	6EC4/EY500
	5U4G	6DQ6B	2050	42EC4A/PY500
<b>50</b> 6Z4	5U4GB 5V3	6GB3A 6GB6	2050A	EY500 PY500
84/6Z4	5V3A/5AU4	6GB7	6BT	11000
01,021	5 <b>W4</b>	6GW6	3AL5	6F
5DA	5W4GT	6GW6/6DQ6B	6AL5	6 <b>C</b> 6
5AR4/GZ34	5Y3G	128Q6GTB/12CU6 → 12CU6	12AL5 5726	6D6 78
GZ32	5Y3GT 5Z4	→ 12000 12DQ6A	6663/6AL5	70
GZ34 GZ37	2076/5R4GB	12DQ6B	6887	6G
R-52	GZ30	12GB3	7055	2A6
<b>Ú</b> 54	RJ2	12GB6 12GB7	D2M9 D63	12 <b>Z</b> 3 75
U70	U50 U52	12GW6/12DQ6B	D152	13
ERF	7	17BQ6GTB	EAA91	6K
<b>5DE</b> 3D <b>G</b> 4	50	17DQ6A	EB91	6Z5
JUGH	6K5GT	17GB3 17GW6/17DQ6B	FAA91 HAA91	6L
5E	5 <b>Y</b>	25BQ6GT	QA2404	1A6
24A	1D5GP	25BQ6GTB/25CU6	XXA-91	106

6M 1B5/25S	7 <b>AC</b> 6W6GT	7 <b>AV</b> 1S4	<b>7BF</b> 5964	<b>7BT</b> 3AV6
100/200	6Y6GA/6Y6G	DL91	ECC91	4AV6
60	7EY6	DLJI	M8081	6AQ6
6AC5GT	12EN6	7AW	T2M05	6AT6
6C5	12L6GT	1619		6AV6
6C5GT	12V6GT		7 <b>BK</b>	6BF6
6J5	12W6GT	7AX	3AU6	12AE6
6J5GT	25C6G	6AE7GT	3BA6	12 <b>AE6A</b>
6L5G	25L6		4AU6	12AJ6
6P5GT_	25L6GT/25W6GT	7AZ	6AH6	12 <b>A</b> T6
12J5GT	25W6GT	6SF7	6AH6WA	12AV6
25AC5GT	35L6GT	12SF7	6AK6	12BF6
884	50C6G 50L6GT		6AU6 6AU6A	12FK6 12F <b>M</b> 6
L63 L63B	7408	7B	6AU6WB	18FY6
LUJD	7581 <b>A</b>	6A6	6BA6/EF93	18FY6A
6R	EL37	6E6	6BD6	2606
2E5	KT-32	53	6HR6	DH77
6AB5/6N5	KT66	7BA	6HS6	EBC90
6E5	KT71	3Q4	12AC6	EBC91
605	0SW3106	3S4	12 <b>AF</b> 6	HBC90
EM35		DL92	12AU6	HBC91
OSW3110	7AF	DL95	12BA6	
Y61	1F7G	N17	12BD6	7BZ
	740	N18	12BL6	5AQ5
6S	7AG		12CX6 12DZ6	6AQ5
6AX5GT	6AD6G 6AF6G	7BB	12EA6	6AQ5A
6X5	DATOG	3A4	12EK6	6BF5
6X5GT	7AH		12EK6/12DZ6/	6D\$5
6ZY5G EZ35	6AE6G	7BC	12EA6	6HG5 6H <b>R</b> 5
EZ33	ONEOU	3 <b>A</b> 5	18GD6A	11DS5
6W	7AJ		19HR6	12AQ5
1F6	7 <b>A</b> 6	7BD	19H\$6	35B5
11.0		3BC5	19 <b>M</b> R9	50B5
6X	7AK	3BC5/3CE5	26A6	6005
1A5GT	1LA6	3CE5	5749	6669/6AQ5A
1C5GT	1LC6	4BC5 6AG5	6660/6BA6	BPM04
1F5G	7AL	6AK5/EF95	7543 EF93	EL90
1G5G	1629	6AN5	EF94	M8245
1J5G	1023	6BC5/6CE5	HF93	N727
1T5GT	7AM	6CE5	HF94	
DL31	1N6G	6RHH2	M8108	7C
		408A	PM04	2A7
7 <b>AA</b>	7AD	5654	W727	6A7 6A7S
1H6G	1LG5	6186	XF94	UM/ S
740	1L <b>N</b> 5	9001		7CC
7AB		9003	7BN	18FW6
1G6GT 1J6G	7AP	DP61 EF95	2D21	18FW6A
1,6GT	3Q5GT DL33	EF96	5696	TOI HON
13001	N16	EF905	5696A	7CH
7AC	1110	PM05	5727	3BE6
5V6GT	7AQ		700	3BY6
6EY6	1LC5	7BF	7BQ	3C\$6
6EZ5		5J6	614	4CS6
6L6	7AT	5MHH3	8532	6BE6
6L6G_	1R5	616	700	6BY6
6L6GB	DK91	6J6A	7 <b>BR</b>	6CS6
6L6GC	X17	6J6WA	6F4	12AD6
6V6	7411	6MHH3	700	12BE6
6V6GT 6V6GTA	<b>7AU</b> 6N6G	1916	7 <b>BS</b>	12EG6
DVOGIA	01106	5844	9002	12GA6

7CH	7CV	7E	7F <b>P</b>	7R
18FX6	12CN5	6F7	6FQ5A	6J7
18FX6A	12005/1205	017	6FY5/EC97	6J7G
26D6	12ED5	7EA	6GK5/6FQ5A	6J7GT
5750	12EH5	6CR6	EC95	6K7
5915	12FX5	12CR6	EC97	6K7G
EH90	17C5	12010	PC95	6K7GT
EK90	17CU5/17C5	7E <b>G</b>	XC95	687
		2BN4	XC97	6S7G
HK90	19FX5 25C5	2BN4A		6U7G
HM04			YC95	6W7G
X77	25CA5	3BN4	7FQ	12J7GT
X107	25EH5	3BN4A	6FV6	
X727	25F5A	6BN4	01 10	12K7GT
	32ET5	6BN4A	7FZ	1620
7CK	32ET5A		35GL6	A863
12U7	34GD5	7EK	50HC6	EF37
	34GD5A	12 K5	50HK6	KTW63
7CM	35C5		JUINU	KTZ63
3BZ6	35EH5	7EN	7 <b>G</b>	W61
3CB6/3CF6	50C5	3DT6	6C7	W63
3CF6	50EH5	3DT6A	007	Z63
3DK6	50FK5	4DT6	7GA	
4BZ6	60FX5	4DT6A	2FS5	7 <b>S</b>
4CB6	HL92	5GX6	2GU5	6DG6GT
4DE6	11202	5HZ6	3FS5	
4DK6	7CY	6DT6	6FS5	6 <b>F6</b>
4EW6	3B4WA	6DT6A	6GU5	6F6G
4GM6	6GZ5		0000	6F6GT
4JH6	0023	6GX6	7GM	6G6G
4LU6	7D	6GY6	2HA5	6K6GT
5EW6	2B7	6GY6/6GX6	2HM5/2HA5	12A6
5G <b>M</b> 6	6B7	6HZ6	2HQ5	25A6
	6B7S		3HM5/3HA5	25A6GT
5JK6	00/3	7EW	3HQ5	25B6G
5JL6	700	2CY5	4H <b>A</b> 5	1613
6AS6	7DC	3CY5	4HA5/PC900	1614
6BH6	1L6	3EA5	4HQ5	1621
6BJ6	705	4CY5	6HA5	1622
6BZ6	7DF	6CY5	6HA5-S	5824
6CB6A/6CF6	3BN6	6EA5	6HK5	5881
6CF6	4BN6	6EV5	6HM5/6HA5	6550
6DC6	6BN6/6KS6	7167	6HQ5	8417
6DE6	6KS6	7717/6 <b>CY</b> 5	EC900	EM840
6DK6	12B <b>N</b> 6		FC3/10	KT-63
6EW6		7F		N63
6GM6	7DK	12A5	PC900	
6JH6	2AF4A/2AF4B	ILIIO	XC900	71
6JK6	2AF4B/2DZ4	7FB	7GW	6L7
12AW6	2DZ4	12EL6	17DQ6B	6L7G
12BZ6	3AF4A	12110	170000	
12DK6	3AF4A/3DZ4	751	7H	1612
5725	3DZ4	7FL	6D7	
6661/6 <b>BH</b> 6	6AF4	2EN5	6Ē7	70
6662/6BJ6	6AF4A		02,	6P7G
6676/6CB6A	6AN4	7 <b>FP</b>	7K	
7056	6DZ4	2ER5	12 <b>A</b> 7	714
EF190	6T4	2FH5		77
	EC94	2FQ5A	7 <b>Q</b>	6B6G
7 <b>CV</b>		2GK5/2FQ5A	6H6	6Q7
4GZ5	7 D Q	3ER5	6H6GT	6Q7G
6AS5	6DL5	3FH5	12H6	6Q7GT
6CA5	6DL5/EL95	3GK5	25Z6	6R7
6CU5	EL95	4GK5	25 <b>Z6GT</b>	6R7G_
6EH5		6ER5	50Y6GT	6R7GT
12C5	7DX	6ES5	117Z6GT	6T7G
12CA5	50X6	6FH5	E <b>B</b> 34	6V7G
4				

			•011 10202111110	TODE MANO
7 <b>V</b>	8B	8C	8ET	8K
12Q7GT	6N7	1E7GT	6CA7/EL34	6K8
DH63	6N7GT	12, 41	6CZ7	6K8G
	6Y7G	8CB	ĔL34	6K8GT
7W	6Z7 <b>G</b>	6S8GT	ELOT	12K8
25N6G	1635	12\$8GT	8EZ	ILMO
LUMBA	1000	120001	3A3	8KB
72	8BD	8CH	3A3/3B2	6FE5
1A7GT	6AS7G	6AL7GT	3A3A/3B2	50FE5
1B7GT	6BL7GT	O/IL/Q1	3A3B	301 L3
1C7G	6BL7GTA	8CJ	3A3C	8KN
1D7G	6BX7GT	5670	3AW3	7355
	6 <b>DN</b> 7	6386	3CZ3	7000
8A	6EA7	5555	3CZ3A	8KQ
6A8	6EM7/6EA7	8CK	55257.	7591
6A8G	6GL7	6AQ7GT	8F	7591A
6A8GT	6SL7GT	ECL180	25A7GT	700211
6 <b>D</b> 8G	6SN7GT		-0 4.	8KS
12A8GT	6SN7GTA	8CN	8FU	5DJ4
PH4	6SN7GTB	1E8	6BD4	0001
X63	10EG7		6BD4A	8LY
	10EM7	8CP	355	8417
8A8	12SL7GT	1AC5	8G	0127
70L7GT	12SN7GT	1AD5	6C8G	8MG
	12SN7GTA		6F8G	50JY6
8AC	12SX7GT	8CT	3.04	00370
7 <b>F</b> 7	13EM7	6BA7	8GB	8MH
7N7	13EM7/15EA7	12BA7	6BL4	3CA3
14AF7	5691		55-1	3CA3A
14F7	5692	ADA	8GC	• • • • • • • • • • • • • • • • • • • •
14N7	6080	1T6	6BK4	8MK
	6080WA	• • •	6BK4A	3CU3A
8AD	6082	8DC	6BK4B	
6SA7GT	6336A	5636	6BK4C/6EL4A	8ML
12S <b>A</b> 7GT	B36	6206	6EL4	6LH6A
	B65			
8AE	ECC32	8DE	8GD	8MQ
7 <b>E</b> 7	ECC35	5639	6CB5	6LJ6
7R <b>7</b>		5840	6CB5A	6LJ6A/6LH6A
9U8A	8BE	5899		,
14E7	12AH/GT	5902	8GH	8MT
14R7			3B2	3CX3
	8BF	80G	907	3DF3
8AJ	7K7	6021	8GT	3DF3A
1D8GT		6111	25E5/PL36	
	8BK	6112	N308	8MU
8AL	6SG7		PL36	2CN3A
7 <b>Q</b> 7	6SH7	80)	8H	3CN3A
8AN	12SG7	58 <b>9</b> 6	6J8G	3CN3B
	12SH7		0,04	
50Y7GT		8DK	8HY	8MX
50Z7G	8BL	5718	7027	3DB3
BAG	7\$7	5719	7027A	3DB3/3CY3
117L7/M7GT	14J7	6814		3DJ3
11/L//W/di		or	8JB	OMV
BAS	8BU	8E	6CK4	8MY 3DA3/3DH3
3A8GT	26A7GT	6B8 6B8 <b>G</b>	8JC	כחתכ /כאתכ
Jiloui				8MZ
BAV	8BW	12C8	6DQ5	3DC3
117N7GT	7F8	8EL	8JP	****
117P7GT	14F8	6AH4GT	6DZ7	8N
			OPE,	6AB7
BAY	8BZ	8EP	8JX	6AC7
6AD7G	7 <b>X</b> 7	KT88	12GC6	6AC7W

8N	8V	9A	9AG	9AQ
6SJ7	7 <b>A</b> 7	6680/12AU7A	12B4A	EF811
6SJ7GT	7AD7	6681/12AX7A	9AJ	EF814
6SJ7Y	7 <b>AG</b> 7	7025 7247	4BC8	LF183 LF184
6SK7 6SK7GT	8V	B152	4BQ7A	XF183
6 <b>SS</b> 7	7AH7	B309	4BQ7A/4BZ7	XF184
12SJ7	7 <b>B7</b>	B329	4B\$8	YF183
12SJ7GT	<u>7C7</u>	B339	4BZ7	YF184
12SK7	7G7	B739	4ES8/XCC189 4KN8/4RHH8	9AU
12 <b>s</b> k7gt 56 <b>9</b> 3	7L7 7V7	B749 B759	4RHH2	6686
KT77	14A7	E81CC	5BK7A	ALV
0SW3111	14C7	E82CC	5BQ7A	<b>9AX</b> 6BC7
	14H7	E83CC	5ES8/YCC189	6BJ7
8N8	EF22	ECC81	6AQ8 6AQ8/ECC85	
26HU5	W81 W143	ECC82 ECC83	6BC8/6BZ8	9BD
8NC	W148	ECC186	6BK7A	6V3A EY81F
26LW6	.,,,,,	ECC801	6BK7B	
_	8W _	ECC802	6BQ7	9BF
8ND	7B6	ECC803	6BQ7/6BZ7/6BS8	11HM7 12BV7
1DG3	7C6 7E6	M8136 M8137	6BS8 6BZ7	12BY7
1DG3A	1486	M8162	6BZ8	12BY7A/12BV7/
8NJ	14E6	PCC18	6DJ8/ECC88	12DQ7
6EN4	AV	QA2406	6DT8	12DQ7
8NL	<b>8X</b> 14B8	QB309	6E\$8/ECC189	12GN7 12GN7A
3DR3		XCC82	6JK8 6KN8/6RHH8	12HG7
3DS3	8Y	9AC	9AQ8/PCC85	12HG7/12GN7A
8NP	6AG4Y	6S4	12DT8	12HL7
6MA6	6AG7	6S4A	17EW8	EL180
00	8Z	040	17EW8/HCC85	9BL
<b>8Q</b> 6AE5GT	32L7GT	<b>9AD</b> 5879	6922/E88CC 7057	7189
6SQ7	9A	3073	7308	9BQ
6SQ7GT	6AU7	9AE	B719	6BK5
6SR7	7 <b>A</b> U7	5EA8	ECC85	12BK5
6ST7	9AU7	5GH8A	ECC88	25BK5
6SZ7 12SQ7	12AE7 12AT7/ECC81	5KD8 5U8	ECC180 ECC189	9BV
12 <b>SQ</b> 7GT	12AT7/ECC01	6AX8	HCC85	6CL6 6197
12SR7	12AT7WB	6EA8	PCC85	6677/6CL6
12SR7GT	12AU7	6GH8	XCC189	•
12SW7	12AU7A/ECC82	6GH8A	YCC189	9BX 6AM4
0BC3 0SW3105	12AV7 12AX7	6GJ8 6HL8	YCL180	
	12AX7A/ECC83	6KD8	9AK	<b>9CA</b> 6AJ8
8R	12AY7	6LM8	5X8	
6 <b>S</b> A7	12AZ7	6MQ8	6X8A	9CB
6SB7Y 12SA7	12AZ7A	6MU8	19X8	6AF3 6AL3
12SY7	12BH7 12BH7A	6U8 6U8A/6KD8	9AQ	6AL3/EY88
OSW3104	12BZ7	9EA8	3EH7	6BR3/6RK19
8\$	12 <b>DW7</b>	9GH8A	3EH7/XF183	6RK19
6SC7	12FV7	9JW8/PCF802	3EJ7	12AF3/12BR3/
12SC7	5751 5814 <b>A</b>	19EA8 6678/6U8A	3EJ7/XF184 4EH7/LF183	12RK19 12BR3
	5814A 5963	7059	4EJ7/LF184	12RK3 12RK19
<b>8T</b> 12B8GT	5965	CXF80	6EH7/EF183	16AQ3
25B8GT	6072	ECF82	6EJ7	16AQ3/XY88
	6189	ECF802	6EJ7/EF184	17BR3
8U 7AQ	6211 6679/12AT7	LCF802 PCF802	EF183 EF184	17B <b>R</b> 3/17K19 17RK19
7 <b>A</b> 8	00/3/12AI/	1 01 002	E1 104	-711140

227	404	ARY	OEN	9FT
<b>9CB</b> 17 <b>Z</b> 3/PY81	9DC 6MG8	9DX 8AW8A	<b>9EU</b> 6GC5	6CH8
20AQ3/LY88	8 <b>A</b> 8	8BA8A	12AB5	00110
30AE3/PY88	9A8	8BH8	6973	9FX
34R3	9A8/PCF80	8CX8	7061	5CL8
EY88	ECF80	8EB8		5CL8A
LY88	LCF80	8GN8	9EX	6CL8
XY88	LZ319 LZ329	8JV8 10GN8	6BM8/ECL82	6CL8A 9CL8
9CF	PCF80	10HF8	8B8 11BM8	19CL8A
9BR7	XCF80	10JA8/10LZ8	16A8/PCL82	1002011
12BR7		10JT8	50BM8/UCL82	9FZ
9CK	9DE	10JY8	ECL82	5KZ8
6CM6	4RHH8	10KR8	LCL82	6CM8
6DW5	6RHH8 ECC89	10LB8	LN119	6KZ8 9K78
•••	L0003	10LW8 10LY8	N369	JIVTO
ODOE (EL OA	9DJ	10L78	PCL82 UCL82	96
6BQ5/EL84 6C <b>W</b> 5	6BW4	11JE8	UCL83	5686
6CW5/EL86	12B <b>W</b> 4	11KV8	00100	
8BQ5	9DP	11LQ8	9FA	96A
8CW5/XL86	6AR8	PCF82	5BR8	6FG6/EM84
10BQ5	6JH8	9DZ	5BR8/5FV8	6HU6/EM87 Em84
10CW5	9DR	5AV8	5FV8	EM87
10CW5/LL86	6BC4	9E	5MB8	Lino
15CW5 15CW5/PL84	0004	5T8	6BR8 6BR8A	96C
EL84	9DS	6AK8/EABC80	6FV8	12J8
EL86	5AS8	6T8	6FV8A	
LL86	6AS8	6T8A	6JN8	96E
M709	9DT	19T8	6MB8	5CQ8 6CQ8
PL84	1RK23	DLO12 EABC80	12EC8	OUGO
XL84	1S2A/DY87	LADGOU	12JN8	9 <b>G</b> F
XL86	3A2_	9EC	19HV8 19JN8/19CL8A	4LJ8
9CY	3A2A	5B8	TAIMO/ TACTOM	5CG8
5AM8	DY87	9ED	9FE	5FG7
6AM8	9DW	6AZ8	5BT8	5GS7
6AM8A	5AT8		3010	5LJ8 6CG8
6HJ8	6AT8	9EF	9FG	6CG8A
9CZ	6AT8A	6CS7 8CS7	3BU8/3GS8	6FG7
6350	9DX	0U3/	3HS8	6GS7
9DA	6AU8	9EG	4BU8	6LJ8_
5AN8	6AU8A	5BE8	4BU8/4GS8	7GS7
6AN8	6AW8	5DH8	4HS8	96K
6AN8A	6AW8A	9EN	4MK8 6BU8	6GK6
10C8	6BA8A 6BH8	6CN7	6HS8	7 <b>KY</b> 6
12CT8	6CX8	8CN7	6MK8	9KX6
7060	6EB8	AFD	6MK8A	9LA6
7258	6GN8	<b>9EP</b> 7058		10GK6 16GK6
9DC	6HF8	7036 7898	9FH	7054
4BL8	6HZ8		12F8	8077/7054
4BL8/XCF80	6JE8	9EQ		PCL800
4KE8	8719 8719	6688A	9FJ	
5JW8 5KE8	6KR8	9ER	6BV8	<b>9GM</b> 6CU8
6BL8	6KV8	6BJ8	arv.	0000
6BL8/ECF80	6LB8	6BN8	9FK 17U2	9GR
6JW8/ECF802	6LF8	8BN8	17H3	6DB5
6KE8	6LQ8	UEG	9FN	12DB5
6LN8	6LY8	<b>9ES</b> 6CM7	6BY8	9 <b>6</b> S
6LN8/LCF80	6MV8 8AU8	8CM7	EF80	12AL8
6LX8/LCF802	UNUU	JUIII/		

9H	9HP	9KR	9LY 10GV8/LCL85	<b>9NZ</b> 6 <b>G</b> T5
5687 7044	17AY3 17AY3A	14JG8 7724/14GT8	11MS8	6GT5A
7044	17BH3	7727717410	18GV8/PCL85	12GT5
9HE	17BS3	9KS	19KG8	12GT5A
6DC8	17BS3A/17DW4/	A 7360	ECL85	17GT5
6DC8/EBF89	17CK3		LCL85	17GT5A
EBF85	17DW4A	9KT	PCL85	7868
EBF89	22BH3	10500	XCL85	9PA
9HF	22BH3A	12FQ8	9LZ	8319
6DE7	25CK3	9KU	6GW8/ECL86	
6DR7	9HR	12FR8	ECL86	9PB
6EW7	12DL8			7905
6FD7	12DV8	9KY	9M	9PG
9RAL1		12FX8	6CA4	20EZ7
10DE7	9HY	12FX8A	EZ4 U70 <del>9</del>	ADI.
10DR7	12 <b>EM</b> 6	9LG	UU12	9PL
10EW7 13DE7	9HX	6CY7	0012	8106
13DE/ 13DR7	6DX8	11CY7	9MB	9PM
13FD7	6DX8/ECL84	11017	6GY8	3JC6
10107	10DX8	91.K		3JC6A
9HG	10DX8/LCL84	7551	9MP	3JD6
12DE8	15DQ8/PCL84	7558	5HG8	3KT6
	ECL84	41 D	5HG8/LCF86	4H <b>M</b> 6 4HT6
9HK	LCL84	9LP	6HG8 6HG8/ECF86	4716 4JC6A
5BW8	9HZ	6CG7 6EV7	7HG8	4JD6
6BW8	12DK7	6FQ7	7HG8/PCF86	4KT6
	12017	6FQ7/6CG7	ECF86	6H <b>M</b> 6
9HL	9JD	6GU7	LCF86	6JC6A
6939	12DY8	8CG7	PCF86	61 <b>D</b> 6
60114		8FQ7	0440	6KT6
9HN	9JE	8FQ7/8CG7	9MQ	9PQ
5CZ5 6CZ5	35DZ8	8GU7	6GM5	8019
6DT5	ALF	12FQ7	9MR	ABULA
6EM5	<b>9)F</b> 5EU8	9LQ	6FA7	ABUL8
8EM5	6EU8	6EQ7		OBV
12DT5	0.00	6KL8	9NH	<b>9PV</b> 6KA8
	916	12EQ7	6GB5	8KA8
9HP	6EH8	12KL8	6GB5/EL500	Olivio
6AY3		20EQ7	13GB5 13GB5/XL500	9PX
6AY3B	9J <u>T</u>	01.0	17BB14	76 <b>9</b> 5
6BA3 6BH3	7199	<b>9LS</b> 6EU7	18GB5/LL500	9PZ
6BH3A	910	OEU/	27GB5/PL500	8233
6BS3	12DS7	9LT	EL500	9QA
6BS3A	12DS7A	6ET7	LL500	4GJ7/XCF801
6CH3		6KU8	PL500	4GX7
6C13/6CH3	9K	8ET7	XL500	5GJ7/LCF801
6CK3	5763	10KU8	9NJ	5GX7
6CL3	6417	9LW	6HU8/ELL80	5HB7
6CL3/6CK3	9KA	3GS8/3BU8	•	6GJ7
6DN3	6EZ8	3GS8	9NK	6GJ7/ECF801 6GX7
6DW4	19EZ8	4GS8	7788	6HB7
6DW4B		4GS8/4BU8	9NW	6HD7
12AY3	9KP		6HA6	8GJ7
12AY3A	6FH8	9LY	6HB6/6HA6	8GJ7/PCF801
12BS3	AVB	6GV8	• • • • •	ECF801
12BS3A/12DW4A 12CL3	9KR CENO	6GV8/ECL85	9NY CDL4/FC00	LCF801
12DW4A	6FM8 14GT8	9GV8 9GV8/XCL85	6DL4/EC88 EC88	PCF801 XCF801
VEHIAV	17410	JUTO/ NULOJ	LUOO	VO1 001

000			1010	1000
<b>9QD</b> 6GF7	<b>9QT</b> 21LR8	9RT 2BJ2	1 <b>2AQ</b> 7586	12CA 6M11
6GF7A	31LR8	2BJ2A	7895	165X11
10GF7			8056	
10GF7A	900	9RU	8203	12CT
13GF7 13GF7 <b>A</b>	6JG6 6JG6A	6 <b>M</b> E8	8393 8628	8058 8627
130177	6JR6	9RX	0020	0027
9QG	6JT6	12CT3	12AS	12DA
6KM8	6JT6A	17CT3	7587	6AG11
90)	6KV6 6KV6A	25CT3	12BF	6AY11
5BC3	12JT6	9SB	6B10	12DG
5BC3A	12JT6A	25HX5	8B10	2AH2
9QK	17JG6 17JG6A	9SG	12BJ	12DM
6GJ5	17JG6A 17JT6	6DK3	6GE5	1 <b>2DM</b> 6AR11
6GJŠA	1 <b>7JT6A</b>		6GF5	8ARII
12GJ5	17KV6A	90	6HB5	8BQ11
12GJ5A 17GJ5	22JG6 22JG6A	1V2 2AV2	12GE5 17GE5	8CB11 11AR11
17GJ5A	22JR6	LNIL	21HB5	11BQ11
	22KV6.\	97	21HB5A	16BQ11
<b>9QL</b> 6JB6	33JR6	5842/417 <b>A</b>	12 <b>BL</b>	
6JB6A	9QY	9X	6AX3	12DP
6JE6	6LC8	5847/404A	6BJ3	6AF11 6AS11
6JE6A	8LC8	3047/4047	12AX3	6BD11
6JF6 6JU6	9QZ	9Y	12BT3 17AX3	15AF11
6KM6	6LE8	1AX2	17 AA3	15BD11 15BD11A
6LQ6/6JE6B	10LE8	1X2A 1X2B/1X2A	12BM	IDDDIIA
6LQ6/6JE6C 6LZ6	15LE8	1X2C	6FJ7	12DR
6 <b>M</b> E6	9RA	DY80	12BQ	6GV5
6MJ6/6LQ6/	6JQ6	R-19	6C10	6GY5 16GY5
6JE6C	12JQ6	10F	6D10	17GV5
12JB6 12JB6A	17JQ6	609	ECH42 X150	21 <b>GY</b> 5
17JB6	9RF	1709	V120	4007
17JB6A	9KC6	104	12BT	<b>12DZ</b> 6JZ8
17JF6 22JF6	986	10K 5U9/LCF201	6J10	6LU8
22306	1BC2	6U9/ECF201	6Z10/6J10	6MF8
22KM6	1BC2A	6X9/ECF200	10Z10 13J10	13JZ8
24JE6A	1BH2 1BH2 <b>A</b>	ECF200 ECF201	13Z10	15MF8 16LU8A
24LQ6/24JE6C 24LZ6	IDUSK	LCF201	13Z10/13J10	17,128
31LQ6	9RJ	-01-01	17AB10/17X10 17X10	21LU8
31LZ6	6KG6A/EL509 21KQ6	10L	17710	23JZ8 24JZ8
36MC6	29KQ6/PL521	6AF9 SY9/EFL200	12BU	25JZ8
9QM	29LE6	11AF9	6AL11	
6GQ7	40KG6A/PL509	11 <b>Y</b> 9	6G11	12 <b>EA</b>
19GQ7	EL509 PL509	11Y9/LFL200	10AL11 12AL11	2DV4
9QP	PL521	17 <b>Y</b> 9 LFL200	4	6DV4
6KT8	9RL	FILLOO	12BW	12EJ
9QT	6LT8	12AQ	6,111	6FM7
6KY8	8LT8	2CW4	1904	13FM7 13FM7/15FM7
6KY8A 6LR8	11 <b>L</b> T8	2DS4 2EG4	<b>12BY</b> 6AV11	15FM7/15FM7 15FM7
15 <b>KY</b> 8	9RQ	6C <b>W</b> 4	6K11	
15 <b>KY8A</b>	6MD8	6DS4	6K11/6Q11	12 <b>EO</b>
17LD8	12MD8	13CW4	6Q11	6FY7

12E0	12FK	12FY	126Y	12HU
11FY7 15FY7	6JN6 12JN6	30MB6 31JS6A	6HV5A 6HZ5	6MN8
13617	17J <b>N</b> 6	31JS6C	6HZ5/6JD5	9MN8
12ER	21JV6	35LR6	01120/0303	12HW
6BA11	33JV6		12GZ	11CF11
8BA11	4.001	12 <b>GA</b>	16AK9	12HX
12ES	<b>12FL</b> 6HJ5	6BE3/6BZ3 12BE3	23Z9	19DE3
12HE7	21HJ5	17BE3/17BZ3	12 <b>HA</b>	12HY
12EV	211170	17 0007 17 000	3AW2	3BS2A
6JB5/6HE5	12FM	12GC	3AW2A	3BT2
·	619	14BL11	19110	3BW2
12EW 2AS2	4.004	12GD	1 <b>2HB</b> 6BV11	3BW2/3BS2A/
2AS2A	<b>12FN</b> 33GY7	6JZ6	12BV11	3BT2
	33GY7A	21,126		12JA
12EY	50GY7A	30J <b>Z</b> 6	12HC	26LX6
6HE5 6JA5		1005	6EJ4A	12JB
SJB5	12FP	12GF 6BN11	12HD	2BU2
10JA8	6BH11	8BN11	6BW11	2BU2/2AH2
	8BU11	ODIVII	0511	•
1 <b>2EZ</b> &AD10	12FQ	12 <b>G</b> H	12HE	1 <b>2JE</b> 6JH5
6BF11	4HA7	21KA6	6AG9	อานา
6BY11	4HA7/4HC7	12GJ	8AL9	12JH
6710	5HA7	6LB6	12HF	12J <b>F</b> 5
10110	4055	0200	6BW3	17HB25
12AE10 12BF11	<b>12FR</b> 4HC7	12GK	6CD3	17HB25
12710	400/	34CE3	6CE3	407A
13V10	12FS	12GL	6CG3/6CE3/ 6CD3/6B <b>w</b> 3	407A 407A
17BF11	38HE7	14BR11	19CG3	
18AJ10	38HK7	ITONII	25CG3	991
24BF11	53HK7	12 <b>G</b> S	10110	<b>9</b> 91
12FA	12FU	11BT11	1 <b>2HG</b> 6M/8	5642
6EA4	8BM11	11CH11	OMIO	5642
6EH4A	9BJ11	12 <b>G</b> U	12HJ	5672
6EH7	•	6KN6	6AH9	5672
12FB	12FV	42KN6	9AH9	
6H <b>F</b> 5	3AT2	1007	12HK	5678
12FC	3AT2B 3BN2	<b>12GV</b> 1AD2	3BL2	5678
33GT7	3BN2A	1AD2 1AD2A	3BL2A	5734
	OBINER	INDEN	3BM2	5734
12FE	12FX	12GW	12HL	5783
6AC10 6AK10	17BW3	6KD6	21LG6	5783
6U10	17BZ3	6LF6 20LF6	21LG6A	6360Å
8AC10	22 <b>BW</b> 3	30KD6	12HN	6360A
9AK10	12FY	36KD6	11CA11	6977
9AM10 12AC10A	6JS6	36KD6/40KD6	TIONIT	6977
	6JS6A	40KD6	12HR	8808
12FJ	6JS6C	1207	31AL10	8808
6JM6	6LR6 21JS6 <b>A</b>	<b>12GY</b> 6HS5	12HT	8950
6JM6A 17JM6A	23JS6A	6HV5	32HQ7	8950
MOMENT	20,000	-		

# II. TYPE NUMBER vs. TERMINAL DIAGRAM DESIGNATION

Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Termina! Diagram
1A3 1A4P 1A5GT 1A6 1A7GT 1AC5 1AD2 1AD2A 1AD5 1AX2	5AP 4M 6X 6L 7Z 8CP 12GV 12GV 8CP 9Y	1LA4 1LA6 1LB4 1LC5 1LC6 1LD5 1LE3 1LG5 1LH4 1LN5	5AD 7AK 5AD 7AQ 7AK 6AX 4AA 7AO 5AG 7AO	2CY5 2D21 2DS4 2DV4 2DZ4 2E5 2EG4 2EN5 2ER5 2FH5	7EW 7BN 12AQ 12EA 7DK 6R 12AQ 7FL 7FP 7FP	3BT2 3BU8/ 3GS8 3BW2 3BW2/ 3BS2A 3BT2 3BY6 3BZ6 3CA3	12HY 9FG 12HY / 12HY 7CH 7CM 8MH	3KT6 3LF4 3Q4 3Q5GT 3S4 3V4 4AU6 4AV6 4BC5 4BC8	9PM 6BA 7BA 7AP 7BA 6BX 7BK 7BT 7BD 9AJ
1AY2 1AY2A 1B3GT 1B4P 1B5/25S 1B7GT 1BC2 1BC2A 1BH2 1BH2A	1AY2 1AY2 3C 4M 6M 7Z 9RG 9RG 9RG	1N2A 1N5GT 1N6G 1P5GT 1Q5GT 1R5 1RK23 1S2A/ DY87 1S4	3C 5Y 7AM 5Y 6AF 7AT 9DT 9DT 7AV	2FQ5A 2FS5 2GK5/ 2FQ5A 2GU5 2HA5 2HQ5 2T4 3A2 3A2A	7FP 7GA 7FP 7GA 7GM 7GM 5T 9DT 9DT	3CA3A 3CB6/ 3CF6 3CF6 3CN3A 3CN3B 3CN3B 3CN3A 3CN3A 3CN3A 3CN3A	8MH 7CM 7BD 7CM 8MU 8MU 7CH 8MK 8MT	4BL8 4BL8/ XCE80 4BN6 4BQ7A 4BQ7A/ 4BZ7 4BS8 4BU8	9DC 9DC 7DF 9AJ 9AJ 9FG
1C5GT 1C6 1C7G 1C21 1D5GP 1D5GT 1D7G 1D8GT 1DG3 1DG3A	6X 6L 7Z 4V 5Y 5R 7Z 8AJ 8ND 8ND	1S5 1T4 1T5GT 1T6 1U4 1U5 1V 1V2 1X2A	6AU 6AR 6X 8DA 6AR 6BW 4G 9U 9Y	3A3 3A3/3B2 3A3A/ 3B2 3A3B 3A3C 3A4 3A5 3A8GT 3AF4A	8EZ 8EZ 8EZ 8EZ 7BB 7BC 8AS 7DK	3CY5 3CZ3 3CZ3A 3DB3 3DB3/ 3CY3 3DC3 3DC3 3DF3 3DG4 3DJ3	7EW 8EZ 8EZ 8MX 8MX 8MZ 8MT 5DE 8MX	4BU8/ 4GS8 4BZ6 4BZ7 4CB6 4CS6 4CY5 4DF6 4DK6 4DT6	9FG 7CM 9AJ 7CM 7CH 7EW 7CM 7CM 7CM
1DN5 1E5GP 1E7GT 1E8 1F4 1F5G 1F6 1F7G 1G3GT/ 1B3GT	6BW 5Y 8C 8CN 5K 6X 6W 7AF	1X2B/ 1X2A 1X2C 2A3 2A5 2A6 2A7 2AF4A/ 2AF4B	9Y 9Y 4D 6B 6G 7C	3AF4A/ 3DZ4 3AL5 3AT2 3AT2B 3AU6 3AV6 3AW2 3AW2A 3AW3	7DK 6BT 12FV 12FV 7BK 7BT 12HA 12HA 8EZ	3DK6 3DT6 3DT6A 3DZ4 3EA5 3EH7 3EH7/ XF183 3EJ7	7CM 7EN 7EN 7DK 7EW 9AQ 9AQ	4DT6A 4EH7/ LF183 4E17/ LF184 4ES8/ XCC189 4EW6 4GJ7/ XCE801	7CM
1G3GTA/ 1B3GT 1G4GT 1G5G 1G6GT 1H4G 1H5GT 1H6G 1J3 1J5G	3C 5S 6X 7AB 5S 5Z 7AA 3C 6X	2AF4B/ 2DZ4 2AH2 2AS2 2AS2A 2AV2 2B7 2BJ2 2BJ2A 2BN4	7DK 12DG 12EW 12EW 9U 7D 9RT 9RT 7EG	3B2 3B4WA 3BA6 3BC5 3BC5/ 3CE5 3BE6 3BL2 3BL2A 3BM2	8GH 7CY 7BK 7BD 7BD 7CH 12HK 12HK 12HK	3EJ7/ XF184 3ER5 3FH5 3FS5 3GK5 3GS8/ 3BU8 3GS8	9AQ 7FP 7FP 7GA 7FP 9LW 9LW	4GK5 4GM6 4GS8 4GS8/ 4BU8 4GX7 4GZ5 4HA5/ PC900	7FP 7CM 9LW 9LW 9QA 7CV 7GM
1J6G 1J6GT 1K3/1J3 1K3A/1J3 1L4 1L6	7AB 7AB 3C 3C 6AR 7DC	2BN4A 2BU2 2BU2/ 2AH2 2CN3A 2CW4	7EG 12JB 12JB 8MU 12AQ	3BN2 3BN2A 3BN4 3BN4A 3BN6 3BS2A	12FV 12FV 7EG 7EG 7DF 12HY	3HM5/ 3HA5 3HQ5 3HS8 3JC6 3JC6A	7GM 7GM 9EG 9PM 9PM	4HA7 4HA7/ 4HC7 4HC7 4HM6 4HQ5	12FQ 12FQ 12FR 9PM 7GM

Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type Na.	Terminal Diagram
4HS8 4JC6A 4JD6 4JH6 4KF8 4KN8/ 4RHH8 4KT6 4LJ8 4LJ8	9FG 9PM 9PM 7CM 9DC 9AJ 9PM 9GF 7CM	5HG8 5HG8/ LCF86 5JC6 5JK6 5JL6 5JW8 5KD8 5KD8	9MP 9MP 7EN 7BF 7CM 7CM 9DC 9AE 9DC	6AE6G 6AE7GT 6AF3 6AF4 6AF4A 6AF6G 6AF9 6AF11 6AG4Y 6AG5	7AH 7AX 9CB 7DK 7DK 7AG 1OL 12DP 8Y 7BD	6AU6A 6AU6WB 6AU7 6AU8 6AU8A 6AV5GA 6AV5GT 6AV6 6AV11 6AW8	7BK 7BK 9A 9DX 9DX 6CK 6CK 7BT 12BY 9DX	6BJ3 6BJ6 6BJ7 6BJ8 6BK4 6BK4A 6BK4B 6BK4C/ 6EL4A 6BK5	12BL 7CM 9AX 9ER 8GC 8GC 8GC 8GC
4RHH2 4RHH8 5AM8 5AN8 5AQ5 5AQ5 5AR4/ GZ34 5AS4 5AS4 5AS8	9AJ 9DE 9CY 9DA 7BZ 5DA 5T 5T 9DS	5KZ8 5LJ8 5M88 5MHH3 5R4GYB 5T8 5U4G 5U4GB 5HA7 5U8	9FZ 9GF 9FA 7BF 5T 9E 5T 5T 12FQ 9AE	6AG7 6AG9 6AH11 6AH4GT 6AH6 6AH6WA 6AH9 6AK5/ EF95 6AK6	8Y 12HE 12DA 8EL 7BK 7BK 12HJ 7BD 7BK	6AW8A 6AX3 6AX4GT 6AX4GTB 6AX5GT 6AX8 6AY3 6AY3B 6AY11 6AZ8	9DX 12BL 4CG 4CG 6S 9AE 9HP 9HP 12DA 9ED	6BK7A 6BK7B 6BL4 6BL7GT 6BL8 6BL8 ECF80 6BM8/ ECL82	9AJ 9AJ 8GB 8BD 8BD 9DC 9DC
5AT8 5AU4 5AV8 5AW4 5AZ4 5B8 5BC3 5BC3A 5BE8 5BK7A	9DW 5T 9DZ 5T 5T 9EC 9QJ 9EG 9AJ	5U9/ LCF201 5V3 5V3A/ 5AU4 5V4G 5V4GA 5V6GT 5W4 5W4GT	10K 5T 5T 5L 5L 7AC 5T	6AK8/ EABC80 6AK10 6AL3 6AL3/ EY88 6AL5 6AL7GT 6AL11 6AM4	9E 12FE 9CB 9CB 6BT 8CH 12BU 9BX	6B4G 6B5 6B6G 6B7 6B7S 6B8 6B8G 6B10 6BA3	5\$ 6AS 7V 7D 7D 8E 8E 12BF 9HP	6BN4 6BN6/ 6KS6 6BN8 6BN11 6BQ5/ EL84 6BQ6GT	7EG 7EG 7DF 9ER 12GF 9CV 6AM
5BQ7A 5BR8 5BR8/ 5FV8 5BT8 5BW8 5CG8 5CL8 5CL8A 5CQ8	9AJ 9FA 9FE 9HK 9GF 9FX 9FX 9GE	5X4G 5X8 5Y3G 5Y3GT 5Y4G 5Y4GA 5Y4GT 5Z3 5Z4 6A3	5Q 9AK 5T 5T 5Q 5Q 5Q 4C 5T 4D	6AM8 6AM8A 6AN4 6AN5 6AN8 6AN8A 6AQ5 6AQ5A 6AQ6 6AQ7GT	9CY 9CY 7DK 7BD 9DA 9DA 7BZ 7BZ 7BT 8CK	6BA6/ EF93 6BA7 6BA8A 6BA11 6BC4 6BC5/ 6CE5 6BC7	7BK 8CT 9DX 12ER 9DR 7BD 9AX	6BQ6GTB, 6CU6 6BQ7 6BQ7A/ 6BS8 6BR3/ 6RK19 6BR8 6BR8A	9AJ 9CB 9FA 9FA
5CZ5 5DH8 5DJ4 5EA8 5ES8/ YCC189 5EU8 5EW6 5FG7 5FY8	9HN 9EG 8KS 9AE 9AJ 9JF 7CM 9GF 9FA	6A6 6A7 6A7S 6A8 6A8G 6A8GT 6AB4 6AB5/ 6N5 6AB7	7B 7C 7C 8A 8A 8A 5CE 6R 8N	6AQ8 6AQ8/ ECC85 6AR5 6AR8 6AR11 6AS5 6AS6 6AS7G 6AS8	9AJ 9AJ 6CC 9DP 12DM 7CV 7CM 8BD 9DS	6BC8/ 6BZ8 6BD4 6BD4A 6BD6 6BD11 6BE3/ 6BZ3 6BE6 6BF5	9AJ 8FU 8FU 7BK 12DP 12GA 7CH 7BZ	6BS3 6BS3A 6BS8 6BU8 6BV8 6BV11 6BW3 6BW4 6BW8 6BW11	9HP 9HP 9AJ 9FG 9FS 12HB 12HF 9DJ 9HK 12HD
5GH8A 5GJ7/ LCF801 5GM6 5GS7 5GX6 5GX7 5HB7	9AE 9QA 7CM 9GF 7EN 9QA 9QA	6AC5GT 6AC7 6AC7W 6AC10 6AD6G 6AD7G 6AD10 6AE5GT	6Q 8N 8N 12FE 7AG 8AY 12EZ	6AS11 6AT6 6AT8 6AT8A 6AU4GT 6AU4GTA 6AU5GT 6AU6	12DP 7BT 9DW 9DW 4CG 4CG 6CK 7BK	6BF6 6BF11 6BG6G 6BH3 6BH3A 6BH6 6BH8 6BH11	7BT 12EZ 5BT 9HP 9HP 7CM 9DX 12FP	6BX7GT 6BY5GA 6BY6 6BY8 6BY11 6BZ6 6BZ7 6BZ8	8BD 6CN 7CH 9FN 12EZ 7CM 9AJ 9AJ

Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type Ne.	Terminal Diagram
6C4 6C5 6C5GT 6C6 6C7 6C8G 6C9 6C10 6CA4	6BG 6Q 6G 6F 7G 8G 10F 12BQ 9M	6CX8 6CY5 6CY7 6CZ5 6CZ7 6D4 6D6 6D7 6D8G	9DX 7EW 9LG 9HN 8ET 5AY 6F 7H 8A	6EA8 6EB8 6EC4/ EY500 6EH4A 6EH5 6EH7/ EF183	9AE 9DX 6EC4 12FA 7CV 12FA 9AQ	6FS5 6FV6 6FV8 6FV8A 6FW5 6FY5/ EC97 6FY7 6G6G	7GA 7FQ 9FA 9FA 6CK 7FP 12EO 7S	6GY6/ 6GX6 6GY8 6GZ5 6H6 6H6GT 6HA5 6HA6 6HB5	7EN 9MB 7CY 7Q 7Q 7GM 9NW 12BJ
6CA5 6CA7/ EL34 6CB5A 6CB5A 6CB6A/ 6CF6 6CD3 6CD6G 6CD6GA 6CE3	7CV 8ET 8GD 8GD 7CM 12HF 5BT 5BT 12HF	6D10 6DA4 6DB5 6DC6 6DC8 6DC8/ EBF89 6DE4 6DE6 6DE7 6DG6GT	12BQ 4CG 9GR 7CM 9HE 9HE 4CG 7CM 9HF 7S	6EH8 6EJ4A 6EJ7 6EJ7 EF184 6EL4 6EM5 6EM7/ 6EA7 6EN4 6EQ7	9JG 12HC 9AQ 9AQ 8GC 9HN 8BD 8NJ 9LQ	6G11 6GB3A 6GB5 6GB5/ EL500 6GB6 6GB7 6GC5 6GE5 6GF5 6GF7	12BU 6AM 9NH 9NH 6AM 6AM 9EU 12BJ 12BJ 9QD	6HB6/ 6HA6 6HB7 6HE5 6HF8 6HG5 6HG8 6HG8/ ECF86 6HJ5	9NW 9QA 12EY 12FB 9DX 7BZ 9MP 9MP
6CE5 6CF6 6CG3/ 6CE3/ 6CD3/ 6BW3 6CG7 6CG8 6CG8A 6CH3	7BD 7CM 12HF 9LP 9GF 9GF 9HP	6DJ8/ ECC88 6DK3 6DK6 6DL4/ EC88 6DL5/ EL95 6DM4A	9AJ 9SG 7CM 9NY 7DQ 7DQ 4CG	6ER5 6ES5 6ES8/ ECC189 6ET7 6EU7 6EU8 6EV5 6EV7 6EW6	7FP 7FP 9AJ 9LT 9LS 9JF 7EW 9LP 7CM	6GF7A 6GH8 6GH8A 6GJ5 6GJ5A 6GJ7 6GJ7/ ECF801 6GJ8	9QD 9AE 9AE 9QK 9QK 9QA 9QA	6HJ8 6HK5 6HL8 6HM5/ 6HA5 6HM6 6HQ5 6HR5 6HR6 6HS5	9CY 7GM 9AE 7GM 9PM 7GM 7BZ 7BK 12GY
6CH8 6CJ3/ 6CH3 6CK3 6CK4 6CL3/ 6CK3 6CL6 6CL8	9FT 9HP 9HP 8JB 9HP 9HP 9BV 9FX	6DN3 6DN6 6DN7 6DQ5 6DQ6A 6DQ6B 6DR7 6DS4 6DS5 6DT5	9HP 5BT 8BD 8JC 6AM 6AM 9HF 12AQ 7BZ 9HN	6EW7 6EX6 6EY6 6EZ5 6EZ8 6F4 6F5 6F5GT 6F6 6F6G	9HF 5BT 7AC 7AC 9KA 7BR 5M 5M 7S 7S	6GK5/ 6FQ5A 6GK6 6GK17 6GL7 6GM5 6GM6 6GN8 6GQ7 6GS7	7FP 9GK 4CG 8BD 9MQ 7CM 9DX 9QM 9GF	6HS6 6HS8 6HU6/ EM87 6HU8/ ELL80 6HV5 6HV5A 6HZ5	7BK 9FG 9GA 9NJ 12GY 12GY 12GY
6CL8A 6CM3 6CM6 6CM7 6CM8 6CN7 6CQ4 6CQ8 6CR6 6CS6	9FX 9HP 9CK 9ES 9FZ 9EN 4CG 9GE 7EA 7CH 9EF	6DT6 6DT6A 6DT8 6DV4 6DW4 6DW4B 6DW5 6DX8 6DX8/ ECL84 6DZ4	7EN 7EN 9AJ 12EA 9HP 9HP 9CK 9HX 9HX 7DK	6F6GT 6F7 6F8G 6FA7 6FD5 6FE5 6FG6/ EM84 6FG7 6FH5 6FH8	7S 7E 8G 9MR 9HF 8KB 9GA 9GF 7FP 9KP	6GT5 6GT5A 6GU5 6GU7 6GV5 6GV8 6GV8/ ECL85 6GW6 6GW6/ 6DQ6B	9NZ 9NZ 7GA 9LP 12DR 9LY 9LY 6AM	6HZ5/ 6JD5 6HZ6 6HZ8 6J4 6J5 6J5GT 6J6 6J6A 6J6WA 6J7	12GY 7EN 9DX 7BQ 6Q 6Q 7BF 7BF 7BF 7R
6CU5 6CU6 6CU8 6CW4 6CW5 6CW5/ EL86	7CV 6AM 9GM 12AQ 9CV	6DZ7 6E5 6E6 6E7 6EA4 6EA5 6EA7	8JP 6R 7B 7H 12FA 7EW 8BD	6FJ7 6FM7 6FM8 6FQ5A 6FQ7 6FQ7/ 6CG7	12BM 12EJ 9KR 7FP 9LP	6GW8/ ECL86 6GX6 6GX7 6GY5 6GY6	9LZ 7EN 9QA 12DR 7EN	6J7G 6J7GT 6J8G 6J10 6J11 6JB5/ 6HE5	7R 7R 8H 12BT 12BW

Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram
6JB6 6JB6A 6JC6A 6JC8 6JE6 6JE6A 6JE6A 6JF6 6JG6	9QL 9QL 9PM 9PA 9PM 9QL 9QL 9DX 9QU	6KN8/ 6RHH8 6KR8 6KS6 6KT6 6KT8 6KU8 6KV6 6KV6A 6KV6A	9AJ 9DX 6DF 9PM 9QP 9LT 9QU 9QU 9DX	6MK8A 6MN8 6MQ8 6MU8 6MV8 6N6G 6N7 6N7GT 6P5GT 6P7G	9FG 12HU 9AE 9AE 9DX 7AU 8B 8B 6Q 7U	6U8A/ 6KD8 6U9/ ECF201 6U10 6V3A 6V6 6V6GT 6V6GTA 6V7G	9AE 10K 12FE 9BD 7AC 7AC 7AC 7AC 7V	7L7 7N7 7Q7 7R7 7S7 7V7 7X7 7Y4 7Z4 8A8	8V 8AC 8AL 8AE 8BL 8V 8BZ 5AB 5AB 9DC
6JG6A 6JH6 6JH8 6JK6 6JK8 6JM6 6JM6A 6JN6 6JN8	9QU 12JE 7CM 9DP 7CM 9AJ 12FJ 12FK 9FA	6KY8 6KY8A 6KZ8 6L5G 6L6 6L6G 6L6GB 6L6GC 6L7 6L7G	9QT 9QT 9FZ 6Q 7AC 7AC 7AC 7AC 7T	6Q7 6Q7G 6Q7GT 6Q11 6R7 6R7G 6R7GT 6RHH2 6RHH8 6RK19	7V 7V 7V 12BY 7V 7V 7V 7BD 9DE 9CB	6W4GT 6W6GT 6W7G 6X4 6X4W 6X5 6X5GT 6X8A 6X9/ ECF200	4CG 7AC 7R 5BS 5BS 6S 6S 9AK	8AC10 8AL9 8AR11 8AU8 8AW8A 8B8 8B10 8BA8A 8BA11 8BH8	12FE 12HE 12DM 9DX 9DX 9EX 12BF 9DX 12ER 9DX
6JQ6 6JR6 6JS6A 6JS6C 6JT6 6JT6A 6JT8 6JU6 6JU8	9RA 9QU 12FY 12FY 12FY 9QU 9DX 9QU 9QL 9PQ	6LB6 6LB8 6LC8 6LE8 6LF6 6LF6 6LH6A 6LJ6 6LJ6A/ 6LH6A	12GJ 9DX 9QY 9QZ 12GW 9DX 8ML 8MQ	6S4 6S4A 6S7 6S7G 6S8GT 6SA7 6SA7GT 6SB7Y 6SC7 6SF5	9AC 9AC 7R 7R 8CB 8R 8AD 8R 8S 6AB	6Y6GA/ 6Y6G 6Y7G 6Y9/ EFL201 6Z4 6Z5 6Z7G 6Z10/ 6J10	7AC 8B 10L 5D 6K 8B 12BT	8BM11 8BN8 8BN11 8BQ5 8BQ11 8BU11 8CB11 8CG7 8CM7 8CN7	12FU 9ER 12GF 9CV 12DM 12FP 12DM 9LP 9ES 9EN
6JU8A 6JV8 6JW8/ ECF802 6JZ6 6JZ8 6K5GT 6K6GT 6K7 6K7G	9PQ 9DX 9DC 12GD 12DZ 5U 7S 7R 7R	6LJ8 6LM8 6LN8/ 6LN8/ LCF80 6LQ6/ 6JE6B 6LQ6/ 6JE6C 6LQ8	9GF 9AE 9DC 9DC 9QL 9QL 9QL 9DX	6SF7 6SG7 6SH7 6SJ7 6SJ7GT 6SJ7Y 6SK7 6SK7GT 6SL7GT 6SN7GT	7AZ 8BK 8BK 8N 8N 8N 8N 8N 8BD 8BD	6ZY5G 7A5 7A6 7A7 7A8 7AD7 7AG7 7AH7 7AU7 7B4	6S 6AA 7AJ 8V 8U 8V 8V 8V 9A 5AC	8CS7 8CW5/ XL86 8CX8 8EB8 8EM5 8ET7 8FQ7 8FQ7/ 8CG7	9EF 9CV 9DX 9DX 9HN 9LT 9LP
6K7GT 6K8 6K8G 6K8GT 6K11 6K11/ 6Q11 6KA8 6KD6 6KD8	7R 8K 8K 8K 12BY 12BY 12GW 9AE	6LR6 6LR8 6LT8 6LU8 6LX8/ LCF802 6LY8 6LZ6 6M11 6MB8	12FY 9QT 9RL 12DZ 9DC 9DX 9QL 12CA 9FA	6SN7GTA 6SN7GTB 6SQ7 6SQ7GT 6SR7 6SS7 6ST7 6SZ7 6T4 6T7G	8BD 8BD 8Q 8Q 8Q 8N 8Q 8D 7DK 7V	7B5 7B6 7B7 7C5 7C6 7C7 7E6 7E7 7EY6 7F7	6AE 8W 8V 6AA 8W 8V 8W 8AE 7AC 8AC	8GJ7 8GJ7/ PCF801 8GN8 8GU7 8JU8A 8JV8 8KA8 8LC8 8LT8	9QA 9QA 9DX 9LP 9PQ 9DX 9PV 9QY 9RL
6KG6A/ EL509 6KL8 6KM6 6KM8	9DC 9RJ 9LQ 9QL 9QG 12GU	6MD8 6ME6 6ME8 6MF8 6MG8 6MHH3 6MJ8 6MK8	9RQ 9QL 9RU 12DZ 9DC 7BF 12HG 9FG	6T8 6T8A 6T9 6T10 6U5 6U7G 6U8	9E 9E 12FM 12EZ 6R 7R 9AE	7G7 7GS7 7HG8 7HG8/ PCF86 7K7	8BW 8V 9GF 9MP 9MP 8BF 9GK	9A8 9A8/ PCF80 9AH9 9AK10 9AM10 9AQ8/ PCC85	9DC 9DC 12HJ 12FE 12FE

Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram
9AU7 9BJ11 9BR7 9CL8 9GH8A 9GV8/ XCL85 9JW8/ PCF802	9A 12FU 9CF 9FX 9AE 9LY 9LY	11CH11 11CY7 11DS5 11FY7 11HM7 11JE8 11KV8 11LQ8 11LT8 11MS8	12GS 9LG 7BZ 12EO 9BF 9DX 9DX 9EX 9RL 9LY	12AZ7 12B4A 12B8GT 12BAG 12BA7 12BD6 12BE3 12BE6 12BF6	9A 9AG 8T 7BK 8CT 7BK 12GA 7CH 7BT	12DS7 12DS7A 12DT5 12DT8 12DV8 12DW4A 12DW7 12DY8 12DZ6 12EA6	9JU 9HN 9AJ 9HR 9HP 9A 9JD 7BK 7BK	12JN6 12JN8 12JQ6 12JT6 12JT6A 12K5 12K7GT 12K8 12KL8 12L6GT	12FK 9FA 9RA 9QU 9QU 7EK 7R 8K 9LQ 7AC
9KC6 9KX6 9KZ8 9LA6 9RAL1 9U8A 10 10AL11 10BQ5 10C8	9RF 9GK 9FZ 9GK 9HF 8AE 4D 12BU 9CV 9DA	11Y9 11Y9/ LF1200 12A5 12A6 12A7 12A8GT 12AB5 12AC6 12AC10A	10L 7F 7S 7K 8A 9EU 7BK 12FE	12BF11 12BH7 12BH7A 12BK5 12BL6 12BN6 12BQ6GTI 12CU6 12BR3 12BR7	12EZ 9A 9BQ 7BK 7DF 8/ 6AM 9CB	12EC8 12ED5 12EG6 12EH5 12EK6 12EK6/ 12DZ6, 12EA6 12EL6 12EM6	9FA 7CV 7CH 7CV 7BK 7 7BK 7FB 9HV	12MD8 12Q7GT 12RK19 12S8GT 12SA7 12SA7GT 12SC7 12SF5 12SF5GT 12SF7	9RQ 7V 9CB 8CB 8R 8AD 8S 6AB 6AB 7AZ
10CW5 10CW5/ LL86 10DE7 10DR7 10DX8 10DX8/ LCL84 10EG7 10EM7	9CV 9CV 9HF 9HF 9HX 9HX 8BD 8BD	12AD6 12AE6 12AE6A 12AE7 12AE10 12AF3/ 12BR3/ 12RK19 12AF6 12AH7GT	7CH 7BT 7BT 9A 12EZ 9CB 7BK 8BE	12BS3 12BS3A/ 12DW4 12BT3 12BV7 12BV11 12BW4 12BY7	9HP A 9HP 12BL 9BF 12HB 9DJ 9BF	12EN6 12EQ7 12F5GT 12F8 12FK6 12FM6 12FQ7 12FQ8 12FR8 12FV7	7AC 9LQ 5M 9FH 7BT 7BT 9LP 9KT 9KU 9A	12SG7 12SH7 12SJ7 12SJ7GT 12SK7 12SK7GT 12SK7GT 12SN7GT 12SN7GT/ 12SQ7	8BK 8BK 8N 8N 8N 8BN 8BD 8BD 4 8BD
10EW7 10GF7 10GF7A 10GK6 10GN8 10GV8/ LCL85 10HE8 10JA8/ 10LZ8	9HF 9QD 9QD 9GK 9DX 9LY 9DX	12AJ6 12AL5 12AL8 12AL11 12AQ5 12AT6 12AT7/ ECC81 12AT7WA 12AT7WB	7BT 6BT 9GS 12BU 7BZ 7BT 9A 9A 9A	12BY7A/ 12BV7/ 12DQ7 12BZ6 12BZ7 12C5 12C8 12CA5 12CL3 12CN5	9BF 7CM 9A 7CV 8E 7CV 9HP 7CV	12FX5 12FX8 12FX8A 12GA6 12GB3 12GB6 12GB7 12GC6 12GE5 12GJ5	7CV 9KV 9KV 7CH 6AM 6AM 6AM 8JX 12BJ 9QK	12SQ7GT 12SR7 12SR7GT 12SW7 12SX7GT 12SY7 12T10 12U7 12V6GT 12W6GT	8Q 8Q 8Q 8BD 8R 12EZ 7CK 7AC 7AC
10JT8 10JY8 10KR8 10KU8 10LB8 10LE8 10LW8 10LZ8 10T10 10Z10	9DX 9DX 9DX 9LT 9DX 9QZ 9DX 9DX 12EZ 12BT	12AU6 12AU7 12AU7A/ ECC82 12AV5GA 12AV6 12AV7 12AW6 12AX3 12AX4GT	7BK 9A 6CK 7BT 9A 7CM 12BL 4CG	12CR6 12CT3 12CT8 12CU5/ 12C5 12CU6 12CX6 12D4 12DB5 12DE8	7EA 9RX 9DA 7CV 6AM 7BK 4CG 9GR 9HG	12GJ5A 12GN7 12GN7A 12GT5 12GT5A 12GW6/ 12DQ6I 12H6 12HE7 12HG7	9QK 9BF 9BF 9NZ 9NZ 9NZ 12ES 9BF	12X4 12Z3 13CW4 13DE7 13DR7 13EM7 13EM7/ 15EA7 13FD7 13FM7	5BS 6G 12AQ 9HF 9HF 8BD 8BD 9HF 12EJ
11 11AF9 11AR11 11BM8 11BQ11 11BT11 11CA11 11CF11	4F 10L 12DM 9EX 12DM 12GS 12HN 12HW	12AX4GTA 12AX4GTE 12AX7 12AX7A/ ECC83 12AY3 12AY3A 12AY7		12DK6 12DK7 12DL8 12DM4 12DM4A 12DQ6A 12DQ6B 12DQ7	7CM 9HZ 9HR 4CG 4CG 6AM 6AM 9BF	12HG7/ 12GN7/ 12HL7 12J5GT 12J7GT 12J8 12JB6 12JB6A	A 9BF 9BF 6Q 7R 9GC 9QL 9QL	13FM7/ 15FM7 13GB5 13GB5/ XL500 13GF7 13GF7A 13J10	12EJ 9NH 9NH 9QD 9QD 12BT

Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram
13JZ8 13V10 13Z10 13Z10/ 13J10 14A4 14A5 14A7 14AF7 14B6	12DZ 12EZ 12BT 12BT 5AC 6AA 8V 8AC 8W	17BB14 17BE3/ 17BE3 17BF11 17BH3 17BJ6 17BQ6GTE 17BR3/ 17K19	9NH 12GA 12EZ 9HP 9QL 36AM 9CB	18AJ10 18FW6 18FW6A 18FX6 18FX6A 18FY6 18FY6A 18GB5/ LL500	12EZ 7CC 7CC 7CH 7CH 7BT 7BT 9NH	22BW3 22DE4 22JF6 22JG6 22JG6A 22JR6 22JU6 22KM6 22KV6A 23JS6A	12FX 4CG 9QL 9QU 9QU 9QU 9QL 9QL 9QU 12FY	26 26A6 26A7GT 26C6 26D6 26HU5 26LW6 26LX6 27	4D 7BK 8BU 7BT 7CH 8NB 8NC 12JA 5A
14B8 14BL11 14BR11 14C5 14C7 14E6 14E7 14F7 14F8	8X 12GC 12GL 6AA 8V 8W 8AE 8AC 8BW	17BS3 17BS3A/ 17DW4/ 17BW3 17BZ3 17C5 17C9 17CK3 17CT3	9HP	18GD6A 18GV8/ PCL85 19 19AU4 19AU4GTA 19BG6G 19BG6GA 19CG3	5BT	23JZ8 23Z9 24A 24BF11 24JE6A 24JZ8 24LQ6/ 24JE6C 24LZ6	12DZ 12GZ 5E 12EZ 9QL 12DZ	27GB5/ PL500 29KQ6/ PL521 29LE6 30 30AE3/ PY88 30JZ6	9NH 9RJ 9RJ 4D 9CB 12GD
14GT8 14H7 14J7 14JG8 14N7 14R7 15 15AF11 15BD11 15BD11	9KR 8V 8BL 9KR 8AC 8AE 5F 12DP 12DP	17CU5/ 17C5 17D4 17DE4 17DM4 17DM4A 17DQ6A 17DQ6B 17DW4A 17EW8	7CV 4CG 4CG 4CG 4CG 6AM 6AM 9HP 9AJ	19CL8A 19DE3 19EA8 19EX5 19FX5 19GQ7 19HR6 19HS6 19HV8 19J6	9FA 12HX 9AE 9KA 7CV 9QM 7BK 7BK 9FA 7BF	25A6 25A6GT 25A7GT 25AC5GT 25AV5GA 25AX4GT 25B5 25B6G 25B8GT 25BK5	7S 7S 8F 6Q 6CK 4CG 6D 7S 8T 9BQ	30KD6 30MB6 31 31AL10 31JS6A 31JS6C 31LQ6 31LR8 31LZ6 32	12GW 12FY 4D 12HR 12FY 12FY 9QL 9QT 9QL 4K
15CW5 15CW5/ PL84 15DQ8/ PCL84 15FW7 15FY7 15KY8 15KY8A 15LE8 15MF8	9CV 9CV 9HX 12E0 9QT 9QT 9QZ 12DZ	17EW8/ HCC85 17GB3 17GE5 17GJ5A 17GT5A 17GT5A 17GV5 17GW6/ 17DQ6E	9AJ 6AM 12BJ 9QK 9QK 9NZ 9NZ 12DR	19JN8/ 19CL8A 19KG8 19MR9 19T8 19X8 20 20AQ3/ LY88 20EQ7 20EZ7	9FA 9LY 7BK 9E 9AK 4D 9CB 9LQ 9PG	25BQ6GTE 25BQ6GTE 25CU6 25C5 25C6G 25CA5 25CD6GA 25CD6GB 25CG3 25CK3 25CK3	6AM 7CV 7CV 7CV 5BT 5BT 12HF 9HP 9RX	32A5 32ET5 32ET5A 32HQ7 32L7GT 33 33GT7 33GY7 33GY7A 33JR6 33JV6	6AA 7CV 7CV 12HT 8Z 5K 12FC 12FN 12FN 9QU 12FK
16A8/ PCL82 16AK9 16AQ3/ XY88 16BQ11 16BX11 16GK6 16GY5	9EX 12GZ 9CB 9CB 12DM 12CA 9GK 12DR	17H3 17HB25 17JB6A 17JF6 17JG6 17JG6A 17JM6A 17JM6 17JQ6 17JJ6	9FK 17HB25 9QL 9QL 9QU 9QU 12FJ 12FK 9RA 9QU	20LF6 21EX6 21GY5 21HB5 21HB5A 21HJ5 21JS6A 21JV6 21JZ6 21KA6	12GW 5BT 12DR 12BJ 12BJ 12FL 12FY 12FK 12GD 12GH	25CU6 25DN6 25E5/ PL36 25EC6 25EH5 25F5A 25HX5 25JZ8 25L6	6AM 5BT 8GT 5BT 7CV 7CV 9SB 12DZ 7AC	34 34CE3 34GD5 34GD5A 34R3 35 35B5 35B5 35C5 35DZ8 35EH5	4M 12GK 7CV 7CV 9CB 5E 7BZ 7CV 9JE 7CV
16LU8A 17AB10/ 17X10 17AX3 17AX4GT 17AX4GTA 17AY3 17AY3A	12DZ 12BT 12BL 4CG 4CG 9HP 9HP	17JT6A 17JZ8 17KV6A 17LD8 17KK19 17X10 17Z3/ PY81	9QU 12DZ 9QU 9QT 9CB 12BT 9CB	21KQ6 21LG6 21LG6A 21LR8 21LU8 22 22BH3 22BH3A	9RJ 12HL 12HL 9QT 12DZ 4K 9HP 9HP	25L6GT/ 25W6GT 25N6G 25W4GT 25W6GT 25Y5 25Z6 25Z6GT	7AC 7W 4CG 7AC 6E 7Q 7Q	35GL6 35L6GT 35LR6 35W4 35Y4 35Z4GT 35Z5GT 36	7FZ 7AC 12FY 5BQ 5AL 5AA 6AD 5E

Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram	l Type No.	T <i>erminal</i> Diagram	l Type No.	Terminal Diagram
36AM3 36AM3A 36AM3B 36KD6	5BQ 5BQ 5BQ 12GW	117L7/ M7GT 117N7GT 117P7GT	VA8	5842/ 417A 5844 5847/	9V 7BF	6677/ 6CL6 6678/ 6U8A	9BV 9AE	8058 8077/ 7054 8106	12CT 9GK 9PL
36KD6/ 40KD6 36MC6 37 38 38HE7	12GW 9QL 5A 5F 12FS	117Z3 117Z4GT 117Z6GT 407A 408A 884	4CB 5AA 7Q 407A 7BD 6Q2	404 <b>A</b> 5879 5881 5896 5899 5902	9X 9AD 7S 8DJ 8DE 8DE	6679/ 12AT7 6680/ 12AU7/ 6681/ 12AX7/	-	8136 8203 8393 8417 8532 8627	5C 12AQ 12AQ 7S 7BQ 12CT
38HK7 39/44 40 40KD6 40KG6A/ PL509 41 42 42EC4A/ PY500	12FS 5F 4D 12GW 9RJ 6B 6B	955 959 991 1612 1613 1614 1619 1620 1621 1622	5BC 5BE 991 7T 7S 7S 7AW 7R 7S	5915 5963 5964 5965 6005 6012 6072 6073 6073/	7CH 9A 7BF 9A 7BZ 6CO 8DG 9A 5BO	6688A 6814 6887 6922/ E88CC 6939 6973 6977 7025	9EQ 8DK 6BT 9AJ 9HL 9EU 6977 9A	8628 8808 9002 9001 9003 9005 9006 A61 A863	12AQ 8808 7BS 7BD 7BD 5BG 6BH 4G 7R
42KN6 43 45 45Z3 45Z5GT 46 47 48 49 50	12GU 6B 4D 5AM 6AD 5C 5B 6A 5C 4D	1629 1635 2050 2050A 2076/ 5R4GYE 5636 5639 5642 5651A	7AL 8B 6BS 6BS	OA2 6074 6074/ OB2 6080 6080WA 6082 6111 6112 6186	5B0 5B0 5B0 8BD 8BD 8BD 8BD 8DG 8DG 7BD	7027 7027A 7044 7054 7055 7056 7057 7058 7059 7060 7061	8HY 9H 9GK 6BT 7CM 9AJ 9EP 9AE 9DA 9EU	AD17 B36 B65 B152 B309 B329 B339 B719 B739 B749 B759	6AU 8BD 9A 9A 9A 9A 9AJ 9A 9A
50A5 50B5 50BM8/ UCL82 50C5 50C6Q 50DC4 50EH5 50FE5 50FK5	6AA 7BZ 9EX 7CV 7AC 5BQ 7CV 8KB 7CV	5651 <b>W</b> A 5654 5663 5670 5672 5678 5686 5687 5691 5692	5B0 7BD 6CE 8CJ 5672 5678 9G 9H 8BD 8BD	6189 6197 6202 6206 6211 6336A 6350 6360A 6386 6417	9A 9BV 5BS 8DC 9A 8BD 9CZ 6360A 8CJ 9K	7167 7189 7199 7247 7258 7308 7355 7360 7408 7543	7EW 9BL 9JT 9A 9DA 9AJ 8KN 9KS 7AC 7BK	BPM04 CXF80 D2M9 D63 D152 DA90 DAF91 DAF92 DF33 DF91	7BZ 9AE 6BT 6BT 6BT 5AP 6AU 6BW 5Y 6AR
50GY7A 50HC6 50HK6 50JY6 50L6GT 50X6 50Y6GT 50Y7GT 50Z7G 53	12FN 7FZ 7FZ 8MG 7AC 7DX 7Q 8AN 8AN 7B	5693 5696 5596A 5718 5719 5725 5726 5727 5734 5749	8N 7BN 7BN 8DK 8DK 7CM 6BT 7BN 5734 7BK	6485 6550 6626/ 0A2WA 6660/ 6BA6 6661/ 6BH6 6662/ 6BJ6	5C 7S 5BO 7BK 7CM 7CM	7551 7558 7581A 7586 7587 7591 7591A 7695 7717/ 6CY5	9LK 9LK 7AC 12AQ 12AS 8KQ 8KQ 9PX 7EW	DF904 DH63 DH77 DK91 DL012 DL31 DL33 DL91 DL92 DL94	6AR 7V 7BT 7AT 9E 6X 7AP 7AV 7BA 6BX
53HK7 60FX5 70L7GT 75 78 80 83 84/6Z4	12FS 7CV 8AA 6G 6F 4C 4C 5D	5751 5763 5783 5814A 5823 5824	7CH 9A 9K 5783 9A 4CK 7S 8DE	6663/ 6AL5 6664/ 6AB4 6669/ 6AQ5A 6676/ 6CB6A	6BT 5CE 7BZ 7CM	7868 7895 7898 7905 8016	9KR 9NZ 12AQ BEP BPB BC 12AQ	DL95 DP61 DY30 DY80 DY87 E81CC E82CC E83CC	7BA 7BD 3C 9Y 9DT 9A 9A 9A

Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram	Type No.	Terminal Diagram
EAA91 EABC80 EB34 EB91 EBC90 EBC91 EBF85 EBF89 EC88 EC90	6BT 9E 7Q 6BT 7BT 7BT 9HE 9HE 9NY 6BG	EF190 EF811 EF814 EF905 EFL200 EFL201 EH90 EK90 EL22 EL34	7CM 9AQ 9AQ 7BD 10L 10L 7CH 7CH 6AA 8ET	KT77 KT81 KT88 KTW63 KTZ63 L63 L63B L77 LC900 LCF80	8N 6AA 8EP 7R 7R 6Q 6Q 6BG 7GM 9DC	0C2 0C3 0C3A 0D3 0D3A 0SW3104 0SW3105 0SW3106 0SW3111 0SW3111		U70 U74 U76 U78 U707 U709 UCL82 UCL83 UU12 V153	5AA 5BS 5BS 5DA 9M 9EX 9EX 9M 4G
EC92 EC94 EC95 EC97 EC900 ECC32 ECC35 ECC81 ECC82 ECC83	5CE 7DK 7FP 7FP 7GM 8BD 8BD 9A 9A 9A	EL37 EL84 EL86 EL90 EL95 EL180 EL500 EL509 EM35 EM84	7AC 9CV 9CV 7BZ 7DQ 9BF 9NH 9RJ 6R 9GA	LCF86 LCF201 LCF801 LCF802 LCL82 LCL84 LCL85 LF183 LF184 LF200	9MP 10K 9QA 9AE 9EX 9HX 9LY 9AQ 9AQ 10L	0Z4 0Z4A 0Z4G PC95 PC900 PCC18 PCC85 PCF80 PCF82 PCF86	4R 4R 7FP 7GM 9A 9DC 9DX 9MP	V741 VSM70 W17 W61 W63 W81 W143 W148 W727 X17	6BG 5BS 6AR 7R 7R 8V 8V 8V 7BK 7AT
ECC85 ECC88 ECC89 ECC91 ECC180 ECC186 ECC189 ECC801 ECC802 ECC803	9AJ 9AJ 9DE 7BF 9AJ 9A 9A 9A 9A	EM87 EM840 EY81F EY88 EY500 EZ4 EZ35 EZ90 EZ900 GZ30	9GA 7S 9BD 9CB 6EC4 9M 6S 5BS 5BS 5T	LFL200 LL86 LL500 LN119 LY88 LZ319 LZ329 M709 M8080 M8081	10L 9CV 9NH 9EX 9CB 9DC 9DC 9CV 6BG 7BF	PCF801 PCF802 PCL82 PCL84 PCL85 PCL800 PH4 PL36 PL84 PL500	9QA 9AE 9EX 9HX 9LY 9GK 8A 8GT 9CV 9NH	X63 X77 X107 X150 X727 XC95 XC97 XC900 XCC82 XCC189	8A 7CH 6CH 12BQ 7CH 7FP 7FP 7GM 9A 9AJ
ECF80 ECF82 ECF86 ECF200 ECF201 ECF801 ECF802 ECH42 ECL82 ECL84	9DC 9AE 9MP 10K 10K 9QA 9AE 12BQ 9EX 9HX	GZ32 GZ34 GZ37 H63 HAA91 HBC90 HBC91 HCC85 HD14 HD94	5DA 5DA 5DA 5M 6BT 7BT 7BT 9AJ 5Z 6AM	M8108 M8136 M8137 M8162 M8245 N16 N17 N18 N19	7BK 9A 9A 7BZ 7AP 7BA 7BA 6BX 7S	PL509 PL521 PM04 PM05 PY81 PY83 PY88 PY500 PY800 QA2401	9RJ 9RJ 7BK 7BD 4G 4G 4G 6EC4 4G 6BG	XCF80 XCF801 XCL85 XF94 XF183 XF184 9CV XL86 XL500 XXA-91	9DC 9QA 9LY 7BK 9AQ 9AQ XL84 9CV 9NH 6BT
ECL85 ECL86 ECL180 EF22 EF37 EF80 EF93 EF94 EF95 EF96	9LY 9LZ 8CK 8V 7R 9FN 7BK 7BK 7BD 7BD	HD96 HF93 HF94 HK90 HL92 HM04 HY90 HZ90 KT-32 KT-63	6AM 7BK 7CH 7CV 7CH 5BQ 5BS 7AC 7S	N148 N308 N369 N727 OA2 OA2WA OA3 OA3A OA4G OB2	6AA 8GT 9EX 7BZ 5B0 5B0 4AJ 4AJ 4V 5B0	QA2404 QA2406 QB309 QL77 R-19 R-52 RJ2 T2M05 U41 U50	6BT 9A 9A 6BG 9Y 5DA 5T 7BF 3C 5T	XY88 Y61 YC95 YCC189 YCL180 YF183 YF184 Z14 Z63	9CB 6R 7FP 9AJ 9AJ 9AQ 9AQ 5Y 7R
EF183 EF184	9AQ 9AQ	KT66 KT71	7AC 7AC	OB2WA OBC3	5B0 8Q	U52 U54	5T 5DA		

#### III. TERMINAL CONNECTIONS

This chart gives the pin or terminal connections for each terminal diagram designation referred to in this manual. The following tabulation gives the meaning of each of

the symbols, letter combinations or subscripts, used in this chart and on the basing diagrams in the Technical Data Section.

#### LETTER COMBINATIONS

Plate (Vacuum tubes) DJA = Deflecting Elec-HA == Heater End A HB = Heater End B trode A DJB = Deflecting Elec-HI = Heater Insulator Anode (Gas-filled trode B tubes) F = Filament End (Un-IC = Do Not Use PA = Plate A polarized) F+ = Filament End IS = Internal Shield PR = Plate R (Electrostatic) RCJ = Ray-Control Elec-(Positive only) IPR = Jumper End trode F- = Filament End K = Cathode REM = Remote (Negative only) LC = May be used only = Metal Shell under Limited Conditions Filament Tap S M = Shell connec-F_M = G = Grid tion, metal 61. G2, etc. = Grid No.1, Grid No.2, etc. H = Heater End (Un-NC = No Internal Contube SHP = nection Sharp NC G = No Base Connec-STR = Starter TA = Fluorescent Target polarized) tion, glass tube = Top Cap = Gas Filled


#### SUBSCRIPTS FOR MULTIUNIT TYPES


5) ⁶


(1) (12)

Please note that the terminal diagrams given in the Technical Data Section are bottom views of the tube base and that the pins or terminals are numbered clockwise. For essentially all modern tubes the spacing between pin No. 1 and the pin having the highest number is somewhat larger than the spacing

between all the other pins. For octal based types, the "key" for orienting the tube when it is inserted in a socket also serves to designate pin No. 1, which is the first pin clockwise from the key. The following diagrams illustrate the terminal configuration of receiving tubes most commonly encountered.







Octal

Term:	i-				ΡI	N N	UMI	BER					
Dia- gram	1	2	3	4	5	6	7	8	9	10	11	12	TC
1AY2	F	F											Р
3C	LC	F	LC	LC	LC	LC	F,IS	LC					P
4 <b>AA</b> *	F	P	NC	NC	IC	G	NC	F					
4 <b>A</b> J*	NC	K	JPR		P		JPR	NC					
4C	PD2	PD1	F	F									
4CB	IC	NC	Н	Н	P	K	NC						
4C <b>6</b>	IC	IC	K		P		Н	H					
4CK*	P	IC	K	STR	IC	!C	K						
4D	F	P	G	F									
4F	F	P	F	G									
4 <b>G</b>	Н	P	K	Н									
4K	F	P	G2	F									G1
4 M	F+	P	G2	F—,G	3								G1
4R*	S	NC	P2		P1		NC	K					
4V*	NC	K	NC		P		STR	NC					
4Z	Н	P	NC	NC	NC	NC	K	Н					
5A	Н	P	G	K	H								
5AA	NC	Н	NC		P		Н	K					
5AB	Н	NC	PD2	NC	NC	PD1	K	H					
5AC	Н	P	NC	NC	NC	G	K	H					
SAD	F+	P	G2	NC	NC	G1	NC	F—,G3					
5AG	F+,IS	PT	NC	PD	NC	GT	NC	F—					
5AL	H	P	NC	нМ	NC	NC	K	H					
āAM	H	P	IC	K	NC	P	Н						
iΑP	Н	P	K	NC	IC	P	H						
AY	G	NC	Н	Н	K	NC	P						
iB	F	P	G1	G2	F								
BC	Н	P	G	Н	K								
BE	F+	G2	G3	F→	F—						T0 B0	P LEA T LEA	D P D G1

Termi na! Dia- gram		2	3	4	P 1 1	N N	U _M B	ER	9	10	11	12	TC
5BG	нв	К	Р	НА	НА		<u> </u>						
5B0*	P	K	1C	K	P	10	K						
5BQ	NC	NC	Н	Н	P	HL	K						
5BS	PD2	NC	Н	Н	NC	PDI	K						
5BT	NC	H	K,G3	NC	G1	NC	Н	G2					ρ
5C	F	P	GI	G2	F								
5CE	P	NC	Н	Н	NC	G	K						
5D	Н	PD2	PD1	K	Н								
5DA	IC	H	PD2	PD1	H,K								
5DE	F	IC	F		PD2		PD1						
5E	H	P	G2	K	Н								G
5F	H	P	G2	K,G3	Н								G1
5K	F+	P	G1	G2	F—,G	3							
5L	NC	H		PD2		PD1	H,K						
5M	NC G S M	Н	NC	P	NC		н	K					G
5 <b>Q</b>	NC	NC	PD2	NC	PD1	NC	F	F					
5R	NC	F	P	G2	NC		F	NC					G1
S	NC	F	P	NC	G	NC	F	NC					
5 <b>T</b>	NC G S M	F		PD2		PD1		F					
5U		H	P		NC		H	K					G1
įΥ	BC	F+	Р	G2	NC		F—,IS G3	NC					G1
5 <b>Z</b>	BC	F+	PT	NC	PD		F	NC					GT
iΑ	Н	P	G2	G1	K	Н							
AA	Н	P	G2	NC	NC	G1	K,G3	Н					
AB	NC G S M	K	G		P		Н	H					
AD	NC	H	нм		P		H	K					
AE	Н	Р	G2	NC	NC	G1	K,G3	Н					

Termi nal Dia- gram	i- 1	2	3	4	PiN 5	I N U	M B	E R	9	10	11	12	TC
6AF	NC	F+	Р	G2	G1		F—,G3	NC					
6AM	NC	Н	NC	G2	G1		Н	K,G3					P
6AR	F—,1S G3	P	G2	NC	F—,IS G3	G1	F+						
6AS	Н	PT2	PT1	GT1	K	Н							
6AU	F— G3P	NC	PD	G2P	PP	G1P	F+						
6AX	F+	PP	G2P	PD	NC	G1P	NC	F— G3P					
6B	Н	P	G2	G1	K G3	Н							
6BA	F+	P	G2	NC	NC	G1	FM G3	F					
6B <b>G</b>	P	IC	Н	Н	P	G	K						
6BH	P	K	Н	Н	P	NC	K						
6BS*		H	P	NC	G1	G2	Н	K					
6BT	KD2	PD1	Н	Н	KD1	18	PD2						
6BW	F— G3P	PP	G2P	PD	NC	GIP	F+						
6BX	F—	P	G2	NC	FM,G3	G1	F+						
<b>6</b> C	F	PT2	GT2	GT1	PTI	F							
6CC	G1	G3,K	Н	Н	P	G2	NC						
6CE*	G1	K	Н,	Н	G2	NC	P						
6CK	G1	Н	G3,K		P		H	G2					
6CN	KD2	Н	IC	PD2	PD1		Н	KD1					
600*	K	H	G1		P		H	G2					
6D	H	PT2	PT1	GT1	K	Н							
6E	Н	PD2	KD2	KD1	PD1	Н							
6EC4	IC	P	H!	H	Н	IC	P	P	IC				K
6F	Н	P	G2	G3	K,IS	Н							G1
6G	H	PT	PD2	PD1	K	H 							G1
6J	Н	ES	PD2	K	PD1	Н							

Termi nal Dia-	i. 1	2	3	4	PIN 5	i N	U M I	BER 8	9	10	11	12	TC
gram 													
6K	HM	H	PD2	K	PDI	H							
6L	F	P	G2	G1	G3,G5	F							G4
6M	F	PT	PD2	PD1	GT	F							
<b>6</b> Q	NC G S M	H	P		G		Н	K					
6R	H	PT RCJ	GŢ	TA	K	H							
68	NC G S M	Н	PD2		PD1		H	K					
6 <b>W</b>	F+	PP	G2P	PD2	PD1	F— G3P							G1P
БΧ	NC	F+	P	G2	G1		F—,G	3					
7AA	NC	F+	PT	PD2	PD1	GT	F—	NC					
7AB	NC	F	PT2	GT2	GT1	PT1	F	NC					
7AC	NC G S M	H	P	G2	G1		Н	K G3					
7AF	NC	F+	PP	PD2	PDI	G2P	F— G3P	NC					G1P
7AG	NC	H	RCJB	RCJA	TA		Н	K					
7ÅH	NC	Н	PT Rem	PT SHP	G		H	K					
7AJ	Н	KD2	PD2	NC	IS	PD1	KD1	H					
7AK	F	P	G2	GI	G3,G5	G4	NC	F					
/AL	NC	Н	PT RCJ	TA	GT		H	K					
/AM	NC	F+	PP	G2P	G1P	PD	F— G3P	NC					
AO	F+	P	G2	G3	F—,IS	G1	NC	F-,IS					
AP	NC	F+	P	G2	G1		F	G3,FM					
PA	NC	F	P	G2	G1		F	FM,G3					
AT	F—,G5	P	G2,G4	G1	F—,G5	G3	F+						
AU	NC	H	PT2	PTI	GT1		Н	K					
AV	F—,G3	Р	G1	G2	F−,G3	Р	F+						

Yerm nai Dia- gram	i- 1	2	3	4	PIN	i N U	J M B	ER 8	9	18	11	12	TC
7AW	S	F	Р	G2	G1		F	G3					
7AX	NC	Н	P	GB	КВ	GA	H	KA					
7AZ	S	G1P	K,G3P	G2P	PD	PP	H	H					
7B	H	PT2	GT2	K	GT1	PT1	H						
7BA	F	P	G1	G2	FM,G3	P	F+						
788	F—	P	G2	G1	FM	P	F+						
7BC	F	PT2	GT2	FM	GT1	PT1	F+						
789	<b>6</b> 1	K,IS G3	H	H	P	G2	K,IS G3						
7BF	PT2	PT1	H	H	GT1	GT2	K						
7 <b>BK</b>	G1	G3,1S	н	H	P	G2	K						
7BN*	G1	K	Н	H	G2	P	G2						
7 <b>8Q</b>	G,IS	K	H	H	G,IS	C,1S	P						
7 <b>BR</b>	Ħ	G	P	P	G	H	K						
7 <b>B</b> S	P	K	Н	H	P	G	K						
7 <b>8</b> T	GT	K	H	H	PD2	PD1	PT						
7BZ	G1	K,G3	H	H	P	G2	<b>G1</b>						
7 <b>C</b>	H	P	G3,G5	G2	G1	K	H						G4
7 <b>CC</b>	G1	G3	H	Н	P	G2	K						
7¢H	G1	K,G5	H	H	P	G2,G4	G3						
7CK	KIS G3	H	G2	K,IS G3	G1	K,IS G3	H	BC					Р
7CM	G1	K	Н	Н	P	G2	G3,IS						
7 <b>CY</b>	K,63	G1	H	H	G1	G2	P						
7CY	<b>G2</b>	FM,G3 IS	G1	F	F	FM,G3 IS	P						
78	H	PP	G2P	PD2	PD1	K,G3P	H						G1P
7 <b>8C</b>	F	P	G2	G1	G3,G5	G4	F						
7 <b>9</b> F	K,IS	G1	H	H	G2	G3	P						
79K	P	6	H	H	K	G	P						

Termi nal Dia- gram		2	3	4	PIN 5	1 N U	J M E	BER 8	9	10	11	12	TC
7DQ	G1	K,G3	Н	н	P	G2	G1						
OX	Н	KD2	P02	NC	NC	PD1	KD1	н					
Έ	Н	PP	G2P	PT	GT	K,G3P	Н						GIP
EA	K,G3P	PD	Н	Н	PP	G2P	G1P						
EG	K	G	Н	H	Р	K	G						
EK	K	G2	H	Н	G1	G1	P						
EN	G1	K,IS	Н	Н	P	G2	G3						
EW	G1	K,IS	H	Н	P	G2	K,IS						
F	H	P	G2	G1	K,G3	нм	Н						
FB	GT	PT	Н	Н	PD2	PD1	K						
FL	NC	PD2	Н	H	K	18	PD1						
FP	K	G2	H	Н	P	IS	K						
FQ	G1	21	H	Н	P	G2	K						
FZ	K,G3	G1	Н	Н	G2	нМ	P						
G	Н	PT	ES	PD2	PD1	K	Н						G1T
GA	G1	K,G2 G4	Н	Н	Р	G3	K,G2 G4						
GM	G1	K	H	Н	Р	IS	K						
H	Н	P	G2	G3	ES	K	Н						G1
K	Н	PP	G2P	KD	PD	KP G3P	Н						GIP
Q	NC G S M	Н	PD2	KD2	PD1		Н	KD1					
R	NC G S M	Н	P	G2	<b>G</b> 3		Н	K					
S	NC G S M	Н	P	G2	G1		Н	K G3					
Γ	NC G S M	Н	P	G2 G4	G3		Н	K G5					G1
J	NC	Н	H	PP	G2P	PT	G1	K,G3P					G1P
1	NC	Н	PT	PD2	PD1		Н	K					GT

rermi nai	-				PIN	ı N	Ј М В	E R				
Dia- gram	1	2	3	4	5	6	7	8 9	10	11	12	TC
7 <b>W</b>	NC	Н	PT2	PT1	GT1		Н	К				
72	BC	F	P	G3,G5	G1	G2	F	NC				G4
BA	NC G S M	Н	P	G3 G5	G1	G2	Н	K				G4
BAA	KD	H	PB	G2B	G1B	KB G3B	Н	PD				
BAC	Н	KT2	PT2	GT2	GT1	PT1	KT1	Н				
BAD	NC	Н	P	G2,G4	G1	K,G5	Н	G3				
BAE	H	PP	PD2	PD1	G2P	G1P	K,G3P	H				
BAJ	NC	F+	PP	G2P	G1P	PT	F— G3P	PD				GT
BAL	Н	P	G2,G4	G1	G5	G3	K	Н				
8AN	NC	Н	PD2	KD2	PD1	нм	Н	KD1				
8A0	KD	H	PB	G1B	G2B	PD	Н	KB G3B				
8AS	FM,IS G3P	F	PP	G2P	GT	PT	F	PD				GT
8AV	NC	Н	PB	G1B	G2B	KB G3B	PD H	KD				
8AY	GT	H	PP	G2P	G1P	PT	Н	K,G3P				
8B	NC G S M	H	PT2	GT2	GT1	PT1	Н	K				
8BD	GT2	PT2	KT2	GT1	PT1	KT1	Н	H				
8BE	GT2	KT2	PT2	KT1	GT1	PT1	Н	H				
8BF	Н	KT	PT	GT	PD2	PD1	KD1 KD2	Н				
8BJ	Н	P	G2	K	IS,G3	G1	K	Н				
8BK	S	Н	K,G3	G1	K,G3	G2	Н	P				
8BL	Н	PHP	PT	GT G3HP	G2HP G4HP	G1HP	K,IS G5HP	Н				
8BU	G1B1	K G3B1 G3B2	G1B2	PB2	G2B1 G2B2	H	Н	PB1				
8BW	GT2	Н	PT2	KT2	KT1	PT1	Н	GT1				

Termi nai Dia- gram	i- 1	2	3	4	P 1 1	N N	U _M B	E R	5	10	11	12	TC
38Z	Н	PT2	GI	KT,IS KD1	PDI	PD2	KD2	н					
8C	NC	F+	PP2	G1P2	G1P1	PP1	F,G3	G2					
BCB	PD3	KT KD2 KD3	PD1	PD2	KD1	PΥ	Н	H					GT
BCH	G	Н	TA	DJ2	DJ3	DJ1	Н	K					
BCJ	Н	KT2	GT2	PT2	IS	PT1	GT1	KT1	Н				
BCK	PD2	KD1 KD2	PD1	GT	PT	KT	н	Н					
BCN	IC	GI	NC	F,G5	F+	P	G2,G4	G3					
BCP	NC	G1	NC	F—,G3	F+	NC	P	G2					
BCT	G2,G4	G1	K	Н	Н	G5,IS	G3	18	P				
BDA	PP	NC	G1P	F— G3P	F+	PD	NC	G2P					
BDC	G1	K,IS	H	G3	P	Н	G2	K,IS					
BDE	G1	K,G3	Н	K,G3	P	Н	G2	K,G3					
BDG	PT2	GT2	Н	KT2	KT1	Н	GT1	PT1					
BDJ	PD2	KD2	Н	IS	PDI	Н	KD1	NC					
BDK	G	NC	Н	NC	K	Н	NC	P					
E	BC	H	PP	PD2	PD1	G2P	Н	K,G3P					GII
BEL	G	H	NC		P		H	K					
EP	<b>G3</b> .	H	P	G2	Gl	NC	Н	K					
ET	G3	H	P	G2	G1	NC	Н	K					
EZ	LC	H	LC		LC		H,K IS						P
F	KD	Н	PP	G2P	G1P	PĐ	н	KP G3P					
FU	K	Н	NC		NC		Н	NC					Р
G	NC	H	PT2	KT2	GT1	PT1	Ħ	KTI					GT:
EB	IC	IC	K	IC	Р	IC	Н	Н					
BEC	K	Н	IC	IC	G	IC	Н	IC					P

Termi- nal Dia- gram	1	2	3	4	PIN 5	e   N	U M E	BER 8	3	10	11	12	TC
86D	G2	Н	G3,K	G1	G1	G3,K	Н	G2					Р
8GH	LC	Н	FC	<b>FC</b>	<b>LC</b>	LC	H,K IS	<b>LC</b>					P
8 <b>6</b> T	IC	Н	IC	G2	G1		Н	K,G3					P
8H	NC	Н	PHP	G2HP G4HP	GT G3HP	PT	Н	K G5HP					G1HP
8HY	G2	Н	P	G2	G1	G1	Н	K,G3					
8JB	G	Н	G		P		Н	K					
8JC	G1	Н	G3,K	G2	G1	G3,K	Н	G2					P
8JP	G1P2	Н	PP2	G2	G1P1	PP1	Н	K,G3					
8JX		Н	K,G3	G2	G1		Н	G2					Р
8K	S	Н	PHX	G2HX G4HX	GT G1HX	PT	Н	K					G3H)
8KB		Н	Р	G2	G1	Н	K,G3						
8KN		Н	P		G3,K	G1	Н	G2					
8KQ		Н	P	G2	G3,K	Gl	Н	G2					
8KS	F	F	PD2	PD2	PD1	PD1	F	F					
8LY	P	Н	P	G2	G1		H	K,G3					
8MG	18	Н	G3	G2	G1	NC	Н	K					P
HM8	<b>LC</b>	Н	FC		TC.		H,K IS	FC					Р
8MK	IC	F	IC		IC		F,IS	IC					P
8ML	IS	Н	IC	IC	G	K	Н	IC					P
8MQ	IC	Н	IS	IC	G	K	Н	IC					P
8MT	NC	IC	Н	IC	IC	IC	NC	H,K IS					Р
8MU	IC	н	IC	NC	IC	NC	H,K IS	IC					Р
8MW	K,IS	Н	IC	IC	G	NC	Н	IC					P
8MX	H,K IS	Н	IC	NC	IC	NC	H,K IS	IC					P
8MY	NC	IC	Н	IC	Н	IC	NC	Н					P
8MZ	F,IS	F	F,IS	NC	F,IS	NC	F,IS	NC					P
8N	S	Н	G3	Gl	K	G2	Н	P					
8NB	G1	K,G3	G2	NC	G1	10	Н	Н					P

Yermi nai	i-				PII	N N	UMI	BER					
Dia- gram	1	2	3	4	5	•	7	8	9	10	11	12	TC
8NC	IC	K,G3	G2	NC	G1	IC	Н	Н					Р
8ND	NC	IC	F	IC	F	IC	NC	F,IS					P
8NJ	K,IS	Н	IC	10	G	G	Н	IC					Р
BNL	IC	H,K IS	Н	NC	Н	H,K IS	NC	H,K IS					P
BNP	IC	IC	Н	18	1\$	G.	K	Н					Р
8Q	S	GT	K	PD2	PD1	PT	Н	Н					
8R	S,G5	Н	P	G2,G4	G1	K	Н	G3					
BS	S	PT2	GT2	GT1	PT1	K	Н	Н					
BT	KP G3P	Н	PP	G2P	PT	KT	Н	GT					G1P
BU	Н	P	G2	G1	G3,G5	<b>G</b> 4	K,G6	Н					
BV	Н	Р	G2	G3	IS	G1	K	Н					
BW	Н	PΤ	GT	IC	PD2	PD1	IS,K	Н					
BX	Н	P	G2	G1	G3,G5	G4	K	H					
BY	G3,S	H	NC	G1	K	G2	Н	P					
BZ	KD	Н	PB	G2B	G1B	PD	Н	KB G3B					
9A	PT2	GT2	KT2	HT2	HT1	PT1	GT1	KT1	НМ				
PAC	IC	K	G	Н	Н	G	IC	IC	P				
BAD	G1	NC	K	Н	Н	NC	G2	P	G3				
BAE	PT	G1P	G2P	H	Н	PP	KP, IS G3P	KT	GT				
BAG	K	G	НМ	Н	H	NC	G	NC	P				
AJ	PT2	GT2	KT2	Н	Н	PT1	GT1	KT1	ſS				
AK	G3P	GT	PT	Н	H	K	G1P	G2P	PP				
PAQ	K	G1	K	H	H	IS	P	G2	G3				
AU	IS	G1	K	Н	Н	IS	Р	G2	G3				
BAX	KD3	PD3	IS	Н	Н	PD2	KD2	PD1	KD1				
BD	NC	P	NC	Н	Н	NC	P	NC	P				K
BF	K	G1	G3,IS	H	H	HM	P	G2	G3,IS				
BL	IC	G1	K,G3	Н	Н	IC	P	IC	G2				
BQ	Р	NC	G1	Н	H	K,G3	G1	G2	NC				
BV	K	G1	G2	H	Н	P	G3,IS	G2	G1				

Termi nai	i-				PIN	i Ni	JMB	ER					
Dia- gram	1	2	3	4	5	6	7	8	9	10	11	12	TC
9BX	G	К	G	G	Р	G	Н	Н	G				
9CA	G2HP G4HP	G1HP	K G5HP	Н	Н	PHP	G3HP	PT	GT				
9CB	IC	IC	IC	Н	Н	IC	IC	IC	P				K
9CF	PT	GT	KT	Н	Н	PD2	PD1	KD1 KD2 IS	нМ				
9CK	G2	NC	G1	Н	Н	G1	K,G3	NC	P				
9CV	IC	G1	K,G3	Н	Н	10	Р	10	G2				
9CY	KP	G1P	G2P	Н	Н	PP	KD	PD	G3P IS				
9CZ	PT2	KT2	GT2	Н	Н	PT1	KT1	GT1	нМ				
9DA	PT	GT	KT	Н	Н	PP	G2P	G1P	G3P KP,IS				
9DC	PT	G1P	G2P	Н	Н	PP	KP,IS G3P	KT	GT				
9DE	PT2	GT2	KT2	Н	Н	PT1	GT1	KT1	IS				
9DJ	PD2	NC	NC	Н	Н	NC	PD1	NC	K				
9DP	DJ2	DJ1	G3	НВ	HA,IS G2	G1	K	P2	P1				
9DR	Р	G	G	Н	Н	K	G	G	Р				
9DS	G2P	G1P	KP	Н	Н	PD	G3P IS	KD	PD				
9DT	H,K IS	Н	NC	H,K IS	Н	H,K IS	NC	Н	H,K IS				P
9DW	GT	PΤ	K	н	Н	PP	G2P	G3P	GIP				
9DX	KT	GT	PT	Н	н	G3P KP,IS	G1P	G2P	PP				
9DZ	KT	GT	PT	Н	Н	G1P	G3P KP,IS	G2P	PP				
9E	PD3	PD2	KD2 IS	Н	Н	PD1	KT,IS KD1 KD3	GT	PΤ				
9EC	G3P KT,IS	GT	ΡŢ	Н	Н	G1P	KP	G2B	PP				
9ED	PP	G2P	KP	Н	H,IS G3P	G1P	KT	PT	GT				
9EF	PT2	NC	GT2	Н	Н	PT1	GT1	KT1	KT2				

Termi pal	i-				PII	N N	JMB	ER					
Dia- gram	1	2	3	4	5	8	7		•	10	11	12	TC
9EG	GT	PT	KT,IS G3P	Н	Н	PP	G2P	KP	GIP				
9EN	PD2	PD1	KD1 KD2 IS	Н	H	KT	GT	PT	HM				
9EP	PT2	GT2	KT2	Н	Н	PT1	GT1	KT1	IC				
9EQ	K	G1	K	Н	Н	IC	P	G3	G2				
9ER	PD2	KD2	KD1	Н	Н	PD1	PT	GT	KT				
ES	PT2	NC	KT1	H	H	PT1	GT1	GT2	KT2				
9EU	G2	NC	G1	H	H	G1	K,G3	<b>G2</b>	P				
9EX	GT	KP,IS G3P	G1P	H	H	PP	G2P	KT	PT				
FA	GT	PT	KT	Н	Н	PP	G2P	KP,IS G3P	G1P				
FE	PD2	PD1	KD1 KD2	H	H	PP	G2P	G1P	KP G3P				
FG	K	G2,IS	PP2	Н	Н	G3P2	G1	PP1	G3P1				
FH	PD2	GP2	PP	Н	Н	PD1	K	G1P	G3P				
₽FJ	KT	GT	PT	Н	Н	PD2	KD1	KD2	PD1				
FK	K	IC	P	H	H	IC	IC	P	IC				
BFN	G1P	G3P IS	KD	Н	Н	PD	PP	G2P	KP				
9FT	KT	PP	G2P	Н	H,IS G3P	KP	G1P	GT	PT				
9FX	GT	PT	KT	Н	Н	PTR	G2TR	KTR IS	G1TR				
FZ	PT	G1P	KP,IS G3P	Н	Н	PP	G2P	KT	GT				
3 <b>G</b>	K,G3	G1	K,G3	Н	Н	G2	P	K,G3	G2				
GA	GT	IC	K	Н	Н	TA	RCJ	IC	PT				
GC	G1TR	KTR	G2TR	Н	Н	PTR	KD1 KD2	PD2	PD1				
GE	PT	G1TR	G2TR	Н	Н	PTR	KTR IS	KT	GT				
)GF	GT	PT	K	Н	Н	PP	G2P	G3P,K	G1P				

lerni nai Dia-			•		PIN		J M B				11	19	TC
1.54 1.15-		2	3	4	5	6	7		•	10	11	12	
æĸ	K	Gl	<b>G3,IS</b>	Н	H	NC	P	<b>G2</b>	G3,IS				
<b>M</b>	KT,IS G3P	PP	62P	H	H	KP	G1P	GT	PT				
)ĈR	62	K,G3	G1	H	H	Gl	K,G3	IC	P				
220	PT	G2TR	G1TR	H	H	PTR	KTR	GT	KT				
H	PT2	GT2	KT2	H	H	KT1	GT1	HM	PT1				
ЩE	G2P	G1P	K,IS	H	H	PP	PD1	PD2	G3P				
WF	PT2	GT2	GT2	H	H	PT1	GT1	KT1	KT2				
MC	GIP	KD	PD	H	H	PP	GP3 IS	G2P	KP				
HK	P02	KD1 KD2	PD1	H	H	G1P	KP,IS G3P	G2P	PP				
ĦL	G1P2	K,63	G1P1	HP2	HP1	PP2	<b>G2</b>	PP1	HM				
MH	62	NC	G1	H	H	Gl	K,G3	IC	P				
	IC	P	IC	H	H	IC	P	IC	K				
HR	PD2	KTR	G1TR	H	H	PTR	G2TR	KD1 KD2 IS	PD1				
MA	GITR	K	G2TR	H	H	PTR	IC	IC	PD				
MEX	GT	PT	KT	H	Н	PP	KP,IS G3P	G1P	G2P				
MZ	GITR	K	G2TR	H	H	PD2	PTR	KTR	PD1				
	G1TR	KTR	G2TR	Н	Н	PTR	KT,IS	PT	GT				
IJE	<b>GT</b>	KP,IS G3P	GIP	Н	Н	PP	G2P	KT	PT				
UF	PP	6T	PT	H	Н	KT	G1P	KP,IS G3P	GZP				
JC	K,IS G3P	GT	PT	H	H	K,IS G3P	G1P	G2P	PP				
UT	PT	PP	G2P	H	Н	KP,IS G3P	G1P	KT	GT				
JH	PD2	NC	G1TR	H	H	PTR	G2TR	K	PD1				
K	Р	NC	63	н	Н	G2	ĸ	G1	<b>G</b> 1				

Termi nal Dia-		•	,		PIN	ู N U	МВ	E R		10	11	10	TC
gram	1	2	3	4	<b></b>			- 8 	9	10	11	12	16
9KA	KT3	GT3	PT3	H KT1 KT2	Н	PT2	GT2	PT1	GT1				
JX	G1TR	K	G2TR	н	Н	PTR	PD2	IC	PD1				
9KP	P1BTR	GT	PT	H,K	Н	G1TR	G2TR	PIATR	P2TR				
9KR	KD2	PD1	KD1	Н	Н	PD2	KT	GT	PT				
9KS	K,IS	G2	G1	Н	Н	РВ	PA	DJB	DJA				
ЭXТ	2PB	2G	2PA	н	Н	1PB	1G	1PA	K				
9KU	GT	KT	GIP	Н	H,G3P KP,IS	G2P	PP	PD	PT				
9KV	G2 G4HP	G1HP	PHP	H	H KT	GT	G5HP KHP IS	PT	G3HP				
9LG	PT2	IC	GT2	Н	Н	PT1	GT1	KT1	KT2				
EK	K	G1	G2	Н	Н	Р	G3	G2	K				
BLP	PT2	GT2	KT2	Н	Н	PT1	GT1	KT	NC				
9LQ	G3P	GlP	K	Н	Н	G2P	PP	PD	1\$				
9LS	Н	Н	NC	KT2	GT2	PT2	PT1	GT1	KT1				
9LT	KD1 KD2 ISD	PD2	PD1	H	Н	KP G3P ISP	G1P	G2P	PP				
9LW	K IS	G2	PP2	Н	Н	G3P2	G1	PP1	G3P1				
9LY	PT	GT	KT	Н	Н	PP	G2	KP G3P	G1P				
9LZ	GT	KŢ	G2P	H	н	PP	KP,IS G3P	G1P	PT				
9M	PD1	NC	K	Н	Н	NC	PD2	NC	NC				
9MB	GT3	PT3	GT2	H,GT1 KT3	н	PT1	KT1	KT2	PT2				
9 <b>M</b> P	KP	G1P	KT,IS	н	Н	GT	PT	PP	G2P				
<b>PMQ</b>	G2	IC	IC	н	Н	G1	K,G3	IC	P				
9MR	PBTR	NC	PD	Н	Н	K,IS	G1TR	G2TR	PATR				
9NH	G1	G1	G3,K	Н	Н	G2	G2	G3,K	IC				Р

Ters:	i-				PΙ	N N	UMI	BER					
Dia- gram	1	2	3	4	5	6	7	8	9	10	11	12	TC
9NJ	G1P1	G2P1	PP1	Н	Н	G1P2	K,IS G3	PP2	G2P2				
9NX	K	Gl	K	H	Н	62	Р	<b>G</b> 3, IS	G2				
9NW	K	G1	G3	н	н	G2	P	G2	G3				
9NY	G	K	G	Н	Н	G	G	Р	G				
9NZ	G2	Gl	K,G3	Н	Н	<b>G</b> 1	G2	IC	Р				
9PA	K,IS G3P	G1P	G2P	Н	Н	PP	K,IS G3P	GT	PT				
9PB	F—	G1	G2	LC	LC	P	G3	G2	F+				
9P <b>G</b>	Н	Н	IC	KT2	GT2	PT2	PT1	GT1	KT1				
9PL	P	K,G3	G2	Н	Н	K,G3	G1	G2	K,G3				
9PM	K	G1	K	Н	Н	NC	Р	G2	G3,IS				
9PQ	PD4	PD3 KD4	KD3	Н	Н	IS	PD2	PD1 KD2	KD1				
9PV	PT	GT	K,IS	Н	Н	GIP	G3P	G2P	PP				
9PX	G2	NC	IC	Н	Н	G1	K,G3	IC	P				
PZ	Р	G3	G2	Н	Н	G3	K	G1	K				
BQA	K,IS G3P	G1P	K,IS G3P	Н	Н	PP	G2P	PT	GT				
9QD	KTI	GT2	KT2	Н	H	PT2	NC	PT1	GT1				
9QG	PIBTR	PIATR	PD	Н	Н	K,1S	GITR	G2TR	P2TR				
100	FB	FA	FA	LC	PD2	PD2	LC	PD1	PD1				
QX	G2	Gl	K,G3	Н	H	G1	G2	IC	IC				Р
QL	G2	G1	K	Н	Н	G1	G2	<b>G</b> 3	IC				Р
MDE	KD3	PD3	IC	Н	Н	PD2	KD2	PD1	KD1				
QP	KT	GT	PT	Н	H,IS G3P	KP	GIP	G2P	PP				
QT	ΚŢ	GIB	KB G3B	Н	Н	PB	G2B	PT	GT				
UD	G2	G1	K	Н	Н	G3	G2	IC	P				
QΥ	Ρſ	GT	KT,IS G3P	н	н	GIP	KP	GP2	PP				
QZ	PP2	G3P2	K	Н	II	PP1	G3P1	G2	G1				
RA	Р	IC	G2	Н	Н	G3,PD	G1	G1	K				
RF I	K	G1	NC	Н	Н	<b>G</b> 3	Р	NC	G2				

Termi nal Dia-		_			PII		UMB						
gram	1	2 	3	4	5	6	7	8	9	10	11	12	TC
erg	F,IS	IC	10	IC	F	IC	NC	IC	IC				P
BRJ	G1	G3	G2	Н	Н	G2	G3	G1	K				P
ORL	KP,IS G3P	G2P	PP	H	Н	PD2	KD	PD1	G1P				
BRQ	PT3	PT2	PT1	Н	Н	GT1	K	GT2	GT3				
PRT	H,K IS	Н	10	H,K IS	H	H,K IS	IC	Н	H,K IS				P
PRU	DJ2	DJ1	G3	НВ	HA,IS	G1	K,G2	P2	P1				
PRX	IC	P	IC	Н	Н	P	IC	IC	K				
SB	G1	K,G3	K,G3	H	Н	G2	G1	IC	P				
SG	Hľ	Р	IC	Н	Н	1C	P	IC	NC				K
9U	P	IC	IC	F	F	IC	IC	IC	P				
Y	P	NC	Н	G	G	K	G	G	Н				
3X	G1	NC	Н	K,IS G3	NC	P	NC	G2	Н				
)Y	F,IS	F	LC	F,IS	F	F,IS	LC	F	F,IS				P
OF	G1TR2	G2TR2	PTR2	Н	Н	KTR1	G1TR1	PTR1	KTR2	KD1 IS			
ØG	PT3	GP3	KT3	Н	H	PT2	GT1	PT1	GT2	KT1 KT2			
OH	G1P	G2P	PP	Н	Н	GP3 IS	KT	GT	PT	KP			
OK	KT	KP	G1P	G3P IS	H	H	PP	G2P	PT	GT			
OL	G1P2	KP2 G3P2	G2P2	PP2	Н	Н	KP1 G3P1 IS	G1P1	G2P1	PP1			
2AQ		P		G				K		Н		Н	
2AS		G2		G1				K		Н		Н	P
2BF	Н	KT2	GT2	PT2	GT1	PT1	KT1	PD2	KD1 KD2	PD1	IS	Н	
2BJ	Н	G2	G1	K,G3	IC	IC	P	IC	IC	K	G1	Н	
2BL	Н	NC	NC	P	NC	NC	K	NC	NC	Р	NC	Н	

Termi- nai Die				PII		UME						
Dia- gram 1	2	3	4	5	6		8 	9	10	11	12	TC
12BM H	NC	GT2	NC	PT2	IC	KT2	NC	KT1	GT1	PT1	Н	
12BQ H	PT3	KT3	KT1	PT2	KT2	GT2	IC	GT1	PT1	GT3	Н	
12BT H	G2P	K,G3P	PB	G3B	G2B	G1B	KB,IS	PP	NC	G1P	H	
12 <b>8U</b> H	ΚP	G1P	G3P	IS	PP	G2P	G1B	KB G3B	G2B	РВ	Н	
12BW H	G2P2	PP2	G3P2 IS	G1P2	KP2	G2P1	KP1	PP1	G3P1 IS	G1P1	Н	
128Y H	PT3	KT3	KT1	PT2	KT2	GT2	IS	GT1	PT1	KT3	Н	
12CA H	G1P	G2P	KT2	GT2	PT2	PT1	GT1	KT1	KP,IS G3P	PP	Н	
12CT	К		K				K		Н	SHEL G	. Н	P
12DA H	KD2	PD2	KT2	GT2	PT2	PT1	GT1	KT1	PD1	KD1	H	
12 <b>dg</b> H,K Is	IC	iC	LC	LC	IC	IC	IC	IC	LC	IC	Н	Р
1 <b>20m</b> H	P <b>P</b> 2	G2P2	G3P2	G1P2	KP2	G3P1 IS	PP1	G2P1	G1P1	KP1	Н	
12DP H	PP	GT2	PT2	KT1	GT1	KT2 IS	PT1	KP,IS G3P	G2P	G1P	H	
<b>12DQ</b> F,IS	IC	IC	LC	IC	IC	IC	IC	IC	LC	IC	F	P
I2DR H	NC	G2	K,G3	G1	NC	G2	NC	G1	K,G3	G2	H	P
I <b>2DZ</b> H	PΤ	NC	PB	NC	G1B	G1B	G2B	KB G3B	GT	KT	Н	
IZEA P	P		G		G	K			Н		H	
IZEJ H	NC	GT2	NC	PT2	10	KT2	GT2	KT1	GT1	PT1	Н	
12EO H	NC	GT2	NC	PT2	NC	KT2	IC	KT1	GT1	PT1	Н	
IZER H	PP2	G2P IS	G1P	G3P2	PP1	G3P1	K IS	GT	KT	PT	H	
IZES H	NC	G1	K,G3	G2	IC	P	IC	G2	K,G3	G1	H	
1 <b>2EW</b> H,K 1S	H,K IS	IC	LC	IC	H,K IS	LC	IC	H,K IS	LC	IC	Н	Р
IZEY H	G1	G2	K,G3	NC	Р	NC	NC	G1	G2	K,G3	Н	
IZEZ H	KP IS	G1P	NC	G3P	G2P	PP	G1B	G3B KB	G2B	РВ	Н	


Termi- nal Dia-				PΙ		-	BER					
gram 1	2	3	4	5	6	7	8	9	10	11	12	TC
<b>12FA</b> H	IC	IC	IC	K,IS	G	NC	IC	IC	10	IC	Н	Р
12FB H	NC	G2	K,G3	G1	G2	NC	G2	G1	K,G3	G2	Н	Р
12FC H	PD	NC	KD	PP	NC	IC	KP G3P	G1P	G2P	G11	РН	
12FE H	PT3	KT3	KT1	PT2	KT2	GT2	NC	GT1	PT1	GT3	Н	
1 <b>2FJ</b> H	K	G2	G3	G1	NC	NC	IC	NC	G3	NC	Н	P
12FK H	K	G2	G3	NC	NC	Р	NC	NC	G3	G1	H	
12FL H	K	G1	G3	G2	IC	P	10	G2	G3	G1	Н	
12FM H	PT	NC	GT	KT	IS	NC	G1P	KP G3P	G2P	PP	Н	
12FN H	PD	NC	KD	PB	NC	IC	KB G3B	G1B	G1B	G2E	Н	
12FP H	KT2	PT2	GT2	KT1 JS	GT1	PT1	G1P	G2P	PP	KP, G3P	IS H	
I <b>2FQ</b> H	PT2	KT2	KT1	IC	NC	NC	IS	GT1	PT1	GT2	Н	
IZFR H	PT2	KT2	KT1	NC	NC	PT1	NC	GT1	PT1	GT2	H	
I <b>2FS</b> H	PD	NC	KD	PP	NC	IC	KP G3P	G1P	10	G2P	Н	
1 <b>2FU</b> H	PP2	G2P2	G3P2	KP2	G1P2	PP1	G3P1 IS	G2P1	KP1	G1P	1 H	
2FV H,K IS	H,K IS	IC	NC	H,K IS	H,K IS	NC	н	K	NC	IC	Н	P
2FX H	NC	NC	P	IC	IC	K	IC	IC	P	NC	Н	
2FY H	K	G2	G3	G1	NC	IC	NC	IC	G3	G2	H	P
2GA H	NC	NC	P	1C	NC	K	NC	IC	P	NC	Н	
2GC H	PP	GT2	KT2	GT1	KT1	PT1	KP,IS G3P	PT2	G2P	G1P	Н	
26D H	K	G2	G3	G1	NC	NC	NC	IC	G3	IC	Н	Р
2GF H	KP2	G1P2	G2P2	PP2	G3P2 IS	G1P1	KP1	G2P1	G3P1 IS	PP1	H	
2 <b>6H</b> H	NC	G2	G3	G1	NC	IC	NC	IC	K	IC	Н	Р
2 <b>G</b> J H	K	G2	G3	G1	NC	IC	NC	IC	G3	IC	Н	Р
ZGK H	IC	IC	Р	IC	IC	K	IC	IC	Р	IC	Н	


Termi nat Dia- gram	1	2	3	4	P 1	N N	U ₇	B E F	9	10	11	12	TC
12GL	Н	GIP	G2P	KP,IS G3P	KT2	PT2	KT1	GT2	PT1	GT1	PP	Н	
12 <b>6</b> \$	Н	PP	GT2	KT2	GT1	KT1 G3P IS	PT1	KP	PT2	G2P	G1F	Н	
12GU	Н	NC	G2	G3	G1	NC	IC	NC	IC	K	IC	Н	Р
12GV	Н	IC	IC	NC	IC	Н	IC	IC	IC	NC	IC	Н	Р
12GW	Н	K	G2	G3	G1	NC	IC	NC	G1	G3	G2	Н	Р
12 <b>G</b> Y	Н	G	ВР	K	IC	IC	Р	IC	IC	ВР	G	Н	
2 <b>G</b> Z	Н	PT2	GT2	NC	PP	IC	K,G3P	G1P	G2P	GT1	PT1	Н	
2HA	H,K IS	H,K IS	IC	NC	H,K IS	H,K IS	NC	IC	H,K IS	NC	IC	Н	Р
2HB	Н	G3P2	PP2	G2P2	KP2	G1P2	G1P1	KP1	G2P1	PP1	G3P1	Н	
2HC I	Н	IC	(C	IC	K	G	IC	10	IS	IC	1C	Н	P
2HD	Н	KP2	G1P2	G2P2	PP2	G3P2 IS	G3P1 IS	PP1	G2P1	KP1	G1P	1 H	
2HE }	Н	PP	NC	G3P	GT	KT	PT	IS	KP	G2P	G1P	Н	
2HF	1	IC	NC	Р	IC	IC	K	IC	IC	Р	NC	Н	
2HG H	1	PT3	K	PT2	NC	PT1	NC	GT1	NC	GT2	GT3	Н	
2HJ	1	GT	PT	KT	G1P	G1P	KP	G2P	G3P IS	NC	PP	Н	
2HK f	7,18	F,IS	IC	NC	F,IS	F,IS	NC	F	F,IS	NC	IC	F	P
2HL H	ł	IC	IC	K,G3	GI	NC	IC	NC	IC	K,G3	G2	Н	Р
2HN H	ł	PT2	GT2	PT1	KT1	GT1	KT2 G3P	G1P	KP	G2P	PP	Н	
2HR ⊦	1	PT2	GT2	PP	G2P	IC	KT2 KP G3P	G1P	PT1	KT1	GT1	Н	
<b>2HT</b> H		PD	NC	KD	PP	NC	IC	KP G3P	G1P	NC	G2P	Н	
<b>2HU</b> H		PT3	K	PT2	NC	PT1	IC	GTI	IC	GT2	GT3	Н	
2HWH		PT2	PP	G2P	G1P	GIP KP	KT2	KTI	GT1	PTI	GT2	H	
RX H		IC	NC	Р	IC	IC	IC	IC	IC	Р	NC	Н	K

ermi- nal					PIN	ı N I	J M B	ΕR					
Dia- ram	1	2	3	4	5	6	7		9	10	11	12	TC
2HY	H,K IS	H,K IS	IC	NC	H,K IS	IC	IC	Н	H,K IS	NC	IC	Н	P
2JA	Н	K	G2	G3	G1	NC	H	NC	G2	63	62	H	P
2JB	H,K IS	H,K IS	IC	NC	H,K IS	IC	H,K IS	H	H,K IS	NC	NC	Н	P
12JF	H	K	62	G3	G1	NC	NC	NC	IC	63	62	H	P
17— BH25		G1	G3	H	Н	G2	G2	G3	K				P
4 <b>0</b> 7A	HT2	KT2	GT2	PT2	HM,IS	PT1	GT1	KT1	HT1				
<b>951</b> *	K	P											
991*	<b>P</b> F	K F	OR										P
5672	P	G2	F+	G1	F—,G3								
5678	P	G2	F—,IS G3	G1	F++ G3								
5734				H	G	Н	K,IS	SHELL	P				
5783	*K		P		K								
6368	G1TR1	K IS	G1TR2	HTR1	HT/R2	PTR1	G2TR1 G2TR2	PTR2	HM				
6977	F	P	G	F									
8888	Ŕ	K		K		K	SHELL	G		Н		H	P
B <b>958</b>	Н	K	62	G3	G1	K	IC	NC	G1	63	62	H	P


# Outlines








2-27/32 3-1/16 3-9/32 3-1/2 2-17/32 2-29/32 2-23/32 3-3/16 2-7/16 ± 1/8 2-15/32 MAX. 2-7/8 ± 1/8 3-1/4 MAX. 7A 7B 7C 7D 7E 7F 7G 7H 2-1/8 ± 1/8 2-5/8 MAX  $2-1/8 \pm 1/8$ 2-15/16




X 1.875 2.375 2.625 2.875 3.050 3.125 1.250-1.500 1.750-2.000 2.000-2.250 2.250-2.500 2.770 MAX. 2.500-2.750 2.750-3.000 8A 8B 8C 8D 8E 8F 3 375




9C

1.188 MAX. } z MAX. 19 MÄX. 11 1 19 LARGE-BUTTON NEONOVAL 9-PIN -10-


2.630 2.900 2.930 3.230 4.125 3.110 Z 2.320 2.620 2.620 2.920 3.750 2.730 1.770-2.010 2.070-2.310 2.070-2.310 2.370-2.610 10A 10B 10C 10D 10E 10F 106 3.080 3.511 2.770 3.169 2.68 10F





3.000 3.080 3.110 3.410 Y 2,620 2,700 2,730 3,010 2,580 2.100-2.280 2.050-2.230 2.210-2.390 2.510-2.690 2.060-2.240 11B 11C 11D




X Y 2-9/32 1-3/4 2-25/32 2-1/4 3-5/32 2-5/8 12B










All measurements in inches.







-	1.5	62 MA	(.  •		MALL AP
				Y	X MAX.
- (	<b>A</b> A	<del>a</del>			
	/ -	MI			
Z	_ LA	RGE-BI OVAR 9	-PIN	N	
		_	32-	-	
		X		Y	_
	32A	3.505	2.87	5-3.12	5






All measurements in inches.





All measurements in inches.



- 1-Glass Envelope
- 2-Internal Shield
- 3-Plate
- 4-Grid No. 3 (Suppressor)
- 5-Grid No. 2 (Screen)
- 6-Grid No. 1 (Control Grid)
- 7-Cathode
- 8-Heater
- 9-Exhaust Tip
- 10-Getter
- 11 Spacer Shield Header
- 12—Insulating Spacer
- 13-Spacer Shield
- 14-Inter-Pin Shield
- 15—Glass Button-Stem Seal
- 16-Lead Wire
- 17-Base Pin
- 18-Glass-to-Metal Seal

## Structure of a Miniature Tube

# Resistance-Coupled Amplifiers

R ESISTANCE-COUPLED, audiofrequency voltage amplifiers utilize simple components and are capable of providing essentially uniform amplification over a relatively wide frequency, range.

#### Suitable Tubes

In this section, data are given for 48 types of tubes suitable for use in resistance-coupled circuits. These types include low- and high-mu triodes, twin triodes, triode-connected pentodes, and pentodes. The accompanying key to tube types will assist in locating the appropriate data chart.

### **Circuit Advantages**

For most of the types shown, the data pertain to operation with cathode bias; for all of the pentodes, the data pertain to operation with series screengrid resistor. The use of a cathode-bias resistor where feasible and a series screen-grid resistor where applicable offers several advantages over fixed-voltage operation.

The advantages are: (1) effects of possible tube differences are minimized; (2) operation over a wide range of plate-supply voltages without appreciable change in gain is feasible; (3) the low frequency at which the amplifier cuts off is easily changed; and (4) tendency toward motorboating is minimized.

### **Number of Stages**

These advantages can be enhanced by the addition of suitable decoupling filters in the plate supply of each stage of a multi-stage amplifier. With proper filters, three or more amplifier stages can be operated from a single powersupply unit of conventional design with-

Type Cha	rt No.	Type Cha	rt No.
3AU6 3AV6 3BC5/ 3CE5 3CB6/ 3CF6	2 9 11 11	6FQ7/ 6CG7 6SL7GT 6SN7GTB 6T8A 7AU7	8 5 8 5 3
4AU6 4AV6 4BQ7A/ 4BZ7 4CB6 5BK7A	2 9 10 11 10	8CN7 8FQ7/ 8CG7 9AU7 12AT6 12AT7/ ECC81	5 8 3 5
5BQ7A 5T8 6AB4 6AG5 6AT6 6AU6A	10 5 4 11 5 2	12AU6 12AU7A/ ECC82 12AV6 12AX7A/ ECC83	2 3 9 9
6AV6 6BC5/ 6CE5 6BK7B 6BQ7A/ 6BZ7/ 6BS8	9 11 10	12AY7 12FQ7 12SL7GT 12SN7GTA 19T8 20EZ7	1 8 5 8 5 9
6C4 6CB6A/ 6CF6 6CN7 6EU7	3 11 5 9	5879P 5879T 7025 7199P 7199T	6 7 9 12 13

T = Triode Unit or Triode Connection
P = Pentode Unit or Pentode Connection

**KEY TO CHARTS** 

out encountering any difficulties due to coupling through the power unit. When decoupling filters are not used, not more than two stages should be operated from a single power-supply unit.

## Symbols Used in Resistance-Coupled Amplifier Charts

 $C = Blocking Capacitor (\mu F).$  $C_k = Cathode Bypass Capacitor$ 

 $(\mu \mathbf{F})$ .

C_{sa} = Screen-Grid Bypass Capacitor

 $(\mu f)$ .

 $E_{bb}$  = Plate-Supply Voltage (volts). Voltage at plate equals platesupply voltage minus drop in  $R_{\nu}$ 

and  $R_k$ .

R_k = Cathode

= Cathode Resistor (ohms).

R₂ = Screen-Grid Resistor

(megohms).

R_g = Grid Resistor (megohms) for following stage.

 $R_{\nu}$  = Plate Resistor (megohms).

V.G. = Voltage Gain.


E_o = Output Voltage (peak volts). This voltage is obtained across R_x (for following stage) at any frequency within the flat region of the output vs. frequency curve, and is for the condition where the signal level is adequate to swing the grid of the resistance-coupled amplifier tube to the point where its grid starts to draw current.

Note: The listed values for E₀ are the peak output voltages available when the grid is driven from a low-impedance source. The listed values for the cathode resistors are optimum for any signal source. With a high-impedance source, protection against severe distortion and loss of gain due to input loading may be obtained by the use of a coupling capacitor connected directly to the input grid and a high-value resistor connected between the grid and ground.

### **General Circuit Considerations**

In the discussions which follow, the frequency (f₂) is that value at which the high-frequency response begins to fall off. The frequency (f₁) is that value at which the low-frequency response drops below a satisfactory value, as discussed below. A variation of 10 per cent in values of resistors and capacitors has only slight effect on perform-

ance. One-half-watt resistors are usually suitable for  $R_{\pi^{\pm}}$ ,  $R_{\mu}$ ,  $R_{\mu}$ , and  $R_{k}$  resistors. Capacitors C and  $C_{\pi^{\pm}}$  should have a working voltage equal to or greater than  $E_{bb}$ . Capacitor  $C_{k}$  may have a low working voltage in the order of 10 to 25 volts



# Triode Amplifier Heater-Cathode Type

Capacitors C and  $C_k$  have been chosen to give an output voltage equal to 0.8  $E_0$  for a frequency  $(f_1)$  of 100 Hz. For any other value of  $f_1$ , multiply values of C and  $C_k$  by  $100/f_1$ . In





Diagram No. 1

the case of capacitor Ck, the values shown in the charts are for an amplifier with dc heater excitation; when ac is used, depending on the character of the associated circuit, the gain, and the value of f₁, it may be necessary to increase the value of Ck to minimize hum disturbances. It may be desirable to operate the heater at a positive voltage of from 15 to 40 volts with respect to the cathode. The voltage output at  $f_1$  of "n" like stages equals  $(0.8)^n \times E_0$ , where E_o is the peak output voltage of final stage. For an amplifier of typical construction, the value of f2 is well above the audio-frequency range for any value of R_p.

## Pentode Amplifier

Heater-Cathode Type

Capacitors C,  $C_k$ , and  $C_{g^2}$  have been chosen to give an output voltage equal to  $0.7 \times E_o$  for a frequency (f₁) of 100 cycles. For any other value of f₁, multiply values of C,  $C_k$ , and  $C_{g^2}$  by  $100/f_1$ . In the case of capacitor  $C_k$ , the values shown in the charts are for



an amplifier with dc heater excitation: when ac is used, depending on the character of the associated circuits, the voltage gain, and the value of f., it may be necessary to increase the value of Ck to minimize hum disturbances. It may be desirable to operate the heater at a positive voltage of from 15 to 40 volts with respect to the cathode. The voltage output at f1 for "n" like stages equals (0.7)"  $\times$  E₀ where E_o is peak output voltage of final stage. For an amplifier of typical construction, and for R_n values of 0.1, 0.25, and 0.5 megohm, approximate values of f₂ are 20000, 10000, and 5000 Hz, respectively.

Eph	R _P	R _s	Rgz	Rk	C _{E2}	Ck	C	E.*	V.G.
90	0.1 0.24 0.51	0.24 0.51 1.0	=	1800 3700 7800	_	=	_	13 14 16	24 26 27
180	0.1 0.24 0.51	0.24 0.51 1.0		1300 2800 5700	=	=	=	31 33 33	27 29 30
300	0.1 0.24 0.51	0.24 0.51 1.0	-	1200 2300 4800	=	=	=	58 30 56	28 30 31



12AY7

Diagram 1

[•] One triode unit.

^{*} Peak volts.

^A Coupling capacitors should be selected to give desired frequency response. Cathode resistors should be adequately bypassed.

	,									
	Ebb	R _p	R _g	R _{g2}	R _k	C _{g2}	C*		E.*	V.G.
3AU6 4AU6 6AU6A	90	0.22 0.22 0.22 0.47 0.47 0.47 1.0	0.22 0.47 1.0 0.47 1.0 2.2 1.0 2.2	0.340 0.370 0.380 1.00 1.00 1.00 1.90 2.40	2700 2900 3100 6000 6200 6300 10800 13100	0.057 0.050 0.050 0.027 0.023 0.027 0.017 0.017	5.8 5.4 5.3 2.8 2.7 2.8 1.7	0.0081 0.0055 0.0034 0.0042 0.0027 0.0019 0.0025 0.0017	16 22 25 13 17 25 10	79 104 125 105 137 161 139 184
12AU6  See Circuit Diagram 2	180	0.22 0.22 0.22 0.47 0.47 0.47 1.0	0.22 0.47 1.0 0.47 1.0 2.2 1.0 2.2	0.520 0.520 0.520 1.05 1.15 1.20 2.40 2.70	1340 1390 1420 2700 2880 2960 5500 6000	0.059 0.059 0.059 0.039 0.037 0.036 0.028 0.022	8.8 8.7 8.6 5.5 5.4 5.4 3.2 2.8	0.0081 0.0053 0.0032 0.0041 0.0027 0.0019 0.0023 0.0015	31 43 48 34 43 50 33 40	143 192 223 189 249 294 230 323
	300	0.22 0.22 0.22 0.47 0.47 0.47 1.0	0.22 0.47 1.0 0.47 1.0 2.2 1.0 2.2	0.530 0.540 0.540 1.15 1.22 1.31 2.50 2.80	780 783 800 1590 1650 1720 3300 3500	0.077 0.077 0.077 0.057 0.049 0.045 0.036 0.031	13.2 13.2 13.1 8.4 7.4 7.2 5.3 4.2	0.0082 0.0053 0.0033 0.0045 0.0027 0.0017 0.0022 0.0015	53 65 74 56 72 82 57 72	200 270 316 275 357 418 352 466
<b>3</b>	90	0.047 0.047 0.047 0.1 0.1 0.22 0.22 0.22	0.047 0.1 0.22 0.1 0.22 0.47 0.22 0.47 1.0		1600 1800 2000 3000 3800 4500 6800 9500 11500		3.2 2.5 2.0 1.6 1.1 1.0 0.7 0.5 0.43	0.061 0.033 0.015 0.032 0.015 0.007 0.015 0.0065 0.0035	9 11 14 10 15 18 14 20 24	10 11 11 11 11 11 11 11
6C4 7AU7* 9AU7* 12AU7A/ ECC82* See Circuit Diagram 1	180	0.047 0.047 0.047 0.1 0.1 0.1 0.22 0.22 0.22	0.047 0.1 0.22 0.1 0.22 0.47 0.22 0.47 1.0	= = = = = = = = = = = = = = = = = = = =	920 1200 1400 2000 2800 3600 5300 8300		3.9 2.9 2.5 1.9 1.4 1.1 0.8 0.56 0.48	0.062 0.037 0.016 0.032 0.016 0.007 0.015 0.007 0.0035	20 26 29 24 33 40 31 44 54	11 12 12 12 12 12 12 12 12 12
	300	0.047 0.047 0.047 0.1 0.1 0.1 0.22 0.22 0.22	0.047 0.1 0.22 0.1 0.22 0.47 0.22 0.47 1.0		870 1200 1500 1900 3000 4000 5300 8800 11000		4.1 3.0 2.4 1.9 1.3 1.1 0.9 0.52 0.46	0.065 0.034 0.016 0.032 0.016 0.007 0.015 0.007 0.0035	38 52 68 44 68 80 57 82 92	12 12 12 12 12 12 12 12 12

[•] One triode unit.

^{*} Peak volts.

Ebb	R,	Rg	Rgo	Rk	Ces	Ck	C	E.*	V.6.	
90	0.1 0.1 0.1 0.22 0.22 0.22 0.47 0.47	0.1 0.22 0.47 0.22 0.47 1.0 0.47 1.0 2.2	- - - - - - -	2680 3060 3390 5500 6300 6930 10900 12500 13500	- - - - - - -	2.4 2.00 1.84 1.33 1.01 0.92 0.63 0.52 0.47	0.026 0.014 0.0074 0.0136 0.0067 0.0038 0.007 0.0043 0.0031	8 11 13 10 14 15 13 14 18	24 25 28 25 28 28 28 26 28 28	6AB4 12AT7/
180	0.1 0.1 0.22 0.22 0.22 0.47 0.47	0.1 0.22 0.47 0.22 0.47 1.0 0.47 1.0 2.2		1407 1674 1786 2890 3860 4660 6960 8450 9600	-	3.6 3.0 2.6 1.75 1.34 1.14 0.83 0.67 0.55	0.029 0.016 0.0083 0.0140 0.0077 0.0047 0.0075 0.0046 0.0032	20 28 31 24 35 42 31 39 45	31 33 34 33 33 33 31 32 32	See Circuit Diagram 1
300	0.1 0.1 0.22 0.22 0.22 0.22 0.47 0.47 <b>0.47</b>	0.1 0.22 0.47 0.22 0.47 1.0 0.47 1.0 2.2		974 1404 2169 2510 4200 4950 5700 8720 9700		4.0 3.1 2.5 1.9 1.3 1.1 0.90 0.62 0.57	0.028 0.015 0.0083 0.015 0.0074 0.0046 0.0076 0.0041 0.0030	37 57 78 50 78 85 57 81 88	34 34 33 33 33 32 33 32 32	
90	0.1 0.1 0.1 0.22 0.22 0.22 0.47 0.47	0.1 0.22 0.47 0.22 0.47 1.0 0.47 1.0 2.2		4200 4600 4800 7000 7800 8100 12000 14000 15000		2.5 2.2 2.0 1.5 1.3 1.1 0.83 0.7 0.6	0.025 0.014 0.0065 0.013 0.007 0.0035 0.006 0.0035 0.002	5.4 7.5 9.1 7.3 10 12 10 14 16	22 27 30 30 34 37 36 39 41	<b>5</b>
180	0.1 0.1 0.22 0.22 0.22 0.47 0.47 0.47	0.1 0.22 0.47 0.22 0.47 1.0 0.47 1.0 2.2		1900 2200 2500 3400 4100 4600 6600 8100 9100		3.6 3.1 2.8 2.2 1.7 1.5 1.1 0.9 0.8	0.027 0.014 0.0065 0.014 0,0065 0.0035 0.0065 0.0035	19 25 32 24 34 38 29 38 43	30 35 37 38 42 44 44 46 47	6AT6 6CN7 6SL7GT* 6T8A 8CN7 12AT6
300	0.1 0.1 0.22 0.22 0.22 0.47 0.47 0.47	0.1 0.22 0.47 0.22 0.47 0.1 0.47 1.0 2.2		1500 1800 2100 2600 3200 3700 5200 6300 7200		4.4 3.6 3.0 2.5 1.9 1.6 1.2 1.0	0.027 0.014 0.0065 0.013 0.0065 0.0035 0.006 0.0035 0.002	40 54 63 51 65 77 61 74 85	34 38 41 42 46 48 48 50	12SL7GT° 19T8 See Circuit Diagram 1

[·] One triode unit.

^{*} Peak volts.

	Ebb	Rp	Re	R _{g2}	Rk	C _{g2}	Ck	C	E.*	V.G.
As Pentode: 5879	80	0.1 0.1 0.1 0.22 0.22 0.22 0.47 0.47	0.1 0.22 0.47 0.22 0.47 1.0 0.47 1.0 2.2	0.35 0.35 0.35 0.80 0.80 0.80 1.9 1.9	1700 1700 1700 3000 3000 3000 7000 7000	0.044 0.046 0.047 0.034 0.035 0.036 0.021 0.022 0.023	4.6 4.5 4.4 3.2 3.1 3.0 1.8 1.7 1.7	0.020 0.012 0.006 0.010 0.005 0.003 0.005 0.003 0.002	13 17 20 15 21 24 21 25 28	29 39 47 43 59 67 59 75
See Circuit Diagram 2	180	0.1 0.1 0.2 0.22 0.22 0.22 0.47 0.47	0.1 0.22 0.47 0.22 0.47 1.0 0.47 1.0 2.2	0.35 0.35 0.35 0.80 0.80 0.80 1.9 1.9	700 700 700 1200 1200 1200 2500 2500 2500	0.060 0.062 0.064 0.045 0.046 0.048 0.033 0.034 0.035	7.4 7.3 7.2 5.5 5.3 5.2 3.5 3.4 3.3	0.020 0.012 0.006 0.010 0.005 0.003 0.005 0.003	24 28 33 24 31 34 27 32 37	39 56 65 65 87 101 98 122 140
1	300	0.1 0.1 0.22 0.22 0.22 0.47 0.47 0.47	0.1 0.22 0.47 0.22 0.47 1.0 0.47 1.0 2.2	0.35 0.35 0.35 0.80 0.80 0.80 1.3 1.3	300 300 300 600 600 600 1200 1200	0.075 0.077 0.080 0.056 0.057 0.058 0.044 0.046 0.047	10.8 10.6 10.5 7.9 7.5 7.4 5.3 5.2 5.1	0.020 0.012 0.006 0.010 0.005 0.003 0.005 0.003	25 32 35 28 37 41 34 42 48	51 68 83 81 109 123 125 152 174
7	98	0.047 0.047 0.047 0.1 0.1 0.1 0.22 0.22	0.047 0.1 0.22 0.1 0.22 0.47 0.22 0.47 1.00	- - - - - - - - - - -	1800 2100 2200 3200 3900 4300 6200 8100 9000		2.9 2.4 2.3 1.8 1.3 1.0 0.87 0.53 0.49	0.060 0.033 0.016 0.027 0.015 0.007 0.015 0.006 0.003	9 12 14 10 13 16 12 16	10 11 21 12 13 13 13 13 14
5879 See Circuit Diagram 1	180	0.047 0.047 0.047 0.1 0.1 0.22 0.22	0.047 0.1 0.22 0.1 0.22 0.47 0.22 0.47 1.00		1200 1600 1800 2200 2900 3400 4500 6400 8200		3.5 2.6 2.4 1.9 1.35 1.1 0.92 0.61 0.52	0.063 0.033 0.016 0.031 0.015 0.007 0.015 0.006 0.003	21 29 35 26 33 40 28 39 47	12 13 13 14 14 14 14 14
	390	0.047 0.047 0.047 0.1 0.1 0.1 0.22 0.22	0.047 0.1 0.22 0.1 0.22 0.47 0.22 0.47 1.00		1100 1500 1700 2000 3400 3700 4300 7200 7400		3.9 2.8 2.5 2.1 1.4 1.1 0.97 0.63 0.63	0.063 0.033 0.016 0.032 0.015 0.007 0.015 0.007 0.003	42 65 71 45 74 83 50 88 94	13 13 14 15 15 15 15 15 15
•	Peak v	Oits								

Еьь	R _p	Rg	R _{g2}	Rk	C _{g2}	Ck	C	E,*	V.G.
90	0.047 0.047 0.047 0.1 0.1 0.1 0.22 0.22 0.22	0.047 0.1 0.22 0.1 0.22 0.47 0.22 0.47 1.00		1870 2230 2500 3370 4100 4800 7000 9100 10500		3.1 2.5 2.1 1.8 1.3 1.1 0.80 0.65 0.60	0.063 0.031 0.016 0.034 0.015 0.006 0.013 0.007 0.004	14 18 20 15 20 23 16 22 25	13 14 14 14 14 15 14 15 14
180	0.047 0.047 0.047 0.1 0.1 0.1 0.22 0.22 0.22	0.047 0.1 0.22 0.1 0.22 0.47 0.22 0.47 1.00	-	1500 1860 2160 2750 3550 4140 5150 7000 7800		3.6 2.9 2.2 1.8 1.4 1.3 1.0 0.71 0.61	0.066 0.055 0.015 0.028 0.015 0.007 0.016 0.007	33 41 47 35 45 51 36 45 51	14 14 15 15 16 16 16
300	0.047 0.047 0.047 0.1 0.1 0.1 0.22 0.22 0.22	0.047 0.1 0.22 0.1 0.22 0.47 0.22 0.47 1.00	- - - - - - - -	1300 1580 1800 2500 3130 3900 4800 6500 7800		3.6 3.0 2.5 1.9 1.4 1.2 0.95 0.69 0.58	0.061 0.032 0.015 0.031 0.014 0.0065 0.015 0.0065 0.0035	59 73 83 68 82 96 68 85 96	14 15 16 16 16 16 16 16
99	0.1 0.1 0.1 0.22 0.22 0.22 0.47 0.47	0.1 0.22 0.47 0.22 0.47 1.0 0.47 1.0 2.2		4400 4700 4800 7000 7400 7600 12000 13000 14000		2.7 2.4 2.3 1.6 1.4 1.3 0.9 0.8 0.7	0.023 0.013 0.007 0.012 0.006 0.003 0.006 0.003 0.002	5 6 8 6 9 11 9	29 35 41 39 45 48 48 52 55
180	0.1 0.1 0.22 0.22 0.22 0.47 0.47 0.47	0.1 0.22 0.47 0.22 0.47 1.0 0.47 1.0 2.2		1800 2000 2200 3000 3500 3900 5800 6700 7400		4.0 3.5 3.1 2.4 2.1 1.8 1.3 1.1	0.025 0.013 0.006 0.012 0.006 0.003 0.006 0.003 0.002	18 25 32 24 34 39 30 39	40 47 52 53 59 63 62 66 68
308	0.1 0.1 0.22 0.22 0.22 0.47 0.47 0.47	0.1 0.22 0.47 0.22 0.47 1.0 0.47 1.0 2.2		1300 1500 1700 2200 2800 3100 4300 5200 5900	- - - - - - - - - -	4.6 4.0 3.6 3.0 2.3 2.1 1.6 1.3	0.027 0.013 0.006 0.013 0.006 0.003 0.006 0.003 0.002	43 57 66 54 69 79 62 77 92	45 52 57 59 65 68 69 73 75

6FQ7/ 6CG7. 6SN7GTB. 8FQ7/ 8CG7. 12FQ7• 12SN7GTA

> See Circuit Diagram 1



**3AV6 4AV6 6AV6** 6EU7* **12AV6** 12AX7A/ **ECC83**° 20EZ7* 7025

See Circuit Diagram 1

[·] One triode unit.

[·] Peak volts.

10
----

4BQ7A/ 4BZ7 5BK7A* 5BQ7A* 6BK7B* 6BQ7A/ 6BZ7/ 6BS8°

See Circuit Diagram 1

(	ĺ	<u> </u>	)
/	•	_	J

3BC5/ 3CE5 3CB6/ **3CF6 4CB6 6AG5** 6BC5/ 6CE5 6CB6A/ 6CF6

See Circuit Diagram 2

Еьь	R _p	Re	R _{e2}	Rx	C _{e2}	C _k	C	E.*	V.G.
90	0.047 0.047 0.047 0.1 0.1 0.1 0.22 0.22 0.22	0.047 0.10 0.22 0.1 0.22 0.47 0.22 0.47 1.0	- - - - - - -	1580 1760 1820 2920 3570 4020 6040 7500 8800		4.0 3.5 3.0 2.1 1.7 1.4 0.98 0.78 0.63	0.058 0.032 0.015 0.029 0.015 0.0075 0.0135 0.0075 0.0036	9 13 16 12 17 20 16 21 25	18 19 20 19 20 20 20 19 20
180	0.047 0.047 0.047 0.10 0.10 0.10 0.22 0.22	0.047 0.1 0.22 0.1 0.22 0.47 0.22 0.47 1.0		694 817 905 1596 1630 1860 3950 4500 5530		6.0 4.4 4.0 2.80 2.30 2.00 1.24 0.96 0.79	0.062 0.032 0.0155 0.030 0.0152 0.0073 0.0150 0.0072 0.0038	25 32 35 30 32 38 35 41 49	23 24 25 23 24 24 22 23 23
300	0.047 0.047 0.047 0.10 0.10 0.10 0.22 0.22	0.047 0.1 0.22 0.10 0.22 0.47 0.22 0.47 1.0		438 542 644 1009 1332 1609 2623 3900 4920		6.70 5.50 4.30 3.5 2.5 2.1 1.5 1.1 0.88	0.062 0.032 0.016 0.031 0.015 0.0074 0.015 0.0073 0.0039	38 48 57 42 56 64 50 70 84	26 27 27 25 26 25 24 24 24
90	0.22 0.22 0.22 0.47 0.47 1.0	0.22 0.47 1.0 0.47 1.0 2.2 1.0 2.2	0.480 0.480 0.500 1.04 1.10 2.50 2.50	3800 3800 4400 7200 7700 8400 16000 18600	0.046 0.049 0.045 0.033 0.033 0.031 0.018 0.016	5.5 5.5 5.3 2.9 2.8 2.6 1.4 1.2	0.0084 0.0054 0.0034 0.0044 0.0029 0.0020 0.0023 0.0017	10 16 23 10 15 18 10	89 114 128 111 133 152 118 139
180	0.22 0.22 0.22 0.47 0.47 0.47 1.0	0.22 0.47 1.0 0.47 1.0 2.2 1.0 2.2	0.550 0.620 0.650 1.00 1.00 2.60 2.60	1600 1800 1900 3400 3500 3800 7300 7400	0.072 0.062 0.062 0.059 0.059 0.059 0.029	9.5 8.5 8.5 6.0 6.0 5.8 2.7 2.7	0.0090 0.0053 0.0034 0.0048 0.0031 0.0020 0.0022 0.0016	30 36 43 34 41 46 33 38	161 208 239 183 229 262 227 281

0.0085

0.0055

0.0033

0.0045

0.0029

0.0019

0.0023

0.0015

223

288 334

285

363

416

334 427

51

51

69

0.22

0.22 0.22 0.47

0.47

0.47

1.0

1.0

300

0.22

0.47

1.0

0.47

1.0

2.2

1.0

2.2

0.600

0.680

0.700

1.25 1.34 1.53

2.60

3.00

980

1090

1150

2000

2150

2350

4000

4700

0.085

0.084

0.081

0.064

0.061

0.057

0.044

0.038

13.0

12.0

11.0

7.9

7.6

7.1 5.2

4.3

[·] One triode unit.

[•] Peak volts.

Еьь	R,	Re	R _{g2}	Rk	C _{g2}	C _k	C	E,*	V.G.	
90	0.22 0.22 0.22 0.47 0.47 0.47 1.0 1.0	0.22 0.47 1.0 0.47 1.0 2.2 1.0 2.2	0.560 0.600 0.640 0.870 0.980 1.00 2.00 2.20	3700 3900 4200 6000 6700 6700 12200 12800	0.046 0.043 0.039 0.036 0.044 0.043 0.021 0.024	4.50 4.30 4.00 2.70 3.00 2.80 1.44 1.74	0.0090 0.0055 0.0033 0.0046 0.0030 0.0020 0.0028 0.0016	12 17 19 16 22 25 15	73 95 109 95 113 131 119 167	7199
180	0.22 0.22 0.22 0.47 0.47 0.47 1.0	0.22 0.47 1.0 0.47 1.0 2.2 1.0 2.2	0.530 0.600 0.650 1.12 1.40 1.57 2.50 3.40	1570 1730 1820 3200 3500 3740 6500 7500	0.069 0.064 0.061 0.053 0.042 0.040 0.039 0.026	7.50 7.40 7.30 5.30 5.10 5.40 2.80 2.30	0.0088 0.0064 0.0034 0.0046 0.0028 0.0019 0.0024 0.0015	32 38 45 35 40 45 34 39	82 164 190 147 209 250 179 277	Pentode Unit
300	0.22 0.22 0.22 0.47 0.47 0.47 1.0	0.22 0.47 1.0 0.47 1.0 2.2 1.0 2.2	0.600 0.670 0.720 1.25 1.43 1.45 3.00 3.30	9200 1010 1100 1950 3210 2200 4100 4340	0.086 0.076 0.076 0.060 0.053 0.055 0.040 0.037	11.2 10.5 10.0 7.0 6.4 6.3 4.2 3.6	0.0085 0.0052 0.0033 0.0044 0.0027 0.0019 0.0022 0.0016	52 66 77 41 72 82 57 74	182 236 257 221 296 345 295 378	See Circuit Diagram 2
90	0.047 0.047 0.047 0.10 0.10 0.10 0.22 0.22	0.047 0.1 0.22 0.1 0.22 0.47 0.22 0.47 1.0		1292 1401 1470 2630 3090 3440 6550 8270 9130		3.3 2.8 2.4 1.60 1.24 1.10 0.70 0.51 0.44	0.060 0.032 0.016 0.029 0.015 0.008 0.015 0.0077 0.0045	8 10 11 9 12 14 12 16 18	12 13 13 13 13 14 12 12 12	13)
180	0.047 0.047 0.047 0.10 0.10 0.10 0.22 0.22	0.047 0.1 0.22 0.1 0.22 0.47 0.22 0.47 1.0	- - - - - - - - - - - - - - - - - - -	723 836 948 1543 2002 2522 4390 6122 8060	      	4.0 3.5 2.9 2.0 1.6 1.2 0.79 0.57 0.47	0.061 0.032 0.016 0.031 0.016 0.0082 0.015 0.0078 0.0046	16 20 24 17 24 30 24 33 41	14 14 15 14 14 13 13 13 12 12	<b>7199</b> Triode Unit
304	0.047 0.047 0.047 0.10 0.10 0.10 0.22 0.22 0.22	0.047 0.1 0.22 0.1 0.22 0.47 0.22 0.47 1.0	- - - - - - - - - - - - - - - - - - -	534 726 840 1117 1613 2043 3133 4480 4930		4.0 3.6 3.0 2.3 1.7 1.31 0.93 0.69 0.56	0.061 0.031 0.015 0.031 0.0155 0.0078 0.015 0,0079 0.0045	27 38 44 26 41 51 36 51 55	15 15 15 15 14 14 14 13 13	See Circuit Diagram 1

^{*} Peak volts.

## Replacement Guide— Entertainment Receiving Types

This guide was prepared to assist in the selection of current direct replacement tube types for foreign and domestic receiving tubes. Domestic and foreign receiving tubes are listed in numerical alphabetical sequence with the RCA type that can be used as a direct replacement. Types replaceable only by themselves are not included. Whenever possible, a defective tube should be replaced by a type having the same number, or a superseding number.

The primary considerations in selecting direct replacement tubes for this guide are: (1) mechanical interchangeability, (2) electrical interchangeability, (3) performance characteristics similar to that of the original equipment. All replacements shown are unilateral—that is the RCA tube can replace the indicated type. The reverse however, is not always permissible because of differences in electrical ratings. In some compact equipment designs, space limitations may make the suggested replacement impractical.

Type to be Replaced	Replace by RCA Type
OZ4, OZ4A, OZ4G	0Z4A/0Z4
1AE4	1L4*, 1T4*
1AF4	104*
1AM4	1T4
1AQ5 1AR5	1R5* 1U5
1A\$5	105
1B3GT	1G3GTA/1B3GT
1B X2	1X2C, 1X2B
IBY2A 101	1AD2A* 1R5
1DN5	105
1F2	1 <u>L</u> 4
1F3	174
1FD9	1\$5
1G3GT, 1G3GTA	1G3GTA/1B3GT
1H33	1R5*
1J3, 1J3A	1K3A/1J3
1K3, 1K3A	1K3A/1J3
1N2, 1N2A	1G3GTA/1B3GT 1KA3A/1J3
1P10	3\$4
IPI1	3V4
106	1L6*
2A3H 2AFA 2AFAA	2A3 2AFAR /2D7A
2AF48	,2AF4B/2DZ4
2AH2	2BU2/2AH2
2BA2	2AV2
2BU2 2C22	2BU2/2AH2 6J5, 6J5GT
2DZ4	2AF48/2DZ4
2EA5	2CY5
2ER5	2GK5/2FQ5A
2ES5 2EV5	2GK5/2FQ5A
2FQ5, 2FA5A	2CY5 2GK5/2FQ5A
2FV6	2CY5

Tung to be Denisco by

p.u.	· tiour	•
Type Repia	to be iced	Replace by RCA Type
2FY5 2GK5 2GU5 2HA5 2HI	, 2HK5, N5	2GK5/2FQ5A 2GK5/2FQ5A 2FS5 2HM5/2HA5
2T4 3AF4, 3AW3	3AF4A	2AF4B/2DZ4* 3AF4A/3DZ4 3A3C, 3DB3/3CY3,* 3DJ3
3B2 3B5 3BA6		3A3C, 3DB3/3CY3,* 3DJ3 3Q5GT 3AU6
3BC5 3BE6 3BS2, 3BS 3BT 3BT	2.	3BC5/3CE5 3CS6 ,3BW2/3BS2A/ 3BT2
3BU8, 3BW2 3BY6 3C4 3C5GT		3BU8/3GS8 3BW2/3BS2A/3BT2 3CS6 3V4* 3Q5GT
3CB6 3CE5 3CF6 3CV3,	3CV3A	3CB6/3CF6 3BC5/3CE5 3CB6/3CF6 3A3C, 3DB3/3CY3 3DJ3
3CX3 3CY3 3DA3 3DB3 3DE6		3DA3/3DH3 3DB3/3CY3, 3DJ3 3DA3/3DH3 3DB3/3CY3 3BZ6
3DH3 3DZ4 3E5 3EA5		3DA3/3DH3 3AF4A/3DZ4 3V4* 3CY5

	-
Type to be Replaced	Replace by RCA Type
3EH7 3EJ7 3EV5 3FH5, 3FQ5, 3FQ5A, 3FY5	3EH7/XF183 3EJ7/XF184 3CY5 3ER5*, 3GK5
3GS8 3GU5 3HA5, 3HM5 3HM6 3HT6	3BU8/3CS8 3FS5* 3HM5/3HA5 3JC6A 3JC6A
3JD6 3KF8 3M-R24 3M-V7	3JC6A 3BU8/3GS8, 3HS8 3DK6 3BZ6
3Q5, 3Q5G, 3Q5GT, 3Q5GT/G 3S4, 3W4, 3Z4	3Q5GT 3Q4*
4BA6 4BC5 4BE6 4BL8 4BQ7, 4BQ7A	4AU6* 4CB6*, 4DK6* 4CS6 4BL8/XCF80 4BQ7A/4BZ7
4BS8 4BU8, 4BU8A 4BX8 4BY6 4BZ7	4BQ7A/4BZ7 4BU8/4GS8 4BQ7A/4BZ7 4CS6 4BQ7A/4BZ7
4BZ8 4CE5 4CF6 4EH7	4BQ7A/4BZ7, 4BC8 4CB6*, 4DK6* 4CB6, 4DE6, 4DK6 4EH7/LF183
	4EJ7/LF184 4ES8 XCC189 4LU6 4GK5

Replacement type may not work in some circuits.

Type to be Replaced	Replace by RCA Type
4GJ7 4GM6 4GS7 4GS8 4HA5, 4HK5, 4HM5	4GJ7/XCF801 4LU6 4LJ8*, 5FG7* 4BU8/4G\$8 4HM5/4HA5, 4HQ5
4HT6 4JK6 4JL6 4FK8	4JD6, 4JC6A* 4LU6 4LU6 4BU8/4GS8, 4HS8
4KN8 4RHH2 4RHH8 5AR4 5AU4	4KN8/4RHH8 4BQ7A/4BZ7 4KN8/4RHH8 5AR4/GZ34 5V3A/5AU4, 5U4GB, 5AS4A
5AV8 5AW4, 5AX4GT 5BC8 5BE8	5B8* 5U4GB, 5AS4A, 5V3A/5AU4 5BQ7A 5BR8/5FV8*
5BR8 5BS8 5BZ7 5CG4	5BR8/5FV8 5BQ7A 5BQ7A 5AR4/GZ34, 5V4GA, 5Z4
5CM8 5CQ8 5CR8 5DH8 5EH8	5KZ8 5GH8A, 5EA8, 5U8 5KZ8* 5BR8/5FV8* 5X8*
5FV8 5GJ7 5GX6 5MHH3	5BR8/5FV8, 5CL8A* 5GJ7/LCF801 5HZ6 5J6
5MQ8 5RHH2 5RHP1 5T4	6MU8, 6HL8, 5GH8A 5BQ7A 4BL8/XCF80 5R4GB 5AR4/GZ34
5V3, 5V3A 5W4, 5W4G, 5W4GT 5X3 5Y4G, 5Y4GA, 5Y4GT	5V3A/5AU4 5Y3GT, 5Z4 80 5U4GB, 5AS4A, 5V3A/5AU4
5Y4GT 5Z4, 5Z4G, 5Z4GT, 5Z4GT/G, 5Z4MG	5Y3A/5AU4 5Y3GT, 5U4GB, 5AS4A, 5Y3A/5AU4
5210	5U4GB
6A8MG 6AB7, 6AB7Y	6AC7, 6SG7*, 6SH7*
6AC7Y,	6AC7
DAU/WA	6AF6G 6AF6G

Type to be Replaced	Replace by RCA Type
6AG5WA 6AG7Y 6AH6WA 6AJ4 6AJ7	6AG5 6AG7 6AH6 6AM4* 6AC7, 6SG7*, 6SH7*
6AJ8 6AK5 6AK7 6AK8 6AL3	6AJ8/ECH81 6AK5/EF95 6AG7 6AK8/EABC80 6AL3/EY88
6AL9 6AQ8 6AR8 6AU7 6AW6	6AG9 6AQ8/ECC85 6JH8* 7AU7 6CB6A/6CF6, 6DE6, 6DC6
6B6, 6B6G 6B8G, 6B8GT 6B32 6BA6 6BC5	68A6/EF93 68C5/6CE5
	6BC8/6BZ8 6BK4C/6EL4A 6BE3/6BZ3 6BR8A/6FV8A, 6CL8A, 6FG7
6BC32 6BD5GT 6BK4. 6BK4A 6BK4B, 6BK4C	6AT6 6AU5GT*, 6AV5GA* ,6BK4C/6EL4A
6BK6 6BK11	6AT6, 6AV6 6KI1/6BQ11*, 6AC10 6BL8/ECF80 6AQ5A, 6HG5
6BL8 68M5	6BL8/ECF80 6AQ5A, 6HG5
6BM8 6BN6 6BQ5 6BQ6G, 6BQ6GA, 6BQ6GT, 6BQ6GTA, 6BQ6GTB	6BM8/ECL82 6BN6/6KS6 6BQ5/EL84 6BQ6GT8/6CU6
6BQ7, 6BQ7A 6BR3 6BR8 6BS8 6BT6	6BQ7A/6BZ7/6BS8 6BR3/RK19 6BR8A/6FV8A 6BQ7A/6BZ7/6BS8 6AT6, 6AV6
6BU6 6BW3 6BW7	6BF6 6CG3/6BW3/6DQ3 6HM6*, 6EJ7*, 6JC6A* 6BC8/6BZ8, 6BQ7A/6B77/
	6B\$8
6BZ3 6BZ7 6BZ8 6C4W, 6C4WA 6C5G, 6C5GT	6BE3/6BZ3 6BQ7A/6BZ7/6B\$8 6BC8/6BZ8 6C4 6C5
6C8G 6C16 6C31 6CA7 6CB6, 6CB6A	6F8G* 6BL8/ECF80 6K8 6CA7/EL34 6CB6A/6CF6

Type to be Replaced	Replace by RCA Type
6CC31 6CC43 6CD3 6CE3 6CE5	6J6A 6AQ8/ECC85 6CE3/6CD3/6DT3 6CE3/6CD3/6DT3 6BC5/6CE5
6CF6 6CG3 6CG6 6CG7 6CH3	6CB6A/6CF6 6CG3/6BW3/6DQ3 6BA6/EF93, 6BD6 6FQ7/6CG7 6CJ3/6CH3
6CJ3 6CK3 6CL3 6CQ4 6CR8	6CJ3/6CH3 6CL3/6CK3 6CL3/6CK3 6DE4/6CQ4 6CM8*, 6KZ8*
6CS5 6CS8 6CU6 6CW5 6D2	6CM6* 6CM8*, 6KZ8* 6BQ6GTB/6CU6 6CW5/EL86 6AL5
6D8, 6D8G 6DA4, 6DA4A 6DE4 6DK3 6DL4	6A8 6DM4A/6DA4 6DE4/6CQ4 6DL3 6DL4/EC88
6DL5 6DM4, 6DM4A	6DL5/EL95 6DM4A/6DA4
6DQ3 6DQ4	6CG3/6BW3/6DQ3 6AX4GTB, 6DE4/6CQ4
6DQ6, 6D6A, 6DQ6B	6GW6/6DQ6B
6DT3 SDT4	6CE3/6CD3/6DT3 6AU4GTA, 6DE4/6CQ4, 6DM4A/6DQ4
6DW5 6DX8 6DY5	6CM6 6DX8/ECL84 6CW5*, 6BQ5/
6EA4	6EH4A
6EA5 6EA7 6EB5 6EC4, 6EC4A	6EV5, 6AK5/ EF95*, 6CY5 6EM7/6EA7 6AL5 6EC4A/EY500
6EF4 6EF6	6EJ4A 6EZ5*, 6W6GT*, 6DG6GT* 6EH7/EF183 6EJ7/EF184
6EH7 6EJ7	6EH7/EF183 6EJ7/EF184
6EL4, 6EL4A 6EL7	6BK4C/6EL4A 6HM6*, 6EJ7*, 6JC6A* 6EM7/6EA7 6ES8/ECC189
6EM7 6ES8	6EM7/6EA7 6ES8/ECC189
6ET6	6DT6A*, 6GY6/6GX6*, 6HZ6*
6ET7 6EX6 6EY6	6HZ6* 6KU8* 6CD6GA 6EZ5
6F5G, 6F5GT, 6F5MG 6F6, 6F6G, 6F6GT, 6F6GT/G, 6F6MG	6F6, 6F6GT

^{*} Replacement type may not work in some circuits.

Type to be Replaced	Replace by RCA Type
6F10 6F24 6F29 6F30 6F31	6AC7 6E17/EF184 6EH7/EF183 6E17/EF184 6AU6A
6F32 6F36 6FG5 6FG6, 6FG6G 6FH6	6AK5/EF95 6AH6 6FS5, 6HS6* 6FG6/EM84 6GW6/6DQ6B
6FQ5, 8FQ5A 6FQ7 6FR7 6FV8, 6FV8A 6FW8	6GK5/6FQ5A 6FQ7/6CG7 6FD7 6BR8A/6FV8A 6KN8/6RHH8, 6DJ8/ECC88, 6ES8/ECC189
6FY5 6G5 6GA8	6FY5/EC97 6U5 6FQ7/6CG7*, 6GU7* 6BQ6GTB/6CU6.
6GB3A 6GB5 6GB6, 6GB7, 6GB9 6GD7	6GB5/EL500 6GW6/6DQ6B 6LI8*, 6CG8A*, 6FG7*
6GJ7 6GJ8 6GK5	6GJ7/ECF801 6GH8A*, 6HL8, 6MU8
6GK17 6GQ7	6BC7*, 6BJ7*
6GS8 6GV5 6GV8	6BU8, 6HS8, 6MK8A 6FS5* 6GV8/ECL85 6GW6/6DQ68
6GW6 6GW8 6GX6 6GY6 6H5	6GW6/6DQ6B 6GW8/ECL86 6GY6/6GX6 6GY6/6GX6 6U5
6H5 6H6G, 6H6GT, 6H6GT/G, 6H6MG	6U5 / 6H6
6H31 6HA5 6HA6 6HB6 6HC8	6BE6 6HM5/6HA5 6HB6/6HA6 6HB6/6HA6 6BM8/ECL82*
6HE5 6HG8 6HK5 6HK8	6JB5/6HE5 6HG8/ECF86 6HQ5 6BC8/6BZ8, 6BQ7A/6BZ7/ 6BS8, 6BK7B
6HM5 6HQ6 6HT6	6HM5/6HA5 6BZ6, 6JH6, 6GM6* 6HM6, 6JC6A, 6JD6
6HU6 6HU8 6HZ5 6HZ8	6HU6/EM87 6HU8/ELL80 6HZ5/6JD5 6AW8A, 6HF8, 6LF8, 6JV8

Type to be Replaced	Replace by RCA Type
6J5, 6J5G, 6J5GT, 6J5GT/G, 6J5GTX, 6J5GX, 6J5MG	6J5, 6J5GT
6J7, 6J7G, 6J7GT, 6J7GTX, 6J7MG 6J10	6J7 6Z10/6J10
6JB5 6JC5 6JD5 6JE6, 6JE6A, 6JE6B, 6JE6C	6JB5/6HE5 6JB5/6HE5 6HZ5/6JD5 6MJ6/6LQ6/ 6JE6C, 6LQ6/6JE6C
6JL6 6JN6, 6JN6A 6JW8	6EW6, 6JK6, 6GM6 6JN6 6JW8/ECF802
6K6, 6K6G, 6K6GT, 6K6GT/G, 6K6MG	6K6GT
6K7, 6K7G, 6K7GT, 6K7GTX, 6K7MG	6K7
6K8, 6K8G, 6K8GT, 6K8GTX 6K11	6K8 6K11/6Q11
6KD8	6U8A/6KD8
6KF8 6KG6A 6KN8 6KS6	68U8, 6HS8, 6GS8, 6MK8A 6KG6A/EL509 6KN8/6RHH8 6BN6/6KS6
6KS8 6KV8 6L5G	6AW8A, 6JV8, 6LF8, 6HF8 6JT8, 6KR8, 6LB8, 6LQ8 6J5, 6J5GT, 6C5
6L6, 6L6A, 6L6G, 6L6GA, 6L6GB, 6L6GC, 6L6GT, 6L6GX, 6L6Y	6L6GC
6L7, 6L7G 6L10 6L12 6L13 6L31	6L7 6AG7 6AQ8/ECC85 12AX7A/ECC83 6AQ5A
6L43 6LD12 6LF6 6LH6, 6LH6A 6LJ6, 6LJ6A	6CL6 6AK8/EABC80 6LF6/6MH6, 6LF6/6LX6 6LJ6A/6LH6A 6LJ6A/6LH6A
6LJ6, 6LJ6A	6LJ6A/6LH6A

Type to be Replaced	Replace by RCA Type
6LN8 6LP12 6LQ6	6LN8/LCF80 6BM8/ECL82 6MJ6/6LQ6/ 6JE6C, 6LQ6/6JE6C
6LX8	
6M1 6M7G 6MH6	6U5 6K7* 6LF6/6MH6, 6LX6*
6MHH3 6MJ6	6J6 6MJ6/6LQ6/6JE6C
6N7, 6N7G, 6N7GT, 6N7GT/G, 6N7MG	6N7, 6N7GT
6P9	6AQ5A, 6HG5
6P15 6PL12 6Q7, 6Q7G, 6Q7GT, 6Q7MG	6BQ5/EL84 6BM8/ECL82 6Q7
6Q8	6A8
6Q11 6R3 6R8	6K11/6Q11 6AF3, 6AL3/EY88, 6BR3/6RK19 6T8A
6RHH2	6BC8/6BZ8
6RHH8 6RK19 6S5G 6S7, 6S7G	6KN8/6RHH8 6BR3/6RK19 6E5 6K7
6SA7G, 6SA7GT, 6SA7GT/G, 6SA7GTX, 6SA7GTY, 6SA7Y	6SA7
6SB7, 6SB7GTY, 6SB7Y	6SB7Y
6SC7, 6SC7GT, 6SC7GTY	6\$C7
6SG7, 6SG7GT, 6SG7Y	6SG7
6SG7Y 6SH7, 6SH7GT, 6SH7L	6SH7
6SJ7, 6SJ7GT, 6SJ7GTX, 6SJ7GTY, 6SJ7Y	68J7
6SK7WA, 6SK7WGT	6SK7, 6SK7GT
6SL7A, 6SL7GT, 6SL7TY, 6SL7L	6SL7GT

^{*} Replacement type may not work in some circuits.

14131 1311	DEMEDITE GOL
Type to be Replaced	Replace by RCA Type
6SN7A, 6SN7GTA, 6V6GTA, 6SN7GTB, 6SN7GTY, 6SN7L	6SN7GTB
6SQ7, 6SQ7G, 6SQ7GT	6SQ7
6SQ7GT/G 6SR7, 6SR7G 6SR7GT	
6SS7, 6SS7GT	6SK7, 6SK7GT
6ST7 6SZ7 6T1	6SR7 6SQ7 6AF4, 6AF4A, 6DZ4 6U5
6T7G 6U4GT	6Q7 6AX4GTB, 6DM4A/ 6DQ4, 6DE4, 6CQ4, 6W4GT
6U6GT 6U7G 6U8, 6U8A 6U9 6V4	6Y6GA/6Y6G 6K7, 6J7 6U8A/6KD8 6U9/ECF201 6CA4
6V6G, 6V6GT, 6V6GTA, 6V6GT/G, 6V6GTX, 6V6GX, 6V6GTY, 6V6GY	6V6GTA
6W5G, 6W5GT 6W7G 6X5, 6X5G, 6X5GT, 6X5GT/G, 6X5L, 6X5MG, 6X5W, 6X5WGT	6AX5GT, 6X5GT 6J7 6X5GT
6X9 6Y6G, 6Y6GT,	6X9/ECF200 6Y6GA/6Y6G
6Y9 6Z10	6Y9/EFL200 6Z10/6J10
6Z31 6ZY5G 7D11 7HG8 8A8	6X4 6X5GT 6CA7/EL34 7HG8/PCF86 9A8/PCF80, 9GH8A, 9U8A
8BA8A 8BH8	8AU8, 8AW8A 8AU8, 8AW8A, 8JV8
8CG7 8CW5, 8CW5A 8EB8	8FQ7/8CG7 8CW5/XL86 8GN8/8EB8
8FQ7	
8GJ7 8GN8 8GX7 8JE8	8FQ7/8CG7 8GJ7/PCF801 8GN8/8EB8 8GJ7/PCF801* 8CX8, 8GN8/8EB8

Type to be	Replace by
Replaced	RCA Type
8K\$8	8AU8, 8AW8A, 8JV8
9A8	9A8/PCF80
9AQ8	9AQ8/PCC85
9EA8	9GH8A, 9U8A
9GV8	9GV8/XCL85
9JW8	9JW8/PCF802
9RAL1	10DE7, 10EW7
9RHH2	9GH8A
10CW5	10CW5/LL86
10D2	12AL5
10DX8	10DX8/LCL84
10GV8	10GV8/LCL85
10JA8	10JA8/10LZ8
10LZ8	10JA8/10LZ8
10PL12	50BM8/UCL82
12AC6	12AF6, 12BL6
12AD7	12AX7A/ECC83, 7025
12AF3	12AF3/12BR3/12RK19
12AG6	12AD6
12AS5	12CA5, 12R5
12AT7	12AT7/ECC81
12AU7.	12AU7A/ECC82
12AU7, 12AU7A 12BB14 12BC22 12BC32	13GB5/XL500 12AV6 12AV6
12BD6 12BK6 12BQ6GA, 12BQ6GT, 12BA6GTA 12BQ6GTB	12BA6 12AT6, 12AV6 12BQ6GTB/12CU6
12BU6	12BF6
12BR3	12AF3/12BR3/12RK19
12BS3,	12BS3A/12DW4A
12B\$3A 12B\$3A 12BT6 12BV7	12AT6, 12AV6 12BY7A/12BV7/12DQ7
12BY7, 12BY7A 12C5	12BY7A/12BV7/12DQ7
12C5 12CK3	12CU5/12C5 12CL3, 12BS3A/ 12DW4A
12CS6	12BE6
12CU5	12CU5/12C5
12CU6	12BQ6GTB/12CU6
12CX6	12BL6, 12AF6
12DF7	12BL7, 12AF6
12DL8	12AX7A/ECC83, 7025
12DM4,	12DS7*
12DM4A	12D4
12DM5 12DM7	12FX5 12AX7A/ECC83*, 7025*
12DQ6, 12DQ6A, 12DQ6B 12DQ7	7025* 12GW6/12DQ6B 12BY7A/12BV7/12DQ7
12DT7	12AX7A/ECC83, 7025
12DW4A	12BS3A/12DW4A
12DZ6	12EK6/12DZ6/12EA6
12E5GT	12JSGT
12E13	6550, 6CA7/EL34

Type to be Replaced	Replace by RCA Type
12EA6 12ED5 12EH5 12EK6 12EN6	12EK6/12DZ6/12EA6 12FX5 12CA5, 12CU5/12C5 12EK6/12DZ6/12EA6 12L6GT, 12W6GT
12EX6 12F31 12FT6 12GB3 12GB6, 12GB7	12EK6/12DZ6/ 12EA6 12BA6 12AE6A, 12BF6 12BQ6GTB/12CU6 12GW6/12DQ6B
12GK17 12GN7, 12GN7A, 12GW6 12H31 12HG7	12D4 12HG7/12GN7A 12GW6/12DQ6B 12BE6 12HG7/12GN7A
12RK19 12RLL3 12RLL5	12AF3/12BR3/12RK1 12AV7 12FQ7
12SA7G, 12SA7GT, 12SA7GT/G 12SA7GTY, 12SA7Y 12SF7GT, 12SF7Y	12SA7 12SF7
12SG7GT, 12SG7Y 12SH7GT 12SJ7GT	12SG7 12SH7 12SJ7
128K7G, 128K7GT, 128K7GT/G 128K7GTY, 128K7Y	12SK7
12SQ7G, 12SQ7GT, 12SQ1GT/G 12SX7GT 12SY7, 12SY7GT	12SQ7 12SN7GTA 12SA7
13D2 13EM7 13FM7 13FR7 13GB5	6SN7GTB 13EM7/15EA7 13FM7/15FM7 13FD7 13GB5/XL500
13J10 13Z10 14JG8 15CW5 15DQ8	13Z10/13J10 13Z10/13J10 14GT8 15CW5/PL84 15DQ8/PCL84
15EA7 15EW7 15FM7 15MX8 16A5	13EM7/15EA7 13DE7 13FM7/15FM7 15KY8A 15CW5*
16A8 16AQ3 16MY8 17A8 17AB 10	16A8/PCL82 16AQ3/XY88 16LU8A 19EA8 17AB10/17X10
17BE3 17BQ6GTB 17BR3 17BS3, 17BS3A	17BE3/17BZ3 17GW6/17DQ6B 17BR3/17RK19 17BS3A/17DW4A

^{*} Replacement type may not work in some circuits.

Type to be Replaced	Replace by RCA Type
17BZ3 17C5 17CL3	17E3/17BZ3 17CU5/17C5 17CK3, 17BS3A/ 17DW4 17CU5/17C5 17DM4A, 17D4
17CU5 17DQ4	17CU5/17C5 17DM4A, 17D4
17DQ6, 17DQ6A,	17GW6/17DQ6B
17DQ6B 17DW4A 17EW8	17B\$3A/17DW4A 17EW8/HCC85
17GW6 17JR6 17J D8	17GW6/17DQ6B 17JG6A 15KY8A 17BR3/17RK19 17AB10/17X10
17LD8 17RK19 17X10	
17Z3 18GB5 18GE6, 18GE6A	17Z3/PY81 18GB5/LL500 18FY6A
18GV8	18GV8/PCL85
19C8 19CG3 19CL8A 19DQ3 19JN8	19T8 19CG3/19DQ3 19JN8/19CL8A 19CG3/19DQ3 19JN8/19CL8A
19MR9, 19MR10	18GD6A
19MR19 20AQ3 21EX6	18FW6A 20AQ3/LY88 25CD6GB, 25DN6
21JS6A 21MY8 24JE6, 24JE6A, 24JE6B	23JS6A 21LU8 24LQ6/24JE6C
24LQ6 25BQ6GA, 25BQ6GT, 25BQ6GTB 25CA5	24LQ6/24JE6C 25BQ6GTB/25CU6 25C5, 25EH5
250116	SEROECTE (SECUE
25E5 25EC6 25GB6	25E5/PL36 25CD6GB 25BQ6GTB/25CU6
25L6, 25L6G, 25L6GT, 25L6GT/G	
25W6G1	25L6GT/25W6GT
25Z6, 25Z6G, 25Z6GT, 25Z6GT/G, 25Z6MG 27GB5	25Z6GT
28GB5 29KQ6 30A5 30AE3 30C1	27GB5/PL500 29KQ6/PL521 35C5, 35EH5 30AE3/PY88 9A8/PCF80
30P4 30P18 30P19 30PL12	25E5/PL36 15CW5/PL84 25E5/PL36 16A8/PCL82

Type to be	Replace by
Replaced	RCA Type
30PL13, 30PL14	16GK6
30PL14 32ET5, 32ET5A	34GD5A
35Z5, 35Z5G, 35Z5GT/G	35Z5GT
36KD6	36KD6/40KD6
40KD6	36KD6/40KD6
40KG6, 40KG6A	40KG6A/PL509
40KG6A 42EC4, 42EC4A	42EC4A/PY500
48A8	50BM8/UCL82
50BM8 50CA5 52KU, 53KU, 54KU 58HE7	50BM8/UCL82 50EH5 5Y3GT
58HE7	53HK7
77	6C6
274	5V4GA
310A, 328A	6C6
349A	6K6GT
351A	6X5GT
403A	6AK5/EF95
731A	6AK5/EF95
1217	6BE6
1221	6C6
1225	6L7
1381HQ	6AK5/EF95
1611	6F6, 6F6GT
1613	6F6, 6F6GT
1649	6AC7
1655	6SC7
1852	6AC7
2057/6H6	6H6
3107	5V4GA
4707	6X4
5661	12SK7
5693	6SJ7
5871	6V6GT
5910	1U4
5931	5U4GB
5932	7027A
5992	6V6GTA
6087	5Y3GT
6100	6C4
6106	5Y3GT
6113	6SL7GT
6134	6AC7
6135	6C4
6853	5Y3GT
6968	6AK5/EF95
7700	6C6
7717	6CY5
7724	14GT8
7732	6CB6A/6CF6
7733	12BY7A/12FV7/12DQ7
8016	1G3GTA/1B3GT
A61 A677 A863 A2900 B36	17Z3/PY81 6C6 6J7 12AT7/ECC81

Type to be	Replace by
Replaced	RCA Type
B65	6SN7GTB
B152	12AT7/ECC81
B309	12AT7/ECC81
B329	12AU7A/ECC82
B339	12AX7A/ECC83
B719	6AQ8/ECC85
B739	12AT7/ECC81
B749	12AU7A/ECC82
B759	12AX7A/ECC83
BPM04	6AQ5A
CK1003 CSF80 CV1758	OZ4A/OZ4 4BL8/XCF80
CV1758, CV2742, C2795 D2M9, D27	1L4 6AL5
D63 D77, D152, D717	6H6 6AL5
D/1/ DAF92 DD6	1U5 6AL5
DF91	1T4
DF92	1L4
DF904	1U4
DH63	6Q7
DH77	6AT6
DH719	6AK8/EABC80
DK91	1R5
DL33	3Q5GT
DL37	6L6GC
DL94	3V4
DL95	3Q4
DL012	6T8A
DP61	6AK5/EF95
DY30	1G3GTA/1B3GT
DY80	1X2C, 1X2B
E81CC	12AT7/ECC81
E82CC	12AU7A/ECC82
E83CC	12AX7A/ECC83
E90F	6BH6
E90Z	6X4
E95F	6AK5/EF95
E99F	6BJ6
E902	6X4
E2157	12AT7/ECC81
E2163	12AU7A/ECC82
E2164 EAA91 EABC80	12AX7A/ECC83 6AL5 6AK8/EABC80, 6T8A
EB34 EB91	6T8A 6H6 6AL5
EBC90	6AT6
EBC91	6AV6
EBF32	6B8
EC88	6DL4/EC88
EC90	6C4
EC92	6AB4
EC94	6AF4, 6AF4A
EC95	6ER5
EC97	6FY5/FC97
EC900	6FY5/EC97, 6ER5 6HM5/6HA5

^{*} Replacement type may not work in some circuits.

Type to b	e Replace by
Replaced	RCA Type
ECC32	6SN7GTB
ECC35	6SL7GT
ECC81	12AT7/ECC81
ECC82	12AU7A/ECC82
ECC83	12AX7A/ECC83
ECC85	6AQ8/ECC85
ECC88	6ES8/ECC189
ECC91	6J6A
ECC180	6BQ7A/6BZ7/6BS
ECC186	12AU7A/ECC82
ECC189	6ES8/ECC189
ECC801	12AT7/ECC81
ECC802	12AU7A/ECC82
ECC803	12AX7A/ECC83
ECC900	6HM5/6HA5
ECF80	6BL8/ECF80
ECF82	6U8A
ECF86	6HG8/ECF86
ECF200	6X9/ECF200
ECF201	6U9/ECF201
ECF801	6GJ7/ECF801
ECF802	6JW8/ECF802
ECH42	6C10
ECH81	6AJ8/ECH81
ECL82	6BM8/ECL82
ECL84	6DX8/ECL84
ECL85	6GV8/ECL85
ECL86	6GW8/ECL86
ECL100	6BQ7A/6BZ7/6BS8
ECL180	6BQ7A/6BZ7/6BS8
ED2 EF36, EF3 EF39 EF93 EF94	
EF95	6AK5/EF95
EF96	6AG5
EF183	6EH7/EF183
EF184	6EJ7/EF184
EF190	6BZ6
EF811	6EH7/EF183
EF814	6EJ7/EF184
EF905	6AK5/EF95
EF1200	6Y6/EFL200
EH90	6CS6
EK90	68E6
EL34	6CA7/EL34
EL36	6GW6/6DQ6B*
EL37	6L6GC
EL84	6BQ5/EL84
EL86 EL90 EL95 EL180 EL500	6CW5/EL86 6AQ5A 6DL5/EL95 12BY7A/12BY7/ 12DQ7 6GB5/EL500
EL505, EL509 ELF86 ELL80 EM35 EM84	6KG6A/EL509 6HG8/ECF86 6HU8/ELL80 6U5 6FG6/EM84
EM87	6HU6/EM87
EM840	6FG6/EM84
EY83	6AL3/EY88
EY88	6AL3/EY88
EY500	6EC4A/EY500

Type to be	Replace by
Replaced	RCA Type
EZ4	6CA4
EZ35	6X5GT
EZ81	6CA4
EZ90, EZ900	6X4
G77	6C6
GZ30	5Y3GT
GZ31	5U4GB
GZ32	5V4GA
GZ34, GZ37	5AR4/GZ34
H52	5U4GB
H63	6F5
H250	6C6
HAA91	12AL5
HABC80	19T8
HBC90	12AT6
HBC91	12AV6
HCC85	17EW8/HCC85
HD93	1X2B, 1X2C
HD94	6BQ6GTB/6CU6
HD96	25BQ6GTB/25CU6
HF93	12BA6
HF94	12AU6
HK90	12BE6
HL92	50C5
HM04	6BE6
HY90	35W4
HY145	1U4
HZ90	12X4
KT32	25L6GT/25W6GT
KT63	6F6, 6F6GT
KT66	6L6GC, 7027A*
KT71	50L6GT
KT77	6CA7/EL34
KTW63	6K7
KTZ63	6J7
L63	6J5, 6J5GT
L77	6C4
LC97	3GK5
LC900	3HM5/3HA5
LCF80	6LN8/LCF80
LCF86	5HG8/LCF86
LCF201	5U9/LCF201
LCF801	5GJ7/LCF801
LCF802	6LX8/LCF802
LCL82	11BM8
LCL84	10DX8/LCL84
LCL85	10GV8/LCL85
LCL200	10DX8/LCL84
LF183	4EH7/LF183
LF184	4EJ7/LF184
LL86	10CW5/LL86
LL500	18GB5/LL500
LL521	21KQ6
LN119	50BM8/UCL82
LY88	20AQ3/LY88
LZ319, LZ329	9A8/PCF80
M8080	6C4
M8081	6J6A
M8101	6BA6/EF93
M8136	12AU7A/ECC82
M8137	12AX7A/ECC83
M8162	12AT7/ECC81
M8245	6AQ5A
MV6-5	6SA7
N15, N16	3Q5GT

Type to be	Replace by
Replaced	RCA Type
N 18	3Q4
N 19	3V4
N 30 E L	6LF6
N 63	6F6, 6F6GT
N 66	6K6GT
N77	6L6GC
N308	25E5/PL36
N369	16A8/PCL82
N378, N379	15CW5/PL84
N709	6BQ5
N727	6AQ5A
OBC3	12SQ7
OM3	6H6
OM6	6K7
OSW2190	6AC7
0SW2192	6AG7
0SW2600	6AC7
0SW2601	6AG7
0SW3104	6SA7
0SW3105	6SQ7
0\$\w3106 0\$\w3107	6V6, 6V6GTA 5AR4/GZ34, 5V4GA, 5Z4
0SW3109 0SW3110	6E5
0\$W3111	6SK7, 6SK7GT
0\$W3112	6J5, 6J5GT
PC95, PC97	4GK5
PC900	4HM5/4HA5
PCC18	7AU7
PCC85	9AQ8/PCC85
PCC186	7AU7
PCF80	9A8/PCF80
PCF82	9U8A
PCF86	7HG8/PCF86
PCF801	8GJ7/PCF801
PCF802	9JW8/PCF802
PCF806	8GJ7/PCF801
PCL82	16A8/PCL82
PCL84	15DQ8/PCL84
PCL85	18GV8/PCL85
PCL800	16GK6
PF9	6K7
PH4	6A8
PL36	25E5/PL36
PL84	15CW5/PL84
PL500	27GB5/PL500
PL505, PL509	40KG6A/PL509
PL521	29KQ6/PL521
PM04	6BA6
PM05 PY81, PY83 PY88 PY500 PY800, PY801	6AK5/EF95* 17Z3/PY81 30AE3/PY88 42EC4/PY500 17Z3/PY81
QA2401	6C4
QA2404	6AL5
QA2406	12AT7/ECC81
QB65	6SN7GTB
QB309	12AT7/ECC81
QL77 R19 R52, RJ2, RS2 T2M05	6C4 1X28, 1X2C 5Y3GT
T2M05	6J6A
T1Z63	6J7

^{*} Replacement type may not work in some circuits.

Type to be Replaced	Replace by RCA Type
U41	1G3GTA/1B3GT
U50, U51 U52	5Y3GT 5U4GB
U54	5AR4/GZ34
Ü77	5AR4/GZ34
U78_	6X4
U147	6X5GT
U153, U193, U251, U34	17Z3/PY81 .9
U707	6X4
U709	6CA4
UCL82 UU12	50GM8/UCL82 6CA4
VZM70	6X4
V153	17Z3/PY81
V741	6C4
VSM70	6X4
W17	1T4 6K7GT
W61, W63 W147	6K7
W727	6BA6
WT210-0006	
WT210-0007	
WT210-0021 WT210-0028	6X5GT 3Q5GT
WT210-0029 WT210-0042	6C5 5Y3GT
WT210-0042	5U4GB
WT210-0060	OZ4A/OZ4
WT210-0081	6SJ7

Type to be Replaced	Replace by RCA Type
WT210-0082	6V6, 6V6GTA 6N7, 6N7GT
WT210-0084	6N7, 6N7GT
WT210-0085	50B5
WT210-0087	6K8
WT210-0088	6J5, 6J5GT
WT210-0090	6C6
WT210-0148	6AX5GT
WT261,	6H6
WT261A	CVEAT
WT308 WT389	6X5GT 3Q5GT
W1389	34361
WT390	6C5
WTT102	5Y3GT
WTT103	6H6
WTT114	0Z4A/0Z4
WTT122	6SJ7
WTT123	6V6, 6V6GTA
WTT124	6AT6
WTT125	6N7, 6N7GT 50B5
WTT126	50B5
WTT128	6K8
WTT129	6J5, 6J5GT
WTT131	6C6
WTT135	5U4GB
X17	1R5
X63	6A8
X64	6L7
X77	6BE6
X107	18FX6*
X 150	6C10
X 155	6BC8/6BZ8

Type to be	Replace by
Replaced	RCA Type
X719	6AJ8/ECH81
X727	6BE6
XAA91, XB91	3AL5
XC95, XC97	2GK5/2FQ5A
XC900	2HM5/2HA5
XCC82 XCC189 XCF80 XCF82	7AU7 4ES8/XCC189 4BL8/XCF80
XCF801	5U8 4GJ7/XCF801
XCL85	9GV8/XCL85
XF94	3AU6
XF183	3EH7/XF183
XF184	3EJ7/XF184
XL84 XL86	8BQ5 8CW5/XL86
XL500	13GB5/XL500
XXA91	3AL5
XY88	16AQ3/XY88
Y61, Y64 YC95	3ER5
YC97	3GK5
YCF86	5HG8/LCF86
YCL180	5BQ7A
YCL84	10DX8/LCL84
YF 183	4EH7/LF183
YF 184	4EJ7/LF184
YL 84	10BQ5
YL86	10CW5/LL86
Z63	6J7

^{*} Replacement type may not work in some circuits.

# Replacement Guide—Industrial Receiving Types

#### How to Use

This guide was prepared to assist in the selection of current replacement types for foreign and domestic industrial receiving tubes. The first column lists in numerical-alphabetical sequence the type designation of the industrial receiving tube types to be replaced. The next two columns give the RCA Replacement Types. The column under the heading "Direct" gives direct replacements for the type in the left hand column. The column under the heading "Similar" gives the types that are similar in many respects to the type to be replaced but which are not directly interchangeable because of differences in mechanical and/or electrical characteristics. For more information as to the degree of interchangeability of "Similar" types, refer to the data for the respective tube types.

#### Types replaceable only by themselves are not included.

Type to be	RCA Replac	ement	Type to be	RCA Replacement		
Replaced	Direct	Similar	Replaced	Direct	Similar	
0A2	OA2, OA2WA		2051	5670		
	6073, 6073/		2D21	2D21, 5727		
	0A2 6626/0A2WA		2D21W	5727	2D21	
0A2WA	0A2WA, 6626/ 0A2WA	0A2, 6073, 6073/0A2	5R4G, 5R4GTY, 5R4GY, 5R4GYA,	5R4GB	5U4GB	
0A3, 0A3/VR75	0A3, 0A3A		5R4GYB			
0A3A 0B2	0A3A 0B2, 0B2WA	0A3	6AC7W, 6AC7WA, 6AC7Y		6AC7	
V62	6074, 6074/		6AG5WA		6AG5	
NDOWA .	0B2	ADD C074	- 6AG7Y		6AG7	
OB2WA	OB2WA	0B2, 6074, 6074/0B2	6AH6WA	6AH6WA	6AH6	
0C3, 0C3/VR105	0C3, 0C3A		6AK5W	5654	6AK5/EF95	
OC3A	.OC3A	0C3	6AL5W	5726	6AL5, 6663/ 6AL5	
DC3W		OC3, OC3A		6005	6AQ5A	
DD3, OD3/VR150	0D3, 0D3A		6AS6, 6AS6W	5725, 6AS6	UNDAN	
DD3A	OD3A	0D3	6AS7G	6AS7G, 6AS7GA,		
DD3W		OD3, OD3A	_	6080,		
)G3	5651A			6080WA		
IC21	1C21, 5823		- 6AS7GA	6AS7GA, 6080,	6AS7G	
IF2	1 <b>L4</b>		_   <del> </del>	6080WA		
G50		2050, 2050A	- 6AS7GYB		6AS7G, 6AS7GA, 6080, 6080WA	
G84		884	6AU6WA,	6AU6WB	6136	
2C22		6J5, 6J5GT	6AU6WB	OVOOMB	0130	

Type to be Replaced	RCA Replac Direct	ement Similar	Type to be Replaced	RCA Replac Direct	ement Similar
6BA6W	5749	6BA6/EF93, 6660/6BA6	150C1, 150C2	0A2, 0A2WA, 6073,	
6BE6W	5750	6BE6	·	6073/ <b>0A2</b>	
6CC10	5692		150C3	6626/0A2WA	
6D2		5726	150C3 150C4	OD3, OD3A OA2WA, 6073,	0A2
6D18	6DJ8/ECC88	6ES8/ECC189	13004	6073/0A2,	UAZ
614	6J4, 8532			6626/0A2WA	<b>\</b>
6J4WA	8532	614	180C1	082, 082WA,	
6J6W, 6J6WA	6J6WA, 5964, 6101	6J6A	<u></u>	6074, 6074/0B2	
6L6W, 6L6WA,		5881, 6L6GC	245	884	
6L6WGA, 6L6WGB.			274A, 274B	5R4GB	
6L6WGT,			301A	83	1000
6L6Y	<del> </del>		310B		1620
6MH1		6.14	313C 328A		1C21 6C6
6RR8, 6RR8C	5847/404A		348A	<del></del>	1620
6SA7Y		6SA7	349A	<del></del>	6F6, 6F6GT, 6K6
6SG7Y	5002	6SG7	351A		6X5GT
6SJ7WGT, 6SJ7Y.	5963	6817	359A		1021
6SJ7WGTY,			395A		5823
6SJ7W 6SL7W,	5691	6SL7GT	403A, 403B	6AK5/EF95, 5654	
6SL7WGT			404A	5847/404A	
6SN7GTY,	5692	6SN7GTB	409A	6AS6	
£SN7W, ESN7WGT.			417A	5942/417A	
6SN7WGTA		_	421, 421A		6AS7G, 6AS7GA,
6V6Y, 6V6GTY		6V6GTA, 6V6	-		6080
6X4W	6X4W, 6202	6X4	423A	0050 00504	5651A, 5651WA
6Z31		6202	502A	2050, 2050A	
7D11		6550	630, 630A	2050, 2050A	004
12AT7WA	12AT7WA,	6201, 6679/ 12AT7	885 954		9001
12AT7WB	12AT7WB 12AT7WB	12AT7WA, 6201,	956		9003
12A1/WD	12M1/WD	6679/12AT7	958A		9002
12AU7WA	6189	6670/12AU7A	1217		5915
	,	5814A,	1219	5670	3313
	0001 (104)(74	12AU7A/ECC82	1221	0070	606
12AX7WA	6681/12AX7A	12AX7A/ECC83	1223		1620
12E13	· · · · · · · · · · · · · · · · · · ·	6550 12SA7	1225	****	6L7
12SA7Y 12SG7Y		12SG7	1266		5823
12SK7Y		12SK7	1267	OA4G	
20A3		2021	1381HQ	6AK5/EF95, 5654	
25B6G	5824		1603		6C6
26A6	26A6		1611	1621	6F6, 6F6GT
26A7GT	26A7GT		1612	1612	6L7
85A3		5783	1613	1621	6F6, 6F6GT
	002 00244		1614		<del></del>
108C1	082, 082WA	0C3, 0C3A	1 1014	1614	6L6, 6L6GC

Type to be Replaced	RCA Repla Direct	cement Similar	Type to be Replaced	RC Direct
1620	1620	6J7	5751WA	
1621	1621	6F6, 6F6GT		
1622	1622	6L6, 6L6GC	5812	
1629	1629	6E5	5814, 5814A	5814A
1631		1614, 6L6, 6L6GC 1622	, 5814WA	
1649		6AC7	- 5840, 5840A.	5840W
1650	955	UNUI	- 5840W	
1655	333	6SC7	<b>-</b> 5842, 5842/	5842/4
1657, 1665		2050, 2050A	417A	
1852		6AC7	_ 5844	
2013	6211	UNU/	5871	
2014	6197	6CL6, 6677/6CL6	5881	5881
2050	2050	2050A	_ 5897	5718
2050A	2050A	2050A	5899, 5899A,	5899
2051	2050	2050A	_ 5900	EDADM
2057/6H6	2030	6H6	_ 5901	5840W
12AY7	12AY7	2082/12AY7	_ 5910	5015
2081,	2081/6AW8A	6AW8A	5915, 5915A	5915
2081/6AW8A		UNITON	5920	
2082.	2082/12AY7	12AY7	_ 5931	
2082/12AY7	2002/ 12/11/	16/11/	5932	
5590/401B 5591/403B		5654, 6AK5/EF95	<b>- 5963</b>	5963
5636A		5636	_   5964	5964
651, 5651A	5651A, 5651W	A	_ 5965A	3304
651WA	5651WA	5651A	_ 5992	
654, 5654/6AK5W	5654	6AK5/EF95	6005, 6005/ 6AQ5W,	6005
659		12 <b>A</b> 6	- 6005/	
663	5663	5696, 5696A	- 6AQ5W/	
670WA		5670	6095	
691	5691	6SL7GT	6012	6012
692	5692	6SN7GTB	6028, 6028/	408A
693	5693	6SJ7	-   408A	
5696	5696	5696A	- 3058	
5696A	5696A	5696	- 6060	
			_ 6062	
725, 5725/6AS6W	5725	6AS6	6063 6067	<del> </del>
726/6AL5W	5726	6663/6AL5, 6AL5	-   ""	
727, 5727/2D21 <b>W</b>	5727	2021	6072	6072, 60
731	955		- 6072A	6072A
734	5734			OU/ ZM
749, 5749/6BA6W	5749	6BA6/EF95	6073, 6073/ 0A2	6073, 66 0A2W
750	5750	6BE6	- 0A2	0A2W/ 6073/
				M11/3/

Type to be	RCA F	teplacement
Replaced	Direct	Similar
5751WA		5751, 6681/ 12AX7A
5812		5763
5814, 5814A	5814A	12AU7A/ECC82, 6189
5814WA		5814A, 6189
5840, 5840A, 5840W	5840W	5840
5842, 5842/ 417A	5842/417	A
5844		5964, 6J6A
5871		6V6GT
5881	5881	6L6GC
5897	5718	
5899, 5899A, 5900	5899	
5901	5840W	5915
5910		104
5915, 5915A	5915	
5920		5964, 6J6A, 6101
5931		5U4GB
5932		7027A
5963	5963	5814A, 12AU7A/ECC82, 6680/12AU7A
5964	5964	6J6WA, 6101
5965A		5965
5992		6V6GTA
6005, 6005/ 6AQ5W, 6005/ 6AQ5W/ 6095	6005	6AQ5A
6012	6012	5727
6028, 6028/ 408A	408A	
3058		5726, 6AL5
6060		6201
6062		5763
6063		6X4W
6067		5814A, 12AU7A/ECC82, 6680/12AU7A
6072	6072, 6072	A 12AY7, 2082/12AY7
6072A	6072A	12AY7, 2082/12AY7, 6072
6073, 6073/ 0A2	6073, 6626, 0A2WA, 6073/ 0A2	/ 0A2, 0A2WA

Type to be Replaced	RCA Replac Direct	ement Similar
6074, 6074/ OB2	6074, 6074/ 0B2	OB2, OB2WA
6080	6080, 6080WA	6AS7G, 6AS7GA
6080WA	6080WA	6080, 6AS7G, 6AS7GA
6082	6082, 6082A	
6082A		6082
6084		5879
6085		5962, 6SN7GTB
6087		5Y3GT
6094	<u></u>	6005, 6AQ5A
6095	6005	6AQ5A
6096		5654, 6AK5/EF95
6097		5726, 6AL5, 6663/6AL5
0000		
6099		5964, 6101, 6J6WA
6100		6C4
6101, 6101/ 6J6 <b>WA</b>	6101	5964, 6J6WA
6106		5Y3GT
6113		6SL7GT
6134		6AC7
6135		6C4
6136	6136	6AU6WB
6140/423A		5651A
6180		5692, 6SN7GTB
6186, 6186/ 6AG5WA		6AG5
6187	6AS6	5725
6189, 6189/ 12 <b>AU7WA</b>	6189	5814A, 5963, 12AU7A/ECC82, 6680/12AU7A
6197	6197	6CL6, 6677/ 6CL6
5201	6201	12AT7WA, 12AT7WB, 6679/12AT7
5202	6202	6X4W
6211A		6211
6336, 6336A, 6337	6336A	7.
6360	6360, 6360A	
5360A	6360A	6360
5385		5670
5394		6082
6414		5965
	C417	7551
5417 CARC CARCA	6417	
6486, 6486A		5725, 6AS6
6520		6AS7G, 6AS7GA

Type to be Replaced	RCA Replac	ement Similar
6550	6550	7027A
6626/0A2WA.	6626/0A2WA	02A, 6073,
6626		6073/0A2
6627		082, 082WA, 6074,
6660/6BA6.	6660/6BA6	6074/0B2 5749, 6BA6/EF93
6660	0000/0000	
6661/6BH6, 6661_	6661/6BH6	6BH6
6662/6BJ6, 6662	6662/6BJ6	6BJ6
6663/6AL5, 6663	6663/6AL5	5726, 6AL5
6664/6AB4, 6664	6664/6AB4	6AB4
6669/6AQ5A, 6669	6669/6AQ5A	6005, 6AQ5A
6676/6CB6A, 6676	6676/6CB6A	6CB6A/6CF6
6677/6CL6, 6677	6677/6CL6, 6197	6CL6
6678/6U8 <b>A,</b> 6678	6678/6U8A	6U8A/6KD8
6679/12AT7, 6679	6679/12AT7	12AT7WA, 12AT7WB
6680/12AU7A, 6680		12AU7A/ECC82
6681/12AX7A, 6681	6681/12AX7A	12AX7A/ECC83
6687		5915
6829		5965
6853	·	5Y3GT
6922/E88CC, 6922	6922/E88CC	
6968		6AK5/EF95
7000		1620
7025, 7025A	7025	12AX7A/ECC83
7036 7054	7054, 8077/ 7054	5915
7062		5965
7105	<del></del>	6080, 6080WA, 6AS7G, 6AS7GA
7184	<del></del>	6V6, 6V6GTA
7244, 7244A		5964, 6101, 6J6WA
7245, 7245A		614, 8532
7318		5814A, 6680/12AU7A, 12AU7A/ECC82


Type to be Replaced	RCA Replace	ement Similar	Type to be Replaced	RCA Replace Direct	meat Similar
7370	· · ·	5687	B739		6679/12AT7,
7494		12AX7A/ECC83,	·		12AT7WA
7543		6681/12AX7A 6AU6WB	B749		5814, 6189, 6680/12AU7A
7543 7645	6939	OAGOND	B759		5751
7700	0333	6C6	BA2		2050
7700 7701		7551	CC81E	12AT7WA,	6679/12AT7,
7717 7717		6CY5	·]	12AT7WB,	12AT7/ECC81
7724		14GT8		6201	
7728	6201		CCa	6922/E88CC	
772 <b>9</b>	0201	6681/12AX7A,	CV216	OD3, OD3A	00
		12AX7A/ECC83	CV618	000 0004	83
7730		6189, 5814A,	CV686	0C3, 0C3A	
		6680/12AU7A	CV752	0A4G	
7731		6678/6U8A,	CV797 CV807	2D21, 5727	<del></del>
		6U8A/6KD8	CV1758	3A4 1L4	<del>,</del>
7732		6CB6A/6CF6	CV1738		
7733		12BY7A/12BV7/ 12DQ7	CA1925	0A2, 0A2WA, 6073	3,
7752		6AS6		6073/0A2, 6626/0A2WA	
8016	1G3GTA/1B3GT		CV1833	0B2, 0B2WA,	<u> </u>
8077, 8077/ 7054	8077/7054	7.054	CA1022	6074, 6074/0B2	
8136	8136	6DK6	ČV1834	6AS7G, 6AS7GA	
8162	12AT7WA	12AT7/ECC81		6080, 6080W	Ä
8196	5754	6AS6	CV1992	0A4G	
8203	8203		CV2129	5763	
8204	5727	2021	CV2240		3B4WA
8380	7587		CV2241	5642	
8382	7586		CV2390	3A4	
8441	7895		CV2466	6939	
8532, 8532/	8532	6J4	CV2492	6922/E88CC	
6J4WA	0050		CV2522	6AS6, 5725	
8556	8056	0074	CV2573	5651A, 5751W/	\
8627	8627	8627A 8627	CV2642	5842/417 <b>A</b>	
8627A	8627A		CV2742,	1L4	
A1834	6080, 6080W	6AS7G, 6AS7GA	CV2795	F707	0001
AA91E	5726	6AL5, 6663/	CV2876 CV2984	5727	2021
		6AL5		6080, 6080WA	6AS7G, 6AS7GA
ABC91	12A6		CV3508	6201	12AT7WA, 12AT7WB 6679/12AT7
AG5210	0B2, 0B2WA, 6074,		CV3512	5696, 5696A	
	6074/0B2		CV3789	5842/417A	
AG5211	0A2, 0A2WA,		CV3798	0A3, 0A3A	
MOVELL	6073, 6073/	0A2	CV3928	5636	5840W
	6626/0A2W	Α	CV3930	5718	
ASG512, ASG5121	2D21, 5727		CV3986	6021	
B339		5751, 6681/	CV4009	5749	6BA6/EF93
2000		12AX7A	CV4011	5725	6AS6

Type to be Replaced	RCA Replace Direct	ement Similar	Type to be Replaced	RCA Replace Direct	ment Similar
CV4017	5751	6681/12AX7A.	E810F		7788
,		12AX7A/ECC83	E1955	2D21, 5727	
CV4018	5727	2021	EAA901,	5726	6AL5, 6663/6AL5
CV4020	0A2WA	0A2	EAA901S		
CV4023	6AU6WB	6AU6A	EC70, EC71	5718	
CV4024	12AT7WA,	6679/12AT7	ECC70	6021	- <del> </del>
014005	12AT7ŴB	CALE CCCO/CALE	ECC88	6DJ8/ECC88	· · · · · · · · · · · · · · · · · · ·
CV4025	5726 OB2WA	6AL5, 6663/6AL5	ECC91		6101
CV4028	UBZWA	082, 6074, 6074/0B2	ECC230	6080, 6080WA	6AS7G, 6AS7GA
CV4031	6101	6J6WA	ECC801 ECC802.	6201	CC00/104U74
CV4039	5763		ECC8025	6189	6680/12AU7A, 12AU7A/ECC82
CV4048	5651A, 5651WA	<del></del>	EF71	5899	1240747 10002
CV4100	OA2WA,	OA2, 6073,	EF72	5840W	
	6626/0A2W	A 6073/0A2	EF93	307011	5749, 6660/6BA6
CV4101	OB2WA	OB2, 6074,	EF94		6136
		6074/0B2	EF95	5654	6AK5/EF95
CV5122	5823		EF730	5636	OANS/ EI 33
CV5186	5651A, 5651W/		EF731	5899	<del></del>
CV5212	6201	12AT7WA, 12AT7WB.	EF732	- 0000	5840
		6679/12AT7	EF905	5654	6AK5/EF95
D2M9		5726	EH900S	3007	5915
DM160		6977		<del></del>	5750
D77. D152.		5726	[EL3/ .		5881, 6L6GC
D717			EN32	2050, 2050A	0001, 02000
DCC90	3A5		EN91	2D21, 5727	
DD6, DD6G		5726	EN92	5696, 5696A	·
DD77	5726		EZ90		6202
DF92	114		G/50/4K		0A2
DL93	3 <b>A4</b>		375/2D		0A3
DL98		3B4WA	G105/1D		OC3
DP61	5654		G150/3D		OD3
DY70	5642		GL546		5696, 5696A
E55L		8233	GQ5G	884	
E81CC	6201, 12AT7W	A 6679/12AT7,	HD51	0A2, 0A2WA,	
<u></u>		12AT7/ECC81	- [	6073,	
E81L	E014A C100	6686	- }	6073/0A2, 6626/0A2W/	A
E82CC	5814A, 6189	6680/12AU7A 12AU7A/ECC82	HD52	082, 082WA,	
E83CC		6681/12AX7A	11032	6074.	
20000		12AX7A/ECC83		6074/0B2	
E88CC	6922/E88CC	<del></del>	HM04		5750
E91AA	5726	6AL5, 6663/6AL5	KD21		0A3
E91H		5915	KD24	OC3, OC3A	
E91N	5727	2021	KD25	OD3, OD3A	
E95F	5654	6AK5/EF95	KT66		5881
E180F		6688A	KT88		6550
	50A7/404A		M8079	5726	6663/6AL5,
E182F	5847/404A		·		6AL5
E188CC		7308	M8081	6101	6J6WA

Type to be Replaced	RCA Replacement Direct Similar		Type to be Replaced	RCA Replac Direct	ement Similar
M8096	5763		Q\$1211	OB2WA	OB2, 6074,
M8098	5651A				6074/0B2
M8100	5654	6AK5/EF95	QS2406	6201	12AT7WA,
M8101		5749, 6660/6BA6			12AT7WB, 6679/12AT
M8136	6189/12AU7WA	12AU7A/ECC82,	QS2404	5726	6AL5
		5814	QS2406	6201	12AT7WA
M8137		5751		<b>3232</b>	12AT7WB
M8138	0001	6202	RL21	2021, 5727	
M8162	6201	6679/12AT7	RL1267	OA4G	
M8180	5654	6AK5/EF95	\$856	0A2, 0A2WA,	
M8190		5783	1	6073/0A2, 6626/0A2WA	ı
M8196		5725	\$860	0B2, 0B2W,	<u>'</u>
M8204	5700	5727	3000	6074,	
M8212	5726, 6663/6AL5	6AL5	1	6074/0B2	
M8223	0A2WA.	OA2, 6073,	STV85/10	5651A	
MULLU	6627/0A2WA	6073/0A2	STV108/30	0B2, 0B2WA,	
M8824	0B2WA	OB2, 6074,		6074, 6074/0B2	
		6074/0B2	STV150/30	00/4/UDZ 042MA 6627/	0A2
M8245	6005	6AQ5A	314130/30	0A2WA, 6627/ 0A2WA, 6073	UAZ
ME1501	2050		.	6073/0A2	•
NE48	991		T2M05		6101
PL21	5727	2D21	T60	8005	
PL1267		0A4G	T66G-GT,		884
PM04		5749	TY66G	· · · · · · · · · · · · · · · · · · ·	<del></del>
PM05	5654	6AK5/EF95	U78		6202
QA2404		5726	VR75	0A3, 0A3A	
QA2408	5692	6SN7GTB	VR105	0C3, 0C3A	
QE03/10, QV03-12	5763		VR150, VR150W	0D3, 0D3A	
QM556		6X4W	VT83		83
QQEQ2/5,	6939		VT138	1629	6 <b>E</b> 5
QQV02-6	000 0004		VT139	0D3, 0D3A	
Q\$150/40	OD3, OD3A		VT202	9002	
QS150C1, QS150C2	0A2, 0A2WA, 6073,		VT203	9003	
<b>G913005</b>	6073/0A2,		W727	0050	5749
	6626/0A2WA		WL630, WL630A	2050	
QS150C3	OD3, OD3A		WT6	1614	6L6, 6L6GC
QS1205	0A3, 0A3A		WT210-0001	2D21, 5727	
QS1206	OC3, OC3A		WT210-0003	884	
QS1207	0A2, 0A2WA,		WT210-0004	2050	2050A
/	6073,		WT210-0006		6H6
	6073/0A2		WT210-0007		6L6, 6L6GC
	6626/0A2WA		WT210-0011	0C3, 0C3A	
QS1208	0B2, 0B2WA,		WT210-0018	OD3, OD3A	
	6074, 6074/0B2		WT210-0019	83	
QS1210	0A2WA.	042 6072	WT210-0021	<del></del>	6X5GT
MO1510	6626/0A2WA	0A2, 6073, 6073/0A2	WT210-0028		3Q5GT

Type to be	RCA Replace	ment	Type to be	RCA Replace	ement
Replaced	Direct	Similar	Replaced	Direct	Similar
WT210-0029		6C5	WT308		6X5GT
WT210-0040	6X4W	6X4	WT389		3Q5GT
WT210-0042		5Y3GT	WT390		6C5
WT210-0048		5U4GB	WT606	2D21, 5727	
WT210-0060		0Z4A/0Z4	WTT100	6X4W	6X4
WT210-0077	5727	2D21	WTT102		5Y3GT
WT210-0081		6SJ7, 5697	WTT103		6H6
WT210-0082		6V6, 6V6GTA	WTT108C1	0B2, 0B2WA,	•
WT210-0084		6N7, 6N7GT	_	6074, 6074/0B2	
WT210-0085	<del> </del>	50B5	WIT114	0Z4A/0Z4	
WT210-0087		6K8	WTT122	5693	6SJ7
WT210-0088		6J5, 6J5GT	WTT123	7092	
WT210-0090		6C6	WIT123	<del></del> _	6V6, 6V6GT/
WT210-0091	OA4G		WTT125	<del></del>	6N7, 6N7GT
WT210-0108	6AS7G, 6080,	6AS7GA	WTT125		5085
	6080WA		- WTT126	833A	3083
WT210-0148		6X5GT	- WTT127	O33M	6K8
WT210-3000	2D21, 5727,				
WTOAF	5727/2D21W		WTT129		6J5, 6J6GT
WT245	884		WTT131		6C6
WT246	2050, 2050A		WTT132	0A4G	
WT261, WT261A		6Н6	WTT135	_	5U4GB
WT269	0C3, 0C3A	<del></del>	X77		5750
WT294	OD3, OD3A		X727		5750
WT301,	83		<del>z900T</del>	5823	
WT301A	UJ		Z3000T	OA4G	<del></del>

H-1081R2



Cutaway Views of Typical Nuvistor Triodes

INDEXING

## PICTURE TUBE CHARACTERISTICS CHART

#### **Color Picture Tubes**

Type No.	Enve- lope Code	Safety Fea- ture	Nom. Befiec- tion Angle Degrees	Heater Volts/mA	Max. Anode Voltage kV <del>-</del>	Range of Focus Voltage in Volts or % of Anode Voltage	Range of G2 Voltage at G1 = 150 V Volts	Screen Diag. Inches	Termi- nal Diagram
14VAHP22* 14VALP22* 15AEP22°	SGA SGA SGA	H M M	90 90 90	6.3/900 6.3/900 6.3/900	22.5 22.5	-75V — +400V ⁹ -75V — +400V ⁹ -75V — +400V ⁹	150 — 390 ⁱ 150 — 390 ⁱ 150 — 390 ⁱ	13.557 13.557 13.557	14BH 14BH 14BH
15LP22° 15NP22°	SGAT SGA	D H	90 90	6.3/900 6.3/900	22.5 -	-75V +400V9 -75V +400V9	150 — 390 ⁱ 150 — 390 ⁱ	13.557 13.557	14BH 14BH
15VADTC01hp 15VAETC01hmp	SGA SGA	H	90 90	6.3/900 6.3/900	27.5 d27.5	16.8 — 20.0 16.8 — 20.0	425 — 820 425 — 820	15.051 15.051	13D 13D
16VACP22° 17EZP22°	SGA SGA	H H	90 90	6.3/900 6.3/900	22.5 - 22.5 -	-75V — +400V ⁹ -75V — +400V ⁹	165 — 420 ¹ 150 — 390 ¹	16.191 16.191	14BH 14BH
17VACP22hm	SGA SGA	F F	90 90	6.3/900 6.3/900	22.5 -	$-75V - +400V^9$ $-75V - +400V^9$	$\frac{150 - 385^{i}}{150 - 385^{i}}$	17.018 17.018	14BH 14BH
17VARP22hm 17VAYTC01bma	SGA	F	90 90	6.3/900 6.3/900 6.3/900	27.5 d27.5	16.8 — 20.0 16.8 — 20.0	255 — 655 425 — 820	17.018 17.018 17.018	14BE 13D
18VAHP225 18VAZP225	SGAT SGA	Ď F	90 90	6.3/900 6.3/900	27.5 27.5 22.5 -	16.8 — 20.0 -75V — +400V ⁹	285 — 685 150 — 390 ¹	18.075 18.075	14BE 14BH
18VBDP22 ^b	SGA	F	90	6.3/900	22.5 -	-75V — +400V ⁹	150 — 390 ⁱ	18.075	14BH
18VBGP22* 18VBJP22*	SGAT SGA	K K	90 90	6.3/900 6.3/900	22.5 -	-75V — +400V ⁹ -75V — +400V ⁹	150 — 390 ¹ 285 — 685	18.075 18.075	14BH 14BH
18VBKP22hm 19GVP22/	SGA	F	90	6.3/900	27.5	16.8 — 20.0	285 — 685	18.075	14BE
19EXP22° 19GWP22/	SGA	Α	90	6.3/900	27.5	16.8 — 20.0	285 — 685	18.075	14BE
19EYP22° 19HCP22/	SGAT	D	90	6.3/900	27.5	16.8 - 20.0	285 — 685	18.075	14BE
19HKP22° 19HNP22°	SGA SGA	F F	90 90	6.3/900 6.3/900	27.5 22.5 -	16.8 — 20.0 -75V — +400V ⁹	285 — 685 150 — 390 ¹	18.075 18.075	14BE 14BH
19JWP22° 19VABP22°	SGAT RGAT	D D	90 70	6.3/900 6.3/1800		$-75V - +400V^9$ $16.8 - 20.0$	150 — 390; 310 — 690	18.075 19.250	14BH 14AU
19VANP22" 19VBLP22"	SGA SGA	F	90	6.3/900		-75V — +400V ⁹	150 — 390	18.897	14BH
19VBQP22hm	SGA	F	110 90	6.3/900 6.3/900	22.5 -	16.8 — 20.0 -75V — +400V ⁹	265 — 665 150 — 375 [†]	18.897 18.897	13 <b>C</b> 14BH
19VBRP22°* 19VCTP22°*	SGA SGA	F F	90 90	6.3/900 6.3/900	27.5 27.5	16.8 — 20.0 16.8 — 20.0	285 — 685 260 — 660	18.897 18.897	14BE 14BE
19VDSP22*** 19VDTP22*	SGA SGA	F F	90 90	6.3/900 6.3/900	d27.5 d27.5	16.8 — 20.0 16.8 — 20.0	260 — 660 260 — 660	18.897 18.897	14BE 14BE
19VEDP22hm 19VEUP22h	SGA SGA	F F	90 90	6.3/900 6.3/900	d32.0 d32.0	16.8 - 20.0 $16.8 - 20.0$	250 — 645 250 — 645	18.897 18.897	14BE 14BE
20VAGP22"	SGAT	D	90	6.3/900	⁻ 27.5	16.8 - 20.0	285 - 685	20.233	14BE
20VAHP22 ^h 21FJP22 ^c 21GUP22/	SGA RGAT	F D	90 70	6.3/900 6.3/1800	22.5 - 27.5	-75V — +400V ⁹ 16.8 — 20.0	150 — 390 ⁱ 310 — 690	20.233 19.250	14BH 14AU
21FBP22A° 21GVP22/	RGA	A	70	6.3/1900	27.5	16.8 — 20.0	310 — 690	19.250	14AU
21FJP22Ac 21VAKP22bm	RGAT SGAT	D D	70 90	6.3/1900 6.3/900	27.5 27.5	16.8 — 20.0 16.8 — 20.0	310 — 690 285 — 685	19.250 20.871	14AU 14BE
21 VAMP22° 21 VBEP22°	SGAT SGA	D F	90 90	6.3/900 6.3/900	27.5 d32.0	16.8 — 20.0 16.8 — 20.0	285 —685 250 — 645	20.871	14BE
22JP22° 22KP22°	SGAT	D	90	6.3/900	27.5	16.8 - 20.0	250 — 645 285 — 685	20 871 20.233	14BE 14BE
22UP22°	SGA SGA	A F	90 90	6.3/900 6.3/900	27.5 <b>2</b> 7.5	16.8 — 20.0 16.8 — 20.0	285 — 685 285 — 685	20.233 20.233	14BE 14BE

Color Picture Tubes (Co	nt.`
-------------------------	------

Type No.	Enve- lope Code	Safety Fea- ture ★	Nom. Deflec- tion Angle Degrees	Hezter Volts/mA	Max. Anode Voltage kV+	Range of Focus Voltage in Volts or % of Anode Voltage	Range of at G1 = —150 V Volts	Screen Diag. Inches	Termi- nal Diagram
23VALP22bm	SGAT	D	90	6.3/900	27.5	16.8 — 20.0	260 — 660	22.995	14BE
23VANP22b	SGAT	Ď	90	6.3/900	27.5	16.8 - 20.0	260 - 660	22.995	14BE
23VAQP22°	SGA	Ē	90	6.3/900	27.5	16.8 - 20.0	260 - 660	22.995	14BE
25BCP22cm	SGAT	Ď	90	6.3/900	27.5	16.8 - 20.0	260 - 660	22.995	14BE
25VABP22cm	SGAT	D	90	6.3/900	27.5	16.8 - 20.0	260 - 660	24.658	14BE
25VAEP22°	SGAT	D	90	6.3/900	27.5	16.8 — 20.0	260 — 660	24.658	14BE
25VAMP22cm	SGAT	D	90	6.3/900	27.5	16.8 - 20.0	250 650	24.658	14BE
25VBEP221m	SGA	K	90	6.3/900	27.5	16.8 - 20.0	285 - 685	24.658	14BE
25VCKP22°	SGAT	Ď	90	6.3/900	d32.0	16.8 - 20.0	250 - 645	24.658	14BE
25VCZP22hm	SGA	F	90	6.3/900	d32.0	16.8 - 20.0	295 - 680	24.658	14BE
25VDXP22hm 25XP22/	SGA	D	90	6.3/900	d32.0	16.8 — 20.0	250 — 645	24.658	14BE
25AP22A°	SGAT	D	90	6.3/900	27.5	16.8 - 20.0	285 - 685	22.995	14BE
25YP22/ 25BP22Ac	SGA	Α	90	6.3/900	27.5	16.8 — 20.0	285 — 685	22.995	14BE

#### **Color Test Picture Tube**

1830P22 1895P22	SGAT SGAT	D			27.5 16.8 — 20.0 d32.0 16.8 — 20.0	285 — 685 260 — 660		
1933177	SPAI	ע	90	0.3/900	032.U 10.8 - 20.U	200 — DDU	18.0/5	148E

#### Silverama Types for Black-and-White TV

Typs Ne.	Enve- iope Code	Safety Fea- ture ★	Nom. Deflec- tion Angle Degree	Heater	Focus- ing Method	Design Max. Anode Voltage kV	Typical G2 Voltage Volts	Screen Diag. Inches	Max. Over- all Length Inches	Termi- nal Diagram
5VABP4	SGA	Α	70	12.0/79	E	15.0	115	5.036	7.550	7GR
80P4‡	SG	A F	90	6.3/600	E	9.0	200	7.750	10.750	12AB
9AEP4	SGA		85	6.3/450	Ε	15.0	100	9.024	8.700	7GR
9VABP4	SGA	F	85	6.3/450	E	15.0	140	9.024	8.700	7GR
9VAJP4	SGA	H	90	11.0/140	Ε	15.0	90	9.000	8.700	7GF
9WP4	SGA	G	90	12.0/75	Ε	12.0	100	8.270	8.270	7GR
10ATP4	SGA	F	85	6.3/300	Ε	15.0	140	9.024	8.700	7GR
10AVP4	SGA	F	85	12.0/79	Ε	15.0	90	9.024	8.700	7GR
11CP4	SGA	Α	110	6.3/450	Ε	15.0	400	10.125	9.188	8HR
11 <b>G</b> P4	SGA	C	110	6.3/450	Ē	15.0	135	10.188	9.188	8HR
12BNP4A	SGA	J	110	6.3/450	E	16.0	250	11.625	9.598	8HF
12DEP4	SGA	F	110	6.3/450	Ē	15.0	100	11.625	9.690	7GF
12DFP4	SGA	Ĥ	110	6.3/450		15.0	200	11.620	9.060	7GF
12DKP4	SĞA	F	110	6.3/450	E E	16.0	140	11.625	9.374	7ĞF
12DSP4	SGA	Н	110	6.3/300	E	15.0	140	11.625	9.274	7GF
12VAGP4	SGA	G	110	6.3/300	E	14.0	200	11.500	9.530	7GF
12VAQP4	SGA	G	110	4.2/450	Ē	15.0	140	11.500	9.530	7ĞF
12VAWP4	SGA	Ī	110	6.3/450	Ē	15.0	130	11.500	9.53	7GI
12VAXP4	SGA	Ĺ	110	11.0/82	Ē	14.0	150	11.500	9.530	ŹĞĒ
12VBNP4	SGA	Ĥ	90	11.0/140	Ē	15.0	90	11.500	11.125	7GI

[▲] Terminal diagrams for RCA picture tubes are shown on pages 672 and 673. For SAFETY PRECAUTIONS and NOTES refer to page 670. ‡ Requires ION trap.

## Silverama^a Types for Black-and-White TV (Cont.)

Type No.	Enve- lope Code	Safety Fea- ture ★	Nom Defie tion Angle Degre	<b>c-</b>	Focus- ing Method	Design Max. Anode Voltage kV	Typical G2 Voltage Volts	Screen	Max. Over- all Length Inches	Termi- nal Diagram
15VACP4 16CMP4A 16RP4B 16VAGP4 16VBYP4	SGA SGA SGA SGA SGA	H G A H F	114 114 70 114 114	6.3/450 6.3/450 6.3/600 6.3/450 11.0/140	E E M E E	20.0 18.0 17.5 20.0 22.0	30 300 300 30 30 130	14.875 14.875 14.875 16.250 16.250	10.811 10.811 19.125 11.445 11.450	8HR 8HR 12 <b>N</b> 8HR 8HR
17BP4D 17CFP4 17BQP4 17DRP4 17LP4B	SGA SGA SGA SGA SGCA	A A A A	70 90 110 110 70	6.3/600 6.3/600 6.3/450 2.68/450 6.3/600	M E E E E	17.5 17.5 17.5 17.5 17.5	300 300 50 300 300	15.562 15.750 15.750 15.750 15.562	19.562 14.375 12.375 11.000 19.562	12N 12L 7FA 8JK 12L
17QP4B 18VAUP4 19ABP4 19AFP4 19AJP4	SGCA SGA SGA SGA SGA	A F A B	70 114 114 114 114	6.3/600 6.3/450 2.68/450 6.3/600 6.3/450	M E E E	20.0 23.5 20.0 20.0 20.0	300 30 300 300 50	15.562 17.562 17.562 17.625 17.562	19.562 11.875 11.125 11.938 11.625	12N 8HR 8JK 8HR 7FA
19AVP4 19AYP4 19BDP4 19CHP4 19CMP4	SGA SGA SGA SGA	A A A A	114 114 92 114 114	6.3/600 6.3/450 6.3/600 6.3/600 6.3/450	E E E E	23.0 23.0 19.8 20.0 20.0	400 400 50 50 30	17.562 17.562 17.562 17.562 17.562	11.625 11.625 15.625 11.875 11.875	8HR 8HR 12L 8HR 8HR
19CVP4 19CXP4 19DBP4 19DQP4 19DRP4	SGA SGA SGA SGA SGA	B A D G	114 114 114 114 114	6.3/450 6.3/600 6.3/450 6.3/450 6.3/600	E E E E	23.0 20.0 19.8 23.0 23.0	50 45 40 300 300	17.625 17.562 17.562 17.562 17.562	11.938 11.875 12.125 11.875 11.875	8HR 7FA 7FA 8HR 8HR
19DSP4 19DUP4 19EBP4 19EGP4 19EZP4	SGA SGA SGA SGA SGA	G F C C	114 114 114 114 114	6.3/600 6.3/450 6.3/600 6.3/450 6.3/450	EEE	20.0 22.0 23.0 21.0 19.8	50 50 400 50 45	17.562 17.562 17.562 17.562 17.562	11.875 11.969 11.875 11.875 11.875	8HR 8HR 8HR 8HR 7FA
19FLP4 19GAP4 19GEP4A 19VAHP4 19VAJP4	SGA SGA SGA SGA SGA	G C L H	114 114 114 114 114	6.3/450 6.3/450 6.3/450 6.3/450 9.45/300	E E E	23.0 19.8 23.0 23.0 23.0	300 400 300 30 30	17.562 17.562 17.562 18.625 18.625	11.625 11.875 11.875 12.519 12.519	8HR 8HR 8HR 8HR 8HR
19VALP4 19VFEP4 20RP4 20VAQP4 21AMP4B	SGA SGA SGA SGA SGA	C F F A	114 114 114 114 90	6.3/450 11.0/140 6.3/450 6.3/450 6.3/600	E E E M	23.0 23.0 22.0 23.5 20.0	300 130 50 30 300	18.625 18.625 18.625 19.625 20.250	12.519 12.644 12.613 12.937 20.375	8HR 8HR 8HR 8HR 12N
21AVP4C 21AWP4A 21CBP4A 21CQP4 21DLP4	SGA SGA SGA SGA SGA	A A A A	72 72 90 110 90	6.3/600 6.3/600 6.3/600 6.3/600 6.3/600	E M E E	22.0 20.0 22.0 20.0 20.0 22.0	300 400 300 300 300	20.250 20.250 20.250 20.250 20.250 20.250	23.406 23.406 18.375 14.812 17.375	12L 12N 12L 7FA 12L
21DSP4 21EMP4/ 21EQP4 21EP4C 21FDP4 21FP4B	SGA SGCA SGA SGCA	A A A A	90 110 70 110 70	6.3/600 6.3/600 6.3/600 6.3/600 6.3/600	E M E E	22.0 20.0 20.0 20.0 20.0	50 500 300 300 300 300	20.250 20.250 20.000 20.250 20.000	18.375 13.440 23.406 13.375 23.406	12L 8HR 12N 8KW 12L

#### Silverama^a Types for Black-and-White TV (Cont.)

Type No.	Enve- lope Code	Safety Fea- ture ★	Nom. Deflec- tion Angle Degrees	Heater s Volts/mA	Focus- ing Method	Design Max. Anode Voltage kV	Typical G2 Voltage Volts	Screen Diag. Inches	Max. Over- all Length Inches	Termi- nal Diagram ▲
21FVP4 21GAP4A 21WP4B 21XP4B 21YP4B	SGA SGA SGA SGA SGA	G G A A	114 114 70 70 70	6.3/450 6.3/450 6.3/600 6.3/600 6.3/600	E M E E	23.0 23.5 20.0 20.0 20.0	400 30 300 300 300 300	19.625 19.625 19.250 19.250 20.000	12.937 12.937 22.812 22.812 23.406	8HR 8HR 12 <b>N</b> 12L 12L
21ZP4C 22YABP4 22YACP4 22YADP4 22YAEP4	SGA SGA SGAT SGA SGA	A F D C K	70 110 110 92 110	6.3/600 6.3/450 6.3/450 6.3/450 6.3/450	M E E E	20.0 23.5 23.0 25.0 23.0	300 30 30 400 300	20.000 22.312 22.312 22.312 22.312	23.406 14.406 14.594 18.375 15.156	12N 8HR 8HR 12L 8HR
23AHP4/ 23ASP4 23ARP4 23BGP4 23BJP4 23BKP4	SGA SGA SGA SGA SGA	A A B A B	92 110 110 92 92	6.3/600 6.3/600 6.3/600 6.3/600 6.3/600	E E E	22.0 22.0 22.0 25.0 25.0	400 400 50 50 50	22.312 22.312 22.312 22.312 22.312 22.312	17.875 15.156 15.562 18.500 18.875	12L 8HR 8HR 12L 12L
23BQP4 23CGP4 23CP4 23CP4A 23CQP4	SGA SGA SGA SGA SGA	B A B B	110 92 110 110 114	6.3/450 6.3/450 6.3/600 6.3/600 6.3/450	E E E E	23.0 22.0 22.0 23.5 23.5	300 500 400 300 500	22.312 22.312 22.312 22.312 22.312 22.312	15.562 18.375 15.562 15.562 14.000	8HR 12L 8HR 8HR 8HR
23DAP4 23DBP4 23EKP4 23ENP4 23EP4	SGA SGA SGA SGA SGA	A G G B	94 110 92 92 110	6.3/600 6.3/600 6.3/450 6.3/600 6.3/600	E E E E	23.0 22.0 25.0 25.0 22.0	50 50 400 50 50	22.312 22.312 22.312 22.312 22.312 22.312	17.391 15.156 18.375 18.500 15.562	8HR 8HR 12L 12L 8KP
23ETP4 23EWP4A 23EYP4 23EZP4 23FP4A	SGA SGA SGA SGA SGA	G F C K A	110 114 92 94 114	6.3/600 6.3/450 6.3/600 6.3/450 6.3/600	EEE	23.0 22.0 25.0 23.5 23.5	300 400 35 50 500	22.312 22.312 22.312 22.312 22.312	15.156 14.812 18.500 17.390 14.062	8HR 8HR 12L 8HR 8HR
23FRP4 23FSP4 23GWP4 23HFP4A 23HWP4A	SGA SGA SGA SGA SGA	CCFGL	110 110 110 110 110	6.3/450 6.3/600 6.3/450 6.3/450 6.3/450	E E E	23.0 23.0 22.0 23.0 22.0	50 400 50 300 50	22.312 22.312 22.312 22.312 22.312	14.500 15.125 14.781 15.156 15.156	8HR 8HR 8HR 8HR 8HR
23JEP4 23JP4 23NP4 23YP4 24AEP4	SGA SGA SGA SGA SGA	K B A B	110 110 114 92 90	6.3/450 6.3/450 6.3/600 6.3/600 6.3/600	E E E	23.0 22.0 22.0 22.0 22.0 22.0	300 50 50 300 300	22.312 22.312 22.312 22.312 22.312 22.812	15.156 15.875 14.812 18.750 19.500	8HR 7FA 8HR 12L 12L
24AHP4 24AUP4 24CP4B	SGA SGA SGA	A A A	110 90 90	6.3/600 6.3/600 6.3/600	E E M	22.0 22.0 22.0	400 300 300	22.812 22.812 22.812	16.188 18.500 21.500	8HR 12L 12N

		Bla	ck-an	d-White	Test	t Pictu	re Tu	be		
8XP4	SGA	A	90	6.3/600	A	22.0	400	7.750	11.750	128

[▲] Terminal diagrams for RCA picture tubes are shown on pages 672 and 673. For SAFETY PRECAUTIONS and MOTES refer to page 670.

#### SAFETY PRECAUTIONS

In servicing a television receiver that requires a replacement picture tube, a tube with the same type number or an RCA recomreplacement tube mended

should be used to assure the same improved integral x-radiation shielding and implosion protection. Note: For additional Safety

Precautions, refer to page 93.

#### Notes for Picture Tube Characteristics Chart

- Envelope Code (All types have spherical faceplate except where noted)
- R Round
- S Rectangular G Glass
- C Cylindrical faceplate
- A Aluminized
- T Treated faceplate

#### ★ Safety Feature

- A Conventional Tube Requires Safety Window in Receiver
- B Integral Moulded-Glass Safety Panel (Bi-Panel*)
- C Filled Rim (Shelbond†)
- D Integral Safety Panel (Laminated)
- F Tension Band Over Formed Rim Bands (Kimcode 1)
- G Welded Tension Band Over Formed Rim Bands (Pan-O-Ply*)
- H Tension Band Over Tape (T-Band)
- J Welded Tension Band Over Tape (T-Band)
- K Tension Band Over Formed Rim Bands With Mounting Lugs (Kimcode/Lugs)

- L Welded Tension Band Over Formed Rim Bands With Mounting Lugs (Pan-O-Ply/Lugs)
- M Tension Band With Mounting Lugs Over Tape (T-Band Lugs)

#### ■ Focusing Method

- A Automatic focus
- E Electrostatic focus
- M Magnetic focus

#### Footnotes

- a. All Materials and parts used in the manufacture of Silverama Picture Tubes are new except for the envelope which, prior to reuse, was carefully inspected to meet the standards of the original new envelope.
- b. Both Colorama and Hi-Lite versions are available.
- c. Only Colorama versions (prefix C- or CA-) are available. RCA Colorama Picture Tubes contain used materials which, prior to reuse, are carefully in-

- spected to meet RCA's high quality standards,
- Absolute-Maximum value. g. This type has an einzel lens focus system. Values shown are in volts which do not vary with anode voltage.
- h. Only Hi-Lite Versions (prefix H-) are available. RCA Hi-Lite Color Picture Tubes contain all New Parts and Materials.
- i. At Grid-No.1 voltage of -- 100 volts.
- k. At Grid-No.1 voltage of -50 volts.
- m. MATRIX Color Picture Tube.
- p. Precison In-Line Color Picture Tube.
- Trademark of RCA, Lancaster, Pa., 17604.
- † Trademark Corning of Glass Works. Corning, N.Y. 14830
- ♦ Trademark Owensof Illinois, Inc., Columbus, Oh. 58727
- ♣ Design-Maximum value unless otherwise noted.


Key to Color Picture Tube Type Designation System

Old-Designa- tion Series (Rounded-off Tube Glass Diagonal in Inches)	Equivalent New Designa- tion Series (Rounded-off Min. Screen Diagonal in Inches)	Comparable Japanese Designation Series (Rounded-off Tube Glass Diagonal in mm)	Other Designation Series Replaced by this Series
11	10 V	270	_
12	_		<del>-</del>
13	12 V	320	
14	-	350	
15	14 V	370	
16	-	400	<del></del>
	15 V	420	_
17	16 V	440	_
_	17 V	470	<b>→</b>
19	18 V	490	-
_	19 V	510	-
21	<del></del>	_	-
21 (Round)	19 V	-	_
22	20 V	550	21
22	21 V		-
23	_	-	-
25	23 V		23
26	25 V		


#### Key to Black-and-White Picture Tube Type Designation System

Old-Designa- tion Series (Rounded-off Tube Glass Diagonal in Inches)	Equivalent New Designa- tion Series (Rounded-off Min. Screen Diagonal in Inches)	Comparable Japanese Designation Series (Rounded-off Tube Glass Diagonal in mm)	
9	_	230	
10	_	240	
11	10 V	280	
12	12 V	310	
13	<del>-</del>		
	13 V	340	
14	<b>→</b>	<b>→</b>	
15	<del>-</del>		
16	15 V	400	
17	16 V	440	
19	18 V	470	
20	19 V	500	
21	20 V	520	
22	21 V		
23	22 V	590	
24	-		
25	<del>-</del> .	_	


# Terminal Diagrams for Picture Tubes




**7FA**Anode = G₃ + G₅ + CL
Focusing Electrode = G₄




**7FG**Anode = G₃ + G₅ + CL
Automatic Focusing




7GR
Anode=G₃+G₅+CL
Focusing Electrode=G₄




8HR
Anode=G₁+G₅+CL
Focusing Electrode=G₄




**8JK**Anode=G₁+G₅+CL
Focusing Electrode=G₄




**8KP**Anode = G₃ + G₅ + CL
Focusing Electrode = G₄




**8KW**Anode=G₃+G₅+CL
Focusing Electrode=G₄




12AB
Anode=G₃+G₅+CL
Focusing Electrode=G₄




12L
Anode=G₃+G₅+CL
Focusing Electrode - G₄




12N Anode=G₃+CL




12S Anode = G₃ + G₅ + CL Automatic Focusing




13C Anode = G₄ + CL Focusing Electrode = G₃




 $\begin{array}{c} \textbf{13D} \\ \textbf{Anode} = \textbf{G_2} + \textbf{CL} \\ \textbf{Focusing Electrode} = \textbf{G_3} \end{array}$ 



14AU
Anode=G₄+G₅+CL
Focusing Electrode==G₁



14BE
Anode=G₄+G₅+CL
Focusing Electrode=G₃



 $\begin{array}{c} \textbf{14BH} \\ \textbf{Anode} = \textbf{G}_3 + \textbf{G}_5 + \textbf{CL} \\ \textbf{Focusing Electrode} = \textbf{G}_4 \end{array}$ 

## Circuits

THE circuits included in this Manual illustrate some of the more important applications of RCA receiving tubes; they are not necexamples of essarily commercial practice. These circuits have been conservatively designed and are capable of excellent performance. The brief description provided with each circuit explains the functional relationships of the various stages and points out intended applications, maior performance characteristics, and significant design features of the over-all circuit. Detailed descriptive information on individual circuit stages (for example, amplifiers, detectors, or oscillators) is given in the section on Electron-Tube Applications earlier in this Manual, as well as in many textbooks on electrontube circuits.

Electrical specifications are given for circuit components to assist those interested in home construction. Layouts and mechanical details are omited because they vary widely with the requirements of individual set builders and with the sizes and shapes of the components employed.

Circuits designed for operation from both ac and dc voltage supplies should be installed in non-metallic cabinets or properly insulated from metallic cabinets. Potentiometer shafts and switches should make use of insulated (plastic) knobs. In practical use, no metallic part of an "ac/dc" chassis should be exposed to touch, accidental or otherwise. When such circuits are tested outside of their cabinets, a line isolation transformer such as the RCA WP-25A Isotap should be used.

Performance of these circuits depends as much on the quality of the components selected and the care employed in layout and construction as on the circuits themselves. Good signal reproduction from receivers and amplifiers requires the use of good-quality speakers, transformers, chokes, and input sources (microphones, phonograph pickups, etc.).

Coils for the receiver circuits may be purchased at local parts dealers by specifying the characteristics required: for rf coils, the circuit position (antenna or interstage), tuning range desired, and tuning capacitances employed; for if coils or transformers, the intermediate frequency, circuit position (1st if, 2nd if, etc.), and, in some cases, the associated tube types; for oscillator coils, the receiver tuning range, the intermediate frequency, the type of converter tube, and the type of winding used (tapped or transformercoupled).

The voltage ratings specified for capacitors are the minimum dc working voltages required. Paper, mica. or ceramic capacitors having higher voltage ratings than those specified may be used except insofar as the physical sizes of such capacitors may affect equipment layout. However, if electrolytic capacitors having substantially higher voltage ratings than those specified are used, they may not "form" completely at the operating voltage, with the result that the effective capacitances of such units may be below their rated value. The wattage ratings specified for resistors assume methods of construction that provide adequate ventilation; com-

D---

pact installations having poor ventilation may require resistors of higher wattage ratings.

Circuits which work at very high frequencies or which are required to handle very wide bandwidths demand more than ordinary skill and experience in construction. Placement of component parts is quite critical and may require considerable experimentation. All rf leads to components including bypass capacitors must be kept short and must be prop-

erly dressed to minimize undesirable coupling and capacitance effects. Correct circuit alignment and oscillator tracking may require the use of a cathode-ray oscilloscope, a high-impedance vacuum-tube voltmeter, and a signal generator capable of supplying a properly modulated signal at the appropriate frequencies. Unless the builder has had considerable experience with broad-band, high-frequency circuits, he should not undertake the construction of such circuits.

	LIST OF CIRCUITS	rage
29-1	AC/DC Superheterodyne Radio Receiver	677
29-2	AM/FM Superheterodyne Radio Receiver	678
29-3	FM Tuner	682
29-4	Three-Stage IF Amplifier/Limiter and Detector	684
29-5	FM Stereo Multiplex Adapter	686
29-6	Preamplifier for Amateur Receiver (21-, 30-, and 50-MHz Amateur Bands and 27-MHz Citizens Band)	688
29-7	Code-Practice Oscillator	690
29-8	Intercommunication Set (With Master Unit and Two or More Remote Units)	691
29-9	High-Fidelity Audio Amplifier (Class AB ₁ ; Power Output, 15 Watts)	692
<b>29-10</b>	High-Fidelity Audio Amplifier (Class AB ₁ ; Power Output, 30 Watts)	694
29-11	High-Fidelity Audio Amplifier (Class AB ₁ ; Power Output, 50 Watts)	696
29-12	Two-Channel Stereophonic Amplifier (Power Output, 1 Watt Each Channel)	
29-13	Microphone and Phonograph Amplifier (Power Output, 8 Watts)	699
29-14		700
29-15	Phonograph Amplifier (Power Output, 1 Watt)	701
29-16		
	(With RIAA Equalization)	702
29-17		
	(With NARTB Equalization)	703
29-18	Preamplifier for Ceramic Phonograph Pickup	704
20.10	(Cathode-Follower Output)	704
4 <b>7-1</b> 9	Low-Distortion Preamplifier (For Low-Output, High-Impedance Microphones)	705

TICT OF CIDCLITTS

29-20	Bass and Treble Tone-Control Amplifier	706
29-21	Electronic Volt-Ohm Meter	707
29-22	Series-Type Stabilized Voltage Supply	710
29-23	All-Purpose Power Supplies	711
29-24	•	713
29-25		
_,	White TV Receiver)	716
29-26		
_, _,	Receiver)	718
29-27		
	Rectifier (For Black-and-White TV Receiver)	720
29-28	Low-Voltage and Heater Supply (For Black-and-White TV Receiver)	724
29-29		
	tions (For Color TV Receiver)	726
29-30	VHF Tuner (For Color TV Receiver)	728
29-31	Video- and Sound-Channel Circuits (For Color TV Receiver)	731
29-32	Sync, AGC, and Vertical-Deflection Circuits (For Color TV Re-	
_,	ceiver)	735
29-33	•	
_,	Color TV Receiver)	737
29-34	Chroma Circuits (For Color TV Receiver)	741
29-35	Picture Tube and Associated Circuits (For Color TV Receiver)	745


## MANUFACTURERS OF SPECIAL COMPONENTS AND MATERIALS REFERRED TO IN PARTS LIST

Allen-Bradley Co. 1201 S. 2nd Street Milwaukee, Wis. 53204 Alpha Wire Corp. 711 Lidgerwood Avenue Elizabeth, N. J. 07202 Arco Electronics, Inc. Community Drive Great Neck, N. Y. 11021 Freed Transformer Company, Inc. 1795 Weirfield Street Brooklyn, N. Y. 11227 **Knight Products** Allied Radio Corp. 100 N. Western Avenue Chicago, Ill. 60612 J. W. Miller Co. 5917 S. Main Street Los Angeles, Calif. 90003

Moldite Electronics Corp. 250 South Street Newark, N. J. 07114 Ohmite Manufacturing Co. 3635 W. Howard Street Skokie, Ill. 60076 Stancor Electronics, Inc. 3501 W. Addison Street Chicago, Ill. 60618 Thordarson-Meissner, Inc. Electronic Center 7th and Bellmont Mt. Carmel, Ill. 62863 Triad Distributor Div. Litton Industries 305 N. Briant Street Huntington, Ind. 46750 United Transformer Corp. Div. Thompson-Ramo-Wooldridge, 150 Varick Street New York, N. Y. 10013

Note: Components and materials identified by RCA stock numbers may be obtained through authorized RCA distributors.

#### 29-1 AC/DC SUPERHETERODYNE RADIO RECEIVER



#### **Parts List**

C1, C5=Ganged tuning capacitors; C1, 10-365 pF, C5, 7-115 pF
C3=Trimmer capacitor, 4-30 pF
C3=0.05 µF, paper, 50 V
C4=0.1 µF, paper, 400 V
C5=Trimmer capacitor, 2-17 pF
C7=56 pF, ceramic
C3=30 µF, electrolytic, 150 V
C6, C10=150 pF, ceramic
C11, C1=0.02 µF, paper, 400 V
C13=0.002 µF, paper, 400 V
C13=0.002 µF, paper, 400 V
C13=380 pF, mice

C15=0.05 µF, paper, 400 V
C1s=50 µF, electrolytic,
150 V
I=Panel lamp, No. 40 or 47
L=Loop antenna or ferriterod antenna, 540-1600 kHz
(with specified values of
capacitance for C1 and C2)
R1=0.22 megohm, 0.5 watt
R3=3000 ohms, 0.5 watt
R4=3.3 megohms, 0.5 watt
R4=3.3 megohms, 0.5 watt
R5=47000 ohms, 0.5 watt
R6=Volume control, potentiometer, 0.5 megolm
R7=4.7 megohms, 0.5 watt
R8, R8=0.47 megohm,
0.5 watt

R₁₀=150 ohms, 0.5 watt R₁₁=1200 ohms, 1 watt S₁=On-off switch; singlepole, single-throw SP₁=Speaker

T1: Oscillator coil for use with 7-115 pF tuning capacitor and 455-kHz intermediate-frequency transformer

T2, T3=Intermediate-frequency transformers, 455 kHz (permeability-tuned type may be used)

T₄=Output transformer for matching impedance of voice coil to 2500-ohm load

#### **Circuit Description**

This basic five-tube superheterodyne radio receiver operates directly from an ac power line or a dc supply of 117 volts. AC power inputs are converted to dc power by the 35W4 half-wave rectifier circuit. The receiver uses a series heater arrangement. With ON-OFF switch S₁ closed, the heater string is connected directly across the 117-volt input terminals. A 6.3-volt panel lamp I₁ connected between heater pins 3 and 6 of the 35W4

rectifier tube lights to indicate that power is applied to the receiver.

A ferrite-rod or loop antenna L and tuning capacitor C₁ select amplitude-modulated rf signals from the desired broadcast-band (550 to 1600 kHz) radio station and couple these signals to grid No. 3 (pin 7) of the 12BE6 pentagrid converter. A local-oscillator signal, developed by the resonant circuit formed by oscillator coil T₁ and variable capacitors C₈ and

#### 29-1 AC/DC SUPERHETERODYNE RADIO RECEIVER (Cont'd)

Circuit Description (Cont'd)

C₆, is also applied to the 12BE6 pentagrid converter, at grid No. 1 (pin 1). The modulated-rf and local-oscillator signals are mixed across the nonlinear impedance of the converter tube to produce the 455-kHz intermediate frequency used in the receiver. The antenna and oscillator tuning capacitors C1 and C5 are mechanically ganged so that the antenna and oscillator resonant circuits can be adjusted together to maintain the 455-kHz difference frequency for any dial setting in the broadcast-frequency band. Trimmer capacitors C2 and Co are adjusted to assure that the desired tracking relationship is maintained across the band. Positive feedback to sustain oscillations is inductively coupled by T1 from the cathode of the 12BE6 converter to the local-oscillator resonant circuit.

A single if stage, which uses a high-transconductance 12BA6 remote-cutoff pentode, provides the required amplification of the intermediate-frequency signals. This stage is made selective at 455 kHz by the double-tuned input and output transformers T₂ and T₃. Audio-signal components are extracted from the if

signal by the second-detector circuit, which consists of the pin 6 diode section in the 12AV6 tube and associated components. (The pin 5 diode section of the 12AV6 is not used and is shorted to the tube cathode, pin 2.) The audio output from the detector is developed across the VOL. CONT. potentiometer Re, which provides manual adjustment of the output sound level of the receiver. The detector also develops a negative de voltage proportional to the rf input across a 150-picofarad capacitor Co for automatic volume control in the receiver. This ave voltage is used as bias for the converter and if amplifier and automatically controls the gain of these stages.

The audio-signal voltage at the wiper arm of the VOL. CONT. potentiometer is amplified by the triode (audio-voltage-amplifier) section of the 12AV6 and is then used to drive the 50C5 audio output stage. The output stage develops the audio power required to produce an audible output from the speaker. Audio output transformer T. matches the 2500-ohm plate-load impedance of the 50C5 to the speaker voice coil.


#### 29-2 AM/FM SUPERHETERODYNE RADIO RECEIVER

#### Circuit Description

This AM/FM radio receiver operates directly from either an ac power line or a dc supply of 117 volts. AC power inputs are converted to dc power by a 1N3756 silicon-rectifier half-wave power supply. The receiver uses a series heater string, which is connected across the 117-volt input when ON-OFF switch S₃ and interlock S₂ are closed. The interlock assures that power is automatically disconnected when the receiver is removed from the chassis.

AM or FM operation of the receiver is selected by means of switch S₁. For AM operation (S₁ set to AM position), amplitude - modulated rf signals in the AM broadcast band (550 to 1600 kHz) from the desired radio broadcast station are selected by antenna L2 and tuning capacitor C25. These signals are amplified and converted to the 455-kHz AM intermediate frequency by the 12BE6 pentagrid converter. Tuning capacitors C25 and C27 are mechanically ganged so that the antenna and local-oscillator sections of the converter can be tuned simultaneously to maintain the 455-kHz difference frequency for any station setting. Trimmer adjustments are provided by variable capacitors Con and Cos.


## AM/FM SUPERHETERODYNE RADIO RECEIVER (Cont'd)



#### **Parts List**

C₁=Part of PC₁ C₂=Part of PC₂ C₃, C₁:=Ganged tuning capacitors; tune L₁ and T₂ to 88-108 MHz C₁, C₁₂=Trimmer capacitors, 1-7 pF C₅, C₁₆, C₁₈=1000 pF, feedthrough, 500 V C₆=0.1 μF, ceramic, 500 V  $C_7$ =36 pF, ceramic, 500 V  $C_8$ ,  $C_{14}$ =6.8 pF, ceramic, 500 V  $C_{0}$ =11 pF, ceramic, 500 V  $C_{10}$ =68 pF, ceramic, 500 V

## AM/FM SUPERHETERODYNE RADIO RECEIVER (Cont'd)



#### Parts List (Cont'd)

 $C_{11}$ =21 pF, ceramic, 500 V  $C_{15}$ =500 pF, feedthrough, 500 V  $C_{17}$ =0.22  $\mu$ F, ceramic disc, 500 V C₁₀, C₂₀=2 pF, feedthrough, 500 V C₂₁, C₃₅, C₃₀=2000 pF, feedthrough, 500 V C₂₂=IF transformer tuning capacitor; value, with cable capacitance, tunes Ts to 10.7 MHz

## AM/FM SUPERHETERODYNE RADIO RECEIVER (Cont'd)

#### Circuit Description (Cont'd)

With switch S, in the FM or FM-AFC position, the FM tuner selects rf signals in the FM broadcast band (88 to 108 MHz) from the desired FM radio station, amplifies these signals, and converts them to the 10.7-MHz FM intermediate frequency. The rf-amplifier and converter stages of the tuner each use one section of a 12DT8 high-mu twin triode. Ganged tuning of the rf-amplifier and converter tuning capacitors. C3 and C12. assures that the converter local-oscillator frequency tracks the input tuning at 10.7 MHz above the center frequency of the FM channel selected. Trimmer adjustments are provided by variable capacitors C, and Cia.

The 19HR6 if amplifier is used in both FM and AM modes of operation. Depending upon the setting of selector switch S₁, this stage amplifies the frequency-modulated 10.7-MHz intermediate-frequency output from the FM converter or the amplitude-modulated 455-kHz intermediate-frequency signal from the AM converter. Additional amplification of FM if signals is provided by the 12AU6 pentode stage, which is used as a combination second FM if amplifier and noise limiter. A portion of the 12AU6 stage is also used as a second detector circuit to extract the audio-signal components from the 455-kHz AM if signals. For this demodulation function, the cathode and control grid of the 12AU6 are used as the detector diode. The 10.7-MHz FM if signals are demodulated and amplitude distortion is removed by a ratio detector that uses the diode sections of a 14GT8 twin diode-highmu triode. Good selectivity in the if amplifier and detector at 10.7 MHz is provided by the double-tuned transformers T₃, T₆, and T₈, and at 455 kHz by the double-tuned transformers T₅ and T₇.

Depending upon the mode of operation, a section of S₁ selects the audio output from the AM detector or from the FM ratio detector. The selected audio output is amplified by an audio voltage amplifier which uses the high-mu triode section of a 14GT8 and a 50C5 audio output stage. The output stage provides the power necessary to produce the required speaker output. Transformer T₀ matches the 2500-ohm plate impedance of the 50C5 to the speaker voice coil. Manual adjustment of the receiver output is provided by the VOL. CONT. potentiometer R₂₀ in the control-grid circuit of the audio voltage amplifier.

A negative de voltage proportional to the input signal level is developed across R18 and C41 during either AM or FM operation of the receiver. This voltage is applied as bias to the control grid (pin 1) of the 19HR6 if amplifier and the signal grid (pin 7) of the 12BE6 AM converter to provide automatic gain control of the receiver in each mode of operation. With  $S_1$  in the FM-AFC position, the 1N3182 AFC diode rectifies the voltage across the tertiary winding of the ratio-detector transformer Ts. The resultant frequency-sensitive voltage, applied to the plate resonant circuits of the FM rf-amplifier and converter stages, provides automatic frequency control in the FM tuner.

#### AM/FM SUPERHETERODYNE RADIO RECEIVER (Cont'd)

L2=Antenna, air-loop type

#### Parts List (Cont'd)

C==4700 pF, ceramic, 500 V C₂₄=0.15 μF, paper, 200 V C25. C27 = Ganged tuning capacitors; tune T4 to 540-1650 kHz C26, C28=Trimmer capaci-C₃₀=Part of Ts C₃₁, C₆₀=1000 pF, ceramic, 500 V C₃₂=Part of Ts C₃₄=0.1 μF, ceramic, 500 V C₃₁=0.047 μF, paper, 400 V C₃₉=80 μF, electrolytic, 150 V 100 V C₄₀, C₄₂=2700 pF, ceramic, 500 V C₄₁, C₄₃=100 pF, ceramic, 500 V, NPO C₄₁, C₄₅=330 pF, mica, 500 V C₁₆=2 μF, electrolytic, 50 V C₁₆=2.0,1 μF, paper, 200 V C₂₆=5600 pF, ceramic, 500 V C₂₇=0.1 μF, paper, 200 V C₂₇=0.022 μF, paper, 200 V C₃₃=50 μF, electrolytic, 150 V MF, electrolytic,

with back cover PC₁, PC₂=Printed circuit; includes 0.5 megohm. 0.25-watt resister and 470picofarad, 500-volt capacitor; RCA Stock No. 104328 R1=Part of PC1 R2=Part of PC2 R₃=2200 ohms, 0.5 watt R₄=1200 ohms, 0.5 watt  $R_5$ ,  $R_{21} = 33000$  ohms, 0.5 watt R₆, R₁₁=22000 ohms, 0.5 watt  $R_7$ ,  $R_{28}$ ,  $R_{31}=0.47$  megohm. 0.5 watt  $R_8=3900$  ohms, 0.5 watt  $R_9$ ,  $R_{22}=47000$  ohms, 0.5 watt R₁₀=220 ohms, 0.5 watt R₁₂, R₁₇=1 megohm, 0.5 watt R₁₃=0.22 megohm, 0.5 watt R14=100 ohms, wire-wound, 4 watts R₁₅, R₂₀=68 ohms, 0.5 watt R₁₆=4700 ohms, 0.5 watt R₁₈=0.33 megohm, 0.5 watt R₁₉, R₂₄=1000 ohms, 0.5 watt  $R_{23}$ ,  $R_{25} = 6800$  ohms, 0.5 watt R20 = 220 ohms, 0.5 watt

 $R_{27}=3.3$  megohms, 0.5 watt R20 = Volume control, potentiometer, 1 megohm, part of assembly with S2 R₂₀=4.7 megohms, 0.5 watt R₂₂=150 ohms, 0.5 watt R:3=1500 ohms, 0.5 watt R:4=820 ohms, 0.5 watt R₃₅=3900 ohms, 0.5 watt R₃₆=560 ohms, 0.5 watt S₁=AM-FM-AFC selector; 3-section slide switch  $S_2 = Interlock$ Sa=ON-OFF switch, part of assembly with Ra T₁=FM antenna transformer T2=FM oscillator transformer Ts, Te=FM if transformer, T₄=AM oscillator coil: with specified values of tuning and trimmer capacitance. tunes to 540 to 1600 kHz
T5, T7=AM if transformer,
455 kHz Ts=Ratio-detector transformer, 10.7 MHz T₀=Audio output transformer, matches impedance of speaker voice coil to 2500-ohm tube load

#### 29-3

#### **FM TUNER**

#### Circuit Description


L1, L3=1 µH, rf coil

This three-stage FM tuner features a pair of 6CW4 nuvistor triodes operated in a low-noise, high-gain cascode rf-amplifier stage. The mixer and local-oscillator sections of the tuner use the pentode and triode sections, respectively, of a 6KE8 triodepentode. The dc operating power for the tuner is obtained from a 180-volt, 20-milliampere supply. Power for the tube heaters is obtained from a 6.3volt. 660-milliampere ac source.

The tuner uses a 300-ohm balanced antenna. Antenna transformer T₁ matches the 300-ohm antenna impedance to the input circuit of the cascode rf amplifier. Antenna tuning capacitor C, is adjusted to select the desired FM channel. The frequencymodulated rf signals are amplified by the cascode rf stage and coupled to

the control grid of the mixer stage. The local oscillator generates a signal, at a frequency 10.7 MHz above the center frequency of the selected FM channel, which is also applied to the control grid of the mixer stage. The rf and local-oscillator signals are mixed to produce the desired 10.7-MHz FM intermediate frequency. Ganged tuning of the antenna, mixer, and local-oscillator tuning capacitors,  $C_4$ ,  $C_{13}$ , and  $C_{16}$ , assures that the localoscillator frequency tracks the input tuning at 10.7 MHz above the selected FM channel. Capacitors Co, C15, and C₁₀ are trimmer adjustments for the tuner. The double-tuned transformer T₂ selects the 10.7-MHz FM if signals at the plate of the mixer stages and couples them to the if-amplifier/ limiter section of the FM receiver.

#### FM TUNER (Cont'd)



* A metal shield should be provided between grid and plate terminals on the 6CW4 socket.

#### Parts List

C1, C8, C35, C35=0.01  $\mu$ F, ceramic disc, 400 V

C2, Cm=2000 pF, feed-through, 400 V

C3, C11, C21, C34, C36, C37, C38=1000 pF feedthrough, C38=:

C4, C13, C16 = Ganged tuning capacitor; 6.6-23 pF, 400 V; Miller No. 1461-BS or

equiv. C5, C9, C28=1000 pF, ceramic, 400 V

Ce, C15, C19=Trimmer capacitors, 1-7.5 pF, ceramic, 400 V

C₇, C₁₈, C₃₃=10 pF, ceramic,

C10=2000 pF, ceramic disc, 400 V

C₁₂, C₃₀=2000 pF, ceramic, 400 V

C14, C32=6.8 pF, ceramic,

C₁₇=0.22  $\mu$ F, ceramic, 400 V C₂₀=18 pF, ceramic, 400 V C₂₂=Capacitor inserted in place of tuning capacitor in secondary winding of T2; value with cable capacitance tunes output circuit

of tuner to 10.7 MHz Can, Can=2 pF feedthrough,

400 V C₂₅=22 pF, ceramic, 400 V C₂₀=2.2 pF, ceramic, 400 V C₂₇=47 pF, ceramic, 400 V C29 = Part of T2

L1=RF coil, 5 turns of No. 22 enamel wire close-

wound on ¼-inch-diameter coil form

L2=RF coil, 12 turns of No. 22 enamel wire close-wound on ¼-inch-diameter slug-tuned coil form; tuning slug = %-inch-long Moldite No. 5101 ferrite or equiv.

Lz=RF choke, 4 μH, J. W. Miller No. 70F396A1 or

equiv. L=RF coil, 3 turns of No.

16 enamel wire wound double-spaced on 14-inchdiameter slug-tuned coil form ; tuning slug = 3/8inch-long Moldite No. 5101 ferrite or equiv.
L=RF coil, 1-½ turns of
No. 16 enamel wire close-

## FM TUNER (Cont'd)

#### Parts List (Cont'd)

wound on ¼-inch-diameter slug-tuned coil form: tuning slug=%-inch-long Moldite No. 5101 ferrite or equiv.

Le=RF choke, 2µH, Ohmite No. Z144 or equiv La=RF coil; 0.4 µH; 20 turns of No. 26 enamel

wire close-wound on a 0.47 megohm, 0.5-watt Allen-Bradley resistor or resistor of equivalent physical size Le, Le=RF chokes; 1μH; 25 turns of No. 24 enamel wire

close-wound on a 0.47megohm, 1-watt Allen-

Bradley resistor or resistor of equivalent physical size R1, R13=220 ohms, 0.5 watt  $R_2=5$  ohms, 0.5 watt  $R_3$   $R_6=0.47$  megohm, 0.5 watt

R4, Re, Rs=47000 ohms, 0.5 watt

 $R_5=0.1$  megohm, 0.5 watt R7=3900 ohms, 0.5 watt R₁₀=22000 ohms, 0.5 watt R₁₁=4700 ohms, 0.5 watt R₁₂=15000 ohms, 0.5 watt S1=AM/FM range switch: open position is used for local stations, closed posiT₁=Antenna transformer; primary: 2 turns of No. 32 wire with type B nylon insulation, Alpha No. 1860 or equivalent, center-tapped; secondary: 3 turns of No. 16 enamel wire; wound double-spaced on W-inch-long coil form; tun-ing slug = %-inch-long Moldite No. 5101 ferrite or equiv.

T2=FM if transformer, 10.7 MHz: J. W. Miller 1451 or equiv.; capacitor in secondary should be replaced by

tion for distant stations Note: See general considerations for construction of high-frequency and broadband circuits on page 675.

#### 29-4 THREE-STAGE IF AMPLIFIER/LIMITER AND DETECTOR

For Monaural or Stereo Tuner


#### Circuit Description

This three-stage if amplifier/ limiter and detector circuit. when used with a front-end circuit such as that shown in circuit 25-3, makes possible an over-all tuner gain of 35 dB. The over-all bandwidth of the ifamplifier stages, between the 6-dBdown points, is 300 kHz, and the peak separation of the detector is 440 kHz. The circuit provides a signal-to-noise ratio of 20 dB for an input of 2.8 microvolts or 30 dB for an input of 4.1 microvolts. The 6HR6 and 6HS6 pentodes used in the if-amplifier stages have very high transconductance and a grid-No.1-to-plate capacitance substantially less than 0.01 picofarad and are, therefore, especially suited for use in FM if amplifiers and television sound if amplifiers. These pentodes operate from a 180-volt, 25-milliampere dc supply. Heater power for the pentodes and for the 6AL5 twin diode used in the ratio detector is obtained from a 6.3volt ac source.

The frequency-modulated, 10.7-MHz intermediate-frequency signal from the mixer stage in the FM tuner is applied to the control grid of the first if-amplifier stage. This signal is amplified by the three transformer-

coupled amplifier stages and applied by transformer T_n to the ratio detector. The doubled-tuned coupling transformers  $T_1$ ,  $T_2$ , and  $T_3$  provide the selectivity at 10.7 MHz and the bandpass characteristics required for optimum transfer of the frequencymodulated signal. Circuit stability is improved by the use of unbypassed cathode resistors in each amplifier stage. The first two if stages are basically amplifiers, although they provide some saturation limiting of large-level signals. The 3300-ohm screen-grid dropping resistors (R2 and R₄) reduce the screen-grid voltages in these stages to obtain the desired limiting characteristics. The 6HR6 pentode used in the first if amplifier is a remote-cutoff tube and, if desired, this stage may be operated with agc bias. The 6HS6 pentodes used in the second and third if stages are sharp-cutoff tubes. In addition, the screen-grid voltage divider network  $(R_7 \text{ and } R_8)$  for the third stage substantially reduces the screen-grid voltage so that the stage will provide both cutoff and saturation limiting of large-level signals. The limiting in the if stages helps remove any amplitude modulation from the frequency-mod-

# THREE-STAGE IF AMPLIFIER/LIMITER AND DETECTOR (Cont'd)



#### Parts List

C1, C4=Part of T1
C2, C4=2200 pF, ceramic disc, 400 V
C3=50 \( \mu F\), electrolytic,
450 V
C3, C4=Part of T3
C3=47 pF, ceramic disc,
400 V
C40, C13, C13, C20, C21=0.01
\( \mu F\), ceramic disc,
400 V
C10=1500 pF ceramic disc,
400 V
C11=Part of T3

C₁₂, C₁₃, C₁₅=330 pF, ceramic disc, 400 V C₁₄=100 pF, ceramic disc, 400 V C₁₆=2  $\mu$ F, electrolytic, 400 V

400 V C₁₇=1000 pF, ceramic disc, 400 V

L₁, L₂, L₃=1  $\mu$ H R₁, R₃=68 ohms, 0.5 watt R₂, R₄, R₁₃=3300 ohms, 0.5 watt R₅=0.1 megohm, 0.5 watt  $R_6$ ,  $R_{10}$ =100 ohms, 0.5 watt  $R_7$ =15000 ohms, 0.5 watt  $R_8$ =22000 ohms, 3 watts  $R_1$ =2200 ohms, 3 watts  $R_{11}$ =1200 ohms, 0.5 watt  $R_{12}$ =390 ohms, 0.5 watt  $R_{14}$ ,  $R_{15}$ =\$800 ohms,

R12_350 ohms, 0.5 watt
R14_R15=6800 ohms,
0.5 watt
R15=68000 ohms, 0.5 watt
T1, T2=IF transformers,
10.7 MHz

T₃=Ratio-detector transformer, 10.7 MHz

Note: Tube shields may be required if regeneration is encountered. See general considerations for construction of high-frequency and broad-band circuits on page 675.

# THREE-STAGE IF AMPLIFIER/LIMITER AND DETECTOR (Cont'd)

Circuit Description (Cont'd)

ulated signals.

The 6AL5 ratio-detector circuit provides additional noise limiting of the FM signal and demodulates this signal to recover the audio information. The detector circuit provides the

input to the audio amplifiers of a monaural receiver or to the multiplex detector in a stereo system. The RC network ( $R_{10}$  and  $C_{17}$ ) in the monaural output lead provides the desired deemphasis of high audio frequencies.

## 29-5 FM STEREO MULTIPLEX ADAPTER

### **Circuit Description**

This FM stereo multiplex adapter demodulates composite multiplex signals from an FM tuner and separates these signals into left- and right-channel inputs for stereo audio-output stages. The dc operating power for the 12AX7A and 6CL8A twin triodes used in the adapter circuit is obtained from a 180-volt, 15-milliampere supply. Power for the dual heaters of the 12AX7A and the single heater of the 6CL8A is obtained from a 6.3-volt source.


The composite signal applied to the multiplex adapter from the ratio detector (or discriminator) in an FM receiver includes a 19-kHz pilot-frequency (multiplex-reference) component and sum (L + R) and difference (L - R) components of left- and right-channel audio signals. The L + R signal is the demodulated in-phase combination of the left- and rightchannel audio information used to modulate the main carrier frequency of the receiver. The L - R signal is the out-of-phase combination of the left- and right-channel information and is used to amplitude-modulate a 38-kHz subcarrier. This subcarrier is suppressed in the FM tuner so that only the L - R sideband components of the amplitude-modulated signal remain.

The composite input signal is amplified by the 12AX7A triode section in the input stage of the adapter. The high input impedance of this stage prevents excessive loading of the ratio detector. The 67-kHz trap (L₁ and C₂) in the cathode circuit of this

stage eliminates any SCA (storecast allocation) signal components that may be included in the composite signal. The composite signal is coupled from the plate of the input stage to the control grid of the 6CL8A triode section used in a signal-separation driver. This stage operates as a cathode follower for the L + R audio components and the L - R subcarrier sideband components. The L + R audio components are developed MATRIX BALANCE across the ADJ, potentiometer R₁₈ and coupled from the wiper arm of this potentiometer to the output resistor matrix network R₁₉ through R₂₂. A 3300picofarad capacitor Cig in the coupling circuit filters out any 19-kHz pilot-frequency components or 38kHz subcarrier sideband components that may be developed across potentiometer R₁₈. The L - R sideband components are coupled from the cathode of the signal-separation driver to the center tap of the secondary winding of the transformer T2 in the peak detector. The 38-kHz band-pass coil L2 and the 67-kHz series-resonant trap Co and Lo assure maximum signal transfer of the L - R sideband components with minimum interference from storecast signals.

The 19-kHz double-tuned transformer  $T_1$  in the plate circuit of the signal-separation driver presents a highly selective load to the 19-kHz pilot-frequency component included in the composite multiplex signal and couples this 19-kHz component to the pilot-frequency doubler. The doubler

# 29-5 FM STEREO MULTIPLEX ADAPTER (Cont'd)



# 29-5 FM STEREO MULTIPLEX ADAPTER (Cont'd)

#### Parts List

C1, C11, C12, C13, C14, C17, C20=0.01  $\mu$ F, ceramic, 500 V C2, C4=2200 pF, film, 500 V, N150 C4=0.04  $\mu$ F, paper, 200 V C5=40  $\mu$ F, electrolytic, 450 V C4=0.22  $\mu$ F, paper, 400 V C7, C4=1500 pF, film, 500 V, N150 C10=1500 pF, film, 500 V, N150 C10=1400 pF, film, 500 V C15=470 pF, ceramic, 500 V C15=470 pF, ceramic, 500 V C15=470 pF, ceramic, 500 V C14=3300 pF, ceramic, 500 V C14=370 pF, ceramic, 500 V C14=70 pF

RCA stock No. 111047 or equiv. L2=RF coil, 38-kHz bandpass, RCA stock No. 111048 or equiv. R.=330 ohms, 1 watt R2=0.56 megohm, 0.5 watt R3=1500 ohms, 0.5 watt R5=68000 ohms, 0.5 watt R5=68000 ohms, 0.5 watt R7=1 megohm, 0.5 watt R8, R10=10000 ohms, 0.5 watt R8, R10=10000 ohms, 0.5 watt R8, R10=10000 ohms, 0.5 watt R9, R1, R15=47000 ohms,

0.5 watt

R12=1.2 megohms, 0.5 watt
R13=0.15 megohm, 0.5 watt
R13, 0.15 megohm, 0.5 watt
R16, R17, R23=22000 ohms,
0.5 watt
R18=Potentiometer, balance
adjustment, 10000 ohms,
RCA stock No. 111044
or equiv.
R10, R50, R21, R22=0.1
megohm, 0.5 watt
T1=19-kHz transformer,

 $R_{11}=4700 \text{ ohms, } 0.5 \text{ watt}$ 

RCA stock No. 111045 or equiv. T₂=38-kHz transformer, RCA stock No. 111046 or equiv.

Note: See general considerations for construction of high-frequency and broadband circuits on page 675.

#### Circuit Description (Cont'd)

circuit, which consists of two 1N295 diodes (CR₁ and CR₂) in a full-wave rectifier configuration, doubles the pilot frequency to regenerate the 38-kHz subcarrier required for demodulation of the L — R sideband components.

The 38-kHz output of the doubler is amplified by the 6CL8A triode section used in the shaping amplifier and reshaped to a sine wave by the tuned primary of the peak detector transformer T₂. In the secondary of T₂, the 38-kHz subcarrier is recombined with the L — R sideband components from the cathode of the signal-separation driver. This combined signal is then demodulated by the 1N295 detector diodes CR₂ and CR₄ to obtain the L — R audio signal.

The L - R audio signal is applied to the control grid of the 6CL8A section used in a phase-splitter circuit.

The cathode and plate outputs of the phase splitter are equal in amplitude and opposite in phase so that one output represents an L - R signal and the other output represents a -L+ R signal. These signals are applied to the output-resistor matrix network where they are added to the L + Raudio signal from the cathode circuit of the signal-separation driver. In the summation of the L + R and L - R audio signal, the R components are canceled, and the resultant obtained is the left-channel audio output. The summation of the L+R and L + R signals results in cancellation of the L components so that only the right-channel audio output is obtained. These outputs are then applied to the stereo receiver left- and right-channel audio-output stages, respectively

## 29-6 PREAMPLIFIER FOR AMATEUR RECEIVER


For 15-, 10-, and 6-Meter (21-, 30-, and 50-MHz) Amateur Bands and 27-MHz Citizens Band

#### Circuit Description

In this preamplifier, two 6CW4 high-mu nuvistor triodes are used in a high-gain, low-noise cascode rfamplifier stage that adds 25 to 35 dB of gain ahead of a receiver operated on the 6-, 10-, or 15-meter amateur band or on the 27-MHz citizens band. This added gain, together with the

low noise figure (approximately 5 dB) of the preamplifier, substantially increases both the sensitivity and the signal-to-noise ratio of the receiver. The preamplifier operates from a dc plate supply of 150 volts at 5 milliamperes. The tube heaters require an ac power input of 6.3 volts at 0.26

## 29-6 PREAMPLIFIER FOR AMATEUR RECEIVER (Cont'd)



ALIGNMENT DATA				
Operating Frequency	Tune T ₁ to:	Tune T ₂ to:		
21 MHz	21,25 MHz	21.22 MHz		
27 MHz	30 MHz	27 MHz		
30 MHz	32 MHz	29.5 MHz		
50 MHz	51 MHz	50 MHz		

#### Parts List

C1, C7=See Note 1
Ca, Ca, Ci, Cs, Cs, Ca,
Ce=0.001 µF, 500 V,
ceramic
R1, R2=100 ohms, 0.5 watt
R4=1000 ohms, 0.5 watt
T1=Input transformer (slugtuned); matches preamplifier to 52-ohm input line,
(for 300-ohm input line,
double number of turns in

primary); wound from #32 copper enamel wire on slugtuned form having ½-inch outer diameter: primary, 1½ turns; secondary, 18 turns for operation at 21, 27, or 30 MHz or 10 turns for operation at 50 MHz T2=O u tp ut transformer (slug-tuned); matches preamplifier to 72-ohm output lines (use of other than a

72-ohm line between preamplifier output and receiver input is not recommended); wound from #32 copper enamel wire on slugtuned form having ¼-inch outer diameter; primary, 18 turns for operation at 21, 27, or 30 MHz or 10 turns for operation at 50 MHz, secondary, 1½ turns.

Notes: 1. For operation at 21 or 27 MHz, use 6.8-pF 500-volt capacitors for C₁ and C₇; for operation at 30 MHz, use 5-pF 500-volt capacitors for C₁ and C₇; for operation at 50 MHz, use 5-pF 500-volt capacitor for C₁ and 6.8-pF 500-volt capacitor for C₂. See general considerations for construction of high-frequency and broadband circuits on page 675.

#### Circuit Description (Cont'd)

ampere. These small power requirements can usually be provided by the receiver.

Input transformer T₁ matches the high input impedance of the preamplifier to a 72-ohm or 300-ohm antenna. When a 72-ohm antenna is used, the primary of T₁ consists of a 1½-turn link wound about the hot end of the secondary coil. For a 300-ohm antenna, a 3-turn link is used. The secondary of T₁ is an 18-turn coil for operation at 10 or 15 meters or on the citizens band. At 6 meters, a 10-turn secondary coil is used. The unit is normally connected to the an-

tenna cable by means of a coaxial connector. If a balanced antenna system is used, however, terminal strips for the twin leads may be used instead of the coaxial connector. In this latter case, the input link (primary of T.) is not grounded.

Nuvistors  $V_1$  and  $V_2$  are operated in a stacked (cascode) arrangement in series with the B+ supply. The input is coupled by  $T_1$  to the control grid of  $V_1$ , which is essentially a grounded-cathode amplifier. The output of  $V_1$  is applied to the cathode of  $V_2$ , which is basically a groundedgrid amplifier. The inherent stability

# 29-6 PREAMPLIFIER FOR AMATEUR RECEIVER (Cont'd)

#### Circuit Description (Cont'd)


of this type of arrangement, together with the ample decoupling and bypassing networks included in the circuit, provides assurance that the preamplifier will not break into oscillation.

The output of V₂ is developed across the primary coil of output transformer T₂. This coil is identical

to the secondary coil of input transformer T₁. The secondary of T₂ consists of a 1½-turn link about the primary coil. This link matches the output of the preamplifier to a 75-ohm receiver input cable. (The maximum length of coaxial cable between receiver and preamplifier should not exceed 12 inches.)

#### 29-7

### CODE-PRACTICE OSCILLATOR



Note: Any two terminals of the secondary of T2 that give the desired tone may be selected. Adjustment of volume control may cause a slight change in tone.

#### **Parts List**

C₁, C₂=20 µF, electrolytic, 150 V C₅=0.001 µF, paper, 200 V C₄=0.03 µF, paper, 200 V F=½ ampere

J₁=Input jack for key R₁=1500 ohms, 1 watt R₂=Potentiometer, 0.1 megohm, 0.5 watt T1=Power transformer, 125 volts rms, 15 ma; 6.3 volts, 0.6 ampere
T2=Output transformer, universal

## **Circuit Description**

This code-practice oscillator operates from a 117-volt ac power line. When ON-OFF switch S₁ is closed, the 117-volt ac input power is stepped up to 125 volts across the upper secondary winding of power transformer T₁ and is stepped down to 6.3 volts across the lower secondary winding. The 6.3-volt winding provides the operating power for the heater of the 6BJ8 twin diode-tride used in the circuit. The diode sections of the 6BJ8 are connected to operate as a single diode in a half-wave rectifier circuit that converts the ac power across the

125-volt winding of  $T_1$  to dc operating power for the 6BJ8 triode section. This triode section is used as the amplifier tube in a simple audio-oscillator stage.

Operation of the oscillator stage is controlled by a telegraph key, which is connected into the circuit by means of jack J₁. When the key is closed, the triode section of the 6BJs supplies energy to the oscillator resonant circuit formed by capacitor C₄ and the effective inductance of the primary of output transformer T₂. This circuit then resonates to pro-

# 29-7 CODE-PRACTICE OSCILLATOR (Cont'd)

#### Circuit Description (Cont'd)

duce an audio signal that is coupled by transformer T₂ to the speaker to produce an audible indication of the keying. Positive feedback to sustain oscillation is developed by the autotransformer action of the tapped primary of transformer T₂.


Output transformer  $T_2$  is a universal type which contains multiple taps on the secondary winding. These taps enable the transformer to match the oscillator output impedance to

different values of speaker voice-coil impedance. The speaker impedance and transformer terminals used, however, affect the effective inductance in the primary of  $T_1$  and, thus, the tone of the audio output. Volume-control potentiometer  $R_2$  adjusts the level of the audio output. Adjustment of potentiometer  $R_2$  varies the loading on the oscillator resonant circuit and may also cause a slight change in the tone of the audio output.

#### 29-8

#### INTERCOMMUNICATION SET

With Master Unit and Two or More Remote Units



Notes: 1. The leads from the LISTEN-TALK switch S₁ to T₁ and T₂ should be kept as far apart as possible to prevent undesirable regenerative effects.
 Connections to the remote speaker units should be made with low-resistance wire, preferably with shielded "intercom" cahle.

#### **Parts List**

0.5 watt

C₁, C₂=0.0022 μF, paper, 200 V. C₄=0.005 μF, paper, 200 V. C₄, C₅=60 μF, electrolytic, 150 V. F₁=Fuse, 1 ampere R₁=Volume control, potentiometer, 0.5 megohm, audio taper, attached to switch S₃ R₂=6.8 megohms, 0.5 watt R₃, R₄=0.47 megohm,

Rs=10000 ohms, 0.5 watt

double-pole, double-throw
S2=Station Selector, rotary
switch
S3=On-off switch, single-pole,
single-throw; attached to
volume-control potentiometer

Re, R7=68 ohms, 0.5 watt Rs=2200 ohms, 1 watt

S1=Talk-listen switch,

SP1, SP2, SP3=Speaker; permanent-magnet; voice-coil impedance, 3 to 4 ohms T₁=Input transformer, 4-ohm primary, 25000-ohm secondary, Knight 54A1492 or equiv.

T₂=Output transformer, 3000ohm primary, 4-ohm secondary, Knight 54A2371 or

equiv.
T₈=Power transformer, 125
volts rms, 50 mA., 6.3 volts
rms. 2 amperes, Knight
54A1411 or equiv.

## 29-8 INTERCOMMUNICATION SET (Cont'd)

#### **Circuit Description**

This simple "intercom" set can be used to achieve reliable voice communications, at normal speaking levels, between any two points in a normal-size house. The system consists of a master unit, centrally located at the hub of household activity. interconnected by low-loss cabling to remote units located at points (e.g., garage, attic, and cellar) beyond the range of normal voice levels. An audio amplifier, which includes a 6AV6 voltage-amplifier stage and a 6EH5 power-output stage, provides the amplification necessary to overcome the attenuation of voice levels by system cabling. A 6X4 half-wave rectifier circuit converts the 117-volt ac input power to the dc power required for operation of the amplifier stages. A 6.3-volt secondary winding on the power transformer (T3) in the rectifier circuit provides heater power for the amplifier and rectifier tubes.

The speaker at each intercom station is used for both talk and listen functions. The talk-listen switch S₁ at the master location establishes the talk or listen mode for all stations. The voice communications are initiated from the master unit. Switch S₁ is depressed to the TALK position, and the initiator talks into the master-unit speaker. The audio (voice-signal) voltage that is then developed across the speaker voice coil is coupled by input transformer T₁ to the control grid of the 6AV6 audio amplifier. Selector switch S₂ connects

the desired remote unit into the intercom system. With S₁ depressed to the TALK position, the remote unit speaker is automatically connected to the audio amplifier output for listen-mode operation. When S₁ is in the LISTEN position, the master-unit speaker is connected in the listen mode, and the remote-unit speaker is connected to the amplifier input. A reply from the remote unit is then coupled from the remote speaker by transformer T₁ to the control grid of the 6AV6 audio amplifier.

Transformer T₁ matches the voice-coil impedance of the 4-ohm permanent-magnet speaker (of either master or remote unit) to the 25000ohm input impedance of the 6AV6 amplifier stage. This stage and the 6EH5 audio output stage amplify the audio (voice) signals received from one location (the master unit or one of the remote units) to develop the audio power required to produce an audible output from the speaker at another location. Output transformer  $T_2$  matches the 3000-ohm plate-circuit impedance of the output stage to the 4-ohm voice-coil impedance of the speaker (master-unit or remote-unit) to which the communication is directed, as determined by the settings of switches S₁ and S₂. The VOL. CONT. potentiometer R1 in the input circuit of the 6AV6 audio amplifier stage provides the volume-control adjustment for the system.

#### 29-9

# HIGH-FIDELITY AUDIO AMPLIFIER


Class AB₁; Power Output, 15 Watts

## **Circuit Description**

This high-fidelity audio power amplifier can deliver 15 watts of rms output power with less than 0.4 per cent total harmonic distortion and less than 1.5 per cent intermodulation distortion. The frequency response of the amplifier is flat within ±0.5 dB from 20 Hz to 60 kHz, and the sensi-

tivity is such that the rated output of 15 watts is obtained for an input of 1.2 volts rms. The total hum and noise, with the input shorted, is 84 dB below 15 watts. The circuit operates from a 117-volt ac power line. The transformer-coupled ac input power is converted to dc operating

#### HIGH-FIDELITY AUDIO AMPLIFIER (Cont'd) 29-9



#### Parts List

C1=40 µF, electrolytic, 450 V. C₂, C₄, C₅=0.25 μF, paper,

Ca=3.3 pF, ceramic or mica,

Ce=150 pF, ceramic or mica, _ 400 V.

C₇, C₈=0.05 μF, paper, 400 V.

C₀=0.02 μF, paper 600 V. C₁₀=100 μF, electrolytic,

C₁₁=80 μF, electrolytic, 450 V.

C₁₂=40 µF, electrolytic, 450 V.

F₁=Fuse, 3 amperes

L1=Choke, 3 H, 160 mA, dc resistance 75 ohms or less,

Triad C-13X or equiv.

R₃==0.82 megohm, 0.5 watt R₄==820 ohms, 0.5 watt R₅==0.22 megohm, 0.5 watt Re, R7=15000 ohm ±5 per cent, 2 watts Rs=3900 ohms, 2 watts Ro, R10=0.1 megohm, 0.5 watt R₁₁, R₁₂=1000 ohms, 0.5 watt R₁₂, R₁₄=100 ohms, 0.5 watt R₁₅=8200 ohms, 0.5 watt

R1=Volume control, potenti-

ometer, 1 megohm R₂=10000 ohms, 0.5 watt

R₁₆=15000 ohms, 1 watt R₁₇=68000 ohms, 0.5 watt R₁₈=4700 ohms, 2 watts R₁₉=0.27 megohm, 1 watt

R20=47000 ohms, 0.5 watt

R21=Hum balance adjustment, potentiometer, 100 ohms, 0.5 watt

SR₁=Selenium rectifier, 20 mA, 135 volts rms

T1=Output transformer (having 8-ohm tap for feedback connection) for matching impedance of voice coil to 6600-ohm plate-to-plate tube load; 50 watts; fre-quency response, 10 to 50000

Hz; Stancor A-8056 or equiv. Power transformer

360-0-360 volts rms, 120 mA; 6.3 V., 3.5 A; 5 V., 3 A; Stancor 8410 or equiv. (see Note 1)

Notes: 1. For stereo operation from a single power supply, the power transformer T₂ must be replaced by one that has a higher current rating. A Stancor Type 6315 or equivalent (370-0-370 volt rms, 275 mA) is recommended.
2. If the amplifier oscillates or "motorboats," reverse ground and feedback connections in secondary of output transformer T₁.

## HIGH-FIDELITY AUDIO AMPLIFIER (Cont'd)

#### Circuit Description (Cont'd)

power for the amplifier stages by the 5BC3 full-wave rectifier. Heater power for the amplifier tubes and the rectifier are obtained from the 6.3-volt and 5-volt secondary windings, respectively, on the rectifier power transformer (T₂).

high-gain pentode voltage amplifier is used as the input stage for the audio power amplifier. The output of this stage is direct-coupled to the control grid of a triode splitload type of phase inverter. The use of direct coupling between these stages minimizes phase shift and, consequently, increases the amount of inverse feedback that may be used without danger of low-frequency instability. A low-noise 7199 tube, which contains a high-gain pentode section and a medium-mu triode section in one envelope, fulfills the active-component requirement for both the pentode input stage and the triode phase inverter. Potentiometer R, in the input circuit of the 7199 pentode section is the volume control for the amplifier.

The plate and cathode outputs of the phase inverter, which are equal in amplitude and opposite in phase, are used to drive a pair of pentode-connected 6973 beam-power tubes used in a class AB₁ push-pull output stage. The 6973 output tubes are biased for class AB₁ operation by the fixed negative voltage applied to the control-grid circuit from the rectifier circuit. Fixed bias is used because a class AB amplifier provides highest efficiency

and least distortion for this bias method.

Transformer T₁ couples the audioamplifier output to the speaker. The taps on the secondary of this transformer match the plate-to-plate impedance of the output stage to the voice-coil impedance of an 8- or 16ohm speaker. Negative feedback of 19.5 dB is coupled from the secondary of the output transformer (speaker voice coil) to the cathode of the input stage to reduce distortion and to improve circuit stability.

Fixed-bias operation of the output stage requires that the power supply provide very good voltage regulation because the plate current of the 6973 tubes varies considerably with the signal level. The conventional choke-input type of power supply used provides the required regulation. The fixed bias for the output stage is obtained from one-half the high-voltage secondary winding of power transformer T2 through a capacitance-resistance voltage divider the 20-milliampere, 135-volt and selenium rectifier. Potentiometer Rate connected across the 6.3-volt secondary winding of transformer T2 provides a hum balance adjustment for the audio power amplifier. The wiper arm of this potentiometer is connected to the junction of a resistive voltage divider across the output of the power supply. The resulting positive bias voltage applied to the tube heaters minimizes heater-to-cathode leakage and substantially reduces hum.

## 29-10 HIGH-FIDELITY AUDIO AMPLIFIER

Class AB1; Power Output, 30 Watts


#### **Circuit Description**

This audio power amplifier can deliver 30 watts of rms output power with less than 0.7 per cent total harmonic distortion and less than 1.5 per cent intermodulation distortion. The frequency response of the amplifier is flat within ±0.5 dB from 15

Hz to 40 kHz. The total hum and noise, with the input shorted, is 85 dB below 30 watts. The rated output of 30 watts is obtained for an input of 1 volt rms.

The 30-watt amplifier is essentially identical to the 15-watt ampli-

#### 29-10 HIGH-FIDELITY AUDIO AMPLIFIER (Cont'd)



#### Parts List

C₂=22 pF, ceramic or mica, 600 V C1=25 µF, electrolytic, 50 V

C₅=80 μF, electrolytic, 450 V C₄, C₅=0.25 μF, paper, 600 V  $C_{0}$ ,  $C_{0}$ =0.25 μF, paper, 600 V  $C_{0}$ =0.01 μF, paper, 600 V Cr,  $C_{0}$ =0.05 μF, paper, 600 V  $C_{0}$ ,  $C_{11}$ =40 μF, electrolytic, 500 V

C10=100 μF, electrolytic, 50 V C₁₂=20 μF, electrolytic, 450 V

F₁=Fuse, 3 amperes, 150 V R1=Volume control, potentiometer, 1 megohm R2=10000 ohms, 0.5 watt Ra=0.22 megohm, 0.5 watt

 $R_4$ =820 ohms, 0.5 watt  $R_5$ =10 ohms, 0.5 watt Ro=0.18 megohm, 0.5 watt  $R_7$ ,  $R_8=15000$  ohms  $\pm 5$  per cent. 2 watts Ro=1000 ohms, 0.5 watt

R₁₀=22000 ohms, 0.5 watt R₁₁=2000 ohms, 2 watts R₁₂, R₁₃=0.1 megohm, 0.5

watt R11, R15=1000 ohms, 0.5 watt R₁₆, R₁₇=56 ohms, 0.5 watt R₁₈=270 ohms, 0.5 watt R₁₀=Hum balance adjustment, potentiometer, 100 ohms, 0.5 watt R20=220 ohms, 10 watts

Ra=50 ohms, 10 watts

R==10000 ohms, 2 watts Ti=Output transformer (having 16-ohm tap for feedback connection) for matching impedance of voice coil to 6600-ohm plate-to-plate tube load; 50 watts; frequency response, 10 to 50000 Hz; Stancor A-8056 or equiv.

T2=Power transformer, 375-0-375 volts rms, 160 mA; 6.3 V., 5 A; 5 V., 3 A; Thordarson type T22R33 or equivalent (see Note 1).

Notes: 1. For stereo operation from a single power supply, the power transformer T₂ must be replaced by one that has a higher current rating. A Stancor Type 6315 or equivalent (370-0-370 volts rms, 275 mA) is recommended.
2. If amplifier oscillates or "motorboats," reverse ground and feedback connections in secondary of output transformer T₁.

#### 29-10 HIGH-FIDELITY AUDIO AMPLIFIER (Cont'd)


## Circuit Description (Cont'd)

fier (circuit 29-9) except that it uses 7868 beam power tubes in the outbut stage to develop the higher audio power output and uses a resistive network in the negative leg of the power supply, rather than a separate

rectifier, to supply the fixed-bias voltage for the output stage. A potentiometer (R19) connected across the 6.3-volt heater winding also provides the hum balance adjustment for the 30-watt amplifier.

#### HIGH-FIDELITY AUDIO AMPLIFIER 29-11

Class AB1: Power Output, 50 Watts



### Preliminary Adjustments

The following adjustments should be made before operation:
(1) With rectifier out of socket, adjust Bias Adj. Rss for -40 volts between the wiper

with rectiner out or socket, adjust Bias Adj. Rss for -40 volts between the wiper arm and ground bus.

With speaker connected, adjust Screen-Grid Voltage Adj. Rss for 400 volts between pin 3 of 6GF7 and ground bus.

With input shorted, adjust Hum Bal. Adj. Rss for minimum hum from speaker.

With input open and Vol. Cont. set for maximum volume, adjust Bal. Cont. R17 for minimum hum from speaker.

minimum hum from speaker.

#### HIGH-FIDELITY AUDIO AMPLIFIER (Cont'd) 29-11

#### Parts List

C₁, C₂=40 μF, electrolytic, 450 V Ca, C4=0.02 μF, paper, 400 V C₅, C₆=1  $\mu$ F, paper, 400 V C₇=0.002  $\mu$ F to 4-ohm tap; 0.0015 μF to 8-ohm tap; 0.001 μF to 16-ohm tap; paper, 400 V Cs, Cp=0.05 μF, paper, 600 V C₁₀=20 μF, electrolytic, C11=100 µF, electrolytic, C₁₂=40 μF, electrolytic, 450 V Fi=Fuse, 5 amperes La=Choke, 8 H, 250 mA, dc resistance 60 ohms, or less R1=Volume control, potentiometer, 0.5 megohm

ometer, 0.5 megonm
Rs=4700 ohms, 0.5 watt
Rs=0.82 megohm, 0.5 watt
Rs=820 ohms, 0.5 watt
Rs=820 ohms, 0.5 watt
Rs=10 ohms, 0.5 watt
R7 Rs= 15000 ohms, 2 watts Re, R₁₀=1.5 megohms, 0.5 watt

R11=33000 ohms, 2 watts

R12, R14=1.3 megohms, 0.5 watt R₁₃=47 ohms, 0.5 watt R₁₅, R₁₉=0.15 megohm, 0.5 watt R₁₆, R₁₈=390 ohms, 0.5 watt R₁₇=AC balance control, po-

tentiometer, 500 ohms R₂₀=0.15 megohm, 1 watt R21, R24=0.33 megohm, 1 watt

R22, R23=0.12 megohm. 2 watts R25, R26=0.1 megohm, 0.5 watt

R27, R28=4700 ohms. 0.5 watt Ren=600 ohms to 4-ohm tap;

820 ohms to 8-ohm tap; or, 1200 ohms to 16-ohm tap; 0.5 watt

Ran=Hum balance adjustment, potentiometer, 100 ohms

R₃₁=0.12 megohm, 5 watts R₃₂, R₃₄, R₃₅, R₃₇=33000 ohms, 2 watts R33=Bias adjustment, poten-

tiometer 50000 ohms,

R₃₆=0.27 megohm, 0.5 watt Rss=10000 ohms, 1 watt Ras=Screen-grid voltage adjustment, potentiometer, 25000 ohms, 2 watts

R₁₀=15000 ohms, 2 watts R₁₁=12000 ohms, 2 watts R₄₂=0.22 megohm, 2 watts R₄₃=22000 ohms, 2 watts SR₁=Selenium rectifier, 20 mA, 135 volts rms

T1=Output transformer for matching impedance of voice coil to 5000-ohm plate-to-plate tube load : 50 watts; frequency response, 10 to 50000 Hz : United Transformer Corp. LS6L4 or equiv. (see Note 1) T₂=Power transformer,

2=rower transformer, 600-0-600 volts rms, 200 mA, 6.3 V., 5 A; 5 V., 3 A; Thorderon 22R36 or equiv. (see Note 2)
T3=Filament transformer,

6.3 volts, center tapped, 1 ampere : Thordarson 21F08 or equiv.

Notes: 1. In many applications, less expensive transformers, such as Stancor Type A8053 or United Transformer Corporation Type S-17, which have a narrower frequency response, may be used for T1 with satisfactory results.

2. For stereo operation from a single power supply, the following changes are required: (a) The power transformer T2 must be replaced by one that has a higher current rating; a Freed Transformer Corporation Type DC6A or equivalent (600-0-600 volts rms, 300 mA) is recommended. (b) The 50000-ohm Bias Adj. potentiometer Rs3 should be replaced by two 100000-ohm potentiometers (one for each channel) connected in parallel. (c) A second 5R4-GYB rectifier tube should be connected in parallel with the one used for monaural operation. (Connect the 5R4-GYB tubes so that the two sections of each tube are in parallel with the corresponding sections of the other tube; do not use separate tubes for each corresponding sections of the other tube; do not use separate tubes for each section of the rectifier circuit.)


3. If the amplifier oscillates or "motorboats," reverse ground and feedback connections in secondary of output transformer T₁.


#### Circuit Description

This four-stage audio power amplifier can deliver 50 watts of rms power output with less than 0.1 per cent total harmonic distortion and less than 1 per cent intermodulation distortion. The frequency response of the amplifier is flat within  $\pm 0.5$ dB from 10 Hz to 50 kHz. Sensitivity is 0.4 volt rms input for 50 watts output. The total hum and noise is 70 dB below 50 watts.

The 50-watt amplifier, like the 15-watt and 30-watt high-fidelity amplifiers (circuits 29-9 and 29-10), uses a 7199 low-noise triode-pentode as an input amplifier and phasesplitter, but has a push-pull driver stage, which uses 6CB6 sharp-cutoff pentodes. The superior performance of this amplifier can also be attributed, in part, to the use of a 450-volt plate supply and a 400-volt electronically regulated grid-No. 2 supply

for the 7027A beam power tubes in the output stage and to the use of inverse-feedback loops from the plates to the grids of the output tubes, from the plates of the output tubes to the cathodes of the driver tubes, and from the voice-coil winding of the output transformer to the cathode of the input amplifier. Additional features are the operation of all heaters at a positive voltage with respect to ground and use of a balancing adjustment (R₂₀) in the heater-supply circuit to minimize hum, a grid-No. 2 voltage adjustment (R₂₀), a grid-No. 1 bias adjustment (R₃₃) for the 7027A output tubes, and an ac-balance adjustment (R13) which may be used to balance the outputs of the pushpull stages. Operation of the 50-watt amplifier is essentially the same as that of the 15- and 30-watt amplifiers.





Parts List
C1, C3=0.22 μF, paper,
400 V
C2=0.1 μF, paper, 400 V
C4, Cs=50 μF, electrolytic,
25 V

25 V C₆=50 μF, electrolytic, 150 V C₇, C₈=50 μF, electrolytic, 150 V F₁=Fuse, 3 amperes  $R_1$ ,  $R_2$  = Volume control potentiometer, 1.5 megohms, ganged, audio taper  $R_2$  = 0.22 megohm, 0.5 watt  $R_1$ ,  $R_3$  = 47000 ohms, 0.5 watt

Ro = 12 ohms, 1 watt
R7 = Balance control, potentiometer, 2 megohms, audio taper

 $R_8$ ,  $R_9 = 60$  ohms, 1 watt  $R_{10} = 280$  ohms, 2 watts  $R_{11} = 220$  ohms, 2 watts  $S_1 = ON$ -OFF switch, singlepole, single-throw

T1, T2 = Output transformer for matching impedance of voice coil to 3000-ohm tube load; Triad S-16X or equiv.

## **Circuit Description**

This ac/dc two-channel (stereo) amplifier operates from either an ac power line or dc supply of 117 volts. AC power inputs are converted to dc power by the 1N1763 silicon-diode half-wave rectifier circuit. The heaters of the 60FX5 power pentodes (one for each channel) used in the amplifier are connected in series directly across the input power line.


In stereo units that use highoutput ceramic stereo cartridges, the high power sensitivity of the 60FX5 tubes at low supply voltage elimineed for preamplifier nates the stages. The 60FX5 provides a power output of 1.3 watts to a 3000-ohm transformer primary with only 3 volts peak drive on grid No. 1. With a transformer having a good impedance match and 85-per-cent efficiency, each channel of the stereo amplifier supplies 1.1 watts of useful power output at the speaker.

No special mounting or layout

precautions are necessary for this amplifier other than the value and placement of the isolating capacitor  $C_2$  between B- and the chassis. This capacitor should be connected to the same point on the chassis at which the common cartridge lead is tied. A value of 0.1 microfarad for the isolating capacitor is suggested so that full output is obtained from the pickup.

As with all single-ended amplifier circuits, especially ac/dc units, adequate screen-grid bypassing is necessary to minimize hum. Screengrid filtering is obtained through use of a 220-ohm dropping resistor Rs and a 50-microfarad electrolytic capacitor Cs. Although, in the circuit shown, separate cathode-bias resistors are used for better dynamic balance, a single 30-ohm common cathode-bias resistor bypassed with a 50-microfarad electrolytic capacitor may also be used.

# 29-13 MICROPHONE AND PHONOGRAPH AMPLIFIER



#### **Parts List**

C₁, C₂=100 pF, disc-ceramic, 300 V

300 V C₃=0.05 μF, paper, 200 V C₄=8 μF, electrolytic, 450 V C₆=16 μF, electrolytic, 450 V C₇=0.1 μF, paper, 200 V C₇=0.1 μF, paper, 200 V C₈=0.001 μF, disc-ceramic, 300 V

C₀=0.01 μF, disc-ceramic, 300 V

C10=470 pF, disc-ceramic,

C₁₁=4700 pF, disc-ceramic, 300 V C₁₂=4 μF, electrolytic, 450

Gave V C₁₂=4  $\mu$ F, electrolytic, 450 V C₁₂=0.05  $\mu$ F, paper, 600 V C₁₄=25  $\mu$ F, electrolytic, 25 V C₁₅, C₁₆, C₁₇=20  $\mu$ F, electrolytic, 450 V

Fi=Fuse, 1 ampere Ji=Jack for high-impedance J=Jack for crystal phonopickup input
L1=Filter choke, 5 H,
200 mA, United Transformer Corp. R20 or equiv.
R1, R10=10000 ohms, 0.5 watt
R2=Volume Control, potenti-

peak

crystal microphone input;

max. input: 2 millivolts

ometer, 1 megohm
R₃=2.2 megohms, 0.5 watt
R₄, R₈, R₂₀=0.22 megohm,
0.5 watt

R₅=27000 ohms, 0.5 watt R₆=1200 ohms, 0.5 watt R₇, R₁₃=0.1 megohm,

0.5 watt

R₉, R₁₁=Tone control, potentiometer, 0.5 megohm
R₁₀=22000 ohms, 0.5 watt
R₁₂=12000 ohms, 0.5 watt

R₁=1800 ohms, 0.5 watt
R₁=0.47 megohm, 0.5 watt
R₁=0.15 megohm, 0.5 watt
R₁=0.15 megohm, 1.5 watt
R₂=180 ohms, 2 watts
R₂=50 ohms, 10 watts
R₂=8200 ohms, 2 watts
S₁=Microphone-phonograph
selector; wafer switch;

single-pole, double-throw S2=ON-OFF switch, singlepole, single-throw

T₁=Power transformer, 300-0-300 V., 90 mA.; 6.3 V., 3.5 A., center tapped; 5 V., 2 A. Thordarson 22R04 or equiv.

T2=Output transformer for matching impedance of voice coil to 4000-ohm tube load; 10 watts; United Transformer Corp. S14 or equiv.

## **Circuit Description**

This microphone and phonograph amplifier can deliver up to 8 watts of audio output power for an input of 200 millivolts rms at J₂ (phonograph input) or an input of 6.8 millivolts rms at J₁ (microphone input). The amplifier uses a 6EU7 twin-triode input amplifier, a 6AV6 driver stage,

and a 6L6GC single-ended output stage to increase the signal power from a high-impedance crystal microphone or crystal phonograph pickup to the desired level. The transformer-coupled ac input power is converted to dc operating power for these stages by a 5Y3GT full-wave recti-

# 29-13 MICROPHONE AND PHONOGRAPH AMPLIFIER (Cont'd)

#### Circuit Description (Cont'd)

fier circuit. A 5-volt winding on power transformer T₁ provides the heater power for the rectifier tube, and a 6.3-volt winding provides heater power for the other tubes in the amplifier. The center tap on the 6.3-volt winding is connected to the junction of a resistive voltage divider (R₁₀ and R₂₀) across the output of the power supply. The resulting positive bias applied to the tube heaters substantially reduces heater-to-cathode leakage and, consequently, minimizes hum.


The signals from a crystal microphone are usually much smaller than those from a crystal phonograph pickup. Microphone signals, therefore, are amplified by both sections of the 6EU7 twin-triode amplifier. The signals are coupled from J₁ to the pin 5 control grid of the 6EU7. The plate output from this triode section is then coupled through switch S₁ (microphone position) and volume-control potentiometer R₂ to

the pin 8 control grid of the 6EU7. With selector switch  $S_1$  in the phonograph position, phonograph inputs are coupled directly from  $J_2$  across volume-control potentiometer  $R_2$  to the pin 8 control grid, and the first section of the 6EU7 is bypassed.

The outputs from the pin 7 plate of the 6EU7 are coupled across the frequency-sensitive tone-control network to the control grid of the 6AV6 driver stage. The bass and treble controls Ro and Ro are adjusted to assure optimum low- and high-frequency response characteristics for the amplifier. The two diode plate sections of the 6AV6 are shorted to the tube cathode and thereby are made inoperative. The output of the driver stage is applied to the 6L6GC output stage which develops the audio power required to drive a speaker. Transformer T2 matches the 4000-ohm plate impedance of the output stage to the speaker voice-coil impedance.

# 29-14 TWO-CHANNEL AUDIO MIXER

Voltage Gain from Each Grid of 6EU7 to Output is Approximately 20



#### Parts List

 $C_1$ =10  $\mu$ F, electrolytic, 25 V  $C_2$ =0.05  $\mu$ F, paper, 400 V  $R_1$ ,  $R_5$ ,  $R_5$ =1 megohm,

0.5 watt R₂ R₆=0.1 megohm, 0.5 watt R₃, R₇=Potentiometers, 0.1 megohm, audio taper R₁=1200 ohms, 0.5 watt

# 29-14 TWO-CHANNEL AUDIO MIXER (Cont'd)

## **Circuit Description**


This high-fidelity mixer circuit can be used to combine audio-frequency program material from two sources. Each signal channel consists of a one-stage voltage amplifier using one section of a 6EU7 lownoise twin-triode. Each section of the mixer can provide a voltage gain

of about 20, and can handle an input signal of about 0.2 volt rms without overloading. The dc plate supply of +250 volts (nominal value) for the mixer stages can usually be obtained from an auxiliary tap on the power supply for the audio power amplifiers.

## 29-15

## PHONOGRAPH AMPLIFIER

Power Output, 1 Watt



#### Parts List

C₁=0.082 μF, paper, 400 V C₂=0.02 μF, paper, 400 V C₃, C₄=40 μF, electrolytic, 150 V

150 V
F1=Fuse, 1 ampere
J1=Input connector, shielded,
for crystal phonograph

pickup
n:=0.22 megohm, 0.5 watt
R:=Volume control, potentiometer, 0.5 megohm,
audio taper
R:=10000 ohms. 0.5 watt

R=22 ohms, 0.5 watt

Rs=210 ohms, 10 watts
Rs, Rr=56 ohms, 0.5 watt
Rs=3300 ohms, 1 watt
Tr=Output transformer for
matching impedance of
voice coil to 3000-ohm
tube load


## **Circuit Description**

This single-stage phonograph amplifier operates directly from either an ac power line or a dc supply of 117 volts. AC power inputs are converted to dc power by the 35W4 half-wave rectifier circuit. The heaters of the amplifier and rectifier tube are connected in series, together with a 210-ohm voltage-dropping resistor,  $R_5$ , directly across the input power line.

The amplifier uses a 50EH5

power pentode to develop up to 1 watt of audio output power from the input supplied from a crystal phonograph pickup. The input is applied at J₁ and coupled through a length of shielded cable to the input circuit of the pentode amplifier. Volume-control adjustment for the amplifier is provided by potentiometer R₂. The output coupling transformer T₁ matches the 3000-ohm plate load impedance of the 50EH5 to the voice-coil impedance of the speaker.

## 29-16 PREAMPLIFIER FOR MAGNETIC PHONOGRAPH PICKUP With RIAA Equalization



Sensitivity=3 millivolts rms input for output of 0.55 volt at frequency of 1000 Hz.

#### Parts List

C₁, C₄=25 μF, electrolytic, 25 V C₂, C₅=20 μF, electrolytic, 450 V C₃=0.1 μF, paper, 600 V C₆=0.0033 μF±5 per cent, paper, 600 V C₇=0.01 μF±5 per cent, paper, 600 V

Cs=180 pF±5 per cent, ceramic or mica, 500 V (includes capacitance of output cable)  $C_0=0.22 \mu F$ , ceramic, 500 V J=Input connector, shielded, for high-impedance magnetic phono pickup (10 mV output, approx.)
R1=Value depends on type

of magnetic pickup used. Follow pickup manufacturer's recommendations R2, R7=2700 ohms, 0.5 watt R₃, R₅=0.1 megohm, 0.5 watt R4=39000 ohms, 0.5 watt  $R_6=0.47$  megohm, 0.5 watt Rs=0.68 megohm, 0.5 watt Re=15000 ohms, 1 watt R10=22000 ohms, 0.5 watt

## Circuit Description

This two-stage audio preamplifier is intended for use with high-fidelity magnetic phonograph pickups. The two amplifier stages provide an overall circuit gain of approximately 150. The 7025 twin triode used in the circuit features exceptionally hum and noise and is designed especially for use in high-fidelity circuits that operate at low signal levels. The preamplifier is ideally suited for use as the low-level input stage for audio power amplifiers such as the 50-watt unit, circuit 29-11. For use with audio power amplifiers such as the 15- and 30-watt units, circuits 29-9 and 29-10, which require higher input signals, another low-level amplifier (e.g., the tone-control amplifier, circuit 29-20) must be inserted between the preamplifier and the power amplifier to obtain the full rated output. The heater and dc operating power required for the preamplifier can usually be obtained from the power-supply circuit for the power amplifier.

The audio signal from the phonograph pickup is applied to J and coupled through a length of shielded cable to the control grid of the input stage of the preamplifier. The interstage coupling between the two amplifier sections of the preamplifier includes an RIAA equalization network ( $R_{10}$  and  $C_6$ ). This network compensates for the Orthophonic recording characteristic* introduced into a record disc by the manufacturer. The output from the preamplifier coupled from the plate of the second stage by output coupling capacitor


# PREAMPLIFIER FOR MAGNETIC PHONOGRAPH PICKUP (Cont'd)

### Circuit Description (Cont'd)

C. to the input of a tone-control amplifier (if used) or directly to the input of the power amplifier. Because of its relatively high output impedance, the preamplifier is recommended for use in systems in which the preamplifier is mounted on the same chassis as the power amplifier and/or tone-control amplifier. The preamplifier may be used at distances up to 6 feet from the following amplifier provided that the capacitance of capacitor C₈ is reduced approximately 30 picofarads for each foot of shielded cable used for the audiofrequency connection between the preamplifier and the following amplifier.

* To achieve wide frequency and dynamic ranges, manufacturers of commercial recordings use equipment which introduces a non-uniform relationship between amplitude and frequency. This relationship is known as a "recording characteristic." To assure proper reproduction of a highfidelity recording, therefore, some part of the reproducing system must have a frequency-response characteristic which is the inverse of the recording characteristic. Most manufacturers of high-fidelity recordings "New Orthophonic" use the RCA (RIAA) characteristic for discs and the NARTB characteristic for magnetic tape.

# 29-17 HIGH-FIDELITY PREAMPLIFIER FOR TAPE-HEAD PICKUP With NARTB Equalization



Sensitivity=3 millivolts rms input for output of 0.55 volt at frequency of 1000 Hz.

#### **Parts List**

 $C_1$ =0.047  $\mu F$ , ceramic, 400 V  $C_2$ =40  $\mu F$ , electrolytic, 450 V

450 V C₃=0.1 μF, ceramic, 400 V C₄=25 μF, electrolytic, 25 V C₅=0.22 μF, ceramic, 400 V C₇=25 μF, electrolytic, 25 V Cs=0.22  $\mu$ F, ceramic, 400 V C₀=40  $\mu$ F, electrolytic, 450 V C₁₀=0.47  $\mu$ F, ceramic, 400 V R₁=1 megohm, 0.5 watt R₂=0.1 megohm, 0.5 watt R₃=1000 ohms, 0.5 watt R₄=0.47 megohm, 0.5 watt R₅=0.22 megohm, 0.5 watt R₀=22000 ohms, 0.5 watt

 $R_7$ =3300 ohms, 0.5 watt  $R_8$ =3.3 megohms, 0.5 watt  $R_9$ =1500 ohms, 0.5 watt  $R_{10}$ =0.1 megohm, 0.5 watt  $R_{11}$ =1500 ohms, 0.5 watt  $R_{12}$ =15000 ohms, 0.5 watt  $R_{12}$ =15000 ohms, 0.5 watt  $R_{13}$ =0.47 megohm, 0.5 watt  $R_{14}$ =4700 ohms, 0.5 watt

# 29-17 HIGH-FIDELITY PREAMPLIFIER FOR TAPE-HEAD PICKUP (Cont'd)

### **Circuit Description**


This three-stage preamplifier provides the amplification necessary to increase the output from a tapehead pickup to the level required to drive an audio power amplifier. The circuit uses a 5879 low-noise sharpcutoff pentode in a high-gain input voltage amplifier, one section of a 7025 twin triode in a second voltage amplifier, and the other section of the 7025 in a cathode-follower output stage. Because of the low-impedance cathode-follower output circuit, the preamplifier may be installed at distances up to 50 feet from the following stage (tone-control or power without adverse effect amplifier) upon its frequency-response characteristics. The preamplifier is intended for use as the low-level input stages for an audio power amplifier, such as the 50-watt unit (circuit 29-11) or, when followed by another low-level amplifier (e.g., the tone-control amplifier, circuit 29-20) the 15- or 30watt unit (circuit 29-9 or 29-10).

The heater and dc operating power for the preamplifier can usually be obtained from the power supply for the power amplifier.

The preamplifier provides over-all circuit gain of 180. An input of 3 millivolts rms at the input terminals, is amplified by the pentode and triode voltage amplifiers to develop an output of approximately 0.55 volt rms at the cathode of the cathode-follower output stage. The interstage coupling between pentode and triode voltage amplifiers equalizes the playback frequency response of the preamplifier to compensate for the NARTB recording characteristic introduced into the magnetic tape by the manufacturer. (See footnote for circuit 29-16.) The output of the preamplifier is coupled by capacitor C₁₀ to the input of the audio power amplifier or to the input of intermediate tone-control an amplifier.

# 29-18 PREAMPLIFIER FOR CERAMIC PHONOGRAPH PICKUP

Cathode Follower (Low-Impedance) Output



# PREAMPLIFIER FOR CERAMIC PHONOGRAPH PICKUP (Cont'd)

#### Parts List

C1=0.1 µF, paper, 400 V C2=0.01 µF, paper, 400 V C2=20 µF, electrolytic, 400 V C4=0.25 µF, paper, 400 V Cs=0.22 µF, paper, 600 V J≡Input connector, shielded,

for high-impedance ceramic phono pickup (0.5-volt output)
R1=1.8 megohms, 0.5 watt
R2=Volume control, potentiometer, 0.5 megohm, audio taper

 $\begin{array}{l} R_3{=}0.82 \ \text{megohm, 0.5 watt} \\ R_4{=}0.22 \ \text{megohm, 0.5 watt} \\ R_5, \, R_8{=}4000 \ \text{ohms, 0.5 watt} \\ R_0{=}4700 \ \text{ohms, 0.5 watt} \\ R_7{=}1000 \ \text{ohms, 0.5 watt} \\ R_0{=}1 \ \text{megohm, 0.5 watt} \\ R_1{=}1800 \ \text{ohms, 0.5 watt} \\ \end{array}$ 

#### **Circuit Description**


This two-stage preamplifier is intended for use with a high-impedance ceramic phonograph pickup. The circuit features a cathode-follower (low-impedance) output which makes it possible to install the preamplifier at distances up to 50 feet from the succeeding stage (tone-control or power amplifier). The preamplifier operates from a dc supply of 230 to 300 volts and a heater supply of 6.3 volts. These voltages can usually be obtained from the power supply for the power amplifier in the audio system.

The preamplifier uses a 7199 triode-pentode in a high-gain pentode input stage and a triode cathode-follower output stage. These stages provide the amplification necessary to increase the output from a crystal phonograph pickup, applied at J₁, to the level required to drive an audio power amplifier. The output of the preamplifier, coupled from the cathode of the 7199 triode section, may be applied directly to the power amplifier, or to an intermediate tone-control amplifier.

#### 29-19

## LOW-DISTORTION PREAMPLIFIER

For Low-Output, High-Impedance Microphones



Sensitivity=3 millivolts rms input for output of 220 millivolts.

#### Parts List

C₁=0.047  $\mu$ F, paper, 400 V C₂=25  $\mu$ F, electrolytic, 25 V C₃=0.22  $\mu$ F, paper, 400 V C₄=40  $\mu$ F, electrolytic, 450 V

 $R_1$ =2.2 megohms, 0.5 watt  $R_2$ =0.1 megohm, 0.5 watt

 $\begin{array}{l} R_3{=}1000 \ ohms, \ 0.5 \ watt \\ R_4{=}0.47 \ megohm, \ 0.5 \ watt \\ R_5{=}22000 \ ohms, \ 0.5 \ watt \end{array}$ 


# 29-19 LOW-DISTORTION PREAMPLIFIER (Cont'd)

#### **Circuit Description**

This single-stage preamplifier is intended for use with a high-fidelity, high-impedance crystal or dynamic microphone. The circuit uses a 5879 low-noise sharp-cutoff pentode in a conventional amplifier circuit that has a high-impedance output, a voltage gain of approximately 70, and a flat frequency response over the

audio range. Because of its high output impedance, the preamplifier should be mounted on the same chassis as the power amplifier and tone-control amplifier (if used). Heater and dc power for the circuit can be obtained from the power supply for the audio power amplifier.

## 29-20 BASS AND TREBLE TONE-CONTROL AMPLIFIER



Sensitivity=0.5 volt rms input for output of 1.25 volts with controls set for flat response.

#### Parts List

C1=0.047  $\mu$ F, paper, 400 V C2, C4=20  $\mu$ F, electrolytic, 450 V C3=0.1  $\mu$ F, paper, 400 V C5=0.0022  $\mu$ F, paper, 400 V C5=0.022  $\mu$ F, paper, 400 V C1=0.22  $\mu$ F, paper, 400 V C8=220  $\mu$ F, ceramic or mica, 500 V

Co=0.0022 µF, paper, 400 V R1=0.47 megohm, 0.5 watt R2=1500 ohms, 0.5 watt R3, R11=15000 ohms, 0.5 watt R4=22000 ohms, 0.5 watt R5, R7, R10=0.1 megohm, 0.5 watt

Ro=1000 ohms, 0.5 watt Rs=Bass control, potentiometer, 1 megohm, audio taper

R₀=10000 ohms, 0.5 watt R₁₂=Treble control, potentiometer, 1 megohm, audio taper

## Circuit Description

This high-fidelity tone-control amplifier uses a 6EU7 low-noise twin triode in a two-stage amplifier cascade that consists of an input cathode follower connected to a triode voltage amplifier through a frequency-sensitive (tone-control) interstage cou-

pling network. The bass and treble controls in the coupling network can be adjusted to provide up to 16 dB of boost or attenuation (cut) at 30 Hz and at 15 kHz. With the bass and treble controls set at the mid-range positions, the amplifier provides an

# 29-20 BASS AND TREBLE TONE-CONTROL AMPLIFIER (Cont'd)

Circuit Description (Cont'd)

over-all voltage gain of approximately 2.5, and its frequency response is flat within  $\pm 1 dB$  from 30 Hz to 15 kHz.

The tone-control amplifier is designed for use immediately ahead of an audio power amplifier, such as the 15-, 30-, or 50-watt unit (circuit 29-9, 29-10, or 29-11, respectively). Operating power for the tone-control circuit can usually be obtained from the power supply for the power amplifier. For operating convenience,

the volume control on the power amplifier may be physically located on the tone-control chassis. In this case, it is advisable to insert a 1-megohm resistor in place of the volume control on the power amplifier. If partial compensation for the reduced high- and low-frequency sensitivity of the ear at low volume levels is desired, the volume-control potentiometer may be replaced by a loudness-control potentiometer.

### 29-21

#### **ELECTRONIC VOLT-OHM METER**


### **Circuit Description**

This electronic volt-ohm meter can be used to measure rms values of ac sine-wave voltages from 0.1 to 1500 volts, dc voltages from 0.2 to 1500 volts, peak-to-peak voltages from 0.2 to 4000 volts, and resistances from 0.2 ohms to 1000 megohms. Within these over-all limits, a Range Selector (S1) can be used to select seven different measurement ranges for each measurement function, as shown in the switch-position chart. The mode of operation of the volt-ohm meter is determined by the setting of the five-position (OFF, AC, -DC, +DC, and OHMS) Function Selector (S₂). A section (S_{2D}) of the Function Selector is also used to control the application of the 117volt, 60-Hz, input ac power. The ac input power is converted to dc power by the 1N1764 selenium rectifier and associated components. A 6.3-volt secondary winding of power transformer T₁ supplies power to the tube heaters. A neon lamp connected across the primary of power transformer T₁ lights when ac power is applied to the circuit.

A balanced push-pull dc amplifier, which includes a dc microammeter M₁ connected as part of a dc bridge network between the two plate sections of the stage, is used as the basic measuring circuit for each measurement function of the volt-ohm meter. This circuit has a linear response, excellent stability, and a very high input impedance. Calibration adjustments are provided for each mode of operation to assure that accurate measurements are obtained. If desired, the ZERO ADJ potentiometer R20 may be adjusted to provide a center-scale zero reading on the meter, which is useful in discriminator and bias voltage measurements.

For ac voltage measurements, Function Selector  $S_2$  must be rotated to the AC position. The ac voltage to be measured, applied between the AC-OHMS and COMMON terminals, is coupled through contacts 10 and 9 of  $S_{1A}$  to the ac-voltmeter multipliers ( $R_2$  through  $R_4$ ). The ac voltage from one of the taps on the multiplier, as determined by the setting of the

# 29-21 ELECTRONIC VOLT-OHM METER (Cont'd)



#### SWITCH POSITIONS

Position	Range Selector, S1		1	Function Selector, S2
1 2 3 4 5 6 7	1.5V 5V 15V 50V 150V 500V 1500V	Rx1 Rx10 Rx100 Rx1000 Rx10,000 Rx10,000 Rx1M	4V 14V 40V 140V 400V 1400V 4000V	AC VOLT -DC VOLTS +DC VOLTS OHMS

Notes: 1. Switches are shown in their maximum counterclockwise position  $(S_1=1.5\ V, R\ X\ 1;\ S_2="OFF")$ .

The accuracy of the volt-ohm meter depends upon the accuracy of the multiplier resistors.

#### Parts List

B₁=Battery, 1.5 V C₁=470 pF, ceramic disc, 1600 V C₂=0.001 μF, ceramic disc, 500 V C₄=0.47 μF, tubular, 400 V C₄, C₅=0.02 μF, ceramic disc, 400 V C₆, C₇=0.005 μF, ceramic disc, 200 V C₈=10 μF, electrolytic, 400 V F, 1-Fuse, 0.5 ampere M₁=Meter, dc, 0-200 μA NE₂=Neon lamp R₁=DC-voltage probe isolating resistor, 1 megohm, 0.25 watt R₂=138000 ohms, 0.25 watt R₂=320000 ohms, 0.5 watt R₄=0.9 megohm, 1 watt
R₅, R₁₈=1 megohm,
0.25 watt
R₆, R₁₆, R₂₅, R₂₇=10000 ohms,
0.5 watt
R₇=20000 ohms, 0.25 watt
R₈=70000 ohms, 0.25 watt
R₉=0.2 megohm, 0.25 watt
R₁₀=0.7 megohm, 0.25 watt
R₁₁=2 megohms, 0.25 watt

## 29-21 **ELECTRONIC VOLT-OHM METER** (Cont'd)

#### Parts List (Cont'd)

 $R_{12}\!\!=\!\!7$  megohms, 0.25 watt  $R_{18}\!\!=\!\!8.2$  ohms, wire-wound, 0.5 watt  $R_{14}\!\!=\!\!100$  ohms, 0.25 watt  $R_{15}\!\!=\!\!1000$  ohms, 0.25 watt  $R_{19}\!\!=\!\!10$  megohms, 0.25 watt  $R_{20}\!\!=\!\!20$  megohms, 0.25 watt  $R_{20}\!\!=\!\!20$  megohms, 0.25 watt  $R_{20}\!\!=\!\!20$  megohms, 0.5 watt  $R_{22}\!\!=\!\!91$  megohms, 0.5 watt  $R_{22}\!\!=\!\!91$  megohms, 0.5 watt  $R_{22}\!\!=\!\!10000$  ohms, potentiometer ac calibration, 0.5 watt

0.5 watt R₂₃=10000 ohms, potentiometer dc calibration, 0.5 watt  $R_{24}=15000$  ohms, potentiometer, ohms adjustment, 0.25 watt  $R_{26}=10000$  ohms, potentiometer, zero adjustment, 0.25 watt  $R_{28}=3.3$  megohms, 0.5 watt  $R_{20}=6.8$  megohms, 0.5 watt  $R_{30}=6.8$  megohms, 0.5 watt  $R_{32}=15000$  ohms, 0.5 watt  $R_{32}=15000$  ohms, 0.5 watt  $R_{34}=10000$  ohms, 0.5 watt  $R_{34}=10000$  ohms, potentiometer, ac balance,

0.5 watt

R₃₀=47000 ohms, 0.5 watt

R₃₀=0.22 megohm, 0.5 watt

S₁=Range selector switch,
7 position, RCA stock No.
217924 or equiv.
S₂=Function selector
switch, 5 position, RCA
stock No. 217923 or equiv.
7₁=Power transformer,
105-125 volts rms, 50-60
Hz, RCA stock No. 217921
or equiv.

#### Circuit Description (Cont'd)

Range Selector (S_{1A} section), is rectified by the 6AL5 twin diode. The resultant dc voltage across the rectifier bleeder resistors R21 and R34 is proportional to the ac voltage from the multiplier network. This voltage is then coupled through contacts 4 and 5 of  $S_{2B}$ , through one of the contacts 4 through 10 (as determined by setting of Range Selector) and contact 1 of Sic, and through contacts 1 and 2 of S2A to the pin 2 control grid of the 12AU7A twin triode in the balanced dc amplifier. This input disturbs the balance of the amplifier and a current proportional to the ac input flows through the dc microammeter connected between plates of the 12AU7. The pointer on the microammeter is then deflected to indicate the value of the voltage being measured.

With the Function Selector rotated to either -DC or +DC, a dc voltage being measured is coupled through the 1-megohm probe R₁, the DC VOLTS terminal, and contacts 6 and 5 of S2B to the dc-voltmeter multipliers (R₆ through R₁₂). The 1-megohm resistance of the dc probe together with the resistance of the multipliers results in an input resistance of 11 megohms for dc voltage measurements. The dc voltage from the appropriate tap on the multiplier network selected by the S₁₀ and S₁₀ sections of the Range Selector is coupled through contact 1 of these switch sections (or contact

3 of  $S_{1C}$ ) and contacts 1 (or 3) and 2 of  $S_{2A}$  to the input of the balanced dc amplifier. The pointer of the microammeter in the balanced amplifier is then deflected to provide an indication of the value of the dc voltage being measured. The  $S_{2C}$  section of the Function Selector reverses the connections of the microammeter when the Function Selector is rotated from -DC to +DC so that current will flow through the microammeter in the same direction regardless of whether a negative or positive dc voltage is being measured.

For resistance measurements. the Function Selector is rotated to the OHMS position, and the external resistance to be measured is connected between the AC-OHMS and COMMON terminals of the volt-ohm meter. A 1.5-volt dry cell then causes current to flow through the external resistance, through contacts 10 and 11 of S2A, and through one of the ohmmeter-section multiplier resistors (R₁₃ through R₁₉), as determined by the setting of the Range Selector  $(S_{1B} \text{ section})$ . Because the multiplier resistance is fixed for each range, the voltage developed across the external resistance provides an accurate indication of the value of this resistance. This voltage is coupled through contacts 10 and 2 of  $S_{2A}$  to the input of the balanced dc amplifier. The pointer of the microammeter is then deflected to indicate the value of the resistance being measured.


#### 29-22 SERIES-TYPE STABILIZED VOLTAGE SUPPLY

#### Circuit Description

This series-type stabilized voltage supply uses type 5651A as a voltage reference tube, type 6080 as a seriesregulator tube, and type 5751 as a control tube. In this circuit, the 5651A supplies a fixed reference voltage between the grid of the first unit of the 5751 and its cathode return. Changes in supply voltage to the load are amplified by the 5751 which is connected as a two-stage dc amplifier to control the drop

through the 6080. The resulting output voltage is essentially independent of change in load current.

The voltage regulation of this supply operated at a fixed line voltage of 117 volts and an output voltage of 250 volts is less than 0.2 volt over the current range of 0 to 225 milliamperes. At full current, the regulation for a variation of ± 10 per cent in line voltage is less than 0.1 volt.



#### **Parts List**

 $C_1 = 0.1 \mu F$ , 400 volts current balanc- $R_1 = Plate$ ing potentiometer, 160

ohms, 10 watts R2 = 12000 ohms, 2 watts

 $R_3 = 470000$  ohms, ½ watt  $R_4 = 470000$  ohms,  $\frac{1}{2}$  was  $R_5 = 12000$  ohms, 2 watt  $R_6 = 68000$  ohms, 1 watt

watts

 $R_7 = 1$  megohm,  $\frac{1}{2}$  watt  $R_8 = 15000$  ohms. 2 watts  $R_8 = 15000$  ohms, Ro = Output voltage-control potentiometer, 10000 ohms


Notes: ▲ 375 volts approx. at zero load current; 325 volts approx. at 225 milliamperes load current.

# Socket connections for the 5651A are made so that removal of the 5651A from its

socket opens the load.

* Pins 3 and 6, do not use.

## ALL-PURPOSE DC POWER SUPPLIES



^{*} Bleeder R_B can be omitted if an external load is permanently connected across the ouput terminals. Bleeder current should be approximatly 10 per cent of the load current.

## 29-23 ALL-PURPOSE DC POWER SUPPLIES (Cont'd)

#### Circuit Description

In these power-supply circuits. 5BC3 and 6X4 full-wave rectifier tubes are used to convert ac input nower to de output power in various combinations of output voltage and load current. The 5BC3 tube is a directly heated novar type intended for use in power supplies for radio equipment, television receivers, and other applications that have relatively high dc requirements. The 6X4 tube is an indirectly heated miniature type used primarily in power supplies for automobile and ac-operated radio receivers and other equipment that have moderate dc requirements.

In each rectifier circuit, the 117-volt ac input power is applied to the primary of a step-up power transformer T₁. The two plate sections of the rectifier tube are connected to opposite ends of the center-tapped secondary winding of transformer T₁. With respect to the grounded center tap, the voltage applied to each plate of the rectifier tube, therefore, is 180 degrees out of phase with that applied to the other plate. With an external load connected to the rectifier cathode, pulses of current flow alternately to one plate

and then to the other plate for each half cycle of the ac input power. This 120-Hz pulsating current develops a positive dc voltage across the load circuit.

Removal of virtually all the 120-Hz ripple component from the dc output can be accomplished by connection of a suitable filter network between the rectifier output (cathode) and the load circuit. Either Filter 1 or Filter 2 provides adequate filtering for the 5BC3 circuit. Any one of the three filter networks is satisfactory for use with the 6X4 circuit. Filter 3 is not recommended for use with the 5BC3 circuit because the use of the two resistors R₁ and R₂ in series with the relatively high output results in excessive power loss.

The chart shown with the rectifier circuits lists a wide range of dc output voltage obtainable for various values of load current. Proper selection of power transformer T₁, of the type of filter network, and of the values of filter choke L₁ and resistors R₁ and R₂ results in the desired combination of output voltage and current.

## **BLACK-AND-WHITE TELEVISION RECEIVER**

Circuits 29-24 through 29-28 are essentially identical to the corresponding circuits in the RCA-KCS-152 Television Receiver. These circuits comprise a complete intercarrier television receiver with the exception of the deflection coils and the picture tube. Portions of any television receiver, however, are required to operate over an extremely wide range of very high frequencies. The construction of such circuits requires more than ordinary skill and experience and the use of sophisticated test equipment (see general consideration for the construction of high-frequency and broadband circuits at the beginning of

this section). Home construction of such circuits is not recommended unless the builder has had considerable experience in this type of work.

The chassis of circuits 29-24 through 29-28 are connected to one side of the ac line during operation. Servicing of these circuits should not be attempted by persons not familiar with the following precautions necessary when working on this type of equipment:

 An isolation transformer should be inserted between the receiver and the ac line before any servicing is attempted. CIRCUITS 713

## BLACK-AND-WHITE TELEVISION RECEIVER (Cont'd)

2. If the receiver must be operated directly from the ac supply, the power plug should be inserted in the proper direction to connect the chassis to the ground side of the ac line. An ac voltmeter should be used to measure

the voltage between the chassis and the power-source ground; no voltage reading should be obtained. If a reading is obtained, the power plug should be reversed and another check made for a zero reading.

29-24

### VHF TUNER

For Black-and-White Television Receiver

### **Circuit Description**

This vhf tuner selects the desired vhf frequency channel, amplifies composite video signals in the frequency channel selected, and converts the signal frequencies to the 45.75-MHz picture intermediate frequency and the 41.25-MHz sound intermediate frequency used in television receivers. When used with a uhf tuner, the vhf tuner is operated as a two-stage broadband rf amplifier tuned to 44 MHz (center frequency of the if band) and is essentially a pre-if amplifier for the television receiver. In each mode of operation, the tuner has a band pass that is broad enough to pass all the video information (including synchronizing and equalizing pulses) and the sound information superimposed on the video and sound carrier frequencies and has sufficient selectivity to assure adequate adjacent-channel and image-frequency rejection. The +140 volts used as the B+ supply for the vhf tuner is obtained from the low-voltage power supply of the receiver. The heaters of the tubes in the circuit are connected in series with those of other tubes in the receiver, and power for the series heater string is obtained directly from the input ac power line.


The antenna used with the vhf tuner may be either a 75-ohm monopole, as used with portable receivers, or a balanced 300-ohm antenna. A balanced 300-ohm antenna system

can be matched to the unbalanced 75-ohm tuner input by means of the antenna-matching balun T1. A 13position channel selector, which consists of several wafer-switch sections (S, through S,) mounted on a common shaft, establishes the operating frequency of the tuner for each of the vhf channels 2 through 13 or adapts the vhf tuner for operation with a uhf tuner. With S, set to any of the channel positions 2 through 13, the selected-channel signal from the vhf antenna is coupled through contacts U and 2 of San and input transformer T2 to the rf amplifier, and the input lead from the uhf tuner is not connected to the vhf circuit.

The vhf input signals are amplified by the 3GK5 high-mu framegrid triode used in the rf amplifier stage. The  $S_3$  section of the channel selector connects the appropriate combination of the inductors  $L_6$  through  $L_{15}$  into the grid circuit of the rf amplifier to tune this stage to the desired frequency channel. The agc bias voltage applied to the control grid of the 3GK5 triode automatically controls the gain of the rf stage. The bias voltage, which varies directly with the amplitude of the received signal, is derived by a keyed agc amplifier in the television receiver.

The output of the rf amplifier is coupled through a resonant impedance network to the control grid of

# VHF TUNER (Cont'd)



# VHF TUNER (Cont'd)

#### **Parts List**

C₁, C₂=82 pF, ±5%, dual disc, ceramic, 500 V, N750 N750
Cs, Cs, Cs, C15, C16=1000 pF, feedthrough, 500 V
Cs=12 pF, 5%, ceramic, 500 V, N750
C7=20 pF, ±5%, feed-through, 500 V, N470
Cs=0.56 pF, ±5%, headed lead, 500 V
Cs=100 pF, ceramic, 500 V, N1500 C₁₀=0.22 μF, ceramic, 500 V C₁₁=0.82 pF, headed lead, 500 V C12=82 pF, ±5%, feed-through, 500 V, N750 C₁₈=8 pF, ceramic, 500 V C₁₄=10 pF, ±5%, radial leads, ceramic, 500 V, N880 GIMMICK=Trimmer-capacitor plate L1, L2, L3=RF coils : with two 82-picofarad capacitors, forms high-pass filter (antenna input network), RCA Stock No. 114458 or equiv. L=RF amplifier grid coil,

part of Sa assembly Ls through Lis=RF-amplifier

tuning coils, part of Sa

Lie=Mixer grid coil, part

assembly

of S2 assembly Liz=Interstage coupling coil for rf amplifier and mixer, part of S2 assembly
L18 through L2=Mixer tuning coils, part of S2 assembly Lao=Variable rf coil; mixer plate tuning adjustment; RCA stock No. 112909 or equiv. Ln=RF choke L32=Variable rf coil; localoscillator tuning adjustment for channel 13 L33 through L43=Localoscillator tuning coils (variable coil Lss is tuning adjustment for channel 6), part of S1 assembly L44=Variable rf coil; fine-tuning control; RCA Stock No. 113323, or

equiv. R₁=4700 ohms, 1 watt R₂=5600 ohms, 0.5 watt Rs=47000 ohms, 0.5 watt Ri=0.1 megohm, 0.5 watt Rs, R7=10000 ohms, 0.5 watt Rs, R10=1000 ohms, 0.5 watt R₈=2200 ohms, 0.5 watt R₉=6800 ohms, 0.5 watt S₁=Local-oscillator section of channel-selector switch; stator assembly, RCA Stock No. 114462 or

equiv., includes localoscillator tuning coils Lss through Les

S2=Mixer section of channel-selector switch; stator assembly, RCA Stock No. 114461 or equiv., includes mixer tuning coils La Le, and Lis through Las

S=RF amplifier section of channel-selector switch; stator assembly, RCA Stock No. 114460 or equiv., includes rf-amplifier tun-ing coils L4 and L7

through L₁₇ S₄=VHF-UHF function selector; two-section switch ganged with channel se-lectors, S1, S2, and S3; RCA Stock No. 114185 or equiv.

T1=Antenna-matching balun; matches 300-ohm balanced antenna-lead line to 75-ohm unbalanced receiver-input line; RCA Stock No. 111973 or equiv.

T2=Antenna transformer; RCA Stock No. 113195 or equiv.

Z1, Z2=Resistance-capacitance network (capristor), RCA Stock No. 109956 or equiv.

Notes: 1. All switches are ganged together on same shaft and are shown with shaft in channel 13 position.

Voltages shown are obtained with no signal input.

3. For dc voltage and heater supply, see circuit 29-28, page 725.

4. See additional notes on page 712.

# Circuit Description (Cont'd)

the 6KZ8 pentode section used in the mixer stage. Section S2 of the ganged channel selector selects the proper combination of the inductors through L₂₂ to tune the mixer input circuit to the same operating frequency as that of the rf amplifier. A signal from the plate of the 6KZ8 triode section used in the local-oscillator stage is also applied to the input circuit of the mixer. Section S1 of the channel selector connects the right combination of the inductors L₃₃ through L43 into the oscillator resonant circuit to maintain the operating frequency of the oscillator at 45.75 MHz above the video carrier frequency (41.25 MHz above the sound carrier frequency) of the vhf channel selected by the tuner. Inductor L., in the series-resonant feedback circuit of the oscillator is the fine-

tuning adjustment for the vhf tuner. This adjustment assures that the oscillator frequency accurately tracks the input tuning in each channel.

The signals from the rf amplifier and the local oscillator are heterodyned in the mixer stage to produce the 45.75-MHz amplitudemodulated and 41.25-MHz frequency-modulated difference frequencies used as the picture and sound intermediate frequencies, respectively, in the television receiver. The picture and sound if signals are coupled from the plate of the mixer to the if stages of the receiver.

When the multiple-section channel selector is rotated to the U position (for uhf operation), a connection from the B+ line of the vhf tuner through a 5600-ohm dropping resistor R2, contacts 4 and 10 of S4A.

## VHF TUNER (Cont'd)

### Circuit Description (Cont'd)

and a 4700-ohm dropping resistor R₁ provides the B+ voltage for the uhf tuner. In addition, transformer T₂, which provides the input to the rf amplifier, is connected through contacts 2 and 13 of S_{1B} to the output of the uhf tuner, and the signal from the vhf antenna is shorted to ground through contacts U and 12 of S_{1A}. The input to the rf amplifier is then the amplitude-modulated 45.75-MHz picture if and frequency-modulated 41.25-MHz sound if signals from the uhf tuner.

In the U positions, switch sec-

tions S₂ and S₂ select the tuning inductors required for operation of the rf amplifier and mixer stages as broadband 44-MHz amplifiers, and section S₁ disables the oscillator stage by connection of the oscillator control grid directly to ground through switch contacts 2 and U. With these changes, the vhf tuner essentially becomes a broadband 44-MHz amplifier which provides two stages of amplification of the picture and sound if signals ahead of the receiver main if strip.

#### 29-25

# VIDEO-IF AMPLIFIERS AND SOUND-CHANNEL CIRCUITS

For Black-and-White Television Receiver


#### **Circuit Description**

These circuit stages are typical of those used in the if and audio channels of any intercarrier type of black-and-white television receiver. The over-all circuit operates from a dc supply of +150 volts obtained from the receiver low-voltage (B+) dc power supply. The heaters of the tubes in the circuit are connected in series with those of tubes in other sections of the receiver. Operating power for the series heater string is obtained directly from the 117-volt ac power line.

The input from the vhf tuner consists of amplitude-modulated 45.75-MHz picture if signals and frequency-modulated 41.25-MHz sound if signals. This composite input is coupled by a broadly tuned bandpass filter network to the control grid of the 4JD6 remote-cutoff pentode used in the first picture if amplifier. A dc bias voltage proportional to the input signal from the agc amplifier is also applied to the control-grid circuit to provide automatic gain control of this stage. The output of the first picture if amplifier is coupled by the single-tuned transformer T₁ to the control grid of the 4JC6A pentode used in the second picture if amplifier. The double-tuned transformer T₂ couples the output of this stage to the video detector (CR₁ and associated components). The input filter network and picture if transformers T₁ and T₂ are stagger tuned to obtain the broad response for the if amplifiers required to assure adequate passage of both the 45.75-MHz video and 41.25-MHz sound if signals.

The video detector demodulates the 45.75-MHz picture if signal, and the resultant video signal is coupled through inductors Ls and L and the lower winding of transformer T₃ to the video amplifier (shown in circuit 29-27). The video detector also operates as a second mixer circuit. The 45.75-MHz picture if signal and the 41.25 sound if signal are heterodyned to produce a second sound if carrier of 4.5 MHz. This 4.5-MHz second sound if carrier is still frequency-modulated by the audio components contained in the original rf signal input at the receiver antenna. The sound-takeoff transformer Ts. which forms a selective load impedance for the detector circuit at 4.5 MHz, couples the 4.5-MHz sound if signal to the control grid of the pentode section of a 6GH8A triode pentode used in the sound if ampli-

# VIDEO-IF AMPLIFIERS AND SOUND-CHANNEL CIRCUITS (Cont'd)



#### Parts List

C1, Ca=470 pF, ceramic, 500 V
C2, Cr=0.001 µF, ceramic 500 V
C3=7 pF, ceramic, 500 V, N150
C1=2 pF, ceramic, 500 V, NPO
C5=56 pF, ±5%, ceramic, 500 V N750
C8=560 pF, ceramic, 500 V
C5=18 pF, 5%, ceramic, 500 V
C1=10 pF, ceramic, 500 V
C1=10 pF, ceramic, 500 V
NPO
C12=39 pF, ceramic, 500 V
N150
C13=68 pF, ceramic, 500 V
N150
C13=68 pF, ceramic, 500 V
N750
C13=68 pF, ceramic, 500 V
N750

C₁₄, C₁₀=0.01 μF, ceramic, 500 V C₁₅, C₁₇=12 pF, part of T₄ C₁₆, C₁₈=0.0022 μF, ceramic, 500 V C₂₀=10 pF, part of T₅ C₂₁=680 pF, ceramic, 500 V C₂₂=0.047 μF, paper, 200 V C₂₃=0.01 μF, ceramic, 500 V C₂₄=0.0068 μF, ceramic, 500 V

CR₁=Video detector, crystal diode, RCA Stock No. 112524 or equiv. L₁=RF coil, RCA Stock No. 114315 or equiv. L₂=RF coil, RCA Stock No.

L₂=RF coil, RCA Stock No. 114314 or equiv. L₃=RF coil, 47.25-MHz trap RCA Stock No. 118097 or equiv.

Lu=RF coil, RCA Stock No. 118097 or equiv.

La=Video-detector peaking coil, 36 µH, RCA Stock No. 109758 or equiv.

No. 109758 or equiv. Ln=Filter choke (reactor), 2.7 \( \text{\mu} \)H, RCA Stock No. 107463 or equiv. R1=3300 ohms, 0.5 watt R2=1000 ohms, 0.5 watt

Rs=39 ohms, ±5%, 0.5 watt R4=4700 ohms, ±5%, 0.5 watt

R₅=1500 ohms, 1 watt R₆=100 ohms, 0.5 watt R₇=470 ohms, 0.5 watt R₈=3000 ohms,  $\pm 5\%$ , 0.5 watt

# VIDEO-IF AMPLIFIERS AND SOUND-CHANNEL CIRCUITS (Cont'd)

Parts List (Cont'd)

Rs=820 ohms, 0.5 watt
Rs=82000 ohms, 0.5 watt
Rs=15000 ohms, 0.5 watt
Rs=560 ohms, 0.5 watt
Rs=470 ohms, 0.5 watt
Rs=0.39 megohm, 0.5 watt
Rs=0.39 megohm, 0.5 watt
Rs=10.39 megohm, 0.5 watt
Rs=10.39 megohm, 0.5 watt
Ti=First pix if transformer,

RCA Stock No. 109158 or equiv.

T2=Second pix if transformer, RCA Stock No. 114317 or equiv.

T3=Sound take-off transformer, 4.5-MHz, RCA Stock No. 114489 or equiv. T4=Sound if transformer (includes primary and secondary capacitors), RCA Stock No. 104137 or equiv.

To=Sound detector resonant circuit (includes 10-pF capacitor), RCA Stock No. 109948 or equiv. To=Audio output trans-

T₀=Audio output transformer, matches speaker voice-coil impedance to tube plate load, RCA Stock No. 114490 or equiv.

Notes: 1. Voltages shown are obtained with no signal input.

2. For dc voltage and heater supply, see circuit 29-28, page 725.

3. See additional notes on page 712.

Circuit Description (Cont'd)

fier. The amplified if signal from this stage is coupled by the doubled-tuned 4.5-MHz transformer T₄ to the 6HZ6 audio detector-amplifier stage. This stage demodulates the 4.5-MHz sound if signal and amplifies the resultant audio signal voltage. The +250 volts used as the plate supply for the 6HZ6 is obtained from the horizontal output stage (shown in circuit 29-27 of the receiver.

The audio-signal power required

to drive the speaker is developed by a 12FX5 pentode used in a single-ended audio output stage. The audio-signal voltage from the plate of the audio detector-amplifier is amplified by the 12FX5 and coupled by transformer  $T_{\rm o}$  to the voice coil of the speaker. The volume-control potentiometer  $R_{\rm 10}$  in the input circuit of the output stage provides manual adjustment of the sound level from the speaker.

#### 29-26

# VIDEO, AGC, AND SYNC AMPLIFIERS

For Black-and-White TV Receiver

#### Circuit Description


This circuit shows video, agc, and sync amplifiers for a black-andwhite television receiver. The video and sync amplifiers operate from a plate supply (B+) voltage of 150 volts obtained from the receiver lowvoltage power supply. The plate supply voltage for the agc amplifier is a positive keying pulse from the high-voltage transformer in the receiver. The heaters of the three tubes are connected in series with those of tubes in other sections of the receiver. Operating power for the series heater string is obtained directly from the ac power line.

In the video amplifier, the pentode section of an 11LQ8 triode-pentode provides the required amplification of the video signal. The video signal is coupled from the video detector to the control grid of the video amplifier. The output from the voltage divider in the plate cir-

cuit of this stage is applied to the cathode of the picture tube to intensity-modulate the electron beam during its vertical and horizontal scanning of the picture-tube screen. The contrast control adjusts both the amplitude of the video output and the dc potential at the cathode of the picture tube to control picture contrast. The voltage-divider network in the plate circuit of the video amplifier is interconnected with another voltage-divider network. This second network includes the brightness control and the width control in the screen-grid circuit of the receiver horizontal-output tube (shown in circuit 29-27. The brightness control adjusts the cathode bias on the picture tube to control the intensity of the screen display.

An output from the video amplifier is also applied to the control grid of the 11LQ8 triode section used

# 29-26 VIDEO, AGC, AND SYNC AMPLIFIERS (Cont'd)



Notes: 1. Voltages shown are obtained with no signal input.

2. For dc voltage and heater supply, see circuit 29-28, page 725.

3. See additional notes on page 712.

#### Parts List

C₁=5  $\mu$ F, electrolytic, 150 V C₂=0.15  $\mu$ F, paper, 200 V C₅=0.033, paper, 200 V C₄=0.0047, ceramic, 500 V C₅=0.1  $\mu$ F, paper, 200 V C₆=470 pF, ceramic, 500 V C₇=100 pF, ceramic, 500 V, N1500

N1500 L₁=Video-amplifier peaking coil, 18 µH, RCA Stock No. 109946 or equiv. R₁=18000 ohms, 0.5 watt R₂=330 ohms, 0.5 watt
R₃=1500 ohms, 0.5 watt
R₄=Contrast control, potentiometer, 4000 ohms,
3 watts

 $R_5=1$  megohm, 0.5 watt  $R_6=10$  ohms,  $\pm 5\%$ , 0.5 watt  $R_7=22000$  ohms, 0.5 watt  $R_8=0.27$  megohm, 0.5 watt  $R_9$ ,  $R_{10}$ ,  $R_{20}=27000$  ohms, 0.5 watt

R₁₁=27000 ohms, 1 watt

R₁₂=18000 ohms, 0.5 watt R₁₃=Brightness control, potentiometer, 0.1 megohm

R₁₄, R₁₇=0.82 megohm, 0.5 watt R₁₅=1 megohm, 0.5 watt

R₁₅=1 megohm, 0.5 watt R₁₆, R₂₁=0.68 megohm, 0.5 watt

 $R_{18}$ =3300 ohms, 0.5 watt  $R_{19}$ =8.2 megohms, 0.5 watt  $R_{22}$ =5.2 megohms, 0.5 watt  $R_{23}$ =33000 ohms, 0.5 watt  $R_{24}$ =15000 ohms, 0.5 watt

## Circuit Description (Cont'd)

in a keyed-agc amplifier stage. The operation of the agc amplifier is gated (keyed) by a positive pulse from the high-voltage power transformer (shown in circuit 29-27).

This 450-volt keying pulse, which is synchronized with the video signal, overcomes the bias provided by the 150 volts applied to the cathode circuit and serves as the plate supply

# 29-26 VIDEO, AGC, AND SYNC AMPLIFIERS (Cont'd)

#### Circuit Description (Cont'd)

voltage for the age amplifier. Portions of the video signal that occur coincident with the keving pulse are amplified by the agc stage. A 0.1microfarad capacitor C₅ and a 0.82megohm resistor R₁₄ in the plate circuit of this stage filter out the pulsating components to obtain a negative dc voltage proportional to the video signal and thus to the rf input at the receiver antenna. The negative voltage developed in the plate circuit of the stage is applied as agc bias to the first picture if amplifier and to the rf amplifier in the vhf tuner.

Synchronizing pulses are included in the video signals transmitted by a television broadcast station to provide timing information required for synchronization of the transmitter and receiver scanning systems. The sync amplifier, or separator, separates and amplifies the

synchronizing pulses contained in the composite video signal it receives from the plate circuit of the video amplifier. The circuit uses the triode section of a 6GH8A triodepentode to develop the synchronizing pulses for the vertical- and horizontal-deflection circuits of the receiver. The sync amplifier is basically a class C limiter stage. With the video signal applied, the stage is biased beyond cutoff by the gridleak bias network formed by the 470-picofarad capacitor Co and the 0.68-megohm resistor R21 in the control-grid circuit. Only the sync pulses in the composite video signal have sufficient amplitude to drive the sync amplifier into conduction. The resultant pulses developed across the output voltage-divider network are used as the synchronizing inputs to the horizontal- and vertical-deflection circuits.

# 29-27 VERTICAL- AND HORIZONTAL-DEFLECTION CIRCUITS AND HIGH-VOLTAGE RECTIFIER

For Black-and-White Television Receiver


#### Circuit Description

These circuits develop the vertical and horizontal scanning signals and the dc operating potentials for the picture tube (RCA Type 16BGP4) used in the black-and-white television receiver and the boosted B+ voltage (+250 volts) used in the audio detector-amplifier (part of circuit 29-26. The circuits operate from a dc supply of 150 volts. With the exception of the 1G3GT (or 1B3GT) high-voltage rectifier tube, the heaters of the various tubes are connected in series with those of tubes in other sections of the receiver and are supplied by the input ac power line. Heater power for the 1G3GT (or 1B3GT) is provided by a 1.25volt winding of the high-voltage tarnsformer T1.

The vertical and horizontaldeflection circuits are synchronized by negative signals from the sync

amplifier (separator) which include horizontal sync pulses, equalizing pulses, and vertical sync pulses. When the composite video signal is generated at the television broadcast station, the leading edge of each horizontal sync pulse, of alternate equalizing pulses, and of alternate serrations of the vertical sync pulses are correctly timed to initiate the horizontal-retrace period. It is necessary, therefore, to extract the leading-edge components from the combined sync waveform prior to application of the synchronizing input to the horizontal-deflection circuit. Similarly, the vertical sync pulses must be separated from the combined waveform before they can be used to synchronize the vertical-deflection circuit.

The combined sync waveform is differentiated at the input to the



Notes: 1. Voltages shown are obtained with no signal input.
2. For dc voltage and heater supply, see circuit 29-28, page 725.
3. See additional notes on page 712.

#### Parts List

C1=0.0039 µF, ceramic. 500 V, N5600 C₂=0.01 μF, ceramic, 500 V C₃, C₀=0.047 μF, paper, 200 V  $C_4$ =0.033  $\mu$ F, paper, 200 V  $C_5$ =0.027  $\mu$ F, paper, 600 V  $C_6$ =0.015  $\mu$ F, tubular paper, 200 V C₇=0.022 μF, paper, 200 V  $C_1 = 0.022 \ \mu F$ , paper, 200 V  $C_8 = 0.0022 \ \mu F$ , paper, 1000 V  $C_{10} = 0.0012 \ \mu F$ ,  $\pm 5\%$ , ceramic, 500 V N3300  $C_{11} = 180 \ \text{nF}$ ,  $\pm 5\%$ , ceramic, 5000 V N2200  $C_{12} = 47 \ \text{pF}$ , ceramic, 2500 V, N1500 C13=0.0033 µF, ceramic, 500 V C14=68 pF, paper, 500 V, N1500 C₁₅=470 pF, ceramic, 500 V C₁₆=0.0039  $\mu$ F, mylar, 400 V C17=0.001 µF, ceramic, C18=0.0033 µF, ceramic, 500 V 500 V C₁₀=0.001 μF, ceramic, 500 V C₂₀=0.056 μF, paper, 200 V C₂₁=150 pF, ceramic, 500 V C₂₂=390 pF, mica, 500 C₂₃=68 pF, ceramic, 500 V,

NPO La=Oscillator coil, RCA Stock No. 114486 or equiv. Le, La=RF chokes (reactors), 8.2 µH, RCA Stock No. 107385 or equiv. PC1=Printed circuit (includes 0.001-µF and 0.0024-μF capacitors and 68000-ohm resistor), RCA Stock No. 114506 or equiv. R₁=0.1 megohm, 0.5 watt R2=47 ohms, 0.5 watt R:, R:=0.82 megohm, 0.5 watt R₅=2.2 megohms, 0.5 watt R:=47000 ohms, 0.5 watt R:=Height control, potenti-ometer, 0.75 megohm Rs=820 ohms, 1 watt Ra=3300 ohms, 0.5 watt Rio=Width control, potentiometer, 2000 ohms, 3 watts R₁₁=0.68 megohm, 0.5 watt R12=47000 ohms, 0.5 watt R₁₃=22 megohms, 0.5 watt Ru=22000 ohms, 0.5 watt R₁₅=Vertical-hold control, potentiometer, 0.75 megohm R₁₀=1.8 megohms, 0.5 watt

R17=Vertical-linearity

0.2 megohm
R₁₈=0.47 megohm, 0.5 watt
R₁₉, R₂₅=27000 ohms, 0.5 watt
R₂₉, R₂₁=1000 ohms, 0.5 watt
R₂₉=68000 ohms, 0.5 watt
R₂₉=68000 ohms, 0.5 watt
R₂₁=0.18 megohm, 0.5 watt
R₂₁=0.18 megohm, 0.5 watt
R₂₁=0.13 megohm, 0.5 watt
R₂₂=0.39 megohm, 0.5 watt
R₂₃=12000 ohms, 0.5 watt
R₂₄=15000 ohms, 0.5 watt
R₂₄=15000 ohms, 0.5 watt
R₂₄=33000 ohms, 0.5 watt
R₂₅=33000 ohms, 0.5 watt
R₂₅=34700 ohms, 0.5 watt
R₂₇=4700 ohms, 0.5 watt
R₂₇=6200 ohms, 0.5 watt
R₂₇=6200 ohms, 0.5 watt
R₂₇=6200 ohms, 0.5 watt
R₂₈=6200 ohms, 0.5 watt
R₂₉=6200 ohms, 0.5 watt
R₂₀=6200 ohms, 0.5 watt
R₂₀=7200 ohms, 0.5 watt

control, potentiometer,

SR₁=Selenium rectifier, RCA Stock No. 109474 or equiv. T₂=High-voltage and horizontal-output transformer, RCA Stock No. 114498 or equiv. T₂=Vertical-output trans-

T2=Vertical-output transformer, RCA Stock No. 114502 or equiv.

#### Circuit Description (Cont'd)

horizontal-deflection circuit to obtain negative and positive voltage spikes which correspond to the leading and lagging edges, respectively, of the rectangular sync pulses. The amplitude of these voltage spikes is dependent upon only the peak value of the sync pulses and is not affected by the time durations of these pulses. The differentiating circuit, therefore, does not respond to the flat portions of the vertical sync pulses, and, with the exceptions of the serrations, the vertical sync pulses do not affect the operation of the horizontal-deflection circuits. The leading edge of alternate serrations, however, corresponds to the start of horizontalretrace periods and thus may be considered as merely another horizontal sync signal.

The differentiated sync waveform is applied to the junction of the twin silicon diodes SR₁ used in a phase-discriminator network. The positive portion of the differentiated waveform has no effect on the discriminator network. The negative

portion is compared with a feedback signal from the horizontal oscillator to derive the synchronizing voltage. The frequency of the horizontal oscillator and the repetition rate of the horizontal sync pulses should both be 15,750 Hz, the desired horizontal scanning rate for the picture tube. If the feedback signal from the oscillator does not occur coincident with the horizontal sync pulse, the phase discriminator develops a dc error voltage at the control grid of the input section of the 8FQ7 twin triode used in the oscillator stage. The resultant change in oscillator bias shifts the phase of the oscillator signal until it is locked in phase with the horizontal sync pulse.

The horizontal oscillator is basically a cathode-coupled multivibrator that free-runs, in asymmetrical half cycles, at a frequency of 15,750 Hz. A parallel LC circuit connected in series with the plate of the input section resonates at 15,750 Hz to provide frequency stabilization for the horizontal oscillator. The HOLD con-

Circuit Description (Cont'd)

trol adjusts the basic multivibrator frequency to achieve an exact lockin with the horizontal sync pulses. In a cathode-coupled multivibrator. one amplifier section conducts at saturation and the other section is cut off during one half-cycle of operation, and these states are automatically reversed for the next half cvcle. Such circuits normally provide rectangular-wave outputs from each plate section that are 180 degrees out of phase and that switch between the saturation plate voltage and B+ (i.e., the cutoff plate voltage).

In the horizontal oscillator a series RC network is connected in parallel with the output tube section. Because of this network, the plate voltage does not immediately rise to the B+ value when the output tube section is cut off. Instead, there is a small immediate rise in plate voltage that results from the voltage drop across the resistor R₃₅ in the output RC network produced by the initial charging current to the capacitor C21. The plate voltage then rises gradually at a rate determined by the long-time-constant circuit through which the capacitor is charged. Before the capacitor can fully charge to the B+ voltage, the combination of the horizontal sync input and the feedback signal from the plate of the output section of the oscillator drives the grid of the input section below cutoff. The instantaneous rise in the plate voltage of the input section is coupled to the grid of the output section and causes this section to conduct. The capacitor C21 in the output RC network is then quickly discharged through the series resistor and the relatively low resistance of the output tube section. The output of the horizontal oscillator, therefore, is a trapezoidal voltage wave. The rising-slope portions of this wave (obtained when the ouput tube section is cut off)

corresponds to the horizontal-trace period on the picture tube; the discharge portion of the trapezoidal wave corresponds to the retrace period. The time-constant coupling circuits between the input and output sections of the oscillator are designed so that the retrace period represents only about 5 to 10 per cent of the over-all oscillator cycle.

The trapezoidal voltage wave is coupled to the control grid of the 22JU6 pentode horizontal - output stage and causes a sawtooth current to flow through the high-voltage (flyback) transformer T₁ and through the horizontal-deflection coils of the picture tube. The gradually rising portion of the sawtooth current causes the horizontal scanning of the picture tube; the more rapid negative-slope portion of the current wave causes the retrace. During the retrace period, the picture-tube screen is blanked by a negative pulse applied to the control grid of the picture tube from the vertical-deflection circuits. The WIDTH control R₁₀ in the screen grid of the horizontaloutput stage adjusts the gain of this stage to control the width of horizontal scanning.

The vertical oscillator eniploys a 15KY8A triode-pentode in a basic plate-coupled multivibrator configuration. This free-running 60-Hz multivibrator is synchronized by the vertical sync pulses. The vertical pulses are separated from the combined svnc waveform by integration of the combined waveform across the 0.022microfarad capacitor C7 in the control-grid circuit of the pentode output section of the multivibrator. The integrating network has negligible response for the narrow horizontal sync and equalizing pulses, but responds to the greater energy included in the much wider vertical sync pulses to develop a triangular voltage wave at the control grid of the pentode output section. The

#### Circuit Description (Cont'd)

VERT LIN potentiometer R₁₇ adjusts the charging period of the integrating capacitor to control vertical liearity. The VERT HOLD potentiometer R₁₈ adjusts the frequency of the multivibrator to achieve an exact lock-in with the vertical sync pulses.

The voltage waveform at the control grid of the pentode output section results in a triangular wave of current through the vertical-output transformer T2 and through the vertical-deflection coils of the picture tube. The rising portion of the triangular current wave produces the vertical scanning, and the decreasing portion of the wave provides the retrace. Blanking pulses to cut off the picture tube during vertical and horizontal retrace periods are coupled from the secondary of T₂ and from the VERT LIN potentiometer (combined sync waveform before integration) to the control grid of the picture tube.

The 1G3GT (or 1B3GT) half-wave rectifier circuit develops the dc operating voltages for the picture tube. The ac input power to the rectifier is supplied by the horizontal-deflection circuits. The sudden cutoff of plate current in the horizontal-output stage at the beginning of the retrace period causes a very large, positive-going voltage pulse

to be generated across the highvoltage transformer T1. The rectifier converts this voltage pulse to a dc output voltage of approximately 18,000 volts, which is applied to the inner coating of the picture tube. Removal of negative overshoots that would be developed across the highvoltage transformer because of a flywheel effect is accomplished by connection of a 17BS3A rectifier (damper) tube across the horizontaldeflection coils which are in parallel with the lower tapped section of the high-voltage transformer. The polarity of the damper tube is such that the positive pulse developed across the high-voltage transformer causes no current flow through it. For negative pulses, however, the damper tube provides a low-impedance path for the current, and energy stored in the horizontal-deflection coils during the preceding half-cycle is dissipated as heat at the damper-tube plate to prevent oscillation in the coils. The current through the damper tube develops a dc voltage of 450 volts across the 0.027-microfarad capacitor C5 in the cathode circuit. The 0.68-megohm dropping resistor R₁₁ reduces this voltage to obtain the boosted B+ of 250 volts required for operation of the audio detector-amplifier (part of circuit 29-25).

#### 29-28

#### LOW-VOLTAGE AND HEATER SUPPLY

For Black-and-White TV Receiver


#### **Circuit Description**

This circuit includes the low-voltage (+150-volt) dc power supply and the series heater connections for circuits 29-24 through 29-27. As mentioned previously, the power supply and these four circuits comprise a complete black-and-white television receiver, with the exception of the picture tube and the vertical- and horizontal-deflection yokes.

The power supply is a half-wave

type which uses a 1N3194 silicon rectifier. The 117-volt ac input is connected to the power supply through an interlock, S₁, which may be mounted on the back cover of the receiver. AC input power is then automatically disconnected from the receiver when the back cover is removed. ON-OFF switch S₂ controls the application of ac power to the power-supply circuit and to the tube heaters. With S₁ and S₂ both closed.

# 29-28 LOW-VOLTAGE AND HEATER SUPPLY (Cont'd)



#### Parts List

C₁=0.22  $\mu$ F, paper, 600 V C₂, C₅=0.001, ceramic, 500 V, part of assembly with L₁ C₃=680 pF, ceramic, 1000 V C₄=250  $\mu$ F, electrolytic, 200 V C₆, C₆=680 pF, ceramic,

C7=400  $\mu$ F, electrolytic, 175 V C8=0.001  $\mu$ F, ceramic, 500 V C₁₀=1000 pF, feedthrough, 5000 V F1=Fuse, chemical, 0.45 ampere, RCA Stock No. 114446 or equiv. L1=RF choke, part of heater printed-circuit board, RCA Stock No. 114499 or equivalent (includes the two 0.001-µF capacitors C2 and C3) L2=Filter choke (reactor),

RCA Stock No. 114501 or

equiv. L3=RF choke for VHF tuner filament circuit R₁=Resistor-fuse, 0.35 ohm, RCA Stock No. 114481 or equiv. RC-330 ohms 1 watt

R2=330 ohms, 1 watt TH1=Surge protection resistor (thermistor), 16 ohms (cold), RCA Stock No. 114480.

### Circuit Description (Cont'd)

the 117-volt power from the ac power line is applied to the series heater network and to the 1N3194 rectifier circuit. Two 0.001-microfarad ( $C_2$  and  $C_5$ ) and two 680-picofarad ( $C_4$  and  $C_5$ ) bypass capacitors and rf chokes  $L_1$  and  $L_5$  are included in the heater circuit to filter out any stray high-frequency signals that may be coupled from the rf and if signal channels.

The 117-volt ac input is converted to pulsating dc by the 1N3194 silicon rectifier. A capacitor-input, pi-type LC filter network filters the

rectifier output to obtain a smooth dc voltage that approaches the peak value of the input ac voltage. The 680-picofarad capacitor  $C_5$  in parallel with the 1N3194 rectifier and the thermistor TH₁ in series with it provide surge-current protection for the rectifier. Initial surges of current that may result when power is first applied to the circuit (before a charge is developed across the input filter capacitor) are partially bypassed by the 680-picofarad capacitor and are limited in magnitude by the cold resistance of the thermistor. The

### 29-28 LOW-VOLTAGE AND HEATER SUPPLY (Cont'd)

#### Circuit Description (Cont'd)

thermistor has a negative temperature coefficient of resistance, and by the time the charge of the input capacitor C_i builds up sufficiently to limit the current through the rectifier to a safe value, the resistance of the heated thermistor is small enough so that circuit power losses across this device are negligible. The resistor-fuse element R_i in series with

the 1N3194 rectifier provides protection against any continuous circuit overload. The +150-volt output from the power-supply filter network is used as the main B+ voltage for the television receiver. The 330-ohm, 1-watt dropping resistor  $R_2$  at the output of the filter network reduces this voltage to the +140 volts required as the B+ voltage in the vhf tuner.

#### COLOR TELEVISION RECEIVER

Circuits 29-29 through 29-35 comprise a complete portable color television receiver. The brief signal-tracing analyses of these circuits assume that the reader has a basic knowledge of the purpose and operation of the various circuit sections of a color receiver. (The analyses can be more easily understood if the reader reviews the general discussions on television circuits given in the section on Electron Tube Applications starting on page 15). The receiver, which is essentially identical to the RCA Type CTC-22, features direct-line op-

eration; the chassis of circuits 29-29 through 29-35, therefore, are connected to one side of the ac line during operation. Servicing of these circuits should not be attempted by persons not familiar with the precautions necessary when working on this type of equipment. (See notes 1 and 2 on page 712.)

Note: Circuits 29-29 through 29-35 are included in this manual primarily to illustrate applications of RCA electron tubes. Because of the exceptionally high voltages (up to 21,500 volts), high frequencies, and large bandwidths that are required and of the many special components that are used, home construction of these circuits is not recommended.

# 29-29 LOW-VOLTAGE POWER SUPPLY, DEGAUSSING COIL, AND HEATER CONNECTIONS


For Color Television Receiver

#### **Circuit Description**

This circuit includes the lowvoltage (+280-volt) dc power supply. degaussing circuitry, and heater connections for a color television receiver. The tube heaters, with the exception of the color picture tube, are connected in series across the ac power line. Heater power for the picture tube is supplied by transformer T₁. With ON-OFF switch S₁ closed, the 117-volt power from the ac power line is applied to the series heater string and to the primary of transformer T1. The 117-volt ac input power is stepped down by transformer  $T_1$  to 6.3 volts at 1.0 ampere and applied to the heater of the 15LP22 color picture tube. Bypass capacitors and rf chokes are included in the series heater string to filter out any stray high-frequency signals that may be coupled from the rf and if signal channels of the receiver.

Two silicon rectifiers  $CR_1$  and  $CR_2$  are used in a voltage-doubler circuit to convert the 117-volt ac input power to the +280-volt B+ supply voltage for the receiver. This doubler circuit also provides a 160-volt output from the junction of resistors  $R_4$  and  $R_5$ , a +140-volt output from the junction of resistor  $R_5$  and capacitor  $C_4$ , and a 95-volt output from the junction of resistor  $R_5$  and capacitor  $C_{15}$ . The dc voltage outputs

# 29-29 LOW-VOLTAGE POWER SUPPLY, DEGAUSSING COIL, AND HEATER CONNECTIONS (Cont'd)



#### Parts List

C1=0.047  $\mu$ F, paper, 600 V C2=250  $\mu$ F, electrolytic, 175 V C3=50  $\mu$ F, electrolytic, 250 V C4=100  $\mu$ F, electrolytic, 350 V C3=160  $\mu$ F, electrolytic, 350 V C4=100  $\mu$ F, electrolytic, 350 V C4=100  $\mu$ F, electrolytic, 350 V C4 Through C1=1000 pF, ceramic, 500 V

C15=2 µF, electrolytic, 175 V CB1=Circuit breaker (includes R2), RCA Stock No. 120784 or equiv

120784 or equiv. CR₁, CR₂=Silicon rectifiers, RCA Stock No. 113998 or equiv. F₁=Fuse, 7-ampere, 250-volt L₁, L₂=Inductor, 60-Hz line filter

L3, L4=Degaussing coils, RCA Stock No. 120793 or equiv.

Ls=Filter choke, RCA Stock
No. 120792 or equiv.
Lt, Ls=RF choke
R1=2 ohms, wirewound,
7 watts

R₂=1.3 ohms, part of CB₁ R₃=3900 ohms, wirewound, 10 watts
Ri=47000 ohms, 1 watt
Ri=10000 ohms, 7 watts
Si=ON-OFF switch, single-pole, single-throw

pole, single-throw
\$2=Degaussing switch, RCA
\$2=Degaussing switch, RCA
\$1=Filament transformer;
primary, 117-volt; secondary, 6.3-volt, 1-ampere
THi=Thermistor; cold recitatings 120 above.

sistance, 120 ohms See Note on page 726.

# 29-29 LOW-VOLTAGE POWER SUPPLY, DEGAUSSING COIL, AND HEATER CONNECTIONS (Cont'd)

Circuit Description (Cont'd)

are filtered by the pi-section filter network formed by L₅, C₅, and C₆.

The ac line is protected against any continuous circuit overload by a 7-ampere fuse, F₁, connected in series with one side of the line to ground. Surge protection is provided by a thermistor TH₁ connected in series with the B+ rectifiers (CR₁ and CR₂). The B+ circuit is protected by a special thermal reset circuit breaker CB₁. The circuit breaker opens the B+ line whenever the current demand on the low voltage power supply or the current through the horizontal output stage becomes excessive.

The circuit breaker has a resistive winding (approximately 1.3 ohms) that completes the ground return for the horizontal output tube. If the cathode current of the output tube becomes excessive, the resistive winding heats and causes the bimetal strip in the circuit breaker to expand unequally. The resultant flexing of the bi-metal strip disconnects the breaker switch contacts and thereby opens the B+ line. The same action occurs when the B+ current demand becomes excessive.

Degaussing of the color receiver is initiated by depression of the spring-loaded switch S₂ to the DE-GAUSS position. With S₂ in the NORMAL position, capacitors C₂ and C₃ are combined in parallel to provide the charging capacitance for the

voltage-doubler circuit. For this condition, the parallel capacitors C₂ and C3 are charged to approximately 142 volts and capacitor C₁ is charged to 140 volts to provide the +280-volt B+ voltage. When S2 is depressed to the DEGAUSS position, capacitor C. is disconnected from the circuit, and degaussing coils La and La are connected in series with the powersupply rectifiers and capacitor C3. When the line voltage swings positive, C3 is charged through C4, degaussing coils L3 and L4, and CR2; when the line voltage is negative. C3 is charged through CR1 and the degaussing coils. This alternate cycling results in a symmetrical decaying wavetrain through the degaussing coils. The degaussing coils physically are looped about the receiver chassis in proximity to the color picture tube. The alternating magnetic fields developed by the decaving current wavetrain through these coils effectively demagnetizes picture tube and adiacent The wavetrain dechassis areas. creases to zero when C3 is charged to twice the peak value of the line voltage (approximately 330 volts dc). The degaussing action is completed in less than 1 second. It is only necessary, therefore, to momentarily depress switch S2 to the DEGAUSS position. When the switch is released, it automatically returns to the NORMAL position.

29-30

#### **VHF TUNER**


For Color Television Receiver

#### Circuit Description

This vhf tuner operates from a dc voltage of +280 volts obtained from the low-voltage power supply in the color television receiver. The tuner employs a 2EG4 nuvistor triode in the rf amplifier stage and uses a 4KE8 triode-pentode for the os-

cillator and mixer stages. The heaters of these tubes are connected in series with those of other tubes in the receiver; power for the series-heater string is obtained directly from the 117-volt ac power line. This tuner is very similar to

### VHF TUNER (Cont'd)



Note: Switches S₁ through S₂ are ganged together on the same shaft and are shown in channel 13 position.

### VHF TUNER (Cont'd)

#### Parts List

C₁=0.033 μF, paper, 200 V C₂, C₂₀, C₂₄, C₂₄=1000 pF, feedthrough, 500 V 1eedthrough, 500 V C₃=47 pF ±5%, ceramic, 500 V, N750 C₄=2 pF, feedthrough, RCA Stock No. 119595 or equiv. C₅=Trimmer, 2 to 10 pF, RCA Stock No. 112038 or C₆=27 pF ±5%, ceramic, 500 V, N750 C₇=47 pF, feedthrough, 500 V Cs, Cs, C10, C11=27 pF ±5%, ceramic, 500 V, N470 C12=2.7 pF, headed lead, 500 V C₁₃=33 pF, ceramic, 500 V, N750 N750
C₁₄=39 pF, feedthrough,
500 V
C₁₅=4.7 pF ±5%, headed
lead, 500 V
C₁₅=680 pF, ceramic, 500 V
C₁₇=62 pF ±5%, ceramic,
1000 V, N1500
C₁₈=27 pF, ceramic, 500 V
C₁₈=2 pF, ceramic, 500 V
NPO
C₂₇=56 pF ±5%, ceramic C₂₁=5.6 pF ±5%, ceramic, 500 V, N150 C₂₂=27 pF, ceramic, 500 V, NPO C₂₆=0.047 μF, ceramic, 500 V L₁=RF amplifier grid coil, part of S₃ assembly L₂=UHF trap L3=RF amplifier grid-circuit coil, part of Ss assembly L., L., L.=Filter coils for high-pass filter network, part of T1 assembly L1=RF amplifier plate coil,

part of S3 assembly Ls through Lis=RF amplifier plate-circuit tuning coils. part of Ss assembly Lie through L28=Antenna tuning coils, part of Ss assembly L29, L30=High-band coupling adjust coils Ls1=Mixer grid coil, part of S₂ assembly L₃₂ through L₄₂=Mixer tuning coils, part of S2 assembly Lis, Li=Low-band coupling adjust Las=RF amplifier grid-circuit coil, part of S₅ assembly L₄₀=IF input coil for signals from uhf tuner. RCA Stock No. 120782 or equiv. L₄₇=RF coil, part of input circuit for signals from uhf tuner L₁₈=Mixer plate coil, RCA Stock No. 112909 or equiv. L₁₉=RF filter coil L₅₀=Channel 13 rangecentering coil
Ls: through Lee=Localoscillator tuning coils, part of S₁ assembly J1, J2=Single-contact female connector, RCA Stock No. 104039 or equiv.
R1=47000 ohms, 0.5 watt
R2=16000 ohms, 3 watts
R3=4700 ohms, 1 watt  $R_4$ =82000 ohms, 0.5 watt  $R_5$ =1500 ohms, 0.5 watt  $R_6$ =10000 ohms, 0.5 watt

R7=2200 ohms, 0.5 watt

Rs, R10=10 ohms, 0.5 watt

Re. R13=1000 ohms, 0.5 watt

R11=27000 ohms, 0.5 watt
R12=68000 ohms, 1 watt
R14=6800 ohms, 0.5 watt
R15=6800 ohms, 0.5 watt
R15=680 ohms, 1 watt
S1=Local-oscillator section of channel-selector switch; stator assembly, RCA
Stock No. 114837 or equiv., includes local-oscillator tuning coils LS1 through
L02
S2=Mirer section of channel-

S2=Mixer section of channelselector switch; stator assembly, RCA Stock No. 120084 or equiv., includes mixer tuning coils L₃₁ through Lu2

S3=RF amplifier section of channel-selector switch; stator assembly, RCA Stock No. 120086 or equiv., includes rf amplifier plate tuning coils L₁ through L₁₈ S₄=UHF function switch

S₄=UHF function switch assembly; part of channelselector switch; stator assembly, RCA Stock No. 114807 or equiv.

S5=Antenna section of channel-selector switch; stator assembly, RCA Stock No. 120087 or equiv., includes antenna tuning coils L1, L45, and L19 through L28

T₁=Antenna matching transformer (includes coils L₄, L₅, and L₆ in high-pass filter network), RCA Stock No. 113968

See Note on page 726.

### Circuit Description (Cont'd)

the tuner for a black-and-white television receiver (shown in circuit 29-24), and it operates equally well for either color or black-and-white transmissions.

The antenna used with the tuner is a balanced 300-ohm dipole type which is matched to the unbalanced tuner input circuit by the antenna matching transformer Т.. ganged 5-section, 13-position channel selector, S₁ through S₅, establishes the operating frequency of the tuner for each of the vhf channels 2 through 13 or adapts the vhf tuner for operation with a uhf tuner. When used with a uhf tuner, the vhf tuner is operated as a two stage broadband rf amplifier and becomes essentially a pre-if amplifier for the color television receiver.

With the channel selector set to any of the channel positions 2 through 13, telecast signals, either color or black-and-white, from the selected channel are coupled from the antenna circuit through sections S₄ and S₅ of the channel selector to the control grid of the 2EG4 rf amplifier. For channel positions 2 through 13, the input lead (IF INPUT) from the uhf tuner is not connected to the vhf tuner.

The vhf input signals are amplified by the rf amplifier. The  $S_s$  and  $S_a$  sections of the channel selector connect the appropriate combinations of inductors into the grid and plate circuits of the rf amplifier to tune this stage to the desired frequency channel. An agc bias voltage, derived from the keyed agc amplifier

#### VHF TUNER (Cont'd)

# Circuit Description (Cont'd)

in another section of the color receiver (circuit 29-32), is applied to the control grid of the 2EG4 to control the gain of the rf amplifier automatically.

The output of the rf amplifier is coupled through sections S2 and Sa of the channel selector to the control grid of the 4KE8 pentode section used in the mixer stage. Section S. of the ganged channel selector selects the proper combination of inductors to tune the mixer input circuit to the same operating frequency as that of the rf amplifier. A signal from the plate of the 4KE8 triode section used in the localoscillator stage is also applied to the mixer. Section S. of the channel selector selects the required inductance so that the oscillator operates at a frequency 45.75 MHz above the video carrier frequency of the vhf channel selected by the tuner.

The signals from the rf amplifier and local oscillator are heterodyned in the mixer stage to produce the 45.75-MHz amplitude-modulated and 41.25-MHz frequency-modulated difference frequencies used as picture and sound intermediate frequencies, respectively. The composite color signal received at the antenna also includes a 3.58-MHz color subcarrier sideband. This subcarrier is also

heterodyned with the local-oscillator frequency to produce a color-subcarrier intermediate frequency of 42.17 MHz. The picture, color-subcarrier, and sound if signals are coupled from the plate of the mixer through J₂ to the if stages of the receiver.

When the multiple-section channel selector is rotated to the UHF position,  $S_6$  disconnects the vhf antenna circuit from the rf amplifier, and section  $S_6$  completes a connection to the 280-volt B+ line through several voltage-dropping resistors to provide a dc voltage output of 18 volts for use as the B+ voltage for a uhf tuner. The video, sound and color-subcarrier if signals from a uhf tuner can then be applied through the IF INPUT jack  $J_1$  and contacts of  $S_6$  and  $S_6$  to the control grid of the 2EG4 rf amplifier.

With the channel selector in the UHF position, switch section S₁ opens the B+ line to the local oscillator to disable this stage. In addition, sections S₂, S₅, and S₆ select the proper combination of components so that the rf amplifier and mixer stages operate as broadband 44-MHz amplifiers to provide two stages of amplification of the picture and sound if signals ahead of the receiver main if strip.

# 29-31 VIDEO-AND SOUND-CHANNEL CIRCUITS


For Color Television Receiver

These circuits form the video and sound channels for a color television receiver. The circuits operate from a dc supply voltage of 280 volts, obtained from the receiver low-voltage power supply. The tube heaters are included in the seriesheater string for the over-all receiver. Operating power for the seriesheater string is obtained directly from the 117-volt ac power line.

The picture if-amplifier circuit

consists of two high-gain stages that use high-transconductance framegrid tubes and double-tuned interstage coupling transformers. The composite if input from the vhf tuner which consists of amplitude-modulated 45.75-MHz picture signals 42.17-MHz color-subcarrier components, and frequency-modulated 41.25-MHz sound signals, are coupled by capacitor C21 and transformer T6 to the control grid of the 3KT6 pentode used in the first picture if

# 29-31 VIDEO- AND SOUND-CHANNEL CIRCUITS (Cont'd)



#### Parts List

 $\begin{array}{l} \text{C}_{1}\text{=-5 pF, part of } T_{1} \\ \text{C}_{2}\text{=-}1000 \text{ pF} \pm 5\%, \text{ ceramic,} \\ 500 \text{ V} \\ \text{C}_{3}, \text{C}_{5}, \text{C}_{9}, \text{C}_{11}\text{=-}0.01 \text{ }\mu\text{F,} \\ \text{ceramic,} 500 \text{ V} \\ \text{C}_{3}\text{=-}10 \text{ pF} \pm 5\%, \text{ ceramic,} \\ 500 \text{ V, NPO} \\ \text{C}_{9}\text{=-}1.5 \text{ pF, ceramic,} 500 \text{ V,} \\ \text{NPO} \\ \text{C}_{7}\text{=-}6 \text{ pF, part of } T_{2} \\ \text{C}_{8}\text{=-}47 \text{ pF, ceramic,} 500 \text{ V,} \\ \text{N750} \\ \end{array}$ 

C₁₀=150 pF, part of T₃ C₁₁=39 pF, ceramic, 500 V, N750 C₁₂=560 pF, ceramic, 500 V C₁₃=10 pF, part of T₄ C₁₅=4 pF, ceramic, 500 V C₁₀=10 pF, ceramic, 500 V,

C₁₇=6800 pF, ceramic, 500 V C₁₈=47 pF, ceramic, 500 V, N750 C₁₉=0.047 pF, ceramic, 500 V C₂₀=0.0033 μF, paper, 1600 V C₂₁=Trimmer, 3 to 15 pF, RCA Stock No. 116502 or equiv.

C₂₂=150 pF ±5%, mica, 500 V

C₂₅, C₂₆, C₂₈, C₃₅=1000 pF, ceramic, 500 V C₂₄=330 pF, mica, 500 V C₂₅=24 pF, ceramic, 500 V, NPO

### 29-31 VIDEO- AND SOUND-CHANNEL CIRCUITS (Cont'd)

#### Parts List (Cont'd)

C₂₇=4700 pF, ceramic, 500 V C₂₉=430 pF ±5%, mica, 500 V C₃₀=150 pF, mica, 500 V C₃₁=0.047 μF, Mylar, 100 V C₃₂=0.047 μF, ceramic, 100 V C₃₁=560 pF, ceramic, 500 V C₃₀=680 pF, ceramic, 500 V C₃₁=560 μF, ceramic, 500 V C₃₁=250 μF, ceramic, 500 V C₃₁=100 μF, ceramic, 500 V

RCA Stock No. 115867 or equiv. DL₁=Delay line, RCA Stock

equiv.
DL₁=Delay line, RCA Stock
No. 120786 or equiv.
L₁=RF choke, 3.9 \( \mu \)H, RCA
Stock No. 116507 or equiv.
L₂, L₁₀=RF choke, 1.8 \( \mu \)H,
RCA Stock No. 109248 or

equiv. L_S=RF choke, 12 µH, RCA Stock No. 120831 L₄=Inductor for 47.25-MHz trap, RCA Stock No. 121447 or equiv.

trap, RCA Stock No.
121447 or equiv.
L₅=Video-detector filter coil,
5.6 μH, RCA Stock No.
109171 or equiv.

109171 or equiv. Le, Le=Part of 4.5-MHz trap, RCA Stock No.

121446 or equiv. L₁=Video-detector filter coil, 36 μH, RCA Stock No. 16056 or equiv

16056 or equiv.
L₆=RF choke, 100 μH, RCA
Stock No. 117380 or equiv.
L₁₁=Filter coil, 27 μH,
RCA Stock No. 116511

or equiv.

L₁₂=Filter network (includes resistor R₃₂); RCA

Stock No. 116499 or equiv.

L₁₃=Second-video plate coil,

330 μH, RCA Stock No. 118710 or equiv. L₁₄=First-video plate coil, 1.8 μH, RCA Stock No. 78466 or equiv.

R₁, R₆, R₃₅, R₄₃=270 ohms, 0.5 watt

R₂, R₂₅=10000 ohms, 0.5 watt R₃=8200 ohms, 0.5 watt R₄=0.15 megohm, may be part of T₂

0.112 R5=3300 ohms, 0.5 watt R7=0.68 megohm, 0.5 watt R8=0.47 megohm, 0.5 watt R8=68000 ohms, may be part of T4

01 14 R₁₀=Potentiometer, volume control, 1 megohm, 0.5 watt

R₁₁=Potentiometer, soundrejection adjustment, 7500 ohms, 0.5 watt R₁₂=0.33 megohm, 0.5 watt R₁₃, R₃₀=0.1 megohm,

0.5 watt R₁₄=3900 ohms, ±5%, 0.5 watt

0.5 watt R₁₅=56 ohms, ±5%, 0.5 watt R₁₆=1000 ohms, 0.5 watt

 $R_{16}=1000$  ohms, 0.5 watt  $R_{17}=22000$  ohms, 4 watts  $R_{18}=6800$  ohms,  $\pm 5\%$ ,

0.5 watt R₁₀=150 ohms, ±5%, 0.5 watt

 $R_{20}$ =470 ohms, 0.5 watt  $R_{21}$ =1200 ohms, 0.5 watt  $R_{22}$ =1200 ohms, 0.5 watt  $R_{22}$ =0.18 megohm, 0.5 watt  $R_{24}$ =5.6 megohms, 0.5 watt  $R_{24}$ =22 megohms, 0.5 watt  $R_{27}$ =2.7 megohms, 0.5 watt  $R_{27}$ =2.7 wegohms, 0.5 watt

R₂₈=Potentiometer, brightness control, 0.25 megohm, RCA Stock No. 120775 or equiv. R₂₀=680 ohms ±5%, 0.5 watt

R₃₁=0.22 megohm, 0.5 watt R₃₂=2200 ohms, part of assembly with L₁₂ R₃₃=0.39 megohm, 0.5 watt R₃₄=0.12 megohm, 0.5 watt R₃₆=100 ohms, 0.5 watt

 $\begin{array}{l} R_{37}{=}5600 \text{ ohms, } 0.5 \text{ watt} \\ R_{39}{=}560 \text{ ohms, } 0.5 \text{ watt} \\ R_{20}{=}22000 \text{ ohms, } 3 \text{ watts} \\ R_{40}{=}6800 \text{ ohms, } 4 \text{ watts} \\ R_{41}{=}10000 \text{ ohms, } 3 \text{ watts} \\ R_{42}{=}33000 \text{ ohms, } 4 \text{ watts} \\ T_{1}{=}Sound-takeoff \text{ trans-} \end{array}$ 

former (includes C₁), RCA Stock No. 120824 or equiv. T₂=4.5-MHz sound if transformer (includes C₇ and may include R₄), RCA Stock No. 120828 or equiv.

Stock No. 120828 or equ Tx=Pix if output transformer and 41.25-MHz trap, RCA Stock No. 120827 or equiv.

120827 or equiv.
T₁=Sound-demodulator
quadrature network (includes C₁3 and may include
R₀), RCA Stock No. 120825
or equiv.

T=Audio output transformer, matches 5000-ohm tube-plate impedance to 3.2-ohm speaker voice coil, RCA Stock No. 120822 or

equiv.
T₀=IF input transformer
and 41.25-MHz trap,
RCA Stock No. 116560

or equiv. T7=Pix if transformer, RCA Stock No. 120826 or equiv.

See Note on page 726.

### Circuit Description (Cont'd)

amplifier. The 3KT6 tube has good characteristics. remote-cutoff automatic-gain-control the bias voltage from the receiver agc amplifier (shown in circuit 29-32) is also applied to the control-grid circuit of this tube. The output of the first picture if amplifier is coupled by transformer T₇ to the control grid of the 3JC6A pentode used in the second picture if amplifier. Capacitor C₀ couples the output of the second picture if amplifier to the sound detector, and transformer T₃ couples the output to the video (pix) detector. Transformers Te, T7, and T3 are stagger-tuned to obtain the wide band pass required for the if amplifiers to pass both the 45.75-MHz video AM signals and the 41.25-MHz

sound FM signals, as well as the intermediate 42.17 color subcarrier.

The sound detector (CR₁ and associated components) is essentially a second mixer circuit. The 45.75-MHz picture if signal and the 41.25 sound if signal are heterodyned to produce a second sound if carrier of 4.5 MHz. This 4.5-MHz sound if carrier is still frequency-modulated by the audio components contained in the original rf signal input at the receiver antenna. The sound-takeoff transformer T₁ forms a selective load impedance for the 4.5-MHz if signal derived in the sound detector circuit.

The 4.5 MHz signal developed across sound-takeoff transformer T, is applied to the control grid of the 3JC6A sound if amplifier. The ampli-

#### 29-31 VIDEO- AND SOUND-CHANNEL CIRCUITS (Cont'd)

Circuit Description (Cont'd)

fied 4.5 MHz FM if signal from this stage is then coupled by the double-tuned transformer T₂ to the control grid of the 5HZ6 sound demodulator. This stage demodulates the 4.5-MHz sound if signal and amplifies the resultant audio signal voltage. The +490 volts used as the plate supply for the 5HZ6 demodulator tube is derived from the 700-volt B Boost supply in the horizontal-output stage (shown in circuit 29-33) of the receiver.

The tuned secondary circuit of transformer T₃ selects the 45.75-MHz amplitude-modulated picture and 42.17-MHz color sideband signals from the composite if signal and applies this picture signal to the video detector (CR2 and associated components). The detected video signal developed across the detectorcircuit filter network (L5, L6, L7, L8, and C₃₀) is then coupled through C₃₁ and R22 to the control grid of the 5GH8A triode section used in the first video amplifier (the pentode section of the 5GH8A tube is used in the sync-agc-and-chroma driver, shown in circuit 29-32). The first video amplifier supplies the input signals to the sync-agc-and-chroma driver and to the second video amplifier.

The second video stage performs many functions. The input circuit of the 11HM7 pentode used in this stage is the insertion point for horizontal blanking pulses (for eventual application to the cathodes of the color picture tube). The horizontal blanking diode CR3 is placed in the conducting mode by a small positive voltage applied to its anode through the dropping resistor R₃₃ from the 280-volt B+ source. During active video scanning time, diode CR1 is (conducting). forward-biased the video signal is coupled by capacitor C₂₁, to the control grid of the video amplifier. During horizontal blanking time, a negative pulse from the horizontal-output transformer

 $(T_1$  in circuit 29-33) is applied through  $C_{34}$  and  $R_{34}$  to the diode. This negative pulse is sufficient to cut off the diode during horizontal retrace time. The pulse is applied to the control grid of the second video amplifier and drives the grid more negative (than would the normal horizontal sync pulse). The negative signal at the grid is inverted at the plate; the added positive level coupled to the cathodes of the color picture tube is sufficient to provide blanking of horizontal retrace lines.

The brightness control for the color receiver is also located in the control-grid circuit of the second video amplifier. Negative de grid bias for the 11HM7 second video tube is derived from the ac voltage obtained from the heater, pin 6, of the second video tube. The 11HM7 heater is in the approximate center of the series heater string (refer to circuit 29-29); at this point, approximately 60 volts of ac voltage is available. The negative dc voltage (about -75 volts) is developed across Cas by the IN3194 rectifier circuit. Adjustment of the brightness control, R28 alters the grid bias by "tapping" the positive voltage applied to the top of the control. This unique circuit arrangement provides automatic brightness compensation with changes in power-line voltage. If line voltage increases, the negative voltage across C32 increases: the increased bias that is then applied to the 11HM7 decreases the conduction of this tube. The opposite action occurs with a decrease in line voltage.

The cathode of the second video amplifier is returned to the contrast control R₁₁. Brightness stability is obtained by use of a fixed 150-ohm, 5-per cent resistor, R₁₃, for dc cathode bias. Adjustment of the contrast control does not change the dc characteristics of the cathode; only the ac signal gain of the stage is altered when the control is adjusted.

CIRCUITS 735


#### 29-31 VIDEO- AND SOUND-CHANNEL CIRCUITS (Cont'd)

#### Circuit Description (Cont'd)

Vertical-retrace blanking is accomplished in the plate circuit of the second video amplifier. During active scan periods, the vertical-blanking diode CR₄ is forward-biased (conducts); during vertical retrace periods, however, a positive (blanking) pulse from the vertical-output transformer (T₂ in circuit 29-33) is applied through R₃₈ to the cathode of the diode. This 60-volt positive

pulse is large enough to bias the diode into cutoff. During the blanking interval, the positive voltage pulse is added to the plate voltage of the 11HM7 second-video tube and applied to the cathode circuits of the color picture tube. As a result of the increased positive potential at the cathode, the picture tube is cut off during vertical retrace periods.

# 29-32 SYNC, AGC, AND VERTICAL-DEFLECTION CIRCUITS For Color Television Receiver



#### Parts List

C₁=0.18 μF, Mylar, 200 V C₂=24 pF, ceramic, 500 V, NPO C₃, C₁τ=0.01 μF, ceramic, 500 V C₅=3800 pF, ceramic, 500 V C₅=3800 pF, ceramic, 500 V C₆=470 pF, ceramic, 500 V C₇=0.1 μF, paper, 600 V C_S=0.0056 μF, Mylar, 400 V C₀=0.01 μF, Mylar, 600 V C₁₀, C₁₅=680 pF, ceramic, 500 V C₁₁=0.047 μF, Mylar, 100 V C₁₂=1500 pF, ceramic, 500 V C₁₃=50 μF, electrolytic, 75 V C₁₁=0.0082 μF, paper, 1000 V C₁₀=0.033 μF, Mylar, 600 V C₁₈=0.001 μF, ceramic, 3000 V C₁₀=25 μF, electrolytic, 25 V L₁=RF choke, 120 μH, part of assembly with R₂, RCA Stock No. 120795 or equiv.

# 29-32 SYNC, AGC, AND VERTICAL-DEFLECTION CIRCUITS (Cont'd)

Parts List (Cont'd)

R₁, R₁₈=0.15 megohm,
0.5 watt

R₂=Potentiometer, agc
adjustment, 50000 ohms,
0.5 watt, RCA Stock No.
120804 or equiv.
R₃=27000 ohms, 0.5 watt
R₄=3300 ohms, 0.5 watt
R₅, R₁₇, R₂₈=10000 ohms,
0.5 watt
R₅=6800 ohms, 0.5 watt
R₇=27000 ohms, 1 watt
R₈=1500 ohms, 1 watt
R₉=68000 ohms, 0.5 watt
R₉=68000 ohms, 0.5 watt
R₁=1000 ohms, 0.5 watt
R₁=1800 ohms, 0.5 watt
R₁=1800 ohms, 0.5 watt
R₁=1800 ohms, 0.5 watt
R₁=12000 ohms, 0.5 watt
R₁=12000 ohms, 0.5 watt
R₂=78,3=0.12 megohm,

0.5 watt
R₁₃=10 megohms, 0.5 watt
R₁₄=22000 ohms, 0.5 watt
R₁₅=10000 ohms, 3 watts
R₁₆=22 megohms, 0.5 watt
R₁₆=23 megohms, 0.5 watt
R₂₀=1.5 megohms, 0.5 watt
R₂₁=Potentiometer, vertical-linearity control, 3.4 megohms, 0.5 watt, RCA
Stock No. 120807 or equiv.
R₂₂=56000 ohms, 0.5 watt
R₂₁=4.7 megohms, 0.5 watt
R₂₂=4.7 megohms, 0.5 watt
R₂₅=1.5 megohms, 0.5 watt
R₂₆=1.5 megohms, 0.5 watt
R₂₆=1.5 megohms, 0.5 watt
R₂₆=0.47 megohm, 0.5 watt
R₂₆=0.47 megohm, 0.5 watt
R₂₆=33000 ohms ±5%,

0.5 watt
Ra=0.22 megohm, 0.5 watt
Ra=1500 ohms, 1 watt
Rai=1500 ohms, wirewound,
3 watts
Rai=Potentiometer, verticalheight control, 1 megohm,
0.5 watt, RCA Stock No.
120805 or equiv.
Ra=0.1 megohm, 1 watt
Rn=Potentiometer, verticalhold control, 0.75 megohm, 0.5 watt
VDR₁=Voltage-dependent
resistor (varistor): 870
volts at 1 mA; RCA
Stock No. 112876 or equiv.

See Note on page 726.

#### **Circuit Description**

This circuit shows the sync-agcand-chroma driver, agc amplifier, sync separator, and vertical deflection circuit for a color television receiver. The sync-agc-and-chroma driver, the sync separator, and the vertical output tube operate from a plate supply (B+) voltage of 280volts obtained from the receiver lowvoltage power supply. The plate supply voltage for the agc amplifier is a positive keying pulse from the horizontal-output transformer, and the plate voltage for the vertical oscillator is obtained from the 700volt B Boost supply in the horizontal output circuit. The tube heaters are connected into the series-heater string for the over-all color receiver; power for the heater operating string is obtained directly from the ac power line.

The drive signal for the sync and age circuits is obtained from the cathode of the first video amplifier (shown in circuit 29-31). This signal is coupled by capacitor C2 and the parallel LR network L₂ and R₀ to the control grid of the 5GH8A pentode section used in the sync-agcand-chroma driver. (The triode section of the 5GH8A tube is used in the first video amplifier). The screengrid and control-grid bias voltages for the driver pentode are also obtained from the first video amplifier. The output of the driver stage is applied to the control grids of the age amplifier and the sync separator and to the chroma circuits (shown in circuit 29-34).

The agc amplifier uses the pentode section of a 5GH8A triodepentode; the triode section of this tube is used in the sync separator. The operation of the agc amplifier is gated by a positive keving pulse from the horizontal-output transformer (shown in circuit 29-33). This pulse, which is synchronized with the video signal, overcomes the bias provided by the 95 volts (obtained from the receiver low-voltage power supply, circuit 29-29) applied to the cathode circuit of the agc amplifier. Portions of the video signal that occur coincident with the keving pulse (i.e. during the horizontal blanking interval) are amplified by the agc stage. Resistor R₁ and capacitor C1, together with other filtering elements in the control-grid circuit of the first picture if amplifier, filter out the pulsating components in the video signal to obtain a negative dc voltage proportional the video signal and thus to the rf input at the receiver antenna. Similarly, an agc bias voltage for the vhf tuner is developed across the filter capacitor C₂.

Synchronizing pulses are included in the composite rf signals transmitted by a television broadcast station to provide timing information required for synchronization of the transmitter and receiver scan-

CIRCUITS 737

# 29-32 SYNC, AGC, AND VERTICAL-DEFLECTION CIRCUITS (Cont'd)

Circuit Description (Cont'd)

ning systems. The sync separator separates and amplifies the synchronizing pulses contained in the composite video signal it receives from sync-age-and-chroma driver. The 5GH8A triode section used in this stage is operated basically as a class C limiter. When the video signal is applied, the stage is biased beyond cutoff by the negative voltage developed by the grid-leak bias network formed by C. and R18. Only the sync pulses in the composite video signal have sufficient amplitude to drive the sync amplifier into conduction. The resultant negative pulses developed in the plate circuit of the 5GH8A triode section are applied as the synchronizing inputs to the vertical and horizontal deflection circuits.

vertical-deflection The circuit employs one section of a 10GF7A dual triode in a vertical oscillator stage and a vertical output stage. These two stages form a basic platecoupled 60-Hz free-running multivibrator that is synchronized by negative vertical sync pulses from the sync separator stage. The negative-pulse output from the zync separator, however, includes horizontal sync pulses and equalizing pulses in addition to the vertical sync pulses. The vertical sync pulses must be

separated from the composite syncseparator output prior to the application of the synchronizing input to the vertical-deflection circuits. This separation is accomplished by integration of the composite syncseparator output across capacitor C12. The integrating network (R27 and C₁₂) has negligible response for narrow horizontal-sync equalizing pulses, but responds to the greater energy contained in the much wider vertical-sync pulses to develop a triangular voltage waveform, coupled by C16, C9, and R25 to the control grid of the vertical-output triode section, that synchronizes the operation of the multivibrator. The combination of the triangular wave input to the grid of the output section and the square-wave multivibrator signal results in a trapezoidal voltage waveform at the plate of the output section. This trapezoidal voltage wave produces a triangular wave of current through the vertical-output transformer (T2 in circuit 29-33) and through the vertical deflection coils of the picture tube (shown in circuit 29-35). The rising portion of the triangular current waveform produces the vertical scanning, and the decreasing portion of the waveform provides the retrace.

# 29-33 HORIZONTAL-DEFLECTION CIRCUIT AND HIGH VOLTAGE POWER SUPPLY

For Color Television Receiver


#### **Circuit Description**

These circuits develop the horizontal scanning signals and the do operating voltage (21,500 volts) for the color picture tube (RCA Type 15LP22) and the receiver B Boost voltage (700 volts). The circuits operate from the receiver low-voltage (280-volt) supply. The heaters of the 5GH8A, 24JE6A, and 17KV6A tubes used in these circuits are included in the series-heater string for the

over-all receiver; operating power for these heaters is obtained directly from the 117-volt ac power line. Heater power for the 3A3A high-voltage rectifier tube is obtained from a 3-volt secondary winding on the high-voltage transformer.

A blocking oscillator in which the transformer coil is located in the cathode circuit is used to obtain a large-amplitude horizontal-drive

#### HORIZONTAL-DEFLECTION CIRCUIT AND 29-33 HIGH-VOLTAGE POWER SUPPLY (Cont'd)



#### Parts List

C₁=82 pF ±1 pF, ceramic, 500 V, NPO C₂=1200 pF, ceramic, 500 V C₃=0.0018  $\mu$ F, paper,

1000 V C₄=150 pF, ceramic, 500 V, NPO

 $C_5=0.15 \mu F$ , Mylar, 75 V  $C_6=0.01 \mu F$ , Mylar, 600 V  $C_7=0.01 \mu F$ , Mylar, 75 V

s, C₁₅=1200 pF, ceramic, 500 V

C₀, C₁₉=0.1 μF, Mylar, 400 V

C₁₀=15 pF, ceramic, 5000 V, N750

C₁₁, C₁₃=1000 pF, ceramic, 500 V

C₁₂, C₁₄=0.01 μF, Mylar, 400 V

C_{1e}=270 pF ±5%, mica,

C17=100 pF, ceramic, 5000 V, N1500

C18=22 pF, ceramic, 1000 V, N750

 $^{1.760}_{20}$ =0.1, Mylar, 200 V  $^{\circ}_{21}$ =0.033  $_{\mu}$ F, Mylar, 600 V  $^{\circ}_{22}$ =0.01  $_{\mu}$ F, Mylar, 600 V  $^{\circ}_{23}$ =40  $_{\mu}$ F, electrolytic, 350 V

C₂₄=0.047 μF, Mylar,

C₂₅=150 pF, ceramic, 2000 V, N1500

2000 V, N1500 C₂₀=270 pF, ceramic, 2500 V, N1500 C₂₁=150 pF, ceramic, 2000 V, N1500 C_N=AFC diodes, RCA Stock No. 109474 or equiv.

CR2=Damper diode, RCA Stock No. 120818 or equiv. J1=Octal socket, convergence-circuit input jack.

RCA Stock No. 77645 or equiv. (mates with P₁ on circuit 26-36)

J2=Octal socket, deflectionyoke input jack, RCA Stock No. 102787 or equiv. (mates with P2 on circuit 26-36)

L1, L2=Horizontal-oscillator dual-coil assembly, RCA Stock No. 109947 or equiv. L₃, L₄=RF choke, 4.7  $\mu$ H, RCA Stock No. 120839

or equiv. L=Variable inductor, hori-

zontal efficiency adjust-ment, RCA Stock No. 120794 or equiv. R1, R22=0.22 megohm,

0.5 watt R₂, R₂₀=0.39 megohm, 0.5 watt

# 29-33 HORIZONTAL-DEFLECTION CIRCUIT AND HIGH-VOLTAGE POWER SUPPLY (Cont'd)

#### Parts List (Cont'd)

R₃=0.27 megohm, 0.5 watt R₄=100 ohms, 0.5 watt R₅=15000 ohms, 0.5 watt R₆=1200 ohms, 0.5 watt R₇=47 ohms, 0.5 watt R₈, R₂₀=0.12 megohm,

0.5 watt  $R_0$ =0.15 megohm, 0.5 watt  $R_{11}$ =82000 ohms, 0.5 watt  $R_{11}$ =8.2 megohms, 0.5 watt  $R_{12}$ =680 ohms, 2 watts  $R_{13}$ =82000 ohms ±2%, 0.5 watt

R₁₄=82000 ohms ±5%, 4 watts R₁₅=100 ohms, 0.5 watt R₁₆=68000 ohms, 1 watt R₁₇=33000 ohms, 0.5 watt R₁₈=1000 ohms, 2 watts R₁₈=10000 ohms, 0.5 watt R₂₁=27000 ohms, 0.5 watt R₂₁=2000 ohms, 0.5 watt

voltage adjustment, 0.5 megohm, 0.5 watt R2:=33000 ohms, 0.5 watt R2:=0.56 megohm, 0.5 watt R2:=0.27 megohm, 1 watt R2:=120 ohms, 0.5 watt R3:=22 megohms, 0.5 watt

R₃₁=Potentiometer, horizontal-hold control, 50000 ohms, 0.5 watt

Soi=Spark-gap capacitor,
0.5 pF, 1000 V, RCA
Stock No. 120819 or equiv.
T1=Horizontal-output (fly-back) transformer, RCA
Stock No. 120820 or equiv.
T2=Vertical-output transformer, RCA Stock No.
120821 or equiv.

See Note on page 726.

#### Circuit Description (Cont'd)

waveform. A control stage establishes the bias for the oscillator and, in this way, controls the firing of the oscillator stage. The 5GH8A triode-pentode is used in these stages. The triode section is used as the oscillator tube; the pentode section is used as a high-gain, low-drift control tube.

When the composite video signal is generated at the television broadcast station, the leading edge of each horizontal sync pulse, of alternate equalizing pulses, and of alternate serrations of the vertical sync pulses are correctly timed to initiate the horizontal retrace period. These leading-edge components are tracted from the composite output from the sync separator (shown in circuit 29-31) and are used to synchronize the operation of the horizontal oscillator.

svnc waveform differentiated by the RC network (C1 and R₂) at the input to the horizontal deflection circuit to obtain negative and positive voltage spikes that correspond to the leading and lagging respectively, of the tangular sync pulses. The amplitude of these voltage spikes is dependent upon only the peak value of the sync pulses and is not affected by the time durations of these pulses. The differentiating circuit, therefore, does not respond to the flat portions of the vertical sync pulses; as a result, with the exception of the serrations, the vertical sync pulses do not affect the operation of the horizontal-deflection circuits. The leading edge of alternate serrations, however, correspond to the start of horizontal-retrace periods and thus may be considered as merely another horizontal sync signal.

The differentiated sync waveform is applied to the junction of the twin silicon diode CR1 used in a phase-discriminator type of afc network. The positive voltage spikes in the differentiated waveform have no effect on the discriminator network. The negative-voltage spikes are compared with pulses fedback from the horizontal oscillator to derive the synchronizing voltage. The frequency of the horizontal oscillator and the repetition rate of the horizontal sync pulses should both be 15,750 Hz, the desired horizontal scanning rate for the picture tube. If the pulses from the oscillator are not coincident with the horizontal sync pulses, the phase discriminator develops an error voltage at the control grid of the control tube. The control tube then varies the bias and, thus, the firing point of the oscillator until it is locked in phase with the horizontal pulses.

The parallel LC network ( $L_2$  and  $C_{12}$ ) in the cathode circuit of the oscillator resonates at 15,750 Hz to provide frequency stabilization for the oscillator. The HOLD control  $R_{21}$  adusts the frequency of the oscil-

# 29-33 HORIZONTAL-DEFLECTION CIRCUIT AND HIGH-VOLTAGE POWER SUPPLY (Cont'd)

#### Circuit Description (Cont'd)

lator to achieve an exact lock-in with the horizontal sync pulses. The output of the blocking oscillator is coupled through C₁₄ and R₄ to the control grid of the 24JE6A power pentode used in the horizontal-output stage. This tube drives the high-voltage flyback transformer T₁ that develops the scanning voltage for the horizontal deflection coils (shown in circuit 29-35.

The sudden cutoff of plate current in the horizontal output stage at the end of the trace period causes a very large, positive-going voltage pulse to be generated across the high-voltage transformer T₁. The 3A3A half-wave rectifier circuit converts this pulse to a positive dc of 21,500 volts which is applied to the second anode of the color picture tube.

Regulation of the high voltage is achieved by use of a 17KV6A pulse-regulator stage connected in shunt with a section of the primary of the high-voltage flyback transformer. The regulator stage acts as a variable load on the flyback pulse source and, in this way, maintains an essentially constant pulse amplitude in the primary winding of the high-voltage transformer with changing loads on the high-voltage supply. This action assures that a constant-amplitude, stepped-up pulse is applied to the 3A3A rectifier. The rectifier output delivered to the picture tube, therefore, is maintained at a constant value of 21,500 volts.

Removal of negative overshoots that would be developed across the high-voltage transformer because of a flywheel effect is accomplished by the damper diode CR₂. This diode is shaped like a fuse and snaps into clips that can be mounted on the same circuit board with the horizontal deflection circuits and is readily replaced during servicing.


The polarity of the damper diode is such that the positive pulse developed across the high-voltage transformer causes no current flow through it. For negative pulses, however, the damper diode provides a low impedance path for the current, and energy stored in the horizontal output transformer (and the horizontal deflection coils) is dissipated in the damper circuit. The rectified current through the damper diode develops the boosted B+ voltage of +700 volts across capacitor C21 in the damper anode circuit.

The two auxiliary windings on the high-voltage transformer supply supplementary pulse voltages. The upper winding supplies gating pulses to the burst-gate and the color-killer amplifiers (shown in circuit 29-34). The convergence pulse is developed across the lower auxiliary winding. Keying pulses for the agc amplifier and the horizontal blanking diode are derived from the capacitor network (junction of C₂₅ and C₂₇) in the primary circuit of the high-voltage transformer.

Transformer T2 shown in the circuit diagram is the vertical output transformer. The drive signal from the vertical output stage (shown in circuit 29-32) is developed across the primary of this transformer and coupled by the secondary winding through jack J2 to the vertical deflection coils (shown in circuit 29-35). An auxiliary winding on transformer T2 develops the keying pulse for the vertical blanking diode. The horizontal scanning signal from the highvoltage (horizontal-output) transformer are also coupled through jack J, to the horizontal deflection coils. The horizontal and vertical signals to the convergence board are routed through jack J2. (Jacks J1 and J₂ mate with plugs P₂ and P₁, respectively, on circuit 29-35.)

29-34

# CHROMA CIRCUITS



### CHROMA CIRCUITS (Cont'd)

#### Parts List

C1=27 pF, ceramic, 500 V, NPO C2=68 pF, ceramic, 500 V, N750 C₃, C₅, C₆, C₈, C₀, C₂₂, C₂₃, C₂₉ through C₃₄=0.01 pF, ceramic, 500 V C4=390 pF, ceramic, 500 V C₇==0.047 μF, Mylar, 100 V C₁₀, C₁₈=1000 pF, ceramic, 500 V C₁₁=Trimmer, 2 to 10 pF, RCA Stock No. 116501 or equiv. C12=220 pF, ceramic, 500 V C13=10 pF, ceramic, 500 V, N150 C14, C16=0.82 pF ±5%. headed lead, 500 V C₁₅=820 pF, ceramic, 500 V C₁₇=390 pF ±5%, Mylar, 500 V 500 V, N150 C₁₉, C₂₇=33 pF, ceramic, 500 V, N150 C₂₁=10 pF ±5%, ceramic, 500 V, NPO  $C_{24}$ =0.027 pF, Mylar, 100 V  $C_{25}$ =430 pF ±5%, mica, 500 V C₂₈=150 pF, ceramic, 500 V C₃₅=1.2 pF, ceramic, 500 V CR₁, CR₄, CR₅, CR₆=Silicon diode, RCA Stock No. 119596 or equiv. CR2=Diode, pulse clipper, RCA Stock No. 113998 CR3=Diode, type 1N60

chroma-takeoff coil, RCA Stock No. 120797 or equiv. L=Variable inductor, oscillator strength adjustment, RCA Stock No. 120798 or equiv.
L=Phase-shift coil, 3.9 μH, part of quadrature assembly (RCA Stock No. 120830 or equiv.) with R. Li=RF coil, 3.9 \(\mu\)H, RCA Stock No. 116510 or equiv. L₅, L₆=RF choke, 620 μH, RCA Stock No. 109257 or equiv.  $R_1=3.9$  megohms, 0.5 watt  $R_2=0.15$  megohm, 0.5 watt R3, R4, R7=47000 ohms, 0.5 watt Rs=82000 ohms, 0.5 watt  $R_6$ ,  $R_{10}=10$  megohms. 0.5 watt Rs=Potentiometer, colorkiller adjustment, 1 meg-ohm, 0.5 watt, RCA Stock No. 120805 or equiv. Ru=82 ohms, 0.5 watt R₁₁=2.7 megohms, 0.5 watt R₁₂=2.2 megohms, 0.5 watt R₁₃=3900 ohms, 0.5 watt R11, R16=390 ohms, 0.5 watt R₁₅=82000 ohms, 0.5 watt R17=47000 ohms, 1 watt R18=560 ohms, 0.5 watt R₁₉=1500 ohms, 0.5 watt R20=Potentiometer, tint control, 10000 ohms, 0.5 watt, RCA Stock No.

120774 or equiv.

R21=6800 ohms, 1 watt Rm=120 ohms ±5%, 1 watt, part of quadrature assembly with Ls

R25, R26=470 ohms, 0.5 watt R21=1500 ohms, 0.5 watt R25=Potentiometer, color control, 500 ohms, 0.5 watt, RCA Stock No. 120776 or equiv. R27=0.1 megohm, 0.5 watt R₂₈, R₃₉=6800 ohms  $\pm 5\%$ , fixed film, 0.5 watt R20=4700 ohms ±5%. 1 watt R:0=0.22 megohm, 0.5 watt R::=8200 ohms, 0.5 watt R::=68000 ohms, 0.5 watt Ra=8200 ohms ±5%, fixed film, 0.5 watt Rat, Rat, Rat=1 megohm. 0.5 watt Ras, Rao=0.18 megohm, 0.5 watt R₃₈=0.33 megohm, 0.5 watt R₄₁, R₄₂, R₄₄=39000 ohms ±5%, 1 watt R₄₃=0.56 megohm, 0.5 watt R₁₅, R₁₆, R₁₇=2.2 megohms, 0.5 watt R₁₈=0.39 megohm, 0.5 watt R₁₉, R₅₀, R₅₁=1000 ohms, 0.5 watt T1=Burst transformer, RCA Stock No. 120816 or equiv. T2=3.58-MHz oscillator transformer, RCA Stock No. 120815 or equiv.

Y1=3.58-MHz oscillator

# L₁=Variable inductor, Circuit Description

These circuits extract the color information from the 3.58-MHz chrominance sidebands included in the composite color video signal. The color information is included in the chrominance sidebands in the form of two difference-frequency components that have a phase difference of 90 degrees and that are derived in the color television transmitter by subtraction of the luminance (Y) signal from the red (R) and blue (B) color signals. [The green colordifference (G - Y) components are not transmitted, but instead, are derived in the color receiver by addiof complements (negative tion values) of the R-Y and B-Y signals.] To accomplish the demodulation function, the chroma circuits are required to develop two continuous-wave 3.58-MHz signals that have a phase difference of 90 degrees, each of which much be added

vectorially to the chrominance sidebands. In other words, the 3.58MHz color subcarrier suppressed during transmission must be reinserted by the chroma circuits before the R — Y and B — Y color-difference information contained in the chrominance sidebands can be detected.

crystal

The chroma circuits operate from the color receiver low-voltage (280-volt) supply. power 5GH8A triode-pentodes fulfill the electron-tube requirements for the ten chroma stages. The heaters of these tubes are connected in series with those of other tubes in the receiver; operating power for the series-heater string is obtained directly from the 117-volt ac power line.

The input to the chroma circuits is the composite video signal after it has been amplified by the first video amplifier and the sync-agc-

#### CHROMA CIRCUITS (Cont'd)

#### Circuit Description (Cont'd)

and-chroma driver (shown on circuits 29-32 and 29-33, respectively). In addition to the chrominance sidebands, this composite signal includes the luminance signal (equivalent to the monochrome picture signal in black-and-white transmissions), the conventional horizontal and vertical sync pulses, and the color burst synchronizing signal. The color "burst" is a 3.58 MHz reference signal of approximately 8 cycles that occurs during the horizontal retrace blanking interval immediately following the horizontal sync pulse (refer to Fig. 96, page 73).

The chroma input is applied simultaneously to the chroma bandpass and burst amplifiers. When no burst signal is included in the chroma input (i.e.. for black-and-white transmissions), the color-killer stage develops, by means of the current through diode CR1, a negative dc voltage across capacitor C, that biases the chroma bandpass amplifier beyond cutoff: as a result the chroma input is not applied to the color demodulators.

The operation of the burst amplifier is controlled by a gating signal (burst-gate and killer pulse) from an auxiliary winding on the horizontal-output transformer (T, in circuit 29-33). This gating pulse is generated at the same time and has the same time duration as the horizontal blanking pulse used to blank out the horizontal retrace on the color picture tube. This interval corresponds to the period of the horizontal sync pulse and the 3.58MHz burst synchronizing signal that immediately follows the sync pulse. The amplifier, therefore, amplifies this portion of the chroma input. The primary of transformer T₁ in the plate circuit of the burst amplifier, however, is tuned to 3.58 MHz so that only the 3.58-MHz burst signal is coupled from the plate of the burst amplifier.

The separated burst is coupled by transformer T₁ to the control-grid circuit of a 3.58-MHz injectionlocked oscillator circuit. The oscillator, therefore, is forced to operate in step (with respect to both frequency and phase) with the incom-The 3.58-MHz burst signal. crystal Y1 is used to assure excellent frequency stability in the oscillator circuit. The oscillator develops the continuous-wave 3.58-MHz reference signal applied to the control grids of the Z and X demodulators. The quadrature network (La and Ra) causes a 90-degree phase shift in the 3.58-MHz signal applied to the control grid of the X demodulator. The 3.58-MHz chrominance sidebands must also be applied to the X and Z demodulators before these stages derive the color difference signals. These sideband signals are obtained from the chroma bandnass amplifier.

The dc bias voltage developed in the grid circuit of the oscillator stage is used to control color-killer action and to derive an agc voltage for the chroma bandpass amplifier. The cathode-to-grid section of the oscillator triode, diode CRa, and associated components from a twodiode voltage-doubler circuit. Any de voltage developed in the oscillator grid circuit is approximately doubled at the voltage-doubler output (anode circuit of diode CR3). When no color signal is received (i.e., no burst signal applied to the oscillator), the dc voltage at the grid of the oscillator is approximately -5 volts. The -10volts developed across C13 and R15 in the anode circuit of voltage-doubler diode CR: is reduced to approximately -1.4 volts at the control grid of the color-killer stage. For this low level of bias, the color killer stage conducts and develops a cutoff bias for the chroma bandpass amplifier.

When color signals are being

#### CHROMA CIRCUITS (Cont'd)

#### Circuit Description (Cont'd)

received, the burst signals applied to the oscillator causes the oscillator grid bias voltage to increase to approximately -8 volts, depending on the amplitude of the burst signal. The dc voltage at the anode of the voltage-doubler diode then rises to approximately -16 volts, and the bias on the color-killer stage is increased to about -4 volts. For this bias level, no current flows through the color-killer stage, and the cutoff bias for the chroma bandpass amplifier provided b the color-killer stage is removed. The grid bias for the bandpass amplifier is then derived from the dc voltage at the grid of the 3.58-MHz oscillator. Because this voltage varies with the amplitude of the burst signal, it provides automatic-gain control for the bandpass amplifier.

With the removal of the cutoff bias provided by the color killer, the handpass amplifier is allowed to amplify and and pass the 3.58-MHz chrominance sidebands contained in the chroma input (video signal). The single-tuned transformer T2 in the plate circuit of the bandpass amplifier forms a selective load to the 3.58-MHz chrominance sidebands. The output of the bandpass amplifier, therefore, is a 3.58-MHz signal that contains the R- Y and B - Y color-difference information. The instantaneous phase difference of the 3.58-MHz color-difference components with respect to the burst signal defines synchronizing color information being transmitted. as indicated by the chart on page 73 in the section Electron Tube Applications.

The 3.58-MHz color-difference signals from the bandpass amplifier are coupled by transformer T₂ to the screen grids of the X and Z color demodulators where they are mixed with the continuous-wave 3.58-MHz signal from the oscillator. The color demodulators are essentially

synchronous detectors. These types of detectors are phase sensitive, and their output is determined not only by the amplitudes of the two input signals, but also by the phase relationship of these inputs. If the amplitudes of the chrominance and continuous wave inputs to the demodulators are considered to be constant, the input of the demodulators is affected by the phase relationship of the two input signals as follows: When the chrominance and the continuous signals are in phase, the output of the demodulators is maximum in the negative direction. When the two signals are 180 degrees out of phase, the output is maximum in the positive direction. A phase difference of 90 or 270 degrees results in a zero output from the demodulators.

The X and Z color demodulators are biased so that the plate current of each demodulator tube is small during the zero-signal condition. The continuous-wave signal applied to the control grid gates the tube into conduction for the full positive half cycle. During most of the negative half cycle, the tube is cut off. With no chrominance signal applied to the screen grid, the plate current of the demodulator tube consists essentially of 3.58-MHz pulses. A low-pass filter in the plate circuit of the demodulator removes the 3.58-MHz component so that the dc plate voltage decreases below the level obtained when there is no input to either the control or screen grid. The dc level obtained when only the continuouswave reference signal is applied represents the zero output of the color demodulators; only changes in the average plate voltage above and below this level will be passed by the output coupling capacitor to the succeeding stages.

When the chrominance signal applied to the screen grid is in phase with the continuous-wave reference signal applied to the control grid,

#### CHROMA CIRCUITS (Cont'd)

#### Circuit Description (Cont'd)

the demodulator tube conducts more heavily during the periods that the reference signal permits conduction. The plate voltage of the demodulator then decreases below the zero level. and the output coupling capacitor couples the negative change to the next stage. Conversely, if the two signals are 180 degrees out of phase. the average plate current decreases. The attendant rise in average plate voltage causes a positive change to be coupled to the next stage. For 90- or 270-degree phase differences, the two signals tend to add together at certain times and to cancel each other times so that the average plate current is essentially unchanged.

In the development of the colordifference signals at the transmitter, the phase of the R - Y signal is shifted 90 degrees with respect to the burst reference signal and the B - Y signal is in phase with the reference signal. The B - Y component of the chrominance sidebands, therefore, is in phase with the reference signal applied to the Z demodulator, and the R - Y component is in phase with the phase-shifted reference signal applied to the X demodulator. The output of the Z demodulator then is the detected G - Y signal, and the output of the X demodulator is the detected R - Y signal. These signals are coupled to the B - Y and R - Y differencesignal amplifiers, respectively.

If strict consideration is given to signal phase relationships, the outputs of the X and Z demodulators are -(R-Y) and -(B-Y) signals. The positive versions of these color-diffrence signals results from the inversions provided by the R - Y and B - Y color-difference amplifiers. The G - Y color-difference signal is synthesized by addition of portions of the R - Y and B - Y signals from the plates of the R - Y and B - Y difference amplifiers in the resistor matrix network at the input to the G - Y colordifference amplifier. The vector sum of these quantities results in a -(G - Y) signal. This signal is amplified and inverted by the G - Yamplifier to obtain the G - Y signal.

The color difference amplifiers all operate in the grounded-cathode mode with the grid bias taken from the blanker circuit, and only capacitance coupling is used from the outputs of these amplifiers to the picture tube. The dc reference level for the three color grids of the picture tube are established by a clamp diode circuit in the output of each difference amplifier. The outputs of the R-Y, G-Y, and B-Y color-difference amplifier are coupled to the red, green, and blue grids, respectively, of the color picture tube.

# 29-35 PICTURE TUBE AND ASSOCIATED CIRCUITS


For Color Television Receiver

#### **Circuit Description**

These circuits include the picture tube and associated input-coupling and biasing networks, the convergence board, and the horizontal and vertical deflection coils for a color television receiver. The dc operating potentials for the picture tube are derived from the receiver low-voltage (280-volt) power supply, the B Boost (700-volt) voltage developed by the horizontal-output circuit, and

the high-voltage (21,500-volt) rectifier circuit. The 6.3 volt heater power for the picture tube is obtained from a transformer (T₁ in circuit 29-29) connected across the 117-volt ac power line.

The 15LP22 color picture tube has a number of unique features. The phosphor-dot screen uses a rare-earth, red-emitting phosphor and improved blue and green phosphors.



#### Parts List

C1=0.1 µF, Mylar, 400 V C=47 pF, ceramic, 500 V. N750

Cs, C4, C5=1000 pF, ceramic, 500 V Ce, C7=0.15 \(\mu \text{F}\), Mylar, 75 V (part of convergence-

board assembly)

Cs=0.082 μF, Mylar, 100 V (part of convergenceboard assembly) C2=0.27 µF, Mylar, 75 V

(part of convergenceboard assembly)
C₁₀=180 pF, 250 V, part
of deflection-yoke assembly

C11=3900 pF, part of deflection-yoke assembly
C12=82 pF, 3000 V, part of

deflection-yoke assembly CR₁, CR₂, CR₃, CR₄=Selenium rectifier assembly, RCA Stock No. 120058

or equiv. Convergence board=RCA
Stock No. 120052 or equiv.
Deflection yoke=RCA Stock

No. 120890 or equiv. Li=820 µH, part of net-work assembly (RCA Stock No. 120796 or equiv.)

with R1 (Ls-Ls, Ls-Ls) (Lr-Ls, Ls-L10) (L13-L14, L13-L15)=Convergence-coil assembly, RCA Stock No. 121343 or equiv., part of convergence-board

La=Variable inductor, right red-green vertical lines adjustment, RCA Stock No. 120059 or equiv., part of convergence-board

assembly L11=Variable inductor, right red/green vertical lines adjustment, RCA Stock No. 121443 or equiv., part of convergence-board

assembly Las=Variable inductor, right blue horizontal lines adjustment, RCA Stock No. 120060 or equiv., part of convergence-board assembly

assembly
Lis, Lac=Vertical-deflection

coils, part of deflectionyoke assembly

Lie, La Horizontal-deflec-tion coils, part of deflection-yoke assembly P1=Connector for conver-

gence_board, 8-pin male type, RCA Stock No. 112728 or equiv. (mates with J₁ on circuit 26-34) P₂=Connector for yoke as-sembly, 8-pin male type, RCA Stock No. 114767

or equiv. (mates with J2 on circuit 26-34) R1=4700 ohms, 0.5 watt, part of network assem-

bly with L₁
R₂=0.18 megohm, 0.5 watt
R₃=0.15 megohm, 0.5 watt R₄=Potentiometer, video peak adjustment, 0.1 megohm, 0.5 watt, part of assembly with R₁ and R₈

(RCA Stock No. 120811 or equiv.) Rs=5600 ohms, 0.5 watt Re=12000 ohms, 0.5 watt R₁=Potentiometer, red drive adjustment, 6000 ohms, 0.5 watt, part of assembly with Re and Rs (RCA

Stock No. 120811 or equiv.) Rs=Potentiometer, green drive adjustment, 6000 ohms, 0.5 watt, part of assembly with R5 and R7 (RCA Stock No. 120811

or equiv.)
R==33000 ohms ±5%,

0.5 watt R₁₀, R₁₁, R₁₂=Three-section potentiometer; screen-grid adjustments for blue green, and red electron guns, respectively; each section: 1.5 megohms, 0.5 watt; RCA Stock No. 120812 or equiv.

R13=47000 ohms, 0.5 watt
R14=1000 ohms, 0.5 watt

R₁₅=Potentiometer, top red/green horizontal lines adjustment, 120 ohms, 0.5 watt, RCA Stock No. 106320 or equiv. (part of convergence-board assembly)

R16=Potentiometer, bottom red/green horizontal lines adjustment, 350 ohms, 0.5 watt, RCA Stock No. 116635 or equiv. (part of convergence-board assembly)

R17=Potentiometer, bottom red/green vertical lines adjustment, 60 ohms, 0.5 watt, RCA Stock No. 105059 or equiv. (part of convergence-board assembly)

R18=Potentiometer, bottom blue horizontal lines adjustment, 60 ohms, 0.5 watt, RCA Stock No. 105059 or equiv. (part of convergence-board

assembly)
Ris, R2=100 ohms, 1 watt,
part of convergence-board assembly

Rm=Potentiometer, left red/green horizontal lines adjustment, 100 ohms, 0.5 watt, RCA Stock No. 120949 or equiv. (part of convergence-board assembly R2=Potentiometer, left

red/green vertical lines adjustment, 100 ohms, 0.5 watt, RCA Stock No. 120949 or equiv. (part of convergence-board assembly

R23=270 ohms, 0.5 watt (part of convergenceboard assembly)
R2=180 ohms, 1 watt (part

of convergence-board assembly) R25=270 ohms, 1 watt (part

of convergence-board assembly)

R20=Potentiometer, left blue adjustment, 60 ohms, 3 watts, RCA Stock No. 114627 or equiv. (part of convergence-board assembly)

R27=Potentiometer, top red/green vertical lines adjustment, 350 ohms, 0.5 watt, RCA Stock No. 116635 or equiv. (part of convergence-board assembly)

R28=Potentiometer, top blue horizontal lines adjustment, 350 ohms, 0.5 watt, RCA Stock No. 116635 or equiv. (part of convergence-board assembly)

R29=82 ohms, 0.5 watt (part of convergenceboard assembly)
R₃₀=4700 ohms, 2 watts

(part of deflection-yoke

(part of deflection-year assembly)

Rai, Raz=220 ohms, 0.5 watt

S=Service switch, RCA

Stock No. 120838 or equiv.

SG1 through SG7=Capacitor, spark-gap, 0.5 pF, 1000 V, RCA Stock No. 120819 or equiv.

TH1=Thermistor; cold resistance, 1.3 ohms ; RCA Stock No. 120891

See Note on page 726.

### Circuit Description (Cont'd)

The new phosphors are more efficient and are capable of producing 38 per cent brighter highlights than previous color picture tubes. The directly viewed shadow-mask picture

tube incorporates a screen with nearly straight sides and sharply rounded corners.

The 15LP22 is designed for operation with the blue gun down. The

#### Circuit Description (Cont'd)

anode bulb contact for high voltage connection is still located in the top section of the tube. Operation in the blue-down orientation, with respect to the viewing screen, provides optimum compromise of pincushion distortion at the top and bottom of the screen. The tube is equipped with an integral filter glass protective window, sealed to the base plate of the tube with a clear resin. An external magnetic shield is not required on the 15LP22. Another main feature of the color picture tube is an einzel-lens focus system. This system is relatively insensitive to variations of the high voltage so that the tube maintains good focus even with variations in picture brightness.

The focus system for the color picture tube is very similar to that used in instruments equipped with a black-and-white picture tube. Normally, the 15LP22 will have optimum focus when connected to ground potential. However, provisions to change the focus potential are facilitated by a pin connector from pin 9 of the picture tube. The focus selected jumper can be connected to 620 volts, 320 volts, or ground merely by relocating the slip-on connector to the proper stake extending from the circuit board.

A three-position service switch S₁ is incorporated into the picture-tube circuitry to facilitate receiver setup and adjustment. The NORMAL position of the switch, of course, permits normal receiver operation. With the switch in the SETUP or RASTER position, the video input is disconnected from the picture tube, and the ground return for the agc circuit is opened. Raster height and width and color and background levels can then be more easily adjusted.

The output of the color difference amplifiers are applied to the respective grids of the tricolor picture tube. The luminance signal from the

second video amplifier is applied to the three cathodes of the color picture tube. These signals combine to intensity modulate the three electron beams to produce the color image on the picture-tube screen.

The horizontal and vertical deflection coils in a yoke on the neck of the picture tube deflect the electron beams, in response to signals received from the horizontal and vertical output stages, to produce the horizontal and vertical scanning required to trace the image on the picture-tube screen. (These coils are connected in shunt with the respective horizontal and vertical output transformer.)

The horizontal output circuit provides a sawtooth current waveform at a frequecy of 15,750 Hz to the horizontal-deflection coils, and the vertical output circuit provides a 60-Hz sawtooth current wave to the vertical-deflection coils. The picture tube electron beams are simultaneously deflected horizontally across the screen at a rate of 15,750 Hz and vertically at a rate of 60 Hz.

At the completion of each horizontal trace (end of rising portion of sawtooth current wave), the beam is deflected back to the left side of the screen (retrace) to start another trace period. A positive blanking pulse (included in the video signal) applied to the cathodes of the picture tubes cuts off the picture tube during this period so that the retrace lines do not appear on the tube screen. The picture tube is similarly blanked at the end of each vertical-trace period.

Correct color reproduction requires that the three beams of the color picture tubes meet, or converge, at the shadow mask and excite color dots of the same trios. The three electron guns of the color picture tube are mechanically tilted toward the center axis of the tube so that virtual convergence is ob-

#### Circuit Description (Cont'd)

tained with no external converging force applied. Slight bending of one or more of the beams may be required for exact convergence. The convergence circuit performs this function.

The components on the convergence board shown in the circuit diagram are mounted on a disk-shaped circuit board with a center hole that permits it to be fitted directly on the neck of the color picture tube. These components are interconnected in a dynamic type of convergence system. In this system, sine wave currents are used to provide horizontal convergence, and parabolic current waves are used to provide vertical convergence.

The sine waves of current used to provide horizontal convergence are derived from a voltage pulse developed across an auxiliary winding of the high-voltage transformer (T₁ in circuit 29-33) and applied through pin 8 of the convergenceboard input connector P1. The current through each of the three sets of horizontal convergence coils (L2 and L4, L8 and L10, and L13 and L15) is individually adjustable in both amplitude and phase. The phase of the convergence current is adjusted b the Horizontal Shape control L. which resonates with the two 0.15microfarad capacitors C6 and C7 at the line frequency (15,750 Hz). The sine-wave convergence current is produced by ringing this resonant

circuit with the pulse obtained from the high-voltage transformer. Po tentiometers R₁₅, R₁₆, R₁₈, R₂₀, and R₂₈ adjust the amplitude of the sinewave convergence current.

Vertical-frequency (60-Hz) sawtooth voltages obtained from secondary windings of the verticaloutput transformer (T2 in circuit 29-33), applied through pins 4 and 5 and pins 6 and 7 of connector P₁, are used to derive the vertical convergence-current waveform. Because of the integrating action of the convergence coils, this sawtooth voltage results in a parabolic current wave through the convergence coils. Potentiometer R2 adjusts the amplitude of the vertical voltage parabola applied to the three sets of vertical convergence coils (L3 and L5, L7 and La, and La and La).

A vertical-frequency sawtooth voltage from a secondary winding of the vertical-output transformer, is applied across potentiometer R₁₇. The sawtooth voltage is obtained from center tapped transformers; voltage at the center of potentiometer R₁₇ therefore, is approximately zero with respect to circuit ground. Adjustment of this potentiometer mixes either positive or negative sawtooth voltages with the parabolic convergence voltage and, in this way, controls the shape of the convergence signal applied to the convergence coils.

# **INDEX**

Absolute Maximum System of Ratings 95	Bias:	.6.
Absolute Maximum System of Ratings 95 AC/DC Superheterodyne Receiver 677		84
Admittance, Input		84
All-Purpose Power Supplies 711		21
AM Detection	grid-resistor 22,	
AM/FM Receiver		10
Amplification	Burst	
Amplification Factor $(\mu)$		84
Amplifier:	and publication and a second s	٠.
audio-frequency	Coloniation of	
audio mixer, circuit 700	Calculation of:	
cathode-drive		13 84
cathode-follower 40		42
Class A		14
class AB		82
class AB1		82
class AB ₂		57
class B		
class C	harmonic distortion	
high-fidelity		33 55
intermediate-frequency, circuit 684		33
limiter	operating conditions from	32
luminance 60		32 97
parallel		97 14
phase-inverter		14
preamplifier circuits 702, 703, 704, 705	plate resistance	
push-pull		33 14
radio-frequency		52
remote-cutoff		32 52
resistance-coupled		32 99
sync	screen-grid voltage dropping resistor transconductance	
television		
tone-control		<del>4</del> 0 54
tone-control, circuit 706		24 89
video 58, 60	Cathode:	92
voltage 25		84
volume-expander 50		84 84
Amplifiers:	o, passang	83
if 52		83
tuned	directly heated	3
wideband	drive	3 <b>7</b>
Amplitude Modulation (AM)	follower	
Anode 5	indirectly heated	4
Application Guide for RCA	ionic-heated	6
Receiving Tubes		84
Arc-Back Limit	types	3
Audio Mixer 700		98
Electronic Volt-Ohmeter 707	Characteristics:	,,
Automatic Frequency Control (AFC) 76		13
Automatic Gain Control (AGC) 46, 48		14 14
Automatic Volume Control (AVC) 46		14 14
The state of the s		13
Bass and Treble Tone-Control		14
Amplifier Stage 702		14 14
Beam Power Tubes 9		13
	DWGO	IJ

	Page	P	age
Charts and Tables:	•	Current:	
grid-No. 2 input rating chart	300	cathode	83
outline drawings	633	dc output	96
picture tube characteristics chart	666	grid	86 75
resistance-coupled amplifier	641 522	peak plate	/3 5
types for replacement use		plate	98
Choke-Input Filter	89 741	Cutoff	27
Chroma Circuits	61	Cuton	~,
Circuit Diagram of:	01		
ac/dc superheterodyne radio receiver	677	Dark Heater	4
all-purpose power supplies	711	Deflection Circuits:	
AM/FM superheterodyne radio		horizontal	67
receiver	677	vertical	68
bass and treble tone-control amplifier	706	Degeneration (See Inverse Feedback)	38
chroma circuits	741	Delayed Automatic Volume Control	47
code practice oscillator	690	(DAVC)	
FM stereo multiplex adapter	686 682	Design-Center System of Ratings	95
FM tuner high-fidelity 15-w audio amplifier	692	Design-Maximum System of Ratings	95
high-fidelity 30-w audio amplifier	694	Detection:	
high-fidelity, 15-w audio amplifier high-fidelity, 30-w audio amplifier high-fidelity, 50-w audio amplifier	696	AM	19
horizontal-deflection circuit and high-		diode	20
power supply (for color		discriminator	23
TV receiver)	735	FM	22
intercommunication set	691	grid bias	21 22
low-distortion preamplifier	705	grid resistor and capacitor ratio detector	24
low-voltage and heater supply	724	synchronous	72
(for TV receiver)	124	Diode:	
circuit, and heater connections		biasing	21
(for color TV receiver)	726	considerations	5
microphone and phonograph		detection	20
amplifier	699	Discriminator	23
phonograph amplifier	701	Dress of Circuit Leads	88
picture tube and associated circuits	<b>.</b>	Dynamic Characteristics	13
(for color TV receiver)	745		
preamplifier for amateur receiver	694	Electron:	
preamplifier for ceramic phonograph-	704	considerations	3
pickup preamplifier for magnetic	704		8, 9
phonograph-pickup	702	Electrons, Electrodes, and Electron Tubes	3
preamplifier for tape-head pickup	703	Electron Tube Application	15
sync, agc, and vertical-deflection		Electron Tube Characteristics	13
circuits (for color TV receiver)	735	Electron Tube Installation	81 100
three-stage if amplifier/limiter and		Electron Tube Testing Electron-Ray Tubes	79
ratio detector	684	Emission:	/>
two-channel audio mixer	700	current	5
two-channel, 1-w stereo amplifier	698	secondary	8, 5
vertical and horizontal deflection		test	101
circuits and high-voltage rectifier	720		
vhf. tuner	713		
video, agc, and sync amplifiers	718	Feedback, Inverse 25,	, 38
video and sound-channel circuits		Filament (also see Heater and Cathode):	
(for color TV receiver)	731		, 81 81
video if amplifiers and sound-channel		resistorseries operation	81
circuits	716	shunt resistor	82
Circuits	674	supply voltage	81
Code-Practice Oscillator	688	Filter:	
Color Demodulation	72	capacitor-input	89
Color Picture Tubes	12	choke-input	89
Color Television	60	corrective	4:
Communications Transceiver	16	radio-frequency	89
Contact Potential	86	smoothing	89
Conversion Nomograph, Use of	33	FM Detection	2
Conversion Transconductance	14	FM Stereo Multiplex Adapter	686
Corrective Filter	43		682
Cross-Modulation	43 27	FM Tuner  Formulas (see Calculation)	004
OTOGS-MICHIGHIANOII	41	rotinulas (see Calculation)	

	Page		Page
Frame Grid	7	Low-Voltage Power Supply, Degaussing	
Frequency Conversion Frequency Modulation (FM)	77	Circuit, and Heater Connections (for	
Frequency Modulation (FM)	22	Color TV Receiver)	726
Full-Wave Rectifier	5, 17	Luminance Amplifier	60
Coin (Maltana Amulification)	26	Maximum Ratings	95
Gain (Voltage Amplification)			73
General System Functions	15	Mercury-Vapor Rectifier:	6
Generic Tube Types	4	considerations	
Grid:	0-	interference from	89
bias	85	Mho-micromho	14
bias detection	21	Microphone and Phonograph Amplifier .	699
control	7	Mixer:	
current	86	audio	700
resistor	85	hexode	79
resistor and capacitor detection	22	pentagridvhf tuner	74
screen	7	vhf tuner	56
suppressor	8	Modulated Wave	19
voltage supply	83	Modulation	19
Grid-Plate Capacitance	7	Modulation-Distortion	27
Grid-Plate Transconductance	14	Multi-Electrode and Multi-Unit Tubes	9
		Multiplex Adapter for FM Stereo	686
		Multivibrator	74
Half-Wave Rectifier	5 17	272474	• • •
Harmonic Distortion			
Heater:	0, 42	Noise	54
	4	Noise Figure	55
cathode	83	Noise Immunity	67
cathode bias	83	Noise immunity	10
cathode connection		Novar	
resistor	82	Nuvistor	10
series operation	82		
supply voltage	81		
warm-up time	95	Operation, Typical Values	98
High-Fidelity Amplifiers 49	ə, 90	Oscillator:	
High-Fidelity, 15-w Audio Amplifier	692	considerations	74
High-Fidelity, 30-w Audio Amplifier	694	local	57
High-Fidelity, 50-w Audio Amplifier	696	multivibrator	75
High-Voltage Regulation	69	relaxation	75
High-Voltage Regulators:		synchroguide	75
Shunt Regulator Circuit	69	Output Capacitance	98
Pulse Regulator Circuit	70	Output-Coupling Devices	90
Horizontal Deflection	66	Cuspat Coupling 2011000 1111111111111	,,
Horizontal-Deflection Circuit and High-			
Voltage Power Supply	737	Parallel Operation	28
Hum and Noise Characteristics	98	Peaking:	20
rium and moise characteristics	70	series	58
			58
TO A continue of the transfer of the state of the state of		shunt	96
IF Amplifier/Limiter and Ratio Detector	684	Peak heater-cathode voltage	97
Impedance, Input	27	Peak Inverse Plate Voltage	97
Injection Voltage	56	Peak Plate Current	
Input Admittance	27	Pentagrid Converter	10
Input Capacitance	98	Pentagrid Mixer	79
Instantaneous Peak Voltage	97	Pentode Considerations	8
Intercommunication Set	689	Phase Inverter	51
Interelectrode Capacitances	7, 98	Phonograph Amplifier	701
Intermodulation Distortion	49	Phonograph and Tape Preamplifiers	43
Interpretation of Tube Data	95	Picture Tube:	
Inverse Feedback:		characteristics chart	666
constant-current type	40	corona considerations	92
constant-voltage type	38	cutaway view of color tube	12
The state of the s		deflection	11
		dust considerations	91
Kinescopes	10	essential elements	10
	-0		
		handling precautions	94
Limiters	50	high-voltage considerations	94
		humidity considerations	91
Load resistance	31	safety considerations	94
Local Oscillator	57	screen	10
Low-Distortion preamplifier	704		
Low-Voltage and Heater Supply (for		structure	11
Black-and-White TV receiver)	724	X-ray radiation precautions	94

Page	Pa	
Picture Tube and Associated Circuits		87
(for Color TV Receiver) 745	Shock-Hazard Warning:	_
Plate:		94
current5		93 100
dissipation	Short-Circuit 1est	65
efficiency		734
load 22		54 54
resistance		, ŝ
	Static Characteristics	13
Plate-Cathode Capacitance 7, 98	Stereo Circuits 686, 7	700
Power Output: calculations		675
calculations	Suppressor Grid (Grid No.3)	
Power Supplies 711	Sync	64
Preamplifier for Amateur Receiver 688	Sync, AGC, and Vertical-Deflection	_
Preamplifier for Ceramic Phonograph	Circuits 7	735
Pickup 704		64
Preamplifier for Magnetic Phonograph	Sync Separator	63
Pickup 702		75
Preamplifier for Tape-Head Pickup 703	Synchronous Detection	73
Preamplifiers, Phonograph and Tape 43		
Pulse Regulator Circuit 70		
Push-Pull Operation 28, 31	Technical Data for Tube Tube	
	Technical Data for Tube Types 1 Television:	111
O (selectivity) 52		72
Q (selectivity) 52		66
		57
Radio-Frequency:	picture tubes 10, 91,	
amplifier 25, 52	receiver	10
filter 89	rf amplifiers	50
Radio Receiver		83
Ratings:		64
absolute-maximum system 95	vertical deflection	68
design-center system 95	Terminal Diagrams:	
design-maximum system 95		572
Ratio Detector 24	For Replacement and Discontinued	
Rectification		612
Rectifiers:		100
full-wave	Tetrode Considerations	- 7
ionic-heated cathode	Three-Stage IF Amplifier/Limiten	-
parallel operation of		582 733
plate-characteristics curves 98		4:
voltage doubler	Transconductance:	٠.
Relaxation Oscillator 75	conversion	14
Remote-Cutoff Tubes	grid-plate	14
Resistance-Coupled Amplifiers 26, 641		101
Resistance Coupling 26	Triode Considerations	7
Resistor:	Tube:	
cathode (self-biasing) 84	outlines 6	633
center tap 82	ratings, interpretation of	95
filament 82		103
plate load	Tube Types, Technical Data 1	112
screen-grid	Tuned Amplifiers	52
Resonant Circuits 52		682
	Tuners, Television	50
Safety Precautions:		75
picture tubes 94	TV Scanning, Sync, and Deflection	61
receiving tubes 93	Twin diode—triode	20 700
Saturation Current 6		
Scanning Fundamentals 63	Two-Channel Stereophonic Amplifier 6 Typical Operation Values,	598
Screen Grid (Grid No.2):		98
considerations		70
input		
input rating chart 300	Mantical and Mantagett Deficial	
voltage supply	Vertical and Horizontal Deflection	-
Secondary Electrons	Circuits and High Voltage Rectifier 7	720
Secondary Emission	Vertical Deflection	68 754
Self Bias (cathode bias) 84	VHF Tuner	133 116
Unit Dies (Cathone Dies) 04	· ····································	, 16

# RCA RECEIVING TUBE MANUAL

Video Amplifiers	by screen-grid-voltage variation delayed automatic (DAVC) Voltage Doubler Volume Compressor and Expander	47 18
amplification, class A 15 doubler rectifier 18 peak heater-cathode 96 peak inverse plate 97 supply 83	Wideband (Video) Amplifiers	
Volume Control: automatic (AVC)	X-Ray Radiation Considerations: picture tubes receiving tubes	94 93

# Other RCA Technical Publications

### Field Service Guides for RCA Color-TV Receivers

ERT-200 Volume - 1 (1955-1966) \$2.00* ERT-201 Volume - 2 (1967-1968) \$1.60* ERT-202 Volume - 3 (1969-1970) \$1.90* ERT-203 Volume - 4 (1971-1972) \$2.90* ERT-204 Volume - 5 (1973-1974) \$3.95*



These guides provide up-to-date service information on RCA color-TV chassis. All of the guides are compact enough to fit into your service caddy; however, they open to a full 11" x 17" for clear, easy reference.

#### Sections include:

- Comprehensive Indexes by Model Number and Model Name
- Step-By-Step Setup Procedures
- Top and Rear Chassis Views
- Easy to Read Schematic Diagrams
- Procedures for Picture Tube Removal and Replacement

# Color-TV Service Handbooks For Major Manufacturers

1A1759 (1967-1968)	\$2.00*
1A1848 (1969-1970)	\$2.25*
1A1973 (1971-1972)	\$2.95*
1A2092 (1973-1974)	\$3.75*



These handbooks permit you to service color-TV receivers of most major manufacturers in the customer's home. Data in these handbooks are based on the original manufacturer's service notes,

The handbooks include manufacturers such as:

Admiral, Airline, Dumont, Curtis Mathes, Emerson, General Electric, Hitachi, Hoffman, Magnavox, Motorola, Olympic, Packard Bell, Panasonic, Philco, RCA, Sony, Sylvania, and Zenith

#### Sections include:

- Comprehensive Index
- Top Chassis View Showing all Major Components
- Simplified Setup Procedures For Purity, Black-and-White Setup Convergence, and AFPC.

^{*} Prices are net and are subject to change without notice at our discretion.

### Solid State Servicing

#### TSG-1673A

#### \$3.95*



Practical bench-oriented service manual covering the application and servicing of solid-state devices (diodes: rectifiers-zeners-varactors; transistors: bipolar-FET's; thyristors: SCR's-triacs; IC's) in Power Supplies, Hi-Fi and Tape-Recorder Amplifiers; AM and FM Receivers (mono and stereo); and Television Receivers (color and black-and-white).

#### Text sections include:

- Solid-State Operating Principles
- Basic Amplifier Considerations
- Power Supplies
- Hi-Fi and Tape-Recorder Amplifiers
- Radio Receivers (AM and FM Mono and Stereo)
- Television Receivers (Color and Black-and-White)
- Servicing Solid-State Circuits

# Solid-State Hobby Circuits

HM-92

\$2.95 *



408 pages containing 68 circuits of general interest to all experimenters. Circuits use diodes, transistors, SCR's, triacs, MOS transistors, integrated circuits, and light and heat detectors. Circuit operation is described in detail; construction laylists are given; and full-size drilling or printed-circuit templates are included for most circuits to simplify construction.

Circuits you can build, use, and enjoy.

- Audio
- Automobile
- Home & Hobby
- Musician
- Photographer
- Amateur Radio

- Communications
- Games & Recreation
- DC Power Supplies
- How to Build Electronic
- How to Test & Troubleshoot Solid-State Devices

^{*} Prices are net and are subject to change without notice at our discretion.

#### **Electro-Optics Handbook**

### **EOH-11**

\$4.95*

256-page Handbook, a carefully edited collection of technical information from many different widely scattered sources, provides general extensive reference material in the rapidly expanding electroptics field. Dozens of tables, charts, graphs as well as descriptive text. A fully indexed valuable timesaving reference.



#### Sections include:

- Radiometric Quantities and Units
- Photometric Quantities, Units, and Standards
- Physical Constants, Angle Conversion Factors, and Commonly Used Units
- Blackbody Radiation
- Eye Response and Luminous Efficacy

- Sources of Radiation
- Atmospheric Transmittance
- Detection, Resolution, and Recognition
- Lasers
- Detector Characteristics
- Image and Camera Tubes
- Optics
- Photographing E-O Displays

# Photomultiplier Manual

PT-61

\$2.50*

192 pages of technical data and information on photomultiplier construction, operation, and applications for designers and users of electro-optical equipment. Data on sources, spectra, noise, and RCA photomultipliers are included. Well illustrated and well written for easy reading, this manual is valuable to students, engineers, and service technicians.



#### Sections include:

- Photoemission
- Secondary Emission
- Principles of Photomultiplier Design
- Statistical Fluctations and Noise
- Applications of Photomultipliers
- Voltage-Divider Considerations
- Photometry
- Radiant Energy and Sources
- Spectrum Response
- Source Detector Matching

^{*} Prices are net and are subject to change without notice at our discretion.

758 Notes

Notes 759

# RCA Products for the Technical Service Industry

Receiving tubes Receiving-type industrial tubes Color picture tubes Black-and-white picture tubes Power tubes Electro-optic devices Replacement semiconductor devices **Batteries** Test equipment **Antennas** Antenna rotators Antenna installation hardware Reception aids Spray chemicals for electronic equipment Servicing aids Industry compatible test jigs Exact replacement parts for RCA products Film resistors (flameproof) Car radios and tape players Speakers Scanning radios

See your RCA Distributor - or, for more information contact:

RCA | Distributor and Special Products Division | Cherry Hill Offices | Camden, N.J. 08101

